# Lwarp

LaTeX HTML5

# The lwarp package

LaTeX to HTML

v0.895 — 2021/02/18

© 2016–2021 Brian Dunn
bd@BDTechConcepts.com

**Abstract**

The lwarp package converts LaTeX to HTML by using LaTeX to process the user's document and directly generate HTML tags. External utility programs are only used for the final conversion of text and images. Math may be represented by SVG images or MathJax. More than 500 LaTeX packages and classes are supported, of which more than 90 also support MathJax.

Documents may be produced by DVI or PDF LaTeX, LuaLaTeX, XeLaTeX; by several CJK engines, classes, and packages; or by customized systems such as perltex and pythontex. A *texlua* script automates compilation, index, glossary, and batch image processing, and also supports *latexmk*. Configuration is semi-automatic at the first manual compile. Support files are self-generated. Print and HTML versions of each document may coexist.

Assistance is provided for HTML import into EPUB conversion software and word processors.

Requirements include the commonly-available Poppler utilities (included with MiKTeX) and Perl. Detailed installation instructions are included for each of the major operating systems and TeX distributions.

A quick-start tutorial is provided, as well as extensive documentation for special cases, a general index, and a troubleshooting index. Automatic error testing is provided for configuration files, package load order, and image generation.

SVG math and many other generated images include LaTeX expressions in the `alt` tags. MathJax may be used with advanced equation numbering under the direct control of lwarp.

Complicated tables are supported, which copy/paste well into LibreOffice Writer.

Supported classes and packages include memoir and koma-script, cleveref, caption, mdframed, siunitx, and many popular packages for tabulars, floats, graphics, theorems, the title page, bibliography, indexing, footnotes, and editorial work, as well as a number of CJK-related classes and packages.

TeX is a self-modifying tokenized macro-expansion language. Since lwarp is written directly in LaTeX, it is able to interpret the document's meaning at a deeper level than external conversions which merely approximate TeX. HTML5 and CSS3 are leveraged to provide advanced features such as booktabs trim, multicolumns, side-by-side minipages, and JavaScript-free navigation.

For a list of supported features, see table 2: Supported packages and features.

To update existing projects, see section 1: Updates.

**Lwarp is still in development. Changes are likely.**

**License:**

This work may be distributed and/or modified under the conditions of the LaTeX Project Public License, either version 1.3 of this license or (at your option) any later version. The latest version of this license is in http://www.latex-project.org/lppl.txt and version 1.3 or later is part of all distributions of LaTeX version 2005/12/01 or later.

# Support TEX development

TEX and related projects:

- are mostly open-sourced and a volunteer effort;
- benefit students, academics, scientists, engineers, and businesses;
- help drive education, public and private research, and commercial activity;
- are used in the fields of mathematics, science, engineering, and humanities;
- are international in reach;
- span decades of development;
- are enduring — many older packages are still actively used and maintained;
- are largely backwards compatible;
- are portable across all the major computing platforms;
- are usable even on older computers and away from internet access;
- are continuing to maintain relevance with modern improvements;
- require no yearly subscription fees;
- and are supported by an active community of knowledgeable volunteers.

Please consider helping by joining and/or contributing to the TEX Users Group, a United States 501(c)(3) tax-exempt charitable organization. Contributions are accepted by credit card, check, or Pay Pal, via the United Way, or by USA or European bank transfer. Membership in TUG supports the development of TEXLive, the major TEX distribution.

Donations may be directed towards individual projects:

**TUG Bursary Fund:** Assistance for attending annual TUG meetings.
**CTAN:** The Comprehensive TEX Archive Network — Central storage for TEX.
**TeX Development Fund:** Support for specific projects.
**EduTeX:** Teaching and using TEX in schools and universities.
**GUST e-foundry fonts:** Enhanced for math and additional language groups.
**LaTeX Project:** Modernizing the LATEX core.
**Libre Font Fund:** Fonts, tools (FontForge), and distribution (the Open Font Library).
**LuaTeX:** Combining the pdfTEX engine and the Lua language.
**MetaPost:** Postscript graphics.
**MacTeX:** TEX for Mac.
**PDF Accessibility:** Modern PDF standards.
**Other:** Additional projects may be specified.

To make a contribution: https://www.tug.org/donate.html

For country-specific TEX users groups: http://tug.org/usergroups.html

For users of MiKTEX: https://miktex.org/donations.html

# Contents

**Support TEX development** . . . . . **2**

**List of Figures** . . . . . **43**

**List of Tables** . . . . . **43**

**1 Updates** . . . . . **44**

**2 Introduction** . . . . . **63**

2.1 Typesetting conventions . . . . . 65

2.2 Supported packages and features . . . . . 66

**3 Alternatives** . . . . . **73**

3.1 internet class . . . . . 73

3.2 TEX4HT . . . . . 73

3.3 Translators . . . . . 73

3.4 AsciiDoc and Asciidoctor . . . . . 74

3.4.1 Asciidoctor-LATEX . . . . . 74

3.5 Pandoc . . . . . 74

3.6 Word processors . . . . . 74

3.7 Commercial systems . . . . . 74

3.8 Comparisons . . . . . 74

**4 Installation** . . . . . **76**

4.1 Installing the lwarp package . . . . . 78

4.2 Installing the *lwarpmk* utility . . . . . 79

4.2.1 Using a local copy of *lwarpmk* . . . . . 81

4.3 Installing additional utilities . . . . . 81

**5 Tutorial** . . . . . **83**

5.1 Starting a new project . . . . . 83

5.2 Compiling the print version with *lwarpmk* . . . . . 87

5.3 Compiling the HTML version with *lwarpmk* . . . . . 88

5.4 Generating the SVG images . . . . . 89

5.5 Using MathJax for math . . . . . 90

5.6 Changing the CSS style . . . 91
5.7 Customizing the HTML output . . . 91
5.8 Using *latexmk* . . . 92
5.9 Using XeLaTeX or LuaLaTeX . . . 93
5.10 Using DVI LaTeX . . . 93
5.11 Using a glossary . . . 94
5.11.1 gloss package . . . 94
5.11.2 glossaries package . . . 94
5.12 Cleaning auxiliary files . . . 95
5.13 Cleaning auxiliary and output files . . . 95
5.14 Cleaning the images from the <project>-images directory . . . 95
5.15 Converting PDF or EPS images to SVG . . . 95
5.16 Creating HTML from an incomplete compile . . . 95
5.17 Processing multiple projects in the same directory . . . 95
5.18 Using the *make* utility . . . 96
5.19 What next? . . . 97
**6 Converting an existing document . . . 98**
**7 Additional details . . . 99**
7.1 Localization . . . 99
7.2 Accessibility . . . 99
7.3 Shell escape . . . 101
7.4 Font and UTF-8 support . . . 101
7.4.1 Indexes, glossaries, and encoding . . . 103
7.5 lwarp package loading and options . . . 104
7.6 Customizing the HTML output . . . 109
7.6.1 Example HTML file naming . . . 115
7.7 Customizing the CSS . . . 115
7.8 Assigning CSS classes and styles . . . 117
7.9 Selecting the operating system . . . 117
7.10 Selecting actions for print, HTML, or MathJax output . . . 117

7.11 Commands to be placed into the warpprint environment . . . . . 118
7.12 Title page . . . . . 119
7.13 HTML page meta descriptions . . . . . 120
7.14 HTML homepage meta title . . . . . 120
7.15 HTML page meta author . . . . . 120
**8 Special cases and limitations . . . . . 121**
8.1 Things to avoid . . . . . 121
8.1.1 Invalid HTML . . . . . 122
8.2 Formatting . . . . . 122
8.2.1 Text formatting . . . . . 122
8.2.2 Small caps . . . . . 122
8.2.3 Horizontal and vertical space and rules . . . . . 122
8.2.4 Text alignment . . . . . 123
8.2.5 Accents . . . . . 123
8.2.6 textcomp package . . . . . 123
8.2.7 Superscripts and other non-math uses of math mode . . . . . 123
8.2.8 Empty \item followed by a new line of text or a nested list: . . . . . 123
8.2.9 Filenames and URLs in lists or footnotes . . . . . 124
8.2.10 relsize package . . . . . 124
8.3 Boxes and minipages . . . . . 124
8.3.1 Marginpars . . . . . 124
8.3.2 Save Boxes . . . . . 124
8.3.3 Minipages . . . . . 124
8.3.4 Side-by-side minipages . . . . . 125
8.3.5 Framed minipages and other environments . . . . . 125
8.3.6 fancybox package . . . . . 127
8.3.7 mdframed package . . . . . 128
8.3.8 tcolorbox package . . . . . 128
8.4 Section names . . . . . 129

8.5 Cross-references . . . 130
8.5.1 Page references . . . 130
8.5.2 cleveref and varioref packages . . . 130
8.5.3 Hyperlinks, hyperref, and url . . . 130
8.5.4 Footnotes, endnotes, and page notes . . . 131
8.5.5 xr, xr-hyper, and xcite packages . . . 132
8.6 Front and back matter . . . 132
8.6.1 Custom classes with multiple authors and affiliations . . . 133
8.6.2 Starred chapters and sections . . . 133
8.6.3 abstract package . . . 133
8.6.4 titling and authblk . . . 134
8.6.5 tocloft package . . . 134
8.6.6 appendix package . . . 134
8.6.7 pagenote package . . . 134
8.6.8 endnotes package . . . 134
8.6.9 *BibTeX* . . . 134
8.6.10 xcite package . . . 135
8.6.11 gloss package . . . 135
8.6.12 glossaries package . . . 135
8.6.13 nomencl package . . . 136
8.6.14 Indexing overview . . . 136
8.6.15 Indexing with makeidx, *makeindex*, *xindy*, *xindex*, gindex . . . 137
8.6.16 Indexing with index . . . 138
8.6.17 Indexing with splitidx . . . 139
8.6.18 Indexing with imakeidx . . . 141
8.6.19 Indexes with memoir . . . 144
8.6.20 Using a custom *makeindex* style file . . . 147
8.6.21 Using a custom *xindy* style file . . . 147
8.6.22 Using a custom *xindex* style file . . . 148
8.6.23 Additional indexing limitations . . . 149

8.6.24 Index positions, TOC, tocbibind . . . 149
8.7 Math . . . 150
8.7.1 Math in section names . . . 150
8.7.2 Rendering tradeoffs . . . 150
8.7.3 SVG option . . . 151
8.7.4 MathJax option . . . 152
8.7.5 Customizing MathJax . . . 152
8.7.6 MathJax limitations . . . 153
8.7.7 Catcode changes . . . 154
8.7.8 Complicated inline math objects . . . 154
8.7.9 Complicated display math objects . . . 155
8.7.10 ntheorem package . . . 155
8.7.11 mathtools package . . . 156
8.7.12 siunitx package . . . 156
8.7.13 units and nicefrac packages . . . 157
8.7.14 physics package . . . 157
8.8 Graphics . . . 157
8.8.1 tikz package . . . 158
8.8.2 grffile package . . . 159
8.8.3 color package . . . 159
8.8.4 xcolor package . . . 159
8.8.5 epstopdf package . . . 159
8.8.6 pstricks package . . . 160
8.8.7 pdftricks package . . . 160
8.8.8 psfrag package . . . 160
8.8.9 pstool package . . . 160
8.8.10 asymptote package . . . 161
8.8.11 overpic package . . . 161
8.8.12 Multimedia packages . . . 161
8.9 Tabbing . . . 162

8.10 Tabular . . . . . 162
8.10.1 tabular environment . . . . . 162
8.10.2 multirow package . . . . . 164
8.10.3 longtable package . . . . . 165
8.10.4 threeparttablex package . . . . . 166
8.10.5 supertabular and xtab packages . . . . . 166
8.10.6 colortbl package . . . . . 166
8.10.7 ctable package . . . . . 167
8.10.8 bigdelim package . . . . . 167
8.11 Floats . . . . . 167
8.11.1 Float contents alignment . . . . . 167
8.11.2 float, trivfloat, and/or algorithmicx together . . . . . 167
8.11.3 caption and subcaption packages . . . . . 168
8.11.4 subfig package . . . . . 168
8.11.5 floatrow package . . . . . 168
8.11.6 keyfloat package . . . . . 169
8.12 KOMA-SCRIPT classes . . . . . 169
8.13 MEMOIR class . . . . . 169
8.14 International languages . . . . . 171
8.15 Miscellaneous packages . . . . . 171
8.15.1 verse and memoir . . . . . 171
8.15.2 newclude package . . . . . 172
8.15.3 babel package . . . . . 172
8.15.4 polyglossia package . . . . . 172
8.15.5 todonotes and luatodonotes packages . . . . . 173
8.15.6 fixme . . . . . 173
8.15.7 acro package . . . . . 173
8.15.8 chemfig package . . . . . 173
8.15.9 chemformula package . . . . . 173
8.15.10 mhchem package . . . . . 173

8.15.11 kotex package . . . 174
**9 Compiling using custom shell commands . . . 175**
9.1 Command options . . . 175
9.2 Literal character macros . . . 175
9.3 *latexmk* . . . 176
9.4 perltex package . . . 177
9.5 pythontex package . . . 177
9.6 Other packages . . . 177
9.7 *make* program . . . 178
9.8 UTF-8 locale . . . 178
**10 EPUB conversion . . . 179**
**11 Word-processor conversion . . . 181**
11.1 Activating word-processor conversion . . . 181
11.2 Additional modifications . . . 182
11.3 Recommendations . . . 184
11.4 Limitations . . . 185
**12 Modifying lwarp . . . 186**
12.1 Creating a development system . . . 186
12.2 Modifying a package for lwarp . . . 188
12.2.1 Adding a package to the lwarp.dtx file . . . 188
12.3 Modifying a class for lwarp . . . 189
12.4 Testing lwarp . . . 189
12.5 Modifying *lwarpmk* . . . 189
**13 Troubleshooting . . . 191**
13.1 lwarp package error conditions and warnings . . . 191
13.1.1 Configuration file `lwarpmk.conf` . . . 191
13.1.2 Image generation with **`lwarpmk limages`** . . . 191
13.1.3 Default bitmapped font . . . 192
13.1.4 Packages . . . 192
13.1.5 Compiling . . . 192

13.2 Using the lwarp package . . . . . 193
13.2.1 Debug tracing output . . . . . 197
13.3 Compiling the lwarp.dtx file . . . . . 197
**14 Trademarks . . . . . 198**
**1 lwarp.sty . . . . . 199**
**15 Implementation . . . . . 199**
**16 Section depths and HTML headings . . . . . 200**
**17 Source code . . . . . 201**
**18 Detecting the TeX engine — *pdflatex*, *lualatex*, *xelatex* . . . . . 202**
**19 Early package requirements . . . . . 202**
**20 Package load order . . . . . 202**
20.1 Tests of package load order . . . . . 203
20.2 Error for disallowed packages and classes loaded before lwarp . . . . 205
20.3 Enforcing package loading after lwarp . . . . . 206
**21 MD5 hashing . . . . . 217**
**22 pdfLaTeX T1 and UTF-8 encoding . . . . . 217**
**23 Unicode input characters . . . . . 218**
**24 Avoid a bitmapped font . . . . . 218**
**25 Upright quotes . . . . . 219**
**26 Avoid bad font combinations . . . . . 219**
**27 Miscellaneous tools . . . . . 220**
27.1 Variables . . . . . 220
27.2 Lengths and units . . . . . 220
27.3 Counters . . . . . 221
27.4 Patching . . . . . 221
27.5 Chinese text isolation . . . . . 221
27.6 Inserting vertical space . . . . . 221
27.7 Argument selection . . . . . 222
27.8 Inside boxes . . . . . 222
27.9 Global boxes . . . . . 222

27.10 Converting a macro name to a cs name . . . 223
27.11 Title case . . . 223
27.12 LetLtxMacrocs . . . 224
27.13 Absorbing a star . . . 224
**28 Operating-System portability . . . 224**
28.1 Literal characters . . . 224
28.2 Common portability code . . . 226
28.3 Unix, Linux, and Mac OS . . . 226
28.4 MS-Windows . . . 226
**29 Package options . . . 226**
29.1 Additional options support . . . 231
29.2 Conditional compilation . . . 233
**30 Required packages . . . 235**
**31 Loading packages . . . 241**
**32 File handles . . . 247**
**33 Include a file . . . 247**
**34 Copying a file . . . 248**
**35 Debugging messages . . . 249**
**36 Defining print and html versions of macros and environments . . . 250**
**37 html-conversion output modifications . . . 255**
37.1 User-level controls . . . 255
37.2 Heading adjustments . . . 257
**38 Remembering original formatting macros . . . 258**
**39 Accents . . . 260**
**40 Configuration files . . . 262**
40.1 Decide whether to generate configuration files . . . 262
40.2 `<project>_html.tex` . . . 262
40.3 *lwarpmk* configuration files . . . 263
40.3.1 Helper macros . . . 263
40.3.2 `lwarpmk.conf` . . . 268

40.3.3 <project>.lwarpmkconf . . . 269
40.4 lwarp.css . . . 269
40.5 lwarp_sagebrush.css . . . 301
40.6 lwarp_formal.css . . . 305
40.7 sample_project.css . . . 309
40.8 lwarp.ist . . . 310
40.9 lwarp.xdy . . . 310
40.10 lwarp_one_limage.cmd . . . 311
40.11 lwarp_mathjax.txt . . . 312
40.12 lwarpmk.lua — lwarpmk option . . . 316
**41 Stacks . . . 334**
41.1 Assigning depths . . . 334
41.2 Closing actions . . . 335
41.3 Closing depths . . . 335
41.4 Pushing and popping the stack . . . 336
**42 Data arrays . . . 337**
**43 Localizing catcodes . . . 338**
**44 Localizing dynamic math . . . 339**
**45 HTML entities . . . 339**
**46 HTML filename generation . . . 340**
**47 Homepage link . . . 343**
**48 Previous/next navigation links . . . 344**
**49 \LWRPrintStack diagnostic tool . . . 346**
**50 Closing stack levels . . . 346**
**51 PDF pages and styles . . . 347**
**52 HTML tags, spans, divs, elements . . . 348**
52.1 Mapping LaTeX sections to HTML sections . . . 349
52.2 Hook while processing tags . . . 349
52.3 Babel-French tag modifications . . . 349
52.4 HTML output formatting . . . 350

52.5 HTML tags. . . . . 351
52.6 Block tags and comments . . . . . 353
52.7 Div class and element class . . . . . 354
52.8 Single-line elements . . . . . 356
52.9 HTML5 semantic elements . . . . . 356
52.10 High-level block and inline classes . . . . . 356
52.11 Closing HTML tags . . . . . 358
**53 Paragraph handling . . . . . 359**
**54 Paragraph start/stop handling . . . . . 362**
**55 Indentfirst . . . . . 365**
**56 Page headers and footers . . . . . 365**
**57 CSS . . . . . 366**
**58 MathJax script . . . . . 366**
**59 Title, HTML meta author, HTML meta description . . . . . 367**
**60 Footnotes . . . . . 368**
60.1 Regular page footnotes . . . . . 369
60.2 Minipage footnotes . . . . . 369
60.3 Titlepage thanks . . . . . 369
60.4 Regular page footnote implementation . . . . . 369
60.5 Minipage footnote implementation . . . . . 372
60.6 Printing pending footnotes . . . . . 373
**61 Marginpars . . . . . 374**
**62 Splitting HTML files . . . . . 375**
62.1 Sanitizing expressions for HTML . . . . . 381
62.2 Customizing MathJax . . . . . 383
**63 Sectioning . . . . . 391**
63.1 User-level starred section commands . . . . . 391
63.2 Book class commands. . . . . 392
63.3 Sectioning support macros . . . . . 392
63.4 Pre- and post- sectioning names . . . . . 400

63.5 \section and friends . . . . . 400
**64 Starting a new file . . . . . 402**
**65 Starting HTML output . . . . . 406**
**66 Ending HTML output . . . . . 409**
**67 Nullifying foreground/background hooks . . . . . 411**
**68 Title page . . . . . 411**
68.1 Setting the title, etc. . . . . 412
68.2 \if@titlepage . . . . . 413
68.3 Changes for \affiliation . . . . . 413
68.4 Printing the thanks . . . . . 414
68.5 Printing the title, etc. in HTML . . . . . 414
68.6 Printing the title, etc. in print form . . . . . 416
68.7 \maketitle for HTML output . . . . . 416
68.8 \published and \subtitle . . . . . 419
**69 Abstract . . . . . 420**
**70 Quote and verse . . . . . 421**
70.1 Attributions . . . . . 421
70.2 Quotes, quotations . . . . . 421
70.3 Verse . . . . . 422
70.3.1 LaTeX core verse environment . . . . . 423
70.3.2 verse and memoir . . . . . 423
**71 Verbatim and tabbing . . . . . 423**
**72 Theorems . . . . . 426**
**73 Lists . . . . . 427**
73.1 List environment . . . . . 428
73.2 Itemize . . . . . 431
73.3 Enumerate . . . . . 432
73.4 Description . . . . . 432
73.5 Patching the lists . . . . . 433

**74 Tabular . . . . . 434**
74.1 Limitations . . . . . 434
74.2 Temporary package-related macros . . . . . 437
74.2.1 arydshln . . . . . 437
74.3 Token lookahead . . . . . 437
74.4 Tabular variables . . . . . 438
74.4.1 Multicolumn variables . . . . . 441
74.4.2 Longtable variables . . . . . 441
74.4.3 Midrule variables . . . . . 441
74.5 Handling &, @, !, and bar . . . . . 441
74.5.1 Handling &. . . . . 443
74.5.2 Filling an unfinished row . . . . . 444
74.6 Handling \\ . . . . . 446
74.7 Looking ahead in the column specifications . . . . . 447
74.8 Parsing @, >, <, !, bar columns . . . . . 447
74.9 Parsing ‘l’, ‘c’, or ‘r’ columns . . . . . 451
74.10 Parsing ‘p’, ‘m’, or ‘b’ columns . . . . . 452
74.11 Parsing ‘w’ columns . . . . . 452
74.12 Parsing ’*’ columns . . . . . 452
74.13 Parsing ‘D’ columns . . . . . 452
74.14 Expanding the star column specifications . . . . . 453
74.15 Parsing the column specifications. . . . . 454
74.16 colortbl and xcolor tabular color support . . . . . 459
74.17 Starting a new row . . . . . 460
74.18 Printing vertical bar tags. . . . . 461
74.19 Printing @ or ! tags . . . . . 461
74.20 Data opening tag . . . . . 462
74.21 Midrules . . . . . 464
74.22 Cell colors . . . . . 469

74.23 Multicolumns . . . 473
74.23.1 Parsing multicolumns . . . 473
74.23.2 Multicolumn factored code . . . 476
74.23.3 Multicolumn . . . 479
74.23.4 Longtable captions . . . 480
74.23.5 Counting HTML tabular columns . . . 482
74.24 Multirow if not loaded . . . 484
74.25 Multicolumnrow . . . 484
74.26 Utility macros inside a table . . . 485
74.27 Special-case tabular markers . . . 485
74.28 Checking for a new table cell . . . 486
74.29 \mrowcell . . . 489
74.30 \mcolrowcell . . . 489
74.31 HTML tabular environment . . . 490
**75 Cross-references . . . 496**
75.1 Setup . . . 498
75.2 New lwarp labels. . . . 498
75.3 Labels . . . 499
75.4 References . . . 502
75.5 Hyper-references . . . 504
**76 Floats . . . 509**
76.1 Float environment . . . 509
76.2 Float tracking . . . 512
76.3 Caption inside a float environment . . . 513
76.4 Caption and LOF linking and tracking . . . 514
**77 Table of Contents, LOF, LOT . . . 517**
77.1 Reading and printing the TOC . . . 518
77.2 High-level TOC commands . . . 521
77.3 Side TOC . . . 521
77.4 Low-level TOC line formatting . . . 522

**78 Index and glossary . . . 526**
**79 Bibliography presentation . . . 534**
**80 Restoring original formatting . . . 535**
**81 Nullifying filename formatting . . . 537**
**82 Math . . . 540**
82.1 Limitations . . . 540
82.2 HTML `alt` tag names . . . 540
82.3 Inline and display math . . . 541
82.4 MathJax support . . . 554
82.5 Equation environment . . . 557
82.6 `\displaymathnormal` and `\displaymathother` . . . 561
82.7 AMS Math environments . . . 562
82.7.1 Support macros . . . 562
82.7.2 Environment patches . . . 563
**83 Lateximages . . . 565**
83.1 Description . . . 565
83.2 Support counters and macros . . . 566
83.3 Font size . . . 567
83.4 Equation numbers . . . 567
83.5 HTML `alt` tags . . . 568
83.6 `lateximage` environment . . . 569
**84 `center`, `flushleft`, `flushright` . . . 575**
**85 Preloaded packages . . . 577**
**86 siunitx . . . 579**
**87 Graphics print-mode modifications . . . 580**
87.1 General limitations . . . 580
87.2 Print-mode modifications . . . 581
**88 xcolor boxes . . . 582**
**89 chemmacros environments . . . 585**
**90 cleveref . . . 585**

**91 Preexisting label and reference definitions . . . 586**
**92 picture environment . . . 586**
**93 Minipages and Boxes . . . 586**
93.1 Computed lengths . . . 587
93.2 Virtual page size . . . 588
93.3 Footnote handling . . . 588
93.4 Minipage handling . . . 588
93.5 \parbox, \mbox, \makebox, \framebox, \fbox, \raisebox . . . 592
**94 Direct formatting . . . 597**
**95 Skips, spaces, font sizes . . . 608**
**96 \phantomsection . . . 615**
**97 \LaTeX and other logos . . . 616**
**98 Starting and stopping lwarp . . . 619**
**99 Loading everyshi patches . . . 620**
**100 Loading textcomp patches . . . 620**
**101 Loading amsmath, amsthm patches, centernot . . . 620**
**102 Loading KOMA-SCRIPT class patches . . . 620**
**103 Loading MEMOIR class patches . . . 621**
**104 ut* class patches . . . 621**
**105 CTEX patches . . . 622**
**106 kotexutf patches . . . 623**
**107 babel and polyglossia warnings . . . 624**
**108 MATHJAX warnings . . . 625**
**2 lwarp-2in1.sty . . . 628**
**3 lwarp-2up.sty . . . 628**
**4 lwarp-a4.sty . . . 628**
**5 lwarp-a4wide.sty . . . 628**
**6 lwarp-a5comb.sty . . . 629**
**7 lwarp-abstract.sty . . . 629**

8 lwarp-academicons.sty . . . . . 631
9 lwarp-accents.sty . . . . . 632
10 lwarp-accessibility.sty . . . . . 633
11 lwarp-accsupp.sty . . . . . 633
12 lwarp-acro.sty . . . . . 634
13 lwarp-acronym.sty . . . . . 636
14 lwarp-adjmulticol.sty . . . . . 637
15 lwarp-addlines.sty . . . . . 638
16 lwarp-afterpage.sty . . . . . 639
17 lwarp-algorithm2e.sty . . . . . 639
18 lwarp-algorithmicx.sty . . . . . 643
19 lwarp-alltt.sty . . . . . 643
20 lwarp-amscdx.sty . . . . . 644
21 lwarp-amsmath.sty . . . . . 645
22 lwarp-amsthm.sty . . . . . 649
23 lwarp-anonchap.sty . . . . . 653
24 lwarp-anysize.sty . . . . . 653
25 lwarp-appendix.sty . . . . . 654
26 lwarp-ar.sty . . . . . 654
27 lwarp-arabicfront.sty . . . . . 656
28 lwarp-array.sty . . . . . 656
29 lwarp-arydshln.sty . . . . . 656
30 lwarp-asymptote.sty . . . . . 658
31 lwarp-atbegshi.sty . . . . . 659
32 lwarp-attachfile.sty . . . . . 660
33 lwarp-attachfile2.sty . . . . . 661
34 lwarp-authblk.sty . . . . . 663

35 lwarp-autobreak.sty . . . . . 664
36 lwarp-autonum.sty . . . . . 664
37 lwarp-awesomebox.sty . . . . . 665
38 lwarp-axessibility.sty . . . . . 667
39 lwarp-axodraw2.sty . . . . . 667
40 lwarp-backnaur.sty . . . . . 668
41 lwarp-backref.sty . . . . . 669
42 lwarp-balance.sty . . . . . 669
43 lwarp-bbding.sty . . . . . 669
44 lwarp-biblatex.sty . . . . . 674
45 lwarp-bibunits.sty . . . . . 678
46 lwarp-bigdelim.sty . . . . . 678
47 lwarp-bigfoot.sty . . . . . 680
48 lwarp-bigstrut.sty . . . . . 680
49 lwarp-bitpattern.sty . . . . . 681
50 lwarp-blowup.sty . . . . . 681
51 lwarp-bm.sty . . . . . 681
52 lwarp-booklet.sty . . . . . 682
53 lwarp-bookmark.sty . . . . . 682
54 lwarp-booktabs.sty . . . . . 683
55 lwarp-bophook.sty . . . . . 685
56 lwarp-bounddvi.sty . . . . . 685
57 lwarp-boxedminipage.sty . . . . . 685
58 lwarp-boxedminipage2e.sty . . . . . 686
59 lwarp-braket.sty . . . . . 686
60 lwarp-breakurl.sty . . . . . 686
61 lwarp-breqn.sty . . . . . 687

**62 lwarp-bsheaders.sty . . . . . 688**
**63 lwarp-bussproofs.sty . . . . . 688**
**64 lwarp-bxpapersize.sty . . . . . 689**
**65 lwarp-bytefield.sty . . . . . 689**
**66 lwarp-cancel.sty . . . . . 690**
**67 lwarp-canoniclayout.sty . . . . . 691**
**68 lwarp-caption.sty . . . . . 691**
**69 lwarp-caption3.sty . . . . . 693**
**70 lwarp-cases.sty . . . . . 695**
**71 lwarp-centernot.sty . . . . . 696**
**72 lwarp-changebar.sty . . . . . 696**
**73 lwarp-changelayout.sty . . . . . 697**
**74 lwarp-changepage.sty . . . . . 697**
**75 lwarp-changes.sty . . . . . 698**
**76 lwarp-chappg.sty . . . . . 703**
**77 lwarp-chapterbib.sty . . . . . 703**
**78 lwarp-chemfig.sty . . . . . 703**
**79 lwarp-chemformula.sty . . . . . 705**
**80 lwarp-chemgreek.sty . . . . . 711**
**81 lwarp-chemmacros.sty . . . . . 711**
**188 chemmacros . . . . . 711**
188.1 Changes to the user's document . . . . . 712
188.2 Code . . . . . 712
188.3 Loading modules . . . . . 712
188.4 New environments . . . . . 712
188.5 Acid-base . . . . . 713
188.6 Charges . . . . . 715
188.7 Nomenclature . . . . . 715

188.8 Particles . . . 717
188.9 Phases . . . 718
188.10 Mechanisms . . . 718
188.11 Newman . . . 720
188.12 Orbital . . . 721
188.13 Reactions . . . 721
188.14 Redox . . . 722
188.15 Scheme . . . 723
188.16 Spectroscopy . . . 723
188.17 Thermodynamics . . . 727

**82 lwarp-chemnum.sty . . . 729**
**83 lwarp-chkfloat.sty . . . 730**
**84 lwarp-chngpage.sty . . . 730**
**85 lwarp-cite.sty . . . 730**
**86 lwarp-citeref.sty . . . 731**
**87 lwarp-CJK.sty . . . 731**
**88 lwarp-CJKutf8.sty . . . 731**
**89 lwarp-cleveref.sty . . . 732**
**90 lwarp-clrdblpg.sty . . . 735**
**91 lwarp-cmbright.sty . . . 735**
**92 lwarp-cmdtrack.sty . . . 736**
**93 lwarp-colonequals.sty . . . 736**
**94 lwarp-color.sty . . . 737**
**95 lwarp-colortbl.sty . . . 737**
**96 lwarp-continue.sty . . . 739**
**97 lwarp-copyrightbox.sty . . . 739**
**98 lwarp-crop.sty . . . 740**
**99 lwarp-ctable.sty . . . 740**

100 lwarp-cuted.sty . . . . . 743
101 lwarp-cutwin.sty . . . . . 743
102 lwarp-dblfloatfix.sty . . . . . 744
103 lwarp-dblfnote.sty . . . . . 744
104 lwarp-dcolumn.sty . . . . . 744
105 lwarp-decimal.sty . . . . . 744
106 lwarp-diagbox.sty . . . . . 745
107 lwarp-dingbat.sty . . . . . 746
108 lwarp-DotArrow.sty . . . . . 747
109 lwarp-dotlessi.sty . . . . . 748
110 lwarp-dprogress.sty . . . . . 748
111 lwarp-draftcopy.sty . . . . . 748
112 lwarp-draftfigure.sty . . . . . 749
113 lwarp-draftwatermark.sty . . . . . 749
114 lwarp-drftcite.sty . . . . . 749
115 lwarp-easy-todo.sty . . . . . 750
116 lwarp-ebook.sty . . . . . 751
117 lwarp-econometrics.sty . . . . . 751
118 lwarp-ed.sty . . . . . 754
119 lwarp-ellipsis.sty . . . . . 754
120 lwarp-embrac.sty . . . . . 755
121 lwarp-emptypage.sty . . . . . 756
122 lwarp-endfloat.sty . . . . . 756
123 lwarp-endheads.sty . . . . . 756
124 lwarp-endnotes.sty . . . . . 757
125 lwarp-engtlc.sty . . . . . 758
126 lwarp-enumerate.sty . . . . . 762

127 lwarp-enumitem.sty . . . . . 763
128 lwarp-epigraph.sty . . . . . 763
129 lwarp-epsf.sty . . . . . 764
130 lwarp-epsfig.sty . . . . . 764
131 lwarp-epstopdf.sty . . . . . 765
132 lwarp-epstopdf-base.sty . . . . . 765
133 lwarp-eqlist.sty . . . . . 766
134 lwarp-eqparbox.sty . . . . . 767
135 lwarp-errata.sty . . . . . 768
136 lwarp-eso-pic.sty . . . . . 769
137 lwarp-esvect.sty . . . . . 769
138 lwarp-etoc.sty . . . . . 770
139 lwarp-eurosym.sty . . . . . 772
140 lwarp-everypage.sty . . . . . 773
141 lwarp-everyshi.sty . . . . . 773
142 lwarp-extarrows.sty . . . . . 773
143 lwarp-extramarks.sty . . . . . 774
144 lwarp-fancybox.sty . . . . . 774
145 lwarp-fancyhdr.sty . . . . . 779
146 lwarp-fancyref.sty . . . . . 780
147 lwarp-fancytabs.sty . . . . . 781
148 lwarp-fancyvrb.sty . . . . . 781
149 lwarp-fbox.sty . . . . . 788
150 lwarp-fewerfloatpages.sty . . . . . 790
151 lwarp-figcaps.sty . . . . . 790
152 lwarp-figsize.sty . . . . . 791
153 lwarp-fitbox.sty . . . . . 791

154 lwarp-fix2col.sty . . . . . 792
155 lwarp-fixmath.sty . . . . . 792
156 lwarp-fixme.sty . . . . . 792
157 lwarp-fixmetodonotes.sty . . . . . 794
158 lwarp-flafter.sty . . . . . 794
159 lwarp-flippdf.sty . . . . . 794
160 lwarp-float.sty . . . . . 795
161 lwarp-floatflt.sty . . . . . 796
162 lwarp-floatpag.sty . . . . . 797
163 lwarp-floatrow.sty . . . . . 797
164 lwarp-fltrace.sty . . . . . 802
165 lwarp-flushend.sty . . . . . 803
166 lwarp-fnbreak.sty . . . . . 803
167 lwarp-fncychap.sty . . . . . 803
168 lwarp-fnlineno.sty . . . . . 804
169 lwarp-fnpara.sty . . . . . 804
170 lwarp-fnpos.sty . . . . . 804
171 lwarp-fontawesome.sty . . . . . 805
172 lwarp-fontawesome5.sty . . . . . 806
173 lwarp-fontaxes.sty . . . . . 807
174 lwarp-fontenc.sty . . . . . 807
175 lwarp-footmisc.sty . . . . . 808
176 lwarp-footnote.sty . . . . . 809
177 lwarp-footnotebackref.sty . . . . . 810
178 lwarp-footnotehyper.sty . . . . . 810
179 lwarp-footnoterange.sty . . . . . 810
180 lwarp-footnpag.sty . . . . . 810

**181 lwarp-foreign.sty . . . . . 810**
**182 lwarp-forest.sty . . . . . 811**
**183 lwarp-fouridx.sty . . . . . 811**
**184 lwarp-fourier.sty. . . . . 812**
**185 lwarp-framed.sty . . . . . 813**
**186 lwarp-ftcap.sty . . . . . 816**
**187 lwarp-ftnright.sty . . . . . 816**
**188 lwarp-fullminipage.sty . . . . . 816**
**189 lwarp-fullpage.sty . . . . . 816**
**190 lwarp-fullwidth.sty . . . . . 817**
**191 lwarp-fvextra.sty . . . . . 817**
**192 lwarp-fwlw.sty . . . . . 820**
**193 lwarp-gensymb.sty. . . . . 820**
**194 lwarp-gentombow.sty . . . . . 821**
**195 lwarp-geometry.sty . . . . . 821**
**196 lwarp-ghsystem.sty . . . . . 822**
**197 lwarp-gindex.sty. . . . . 822**
**198 lwarp-gloss.sty . . . . . 823**
**199 lwarp-glossaries.sty . . . . . 824**
**200 lwarp-gmeometric.sty . . . . . 826**
**201 lwarp-graphics.sty . . . . . 826**
**308 graphics . . . . . 826**
308.1 Graphics extensions . . . . . 827
308.2 Length conversions and graphics options . . . . . 827
308.3 Printing HTML styles . . . . . 830
308.4 \includegraphics . . . . . 830
308.5 Boxes . . . . . 836
**202 lwarp-graphicx.sty. . . . . 838**

203 lwarp-grffile.sty . . . . . 839
204 lwarp-grid.sty . . . . . 839
205 lwarp-grid-system.sty . . . . . 839
206 lwarp-gridset.sty . . . . . 840
207 lwarp-hang.sty . . . . . 840
208 lwarp-hanging.sty . . . . . 842
209 lwarp-hepunits.sty . . . . . 842
210 lwarp-hhline.sty . . . . . 844
211 lwarp-hhtensor.sty . . . . . 844
212 lwarp-hypbmsec.sty . . . . . 845
213 lwarp-hypcap.sty . . . . . 845
214 lwarp-hypdestopt.sty . . . . . 846
215 lwarp-hypernat.sty . . . . . 846
216 lwarp-hyperref.sty . . . . . 846
217 lwarp-hyperxmp.sty . . . . . 855
218 lwarp-hyphenat.sty . . . . . 856
219 lwarp-idxlayout.sty . . . . . 856
220 lwarp-ifoddpage.sty . . . . . 857
221 lwarp-imakeidx.sty . . . . . 858
222 lwarp-impnattypo.sty . . . . . 862
223 lwarp-index.sty . . . . . 862
224 lwarp-inputtrc.sty . . . . . 863
225 lwarp-intopdf.sty . . . . . 864
226 lwarp-isomath.sty . . . . . 864
227 lwarp-isotope.sty . . . . . 865
228 lwarp-jurabib.sty . . . . . 866
229 lwarp-karnaugh-map.sty . . . . . 867

230 lwarp-keyfloat.sty . . . . . 870
231 lwarp-keystroke.sty . . . . . 876
232 lwarp-kpfonts.sty . . . . . 877
233 lwarp-kpfonts-otf.sty . . . . . 879
234 lwarp-layaureo.sty . . . . . 880
235 lwarp-layout.sty . . . . . 880
236 lwarp-layouts.sty . . . . . 881
237 lwarp-leading.sty . . . . . 883
238 lwarp-leftidx.sty . . . . . 883
239 lwarp-letterspace.sty . . . . . 884
240 lwarp-lettrine.sty . . . . . 884
241 lwarp-libertinust1math.sty . . . . . 885
242 lwarp-lineno.sty . . . . . 891
243 lwarp-lips.sty . . . . . 894
244 lwarp-listings.sty . . . . . 894
245 lwarp-listliketab.sty . . . . . 899
246 lwarp-lltjext.sty . . . . . 899
247 lwarp-longtable.sty . . . . . 900
248 lwarp-lpic.sty . . . . . 903
249 lwarp-lscape.sty . . . . . 903
250 lwarp-ltablex.sty . . . . . 903
251 lwarp-ltcaption.sty . . . . . 904
252 lwarp-ltxgrid.sty . . . . . 904
253 lwarp-ltxtable.sty . . . . . 905
254 lwarp-lua-check-hyphen.sty . . . . . 905
255 lwarp-lua-visual-debug.sty . . . . . 905
256 lwarp-luacolor.sty . . . . . 905

257 lwarp-luamplib.sty . . . . . 906
258 lwarp-luatexko.sty . . . . . 906
259 lwarp-luatodonotes.sty . . . . . 908
260 lwarp-luavlna.sty . . . . . 910
261 lwarp-lyluatex.sty . . . . . 910
262 lwarp-magaz.sty . . . . . 912
263 lwarp-makeidx.sty . . . . . 913
264 lwarp-manyfoot.sty . . . . . 913
265 lwarp-marginal.sty . . . . . 915
266 lwarp-marginfit.sty . . . . . 915
267 lwarp-marginfix.sty . . . . . 916
268 lwarp-marginnote.sty . . . . . 916
269 lwarp-marvosym.sty . . . . . 917
270 lwarp-mathalpha.sty . . . . . 917
271 lwarp-mathastext.sty . . . . . 918
272 lwarp-mathcomp.sty . . . . . 919
273 lwarp-mathdesign.sty . . . . . 919
274 lwarp-mathdots.sty . . . . . 921
275 lwarp-mathfixs.sty . . . . . 921
276 lwarp-mathpazo.sty . . . . . 922
277 lwarp-mathptmx.sty . . . . . 922
278 lwarp-mathspec.sty . . . . . 923
279 lwarp-mathtools.sty . . . . . 925
280 lwarp-mattens.sty . . . . . 931
281 lwarp-maybemath.sty . . . . . 933
282 lwarp-mcaption.sty . . . . . 933

**283 lwarp-mdframed.sty . . . . . 933**

**390 mdframed . . . . . 933**

390.1 Limitations . . . . . 934

390.2 Package loading . . . . . 934

390.3 Patches . . . . . 934

390.4 Initial setup . . . . . 935

390.5 Color and length HTML conversion . . . . . 935

390.6 Environment encapsulation . . . . . 936

390.7 Mdframed environment . . . . . 937

390.8 Titles and subtitles . . . . . 938

390.9 New environments . . . . . 940

**284 lwarp-mdwmath.sty . . . . . 942**

**285 lwarp-media9.sty . . . . . 943**

**286 lwarp-memhfixc.sty . . . . . 945**

**287 lwarp-menukeys.sty . . . . . 945**

**288 lwarp-metalogo.sty . . . . . 946**

**289 lwarp-metalogox.sty . . . . . 946**

**290 lwarp-mhchem.sty . . . . . 947**

**291 lwarp-microtype.sty . . . . . 949**

**292 lwarp-midfloat.sty . . . . . 950**

**293 lwarp-midpage.sty . . . . . 951**

**294 lwarp-minibox.sty . . . . . 951**

**295 lwarp-minitoc.sty . . . . . 952**

**296 lwarp-minted.sty . . . . . 952**

**297 lwarp-mismath.sty . . . . . 953**

**298 lwarp-mleftright.sty . . . . . 957**

**299 lwarp-morefloats.sty . . . . . 957**

**300 lwarp-moreverb.sty . . . . . 957**

301 lwarp-movie15.sty . . . . . 958
302 lwarp-mparhack.sty . . . . . 960
303 lwarp-multibib.sty . . . . . 960
304 lwarp-multicap.sty . . . . . 960
305 lwarp-multicol.sty . . . . . 961
306 lwarp-multicolrule.sty . . . . . 962
307 lwarp-multimedia.sty . . . . . 962
308 lwarp-multiobjective.sty . . . . . 963
309 lwarp-multirow.sty . . . . . 964
310 lwarp-multitoc.sty . . . . . 968
311 lwarp-musicography.sty . . . . . 968
312 lwarp-nameauth.sty . . . . . 971
313 lwarp-nameref.sty . . . . . 972
314 lwarp-natbib.sty . . . . . 973
315 lwarp-nccfancyhdr.sty . . . . . 973
316 lwarp-nccfoots.sty . . . . . 974
317 lwarp-nccmath.sty . . . . . 975
318 lwarp-needspace.sty . . . . . 976
319 lwarp-newpxmath.sty . . . . . 976
320 lwarp-newtxmath.sty . . . . . 977
321 lwarp-newtxsf.sty . . . . . 978
322 lwarp-nextpage.sty . . . . . 979
323 lwarp-nfssext-cfr.sty . . . . . 979
324 lwarp-nicefrac.sty . . . . . 986
325 lwarp-niceframe.sty . . . . . 987
326 lwarp-nicematrix.sty . . . . . 987
327 lwarp-noitcrul.sty . . . . . 990

**328 lwarp-nolbreaks.sty . . . . . 990**

**329 lwarp-nomencl.sty . . . . . 990**

**330 lwarp-nonfloat.sty . . . . . 991**

**331 lwarp-nonumonpart.sty . . . . . 991**

**332 lwarp-nopageno.sty . . . . . 991**

**333 lwarp-notes.sty . . . . . 991**

**334 lwarp-notespages.sty . . . . . 992**

**335 lwarp-nowidow.sty . . . . . 992**

**336 lwarp-ntheorem.sty . . . . . 993**

**443 ntheorem . . . . . 993**

443.1 Limitations . . . . . 993

443.2 Options . . . . . 994

443.3 Remembering the theorem style . . . . . 995

443.4 HTML cross-referencing . . . . . 998

443.5 \newtheoremstyle . . . . . 998

443.6 Standard styles . . . . . 998

443.7 Additional objects . . . . . 1000

443.8 Renewed standard configuration . . . . . 1000

443.9 amsthm option . . . . . 1001

443.10 Ending a theorem . . . . . 1003

443.11 \NoEndMark . . . . . 1004

443.12 List-of . . . . . 1004

443.13 Symbols . . . . . 1004

443.14 Cross-referencing . . . . . 1005

**337 lwarp-octave.sty . . . . . 1005**

**338 lwarp-overpic.sty . . . . . 1006**

**339 lwarp-pagegrid.sty . . . . . 1007**

**340 lwarp-pagenote.sty . . . . . 1007**

**341 lwarp-pagesel.sty . . . . . 1007**

342 lwarp-paralist.sty . . . . . 1007
343 lwarp-parallel.sty . . . . . 1008
344 lwarp-parcolumns.sty . . . . . 1010
345 lwarp-parnotes.sty . . . . . 1012
346 lwarp-parskip.sty . . . . . 1013
347 lwarp-pbox.sty . . . . . 1013
348 lwarp-pdfcol.sty . . . . . 1014
349 lwarp-pdfcolfoot.sty . . . . . 1014
350 lwarp-pdfcolmk.sty . . . . . 1015
351 lwarp-pdfcolparallel.sty . . . . . 1015
352 lwarp-pdfcolparcolumns.sty . . . . . 1015
353 lwarp-pdfcomment.sty . . . . . 1016
354 lwarp-pdfcrypt.sty . . . . . 1016
355 lwarp-pdflscape.sty . . . . . 1017
356 lwarp-pdfmarginpar.sty . . . . . 1017
357 lwarp-pdfpages.sty . . . . . 1017
358 lwarp-pdfprivacy.sty . . . . . 1020
359 lwarp-pdfrender.sty . . . . . 1020
360 lwarp-pdfsync.sty . . . . . 1020
361 lwarp-pdftricks.sty . . . . . 1020
362 lwarp-pdfx.sty . . . . . 1021
363 lwarp-perpage.sty . . . . . 1021
364 lwarp-pfnote.sty . . . . . 1023
365 lwarp-phfqit.sty . . . . . 1023
366 lwarp-physics.sty . . . . . 1023
367 lwarp-physunits.sty . . . . . 1024
368 lwarp-picinpar.sty . . . . . 1025

369 lwarp-pifont.sty . . . . . 1027
370 lwarp-pinlabel.sty . . . . . 1027
371 lwarp-placeins.sty . . . . . 1028
372 lwarp-plarydshln.sty . . . . . 1028
373 lwarp-plext.sty . . . . . 1028
374 lwarp-plextarydshln.sty . . . . . 1029
375 lwarp-plextcolortbl.sty . . . . . 1030
376 lwarp-plimsoll.sty . . . . . 1030
377 lwarp-prelim2e.sty . . . . . 1030
378 lwarp-prettyref.sty . . . . . 1031
379 lwarp-preview.sty . . . . . 1031
380 lwarp-psfrag.sty . . . . . 1031
381 lwarp-psfragx.sty . . . . . 1032
382 lwarp-pst-eps.sty . . . . . 1032
383 lwarp-pstool.sty . . . . . 1033
384 lwarp-pstricks.sty . . . . . 1033
385 lwarp-pxatbegshi.sty . . . . . 1034
386 lwarp-pxeveryshi.sty . . . . . 1034
387 lwarp-pxfonts.sty . . . . . 1034
388 lwarp-pxftnright.sty . . . . . 1035
389 lwarp-pxjahyper.sty . . . . . 1035
390 lwarp-quotchap.sty . . . . . 1035
391 lwarp-quoting.sty . . . . . 1036
392 lwarp-ragged2e.sty . . . . . 1037
393 lwarp-realscripts.sty . . . . . 1037
394 lwarp-refcheck.sty . . . . . 1040
395 lwarp-register.sty . . . . . 1041

396 lwarp-relsize.sty . . . . . 1042
397 lwarp-repeatindex.sty . . . . . 1043
398 lwarp-repltext.sty . . . . . 1044
399 lwarp-resizegather.sty . . . . . 1044
400 lwarp-returntogrid.sty . . . . . 1044
401 lwarp-rlepsf.sty . . . . . 1045
402 lwarp-rmathbr.sty . . . . . 1045
403 lwarp-rmpage.sty . . . . . 1045
404 lwarp-romanbar.sty . . . . . 1046
405 lwarp-romanbarpagenumber.sty . . . . . 1046
406 lwarp-rotating.sty . . . . . 1046
407 lwarp-rotfloat.sty . . . . . 1047
408 lwarp-rviewport.sty . . . . . 1048
409 lwarp-savetrees.sty . . . . . 1048
410 lwarp-scalefnt.sty . . . . . 1048
411 lwarp-scalerel.sty . . . . . 1049
412 lwarp-schemata.sty . . . . . 1049
413 lwarp-scrextend.sty . . . . . 1050
414 lwarp-scrhack.sty . . . . . 1054
415 lwarp-scrlayer.sty . . . . . 1054
416 lwarp-scrlayer-notecolumn.sty . . . . . 1055
417 lwarp-scrlayer-scrpage.sty . . . . . 1056
418 lwarp-scrpage2.sty . . . . . 1057
419 lwarp-section.sty . . . . . 1058
420 lwarp-sectionbreak.sty . . . . . 1059
421 lwarp-sectsty.sty . . . . . 1059
422 lwarp-selectp.sty . . . . . 1060

423 lwarp-semantic-markup.sty . . . . . 1060
424 lwarp-seqsplit.sty . . . . . 1061
425 lwarp-setspace.sty . . . . . 1062
426 lwarp-shadethm.sty . . . . . 1063
427 lwarp-shadow.sty . . . . . 1063
428 lwarp-shapepar.sty . . . . . 1064
429 lwarp-showidx.sty . . . . . 1064
430 lwarp-showkeys.sty . . . . . 1064
431 lwarp-showtags.sty . . . . . 1065
432 lwarp-shuffle.sty . . . . . 1065
433 lwarp-sidecap.sty . . . . . 1066
434 lwarp-sidenotes.sty . . . . . 1067
435 lwarp-simplebnf.sty . . . . . 1068
436 lwarp-SIunits.sty . . . . . 1069
437 lwarp-siunitx.sty . . . . . 1078
438 lwarp-skmath.sty . . . . . 1092
439 lwarp-slantsc.sty . . . . . 1098
440 lwarp-slashed.sty . . . . . 1098
441 lwarp-soul.sty . . . . . 1098
442 lwarp-soulpos.sty . . . . . 1100
443 lwarp-soulutf8.sty . . . . . 1101
444 lwarp-splitbib.sty . . . . . 1101
445 lwarp-splitidx.sty . . . . . 1102
446 lwarp-srcltx.sty . . . . . 1103
447 lwarp-srctex.sty . . . . . 1104
448 lwarp-stabular.sty . . . . . 1104
449 lwarp-stackengine.sty . . . . . 1105

450 lwarp-stackrel.sty . . . . . 1106
451 lwarp-statex2.sty . . . . . 1107
452 lwarp-statistics.sty . . . . . 1111
453 lwarp-statmath.sty . . . . . 1116
454 lwarp-steinmetz.sty . . . . . 1118
455 lwarp-stfloats.sty . . . . . 1119
456 lwarp-struktex.sty . . . . . 1119
457 lwarp-subcaption.sty . . . . . 1120
458 lwarp-subfig.sty . . . . . 1120
459 lwarp-subfigure.sty . . . . . 1125
460 lwarp-subsupscripts.sty . . . . . 1125
461 lwarp-supertabular.sty . . . . . 1126
462 lwarp-svg.sty . . . . . 1128
463 lwarp-swfigure.sty . . . . . 1129
464 lwarp-syntonly.sty . . . . . 1129
465 lwarp-tabfigures.sty . . . . . 1129
466 lwarp-tablefootnote.sty . . . . . 1130
467 lwarp-tabls.sty . . . . . 1130
468 lwarp-tabularx.sty . . . . . 1130
469 lwarp-tabulary.sty . . . . . 1131
470 lwarp-tagpdf.sty . . . . . 1131
471 lwarp-tascmac.sty . . . . . 1133
472 lwarp-tcolorbox.sty . . . . . 1135
473 lwarp-tensor.sty . . . . . 1141
474 lwarp-termcal.sty . . . . . 1142
475 lwarp-textarea.sty . . . . . 1143
476 lwarp-textcomp.sty . . . . . 1143

477 lwarp-textfit.sty . . . . . 1147
478 lwarp-textpos.sty . . . . . 1147
479 lwarp-theorem.sty . . . . . 1148
480 lwarp-thinsp.sty . . . . . 1151
481 lwarp-thm-listof.sty . . . . . 1152
482 lwarp-thm-restate.sty . . . . . 1153
483 lwarp-thmbox.sty . . . . . 1153
484 lwarp-thmtools.sty . . . . . 1154
485 lwarp-threadcol.sty . . . . . 1154
486 lwarp-threeparttable.sty . . . . . 1154
487 lwarp-threeparttablex.sty . . . . . 1155
488 lwarp-thumb.sty . . . . . 1156
489 lwarp-thumbs.sty . . . . . 1157
490 lwarp-tikz.sty . . . . . 1157
491 lwarp-tikz-imagelabels.sty . . . . . 1158
492 lwarp-titleps.sty . . . . . 1159
493 lwarp-titleref.sty . . . . . 1162
494 lwarp-titlesec.sty . . . . . 1162
495 lwarp-titletoc.sty . . . . . 1164
496 lwarp-titling.sty . . . . . 1166
497 lwarp-tocbasic.sty . . . . . 1170
498 lwarp-tocbibind.sty . . . . . 1170
499 lwarp-tocdata.sty . . . . . 1172
500 lwarp-tocenter.sty . . . . . 1174
501 lwarp-tocloft.sty . . . . . 1174
502 lwarp-tocstyle.sty . . . . . 1180
503 lwarp-todo.sty . . . . . 1180

504 lwarp-todonotes.sty . . . . . 1181
505 lwarp-topcapt.sty . . . . . 1183
506 lwarp-tram.sty . . . . . 1183
507 lwarp-transparent.sty . . . . . 1183
508 lwarp-trimclip.sty . . . . . 1184
509 lwarp-trivfloat.sty . . . . . 1185
510 lwarp-truncate.sty . . . . . 1185
511 lwarp-turnthepage.sty . . . . . 1186
512 lwarp-twoup.sty . . . . . 1186
513 lwarp-txfonts.sty . . . . . 1186
514 lwarp-txgreeks.sty . . . . . 1187
515 lwarp-typearea.sty . . . . . 1187
516 lwarp-typicons.sty . . . . . 1188
517 lwarp-ulem.sty . . . . . 1188
518 lwarp-umoline.sty . . . . . 1190
519 lwarp-underscore.sty . . . . . 1191
520 lwarp-unicode-math.sty . . . . . 1191
521 lwarp-units.sty . . . . . 1195
522 lwarp-unitsdef.sty . . . . . 1196
523 lwarp-upgreek.sty . . . . . 1197
524 lwarp-upref.sty . . . . . 1197
525 lwarp-url.sty . . . . . 1198
526 lwarp-ushort.sty . . . . . 1198
527 lwarp-uspace.sty . . . . . 1198
528 lwarp-varioref.sty . . . . . 1199
529 lwarp-verse.sty . . . . . 1199
530 lwarp-versonotes.sty . . . . . 1201

**531 lwarp-vertbars.sty . . . . . 1201**
**532 lwarp-vmargin.sty . . . . . 1201**
**533 lwarp-vowel.sty . . . . . 1202**
**534 lwarp-vpe.sty . . . . . 1202**
**535 lwarp-vwcol.sty . . . . . 1203**
**536 lwarp-wallpaper.sty . . . . . 1205**
**537 lwarp-watermark.sty . . . . . 1205**
**538 lwarp-widetable.sty . . . . . 1206**
**539 lwarp-widows-and-orphans.sty . . . . . 1206**
**540 lwarp-witharrows.sty . . . . . 1206**
**541 lwarp-wrapfig.sty . . . . . 1208**
**542 lwarp-xbmks.sty . . . . . 1209**
**543 lwarp-xcolor.sty . . . . . 1209**
**650 xcolor . . . . . 1209**
650.1 Limitations . . . . . 1210
650.2 xcolor definitions: location and timing . . . . . 1210
650.3 Package loading . . . . . 1212
650.4 Remembering and restoring original definitions . . . . . 1212
650.5 \normalcolor . . . . . 1212
650.6 HTML color style . . . . . 1212
650.7 HTML border . . . . . 1214
650.8 High-level macros . . . . . 1214
650.9 Row colors . . . . . 1218
**544 lwarp-xechangebar.sty . . . . . 1220**
**545 lwarp-xellipsis.sty . . . . . 1220**
**546 lwarp-xetexko-vertical.sty . . . . . 1221**
**547 lwarp-xevlna.sty . . . . . 1221**
**548 lwarp-xfakebold.sty . . . . . 1221**

549 lwarp-xfrac.sty . . . . . 1222
550 lwarp-xltabular.sty . . . . . 1224
551 lwarp-xltxtra.sty . . . . . 1225
552 lwarp-xmpincl.sty . . . . . 1225
553 lwarp-xpiano.sty . . . . . 1225
554 lwarp-xpinyin.sty . . . . . 1226
555 lwarp-xr.sty . . . . . 1227
556 lwarp-xr-hyper.sty . . . . . 1228
557 lwarp-xtab.sty . . . . . 1228
558 lwarp-xunicode.sty . . . . . 1230
559 lwarp-xurl.sty . . . . . 1231
560 lwarp-xy.sty . . . . . 1231
561 lwarp-zhlineskip.sty . . . . . 1232
562 lwarp-zwpagelayout.sty . . . . . 1233
563 lwarp-patch-komascript.sty . . . . . 1234
564 lwarp-patch-memoir.sty . . . . . 1236
671 patch-memoir . . . . . 1236
671.1 Packages . . . . . 1237
671.2 Label handling . . . . . 1238
671.3 Page layout . . . . . 1239
671.4 Text and fonts . . . . . 1242
671.5 Titles . . . . . 1242
671.6 Abstracts . . . . . 1243
671.7 Docment divisions . . . . . 1243
671.8 Pagination and headers . . . . . 1246
671.9 Paragraphs and lists . . . . . 1247
671.10 Contents lists . . . . . 1247
671.11 Floats and captions . . . . . 1251

671.12 Footnotes and page notes . . . 1255
671.13 Decorative text . . . 1257
671.14 Poetry . . . 1257
671.15 Boxes, verbatims and files . . . 1258
671.16 Cross referencing . . . 1258
671.17 Back matter . . . 1259
671.18 Miscellaneous . . . 1261
671.19 ccaption emulation . . . 1261
671.20 Final patchwork . . . 1264

**565 lwarp-common-multimedia.sty . . . 1264**

**566 lwarp-common-mathjax-letters.sty . . . 1269**

**567 lwarp-common-mathjax-newpxtxmath.sty . . . 1276**

**568 lwarp-common-mathjax-nonunicode.sty . . . 1282**

**569 lwarp-common-mathjax-overlaysymbols.sty . . . 1285**

**Change History . . . 1286**

**677 Chg Hist . . . 1286**

**Index of Objects . . . 1324**

**General Index . . . 1348**

**Troubleshooting Index . . . 1353**

**Index of Indexes . . . 1360**

# List of Figures

1 tutorial.tex listing . . . . . 84

# List of Tables

1 Typesetting conventions . . . . . 65
2 LaTeX lwarp package — Supported features . . . . . 66
3 Required software programs . . . . . 77
4 Configuration files created by print version . . . . . 86
5 Localization settings . . . . . 99
6 Accessibiltiy settings . . . . . 100
7 Lwarp package options . . . . . 105
8 HTML settings . . . . . 110
9 Literal character macros . . . . . 176
10 Section HTML headings for word-processor conversion . . . . . 184
11 Section depths and HTML headings . . . . . 200
12 Tabular baseline . . . . . 455
13 Tabular HTML column conversions . . . . . 455
14 Cross-referencing data structures . . . . . 497
15 Float data structures . . . . . 509
16 CSS related to the sidetoc . . . . . 521
17 amsthm package — CSS styling of theorems and proofs . . . . . 649
18 Ntheorem package — CSS styling of theorems and proofs . . . . . 993
19 Theorem package — CSS styling of theorems and proofs . . . . . 1148

# 1 Updates

The following is a summary of updates to lwarp, highlighting new features and any special changes which must be made due to improvements or modifications in lwarp itself.

For a detailed list of the most recent changes, see the end of the Change History on page 1323.

**v0.895:** Vector packages, greatly improved MathJax for siunitx.

core
- Fixed quotes in HTML tags while using old font packages with XeLaTeX and LuaLaTeX.

MathJax
- Added `\ifblank` and `\ifstrequal` to MathJax emulation.

packages
- multirow: Allow `\par` per v2.7.
- acro: Updated to v3.5.
- fancyhdr: Updated to v4.0.
- changes: Updated to v4.0.1.
- epsfig, rotating: Now work inside `lateximage`.
- amscdx: Verified to work with SVG math. Warning added about use with MathJax.
- Added MathJax emulation for isomath, mattens, maybemath, skmath, tensor.
- Improved MathJax emulation for siunitx `\ang`, `\num`, `\SI`.
- Added epsf, impnattypo, isotope, lpic, luavlna, mdwmath, pinlabel, rlepsf, tikz-imagelabels, xevlna.
- Verified to work as-is: tensind.

**v0.894:** MathJax additions and improvements.

MathJax
- Improved warning message for enabling SVG graphics for select math expressions while using MathJax.
- Accept and ignore a star for `\hspace`.
- Ignores `\arabic`, `\number`, `\noalign`.

packages
- Added MathJax emulation for backnaur, colortbl, nicematrix.
- booktabs: MathJax emulation now absorbs and discards trim.
- menukeys: Updated to v1.6.1.

**v0.893:** Minor fixes, more packages.

MathJax
- Added MathJax emulation for `\mathnormal`.

packages
- Fixed pstricks `pspicture*`.
- Fixed tikz font macros.
- braket: Now uses the MathJax extension.
- Added esvect, fixmath, keystroke, mathastext, menukeys, picinpar, plimsoll, repltext, selectp, seqsplit, simplebnf, statistics, swfigure.
- Added MathJax emulation for mathspec.
- Verified to work as-is for apxproof, syntaxdi, venndiagram.

**v0.892:** minted, fvextra, MathJax `\left/\right`.

MathJax
- fourier, libertinust1math, newpxmath, newtxmath, newtxsf, unicode-math: Added MathJax `\left/\right` support for additional delimiters.

packages
- textpos: Updated to v1.10.
- xcolor: Fixed optional args for `\fcolorbox` and related.
- Added fvextra, minted.

**v0.891:** MathJax additions and improvements.

core
- Now displays inline `\verb` text as `\texttt`.
- Fixed alltt and verbatims with LaTeX lists.
- Now generates an error if nested each of `warpHTML`, `warpprint`, `warpMathJax` inside itself.

MathJax
- Added MathJax *textmacros* extension, allowing formatting inside `\text`.

packages
- biblatex, hyperref: Added back page references.
- fancyvrb: Fixed `BVerbatim` with a label.
- listings: Fixed MathJax with captions, improved HTML sanitation.
- babel-french: Fixed `\texorpdfstring` conflict.
- Now honors Greek package options for mathdesign, mathpazo, mathptmx, newpxmath, newtxmath.
- Improved MathJax for colonequals, mathdesign, mathdots, mathfixs, mathtools, multiobjective, nicefrac, shuffle, units.
- unicode-math: Added Greek macros, as well as macros for the first several categories listed in **`texdoc unimath-symbols`**. Improved symbol shape macros with Greek. Improved documentation.
- Added bussproofs, cmbright, fourier, kpfonts, kpfonts-otf, libertinust1math, scalerel, txgreeks.

**v0.89:** Additional MathJax support.

core
- Adapted to upcoming LaTeX kernel changes.
- Allows load of amsmath before lwarp.

*lwarpmk*
- Also removes `*.bbl` when cleaning aux files.

MathJax
- MathJax: Neutralized `\protect`, `\mathcode` and related, ligatures. Fixed nested environments.

packages
- caption: Updated for v3.5, fix for label sep.
- thmtools: Updated for v0.72. Fixed `swapnumber`, `margin`.
- Improved MathJax for centernot, mathtools, mismath, SIunits, siunitx, statmath.
- Added MathJax emulation for accents, hepunits, hhtensor, mathalpha, mathdesign, mathpazo, mathptmx, mleftright, newpxmath, newtxmath, newtxsf, pxfonts, shuffle, txfonts, upgreek, ushort.
- Verified to work as-is: authoraftertitle.

**v0.88:** Indexing, boxing, theorems.

- Now has programmed support for more than 500 packages and classes, of which more than 60 also support MathJax.

core
- Fixed: `\ref*`, and also added MathJax emulation.
- If starting a new paragraph, `\hrulefill` creates a `<div>` with a thin horizontal line across the page. Use instead of `\hrule`.
- Fixed: Use `\chaptername` where appropriate.
- Fixed: Inline links causing extraneous paragraphs.

*lwarpmk*
- Added **`lwarpmk -v`** to print the version number.

indexing
- Added the `IndexRef` option to control the display of index entries. See section 7.5.
- Added `\IndexPageSeparator` and `\IndexRangeSeparator` for custom index styles.
- Added support for gindex, *xindex*.
- Verified to work as-is with varindex.

packages
- cleveref, varioref: Fix for starred macros.
- varioref: Removed page-related text from HTML output.
- xfakebold: Updated to v0.08, using pdfrender.
- caption, scrextend: Fixed `\caption*`.
- Added fbox, shadethm, tcolorbox, termcal, thmbox, thmtools.

**v0.87:** MathJax, bibliography packages.

core
- Added boolean `FixSmallCaps` for fonts which render small caps as all caps.
- Fixed `\bibliography` to use the HTML version's `.bbl` file. Previously the HTML bibliography relied on the print version's `.bbl`, thus would fail if the print document had not yet been created.

MathJax
- Added `\ifstar` and `\ifnextchar` to MathJax, and removed `\DeclareIfstar`. See section 8.7.5.

⚠ Removed `\DeclareIfstar`

packages
- physics: Now supports the MathJax v3 extension.
- mathtools: Improved `\underbrakcet`, `\overbracket` for MathJax.
- nccmath: Improved `\underrel` for MathJax.
- mhchem: Now supports the MathJax v3 extension for `\ce` inside math.
- cancel: Now supports the MathJax v3 extension.
- embrac: Neutralized kerning for improved HTML conversion.
- Added citeref, drftcite, jurabib, multibib, splitbib.
- Verified to work as-is with bibtopic, collref, mciteplus.

**v0.86:** MathJax major updates.

core
- Fixed: Filename if named files with *, parens, period in section name.
- Fixed: Labels in `eqnarray`, `lateximage`.

MathJax
- Updated to MathJax v3. New repository.
- Fixed forward references for MathJax.
- Improved MathJax equation number formatting, now compatible with amsmath `\numberwithin` for chapters, sections, subsections, as well as amsmath `subequations`. See section 8.7.5.
- Added `\DeclareIfstar` to define starred TeX macros in MathJax. See section 8.7.5.
- Generates an error if `\MathJaxFilename` file does not exist.

packages
- mathtools, nccmath, physics: Added starred macros for MathJax.
- nccmath: Fixed `\nr`, `\displaybreak` for MathJax.
- xcolor: Fixed `\textcolor` with babel-french.

**v0.85:** fontspec

packages
- fontspec: Fixed core font change macros for world languages.

⚠ acro formats
- acro: Due to v3 changes, when defining acronym formats, use `\textbf` instead of `\bfseries`, etc.
- Fixed idxlayout, mathtools, titlesec, url.

**v0.84:** Previous/next page links, numerous fixes.

docs
- Added documentation of `BlockClass` and `\InlineClass` for css `<div>`s and `<span>`s. See section 7.8.

- Added `\LinkPrevious`, `\LinkNext` page links. See section 7.6.

⚠ home page footer changed
- Added `\FirstPageBottom`. Home page no longer shares `\PageBottom`. See section 7.6.

core
- Improved coexistence with comment, support for nested environments.
- No longer requires but still supports the caption package.
- Improved filenames and HTML titles when using special characters.

⚠
- Change: Append `-0` to section named Index previously _index to distinguish from `index.html`

- Fixed style tags for `\multicolumn`, `\multirow`.
- Fixed spacing in `tabbing`.
- Fixed `lateximage` for: `quote`, `quotation`, `verse`, `center`, `flushleft`, `flushright`, `<par>` tags, packages verbatim, alltt, epigraph.
- Fixed textcomp due to integration into LaTeX kernel.
- Fixed `\itshape`, etc. Adapted to LaTeX fontaxes integration.
- Fixed `\@fnsymbol`.
- Warns about section names with dollar-delimited math.
- Warns about a `<span>` containing a float, caption, section, mdframed, or other `<div>` object.

- Only warn about XeTeX logo and graphics if actually used `\Xe`.

*lwarpmk*
- **`lwarpmk clean`** also removes `comment_*.cut`.

packages
- scrextend, scrartcl, scrbook: Added `\titlehead`, `\subject`, `\subtitle`, `\publishers`.
- titling: Fixed `\printthanks`.
- memoir, abstract: Fixed for updated memoir.
- memoir: Fixed `\newcomment`, pagenotes, crossreferences. Fixed setting a recursive name.
- Fixed or improved: amsthm, backref, biblatex, fixme, nfssext-cfr, ntheorem, parcolumns, realscripts, rotfloat, titling.
- Added boxedminipage, renamed from boxedminipage2e per author.
- Verified to work as-is with mcite.

**v0.83:** memoir fixes.

packages
- memoir: Various fixes and updates.
- physunits: Updated to v1.0.4.

**v0.82:** MathJax notes, xpinyin improvements, various updates.

MathJax
- Improved footnotes with MathJax.
- Added MathJax emulation for endnotes, marginnote, nccfoots, pagenote, parnotes, sidenotes.

packages
- xpinyin: Added pinyin with modern HTML.
- luatexko: Added `\dotemph`, `\ruby`, `\uline`, etc.
- soul: Fixed `\<`.
- chemfig: Updated to v1.5.
- draftwatermark: Updated to v2.0.
- ulem: Fixed: `\dashuline`.
- amsmath: Fixed: `\intertext` with MathJax.
- endnotes: Fixed: Marks in print mode.
- tocvsec2, tableof: Verified to work as-is.
- Added etoc (nullified).

**v0.81:** MathJax speedup and additional emulations.

core
- Improved warning regarding SVG math sizing/baselines and graphics/graphicx. See section 8.7.

MathJax
- Improved MathJax emulation processing speed.
- Added MathJax emulation for accsupp, axessibiltiy, colonequals, decimal, dotlessi, econometrics, engtlc, multiobjective, physunits, SIunits, stackrel, statmath.

packages
- axessibility: Updated to 2020/01/08 version.
- gridset: Updated to v0.3.
- SIunits: Fixed for math mode.
- Added DotArrow, nolbreaks, luamplib, returntogrid, statex2, tagpdf.
- Verified to work as-is with icomma, mathpunctspace, textualicomma.

**v0.80:** MathJax, biblatex.

MathJax
- Added docs and warning/info messages re: avoiding slow MathJax compilation. See section 8.7.5, Customizing MathJax.
- Added MathJax emulation for accessibility, autobreak, centernot, extarrows, fouridx, gensymb, leftidx, mathcomp, mathdots, mathfixs, mismath, nccmath, noitcrul, pdfcomment, relsize, rmathbr, subsupscripts, xfrac.
- Improved MathJax emulation for unicode-math.

packages
- biblatex, url: Now create hyperlinks.
- amsmath: Fix to center starred environments.
- xcolor, graphics: Made more macros robust.
- colortbl: Fix: Rule color in a `lateximage`.
- chemmacros: Updated to v5.10.
- Added fewerfloatpages, ghsystem, hhline, mismath, nccmath.

**v0.79:** MathJax, nested `tabular`.

MathJax
- Added or improved MathJax emulation for amsmath, ar, arydshln, bm, bigdelim, bigstrut, booktabs, braket, mathtools, multirow, physics, siunitx, slashed, unicode-math, xfakebold.
- Warn if using certain packages not supported by MathJax.

core
- `tabular`: Now may be nested.
- `minipage`, `\parbox`, `fminipage`, `\makebox`, `\framebox`: Fix: Adjust for virtual page size.
- Uses new iftex.

packages
- graphicx: Fix: Negative angles.
- caption: Fix: `\captionlistentry` with longtable.
- multirow: Fix: Centered vertical alignment.
- siunitx: Fix: `\square`, `\cubed`.
- booktabs: Fix: memoir with `lateximage`.
- babel and polyglossia: Added troubleshooting warnings.
- fontawesome, fontawesome5: Supports text color and size.
- transparent: Fix: `lateximages`.
- epigraph: Updated to v1.5e.
- xurl: Updated to v0.08.
- subcaption: Fixed with memoir.
- floatrow: Fix: `\linewidth`. No longer require float, graphics.
- floatflt, wrapfig, niceframe: Fix: Adjust for virtual page size.
- Added widetable, witharrows, steinmetz.
- Added awesomebox, catoptions.
- Added svg, supports svg-extract.
- Added parcolumns, pdfcolparcolumns,
- Added parallel, pdfcolparallel.
- Added pdfcol, pdfcolfoot, pdfcolmk.

**v0.78:** Fixes for support files, `alt` tags, hyperlinks, and the 2019/10 LaTeX release.

docs
- Docs: Improved documentation regarding package options. See section 8.1.
- Fix to overwrite existing support files using new `filecontents` environment.

packages
- breqn: Previously broken by the 2019/10 LaTeX update, but now working again.
- graphics: Fix for `\includegraphics` `alt` tags.
- babel-french: Fix for hyperlinks.
- media9, movie15, multimedia: Fix for the 2019/10 LaTeX update.
- accessibility: Added.

**v0.77:** Updates to fix recently-broken packages.

- booktabs: Updated to v1.6180339.
- chemformula: Updated to v4.15.

**v0.76:** MathJax, updates for LaTeX 2019/10 release.

docs
- Docs: Expanded documentation regarding the use of multiple projects in the same directory. See section 5.17.

MathJax
- MathJax: Updated to v2.7.6.

packages
- xr: Updated to v5.05.
- xr-hyper: Updated to v6.1.
- Verified works as-is with xcite.
- acro: Updated to v2.10.

⚠ broken
- Currently broken in print mode by the 2019/10 LaTeX update, and waiting for fixes: breqn, grffile, multimedia, movie15.

**v0.75:** keyfloat, wrapfig

- `\minipage`: Fix for `\linewidth`.

packages
- keyfloat: Improved color control.
- wrapfig: Fix for `\linewidth`.

**v0.74:** Docs, SVG math, *lwarpmk*, HTML `alt` and `title` text, lyluatex

docs
- Added to the tutorial the section What next?. See section 5.19.
- Added documentation about localization options. See section 7.1.
- Added documentation about accessibility options. See section 7.2.

HTML `alt` text
⚠ changed names
- Renamed and updated HTML `alt` text macros:

| Old | New |
|---|---|
| (hard coded as “image”) | `\ImageAltText` |
| `\mathimagename` | `\MathImageAltText` |
| `\packagediagramname` | `\PackageDiagramAltText` |

- Added `\ImageAltText` for the default HTML `alt` text for an image. See section 7.6.

- Added `\ThisAltText`, which may be used to assign a one-time HTML `alt` tag to the very next image generated by lwarp, such as a `lateximage`, `picture`, `tikzpicture`, an image generated by various chemistry or engineering packages, or an SVG math image. This macro also adds a `title` tag to a reference or hyperlink. See section 7.6.

svg math
- Adjusted `\LateximageFontScale` default from .75 to 1.
- Fix: Font control for SVG math.

misc
- Fix: Ignores negative `\hspace`.
- Warning if `SideTOCDepth` < `FileDepth`.

*lwarpmk*
- *lwarpmk*: **`lwarpmk clean`** removes additional files.
- *lwarpmk*: **`lwarpmk epstopdf`** and **`lwarpmk pdftosvg`** now honor directories.

packages
- lyluatex: Split images by `system` or per `fullpage`, improved margins and scaling.
- Tested to work as-is with mathspec, unicode-math.

**v0.73:** `\include`, memoir, koma-script, caption, xy, datatool, music scores.

- Fix for `\include`.
- Warning for a `tabular` inside a .
- `\color`: Added HTML support for rules and frames, but not inline text. Use `\textcolor` if possible.
- Improved many HTML tags, reducing *tidy* warnings. See Change History.

packages
- memoir: Fixes for `\frontmatter*` and `\mainmatter*`. Added `\book`.
- koma-script: Fix for starred captions in the TOC.
- caption: Fix for starred captions.
- datatool: Added pie, bar, and plot charts.
- threeparttable: Added `measuredfigure`.
- intopdf: Updated to v0.2.1.
- tocdata: Updated to v2.03.
- quotchap: Updated to v1.2.
- versonotes: Updated to v0.4.
- backnaur: Now uses SVG images. Updated to v3.1.
- xy: Fix for `\xybox`, improved `xy`, also now compatible with qcircuit.
- fancyvrb: Fix for label HTML tags.
- Added stackengine.

music
- Added lyluatex. (Music scores.)
- musicography: Updated to 2019/05/28. Added support for `lateximages`.

**v0.72:** Font control, `\multicolumn`, xr and xr-hyper.

⚠ images

- Due to internal changes, images for inline SVG math and `lateximages` will have new hash values, and will have to be regenerated using

  Enter ⇒ **`lwarpmk cleanlimages`**

  and

  Enter ⇒ **`lwarpmk limages`**

- Docs: Color-codes package names in the table of supported packages and features, table 2, according to each package's level of support by lwarp.
- `\multicolumn`: Fix for paragraph columns.

packages

- xr, xr-hyper: Fixes for references, `\externaldocument`.
- soulutf8: Fix: Loads soul for emulation.
- boxedminipage2e: Added support for `lateximages`.
- zhlineskip: Updated to v1.0e.
- Added fontaxes, slantsc, tabfigures.
- Added nfssext-cfr, thus supporting cfr-lm and several other font packages.
- Added backnaur, hypbmsec, minibox, pdfcrypt, shapepar.

**v0.71:** Error handling, multimedia, `tabular`.

- `tabular`: Added support for '`*`' columns. Fix for paragraph tags.
- `quotation`: Fix for HTML tag.
- Docs: Added a section about error conditions tested by lwarp. See section 13.1.
- *lwarpmk*: If file `lwarpmk.conf` is an older version, or the incorrect operating system, displays the print command to use to recompile.

packages

- chemfig: Updated for v1.4.
- endfloat: Updated for v2.7.
- textpos: Updated for v1.9.1.

multimedia

- Added media9, movie15, multimedia.

**v0.70:** Error handling, MathJax, mathtools.

- Error handling for "Label(s) changed." Refuses to **`lwarpmk limages`** until recompile first.
- Fix: If Computer Modern font is used, ensures cm-super or lmodern is used.
- Fixes for `\makebox`.
- Fixes for `\parbox` inside a `<span>`.
- MathJax: Updated to v2.7.5. Loads the `autoload-all.js` extension. Added `\MathJaxFilename` to select custom scripts.

packages

- textcomp, xunicode: Fix for `\textinterrobang`.
- mhchem: Works with MathJax. See section 397.
- changes: Updated to v3.1.2.
- Added autonum, changelayout, inputtrc, mathtools, metalogox.

**v0.69:** Error handling, many fixes, improved keyfloat/tocdata.

- Fix for HTML corruption of `lateximage` displays.
- `\makebox`, `\framebox`: Fix for (⟨*width,height*⟩) arguments.
- `fminipage`: Honors `\minipagefullwidth`.

packages

- array, longtable: Fix for `\tabularnewline`.
- tabularx, tabulary: Fix to require the array package.
- supertabular, xtab: Fix to clear caption after use.
- graphics: Added a warning if used the `\includegraphics scale` option.
- multirow: Added an error if didn't use `\mrowcell` or `\mcolrowcell` when using `\multirow` or `\multicolumnrow`.
- keyfloat: Updated for v2.00, additional improvements.
- Added ctable, eqlist, eqparbox, ftcap, listliketab, minitoc, tocdata, topcapt.

**v0.68:** Error handling, tabulars, footnotes.

*lwarpmk*

- *lwarpmk*: Improved error handling for image generation if compile was incomplete.
- `tabular`: Fix for `\warpprintonly`.

packages

- longtable: Improved flexibility for `\endhead`, etc. Improved error reporting if `\endhead`, etc. incorrect for lwarp.
- threeparttable: Fix for caption type.
- hyperref: Fix for options with braces.
- morefloats: Fix to be loaded early for print output.
- listings: Updated for v1.7.
- Added bigfoot, fnpara, footnotebackref, manyfoot, tablefootnote, threeparttablex.
- Added layouts, niceframe, perpage, showtags.
- Prevented alg, algorithmic, pdfcprot, fncylab.

**v0.67:** Filename generation, symbol fonts.

docs

- Documentation fix for `<project>-images`, `<project>-images.txt`.
- Added discussion regarding section names. See section 8.4.

filenames

- Added `\FilenameNullify` and `\FilenameSimplify` for filename generation. See section 8.4.
- Core, textcomp, xunicode: Nullified additional symbols during filename generation.

packages

- color: Fix for version number warnings.
- Added academicons, bbding, dingbat, eurosym, fontawesome, fontawesome5, marvosym, pifont, typicons.
- Added changes, easyReview, fitbox, foreign, gloss, karnaugh-map, multicap, nomencl, notes, struktex, umoline, xfakebold.
- Tested to work as-is with askmaps, curves, euro, karnaughmap, tikz-karnaugh.

**v0.66:** xr, multiple projects, image names/directory, HTML formatting

⚠ Reset the configuration

- Due to changes in *lwarpmk*, recompile any existing project a single time using **`pdflatex filename.tex`** or similar, after which *lwarpmk* may then be used with the new configuration files.

`lateximage`

- Adds options `ImagesDirectory` and `ImagesName` to assign directory and name prefixes for `lateximage` images. The new defaults include the jobname, allowing the image directories for multiple projects to coexist.

⚠ existing projects

- To reuse existing `lateximage` directories, add lwarp options

```
\usepackage[
  ImagesDirectory={lateximages},
  ImagesName={lateximage-}
]{lwarp}
```

  If not reused, the existing `lateximages` directory and `lateximages.txt` file may be removed.

filenames

- Added `\FilenameLimit` to control the maximum length of the filenames generated by lwarp.

⚠ Possible filename changes

- Improved filename generation when special characters or macros are used in section names.

WINDOWS

- Fix for **`lwarpmk cleanlimages`** with WINDOWS.

floats

- Fixes for floats in the home page.

lists, table notes

- Improved CSS for definition lists, table notes.

`tabular`

- `tabular`: Fixes for `\par` in column specifier, minipage inside `tabular`.

indexing

- Indexing: Fix for a long line of multiple entries.

`minipage`

- `\minipagefullwidth`: Fix for global changes.
- Added `\UseMinipageWidths` and `\IgnoreMinipageWidths`. See section 8.3.3.

colors

- Improved `\fbox`, `\fboxBlock`, `\fminipage` to use current text color.

HTML

- Improved HTML output formatting.

docs

- Added discussion regarding invalid HTML. See section 8.1.1.
- Added discussion regarding math in section names, `\imagegraphics scale` option. See section 6.
- Added discussion regarding international languages in section names. See section 8.14.

packages

- caption: Fix for options clash.
- xr, xr-hyper: Now compatible.
- subcaption: Improved horizontal spacing.
- multicol: Fix for minipage inside `multicols`.
- multicolrule: Updated for v1.2.
- tocbasic: Minor update.
- acronym: Fix for acronym in float caption.
- kotexutf: Patch with *pdflatex* and new lwarp labels.
- extramarks, fancyhdr: Updated for v3.10.
- memoir: Added docs regarding version numbers. See section 8.13.

- zref: No longer required.
- Added ar, ed, indentfirst, nameauth, truncate.
- Verified to work as-is with changelog.
- Prevented colortab, epsf, hyper, picinpar, picins, sistyle, ucs.

**v0.65:** CSS layout, `alt` tags, Japanese.

page layout
- Moved the sideTOC to the left side, allowing improved CSS for margin notes.
- Improved page layout CSS.

image `alt` tags
- graphicx `\includegraphics`: Added the `alt` key to assign an `alt` tag to an image. Default is "`image`", assigned to pass validation.

duplicate HTML files
- Detects and causes an error if duplicate HTML file names are generated, caused by identical or similar sectioning names.

fixes
- Fix for `tabular*`.
- Fix for tabular border colors.
- Fixes `\quad`, `\enskip`, and figure captions to pass validation.

Japanese
- Added ltj* classes, bounddvi, gentombow, lltjext, plarydshln, plext, plextarydshln, plextcolortbl, pxatbegshi, pxeveryshi, pxftnright, pxjahyper, tascmac.
- Verified to work with plarray, plautopatch, plextarray, plextdelarray, pxgentombow, plsiunitx, pxpdfpages, pxpgfrcs, pxpgfmark.

packages
- Added support for fontspec `\textsi` and `\sishape`.
- Added multicol's `\docolaction`.
- Added embrac, footnoterange, multicolrule, versonotes.

**v0.64:** Koma-Script, Japanese, Chinese.

Japanese
- Added utarticle and related classes.
- Improved ujarticle and related classes.

Chinese
- Fix for biblatex with CTEX and other classes.

Koma-Script
- Fixes for scrlayer, scrlayer-scrpage.

packages
- addlines: Updated to v0.3.
- Added bsheaders, gmeometric, marginal, rmpage, scrpage2.

**v0.63:** mdframed, Chinese, Japanese, Korean

localization
- Added `\linkhomename`: A user-definable name for the Home link.
- Documented `\sidetocname`: A user-definable name for the sideTOC.

fixes
- Fix: `\LinkHome` for print output.

optimizations
- Moved package load checks to the lwarp core to reduce the number of `lwarp-*` files.

packages
- mdframed: Fix with amsthm, improved titles and font control. Improved rule widths.

Chinese
- Fixes for xeCJK.
- Added xpinyin, zhlineskip.

- Verified to work with cjkpunct, upzhkinsoku, zhspacing.

Japanese
- Verified to work with zxjatype, luatexja, luatexja-fontspec.
- Added bxjsarticle and related classes.
- Added ltjsarticle and related classes.
- Added pLaTeX, upLaTeX, ujarticle and related classes.
- Prevented utarticle and related classes.
- Prevented bxcjkatype.

Korean
- Verified to work with kotex, xetexko, luatexko.

**v0.62:** MiKTeX docs, HTML title, CTeX, xeCJK, bitpattern.

docs
- Docs: Setting a UTF-8 locale. See section 9.8.

MiKTeX
- MiKTeX: Docs for *MiKTeX Console* and miktex-poppler-bin.

HTML <title>
- HTML subpage titles: Added `\HTMLTitleBeforeSection` and `\HTMLTitleAfterSection` to select whether the HTML `<title>` displays the website name before or after the section name. See section 7.6.

fixes
- Fix for package options handling.
- Fixes for horizontal white space between `fminipage`, `fcolorminipage`, `colorboxBlock`, `fcolorboxBlock`.
- Logos: Fix for XeTeX logo, improved CSS, made robust, improved search-engine optimization.
- `\\[$1]`: Additional HTML `<br>` if $1 > 0 pt.
- Fixes for `\includgraphics` filename, and with `FormatWP`.
- Fix: CSS for `\textup`.
- Fix: Added `\slshape`.

Chinese
- Added ctex package and related classes, xeCJK.
- Prevented CJK, CJKutf8 unless xeCJK, ctex are used.

packages
- chemfig: Docs for new macro `\polymerdelim`.
- asymptote: Docs for compilation.
- chngpage: Fix to load lwarp-changepage.
- algorithm2e: Fix with non-book classes.
- register: Updated to v1.8.
- nicefrac: Improved font control and CSS, honors `nice` and `ugly`.
- units: Improved font control and CSS, honors `tight` and `loose`.
- xfrac: Improved CSS.
- textcomp and xunicode: Fix conflicts with `\textcircled`.
- ulem: Improved compatibility with CJKulem, `lateximage`.
- MathJax and siunitx: Removed inoperable extension.
- Added bitpattern, pdfcomment, pdfmarginpar, tram, unitsdef, xechangebar.
- Added musicography, octave, semantic-markup.
- Added 2in1, flippdf, notespages, rviewport, twoup.

**v0.61:** Custom compilation, EPS-related packages, documentation, indexes.

docs
- Split index into multiple indexes.
- Improved documentation regarding font selection. See section 7.4.
- Added documentation regarding debugging options. See section 35.
- Added documentation regarding HTML entities inside program listings. See section 8.2.1.

custom compiling
- Added options to specify the shell commands to execute for **`lwarpmk print`** and **`lwarpmk html`**, allowing the use of lwarp with perltex, pythontex, etc. If not specified, these are set automatically depending on the LaTeX engine, `--shell-escape`, and lwarp options. See section 9.

⚠ changed names
- Changed macro names to match `\displaymathother`, `\displaymathnormal`:

| Old | New |
|---|---|
| `\StartDynamicMath` | `\inlinemathother` |
| `\StopDynamicMath` | `\inlinemathnormal` |

fixes
- Fix: Paragraph tags in a `tabular`.
- Fix: supertabular and xtab captions.
- Fix: DVI LaTeX `\includegraphics` EPS images.
- Fix: newfloat lists.
- Fix: CSS footnotes text align, minipage tabular and footnote margins.

packages
- Added epsfig, psfrag, psfragx, pstool.
- Added copyrightbox, pdfprivacy, thinsp, threadcol, uspace.
- Added chkfloat, cmdtrack, dprogress, lua-visual-debug, refcheck, srcltx, srctex, vpe, xbmks.

**v0.60:** Fixes for longtable, listings.

fixes
- longtable, etc.: Fixes for slowdown and memory management for very long tables.
- listings: Fix for HTML entities, and also when used inside a list.
- diagbox: Fix for incorrect HTML par tags.

packages
- Added 2up, booklet.
- Added bophook, draftfigure, fullminipage, grid-system, layaureo.
- Added leading, widows-and-orphans.
- Added fancytabs, thumb, thumbs.

**v0.59:** DVI *latex*, MathJax, asymptote, pdftricks and pstricks, epstopdf, brqen.

⚠ Reset the configuration
- Due to changes in *lwarpmk*, recompile any existing project a single time using **`pdflatex filename.tex`** or similar, after which *lwarpmk* may then be used with the new configuration files.

*lwarpmk*
- Added an error if `lwarpmk.conf`'s format has changed and the document must be recompiled.
- Added a warning if the `lwarpmk.conf` configuration file appears to be for the wrong operating system, in case files are transferred between systems.

- Added
  ```
  lwarpmk epstopdf <list-of-EPS-files>
  ```
  to quickly convert a document's EPS images to PDF or SVG. See section 8.8.

DVI *latex*
- Added support for DVI *latex*. See section 7.5.

*latexmk*
- Fix for `--shell-escape` with *latexmk*.

math
- Updated MathJax script to v2.7.4.
- Fix: MathJax chapter number removed from non-numeric tagged equations.
- Added MathJax support for nicefrac, units.
- Fix for `\[` and `\]` with `\displaymathnormal`.

images
- Fix for `\includegraphics` filename expansion.
- `\includegraphics` now works with `.pdf` and `.eps` filename extensions.

packages
- Moved amsmath out of the lwarp core.
- Fix for chemformula `\NMR`.
- Added asymptote, pdftricks, pstricks, pst-eps.
- Added breqn, SIunits.
- Added bxpapersize, canoniclayout, draftcopy, fnbreak, nccfancyhdr.
- Added accsupp, axessibility.
- Added xunicode.
- Improved and now supports epstopdf.
- Tested to work as-is: eepic, sepfootnotes.

docs
- Added information about setting up a development version of lwarp.

**v0.58:** Extensive improvements in indexing, glossaries. Adds PDF-inclusion packages.

⚠ Reset the configuration
- Due to changes in *lwarpmk*, recompile any existing project a single time using **`pdflatex filename.tex`** or similar, after which *lwarpmk* may then be used with the new configuration files.

*lwarpmk*
- *lwarpmk*: Added the `-p` option to specify the project name.

glossaries
- *lwarpmk*: Now uses *makeglossaries* for glossary generation, allowing the processing of multiple glossaries at once.
- Added lwarp option `GlossaryCmd` to specify the shell command used by **`lwarpmk printglossary`** and **`lwarpmk htmlglossary`**. Defaults to **`makeglossaries`**.

index and glossary
- Docs: Extra indexing options. See section 8.6.14.
- Added support for *makeindex*. (Previously supported only *xindy*.) Also added indexing packages listed below.
- Added lwarp options `PrintIndexCmd`, `HTMLIndexCmd`, and `LatexmkIndexCmd` to specify shell commands used by **`lwarpmk printindex`**, **`lwarpmk htmlindex`**, and *latexmk*. May be preset with the `makeindex` or `xindy` lwarp options. See section 7.5.
- Added lwarp options `makeindex` and `xindy` to set `PrintIndexCmd`, `HTMLIndexCmd`, and `LatexmkIndexCmd` to sensible values for a typical single index. See section 7.5.

- Added lwarp option `makeindexStyle` to tell *lwarpmk* to use a custom style instead of `lwarp.ist`. See section 8.6.20.
- Fix for index entries with `\see`, `\seealso`, `\emph`, `\textbf`, etc.

misc. fixes
- Replaced each `\csuse` with `\@nameuse` for improved error detection.
- Additional internal print/HTML macro selection improvements.
- Fix: `\printindex` finishes pending `\index` writes first.

packages
- Fixes for memoir: makeidx, ccaption, multiple indexes, `\specialindex`.
- Fixes for komascript: Indexing improvements.
- Added imakeidx, index, repeatindex, splitidx.
- Added attachfile, attachfile2, intopdf, pdfpages, pdfx.
- Added cases.
- Tested to work as-is: notes2bib, hvindex.

**v0.57:** algorithm2e, float styles, tabular packages, internal improvements.

MathJax
- Added support for MathJax equations with `\footnote`, `\footnotemark`.

math macros
- Added `\StartDefiningMath` and `\StopDefiningMath` for use when defining macros in the preamble which contain $. See section 8.7.7.

dynamic math
- Added `\inlinemathother` and `\inlinemathnormal` to delimit math expressions which depend on a variable condition such as a counter. Such expressions will not be hashed for reuse, and will be converted to SVG math images even when MathJax is enabled. See section 8.7.8.

⚠ new name
- Renamed `\EndDefiningTabulars` to `\StopDefiningTabulars`.

`lateximage alt` tags
- Improved localization for `lateximage` HTML `alt` tags. For SVG math images, the `alt` tag under some conditions will be set to `\MathImageAltText`, which defaults to `math image`. For packages, the `alt` tag is set using the package name followed by `\PackageDiagramAltText`, which defaults to `diagram`. Ex:

  ```
  (-xy- diagram)
  ```

  See section 7.6.
- Fix: Improved print/HTML macro selection.

misc. fixes
- Fix: `\href` text catcodes.
- Fix: `\subref` text.
- Fixes: Colored `\rule` and `\boxframe`.

packages
- float, rotfloat: Adds support for float styles `ruled` and `boxed`.
- float: Fix: Do not create `\l@<type>` until `\listof` is used.
- marginnote: Fix: Long optional argument.
- ellipsis: Adds `\midwordellipsis`.
- breakurl: Fix for text catcodes.
- Added algorithm2e, register, ltablex, xltabular, xellipsis, trimclip, errata, vowel, xpiano.
- Prevents glossary.
- Tested to work as-is with gauss, phonrule, piano, SIunits, tikzcodeblocks.

**v0.56:** Shell escape, tabular packages.

*lwarpmk*
- Added
  ```
  lwarpmk pdftosvg <list-of-PDF-files>
  ```
  to quickly convert a document's PDF images to SVG, for use with HTML. See section 8.8.
- Added support for `--shell-escape`. See section 7.3.

`tabular`
- Added support for array `w` and `W` columns.
- Fix: `\multicolumn` parameter handling.
- Added support for double `\hlines`, `\midrules`, and vertical rules.
- Added support for arydshln dashed lines with HTML `tabular`, but reverts to plain rules for `lateximage` and SVG math `array`.

misc. fixes
- Fix: `\thinspace`.
- Fix: paralist compact environments.

packages
- Added parnotes, quoting, lua-check-hyphen, tocenter, underscore.
- Added bibunits.
- Tested to work as-is with babelbib, bodegraph, fast-diagram, nicematrix, structmech.

**v0.55:** Various fixes.

misc fixes
- Fix: Extraneous space in file links, which also prevented *Calibre* EPUB conversions.
- Fix: Float optional argument regression.
- Fix: `\ForceHTMLTOC` with `\phantomsection`.
- Fix: Overfull boxes in `lateximages`.
- Fix: QED symbols in `lateximage`.

packages
- koma-script: Fix: Figure with `\centering`, etc.
- Added clrdblpg.

**v0.54:** Float `\centering`, improved image checks.

⚠ Reset the configuration
- Due to changes in *lwarpmk*, recompile any existing project a single time using **`pdflatex filename.tex`** or similar, after which *lwarpmk* may then be used with the new configuration files.

*lwarpmk*
- `lwarpmk limages` checks for the presence of the HTML version of the document and valid image references before attempting to create the `lateximages`.
- *lwarpmk*: Improved error message if configuration file does not exist.

BibTeX
- Added documentation for avoiding error with BibTeX and `\etalchar`. See section 8.6.9.

polyglossia
- Added documentation regarding polyglossia. See section 8.15.4.

macros in section names
- Added documentation regarding the use of macros in section names. See section 8.1.

document encoding
⚠ New and revised encoding options
- Renamed and added package options:

| Old Package Option | New Package Option |
|---|---|
| `xdyFilename` | `xindyStyle` |
| `IndexLanguage` | `xindyLanguage` |
| – | `xindyCodepage` |
| – | `pdftotextEnc` |

Use these options along with inputenc or inputenx to process documents in an encoding other than UTF-8. See section 7.4.

floats with `\centering`, etc.

- Floats now honor `\centering`, `\raggedright`, `\raggedleft`, and their ragged2e equivalents, when placed directly after:

```
\begin{floattype}
\centering
```

misc. fixes

- tikz: `\pgfpicture`, fit, align, font.
- ragged2e: `\centering` etc.
- hyperref: `\hypertarget` was creating duplicate of `\label`.
- hyperref: Active chars inside `\hyperref`, `\hyperlink`.
- hyperref: `\ref` inside `\hyperlink` caused a nested HTML link.
- glossaries: Fix when not using babel or polyglossia.
- textcomp: `\textperthousand`.
- LaTeX core `verse` environment: line spacing.

⚠

- Removed `\citetitle`, adjusted `\attribution`.

packages

- memoir: Minor update for v3.7g.
- Added inputenx, bibunits, chngpage, forest, magaz, gridset.
- Prevents loading ae, aecc, t1enc, and wasysym.

**v0.53:** Improved image checks.

*lwarpmk*

- *lwarpmk*: Added a warning about corrupted images due to the need to recompile the document one more time.
- *lwarpmk*: Added the **`lwarpmk cleanlimages`** command.
- Added documentation for **`lwarpmk cleanlimages`** and **`lwarpmk pdftohtml`**.

**v0.52:** Improved footnotes, SVG math.

documentation

- Improved install instructions regarding `lwarp_baseline_marker.png`.
- Added documentation regarding footnotes in section headings, and footnotes with `\VerbatimFootnotes` from fancybox, fancyvrb. See section 8.5.4.
- Added documentation regarding font selection when using XeLaTeX or LuaLaTeX with fontspec and traditional font packages. See section 7.4.

SVG math

- Fix: Limit the number of background tasks when generating `lateximages`.
- Added user-adjustable SVG math font scaling. See section 83.3.
- Added warnings if `lwarp_baseline_marker.png` is not present, or if graphicx or graphics is not loaded.
- Improved `\ensuremath` hashing expansion.

- Fix: `equation*` with `split`.
- `tabbing` now works inside a `lateximage`. Use for math in `tabbing`.

MathJax
- Fix: MathJax script was not executing in some conditions.
- Added `\CustomizeMathJax` to add custom functions. See section 8.7.

footnotes
- Fix: Footnote numbering when using `HTMLDebugComments`.
- Fix: Footnote paragraph tags.
- Fix: `FootnoteDepth` defaults to `\subsubsection`.

misc. fixes
- Fix: `\kill` in a `lateximage`.
- Fix: `\FileDepth`, misc. others, when input encoding is not `utf8`.
- Fix: `\texorpdfstring` in a section name.

packages
- hyperref emulation: Fix for #, %, &, ~, _ characters in URLs.
- fancybox, fancyvrb: Initial support for `\VerbatimFootnotes`.
- nicefrac: Added with fix for `\ensuremath`.
- graphicx: Fix for option defaults. Added v1.1a/b options.
- endfloat: Updated for v2.6.
- url: Fixes for active characters.

**v0.51:** Improved SVG math, added numerous chemistry packages.

documentation
- Docs: Added Things to avoid.
- Docs: Added to Converting an existing document.
- Docs: Multiple authors and affiliations with custom classes. See section 8.6.1.
- Docs: tikz with matrices. See section 8.8.1.

SVG math
- Improved SVG math baseline.
- Improved SVG math font and color.
- Faster SVG math rendering.
- Improved support for display math containing complicated math objects, such as tikz-cd. See section 8.7.9.
- Fix: `\addcontentsline` inside SVG math.
- Fix: SVG math containing an embedded `lateximage`.

MathJax
- MathJax now handles `\ensuremath` in expressions.

misc. fixes
- Fix: Added `alignat` environment.
- Fix: afterpackage no longer required, which conflicted with scrlfile.
- Fix: titling `\thanks` mark.
- Fix: fancybox improvements.
- Fix: tikz `\tikz` macro. (Previously only the `tikzpicture` environment worked.)
- Fix: tikz with optional argument.

packages
- Added mhchem, chemfig, chemformula, chemmacros, chemnum, chemgreek, epstopdf-base, grid, ltxgrid.

# 2 Introduction

The lwarp project aims to allow a rich LaTeX document to be converted to a reasonable HTML5 interpretation, with only minor intervention on the user's part. No attempt has been made to force LaTeX to provide for every HTML-related possibility, and HTML cannot exactly render every possible LaTeX concept. Where compromise is necessary, it is desirable to allow the print output to remain typographically rich, and compromise only in the HTML conversion.

Several "modern" features of HTML5, CSS3, and SVG are employed to allow a fairly feature-rich document without relying on the use of JavaScript. Limited testing on older browsers shows that these new features degrade gracefully.

---

lwarp is a native LaTeX package, and operates by either patching or emulating various functions. Source-level compatibility is a major goal, but occasional user intervention is required in certain cases.

As a package running directly in LaTeX, lwarp has some advantages over other methods of HTML conversion. TeX itself is still used, allowing a wider range of TeX trickery to be understood. Lua expressions are still available with LuaTeX. Entire categories of LaTeX packages work as-is when used with lwarp: definitions, file handling, utilities, internal data structures and calculations, specialized math-mode typesetting for various fields of science and engineering, and anything generating plain-text output. Blocks of PDF output may be automatically converted to SVG images while using the same font and spacing as the original print document, directly supporting Ti*k*z and `picture`. Numerous packages are easily adapted for HTML versions, either by loading and patching the originals, or by creating nullified or emulated replacements, and all without resorting to external programming. As a result, several hundred packages have already been adapted (table 2), and an uncounted number more work as-is.

Packages have been selected according to several criteria: perceived importance, popularity lists, recent CTAN updates, CTAN topics, mention in other packages, support by other HTML conversion methods, and from sample documents taken from public archives. These include some "obsolete" packages as well.[1]

---

Assistance is also provided for modifying the HTML output to suit the creation of EPUB documents, and for modifying the HTML output to ease import into a word processor.

---

*pdflatex*, *xelatex*, or *lualatex* may be used, allowing lwarp to process the usual image formats. While generating HTML output, SVG files are used in place of PDF. Other formats such as PNG and JPG are used as-is.

[1] An amazing number of decades-old packages are still in use today.

SVG images may be used for math, and are also used for `picture`, Ti*k*z, and similar environments. The SVG format has better browser and e-book support than MathML (as of this writing), while still allowing for high-quality display and printing of images (again, subject to potentially bug-ridden[2] browser support).

Furthermore, SVG images allow math to be presented with the same precise formatting as in the print version. Math is accompanied by `<alt>` tags holding the LaTeX source for the expression, allowing it to be copy/pasted into other documents.[3] Custom LaTeX macros may be used as-is in math expressions, since the math is evaluated entirely inside LaTeX. An MD5 hash is used to combine multiple instances of the same inline math expression into a single image file, which then needs to be converted to SVG only a single time.

The MathJax JavaScript display engine may be selected for math display instead of using SVG images. Subject to browser support and Internet access, MathJax allows an HTML page to display math without relying on a large number of external image files.[4] lwarp maintains LaTeX control for cross-referencing and equation numbering, and attempts to force MathJax to tag equations accordingly.

---

A *texlua* program called *lwarpmk* is used to process either the print or HTML version of the document. A few external utility programs are used to finish the conversion from a LaTeX-generated PDF file which happens to have HTML5 tags, to a number of HTML5 plain-text files and accompanying images.

lwarp automatically generates the extra files necessary for the HTML conversion, such as CSS and `.xdy` files, and configuration files for the utility *lwarpmk*. Also included is a parallel version of the user's source document, `<sourcename>-html.tex`, which selects HTML output and then inputs the user's own source. This process allows both the printed and HTML versions to co-exist side-by-side, each with their own auxiliary files.

When requesting packages during HTML conversion, lwarp first looks to see if it has its own modified version to use instead of the standard LaTeX version. These `lwarp-packagename.sty` files contain code used to emulate or replace functions for HTML output.

[2] Firefox has had an on-again/off-again bug for quite some time regareding printing SVGs at high resolution.

[3] There seems to be some debate as to whether MathML is actually an improvement over LaTeX for sharing math. The author has no particular opinion on the matter, except to say that in this case LaTeX is much easier to implement!

[4] One SVG image file per math expression, except that duplicate inline math expressions are combined into a single file according to the MD5 hash function of its contents. A common scientific paper can easily include several thousand files, and in one case the MD5 hash cut the number of files in half and the rendering time by 30%.

## 2.1 Typesetting conventions

Font weight, family, and style are used to indicate various objects:

Table 1: Typesetting conventions

| | |
|---|---|
| package | LaTeX package. |
| *program* | Program's executable name. |
| `option` | Program or package option. |
| `filename` | File name in the operating system. |
| Brand Name | Proper name for a program, operating system, etc. |
| **commands** | Commands to be entered by the user. |
| `code` | Program code. |
| `\macroname` | LaTeX macro. |
| `environment` | LaTeX environment. |
| `counter` | LaTeX counter. |
| `boolean` | LaTeX boolean. |
| `<element>` | HTML element. |
| `attribute` | HTML attribute. |
| User Interface | A user-interface item. |
| acro | Acronym. |

## 2.2 Supported packages and features

Table 2 lists some of the various LaTeX features and packages which may be used.

Package names are colored according to their support level:

name: Supported as-is.

name: Modifed to work with HTML output, and perhaps also as print output in SVG math or `latexmage` environments.

name: Emulated for HTML output.

name: Ignored for HTML output, but provides source-level compatibility.

MJ: Supported as-is for MathJax, subject to limitations.

MJ: Emulated for MathJax using custom macros, subject to limitations.

MJ: Ignored by MathJax, but may be used in the document source. May be converted to SVG images.

Table 2: LaTeX lwarp package — Supported features

| Category | Status and supported features. |
|---|---|
| Engines: | DVI LaTeX, pdfLaTeX, XeLaTeX, LuaLaTeX, upLaTeX |
| Compiling: | *latexmk*, *perltex*, *pythontex*, *make*, etc. |
| Classes: | article, book, report, scrartcl, scrbook, scrreprt, memoir, CJK-related as listed below. |
| Koma-script: | scrextend, scrhack, scrlayer. Others as listed below. |
| Memoir: | memhfixc |
| Languages: | babel, cjkpunct, impnattypo, luavlna, polyglossia, xeCJK, xevlna. |
| Chinese: | CTeX, ctex, upzhkinsoku, xpinyin, zhlineskip, zhspacing. |
| Japanese: | upLaTeX, LuaTeX-ja, gentombow, lltjext, plarray, plarydshln, plautopatch, plext, plextarray, plextarydshln, plextcolortbl, plextdelarray, pxatbegshi, pxeveryshi, pxftnright, pxgentombow, pxjahyper, pxpdfpages, pxpgfrcs, pxpgfmark, tascmac, zxjatype. bxjsarticle and related, ltjsarticle and related, luatexja, luatexja-fontspec, ujarticle and related, utarticle and related. |
| Korean: | kotex, luatexko, xetexko. |

lwarp Supported Functions — continued

| Category | Status |
|---|---|
| Page layout: | 2in1, 2up, a4, a4wide, a5comb, addlines, anysize, atbegshi, blowup, booklet, bophook, bounddvi, bxpapersize, canoniclayout, changelayout, changepage, chngpage, clrdblpg, continue, draftcopy, draftfigure, draftwatermark, ebook, everyshi, fancyhdr, fancytabs, flippdf, fullminipage, fullpage, fwlw, geometry, gmeometric, grid, grid-system, gridset, layaureo, layout, layouts, leading, ltxgrid, nccfancyhdr, notespages, nowidow, pagegrid, pagesel, parallel, parcolumns, pdfcolparallel, pdfcolparcolumns, pdfcrypt, pdfprivacy, preview, ragged2e, returntogrid, rmpage, scrlayer-scrpage, scrpage2, setspace, selectp, textarea, threadcol, thumb, thumbs, titleps, tocenter, turnthepage, twoup, typearea, underlin, vmargin, watermark, widows-and-orphans, zwpagelayout. |
| Sectioning: | Adds `FileDepth` for splitting the HTML output. Files may be numbered sequentially or named according to section name. Common short words and punctuation are removed from the filenames. anonchap, bsheaders, fncychap, hypbmsec, indentfirst, quotchap, section, sectionbreak, secdot, sectsty, titlesec, tocvsec2. |
| Table of contents, figures, tables: | Supported, with hyperlinks. etoc, minitoc, multitoc, shorttoc, tableof, titletoc, tocbasic, tocbibind, tocdata, tocloft, tocstyle, tocvsec2. |
| Title page: | `\maketitle`, `titlepage`, authblk, authoraftertitle, titling. |
| Front & back matter: | abstract, appendix. |
| Indexing: | *makeindex*, *xindy*, and *xindex* are supported, with hyperlinks.<br>gindex, hvindex, idxlayout, imakeidx, index, makeidx, repeatindex, splitidx, varindex, xindex. |
| Glossary: | gloss, glossaries and *xindy*, nomencl. |
| Bibliography: | babelbib, bibtopic, backref, biblatex, bibunits, chapterbib, cite, citeref, collref, drftcite, hypernat, jurabib, mcite, mciteplus, multibib, natbib, notes2bib, splitbib, showtags. |

lwarp Supported Functions — continued

| Category | Status |
|---|---|
| Cross-references: | bookmark, breakurl, cleveref, fancyref, hypdestopt, hyperref, perpage, prettyref, titleref, url, varioref, xcite, xr, xr-hyper, xurl, zref. |
| Margin notes: | marginal, marginfit, marginfix, scrlayer-notecolumn, versonotes. |
| Footnotes: | Adds `FootnoteDepth` to print footnotes at section breaks. MathJax emulation for `\footnote`, and also as marked in the following: bigfoot, dblfnote, endheads, endnotes[MJ], fixfoot, fnbreak, fnpara, fnpos, footmisc, footnote, footnotebackref, footnoterange, footnpag, manyfoot, marginnote[MJ], nccfoots[MJ], pagenote[MJ], parnotes[MJ], pdfcolfoot, pfnote, sepfootnotes, sidenotes[MJ], tablefootnote. |
| Math: | Converted to SVG images with HTML `<alt>` tags containing the LaTeX source for the math expression. MathJax supported as an alternative. amsmath[MJ]: $\mathcal{AMS}$ environments are supported. User-defined macros are available during converson, due to native LaTeX processing. |
| Theorems: | Native LaTeX theorems, amsthm, apxproof, ntheorem, shadethm, theorem, thmbox, thmtools. |
| Additional math: | Math fonts via SVG images, accents[MJ], amscd[MJ], amscdx, autobreak[MJ], autonum, backnaur[MJ], bm[MJ], braket[MJ], breqn[MJ], bussproofs[MJ], cases[MJ], centernot[MJ], cmbright[MJ], colonequals[MJ], decimal[MJ], delarray, DotArrow[MJ], dotlessi[MJ], dotlessj[MJ], esvect[MJ], extarrows[MJ], fixmath[MJ], fouridx[MJ], fourier[MJ], guass, hhtensor[MJ], icomma[MJ], isomath[MJ], jkmath, kpfonts[MJ], kpfonts-otf[MJ], leftidx[MJ], libertinust1math[MJ], mathalpha[MJ], mathastext[MJ], mathcomp[MJ], mathdesign[MJ], mathdots[MJ], mathfixs[MJ], mathpazo[MJ], mathptmx[MJ], mathpunctspace[MJ], mathspec[MJ], mathtools[MJ], mattens[MJ], maybemath[MJ], mdwmath[MJ], mismath[MJ], mleftright[MJ], multiobjective[MJ], nccmath[MJ], nicematrix[MJ], noitcrul[MJ], newpxmath[MJ], newtxmath[MJ], newtxsf[MJ], pb-diagram, pxfonts[MJ], resizegather[MJ], rmathbr[MJ], scalerel[MJ], shuffle[MJ], skmath[MJ], stackrel[MJ], statex2[MJ], statistics, statmath[MJ], subsupscripts[MJ], tensind, tensor[MJ], textualicomma[MJ], txfonts[MJ], txgreeks[MJ], unicode-math[MJ], upgreek[MJ], ushort[MJ], witharrows[MJ], xfakebold[MJ], xy. Many others work as-is. |

lwarp Supported Functions — continued

| Category | Status |
|---|---|
| Display math with `\displaymathother`: | Complicated math objects in display math, such as tikz-cd, etc. |
| Units and fractions: | nicefrac[MJ], SIunits[MJ], siunitx[MJ], units[MJ], unitsdef, xfrac[MJ]. |
| Floats: | Appear where declared. capt-of, caption, cutwin, dblfloatfix, endfloat, fewerfloatpages, fix2col, flafter, float, floatflt, floatrow, fltrace, ftcap, hypcap, keyfloat, morefloats, multicap, newfloat, nonfloat, picinpar, placeins, rotfloat, stfloats, subcaption, subfig, subfigure, subfloat, swfigure, topcapt, trivfloat, wrapfig. |
| Tabular: | `tabular` environment, array[MJ], arydshln[MJ], bigdelim[MJ], bigstrut[MJ], booktabs[MJ], colortbl[MJ], ctable, diagbox, hhline[MJ], longtable, ltablex, ltxtable, multirow[MJ], supertabular, tabularx, tabulary, threeparttable, threeparttablex, widetable, xltabular, xtab. |
| Graphics: | graphics and graphicx. `\includegraphics` supports `width`, `height`, `origin`, `angle`, and `scale` tags, and adds `class`. References to PDF files are changed to SVG, other image types are accepted as well. `\rotatebox` and `\scalebox` are supported as well as HTML can handle. rotating is emulated but all objects are unrotated in HTML. `picture`, tikz, and xy are converted to an SVG image.<br>asymptote, curves, datatool, eepic, epsf, epsfig, epstopdf, figsize, fitbox, grffile, lpic, luamplib, media9, movie15, multimedia, overpic, pict2e, pinlabel, psfrag, psfragx, pst-eps, pstool, pstricks, rlepsf, rviewport, svg, svg-extract, tikz, tikz-3dplot, tikz-imagelabels, xy |
| xcolor: | Full package color names, any color models, and mixing. `\textcolor`, `\colorbox`, `\fcolorbox`. Enhanced for HTML compatibility. |
| Lists: | Standard LaTeX environments, enumerate, enumitem, eqlist, hang, listliketab, paralist. |
| Environments: | Standard LaTeX environments. |
| `minipage`, `\parbox`: | Some HTML5-imposed limitations. Nested minipages are supported. eqparbox, minibox, pbox, shapepar. |
| Quotations: | copyrightbox, csquotes, epigraph, quoting, verse. |

lwarp Supported Functions — continued

| Category | Status |
|---|---|
| Verbatim: | fancyvrb, fvextra, moreverb, shortvrb, verbatim. |
| Frames: | boxedminipage, boxedminipage2e, fancybox, fbox[MJ], framed, mdframed, niceframe, shadow, tcolorbox[MJ], vertbars. |
| Multi-columns: | adjmulticol, multicol, multicolrule, vwcol. |
| Margins: | fullwidth, hanging, midpage. |
| Line numbering: | fnlineno, lineno. |
| Direct formatting: | `\emph`, `\textsuperscript`, `\textbf`, etc are supported. `\bfseries`, etc. are only supported in some cases. cancel[MJ], ellipsis, embrac, enparen, hyphenat, lettrine, lips, lua-check-hyphen, luacolor, magaz, moresize, nolbreaks, normalcolor, pdfcol, pdfcolmk, pdfrender, realscripts, relsize[MJ], scalefnt, seqsplit[MJ], soul, soulpos, soulutf8, stackengine, textfit, thinsp, trimclip, truncate, ulem, umoline, underscore, uspace, xellipsis. |
| Acronyms: | acro, acronym. |
| Ordinals: | engord, fmtcount, nth. |
| Text ligatures: | Ligatures for symbols are supported. Ligatures for f, q, t are intentionally turned off because many simpler browsers do not display them correctly. Modern full-featured browsers re-create these ligatures on-the-fly. |
| Horizontal space: | HTML output for thin-unbreakable, unbreakable, `\enskip`, `\quad`, `\qquad`, `\hspace`. |
| Rules: | `\rule` with width, height, raise, text color. |
| HTML reserved characters: | `\&`, `\textless`, and `\textgreater` are converted to HTML entities. |
| Fonts: | Used as-is. Appear in SVG math expressions or embedded image environments. fontaxes, nfssext-cfr, slantsc, tabfigures.<br>Tested to work as-is: Special font macros in cfr-lm and others which use nfssext-cfr.<br>Also see the math section for math and MathJax support for math font packages. |

lwarp Supported Functions — continued

| Category | Status |
|---|---|
| Symbols: | Native LaTeX diacriticals, academicons, amssymb[MJ], bbding, chemgreek, dingbat, euro, eurosym, fontawesome, fontawesome5, gensymb[MJ], latexsym[MJ], marvosym, metalogo, metalogox, pifont, textalpha, textcomp, textgreek, typicons, xunicode. |
| Files: | attachfile, attachfile2, hyperxmp, inputtrc, intopdf, pdfpages, pdfx, xmpincl. |
| Science and engineering: | algorithm2e, algorithmicx, ar[MJ], askmaps, axodraw2, bitpattern, blochsphere, bodegraph, bohr, bytefield, chemfig, chemformula, chemgreek, chemmacros, chemnum, circuitikz, econometrics[MJ], elements, engtlc[MJ], fast-diagram, ghsystem, hepnicenames, heppennames, hepunits[MJ], isotope[MJ], karnaughmap, karnaugh-map, keystroke, listings, listingsutf8, linop, menukeys, mhchem[MJ], minted, pgfgantt, phfqit, physics[MJ], physunits[MJ], plimsoll[MJ], qcircuit, register, simplebnf, simpler-wick, slashed[MJ], steinmetz[MJ], structmech, struktex, syntaxdi, tikz-karnaugh, tikzcodeblocks, venndiagram |
| Arts and humanities: | foreign, forest, lyluatex, musicography, nameauth, octave, phonrule, piano, schemata, semantic-markup, tikz-dependency, vowel, xpiano |
| Calendars: | termcal |
| Admonitions: | awesomebox, notes. |
| Editorial: | changebar, changelog, changes, easy-todo, easyReview, ed, errata, fixme, fixmetodonotes, pdfcomment[MJ], pdfmarginpar, todo, todonotes, tram, xechangebar. |
| Accessibility: | accessibility[MJ], accsupp[MJ], axessibility[MJ], pdfcomment[MJ], repltext[MJ], tagpdf. |
| Package handling: | catoptions. |
| Debug: | chkfloat, cmdtrack, dprogress, lua-visual-debug, refcheck, srcltx, srctex, vpe, xbmks. |

lwarp Supported Functions — continued

| Category | Status |
|---|---|
| Working as-is: | Various utility, calculation, file, and text-only packages, such as calc, fileerr, somedefs, trace, xspace. Also, most math-only packages, including specialized typesetting for various fields of science and engineering. |

# 3 Alternatives

Summarized below are several other ways to convert a LaTeX or other document to HTML. Where an existing LaTeX document is to be converted to HTML, lwarp may be a good choice. For new projects with a large number of documents, it may be worth investigating the alternatives before decided which path to take.

## 3.1 internet class

Cls internet The closest to lwarp in design principle is the `internet` class by Andrew Stacey — an interesting project which directly produces several versions of markdown, and also HTML and EPUB. https://github.com/loopspace/latex-to-internet

## 3.2 TeX4ht

Prog TeX4ht http://tug.org/tex4ht/

Prog htlatex

This system uses native LaTeX processing to produce a DVI file containing special commands, and then uses additional post-processing for the HTML conversion by way of numerous configuration files. In some cases lwarp provides a better HTML conversion, and it supports a different set of packages. TeX4ht produces several other forms of output beyond HTML, including ODT and a direct path to EPUB, and is still being developed.

## 3.3 Translators

These systems use external programs to translate a subset of LaTeX syntax into HTML. Search for each on CTAN (http:\ctan.org).

Prog Hevea **HeVeA:** http://hevea.inria.fr/ (not on CTAN)

Prog TtH **TtH:** http://hutchinson.belmont.ma.us/tth/

Prog GELLMU **GELLMU:** http://www.albany.edu/~hammond/gellmu/

Prog LaTeXML **LaTeXML:** http://dlmf.nist.gov/LaTeXML/

Prog Plastex **PlasTeX:** https://github.com/tiarno/plastex

Prog LaTeX2HTML **LaTeX2HTML:** http://www.latex2html.org/
and http://ctan.org/pkg/latex2html.

Prog TeX2page **TeX2page:** http://ds26gte.github.io/tex2page/index.html

Finally, GladTeX may used to directly insert LaTeX math into HTML:

Prog GladTeX **GladTeX:** http://humenda.github.io/GladTeX/

## 3.4 AsciiDoc and Asciidoctor

AsciiDoc is one of the most capable markup languages, providing enough features to produce the typical technical-writing document with cross-references, and it writes LaTeX and HTML.

Prog AsciiDoc **Asciidoctor:** http://asciidoctor.org/ (More active.)

Prog AsciiDoctor **AsciiDoc:** http://asciidoc.org/ (The original project.)

### 3.4.1 Asciidoctor-LaTeX

The Asciidoctor-LaTeX project is developing additional LaTeX-related features.

**Asciidoctor-LateX:**
http://www.noteshare.io/book/asciidoctor-latex-manual
Prog Asciidoctor-LaTeX https://github.com/asciidoctor/asciidoctor-latex

## 3.5 Pandoc

Prog Pandoc A markup system which also reads and writes LaTeX and HTML.

**Pandoc:** http://pandoc.org/

(Watch for improvements in cross-references to figures and tables.)

## 3.6 Word processors

Prog Word
Prog LibreOffice
Prog OpenOffice

It should be noted that the popular word processors have advanced through the years in their abilities to represent math with a LaTeX-ish input syntax, unicode math fonts, and high-quality output, and also generate HTML with varying success. See recent developments in Microsoft ® *Word* ® and LibreOffice ™ *Writer*.

## 3.7 Commercial systems

Prog Adobe
Prog FrameMaker
Prog InDesign
Prog Flare
Prog Madcap

Likewise, several professional systems exist whose abilities have been advancing in the areas of typesetting, cross-referencing, and HTML generation. See Adobe ® *FrameMaker* ®, Adobe *InDesign* ®, and Madcap *Flare* ™.

## 3.8 Comparisons

AsciiDoc, Pandoc, and various other markup languages typically have a syntax which tries to be natural and human-readable, but the use of advanced features tends to require many combinations of special characters, resulting in a complicated mess of syntax. By

contrast, LaTeX spells things out in readable words but takes longer to type, although integrated editors exist which can provide faster entry and a graphic user interface. For those functions which are covered by the typical markup language it is arguable that LaTeX is comparably easy to learn, while LaTeX provides many more advanced features where needed, along with a large number of pre-existing packages which provide solutions to numerous common tasks.

Text-based document-markup systems share some of the advantages of LaTeX vs. a typical word processor. Documents formats are stable. The documents themselves are portable, work well with revision control, do not crash or become corrupted, and are easily generated under program control. Formatting commands are visible, cross-referencing is automatic, and editing is responsive. Search/replace with regular expressions provides a powerful tool for the manipulation of both document contents and structure. Markup systems and some commercial systems allow printed output through a LaTeX back end, yielding high-quality results especially when the LaTeX template is adjusted, but they lose the ability to use LaTeX macros and other LaTeX source-document features.

The effort required to customize the output of each markup system varies. For print output, LaTeX configuration files are usually used. For HTML output, a CSS file will be available, but additional configuration may require editing some form of control file with a different syntax, such as XML. In the case of lwarp, CSS is used, and much HTML output is adjusted through the usual LaTeX optional macro parameters, but further customization may require patching LaTeX code.

The popular word processors and professional document systems each has a large base of after-market support including pre-designed styles and templates, and often include content-management systems for topic reuse.

# 4 Installation

Table 3 shows the tools which are used for the LaTeX to HTML conversion. In most cases, these will be available via the standard package-installation tools.

Detailed installation instructions follow.

Table 3: Required software programs

**Provided by your LaTeX distribution:**

From TeXLive: http://tug.org/texlive/.

**LaTeX:** *pdflatex*, *xelatex*, or *lualatex*.

**The lwarp package:** This package.

**The *lwarpmk* utility:** Provided along with this package. This should be an operating-system executable in the same way that *pdflatex* or *latexmk* is. It is possible to have the lwarp package generate a local copy of *lwarpmk* called `lwarpmk.lua`. See table 4.

***luatex*:** Used by the *lwarpmk* program to simplify and automate document generation.

***xindy*:** The *xindy* program is used by lwarp to create indexes. On a MiKTeX system this may have to be acquired separately, but it is part of the regular installer as of mid 2015.

***latexmk*:** Optionally used by *lwarpmk* to compile LaTeX code. On a MiKTeX system, *Perl* may need to be installed first.

***pdfcrop*:** Used to pull images out of the LaTeX PDF.

**Poppler PDF utilities:**

***pdftotext*:** Used to convert PDF to text.

***pdfseparate*:** Used to pull images out of the LaTeX PDF.

***pdftocairo*:** Used to convert images to SVG.

These might be provided by your operating-system package manager, and MiKTeX provides miktex-poppler-bin-* packages.

From Poppler: poppler.freedesktop.org.

For MacOS®, see https://brew.sh/, install *Homebrew*, then

Enter ⇒ **`brew install poppler`**

For Windows, see MikTeX miktex-poppler-bin-*, or:
https://sourceforge.net/projects/poppler-win32/ and:
http://blog.alivate.com.au/poppler-windows/

***Perl*:**

This may be provided by your operating-system package manager, and may be required for some of the Poppler PDF utilities.

strawberryperl.com (recommended), perl.org

**Automatically downloaded from the internet as required:**

**MathJax:** Optionally used to display math. From: mathjax.org

## 4.1 Installing the lwarp package

There are several ways to install lwarp. These are listed here with the preferred methods listed first:

**Pre-installed:** Try entering into a command line:

Enter ⇒ **`kpsewhich lwarp.sty`**

If a path to `lwarp.sty` is shown, then lwarp is already installed and you may skip to the next section.

**TEX Live:** If using a TEX Live distribution, try installing via *tlmgr*:

Enter ⇒ **`tlmgr install lwarp`**

**MiKTEX:**

1. For newer versions of MiKTEX, install or update lwarp using the *MiKTeX Console* program.
2. For older versions of MiKTEX, to install lwarp the first time, use the *MiKTeX Package Manager (Admin)*. To update lwarp, use *MiKTeX Update (Admin)*.
3. Either way, also update the package miktex-misc, which will install and update the *lwarpmk* executable.

**Operating-system package:** The operating-system package manager may already have lwarp, perhaps as part of a set of TEX-related packages.

**CTAN TDS archive:** lwarp may be downloaded from the Comprehensive TEX Archive:

1. See http://ctan.org/pkg/lwarp for the lwarp package.
2. Download the TDS archive: `lwarp.tds.zip`
3. Find the TEX `local` directory:

   **TEX Live:**

   Enter ⇒ **`kpsewhich -var-value TEXMFLOCAL`**

   **MiKTEX:**

   In the Settings window, Roots tab, look for a local TDS root.

   This should be something like:

   ```
   /usr/local/texlive/texmf-local/
   ```

4. Unpack the archive in the TDS local directory.
5. Renew the cache:

   Enter ⇒ **`mktexlsr`**

   — or —

   Enter ⇒ **`texhash`**

   Or, for WINDOWS MiKTEX, start the program called *MiKTeX Settings (Admin)* and click on the button called Refresh FNDB.

**CTAN `.dtx` and `.ins` files:** Another form of TEX package is `.dtx` and `.ins` source files. These files are used to create the documentation and `.sty` files.

1. See http://ctan.org/pkg/lwarp for the lwarp package.
2. Download the zip archive `lwarp.zip` into your own `lwarp` directory.
3. Unpack `lwarp.zip`.
4. Locate the contents `lwarp.dtx` and `lwarp.ins`
5. Create the `.sty` files:

   Enter ⇒ **`pdflatex lwarp.ins`**
6. Create the documentation:

```
pdflatex lwarp.dtx  (several times)
makeindex -s gglo.ist -o lwarp.gls lwarp.glo
makeindex -s gind.ist lwarp.idx
pdflatex lwarp.dtx  (several times)
```

7. Copy the `.sty` files somewhere such as the TEX Live local tree found in the previous CTAN TDS section, under the subdirectory:

   `<texlocal>/tex/latex/local/lwarp`
8. Copy `lwarp_baseline_marker.png` and `lwarp_baseline_marker.eps` to the same place as the `.sty` files.
9. Copy the documentation `lwarp.pdf` to a `source` directory in the local tree, such as:

   `<texlocal>/doc/local/lwarp`
10. Renew the cache:

    Enter ⇒ **`mktexlsr`**

    — or —

    Enter ⇒ **`texhash`**

    Or, for WINDOWS MiKTEX, start the program called *MiKTeX Settings (Admin)* and click on the button called Refresh FNDB.
11. See section 4.2.1 to generate your local copy of *lwarpmk*.
12. Once the local version of `lwarpmk.lua` is installed, it may be made available system-wide as per section 4.2.

**Project-local CTAN `.dtx` and `.ins` files:** The `.dtx` and `.ins` files may be downloaded to a project directory, then compiled right there, alongside the document source files. The resultant `*.sty` and `lwarpmk.lua` files may be used as-is, so long as they are in the same directory as the document source. The files `lwarp_baseline_marker.png` and `lwarp_baseline_marker.eps` must also be copied as well. This approach is especially useful if you would like to temporarily test lwarp before deciding whether to permanently install it.

Just testing!

## 4.2 Installing the *lwarpmk* utility

(Note: If *lwarpmk* is not already installed, it is easiest to use a local copy instead of installing it system-wide. See section 4.2.1.)

After the lwarp package is installed, you may need to setup the *lwarpmk* utility:

1. At a command line, try executing **`lwarpmk`**. If the *lwarpmk* help message appears, then *lwarpmk* is already set up. If not, it is easiest to generate and use a local copy. See section 4.2.1.

2. For MiKTEX, try updating the miktex-misc package. This may install the *lwarpmk* executable for you.

   Otherwise, continue with the following:

3. Locate the file `lwarpmk.lua`, which should be in the `scripts` directory of the TDS tree. On a TEX Live or MiKTEX system you may use

   Enter ⇒ **`kpsewhich lwarpmk.lua`**

   (If the file is not found, you may also generate a local copy and use it instead. See section 4.2.1.)

4. Create *lwarpmk*:

   **Unix:** Create a symbolic link and make it executable:

   (a) Locate the TEX Live binaries:

   Enter ⇒ **`kpsewhich -var-value TEXMFROOT`**

   This will be something like:

   `/usr/local/texlive/<year>`

   The binaries are then located in the `bin/<arch>` directory under the root:

   `/usr/local/texlive/<year>/bin/<architecture>/`

   In this directory you will find programs such as *pdflatex* and *makeindex*.

   (b) In the binaries directory, create a new symbolic link from the binaries directory to `lwarpmk.lua`:

   Enter ⇒ **`ln -s <pathtolwarpmk.lua> lwarpmk`**

   (c) Make the link executable:

   Enter ⇒ **`chmod 0755 lwarpmk`**

   **Windows TEX Live:** Create a new `lwarpmk.exe` file:

   (a) Locate the TEX Live binaries as shown above for Unix.

   (b) In the binaries directory, make a *copy* of `runscript.exe` and call it `lwarpmk.exe` This will call the copy of `lwarpmk.lua` which is in the `scripts` directory of the distribution.

   **Windows MiKTEX:** Create a new `lwarpmk.bat` file:

   (a) Locate the MiKTEX binaries. These will be in a directory such as:

   `C:\Program Files\MiKTeX 2.9\miktex\bin\x64`

   In this directory you will find programs such as `pdflatex.exe` and `makeindex.exe`.

   (b) Create a new file named `lwarpmk.bat` containing:

   ```
   texlua "C:\Program Files\MiKTeX 2.9\scripts\lwarp\lwarp.texlua" %*
   ```

   This will call the copy of `lwarpmk.lua` which is in the `scripts` directory of the distribution.

### 4.2.1 Using a local copy of *lwarpmk*

It is also possible to use a local version of *lwarpmk*:

1. When compiling the tutorial in section 5, use the `lwarpmk` option for the lwarp package:

   ```
   \usepackage[lwarpmk]{lwarp}
   ```

2. When the tutorial is compiled with *pdflatex*, the file `lwarpmk.lua` will be generated along with the other configuration files.

3. `lwarpmk.lua` may be used for this project:

   **Unix:**

   (a) Make `lwarpmk.lua` executable:
   Enter ⇒ **`chmod 0755 lwarpmk.lua`**

   (b) Compile documents with
   Enter ⇒ **`./lwarpmk.lua html`**
   Enter ⇒ **`./lwarpmk.lua print`**
   etc.

   (c) It may be useful to rename or link to a version without the `.lua` suffix.

   **Windows:**

   Compile documents with either of the following, depending on which command shell is being used:
   Enter ⇒ **`texlua lwarpmk.lua html`**
   Enter ⇒ **`texlua lwarpmk.lua print`**
   etc.

   Or:
   Enter ⇒ **`lwarpmk html`**
   Enter ⇒ **`lwarpmk print`**
   etc.

## 4.3 Installing additional utilities

**To test for the existence of the additional utilities:**

Enter the following in a command line. If each programs' version is displayed, then that utility is already installed. See table 3 on page 77.

Enter ⇒ **`luatex --version`**
Enter ⇒ **`xindy --version`**
Enter ⇒ **`latexmk --version`**
Enter ⇒ **`perl --version`**
Enter ⇒ **`pdfcrop --version`**
Enter ⇒ **`pdftotext -v`**
Enter ⇒ **`pdfseparate --version`**
Enter ⇒ **`pdftocairo -v`**

**To install *xindy*, *latexmk*, and *pdfcrop*:**

The TEX utilities *xindy*, *latexmk*, and *pdfcrop* may be installed in *TexLive* with *tlmgr*, installed by *MiKTeX*, provided by your operating system's package manager, or downloaded from the *CTAN* archive:

http://ctan.org/pkg/xindy
http://ctan.org/pkg/latexmk
http://ctan.org/pkg/pdfcrop

Prog [requirement] pdftotext
Prog [requirement] pdfseparate
Prog [requirement] pdftocairo

**To install the Poppler utilities to a Unix/Linux system:**

The tools from the Poppler project should be provided by your operating system's package manager.

**To install the Poppler utilities to a MacOS machine:**

1. Install *Homebrew* from https://brew.sh/:

```
/usr/bin/ruby -e "$(curl -fsSL https://raw.githubusercontent.com/Homebrew/install/master/install)"
```
Enter

2. Install the Poppler utilities:

Enter ⇒ `brew install poppler`

**To install the Poppler utilities to a Windows machine:**

If using MikTeX, install a miktex-poppler-bin-* package. Otherwise:

1. See table 3 on page 77.
2. Download and extract the Poppler utilities *pdftotext*, *pdfseparate*, and *pdfseparate* to a directory, such as `Poppler`.
3. In the Start window, type "Path" to search for results related to Path. Or, open the control panel and search for "Path".
4. Choose Edit the system environment variables in the control panel.
5. Choose the Environment Variables button.
6. Choose the Path variable, then the Edit button.
7. Choose the New button to make an additional entry.
8. Enter the `bin` directory of the Poppler utilities, such as:

   `C:\Users\<myname>\Desktop\Poppler\poppler-0.5_x86\poppler-0.5\bin`

   Be sure to include `\bin`.
9. Click Ok when done.

Prog [requirement] perl

**To install Perl to a Windows machine:**

1. Download and install a version of Perl, such as Strawberry Perl, to a directory without a space in its name, such as `C:\Strawberry`.
2. Edit the Path as seen above for the Poppler utilities.
3. Enter the `bin` directory of the *perl* utility, such as:

   `C:\Strawberry\perl\bin`

   Be sure to include `\bin`.
4. Click Ok when done.

**Any utilities installed by hand must be added to the PATH.**

# 5 Tutorial

This section shows an example of how to create an lwarp document.

Need help?

See the General Index for "how-to", and the Troubleshooting Index if something doesn't work. A Troubleshooting section is also available. The Index of Objects contains automated entries for each package, macro, environment, counter, boolean, and other objects; individually and also sorted by category.

## 5.1 Starting a new project

1. Create a new project directory called `tutorial`.

File `tutorial.tex`

2. Inside the `tutorial` directory, create a new file called `tutorial.tex`. This may be done several ways:

   **Copy from the documentation PDF:**

   A listing is in fig. 1, which may be copied/pasted from the figure directly into your own editor, depending on the quality of the PDF viewer and editor, or:

   **Copy from the lwarp documentation directory:**

File `lwarp_tutorial.txt`

⚠ Note: `.txt` suffix!

   Another copy may be found by entering into a command line:

   Enter ⇒ **`texdoc -l lwarp_tutorial.txt`**

   This should be in the `doc/latex/lwarp/` directory along with this PDF documentation. Copy `lwarp_tutorial.txt` directly into your `tutorial` directory, renamed as `tutorial.tex`.

⚠ Bad formatting!

   *When using Windows, use an editor other than Notepad, since Notepad does not accept the end-of-line from a Unix text file.*

3. Compile the project:

   Enter ⇒ **`pdflatex tutorial.tex`**

   (several times)

   (*xelatex* or *lualatex* may be used as well. lwarp also supports DVI *latex* for use with `.eps` images.)

4. View the resulting `tutorial.pdf` with a PDF viewer.

A number of new files are created when `tutorial.tex` is compiled, as shown in table 4. These files are created by the `lwarp` package.

(Two of the new files are configuration files for the helper program *lwarpmk*. Whenever a print version of the document is created, the configuration files for *lwarpmk* are updated to record the operating system, LaTeX engine (*latex*, *pdflatex*, *xelatex*, or *lualatex*), the filenames of the source code and HTML output, and whether the additional helper program *latexmk* will be used to compile the document.)

Figure 1: tutorial.tex listing

Note: There are two pages!

```
% Save this as tutorial.tex for the lwarp package tutorial.

\documentclass{book}

\usepackage{iftex}

% --- LOAD FONT SELECTION AND ENCODING BEFORE LOADING LWARP ---

\ifPDFTeX
\usepackage{lmodern}            % pdflatex or dvi latex
\usepackage[T1]{fontenc}
\usepackage[utf8]{inputenc}
\else
\usepackage{fontspec}           % XeLaTeX or LuaLaTeX
\fi

% --- LWARP IS LOADED NEXT ---
\usepackage[
%   HomeHTMLFilename=index,     % Filename of the homepage.
%   HTMLFilename={node-},       % Filename prefix of other pages.
%   IndexLanguage=english,      % Language for xindy index, glossary.
%   latexmk,                    % Use latexmk to compile.
%   OSWindows,                  % Force Windows. (Usually automatic.)
%   mathjax,                    % Use MathJax to display math.
]{lwarp}
% \boolfalse{FileSectionNames}  % If false, numbers the files.

% --- LOAD PDFLATEX MATH FONTS HERE ---

% --- OTHER PACKAGES ARE LOADED AFTER LWARP ---
\usepackage{makeidx} \makeindex
\usepackage{xcolor}             % (Demonstration purposes only.)
\usepackage{hyperref,cleveref}  % LOAD THESE LAST!

% --- LATEX AND HTML CUSTOMIZATION ---
\title{The Lwarp Tutorial}
\author{Some Author}
\setcounter{tocdepth}{2}        % Include subsections in the \TOC.
\setcounter{secnumdepth}{2}     % Number down to subsections.
\setcounter{FileDepth}{1}       % Split \HTML\ files at sections
\booltrue{CombineHigherDepths}  % Combine parts/chapters/sections
\setcounter{SideTOCDepth}{1}    % Include subsections in the side\TOC
\HTMLTitle{Webpage Title}       % Overrides \title for the web page.
\HTMLAuthor{Some Author}        % Sets the HTML meta author tag.
\HTMLLanguage{en-US}            % Sets the HTML meta language.
\HTMLDescription{A description.}% Sets the HTML meta description.
\HTMLFirstPageTop{Name and \fbox{HOMEPAGE LOGO}}
\HTMLPageTop{\fbox{LOGO}}
\HTMLPageBottom{Contact Information and Copyright}
\CSSFilename{lwarp_sagebrush.css}
```

```
\begin{document}

\maketitle                      % Or titlepage/titlingpage environment.

% An article abstract would go here.

\tableofcontents                % MUST BE BEFORE THE FIRST SECTION BREAK!
\listoffigures

\chapter{First chapter}

\section{A section}

This is some text which is indexed.\index{Some text.}

\subsection{A subsection}

See \cref{fig:withtext}.

\begin{figure}\begin{center}
\fbox{\textcolor{blue!50!green}{Text in a figure.}}
\caption{A figure with text\label{fig:withtext}}
\end{center}\end{figure}

\section{Some math}

Inline math: $r = r_0 + vt - \frac{1}{2}at^2$
followed by display math:
\begin{equation}
a^2 + b^2 = c^2
\end{equation}


\begin{warpprint}   % For print output ...
\cleardoublepage    % ... a common method to place index entry into TOC.
\phantomsection
\addcontentsline{toc}{chapter}{\indexname}
\end{warpprint}
\ForceHTMLPage      % HTML index will be on its own page.
\ForceHTMLTOC       % HTML index will have its own toc entry.
\printindex

\end{document}
```

Table 4: Configuration files created by print version

**tutorial.pdf:** The PDF output from LaTeX. The print version of the document.

**tutorial_html.tex:** A small `.tex` file used to create a parallel HTML version of the document, which co-exists with usual the PDF version, and which will have its own auxiliary files. In this way, both PDF and HTML documents may co-exist side-by-side.

**Auxiliary files:** The usual LaTeX files `.aux`, `.log`, `.out`, `.toc`, `.lof`, `.idx`. When an HTML version of the document is created, `_html` versions of the auxiliary files will also be generated.

**lwarpmk.conf:** A configuration file for *lwarpmk*, which is used to automate the compilation of PDF or HTML versions of the document.

**tutorial.lwarpmkconf:** Another configuration file used by *lwarpmk*, which is only useful if you wish to have several projects residing in the same directory.

**.css files:** `lwarp.css`, `lwarp_formal.css`, `lwarp_sagebrush.css` These files are standard for lwarp, and are not meant to be modified by the user.

**sample_project.css:** An example of a user-customized CSS file, which may be used for project-specific changes to the lwarp defaults.

**lwarp.ist:** Used by lwarp while creating an index using *makeindex*. This file should not be modified by the user. A custom file may be used instead, if necessary.

**lwarp.xdy:** Used by lwarp while creating an index using *xindy*. This file should not be modified by the user. A custom file may be used instead, if necessary.

**lwarp_one_limage.txt:** For Windows only. Used to process SVG images in the background. Copied to `lwarp_one_limage.cmd` when images are generated.

**lwarp_mathjax.txt:** Inserted into the HTML files when MathJax is used to display math. Do not modify, see `\MathJaxFilename` instead.

**comment_*.cut:** Temporary files used by lwarp to conditionally process blocks of text. These files may be ignored.

---

When the `lwarpmk` option is given to the lwarp package:

**lwarpmk.lua:** A local copy of the *lwarpmk* utility.

On Unix-related operating systems this file must be made executable:

```
chmod u+x lwarpmk.lua
```

This may be useful to have to archive with a project for future use.

## 5.2 Compiling the print version with *lwarpmk*

The *lwarpmk* utility program is used to compile either the printed or the HTML version of the document.

`lwarpmk print` is used to recompile a printed version of the document.

1. Re-compile the print version:

   Enter ⇒ **`lwarpmk print`**

   *lwarpmk* prints an introduction then checks to see if the document must be recompiled. If it seems that the files are up-to-date, then *lwarpmk* informs you of that fact and then exits.

2. Make a small change in the original document, such as adding a space character.

3. Recompile again.

   Enter ⇒ **`lwarpmk print`**

   The document is recompiled when a change is seen in the source. Several compilations may be necessary to resolve cross-references.

4. Force a recompile to occur.

   Enter ⇒ **`lwarpmk again`**

   Enter ⇒ **`lwarpmk print`**

   `lwarpmk again` updates the date code for the file, triggering a recompile the next time the document is made.[5]

5. Process the index.[6] [7]

   Enter ⇒ **`lwarpmk printindex`**

6. Recompile again to include the index.

   Enter ⇒ **`lwarpmk print`**

7. To force a single recompile when needed, even if no changes were detected:

   Enter ⇒ **`lwarpmk print1`**

Note that the HTML customization commands are ignored while making the print version.

[5] Although, when using the utility *latexmk* (introduced later), the changed date is ignored and an actual change in contents must occur to cause a recompile.

[6] The command **`lwarpmk printglossary`** is also available to process a glossary produced with the glossaries package. See section 8.6.12.

[7] Also see section 8.6.15 for index options.

## 5.3 Compiling the HTML version with *lwarpmk*

`lwarpmk html` is used to recompile an HTML version of the document.

1. Compile the HTML version:

   Enter ⇒ **`lwarpmk html`**

   (a) *lwarpmk* uses LaTeX to process `tutorial_html.tex` to create `tutorial_html.pdf`.

   (b) *pdftotext* is then used to convert to the file `tutorial_html.html`. This file is a plain-text file containing HTML tags and content for the entire document.

   (c) *lwarpmk* manually splits `tutorial_html.html` into individual HTML files according to the HTML settings. For this tutorial, the result is `tutorial.html` (the home page), along with `First-chapter.html`[8], `Some-math.html`, and the document's index in `_Index.html`.[9]

2. View the HTML page in a web browser.

   Open the file `tutorial.html` in a web browser.

   math Note that math is still displayed as its `alt` tag, which is the plain-text LaTeX source, until the images of the math expressions have been generated. Math may be displayed as SVG images or by a MathJax script, as seen in sections 5.4 and 5.5.

3. Force a recompile:

   Enter ⇒ **`lwarpmk again`**

   Enter ⇒ **`lwarpmk html`**

   Enter ⇒ **`lwarpmk print`**

4. Process the HTML index and recompile:[10][11]

   Enter ⇒ **`lwarpmk htmlindex`**

   Enter ⇒ **`lwarpmk html`**

   `_Index.html` is updated for the new LaTeX index.

5. Reload the web page to see the added index.

6. To force a single recompile when needed, even if no changes were detected:

   Enter ⇒ **`lwarpmk html1`**

[8] `First-chapter.html` also contains the first section, even though the second section is its own HTML page. This behavior is controlled by the boolean `CombineHigherDepths`.

[9] `index.html` is commonly used as a homepage, so the document index is in `_Index.html`.

[10] The command **`lwarpmk htmlglossary`** is also available to process a glossary produced with the glossaries package. See section 8.6.12.

[11] Also see section 8.6.15 for index options.

## 5.4 Generating the SVG images

math as SVG images

By default lwarp represents math as SVG images, with the LaTeX source included in `alt` attributes. In this way, the math is displayed as it was drawn by LaTeX, and the LaTeX source may be copied and pasted into other documents.

`picture` and Ti*k*z

lwarp uses the same mechanism for `picture` and Ti*k*z environments.

1. Create the SVG images:

   Enter ⇒ **`lwarpmk limages`**

   Enter ⇒ **`lwarpmk html`**

2. Move to the tutorial's HTML math page and reload the document in the browser.
3. The math images are displayed using the same font and formatting as the printed version.
4. Copy/paste a math expression into a text editor to see the LaTeX source.

⚠ adding/removing

When a math expression, `picture`, or Ti*k*z environment is added or removed, the SVG images must be re-created by entering **`lwarpmk limages`** to maintain the proper image-file associations. Inline SVG math may be hashed and thus not need to be recreated, but display math and objects such as Ti*k*z may move to new image numbers when the document is changed.

recompile first

Before attempting to create the SVG image files, *lwarpmk* verifies that the HTML version of the document exists and has correct internal image references.[12] If it is necessary to recompile the document's HTML version one more time, *lwarpmk* usually will inform the user with an error message, but there are some conditions which cannot be detected, so the user should watch for the LaTeX recompile warnings.

⚠ HTML instead of images

If HTML appears where an SVG image should be, recompile the document one more time to get the page numbers back in sync, then remake the images one more time.

⚠ page counter

Incorrect SVG images will also occur if the document changes the page counter:

```
\setcounter{page}{<value>}
```

The page counter must *not* be adjusted by the user.

⚠ Lots of files!

Expressing math as SVG images has the advantage of representing the math exactly as LaTeX would, but has the disadvantage of requiring an individual file for each math expression. For inline math, and some other objects, lwarp uses an MD5 hash on its LaTeX source to combine multiple instances of identical inline expressions into a single image file, but display math and other environments such as `picture` and Ti*k*z require one image file each. For a document with a large amount of math, see section 5.5 to use MathJax instead.

[12] This becomes important when dealing with a document containing thousands of images.

## 5.5 Using MathJax for math

math with MathJax

Math may also be represented using the MathJax Javascript project.

1. In the tutorial's source code, uncomment the `mathjax` package option for lwarp:

   ```
   mathjax, % Use MathJax to display math.
   ```

2. Recompile

   Enter ⇒ **`lwarpmk html`**

3. Reload the math page.

⚠ MathJax requirements

MathJax requires web access unless a local copy of MathJax is available, and it also requires that Javascript is enabled for the web page. The math is rendered by MathJax. Right-click on math to see several options for rendering, and for copying the LaTeX source.

While using MathJax has many advantages, it may not be able to represent complex expressions or spacing adjustments as well as LaTeX, and it may not support some math-related packages.

## 5.6 Changing the css style

For a formal CSS style, add to the preamble:

```
\usepackage{lwarp}
. . .
\CSSFilename{lwarp_formal.css}
. . .
\begin{document}
```

For a modern CSS style, `lwarp_sagebrush.css` is also provided:

```
\CSSFilename{lwarp_sagebrush.css}
```

See section 7.7 for more information about modifying the CSS styling of the document.

## 5.7 Customizing the HTML output

A number of settings may be made to control the HTML output, including filename generation, automatic compilation, math output, document splitting, meta data, and page headers and footers.

See section 7.6 for more information.

## 5.8 Using *latexmk*

*latexmk* is a LaTeX utility used to monitor changes in source files and recompile as needed.

1. In the tutorial's source code uncomment the `latexmk` option for the lwarp package:

   ```
   latexmk, % Use latexmk to compile.
   ```

2. Recompile the printed version of the document.

   Enter ⇒ **`lwarpmk print`**

   lwarp updates its own configuration files (`lwarpmk.conf` and `tutorial.lwarpmkconf`) whenever the printed version of the document is compiled. These configuration files remember that *lwarpmk* should use *latexmk* to compile the document.

3. Recompile the document.

   Enter ⇒ **`lwarpmk print`**

   and/or

   Enter ⇒ **`lwarpmk html`**

Changes are detected by comparing checksums rather than modification times, so `lwarpmk again` will not trigger a recompile, but *latexmk* has a much better awareness of changes than the *lwarpmk* utility does and it is likely to correctly know when to recompile. A recompile may be forced by making a small change to the source, and a single recompile may be forced with:

forced single-pass recompile

Enter ⇒ **`lwarpmk print1`**

and/or

Enter ⇒ **`lwarpmk html1`**

## 5.9 Using XeLaTeX or LuaLaTeX

XeLaTeX or LuaLaTeX may be used instead of LaTeX.

1. Remove the auxiliary files for the project:

   Enter ⇒ **`lwarpmk cleanall`**

2. Use *xelatex* or *lualatex* to compile the printed version a single time.

   Enter ⇒ **`xelatex tutorial.tex`**

   — *or* —

   Enter ⇒ **`lualatex tutorial.tex`**

   When the compile occurs, the configuration files for *lwarpmk* are modified to remember which TeX engine was used. XeLaTeX or LuaLaTeX will be used for future runs of *lwarpmk*.

3. To recompile the document:

   Enter ⇒ **`lwarpmk print`**

   -and-

   Enter ⇒ **`lwarpmk html`**

4. Also remember to update the indexes and recompile again:

   Enter ⇒ **`lwarpmk htmlindex`**

   Enter ⇒ **`lwarpmk html`**

   Enter ⇒ **`lwarpmk printindex`**

   Enter ⇒ **`lwarpmk print`**

## 5.10 Using DVI LaTeX

Traditional DVI LaTeX may also be used along with `.eps` image files. An SVG version of each image must also be provided. *lwarpmk* may be used to convert image formats.

To convert EPS files to PDF:

Enter ⇒ **`lwarpmk epstopdf *.eps`** **(or a list of files)**

To convert PDF files to SVG:

Enter ⇒ **`lwarpmk pdftosvg *.pdf`** **(or a list of files)**

⚠ bitmapped fonts See section 7.4 regarding font selection to avoid the use of bitmapped fonts.

## 5.11 Using a glossary

lwarp supports the gloss and glossaries packages, although this tutorial does not supply an example.

### 5.11.1 gloss package

See section 8.6.11.

### 5.11.2 glossaries package

To process the glossary for the print version:

Enter ⇒ **`lwarpmk printglossary`**

⚠ (If **`makeglossaries`** is not found, see section 8.6.12.)

To process the glossary for the HTML version:

Enter ⇒ **`lwarpmk htmlglossary`**

In each case, the document will have to be recompiled afterwards:

Enter ⇒ **`lwarpmk html1`**

Enter ⇒ **`lwarpmk html`**

Enter ⇒ **`lwarpmk print1`**

Enter ⇒ **`lwarpmk print`**

See section 8.6.12 to set options for processing glossaries.

## 5.12 Cleaning auxiliary files

To remove the auxiliary files `.aux`, `.toc`, `.lof`, `.lot`, `.idx`, `.ind`, `.log`, and `.gl*`, and a few others:

Enter ⇒ **`lwarpmk clean`**

## 5.13 Cleaning auxiliary and output files

To remove the auxiliary files, and also remove the `.pdf` and `.html` files:

Enter ⇒ **`lwarpmk cleanall`**

## 5.14 Cleaning the images from the <project>-images directory

The `<project>-images` directory contains SVG images automatically generated for inline and display math, tikz, etc. To remove all the images from the `<project>-images` directory:

Enter ⇒ **`lwarpmk cleanlimages`**

## 5.15 Converting PDF or EPS images to SVG

HTML cannot display PDF or EPS images, so any external PDF graphics images must be converted to SVG format. *pdftocairo* and *epstopdf* may be used one image at a time, but *lwarpmk* also provides a way to convert PDF or EPS images in bulk:

Enter ⇒ **`lwarpmk epstopdf *.eps`** **(or a list of files)**

Enter ⇒ **`lwarpmk pdftosvg *.pdf`** **(or a list of files)**

Be sure to always provide SVG files for HTML output.

## 5.16 Creating HTML from an incomplete compile

During testing it may be useful to finish the HTML conversion even when the document had errors and did not compile successfully. To attempt an HTML conversion of an incomplete document:

Enter ⇒ **`lwarpmk pdftohtml [-p project]`**

## 5.17 Processing multiple projects in the same directory

⚠ xr, xr-hyper, xcite

It is possible to have several projects in the same directory. *lwarpmk* has an optional parameter which is the document to compile.

To create each project:

Enter ⇒ **pdflatex project_a**

Enter ⇒ **pdflatex project_b**

Each project is given its own configuration file:

`project_a.lwarpmkconf, project_b.lwarpmkconf`

To compile each project with `lwarkmk`:

Enter ⇒ **lwarpmk print -p project_a**

Enter ⇒ **lwarpmk print -p project_b**

Enter ⇒ **lwarpmk html -p project_a**

Enter ⇒ **lwarpmk html -p project_b**

To generate each project's images:

Enter ⇒ **lwarpmk limages -p project_a**

Enter ⇒ **lwarpmk limages -p project_b**

To clean each project's images:

Enter ⇒ **lwarpmk cleanlimages -p project_a**

Enter ⇒ **lwarpmk cleanlimages -p project_b**

To clean each project's auxiliary files:

Enter ⇒ **lwarpmk cleanall -p project_a**

Enter ⇒ **lwarpmk cleanall -p project_b**

If using *bibtex*, for example, the HTML version must also be processed:

Enter ⇒ **bibtex project_a_html**

## 5.18 Using the *make* utility

*lwarpmk* has an action which may be useful for integration with the common *make* utility:

`lwarpmk pdftohtml [-p project]`

*make* may be used to compile the code to PDF with HTML tags (`project_html.pdf`), then *lwarpmk* may be used to convert each target to HTML files.

## 5.19 What next?

**How do I do something?** See the General Index.

**Something do not work!** See the Troubleshooting Index or section 13: Troubleshooting.

**Package options:** See section 29, Package options.

**HTML and filename settings:** See section 7.6, Customizing the HTML output.

**Footnote placement:** See section 7.6, Customizing the HTML output.

**Title page, indexing, glossaries:** See section 8.6, Front and back matter.

**Shell escape:** See section 7.3, Shell escape.

**CSS customization:** See section 7.7, Customizing the CSS.

**MathJax customization:** See section 8.7.5, Customizing MathJax.

**Localization:** (languages) — See section 7.1, Localization.

**Accessibility:** (`alt` and `title` tags) — See section 7.2, Accessibility.

**Converting an existing document:** See section 6, Converting an existing document.

**EPUB conversion:** See section 10, EPUB conversion.

**Word processor conversion:** See section 11, Word-processor conversion.

# 6 Converting an existing document

To convert an existing document for use with lwarp:

1. Arrange the document in the following order:
   (a) Declare the `\documentclass`.
   (b) Load text fonts.
   (c) Load inputenc or inputenx, fontenc, or fontspec.
   (d) Load lwarp.
   (e) Load remaining packages.
2. Modify the document:

⚠ math in section names

   (a) If using named HTML files, in section names use paren math `\(x+y\)` instead of dollar math `$x+y$`. (Dollar math works, but appears in the filename.) Or, use a short name for the TOC entry without the math, or use `\texorpdfstring` from the hyperref package:

```
\section{Some math \texorpdfstring{$1+2=3$}{three}}
```

⚠ `scale`

   (b) Avoid using the `\includegraphics` `scale` option. Change:

```
\includegraphics[scale=<xx>]{ . . . }
```

   to:

```
\includegraphics[width=<yy>\linewidth]{ . . . }
```

⚠ tabular

   (c) Possible changes to `tabular` environments include: `*` columns, multirow, longtable, supertabular, xtab, bigdelim. See section 8.10.1.

⚠ package options

   (d) If using braces in package options, such as with caption, see section 8.1.
   (e) Possible option clashes with memoir. See section 8.13.

⚠ indexes

   (f) If using indexes, see section 8.6.15.
   (g) If using many indexes, glossaries, `.aux` files, etc., see section 8.6.15 regarding morewrites. If morewrites is already used, be sure to add the setup with `allocate=10`.
   (h) Other changes as per Special cases and limitations, section 8.
3. Convert any PDF images to SVG. See section 8.8.
4. Manually compile the print version with *latex*, *pdflatex*, *lualatex*, or *xelatex*.
5. `lwarpmk print` to finish the print version.
6. `lwarpmk html` to create the HTML version.
7. `lwarpmk limages` to create the SVG images of any SVG math, `lateximage`, Ti*k*z, etc.

Need help?

See the General Index for "how-to", and the Troubleshooting Index if something doesn't work. A Troubleshooting section is also available. The Index of Objects contains automated entries for each package, macro, environment, counter, boolean, and other objects; individually and also sorted by category.

Table 5: Localization settings

**Object names:** LaTeX provides redefinable names for various objects, and lwarp adds a few more. Use `\renewcommand` to change these.

**`\abstractname`:** This macro is honored by lwarp.

**`\linkhomename`:** Displayed by the link to the homepage.

**`\linkpreviousname`:** Displayed by the link to the previous page

**`\linknextname`:** Displayed by the link to the next page.

**`\sidetocname`:** Displayed at the head of the sideTOC.

**HTML settings:** See table 8 and section 7.6 for details.

**`\HTMLLanguage`:** The language to declare for each web page.

**`\ImageAltText`, `\MathImageAltText`, `\PackageDiagramAltText`, `\AltTextOpen`, `\AltTextClose`:** The defaults used for HTML `alt` text for images. See section 7.2.

**`\CSSFilename`:** The name of the CSS file to use.

**`\MathJaxFilename`:** The name of the MathJax script to use.

**Package options:**

**`ImagesName` and `ImagesDirectory`:** These options control the filenames used by lwarp when it automatically generates images. See table 7 and section 7.5.

**`xindyStyle`, `xindyLanguage`, `xindyCodepage`:** When using *xindy*, these options may be set according to local use. See section 8.6.21.

**`pdftotextEnc`:** To adjust the encoding of *pdftotext*.

# 7 Additional details

## 7.1 Localization

Regional localization is supported by lwarp via the package options and macros shown in table 5.

## 7.2 Accessibility

lwarp provides several methods for improving access to the document using tools such as text-only browsers, copy/paste, text-to-speech readers, or Braille readers. HTML provides the `alt` text attribute for images, which is used by lwarp as describe below. HTML also provides the `title` attribute, which usually generates a pop-up text. lwarp can add this to a reference or hyperlink. MathJax also has provisions for improved accessibility as well. See table 6.

Table 6: Accessibiltiy settings

**\ImageAltText:** The default HTML `alt` text for `\includegraphics` and `lateximages`. Set with `\renewcommand`.

**\includegraphics alt key:** For `\includegraphics`, lwarp adds the `alt` key/value. For example:

```
\includegraphics[alt={Some text.}]{filename}
```

**SVG math:** For simple SVG math, lwarp places the LaTeX math expression in the `alt` text, so that the LaTeX expression may be copied and pasted to another document as plain text.

**\MathImageAltText:** For complicated SVG math, such as enclosed in `\InlineMathOther`/`\InlineMathNormal`, or `\DisplayMathOther`/`\DisplayMathNormal`, the HTML `alt` text will be set to `\MathImageAltText`. Set with `\renewcommand`.

**MathJax:** For MathJax, the accessibility tools provided by MathJax are enabled by default by lwarp's MathJax scripts.

**\PackageDiagramAltText:** Various packages create diagrams which lwarp converts into SVG images. These are given `alt` text set to `\PackageDiagramAltText`. Set with `\renewcommand`.

**\ThisAltText:** The HTML `alt` text of the next image may be set with:

```
\ThisAltText{Custom text about the image.}
<SVG math, Tikz, picture, etc.>
```

The next single image will be generated with the given text, and the following images will revert to back to their defaults.

`\ThisAltText` may also be used to assign an HTML `title` to the next reference or hyperlink.

```
\ThisAltText{Custom text about the link.}
Text ... \ref{label_name} ... text.
```

See section 7.6.

**\AltTextOpen and \AltTextClose:** By default, HTML `alt` text is enclosed by parentheses. This may be changed by redefining `\AltTextOpen` and `\AltTextClose`. Set with `\renewcommand`.

## 7.3 Shell escape

Opt --shell-escape

Some documents require the use of an external program, which is allowed when using the `--shell-escape` command-line option. When the document is first compiled manually, and also whenever the print version is recompiled, lwarp detects and remembers whether shell escape is enabled. If so, it will also be enabled when the document is recompiled with *lwarpmk*.

## 7.4 Font and UTF-8 support

⚠ type 3 bitmapped fonts

lwarp uses *pdftotext* to convert PDF output into UTF-8-encoded text. This process requires that UTF-8 information be embedded in the PDF file, which may prevent the use of older "type 3" bit-mapped fonts, and of older packages such as ae. The lwarp option `pdftotextEnc` may be useful in some situations. See section 7.5.

vector fonts
Computer Modern
⚠ *pdflatex*
⚠ DVI *latex*
Pkg cm-super

While using DVI *latex* or PDF *pdflatex*, if no font-related package is specified then the default Computer Modern font is used, which may be a "type 3" bit-mapped font which may not convert well to plain text. A "type 1" vector font is required.

To use the updated cm-super's type 1 fonts instead of Computer Modern, install the cm-super font package.

Pkg lmodern

To use Latin Modern instead, add

```
usepackage{lmodern}
```

to the preamble.

Pkg dejavu

Another useful option is the Deja Vu series of fonts, which have an increased coverage of language and glyphs:

```
\usepackage{dejavu}
```

*latex*, *pdflatex*, T1, UTF8

While using DVI *latex* or PDF *pdflatex*, lwarp automatically loads fontenc with T1 encoding. fontenc may be loaded with an additional encoding after lwarp. inputenc is automatically loaded with UTF8 encoding if if has not yet been loaded, but may also be specified with another encoding such as `latin1`. See the next section regarding index encoding.

⚠ *xelatex*, *lualatex*, fontspec

XeLaTeX and LuaLaTeX users must use the fontspec package. Do NOT use fontenc!

Place fontspec or fontenc, xunicode, and other font and UTF-8 related commands after the `\documentclass` command and before `\usepackage{lwarp}`.

⚠ package conflicts

In some cases, a package conflict may require that a font package be loaded after lwarp, which should work as well:

1. `documentclass{article/book/report}` comes first, followed by any of:
2. Font and UTF-8 related commands:
   - For XeLaTeX or LuaLaTeX:
     - fontspec and font choices

Pkg fontspec

ligatures

lwarp sets the following to turn off TeX ligatures during the generation

of HTML tags, and turn off common ligatures in regular text, since older browsers may not display them correctly and newer browsers can automatically re-create them.

```
\defaultfontfeatures[\rmfamily]{Ligatures={NoCommon,TeX}}
\defaultfontfeatures[\sffamily]{Ligatures={NoCommon,TeX}}
\defaultfontfeatures[\ttfamily]{Ligatures=NoCommon}
```

- For *pdflatex*:

Pkg lmodern
Pkg fontenc
Pkg inputenc
Pkg inputenx
Pkg newunicodechar
File glyphtounicode.tex

(a) `\usepackage{lmodern}`, or other font-related packages
(b) `\usepackage[T1]{fontenc}`
(c) `\usepackage[utf8]{inputenc}`, or `latin1`, etc. Or use inputenx.
(d) `\usepackage{newunicodechar}` along with related definitions.
(e) To assist with the PDF-HTML conversion:
   i. `\input glyphtounicode.tex`
   ii. `\input glyphtounicode-cmr.tex% from the pdfx package`
   iii. `\pdfgentounicode=1`

⚠ dotless j

Pkg cmap
Pkg mmap

(f) Another option to assist with the PDF-HTML conversion, such as the dotless j (`\j`):
   – `\usepackage{cmap}` — *or* —
   – `\usepackage{mmap}` — *or* —
   – `\usepackage[noTeX]{mmap}`

Pkg textcomp

(g) `\usepackage{textcomp}`

3. `\usepackage{newtxmath}` or other math-related font packages. Many of these load amsmath, which may now be loaded before lwarp.

4. `\usepackage{lwarp}` (section 7.5) is placed after any of the above, followed by:

⚠ fontspec with monospaced fonts

5. `\setmonofont{TeX Gyre Cursor}` or similar may be required if using XeLaTeX or LuaLaTeX and fontspec along with traditional font packages such as txfonts, newtxtext, etc. This is required to turn off the monospaced font's ligatures with fontspec after loading the traditional font packages. Monospaced output ligatures must be turned off to produce the correct HTML characters.

   Any monospace font with built-in ligatures may require these ligatures to be disabled for HTML. In one example, JetBrain Mono, it is required to use

⚠ JetBrain Mono
⚠ HTML corrupted

```
\setmonofont{JetBrains Mono}[%
. . .
Contextuals=AlternateOff,
]
```

   After lwarp is loaded, the ligature may be re-enabled for print mode by using `\setmonofont` again inside a `warpprint` environment.

6. … the rest of the preamble and the main document.

⚠ UTF-8 locale

In some cases, an external program may require a UTF-8 "locale". See section 9.8.

### 7.4.1 Indexes, glossaries, and encoding

lwarp supports *makeindex*, *xindy*, *xindex*, and glossaries, gloss, and nomencl.

See section 8.6.14 for indexing, and section 8.6.12 for the glossaries package.

## 7.5 lwarp package loading and options

lwarp supports book, report, and article classes, as well as the equivalent Koma-script classes and memoir, and various CJK-related classes and packages.

Load the lwarp package immediately after the font and UTF-8 setup commands.

Package options may be set while loading lwarp, or later with

```
\lwarpsetup{⟨key=value, . . . ⟩}
```

Pkg lwarp

lwarp package options are as follows:

Opt mathsvg
Opt mathjax
Default: mathsvg

**mathsvg** and **mathjax:** Selects SVG images or MathJax for math display. See section 8.7.

Opt latexmk
Default: false

**latexmk:** Tells *lwarpmk* to use *latexmk* to recompile the document several times if necessary. Otherwise, *lwarpmk* attempts to determing for itself whether to recompile. See section 7.6.

Opt dvips
Default: false

**dvips:** Tells *lwarpmk* to use *dvips* and *ps2pdf* to convert DVI output to PDF.

Opt dvipdfm
Default: false

**dvipdfm:** Tells *lwarpmk* to use *dvipdfm* to convert DVI output to PDF.

Opt dvipdfmx
Default: false

**dvipdfmx:** Tells *lwarpmk* to use *dvipdfmx* to convert DVI output to PDF.

Opt HomeHTMLFilename
Default: \BaseJobname

**HomeHTMLFilename:**

Filename of the homepage, without the "`.html`" suffix. Defaults to the `\BaseJobname`. A common setting is:

```
HomeHTMLFilename=index
```

filename underscores

causing the homepage to be the file `index.html`. Underscores are allowed in `HomeHTMLFilename` and `HTMLFilename` options, but may need to be escaped elsewhere, such as when appearing in a list:

```
\item [\href{file\_name.pdf}{text}] \
```

See section 7.6.1 for examples of naming and numbering HTML files.

Opt HTMLFilename
Default: <empty>

**HTMLFilename:** A filename prefix for the rest of the HTML web pages. Useful for numbered web pages with a common prefix. May be empty. See section 7.6.1 for examples of naming and numbering HTML files.

Opt ImagesName
Default: image-

**ImagesName:** The prefix for the images automatically generated by lwarp for objects such as SVG math and `lateximages`.

Opt ImagesDirectory
Default: \jobname-images

**ImagesDirectory:** The directory for the images automatically generated by lwarp for objects such as SVG math and `lateximages`. By default, these images will appear in a

Table 7: Lwarp package options

| Option | Description |
|---|---|
| mathsvg | Show math using SVG images. |
| mathjax | Show math using MathJax. |
| latexmk | Use *latexmk* for compiling documents. |
| dvips | Use *dvips* and *ps2pdf* to convert DVI documents. |
| dvipdfm | Use *dvipdfm* to convert DVI documents. |
| dvipdfmx | Use *dvipdfmx* to convert DVI documents. |
| HomeHTMLFilename | The filename of the home page. |
| HTMLFilename | A prefix for the filenames of the remaining web pages. |
| ImagesName | A prefix for the filenames of generated images. |
| ImagesDirectory | The directory used to hold generated images. |
| PrintLatexCmd | The shell commands for **lwarpmk print**. |
| HTMLLatexCmd | The shell commands for **lwarpmk html**. |
| For indexing (section 8.6.15) and glossaries (section 8.6.12): | |
| makeindex | Use *makeindex* to generate indices. |
| makeindexStyle | Set a custom style for *makeindex*. |
| xindy | Use *xindy* to generate indices. |
| xindyStyle | Set a custom style for *xindy*. |
| xindyLanguage | The *xindy* language option used for index generation. |
| xindyCodepage | The *xindy* codepage option used for index generation. |
| xindex | Use *xindex* to generate indices. |
| xindexConfig | Set a custom configuration file for *xindex*. |
| PrintIndexCmd | Shell commands executed by **lwarpmk printindex**. |
| HTMLIndexCmd | Shell commands executed by **lwarpmk htmlindex**. |
| LatexmkIndexCmd | Shell commands executed by *latexmk*. |
| IndexRef | How to format index links. |
| GlossaryCmd | Shell command executed by **lwarpmk printglossary** and **lwarpmk htmlglossary**. |
| Seldom necessary: | |
| OSWindows | Force compatibility with MS-Windows. |
| pdftotextEnc | Set the encoding for *pdftotext*. |
| lwarpmk | Generate a local copy of `lwarpmk.lua`. |
| Used internally by lwarp: | |
| warpprint | Generate print output, and also generate configuration files. |
| warpHTML | Generate HTML output. |
| BaseJobname | The `\jobname` to use. Set to the `\jobname` of the printed version even while generating HTML. |

directory named `<jobname>-images`, and the images will be named and numbered `image-<nn>`.

Opt `PrintLatexCmd` Default: `<automatic>`

**`PrintLatexCmd:`** Sets the shell commands executed by **`lwarpmk print`**. If not specified, will automatically be set according to the detected LaTeX engine and the use of `--shell-escape`.

Opt `HTMLLatexCmd` Default: `<automatic>`

**`HTMLLatexCmd:`** Sets the shell commands executed by **`lwarpmk html`**. If not specified, will automatically be set according to the detected LaTeX engine and the use of `--shell-escape`.

Opt `makeindex` Default: `makeindex`

**`makeindex:`** Sets `PrintIndexCmd`, `HTMLIndexCmd`, and `LatexmkImageCmd` to use *makeindex* when generating indexes with **`lwarpmk printindex`**, **`lwarpmk htmlindex`**, or *latexmk*. If neither `makeindex` nor `xindy` is used, `makeindex` is assumed.

Opt `makeindexStyle` Default: `lwarp.ist`

**`makeindexStyle:`** If you wish to use a custom `.ist` file for index generation, see section 8.6.20.

Opt `xindy` Default: `makeindex`

**`xindy:`** Sets `PrintIndexCmd`, `HTMLIndexCmd`, and `LatexmkImageCmd` to use *xindy* when generating indexes with **`lwarpmk printindex`**, **`lwarpmk htmlindex`**, or *latexmk*.

Opt `xindyStyle` Default: `lwarp.xdy`

**`xindyStyle:`** If you wish to use a custom `.xdy` file for index generation, see section 8.6.21.

Opt `xindyLanguage` Default: `english`

**`xindyLanguage:`** If using an index or glossary, see section 29.

Opt `xindyCodepage` Default: `utf8`

**`xindyCodepage:`** If using an index, see section 29.

Opt `xindex` Default: `makeindex`

**`xindex:`** Sets `PrintIndexCmd`, `HTMLIndexCmd`, and `LatexmkImageCmd` to use *xindex* when generating indexes with **`lwarpmk printindex`**, **`lwarpmk htmlindex`**, or *latexmk*.

Opt `xindexConfig` Default: `<empty>`

**`xindexConfig:`** If you wish to use a custom `xindex-*.lua` file for index generation, see section 8.6.22.

Opt `PrintIndexCmd` Default: `<automatic>`

**`PrintIndexCmd:`** Sets the shell commands executed by **`lwarpmk printindex`**. If not specified, will be set by the selection of `makeindex` or `xindy`. May be used to specify the creation of multiple indexes. See section 8.6.15.

Examples:

```
makeindex -s lwarp.ist projectname.idx                (makeindex)
xindy -M lwarp.xdy -L english -C utf8 projectname.idx      (xindy)
```

automatic setting

The use of the `makeindex` or `xindy` options sets `PrintIndexCmd` to sensible values for each of those programs while compiling a single index. lwarp's `makeindexStyle`, `xindyStyle`, `xindyLanuage`, and `xindyCodepage` options will be used if specified.

⚠ xindy

If specifying `PrintIndexCmd` manually, be sure to assign an *xindy* language and

codepage with the `-L` and `-C` *xindy* options, as the lwarp `xindyLanguage` and `xindyCodepage` options are not used for the `PrintIndexCmd` option when it is set manually.

This option is stored in the configuration files `lwarpmk.conf` and `*.lwarpmkconf`, and is then passed by the **`lwarpmk printindex`** command to the operating system to compile the print indexes. Since the command string is parsed by TEX, written to a file, read from the file by LuaTEX, and finally passed to the operating system, any attempt at quoting will be problematic. For complicated commands, it would be best to create a shell script, and simply refer to the script with the lwarp `PrintIndexCmd` option.

Opt `HTMLIndexCmd`
Default: `<automatic>`

**`HTMLIndexCmd:`** Sets the shell commands executed by **`lwarpmk htmlindex`**. If not specified, will be set by the selection of `makeindex` or `xindy`. May be used to specify the creation of multiple indexes. See section 8.6.15.

⚠ filenames

Example settings are similar to `PrintIndexCmd`, but append `_html` to the filenames:

```
makeindex -s lwarp.ist projectname_html.idx            (makeindex)
xindy -M lwarp.xdy -L english -C utf8 projectname_html.idx  (xindy)
```

automatic setting

The use of the `makeindex` or `xindy` options sets `HTMLIndexCmd` to sensible values for each of those programs while compiling a single index. lwarp's `makeindexStyle`, `xindyStyle`, `xindyLanuage`, and `xindyCodepage` options will be used if specified.

⚠ xindy

If specifying `HTMLIndexCmd` manually, be sure to assign an *xindy* language and codepage with the `-L` and `-C` *xindy* options, as the lwarp `xindyLanguage` and `xindyCodepage` options are not used for the `HTMLIndexCmd` option when it is set manually.

As with `PrintIndexCmd`, to generate complicated indexes it may be worthwhile to use a shell script, then refer to that script with `HTMLIndexCmd`.

Opt `LatexmkIndexCmd`
Default: `<automatic>`

**`LatexmkIndexCmd:`** Sets the shell commands executed by *latexmk*. Unlike `PrintIndexCmd` and `HTMLIndexCmd`, `LatexmkIndexCmd` does not include any filenames, which will be provided instead by *latexmk*. See section 8.6.15.

Example settings are similar to `PrintIndexCmd`, but without a filename:

```
makeindex -s lwarp.ist                                 (makeindex)
xindy -M lwarp.xdy -L english -C utf8                      (xindy)
```

automatic setting

The use of the `makeindex` or `xindy` options sets `LatexmkIndexCmd` to either of the two settings show above. lwarp's `makeindexStyle`, `xindyStyle`, `xindyLanuage`, and `xindyCodepage` options will be used if specified. Unlike `PrintIndexCmd` and `HTMLIndexCmd`, *latexmk* uses either of the single-line settings of `LatexmkIndexCmd` shown above to compile each of multiple indexes if necessary.

⚠ xindy

If specifying `LatexmkIndexCmd` manually, be sure to assign an *xindy* language and codepage with the `-L` and `-C` *xindy* options, as the lwarp `xindyLanguage` and `xindyCodepage` options are not used for the `LatexmkIndexCmd` option when it is set manually.

Opt `IndexRef`
Default: `cref`

**`IndexRef:`** Describes how to display the index entries for HTML output. Possible values are `ref`, `nameref`, `refnameref`, `cref`, `crefnameref`, `autoref`, or a text string such

as (link) or (*) for each index entry reference. (Adding parentheses around a single character makes the link larger and easier to click on.) The default is cref, which is available even if the print document does not use cleveref, as the lwarp package relies on cleveref during HTML output. Option autoref gives the same results as cref.

\ref and \cref to starred or otherwise unknown links will display as (*) instead of ??.

⚠ ?? If using cref (the default), and if a reference appears as ?? with a non-functional link, use cleveref's \crefname to give a name to that type of label.

In general, crefnameref gives the most information, but the index can become quite verbose. Using (*) or similar yields a very compact index.

Opt GlossaryCmd
Default: **makeglossaries**

**GlossaryCmd:** Sets the shell command executed by **lwarpmk printglossary** and **lwarpmk htmlglossary**. The print or HTML glossary filename is appended to this command. See section 8.6.12.

Opt OSWindows

**OSWindows:** lwarp attempts to automatically sense WINDOWS, but it may be forced with this option. See section 7.9.

Opt pdftotextEnc
Default: UTF-8

**pdftotextEnc:** Used to specify the encoding used by *pdftotext* during the PDF-HTML conversion. In most situations, the default is the correct choice.

Opt lwarpmk

**lwarpmk:** If you wish to have lwarp generate a local copy of lwarpmk.lua for archival or local-installation purposes, compile the print version with the lwarpmk option set. See section 29.

---

The following options are used internally by lwarp, and usually are not used in the user's document:

---

Opt warpprint
Opt warpHTML

**warpprint** and **warpHTML:** Usually controlled by *lwarpmk*, and not set in the document. Select the warpprint option to generate print output (default), or the warpHTML option to generate HTML5 output. The default is print output, so the print version may be compiled with the usual *pdflatex*, etc. When lwarp is loaded in print mode, it creates <project>_html.tex, which sets the warpHTML option before calling the user's source code <project>.tex. In this way, <project>.tex can \usepackage{lwarp} without any options to create a printed version, while <project>_html.tex will create an HTML version.

Opt BaseJobname
Default: \jobname

**BaseJobname:** Not intended for the user. Used internally by lwarp when creating the *_html.tex file used to compile the HTML version. See section 29.

## 7.6 Customizing the HTML output

Table 8 shows several settings may be used to customize the HTML output. Watch for the correct placement of each!

⚠ Placement!

⚠ Changes! Note that if changes are made, it is best to first:

1. Clear all the HTML, PDF, and auxiliary files:
   Enter ⇒ **`lwarpmk clearall`**
2. Recompile the print version in order to recreate the configuration files for *lwarpmk*:
   Enter ⇒ **`lwarpmk print`**
3. Finally, recompile the HTML version with the new settings:
   Enter ⇒ **`lwarpmk html`**

**Placed in the preamble before `\begin{document}`:**

`\HTMLFirstPageTop` Default: `<empty>`

**`\HTMLFirstPageTop`:** {⟨*contents*⟩} A user-definable custom action applied to the top of the home page. Useful for logos, etc. `\LinkNext` may be used to link to the next web page. Defaults empty. Ignored in print output.

`\HTMLFirstPageBottom` Default: `<empty>`

**`\HTMLFirstPageBottom`:** {⟨*contents*⟩} A user-definable custom action applied to the bottom of the home page. Useful for logos, etc. `\LinkNext` may be used to link to the next web page. Defaults empty. Ignored in print output.

`\linkhomename` Default: `Home`

**`\linkhomename`:** Name of the link to the home page. Paragraphs are allowed. Redefine with `\renewcommand`.

`\linkpreviousname` Default: `Previous`

**`\linkpreviousname`:** Name of the link to the previous page. Paragraphs are allowed. Redefine with `\renewcommand`.

`\linknextname` Default: `Next`

**`\linknextname`:** Name of the link to the next page. Paragraphs are allowed. Redefine with `\renewcommand`.

Ctr `tocdepth`

**`tocdepth`:** Sectioning depth of the table of contents. See section 16 for a list of LaTeX stack depths.

Ctr `SideTOCDepth` Default: 1

**`SideTOCDepth`:** Sectioning depth of the sideTOC. Defaults to 1, causing the sideTOC to show sections but not subsections.

sideTOC

Each subpage of the website has its own small table of contents on the side (the "sideTOC"). Its depth is set by `SideTOCDepth`. This sideTOC is only shown if the browser display is wide enough. When using a narrow web browser window, "responsive web design" is used to show the sideTOC at the top of the page, as well as a link back to Home at the top and bottom.

It is recommended to set:

```
SideTOCDepth=FileDepth
```

or

```
SideTOCDepth=FileDepth+1
```

Table 8: HTML settings

| Macro/Cntr/Bool | Loc* | Description |
|---|---|---|
| \linkhomename | P | Name of the link to the homepage. |
| \linkpreviousname | P | Name of the link to the previous page. |
| \linknextname | P | Name of the link to the next page. |
| SideTOCDepth | P | Sectioning depth of the sideTOC. |
| \sidetocname | P | Name of the sideTOC. |
| FileDepth | P | Sectioning depth of the file splits. |
| CombineHigherDepths | P | Combine higher section levels. |
| FileSectionNames | P | Use section names for file names, else use numbers. |
| \FilenameLimit | P | Maximum length of the generated filenames. |
| FootnoteDepth | P | Sectioning depth of footnotes. |
| \abstractname | P | The name of the abstract. |
| \ImageAltText | PD | \includegraphics and other images' alt tag. |
| \ThisAltText {⟨text⟩} | PD | Assigns an alt/title tag for the next image or link. |
| \MathImageAltText | PD | The SVG math image lateximage alt tag. |
| \PackageDiagramAltText | PD | The suffix for a package's lateximage alt tags. |
| \AltTextOpen | PD | Start an HTML alt tag. |
| \AltTextClose | PD | End an HTML alt tag. |
| \CSSFilename | PS | The CSS for the following files. |
| \MathJaxFilename | PS | The MathJax script for the following files. |
| \HTMLLanguage | PS | The HTML lang tag. |
| \HTMLTitle | PS | The homepage's <title>, overriding \title. |
| \HTMLTitleBeforeSection | PS | Set subpage <title>s to \HTMLTitle - sectionname |
| \HTMLTitleAfterSection | PS | Set subpage <title>s to sectionname - \HTMLTitle |
| \HTMLAuthor | PS | The HTML author meta tag, overriding \author. |
| \HTMLDescription | PS | The HTML description meta tag. |
| \HTMLFirstPageTop | P | Heading for the home page. |
| \HTMLFirstPageBottom | P | Footer for the home page. |
| \HTMLPageTop | PS | Heading for the other pages. |
| \HTMLPageBottom | PS | Footer for the other pages. |
| \IndexPageSeparator | P | Index page list separator. |
| \IndexRangeSeparator | P | Index page range separator. |
| FixSmallCaps | P | Set true if small caps rendered as all caps. |
| HTMLDebugComments | P | Boolean to generate HTML comments. |

* **P:** Preamble, **D:** Anywhere in the document. **S:** Before a section.

⚠ inaccessible pages

If SideTOCDepth < FileDepth, web pages will be inaccessible via the sideTOC.

\sidetocname
Default: Contents

**\sidetocname:** Name of the sideTOC. Paragraphs are allowed. Redefine with \renewcommand.

Ctr FileDepth
Default: -5

**FileDepth:** Sectioning depth of file splits. Defaults to -5, causing the entire HTML website to be one single file.

- To place the entire file into one HTML page, use:
  \setcounter{FileDepth}{-5}
- To split the HTML file at \section depth, use:
  \setcounter{FileDepth}{1}
- To ensure that the HTML pages/files are accessible:
  Place a \tableofcontents somewhere before the first section break (therefore in the "home page"), and set
  tocdepth >= FileDepth

⚠

Bool CombineHigherDepths
Default: true

**CombineHigherDepths:** Combine a higher section with its first lower subsections, down to the FileDepth. Defaults to true. Set to false to simulate the concept of a chapter opening on its own page, for example.

The file splits are controlled by the counter FileDepth and the boolean CombineHigherDepths. Setting FileDepth to 0 splits the file at chapters, 1 at sections, etc. CombineHigherDepths controls whether to combine pages at levels higher than the chosen FileDepth, such as in this tutorial where the page which opens the chapter also contains the first section. Be careful to set tocdepth and SideTOCDepth to allow access to each page of the website. Set tocdepth and SideTOCDepth to be greater than or equal to FileDepth.

⚠ Inaccesible pages!

⚠ Lost in an old page!

When making changes to the file structure, it is possible to end up with the web browser pointing to an old file which is no longer in use. When this occurs, changes to the web site will not appear in the browser, even if reloading the page, because that page is no longer in use. It is best to return to the home page, clean the files (lwarpmk cleanall), change FileDepth and/or CombineHigherDepths, then finally recompile and renavigate to the desired page using the new file structure.

Bool FileSectionNames
Default: true

**FileSectionNames:** If true, web page filenames are derived from a sanitized version of the section names. If false, web pages are numbered. Either way, the HTMLFilename option is used as a prefix. See section 7.6.1 for examples of naming and numbering HTML files. The user must ensure that filenames are unique after begin sanitized. For example, math in the section name is removed before creating the filename, so the rest of the filename must be sufficiently unique to avoid name collisions.

⚠ Unique filename!

\FilenameLimit
Default: 80

**\FilenameLimit:** The maximum length of the filenames generated by lwarp. ".html" is added to this length. Redefine with \renewcommand.

Ctr FootnoteDepth
Default: 3

**FootnoteDepth:** Determines where to place pending footnotes. 3 places footnotes before each break down to the \subsubsection level. 1 places footnotes before each \section break. Any pending footnotes are also placed at the bottom of each page before each file break.

Bool FixSmallCaps
Default: false

**FixSmallCaps:** Set true if Small Caps are rendering in all caps ("SMALL CAPS").

May be required for some fonts (erewhon, utopia, fbb, et al.), and packages such as embrac.

Bool HTMLDebugComments
Default: false

**HTMLDebugComments:** Set true to generate HTML comments, such as which section or  is being opened or closed.

\abstractname
Default: Abstract

**\abstractname:** The name of the abstract. This may also be over-written by the babel package. Defaults to "Abstract". Redefine with \renewcommand.

\IndexPageSeparator
Default: ", "

**\IndexPageSeparator:** Index page list separator. Adjust to match index style file. If using gindex, this is set automatically to gindex's \indexpagessep.

\IndexRangeSeparator
Default: "--"

**\IndexRangeSeparator:** Index page range separator. Adjust to match index style file. If using gindex, this is set automatically to gindex's \indexrangesep.

**Placed before \begin{document}, or before any sectioning command which causes a file break:**

\CSSFilename
Default: lwarp.css

**\CSSFilename:** {⟨*filename.css*⟩} Sets the CSS file to use for the following files. May be changed before each each sectioning command which would cause a file split.

The CSS styles of the web pages are set by the \CSSFilename command. If \CSSFilename is not used, a default plain style is used to mimic printed LaTeX output. lwarp_sagebrush.css is a semi-fancy colored style as shown in this tutorial. Change it to lwarp_formal.css for a more formal look, or comment out the \CSSFilename command to see the default. \CSSFilename may be used before each file break to set the CSS for individual pagess of the website.

\MathJaxFilename
Default: lwarp_mathjax.txt

**\MathJaxFilename:** {⟨*filename*⟩} Sets the MathJax script file to use for the following files. May be changed before each each sectioning command which would cause a file split.

The MathJax script file is copied into the head of each HTML file. This may be used to point to a local repository, add extensions, or change the script somewhere in the middle of the document. \MathJaxFilename may be used before each file break to set the script file for individual pages of the website.

\HTMLLanguage
Default: en-US

**\HTMLLanguage:** {⟨*langauge*⟩} The HTML file's HTML lang meta tag. Defaults to en-US.

\HTMLTitle
Default: \thetitle

**\HTMLTitle:** {⟨*title*⟩} Overrides \title for the HTML header's meta title. Defaults to \thetitle, which is set by \title, or empty otherwise. Unlike the author, \thetitle is set by \title even if not using the titling package.

\HTMLTitleBeforeSection
Default: \HTMLTitleBeforeSection

**\HTMLTitleBeforeSection:** Sets subpage <title> tags to show the website title followed by the section name.

\HTMLTitleAfterSection

**\HTMLTitleAfterSection:** Sets subpage <title> tags to show the section name followed by the website title.

custom <title>

To customize subpage <title>s, redefine \theHTMLTitleSection, which defaults to:

```
\def\theHTMLTitleSection{%
  \theHTMLTitle\theHTMLTitleSeparator\theHTMLSection%
}
```

\HTMLAuthor
Default: \theauthor

**\HTMLAuthor:** {⟨*author*⟩} The HTML header's meta author. Defaults to \theauthor, which is set by \author if using the titling package, but is empty otherwise. There are several ways to represent the author and affiliations, especially if using the authblk package, most of which do not result in a sensible \theauthor, so \HTMLAuthor is useful to create a list of authors without their affiliations.

\HTMLDescription
Default: <empty>

**\HTMLDescription:** {⟨*description*⟩} Sets the HTML description tag for the following files. May be changed before each each sectioning command which would cause a file split.

\HTMLPageTop
Default: <empty>

**\HTMLPageTop:** {⟨*contents*⟩} A user-definable custom action applied to the top of pages other than the home page. Useful for logos, etc. Defaults empty. \LinkHome may be used to place a link back to the homepage, as well as \LinkPrevious and \LinkNext. Ignored in print output.

\HTMLPageBottom
Default: <empty>

**\HTMLPageBottom:** {⟨*contents*⟩} A user-definable custom action applied to the bottom of pages other than the home page. Useful for authors, copyright notices, contact information, etc. Defaults empty. \LinkHome may be used to place a link back to the homepage, as well as \LinkPrevious and \LinkNext. Ignored in print output.

\LinkHome

**\LinkHome:** Creates a link to the home page. Usually used in \HTMLPageTop and related.

\LinkPrevious

**\LinkPrevious:** Creates a link to the previous HTML page, unless already at the home page. Usually used in \HTMLPageTop and related.

\LinkNext

**\LinkNext:** Creates a link to the next HTML page, unless already at the end. Usually used in \HTMLPageTop and related.

**Placed in the home page before the first sectioning command which causes a file break:**

\tableofcontents
⚠ TOC on the homepage!

**\tableofcontents:** Used to place a table of contents on the home page. This command must be used before the first file split, so that a way is available to navigate to other files from the homepage.

Links to each chapter/section are provided, as selected by tocdepth.

**Placed in the document wherever necessary:**

\ImageAltText
Default: image

**\ImageAltText:** Redefine with \renewcommand. \includegraphics and other images are assigned an HTML alt tag according to \ImageAltText along with \AltTextOpen and \AltTextClose. This text is visible in the browser if images are not loaded, and appears when the text is copied and pasted. The default is "image", and it may be changed according to the document's language. This may be set in the preamble, or changed as necessary inside the document, where it will affect the following \includegraphics and other images.

\ThisAltText

**\ThisAltText:** {⟨*text*⟩} \ThisAltText can be used to assign an HTML alt text attribute to the next image generated by a lateximage, picture, tikzpicture, or any other similar environment which generates an image, or the next SVG math expression. This tag is cleared after use. The tag is also cleared after

each MathJax expression, in case the user changes between SVG math and MathJax.

`\ThisAltText` also may be used to add an HTML `title` to a reference or hyperlink, such as a `\ref`, `\cref`, `\href`, `\url`, `\hyperref`, or `\hyperlink`. In each case, the alternative text is cleared after use.

`\MathImageAltText` Default: `math image`

**`\MathImageAltText`:** Redefine with `\renewcommand`. When creating an SVG math image, its HTML `alt` tag may be set to the math expression, which may be hashed for image reuse. In the case of `\ensuremath` or after `\inlinemathother`, where the contents require a unique image for each instance of the same expression, the `alt` tag is set to `\MathImageAltText`, along with `\AltTextOpen` and `\AltTextClose`, and the image is not reused.

This `alt` expression is visible in the browser if images are not loaded, and appears when the text is copied and pasted. The default is "`math image`", and it may be changed according to the document's language. This may be set in the preamble, or changed as necessary inside the document, where it will affect the following SVG math images.

`\PackageDiagramAltText` Default: `diagram`

**`\PackageDiagramAltText`:** Redefine with `\renewcommand`. For many packages, the output is placed inside a `lateximage` with an HTML `alt` tag set to the package name followed by `\PackageDiagramAltText`. For example:

```
(-xy- diagram)
```

This expression is visible in the browser if images are not loaded, and appears when the text is copied and pasted. The default is "diagram", and may it be changed according to the document's language. This may be set in the preamble, or changed as necessary inside the document, where it will affect the following package diagrams.

`\AltTextOpen` Default: `(`

**`\AltTextOpen`:** Redefine with `\renewcommand`.

`\AltTextClose` Default: `)`

**`\AltTextClose`:** Redefine with `\renewcommand`. HTML `alt` text is enclosed by the macros `\AltTextOpen` and `\AltTextClose`, which default to an opening and closing parenthesis.

Env `warpprint`

**`warpprint`:** An environment which is only used while generating print output. Place inside anything which does not apply to HTML and which may cause problems with lwarp. If lwarp knows about and emulates or supports a package then its related macros, lengths, counters, etc. probably won't have to be placed inside a `warpprint` environment, but unknown packages may cause problems which may be isolated from lwarp using this environment.

⚠ *Do not place anything else on the same line as* `\end{warpprint}`. Also do not nest `warpprint` inside itself.

Env `warpHTML`

**`warpHTML`:** An environment which is only included while generating HTML output. This is useful for website logos and other items which have no purpose in printed output.

⚠ *Do not place anything else on the same line as* `\end{warpHTML}`. Also do not nest `warpHTML` inside itself.

`\warpprintonly`

**`\warpprintonly`:** {⟨*contents*⟩} A macro version of the `warpprint` environment.

\warpHTMLonly **\warpHTMLonly:** {⟨*contents*⟩} A macro version of the warpHTML environment.

### 7.6.1 Example HTML file naming

Examples of ways to name or number HTML files:

**Numbered HTML nodes:**

Example: Homepage index.html, and node-1, node-2. [13]

```
\usepackage[
    HomeHTMLFilename=index,
    HTMLFilename={node-}
]{lwarp}
\boolfalse{FileSectionNames}
```

**Named HTML sections, no prefix:**

Example: index.html, and About.html, Products.html

```
\usepackage[
    HomeHTMLFilename=index,
    HTMLFilename={}
]{lwarp}
\booltrue{FileSectionNames}
```

**Named HTML sections, with prefix:**

Example: Homepage mywebsite.html, and additional pages such as mywebsite-About.html, mywebsite-Products, etc.

```
\usepackage[
    HomeHTMLFilename=mywebsite,
    HTMLFilename={mywebsite-}
]{lwarp}
\booltrue{FileSectionNames}
```

## 7.7 Customizing the CSS

\CSSFilename {⟨*filename*⟩}
Default: lwarp.css

\CSSFilename may be used to choose which .css file is used to display each page of the web site. Use \CSSFilename before \begin{document} to assign the style of the home page. If different parts of the website should have different styles, call \CSSFilename again before each section heading which creates a new file. This may be changed numerous times throughout the file, resulting in different HTML pages having different CSS files assigned:

[13] See \SetHTMLFileNumber to number in groups by chapter, for example.

```
...
\CSSFilename{myCSS.css}
\chapter{Another Chapter}
...
```

The styles provided by lwarp include:

**lwarp.css:** A default style if \CSSFilename is not used. This style is comparable to a plain LaTeX document. To set this style, you may use \CSSFilename{lwarp.css}, or no \CSSFilename call at all.

**lwarp_formal.css:** A formal style with a serif fonts and a traditional look.

**lwarp_sagebrush.css:** A style with muted colors, gradient backgrounds, additional borders, and rounded corners.

To see each style in use, change the \CSSFilename entry in the tutorial, lwarpmk html again, and then reload the tutorial webpage.

Custom css

A customized style may also be created. For each new project a file called sample_project.css is generated. This may be renamed to <project>.css then used by assigning \CSSFilename{<project>.css}.

⚠ Rename it!

Note that sample_project.css is overwritten whenever lwarp is loaded in print mode. It is therefore important to rename the file to something like <project>.css before using it, so that your own changes are not overwritten.

<project>.css has an entry which loads lwarp.css, and this entry may be changed to load lwarp_formal.css or lwarp_sagebrush.css if desired. Additional changes to the css may be made by making entries later in the <project>.css file.

File lwarp.css
File project.css
File sample_project.css

It is best to make a local project-specific css file such as project.css, containing only things which are different from lwarp.css. The file project.css should refer to lwarp.css as follows:

```
/* ( --- Start of project.css --- ) */
/* ( --- A sample project-specific CSS file for lwarp --- ) */

/* Uncomment one of the following: */
@import url("lwarp.css") ;
/* @import url("lwarp_formal.css") ; */
/* @import url("lwarp_sagebrush.css") ; */

/* Project-specific CSS setting follow here. */
/* . . . */

/* ( --- End of project.css --- ) */
```

Finally use \CSSFilename{<project>.css} in the document to activate the custom css.

## 7.8 Assigning css classes and styles

HTML CSS classes and styles may be assigned to fragments of the document.

Env BlockClass [⟨*style*⟩] {⟨*class*⟩}

An entire block of text, including paragraphs, may be assigned a CSS class and optional CSS style using the BlockClass environment. The result is placed inside a . A BlockClass may nest other BlockClasses or \InlineClasses.

\InlineClass (⟨*WP CSS style*⟩) [⟨*web CSS style*⟩] {⟨*CSS class*⟩} {⟨*text*⟩}

A section of text without paragraphs may be assinged a CSS class and optional CSS style using the \InlineClass macro. The result is placed inside a . \InlineClass may be nested, but per the HTML standard it must not contain BlockClass, nor may it contain a paragraph, nor several other objects such as HTML figures. \InlineClass also accepts a second optional parameter, enclosed inside parentheses, which assigns the style while generating output for a word processor, while ignoring the web style.

Nullified versions of BlockClass and \InlineClass are provided for the print version, so they may be used in the document without placing them inside warpHTML or \warpHTMLonly.

## 7.9 Selecting the operating system

Prog Unix
Prog Mac OS
Prog Linux
Prog MS-Windows
Prog Windows
Opt OSWindows

lwarp tries to detect which operating system is being used. UNIX / MAC OS / LINUX is the default (collectively referred to as "UNIX" in the configuration files), and MS-WINDOWS is supported as well.

If MS-WINDOWS is not correctly detected, use the lwarp option OSWindows.

When detected or specified, the operating-system path separator used by lwarp is modified, and the boolean usingOSWindows is set true. This boolean may be tested by the user for later use.

## 7.10 Selecting actions for print, HTML, or MATHJAX output

The following environments and macros are used to select actions which only apply to either traditional LaTeX print-formatted PDF generation, or to HTML generation, or to HTML with MATHJAX.

For most of built-in LaTeX and many additional packages there is user-level source code support or emulation, so no special handling will be required. For those cases which lwarp does not handle by itself, the following environments and macros may be used to isolate sections of code for print-only or HTML-only.

These environments are also useful for creating a special version of the titlepage for print and another for HTML.

Env warpHTML Anything which is to be done only for HTML5 output is surrounded by a warpHTML environment:

```
\begin{warpHTML}
 ... something to be done only during \HTML\ generation
\end{warpHTML}
```

⚠ `\end{warpHTML}` ⚠ nesting

Do *not* place anything else on the same line as `\end{warpHTML}`. The exact phrase is used to mark the end of the environment. Do not nest `warpHTML` inside itself. `warpMathJax` may be used inside `warpHTML`.

Env `warpprint`

Anything which is to be done only for print output is surrounded by a `warpprint` environment:

```
\begin{warpprint}
 ... something to be done only during traditional \PDF\ generation
\end{warpprint}
```

⚠ `\end{warpprint}` ⚠ nesting

As above, do not place anything else on the line with `\end{warpprint}`. Do not nest `warpprint` inside itself.

Env `warpall`

Anything which is to be done for any output may be surrounded by a `warpall` environment. Doing so is optional.

```
\begin{warpall}
 ... something to be done during print \PDF\ or \HTML\ output
\end{warpall}
```

⚠ `\end{warpall}` ⚠ nesting

As above, do not place anything else on the line with `\end{warpall}`. Do not nest `warpall` inside itself.

Macros are also provided for print-only or HTML-only code:

`\warpprintonly` {⟨*actions*⟩}

Performs the given actions only when print output is being generated.

`\warpHTMLonly` {⟨*actions*⟩}

Performs the given actions only when HTML output is being generated.

Env `warpMathJax`

⚠ `\end{warpMathJax}` ⚠ nesting

Anything which is to be done only while using HTML output with MathJax is surrounded by a `warpMathJax` environment. Usually, this is `\CustomizeMathJax`, used to add emulation macros. `\end{warpMathJax}` must appear on its own line. Do not nest `warpMathJax` inside itself. `warpMathJax` may be used inside `warpHTML`.

## 7.11 Commands to be placed into the `warpprint` environment

Certain print-related commands should always be placed inside a `warpprint` environment, or may need other special handling. These are unrelated to HTML output, but are hard to isolate automatically. For example:

- Paragraph formatting: `\parindent` `\parskip`
- Manual page positions such as the textpos package, which is emulated but only in a limited way.
- Anything changing the page counter. lwarp requires that the page counter not be adjusted during HTML output.

Some packages require additional setup commands. Where these packages are emulated for HTML, setup commands may work for the emulated HTML output as well as for print output. See the details for each package in this document for more information.

Also see section 13: Troubleshooting.

## 7.12 Title page

In the preamble, place an additional block of code to set the following:

```
\title{Document Title} % One line only
\author{Author One\affiliation{Affiliation One} \and
    Author Two\affiliation{Affiliation Two} }
\date{Optional date}
```

The title is used in the meta tags in the HTML files, unless overridden by `\HTMLTitle`, and the rest are used in `\maketitle`. To use a `\subtitle` or `\published` field, see section 68.8.

`\maketitle` Use `\maketitle` just after the `\begin{document}`, as this will establish the title of the homepage. Optionally, use a `titlepage` environment instead.

Env `titlepage` The `titlepage` environment may be used to hold a custom title page. The titlepage will be set in a `<div>` class `titlepage`, and `\printtitle`, etc. may be used inside this environment.

Env `titlingpage` Another form of custom title page, where `\maketitle` is allowed, and additional information may be included as well.

`\title` {⟨*title*⟩}

⚠ HTML corrupted ⚠ newlines Avoid newlines in the `\title`; these will interfere with the file break and CSS detection. Use a `\subtitle` command instead (section 68.8). The title will appear in the document `\maketitle` as a heading `<h1>`. The HTML meta `title` tag will also have this title, unless `\HTMLTitle` is used to set the meta title to something else instead.

`\author` {⟨*author*⟩}

In `\author`, `\protect` may be needed before some formatting commands. In HTML, the author will appear in a `<div>` of class `author` in the `\maketitle`. If the titling package is used, the author will also appear in a HTML meta tag, but `\HTMLAuthor` may be necessary to create a plain list of names if `\author` had affiliations added. `\affiliation` is a new addition to lwarp.

`\date` {⟨*date*⟩}

\date works as expected. In HTML, this will appear in a  class titledate.

\thanks {⟨*text*⟩}

\thanks are allowed in the titlepage fields, and will be rendered as HTML notes at the bottom of the title page.

## 7.13 HTML page meta descriptions

\HTMLDescription {⟨*A description of the web page.*⟩}
Default: (none)

limitations Each page of HTML output should have its own HTML meta description, which usually shows up in web search results, is limited to around 150 characters in length, and should not include the ASCII double quote character (").

placement Use \HTMLDescription just before \begin{document} to set the description of the home page, and also just before each sectioning command such as \chapter or \section where a new file will be generated, depending on FileDepth. For example, if FileDepth is 1, use \HTMLDescription just before each \section command, and that description will be placed inside the HTML page for that \section. The same descrition will be used for all following HTML files as well, until reset by a new \HTMLDescription. It is best to use a unique description for each HTML file.

disabling To disable the generation of HTML description meta tags, use:

```
\HTMLDescription{}
```

## 7.14 HTML homepage meta title

\HTMLTitle {⟨*title*⟩}
Default: \HTMLtitle{\thetitle}

Sets the contents of the web page <meta name="title"> element. May be set empty to cancel the meta title tag.

See section 7.6 for \HTMLTitleBeforeSection and \HTMLTitleAfterSection, used to set the title for HTML subpages.

## 7.15 HTML page meta author

\HTMLAuthor {⟨*author*⟩}
Default: \HTMLAuthor{\theauthor}

Sets the contents of the web page <meta name="author"> element. May be set empty to cancel the meta author tag.

\author may be used to create a list of authors and their affiliations, in several formats if using authblk, and these may not successfully parse properly into a sensible list for \theauthor. \HTMLAuthor may be used to set the meta tag to a simple list of names.

# 8 Special cases and limitations

Some commonly-used LaTeX expressions should be modified as follows to allow for a smooth conversion to both HTML and print-formatted outputs.

Need help?

See the General Index for "how-to", and the Troubleshooting Index if something doesn't work. A Troubleshooting section is also available. The Index of Objects contains automated entries for each package, macro, environment, counter, boolean, and other objects; individually and also sorted by category.

## 8.1 Things to avoid

In the document, avoid the following:

⚠ options with braces

**Package options:** Package options may cause problems with lwarp, especially if they include curley braces.

If selecting options with braces in `\usepackage` does not work:

```
\usepackage[font={it,small}]{caption}% does not work
```

... try instead selecting the package options before loading lwarp:

```
\PassOptionsToPackage{font={it,small}}{caption}
...
\usepackage{lwarp}
...
\usepackage{caption}
```

... or try setting package options after the package has been loaded:

```
\usepackage{caption}
\captionsetup{font={it,small}}
```

**page counter:** Do not adjust the page counter. If doing so is required for the print version, place the adjustment inside a `warpprint` environment.

**Custom math environment macros:** Do not use expressions such as `\beq` as a replacement for `\begin{equation}`.

**Custom macros in section, figure, table names:** Custom macros which appear in sectioning commands or float captions then appear in the `.toc`, `.lof`, and `.lot` lists, and should be made robust using `\newrobustcmd` or `\robustify` from etoolbox, xparse, etc.

When setting `FileSectionNames` to `true` to name the HTML files from the section names, the file names are created from sanitized versions of the chapter or section names, but the section names must be plain text or something which expands into plain text. Robust macros will not work at the sectioning level which is used for file names, but a robust macro or other complicated name may be used for the manditory argument of `\chapter`, `\section`, etc., if a plain-text version is also included in the optional argument:

```
\chapter[Plain Name]{\ARobustMacro{Fancy Name}}
```

### 8.1.1 Invalid HTML

Additionally, some objects are valid LaTeX, but invalid HTML. An example is a tabular inside `\textbf`, since HTML does not allow a table inside a span. lwarp will create the table, and the browser may support it, but the result is technically invalid.

## 8.2 Formatting

### 8.2.1 Text formatting

⚠ `\bfseries`, etc. `\textbf`, etc. are supported, but `\bfseries`, etc. work only in some situations.

⚠ HTML special chars &, <, and > have special meanings in HTML. If `\&`, `\textless`, and `\textgreater` are used, proper HTML entities will be used, but there may be HTML parsing problems if these special characters occur unescaped in program listings or other verbatim text.

program listings For program listings, the listings package is supported, and its `literate` option is used to convert &, <, and > to proper HTML entities.

verbatim The various `verbatim`-related environments do not convert &, <, and >, so care must be taken to avoid accidentally including valid HTML code inside these environments. Adding a space on either side may be sufficient.

### 8.2.2 Small caps

`Bool FixSmallCaps` Some fonts, such as erewhon, utopia, or fbb, and some packages such as embrac, copy/paste "Small Caps" as all caps ("SMALL CAPS"), which lwarp then reads as all caps, so the text is printed in all caps. If small caps are being rendered as all caps, set:

```
\booltrue{FixSmallCaps}
```

⚠ CJK fonts Some CJK fonts may not work if `FixSmallCaps` is set `true`.

### 8.2.3 Horizontal and vertical space and rules

`\hspace` `\hspace` is converted to an inline HTML span of the given width, except that `0` width is ignored, a width of `.16667em` is converted to an HTML thin breakable space (`U+2009`), and a `\fill` is converted to a `\qquad`.

`\vspace` `\vspace` is ignored for HTML.

`~` `\,` ~ and `\,` are converted to HTML entities.

`\kern` `\hskip` `\kern` and `\hskip` are entered into the HTML PDF output as-is, then interpreted by *pdftotext*, and thus usually appear as a single space.

`\rule` `\rule` is converted to an HTML rule of the same dimensions, of the currently selected text color.

\hrule
\vrule

Both \hrule and \vrule are ignored for HTML. To create a horizontal dividing rule across the page, use \hrulefill in its own paragraph.

\hrulefill

\hrulefill usually creates a one-inch rule, similar to a "fill in the blank". If it is used at the start of a new paragraph, it creates a  with a thin horizontal border across the page, as would often be done with \hrule.

### 8.2.4 Text alignment

Use the environments center, flushright, flushleft instead of the macros \centering, \raggedright, \raggedleft.

⚠ figure & table alignment

\centering, etc. are honored in a figure or table if they are the first command inside the float:

```
\begin{table*}
\centering
\caption{A Table}
. . .
```

### 8.2.5 Accents

Native LaTeX accents such as \" will work, but many more kinds of accents are available when using Unicode-aware XeLaTeX and LuaLaTeX. If using accents in section names which will become file names, it is recommended to use the LaTeX accents such as \" and \v instead of Unicode accents. The LaTeX accents will have the accents stripped when creating the filenames, whereas the Unicode accents will appear in the file names, which may cause issues with some operating systems.

### 8.2.6 textcomp package

Pkg textcomp

Some textcomp symbols do not have Unicode equivalents, and thus are not supported.

⚠ missing symbols

Many textcomp symbols are not supported by many system/browser fonts. In the CSS try referencing fonts which are more complete, but expect to see gaps in coverage.

### 8.2.7 Superscripts and other non-math uses of math mode

Use \textsuperscript{x} instead of $^{x}$

### 8.2.8 Empty \item followed by a new line of text or a nested list:

lists

Use a trailing backslash: \item[label] \

### 8.2.9 Filenames and URLs in lists or footnotes

filename underscore

Escape underscores in the filenames:

```
\item[\href{file\_name.pdf}{text}]
```

### 8.2.10 relsize package

Pkg relsize

For HTML, only the inline macros are supported: `\textlarger`, `\textsmaller`, and `\textscale`. Each becomes an inline span of a modified `font-size`.

`\relsize`, `\larger`, `\smaller`, and `\relscale` are ignored.

While creating SVG math for HTML, the original definitions are temporarilty restored, and so should work as expected.

⚠ not small

The HTML browser's setting for minumum font size may limit how small the output will be displayed.

## 8.3 Boxes and minipages

### 8.3.1 Marginpars

`\marginpar` `[⟨left⟩]{⟨right⟩}` `\marginpar` may contains paragraphs, but in order to remain inline with the surrounding text lwarp nullifies block-related macros inside the `\marginpar`. Paragraph breaks are converted to `<br />` tags.

`\marginparBlock` `[⟨left⟩]{⟨right⟩}` To include block-related macros, use `\marginparBlock`, which takes the same arguments but creates a `<div>` instead of a `<span>`. A line break will occur in the text where the `\marginBlock` occurs.

### 8.3.2 Save Boxes

⚠ HTML corrupted

⚠ boxes

TEX boxes are placed inline and do not allow line breaks, so boxes with long contents may overflow the line during HTML conversion. lwarp uses methods which help avoid this problem.

⚠ minipage, \parbox

`\savebox` and related do not (yet) support `minipage` or `\parbox`.

### 8.3.3 Minipages

⚠ inline

A line of text with an inline `minipage` or `\parbox` will have the `minipage` or `\parbox` placed onto its own line, because a paragraph is a block element and cannot be made `inline-block`.

placement

`minipages` and `\parboxes` will be placed side-by-side in HTML unless you place a `\newline` between them.

side-by-side

Side-by-side `minipages` may be separated by `\quad`, `\qquad`, `\enskip`, `\hspace`, `\hfill`, or a `\rule`. When inside a `center` environment, the result is similar in print and HTML. Paragraph tags are suppressed between side-by-side `minipages` and these spacing commands, but not at the start or end of the paragraph.

⚠ minipage in a span

There is limited support for `minipages` inside an HTML `<span>`. An HTML `<div>` cannot appear inside a `<span>`. While in a `<span>`, `minipages`, and `\parboxes`, and any enclosed lists have limited HTML tags, resulting in an "inline" format, without markup except for HTML breaks. Use `\newline` or `\par` for an HTML break.

⚠ minipage size

When using `minipage`, `\parbox`, and `fminipage`, a virtual $6 \times 9$ inch text area is used for `\linewidth`, `\textwidth`, and `\textheight`, both for sizing the minipage, and also for its contents.

if width is `\linewidth`

If a `minipage` or `\parbox` is assigned a width of exactly `\linewidth`, in HTML it is automatically given no HTML width, thus allowed to fill the line as needed, similar to how it appears in print output.

full-width if HTML

A new macro `\minipagefullwidth` requests that, during HTML output, the next single `minipage` or `\parbox` be generated without an HTML `width` attribute, allowing it to be the full width of the display rather than the declared print-output width. This may be useful where the printed version's width makes no sense in HTML.

⚠ `tabular`, `multicols`

`\UseMinipageWidths`
`\IgnoreMinipageWidths`

Inside a `tabular` or `multicols` environment, where the width depends on the browser window, `\minipagefullwidth` is effectively used by default for every `minipage` or `\parbox` inside the environment. `\UseMinipageWidths` may be used to tell lwarp to honor the specified widths of all following `minipages` and `\parboxes` until the end of the local scope, and `\IgnoreMinipageWidths` may be used to tell lwarp to ignore the specified widths.

⚠ multicol

Inside a `multicols`, `\linewidth` is divided by the specified number of columns.

⚠ text alignment

Nested `minipages` adopt their parent's text alignment in HTML, whereas in regular LaTeX PDF output they do not. Use a `flushleft` or similar environment in the child `minipage` to force a text alignment.

### 8.3.4 Side-by-side minipages

Place side-by-side minipages inside a `center` environment, with horizontal space between them, such as `\quad`, `\qquad`, `\hspace`, or `\hfill`. The result is similar in print and HTML. Do not use space commands at the start or end of the line.

### 8.3.5 Framed minipages and other environments

`\fbox` can only be used around inline `<span>` items during HTML output, but HTML cannot place a block element such as a `<div>` for a minipage or a list inside of a `<span>`. Several options are provided for framing an object, depending on which kind of object and which packages are loaded:

`\fbox`
`\fboxBlock`
Env `fminipage`

For a framed object, options include:

**To remove the frame in HTML output:** Place the `\fbox` command and its closing brace inside `warpprint` environments. This will nullify the frame for HTML output.

For inline text:

**To frame the contents inline with some formatting losses in HTML:** This is the default action of `\fbox` when enclosing a minipage. During HTML output, `\fbox` nullifies the HTML tags for `minipage`, `\parbox`, and lists. The contents are included as inline text inside the `\fbox`'s `<span>` of class `framebox`. For lists, line breaks are converted to HTML breaks. The result is a plain-text inline version of the contents, framed inline with the surrounding text, but lacking any extra HTML markup.

For inline `minipage` and lists:

**To frame the contents on their own line with improved formatting in HTML:** A new command `\fboxBlock` is included, intended to be a direct replacement for `\fbox` for cases where the `\fbox` surrounds a minipage, table, or list. For print output, this behaves as `\fbox`. For HTML output, the contents are placed inside an HTML `<div>` with the class `framed`, resulting in the contents being placed on their own line with a frame surrounding them. The contents preserve their HTML formatting, so lists and minipages look nicer, and valid HTML is created for a `tabular`. While an `\fbox` containing a `tabular` is valid LaTeX code, the result in HTML is problematic since a table is a `<div>` not a `<span>`, so use `\fboxBlock` around a `tabular`, or else place the `tabular` inside a `minipage`, or use `fminipage`, described next. Also see below regarding the "Misplaced alignment tab character &." error.

For display `tabular`, minipages, and lists:

**To create a framed minipage in both print and HTML:** A new environment `fminipage` is included. For print output, this is identical to `minipage`, except that it is also framed. For HTML output, this forms a `<div>` of class `framed`, the contents preserve their HTML formatting, and valid HTML is created for a `tabular`. Also see section 88 for a new environment `fcolorminipage`. Also see below regarding the "Misplaced alignment tab character &." error.

colored boxes and frames:

**To create colored frames and boxes:** See section 650 for xcolor's `\colorbox` and `\fcolorbox`, and lwarp's additional `\colorboxBlock` and `\fcolorboxBlock`.

⚠ Misplaced alignment tab character &

**To frame tables or verbatim environments:** Place the contents inside a `fminipage`, or perhaps a `\fboxBlock` for a `tabular`. Also, if using `\fboxblock` with `tabular`, you will have to use `\StartDefiningTabulars` before the start of the macro which uses `\fboxBlock` and the `tabular`, and `\StopDefiningTabulars` afterwards. Also see the lwarp documentation for the fancybox package.

**To frame equations:** See section 251 for the fancybox package.

**For fancy framed minipages:** See packages boxedminipage, shadow, fancybox, framed, mdframed.

**Custom environments:** Use a custom environment to create a sidebar, containing a `BlockClass` environment with custom CSS formatting, and `\warpprintonly{\hrule}` command:

```
\begin{BlockClass}{frameminipage}% ignored in print output
  % use \CSS\ to format div class framedminipage
\warpprintonly{\hrule} % only appears in print output
Contents
\warpprintonly{\hrule} % only appears in print output
\end{BlockClass}
```

### 8.3.6 fancybox package

Pkg fancybox

framed equation example

fancybox's documentation has an example FramedEqn environment which combines math, \Sbox, a minipage, and an \fbox. This combination requires that the entire environment be enclosed inside a lateximage, which is done by adding \lateximage at the very start of FramedEqn's beginning code, and \endlateximage at the very end of the ending code. Unfortunately, the HTML alt attribute is not used here.

```
\newenvironmentFramedEqn
{
\lateximage% NEW
\setlength{\fboxsep}{15pt}
. . . }{. . .
\[\fbox{\TheSbox}\]
\endlateximage% NEW
}
```

framing alternatives

\fbox works with fancybox. Also see lwarp's \fboxBlock macro and fminipage environment for alternatives to \fbox for framing environments.

framed table example

The fancybox documentation's example of a framed table using an \fbox containing a tabular does not work with lwarp, but the FramedTable environment does work if \fbox is replaced by \fboxBlock. This method does lose some HTML formatting. A better method is to enclose the table's contents inside a fminipage environment. The caption may be placed either inside or outside the fminipage:

```
\begin{table}
\begin{fminipage}{\linewidth}
\begin{tabular}{lr}
. . .
\end{tabular}
\end{fminipage}
\end{table}
```

⚠ framed verbatim

lwarp does not support the verbatim environment inside a span, box, or fancybox's \Sbox, but a verbatim may be placed inside a fminipage. The fancybox documentation's example FramedVerb may be defined as:

```
\newenvironment{FramedVerb}[1] % width
{
  \VerbatimEnvironment
  \fminipage{#1}
  \beginVerbatim
}{
  \endVerbatim
  \endfminipage
}
```

framed \VerbBox

fancybox's \VerbBox may be used inside \fbox.

indented alignment

LVerbatim, \LVerbatimInput, and \LUseVerbatim indent with horizontal space which may not line up exactly with what *pdftotext* detects. Some lines may be off slightly in their left edge.

### 8.3.7 mdframed package

Pkg mdframed

support Most basic functionality is supported, including frame background colors and single-border colors and thickness, title and subtitle background colors and borders and thickness, border radius, and shadow. CSS classes are created for mdframed environments and frame titles.

⚠ loading When used, lwarp loads mdframed in HTML with `framemethod=none`.

font For title font, use

```
frametitlefont=\textbf,
```

instead of

```
frametitlefont=\bfseries,
```

where `\textbf` must appear just before the comma and will receive the following text as its argument (since the text happens to be between braces in the mdframed source). Since lwarp does not support `\bfseries` and friends, only one font selection may be made at a time.

theoremtitlefont `theoremtitlefont` is not supported, since the following text is not in braces in the mdframed source.

ignored options `userdefinedwidth` and `align` are currently ignored.

css classes Environments created or encapsulated by mdframed are enclosed in a `<div>` of class `mdframed`, and also class `md<environmentname>` for new environments.

Frame titles are placed in a `<div>` of class |mdframedtitle|. Subtitles are in a `<div>` of class |mdframedsubtitle|, and likewise for subsubtitles.

### 8.3.8 tcolorbox package

Pkg tcolorbox

tcolorbox is emulated for HTML and MathJax, and supported as-is inside a `lateximage` or SVG math.

What has been tested to work (at least partly) includes:

- `tcolorbox`, `\tcbox`.
- Title, subtitle.
- Upper, lower parts.
- Colors and title fonts.
- Floating objects.
- Some layered box features.
- Counters, labels, references.
- listings, listingsutf8.
- `theorems`: Theorems are supported. `math`, `ams equation`, etc. are not supported. Use a `tcolorbox` with regular math inside it. `\tcboxmath` and `\tcbhighmath` are suppored in SVG math, and emulated in MathJax.

⚠ math

- Fitting features: `\tcboxfit` becomes `\tcbox` in HTML.

⚠ footnotes

- Footnote numbering does not match the printed output.
- MathJax emulation is provided for common macros.

⚠ undefined references

If using cleveref, it may be necessary to name theorems such as:

```
\crefname{tcb@cnt@mytheo}{my theorem}{my theorems}
```

## 8.4 Section names

If using named HTML files, by selecting `\booltrue{FileSectionNames}`, the generated filenames may be simplified by using `\FilenameSimplify` and `\FilenameNullify`:

`\FilenameSimplify` {⟨*text*⟩}

To remove common short words from the automatically-generated filenames, replacing each with a single hyphen "-", use `\FilenameSimplify`:

```
\FilenameSimplify*{-in-}
\FilenameSimplify*{A-}
```

The first example removes the word "in" in the middle of a filename, and the second example removes "A" at the start of the filename. The star forces the arguments to be detokenized, which is required for a plain-text comparison. (The unstarred form is used for a token-sensitive comparison, which is seldom required by the user.) After simplfication, repeated hyphen characters will be further simplified to a single hyphen "-". Finally, single hyphens at the start or end of the filename are removed.

`\FilenameNullify` {⟨*macros*⟩}

⚠ macros in section names

Macro names may appear in the automatically-generated file names. To remove these, create *non-robust* nullified versions of the macros, ensuring that each line ends with a percent character % as shown below. These are placed inside `\FilenameNullify`, which adds them to the list of macros which are nullfiied during filename generation. Low-level macros such as `\begingroup` will cause problems when nullfied. Many macros such as `\textbf` are already nullfied. lwarp also already nullifies built-in symbol and textcomp macros, including if defined by xunicode, but not all xunicode macros. See the definition of `\LWR@nullfonts` for a complete list.

```
\FilenameNullify{%
  \renewcommand*{\macroname}[1]{#1}%
  \renewcommand*{\anothermacro}{}%
}
```

⚠ duplicate filename

Avoid duplicate file names. Section names at levels which result in HTML file splits must be unique. lwarp will generate an error if a duplicate HTML filename is generated. Use the optional TOC caption entry parameter for formatting. Remember to `\protect` LaTeX commands which appear in section names and TOC captions.

⚠ math in section names

If using named HTML files, in section names use paren math `\(x+y\)` instead of dollar math `$x+y$`. (Dollar math works, but appears in the filename.) Or, use a short name for the TOC entry without the math, or use `\texorpdfstring` from the hyperref package:

```
\section{Some math \texorpdfstring{$1+2=3$}{three}}
```

## 8.5 Cross-references

labels
⚠ label characters

Labels with special characters may be a problem. It is best to stick with alpha-numeric, hyphen, underscore, and perhaps the colon (if not French).

\nameref
⚠ empty link

\nameref refers to the most recently-used section where the \label was defined. If no section has been defined before the \label, the link will be empty. Index entries also use \nameref and have the same limitation.

### 8.5.1 Page references

⚠ LaTeX page numbers

The printed page does not translate to the HTML page, so \pageref references are converted to parentheses containing \pagerefPageFor, which defaults to "see ", followed by a hyperlink to the appropriate object.

Ex:

```
\ref{sec:name} on page \pageref{sec:name}
```

in HTML becomes:

"Sec. 1.23 on page (**see** sec. 1.23)".

\pagerefPageFor may be redefined to "page for ", empty, etc. See page 504.

### 8.5.2 cleveref and varioref packages

Pkg cleveref
Pkg varioref
⚠ cleveref page numbers

cleveref and varioref are supported, but printed page numbers do not map to HTML, so a section name or a text phrase are used for \cpageref and \cpagerefrange. This phrase includes \cpagerefFor, which defaults to "for".

Ex:

```
\cpageref{tab:first,tab:second}
```

in html becomes:

"pages **for** table 4.1 and **for** table 4.2"

See \cpagerefFor at page 733 to redefine the message which is printed for page number references.

⚠ varioref types

cleveref changes the behavior of varioref in that the reference type is automatically printed if cleveref is loaded. Lwarp requires cleveref, so the HTML version will always automatically print the reference types even if the print mode does not. The simplest way to make them match is to require the cleveref package for the document.

### 8.5.3 Hyperlinks, hyperref, and url

Pkg hyperref
Pkg url

lwarp emulates hyperref, including the creation of active hyperlinks, but does not require that hyperref be loaded by the document.

⚠ comments between arguments

Do not place a comment with a % character between arguments for \hyperref, etc., as it is neutralized for inclusion in HTML URLs.

lwarp can also load url, but url should not be used at the same time as hyperref, since they both define the `\url` command. lwarp does not (yet) attempt to convert url links into hyperlinks during HTML output, nor does the print version of url create hyperlinks.

⚠ backref When generating HTML, lwarp's emulation of hyperref does not automatically load backref, so backref must be loaded explicitly.

### 8.5.4 Footnotes, endnotes, and page notes

lwarp uses native LaTeX footnote code, although with its own `\box` to avoid the LaTeX output routine. The usual functions mostly work as-is.

footnote numbering To have footnote numbers reset each time footnotes are printed:

```
\setcounter{footnoteReset}{1}
```

For bigfoot, manyfoot, or perpage:

```
\MakePerPage{footnoteX}
— or —
\MakeSortedPerPage{footnoteX}
```

The footnotes are reset when they are printed, according to section level as set by `FootnoteDepth`, which is not necessarily by HTML page. This is recommended for `\alph`, `\Alph`, or `\fnsymbol` footnotes, due to the limited number of symbols which are available.

⚠ MathJax, `\footnotemark` If using MathJax, after each math expression with a `\footnotemark`, adjust the `footnote` counter by the number of `\footnotemarks`:

```
\[ (math expression with two instances of \footnotemark) \]
\warpHTMLonly{\addtocounter{footnote}{2}}
```

Similarly for endnotes, but *not* sidenotes.

Also for MathJax, `\footnotename` is used for a `\footnotemark` if the actual footnote number is not known. To redefine it, provide it before loading lwarp:

```
\providecommand{\footnotename}{something}
\usepackage{lwarp}
```

Similar for sidenotes. For endnotes:

```
\def\endnotename{something}% \def allows name to start with "end"
```

For the pagenote package, there is no `\pagenotename` to define, since there is no `\pagenotemark` command.

footmisc The footmisc `stable` option is emulated by lwarp.

⚠ sectioning commands When using footnotes in sectioning commands, to generate consistent results between print and HTML, use the footmisc package with the `stable` option, provide a short TOC entry, and `\protect` the `\footnote`:

```
\usepackage[stable]{footmisc}
. . .
\subsection[Subsection Name]
    {Subsection Name\protect\footnote{A footnote.}}
```

memoir with footmisc
⚠ memoir

If using memoir class, with which lwarp preloads footmisc, the `stable` option must be declared before lwarp is loaded:

```
\PassOptionsToPackage{stable}{footmisc}
\usepackage{lwarp}
. . .
```

Do not use a starred sectioning command. As an alternative, it may be possible to adjust `\secnumdepth` instead.

fancybox, fancyvrb
⚠ `\VerbatimFootnotes`
⚠ sectioning or displaymath

If using fancybox or fancyvrb with `\VerbatimFootnotes`, and using footnotes in a sectioning command or display math, use `\footnotemark` and `\footnotetext`:

```
\subsection[Subsection Name]
    {Subsection Name\protect\footnotemark}
\footnotetext{A footnote with \verb+verbtim+.}
```

and likewise for equations or display math.

At present there is a bug such that paragraph closing tags are not present in footnotes when `\VerbatimFootnotes` are selected. The browser usually compensates.

pfnote
⚠ pfnote numbers

While emulating pfnote, lwarp is not able to reset HTML footnote numbers per page number to match the printed version, as HTML has no concept of page numbers. lwarp therefore uses continuous footnote numbering even for pfnote.

bigfoot, manyfoot
⚠ verbatim

Verbatim footnotes are not yet supported.

If using the bigfoot package, and possibly also manyfoot, problems may occur with counter allocation because lwarp uses many counters, and there is a difference in how counters numbered 256 and up are handled in pdfLaTeX. With bigfoot this has been known to show up as an error related to one footnote insert being forbidden inside another. Another problem showed up as a input stack error, and which of these problems occurred depended on how many counters were allocated.

As a possible solution, try creating several new counters before defining bigfoot or manyfoot footnotes, hoping to shift the problematic counter above the 256 threshold. It may instead be necessary to use XeLaTeX or LuaLaTeX instead of pdfLaTeX.

### 8.5.5 xr, xr-hyper, and xcite packages

See section 5.17.

## 8.6 Front and back matter

### 8.6.1 Custom classes with multiple authors and affiliations

Some classes allow multiple authors and affiliations. Often it is possible to emulate these using a standard class along with authblk:

```
%\documentclass{customclass} % for print document
\documentclass{article} % for html document

\usepackage{lwarp}
\begin{warpHTML}
\usepackage{authblk}
\let\affiliation\affil % maybe required
\end{warpHTML}
```

### 8.6.2 Starred chapters and sections

HTML page and TOC

The following describes \ForceHTMLPage and \ForceHTMLTOC, which may be used for endnotes, glossaries, tocbibind, bibliographies, and the index. See the following sections where applicable. Continue here if interested in the reason for adding these commands to lwarp.

Some packages use \chapter* or \section* to introduce reference material such as notes or lists, often to be placed in the back matter of a book. These starred sections are placed inline instead of on their own HTML pages, and they are not given TOC entries.

lwarp provides a method to cause a starred section to be on its own HTML page, subject to FileDepth, and also a method to cause the starred section to have its own TOC entry during HTML output.

\ForceHTMLPage

To place a starred section on its own HTML page, use \ForceHTMLPage just before the \chapter* or \section*. lwarp will create a new page for the starred sectional unit.

A starred sectional unit does not have a TOC entry unless one is placed manually. The typical method using \phantomsection and \addcontentsline works for inline text but fails when the new starred section is given its own webpage after the TOC entry is created, or when creating an EPUB where the TOC entry will point to the page before the starred section. If the starred section has its own HTML page but no correct TOC entry pointing to that page, the page will be inaccessible unless some other link is created.

⚠ inaccessible HTML page

\ForceHTMLTOC

To automatically force the HTML version of the document to have a TOC entry for a starred section, use \ForceHTMLTOC just before the \chapter* or \section*, and place \phantomsection and \addcontentsline inside a warpprint environment.

For print output, \ForceHTMLTOC and \ForceHTMLPage have no effect.

### 8.6.3 abstract package

Pkg abstract

If using the number option with file splits, be sure to place the table of contents before the abstract. The number option causes a section break which may cause a file split, which would put a table of contents out of the home page if it is after the abstract.

⚠ missing TOC

### 8.6.4 titling and authblk

Pkg titling
Pkg authblk
package support
⚠ load order
\published and \subtitle

lwarp supports the native LaTeX titling commands, and also supports the packages authblk and titling. If both are used, authblk should be loaded before titling.

If using the titling package, additional titlepage fields for \published and \subtitle may be added by using \AddSubtitlePublished in the preamble. See section 68.8.

### 8.6.5 tocloft package

Opt [tocloft] titles
Pkg tocloft
Pkg tocloft
⚠ tocloft & other packages

If using tocloft with tocbibind, anonchap, fncychap, or other packages which change chapter title formatting, load tocloft with its titles option, which tells tocloft to use standard LaTeX commands to create the titles, allowing other packages to work with it.

### 8.6.6 appendix package

Pkg appendix
⚠ incorrect TOC link

During HTML conversion, the option toc without the option page results in a TOC link to whichever section was before the appendices environment. It is recommended to use both toc and also page at the same time.

### 8.6.7 pagenote package

Pkg pagenote

pagenote works as-is, but the page option is disabled.

⚠ labels

Note that labels in page notes do not appear as expected, even in the print version.

### 8.6.8 endnotes package

Pkg endnotes
table of contents

To place the endnotes in the TOC, use:

```
\usepackage{endnotes}
\appto\enoteheading{\addcontentsline{toc}{section}{\notesname}}
\renewcommand*{\notesname}{Endnotes} % optional
```

HTML page

To additionally have the endnotes on their own HTML page, if FileDepth allows:

```
\ForceHTMLPage
\theendnotes
```

⚠ \endnotemark numbering

If using MathJax, see section 8.5.4 regarding the use of \endnotemark and \endnotetext.

### 8.6.9 *BibTeX*

\etalchar

Displays a superscript "+" to indicate "and others".

⚠ Modify *.bib

When enough authors are cited for a source, BibTeX may use the \etalchar command to

display a math superscript with a + character to indicate "and others". Without modification, this will result in an "Improper \prevdepth" error. At present, lwarp requires that \etalchar be replaced by a text superscript. To do so, add to the start of the .bib file the following:

```
@PREAMBLE{"\let\etalchar\relax \newcommand{\etalchar}[1]{\textsuperscript{#1}}"}
```

### 8.6.10 xcite package

See section 5.17.

### 8.6.11 gloss package

Pkg gloss

⚠ compiling

To process the HTML glossary:

```
bibtex <projectname>_html.gls
```

### 8.6.12 glossaries package

Pkg glossaries

processing glossaries

Opt GlossaryCmd

Default: makeglossaries

Opt [lwarpmk] printglossary

Opt [lwarpmk] htmlglossary

⚠ *makeglossaries* not found

*lwarpmk* has the commands **lwarpmk printglossary** and **lwarpmk htmlglossary**, which process the glossaries created by the glossaries package using that package's *makeglossaries* program.

The shell command to execute is set by the lwarp option GlossaryCmd, which defaults to **makeglossaries**. The print or HTML glossary filename is appended to this command.

In some situations it may be required to modify the default command, such as to add the **perl** command in front:

```
\usepackage[
   GlossaryCmd={perl makeglossaries},
] {lwarp}
```

*xindy* language

To set the language to use for processing glossaries with *xindy*:

```
\usepackage[
   GlossaryCmd={makeglossaries -L english},
] {lwarp}
```

Other options for *makeglossaries* may be set as well.

placement and TOC options

The glossaries may be placed in a numbered or unnumbered section, given a TOC entry, and placed inline or on their own HTML page:

**Numbered section, on its own HTML page:**

```
\usepackage[xindy,toc,numberedsection=nolabel]{glossaries}
. . .
\printglossaries
```

**Unnumbered section, inline with the current HTML page:**

```
\usepackage[xindy,toc]{glossaries}
. . .
\printglossaries
```

**Unnumbered section, on its own HTML page:**

```
\usepackage[xindy,toc]{glossaries}
. . .
\ForceHTMLPage
\printglossaries
```

⚠ glossary style — The default `style=item` option for glossaries conflicts with lwarp, so the style is forced to `index` instead.

⚠ number list — The page number list in the printed form would become `\namerefs` in HTML, which could become a very long string if many items are referenced. For now, the number list is simply turned off.

print/HTML versions — The print and HTML versions of the glossary differ in their internal page numbers. Separate commands for generating print and HTML glossaries are used, even though the page number is currently ignored.

### 8.6.13 nomencl package

Pkg nomencl — To process the HTML nomenclature:

```
makeindex <project>_html.nlo -s nomencl.ist -o <project>_html.nls
```

### 8.6.14 Indexing overview

There are many ways to process indexes for a LaTeX document, including native LaTeX capabilities, a number of packages and classes, the possible availability of shell escape and *latexmk*, and the need to process print and HTML versions. lwarp attempts to provide easy recompilation of indexes along with the rest of the document, but the various indexing options must be set correctly. Numerous examples are given below. Some differ in minor details, so the important parts are highlighted in red, and options are in green.

Once set up properly, the entire document may be recompiled with **`lwarpmk print`** and **`lwarpmk html`**. In some cases, it will also be necessary to compile the indexes with **`lwarpmk printindex`** and **`lwarpmk htmlindex`**. A recompile may then be forced with **`lwarpmk print1`** and **`lwarpmk html1`**.

manual processing — The user may continue to process indexes manually or by shell script without the use of *lwarpmk*, but adjustments will be required to process HTML indexes as well. In general, `*.idx` and `*.ind` files will be accompanied by `*_html.idx` and `*_html.ind` files.

custom index style — If using a custom indexing style file, see sections 8.6.20 to 8.6.22.

link appearance — To control how the index links appear in the HTML output, see the `IndexRef` option in section 7.5, page 107.

source code — See section 78 for lwarp's core index and glossary code, section 330 for index, section 552

for splitidx, section 328 for imakeidx, section 605 for tocbibind, and section 671.17 for memoir's indexing patches.

### 8.6.15 Indexing with makeidx, *makeindex*, *xindy*, *xindex*, gindex

*lwarpmk* processing

The following allow the user to process indexes automatically, or using *lwarpmk*'s commands:

Enter ⇒ **`lwarpmk printindex`**

Enter ⇒ **`lwarpmk htmlindex`**

Prog makeindex

**For a single index using *makeindex*:**

```
\usepackage[makeindex,latexmk] {lwarp}
```

The usual `.idx` and `.ind` files will be used, along with the new `lwarp.ist` style file. When creating the HTML index, "`_html`" is automatically appended to each of the names.

*lwarpmk* will use *latexmk* if specified, in which case *latexmk* will create the index automatically. Otherwise, use

Enter ⇒ **`lwarpmk printindex`**

Enter ⇒ **`lwarpmk htmlindex`**

to compile the indexes.

To use a custom configuration file, see section 8.6.20.

Prog xindy

**For a single index using *xindy*:**

```
\usepackage[
    xindy,
    xindyLanguage=english,                  <optional>
    xindyCodepage=utf8,                     <optional>
    latexmk                                 <optional>
]{lwarp}
```

The usual `.idx` and `.ind` files will be used, along with the new `lwarp.xdy` style file.

*lwarpmk* will use *latexmk* if specified, in which case *latexmk* will create the index automatically. Otherwise, use

Enter ⇒ **`lwarpmk printindex`**

Enter ⇒ **`lwarpmk htmlindex`**

to compile the indexes.

To use a custom configuration file, see section 8.6.21.

Prog xindex **For a single index using *xindex*:**

```
\usepackage[
    xindex,
    latexmk                                    <optional>
]{lwarp}
```

The usual `.idx` and `.ind` files will be used.

*lwarpmk* will use *latexmk* if specified, in which case *latexmk* will create the index automatically. Otherwise, use

Enter ⇒ **`lwarpmk printindex`**

Enter ⇒ **`lwarpmk htmlindex`**

to compile the indexes.

To use a custom configuration file, see section 8.6.22.

Pkg gindex **For a single index using gindex:**

```
\usepackage[
    makeindex,
    makeindexStyle=gindex.ist,
    . . . or . . .
    makeindexStyle=gindexh.ist,
    latexmk                                    <optional>
]{lwarp}
```

The usual `.idx` and `.ind` files will be used.

*lwarpmk* will use *latexmk* if specified, in which case *latexmk* will create the index automatically. Otherwise, use

Enter ⇒ **`lwarpmk printindex`**

Enter ⇒ **`lwarpmk htmlindex`**

to compile the indexes.

To use a custom configuration file, copy `gindex.ist` to a new file, modify, then specify it with `MakeindexStyle` as above. lwarp will automatically adapt to gindex's `\indexpagessep` and `\indexrangesep` settings.

### 8.6.16 Indexing with index

Prog index

lwarp is told how to use *makeindex* using the `PrintIndexCmd` and `HTMLIndexCmd` options. The file `lwarp.ist` is specified, which generates index letter heads for print output and also allows special HTML formatting for HTML output.

**For multiple indexes using *makeindex* and** index**:**

(Assuming that the second index has file extensions `.sist` and `.sind`)

```
\usepackage[
  makeindex, latexmk,
  PrintIndexCmd={
    makeindex -s lwarp.ist <projectname>.idx ;
    makeindex -s lwarp.ist
      -o <projectname>.sind <projectname>.sidx
  },
  HTMLIndexCmd={
    makeindex -s lwarp.ist <projectname>_html.idx ;
    makeindex -s lwarp.ist
      -o <projectname>_html.sind <projectname>_html.sidx
  }
]{lwarp}
\usepackage{index}
. . .
\makeindex
\newindex{secondname}{sidx}{sind}{Second Index}
```

⚠ Windows *For Windows, replace the two ";" characters with "&".*

When creating the HTML index, "`_html`" is automatically appended to the index filenames.

Use

Enter ⇒ **`lwarpmk printindex`**

Enter ⇒ **`lwarpmk htmlindex`**

to compile the indexes.

If the `latexmk` option is selected for lwarp, *latexmk* will compile the document but will *not* compile the indexes. **`lwarpmk printindex`** and **`lwarpmk htmlindex`** will still be required.

### 8.6.17 Indexing with splitidx

Prog `splitidx`

lwarp is told how to use *splitindex* using the `PrintIndexCmd` and `HTMLIndexCmd` options. The file `lwarp.ist` is specified, which generates index letter heads for print output and also allows special HTML formatting for HTML output.

If the `latexmk` option is selected for lwarp, *latexmk* will compile the document but will *not* compile the indexes. **`lwarpmk printindex`** and **`lwarpmk htmlindex`** will still be required.

⚠ `\thepage` When using `\AtWriteToIndex` or `\AtNextWriteToIndex`, the user must not refer to `\thepage` during HTML output, as the concept of a page number is meaningless. Instead, do

```
\addtocounter{LWR@autoindex}{1}
\LWR@new@label{LWRindex-\arabic{LWR@autoindex}}
```

where the \index-like action occurs, and then refer to \arabic{LWR@autoindex} instead of \thepage where the reference should occur.

See section 671.17 in the lwarp-patch-memoir package for the \@@wrspindexhyp macro as an example.

**For multiple indexes using *makeindex* and splitidx:**

```
\usepackage[
  makeindex, latexmk,
  PrintIndexCmd={
    splitindex <projectname> -- -s lwarp.ist
  },
  HTMLIndexCmd={
    splitindex <projectname>_html -- -s lwarp.ist
  }
]{lwarp}
\usepackage{splitidx}
. . .
\makeindex
\newindex[Second Index]{secondname}
```

When creating the HTML index, "_html" is automatically appended to each of the names.

Use

Enter ⇒ **lwarpmk printindex**

Enter ⇒ **lwarpmk htmlindex**

to compile the indexes.

**For multiple indexes using *xindy* and splitidx:**

```
\usepackage[
  xindy, latexmk,
  PrintIndexCmd={
    splitindex -m xindy <projectname> -- -M lwarp.xdy
      -L english -C utf8                          <optional>
  },
  HTMLIndexCmd={
    splitindex -m xindy <projectname>_html -- -M lwarp.xdy
      -L english -C utf8                          <optional>
  }
]{lwarp}
\usepackage{splitidx}
. . .
\makeindex
\newindex[Second Index]{secondname}
```

When creating the HTML index, "_html" is automatically appended to each of the names.

Use

Enter ⇒ **lwarpmk printindex**

Enter ⇒ **lwarpmk htmlindex**

to compile the indexes.

### 8.6.18 Indexing with imakeidx

Prog imakeidx

Due to the number of methods which may be used to process multiple indexes, the options for style file and *xindy* language and codepage must be specified in one of several different ways. These are described in detail later in this section, but are summarized here.

If shell escape is used, imakeidx will automatically compile the indexes by itself. Options specifying a custom style file and *xindy* language and codepage must be specified for each `\makeindex` command using its `options=` option, which must include lwarp's special `lwarp.ist` or `lwarp.xdy` file, or a file based on them. If using a custom indexing style file, see sections 8.6.20 to 8.6.22.

The `splitindex` option is also available of shell escape is used, in which case the splitidx package and *splitindex* program will also be used.

If shell escape is not possible, *latexmk* may be used to automatically compile the indexes. The style, language, and codepage options are specified with lwarp's `makeindexStyle`, `xindyStyle`, `xindyLanguage`, and `xindyCodepage` options. These are passed to *latexmk* by *lwarpmk*'s **lwarpmk printindex** and **lwarpmk htmlindex** commands.

Where shell escape and *latexmk* are not possible, *lwarpmk* may be used to manually compile the indexes. lwarp's `PrintIndexCmd` and `HTMLIndexCmd` options are used.

**For a single or multiple indexes using *makeindex* and imakeidx:**

The index style `lwarp.ist` is automatically used for HTML output. This file turns on letter headings, so it may be desirable to specify it as an option, in which case it will also be used for print output, which will help match the print and HTML output.

```
\usepackage[makeindex,latexmk] {lwarp}
\usepackage[makeindex]{imakeidx}
. . .
\makeindex[options={-s lwarp.ist}]
\makeindex[name=secondname,options={-s lwarp.ist}]
```

imakeidx will automatically compile the indexes. Shell escape is not required while using *makeindex*. `latexmk` may be specified, and if so it will be used for **lwarpmk print** and **lwarpmk html**, but *imakeidx* will actually create the indexes.

**For a single or multiple indexes using *makeindex* and *splitindex* with imakeidx:**

The index style `lwarp.ist` is automatically used for HTML output. This file turns on letter headings, so it may be desirable to specify it as an option, in which case it will also be used for print output, which will help match the print and HTML output.

```
\usepackage[makeindex,latexmk] {lwarp}
\usepackage[makeindex,splitindex]{imakeidx}
. . .
\makeindex[options={-s lwarp.ist}]
\makeindex[name=secondname,options={-s lwarp.ist}]
```

⚠ enable shell escape

Shell escape is required while using *splitindex*. For the first compile, use

Enter ⇒ **pdflatex --shell-escape projectname.tex**

Enter ⇒ **pdflatex --enable-write18 projectname.tex** **(MiKTeX)**

or similar with *xelatex* or *lualatex*. lwarp will remember that shell escape was used.

*imakeidx* will automatically execute *splitindex*, and will also use *makeindex* to compile the indexes.

`latexmk` may be specified, and if so it will be used for **`lwarpmk print`** and **`lwarpmk html`**, but *imakeidx* will actually create the indexes.

**For multiple indexes using *xindy* and** imakeidx**, using shell escape:**

Options may be given to imakeidx's `\makeindex` command. The style file `lwarp.xdy` is automatically used for HTML output, and is not necessary for print output since the output will be similar. If language or codepage must be set, they should be specified as options for `\makeindex`, since imakeidx will process the indexes.

```
\usepackage[xindy,latexmk] {lwarp}
\usepackage[xindy,splitindex]{imakeidx}
. . .
\makeindex[
  options={ -M lwarp.xdy -L english -c utf8 }
]
\makeindex[
  name=secondname,
  options={ -M lwarp.xdy -L english -c utf8 }
]
```

⚠ enable shell escape

For the first compile, use

Enter ⇒ **pdflatex --shell-escape projectname.tex**

Enter ⇒ **pdflatex --enable-write18 projectname.tex** **(MiKTeX)**

or similar with *xelatex* or *lualatex*. lwarp will remember that shell escape was used.

*imakeidx* will automatically execute *splitindex* if selected, and will also use *xindy* to compile the indexes.

If selected, *latexmk* will automatically recompile the entire document as necessary.

**For indexes using *xindy* and *imakeidx*, without shell escape, but *with latexmk*:**

lwarp's options are used, and are passed to *latexmk*.

```
\usepackage[
  xindy,
  xindyLanguage=english,                    <optional>
  xindyCodepage=utf8,                       <optional>
  latexmk,
]{lwarp}
\usepackage[xindy]{imakeidx}
. . .
\makeindex
\makeindex[name=secondname]
```

*latexmk* will create the indexes automatically when **`lwarpmk print`** and **`lwarpmk html`** are executed.

**For indexes using *xindy* and *imakeidx*, without shell escape, and *without latexmk*:**

*lwarpmk* must be told how to create the indexes:

```
\usepackage[
  xindy,
  PrintIndexCmd={
    xindy -M lwarp.xdy -L english -C utf8
      <projectname>.idx ;
    xindy -M lwarp.xdy -L english -C utf8
      secondname.idx
  },
  HTMLIndexCmd={
    xindy -M lwarp.xdy -L english -C utf8
      <projectname>_html.idx ;
    xindy -M lwarp.xdy -L english -C utf8
      secondname_html.idx
  }
]{lwarp}
\usepackage[xindy]{imakeidx}
. . .
\makeindex
\makeindex[name=secondname]
```

⚠ Windows *For Windows, replace the two ";" characters with "&".*

<projectname> is the \jobname: if compiling "name.tex", use the filenames name.idx and name_html.idx.

Use

Enter ⇒ **lwarpmk printindex**

Enter ⇒ **lwarpmk htmlindex**

to compile the indexes.

**For multiple indexes using *xindex* and** imakeidx**, using shell escape:**

*xindex*, *makeindex*, *imakeidx*, and *splitindex* can all work together:

```
\usepackage[%
  xindex,
  xindexConfig=-imakeidx,
  latexmk
] {lwarp}
\usepackage[makeindex,splitindex]{imakeidx}
. . .
\makeindex[%
  options={ -s lwarp.ist} }
]
\makeindex[
  name=secondname,
  options={ -s lwarp.ist} }
]
```

⚠ enable shell escape For the first compile, use:

Enter ⇒ **pdflatex --shell-escape projectname.tex**

Enter ⇒ **pdflatex --enable-write18 projectname.tex** **(MiKTeX)**

or similar with *xelatex* or *lualatex*. lwarp will remember if shell escape was used.

*xindex* will use *imakeidx*, and *imakeidx* will automatically execute *splitindex* if selected.

If selected, *latexmk* will automatically recompile the entire document as necessary.

### 8.6.19 Indexes with memoir

**For a single index with memoir and *makeindex*:**

```
\documentclass{memoir}
\usepackage[makeindex,latexmk]{lwarp}
. . .
\makeindex
```

The usual `.idx` and `.ind` files will be used, along with the `lwarp.ist` style file.

*lwarpmk* will use *latexmk* if specified, in which case *latexmk* will create the index automatically. Otherwise, use

Enter ⇒ **lwarpmk printindex**

Enter ⇒ **lwarpmk htmlindex**

to compile the indexes.

**For multiple indexes with memoir and *makeindex*, using *latexmk*:**

lwarp's options are used, and are passed to *latexmk*.

```
\documentclass{memoir}
\usepackage[makeindex,latexmk]{lwarp}
. . .
\makeindex
\makeindex[secondname]
```

*lwarpmk* will use *latexmk* to create the indexes automatically when the user executes **lwarpmk print** and **lwarpmk html**.

**For multiple indexes with** memoir **and *makeindex*, *without*** latexmk**:**

*lwarpmk* must be told how to create the indexes:

```
\documentclass{memoir}
\usepackage[
  makeindex,
  PrintIndexCmd={
    makeindex -s lwarp.ist <projectname>.idx ;
    makeindex -s lwarp.ist secondname.idx
  },
  HTMLIndexCmd={
    makeindex -s lwarp.ist <projectname>_html.idx ;
    makeindex -s lwarp.ist secondname_html.idx
  }
]{lwarp}
. . .
\makeindex
\makeindex[secondname]
```

⚠ Windows *For Windows, replace the two ";" characters with "&".*

`<projectname>` is the `\jobname`: if compiling "`name.tex`", use the filenames `name.idx` and `name_html.idx`.

Use

Enter ⇒ **`lwarpmk printindex`**

Enter ⇒ **`lwarpmk htmlindex`**

to compile the indexes.

**For a single index with** memoir **and *xindy*:**

```
\documentclass{memoir}
\usepackage[
    xindy,
    xindyLanguage=english,                  <optional>
    xindyCodepage=utf8,                     <optional>
    latexmk                                 <optional>
]{lwarp}
. . .
\xindyindex
\makeindex
```

The usual `.idx` and `.ind` files will be used, along with the `lwarp.xdy` style file.

*lwarpmk* will use *latexmk* if specified, in which case *latexmk* will create the index automatically. Otherwise, use

Enter ⇒ **`lwarpmk printindex`**

Enter ⇒ **`lwarpmk htmlindex`**

to compile the indexes.

**For multiple indexes with** memoir **and *xindy*, using** latexmk**:**

lwarp's options are used, and are passed to *latexmk*.

```
\documentclass{memoir}
\usepackage[
    xindy,
    xindyLanguage=english,                    <optional>
    xindyCodepage=utf8,                       <optional>
    latexmk
]{lwarp}
. . .
\xindyindex
\makeindex
\makeindex[secondname]
```

*lwarpmk* will use *latexmk* to create the indexes automatically.

**For multiple indexes with** memoir **and *xindy*, *without*** latexmk**:**

*lwarpmk* must be told how to create the indexes:

```
\documentclass{memoir}
\usepackage[
  xindy,
  PrintIndexCmd={
    xindy -M lwarp.xdy -L english -C utf8
      <projectname>.idx ;
    xindy -M lwarp.xdy -L english -C utf8
      secondname.idx
  },
  HTMLIndexCmd={
    xindy -M lwarp.xdy -L english -C utf8
      <projectname>_html.idx ;
    xindy -M lwarp.xdy -L english -C utf8
      secondname_html.idx
  }
]{lwarp}
. . .
\xindyindex
\makeindex
\makeindex[secondname]
```

⚠ Windows *For Windows, replace the four ";" characters with "&".*

`<projectname>` is the `\jobname`: if compiling "`name.tex`", use the filenames `name.idx` and `name_html.idx`.

Use

Enter ⇒ **`lwarpmk printindex`**

Enter ⇒ **`lwarpmk htmlindex`**

to compile the indexes.

### 8.6.20 Using a custom *makeindex* style file

Prog makeindex
File lwarp.ist

When using *makeindex*, *lwarpmk* uses the file `lwarp.ist` to process the index. This file is over-written by lwarp whenever a print version of the document is processed.

To use a custom *makeindex* style file:

1. Copy `lwarp.ist` to a new filename such as `projectname.ist`
2. Make changes to `projectname.ist`. Keep the lines which refer to `\hyperindexref`. These lines creates the hyperlinks for the HTML index. During print output `\hyperindexref` becomes a null function.
3. If changing

   ```
   delim_n -and- delim_r
   ```

   in `projectname.ist`, then in the document preamble redefine

   ```
   \IndexPageSeparator -and- \IndexRangeSeparator
   ```

   to match.

Opt makeindexStyle

4. In the document source use the `makeindexStyle` option for lwarp:

   ```
   \usepackage[
     . . . other options . . .
     makeindex,
     makeindexStyle=projectname.ist,
   ]{lwarp}
   ```

   Likewise, refer to the custom style file if using `\PrintIndexCmd`, `\HTMLIndexCmd`, or `\LatexmkIndexCmd`.
5. Recompile the print version, which causes lwarp to rewrite the `lwarpmk.conf` configuration file. This tells *lwarpmk* to use the custom `projectname.ist` file instead of `lwarp.ist`.

### 8.6.21 Using a custom *xindy* style file

Prog xindy
File lwarp.xdy

When using *xindy*, *lwarpmk* uses the file `lwarp.xdy` to process the index. This file is over-written by lwarp whenever a print version of the document is processed.

To use a custom *xindy* style file:

1. Copy `lwarp.xdy` to a new filename such as `projectname.xdy`
2. Make changes to `projectname.xdy`.

   Keep the lines which refer to `\hyperindexref`:

   ```
   (define-attributes (("hyperindexref")))
   (markup-locref :open "\hyperindexref{" :close "}")
   ...
   (markup-locref :open "\textit{\hyperindexref{" :close "}}" :attr "textit")
   ```

These lines create the hyperlinks for the HTML index. During print output `\hyperindexref` becomes a null function.

To create custom styles, refer to the lines for `\textbf` and `\textit`.

3. If changing any of

```
markup-locref-list :sep
markup-locclass-list :open
markup-locclass-list :sep
markup-crossref-layer-list :sep
markup-range :sep
```

in `projectname.xdy`, then in the document preamble redefine

```
\IndexPageSeparator -and- \IndexRangeSeparator
```

to match.

Opt `xindyStyle`

4. In the document source use the `xindyStyle` option for lwarp:

```
\usepackage[
  . . . other options . . .
  xindy,
  xindyStyle=projectname.xdy,
]{lwarp}
```

Likewise, refer to the custom style file if using `\PrintIndexCmd`, `\HTMLIndexCmd`, or `\LatexmkIndexCmd`.

5. Recompile the print version, which causes lwarp to rewrite the `lwarpmk.conf` configuration file. This tells *lwarpmk* to use the custom `projectname.xdy` file instead of `lwarp.xdy`.

### 8.6.22 Using a custom *xindex* style file

Prog `xindex`

To use a custom *xindex* style file:

⚠ filename

1. Copy `xindex-cfg.lua` to a new filename such as `xindex-projectname.lua`. The filename must start with `xindex-` and end with `.lua`.

2. Make changes to `xindex-projectname.lua`.

3. If changing

```
itemPageDelimiter -and- rangeSymbol
```

in `xindex-projectname.lua`, then in the document preamble redefine

```
\IndexPageSeparator -and- \IndexRangeSeparator
```

to match.

Opt `xindexConfig`

4. In the document source use the `xindexConfig` option for lwarp:

```
\usepackage[
  . . . other options . . .
  xindex,
  xindexConfig=projectname,    % (without xindex- or .lua)
]{lwarp}
```

Likewise, refer to the custom style file if using `\PrintIndexCmd`, `\HTMLIndexCmd`, or `\LatexmkIndexCmd`.

5. Recompile the print version, which causes lwarp to rewrite the `lwarpmk.conf` configuration file. This tells *lwarpmk* to use the custom `xindex-projectname.lua` file instead of the default `xindex-cfg.lua`.

### 8.6.23 Additional indexing limitations

⚠ *xindy* with hyperref

*xindy* and hyperref may not work well together for print output with "see", "see also", reference ranges, or stylized index references. It may be necessary to turn off hyperreferencing for indexes:

```
\usepackage[hyperindex=false]{hyperref}
```

⚠ empty index

If an HTML index is empty, it may be necessary to add the following before lwarp is loaded:

```
\usepackage{morewrites}
\morewritessetup{allocate=10}
. . .
\usepackage{lwarp}
```

*makeindex* custom display styles

When using *makeindex*, custom display styles are possible:

```
\begin{warpprint}
\newcommand{\notesstyle}[1]{#1nn}
\end{warpprint}

\begin{warpHTML}
\makeatletter
\newcommand{\notesstyle}[1]{\LWR@doindexentry{#1} notes }
\makeatother
\end{warpHTML}
. . .
A sentence.\index{key|notesstyle}
```

*xindy* custom display styles

For custom styles with *xindy*, see `lwarp.xdy` for `\textbf` and `\textit` as examples.

### 8.6.24 Index positions, TOC, tocbibind

placement and TOC options

An index may be placed inline with other HTML text, or on its own HTML page:

Pkg makeidx

**Inline, with a manual TOC entry:**

A commonly-used method to introduce an index in a LaTeX document:

```
\cleardoublepage
\phantomsection
\addcontentsline{toc}{section}{\indexname}% or chapter
\printindex
```

Pkg makeidx **On its own HTML page, with a manual TOC entry:**

```
\begin{warpprint}
\cleardoublepage
\phantomsection
\addcontentsline{toc}{section}{\indexname}% or chapter
\end{warpprint}
\ForceHTMLPage
\ForceHTMLTOC
\printindex
```

Pkg tocbibind **Inline, with an automatic TOC entry:**

The tocbibind package may be used to automatically place an entry in the TOC.

```
\usepackage[nottoc]{tocbibind}
. . .
\cleardoublepage
\phantomsection % to fix print-version index link
\printindex
```

Pkg tocbibind **On its own HTML page, with an automatic TOC entry:**

```
\usepackage[nottoc]{tocbibind}
. . .
\cleardoublepage
\phantomsection % to fix print-version index link
\ForceHTMLPage
\printindex
```

Opt [tocbibind] numindex
numbered index section

Use the tocbibind `numindex` option to generate a numbered index. Without this option, the index heading has no number.

Other packages, such as imakeidx, may also have options for including the index in the Table of Contents.

Pkg tocloft
⚠ tocloft & other packages

If using tocloft with tocbibind, anonchap, fncychap, or other packages which change chapter title formatting, load tocloft with its `titles` option, which tells tocloft to use standard LaTeX commands to create the titles, allowing other packages to work with it.

## 8.7 Math

### 8.7.1 Math in section names

⚠ math in section names

If using named HTML files, in section names use paren math `\(x+y\)` instead of dollar math `$x+y$`. (Dollar math works, but appears in the filename.) Or, use a short name for the TOC entry without the math, or use `\texorpdfstring` from the hyperref package:

```
\section{Some math \texorpdfstring{$1+2=3$}{three}}
```

### 8.7.2 Rendering tradeoffs

Math rendering

Math may be rendered as SVG graphics or using the MathJax JavaScript display engine.

SVG files

Rendering math as images creates a new SVG file for each expression, except that an MD5 hash is used to combine identical duplicates of the same inline math expression into a single file, which must be converted to SVG only once. Display math is still handled as individual files, since it may contain labels or references which are likely to change.

SVG inline

The SVG images are currently stored separately, but they could be encoded in-line directly into the HTML document. This may reduce the number of files and potentially speed loading the images, but slows the display of the rest of the document before the images are loaded.

PNG files

Others LaTeX-to-HTML converters have used PNG files, sometimes pre-scaled for print resolution but displayed on-screen at a scaled down size. This allows high-quality print output at the expense of larger files, but SVG files are the preferred approach for scalable graphics.

MathML

Conversion to MathML might be a better approach, among other things allowing a more compact representation of math than SVG drawings. Problems with MathML include limited browser support and some issues with the fine control of the appearance of the result. Also see section 10 regarding EPUB output with MathJax.

### 8.7.3 svg option

SVG math option

For SVG math, math is rendered as usual by LaTeX into the initial PDF file using the current font[14], then is captured from the PDF and converted to SVG graphics via a number of utility programs. The SVG format is a scalable-vector web format, so math may be typeset by LaTeX with its fine control and precision, then displayed or printed at any size, depending on (sometimes broken) browser support. An HTML `alt` attribute carries the LaTeX code which generated the math, allowing copy/paste of the LaTeX math expression into other documents.

SVG image font size

For the `lateximage` environment, the size of the math and text used in the SVG image may be adjusted by setting `\LateximageFontSizeName` to a font size name — *without the backslash*, which defaults to:

```
\renewcommand{\LateximageFontSizeName}{normalsize}
```

For inline SVG math, font size is instead controlled by `\LateximageFontScale`, which defaults to:

```
\newcommand*{\LateximageFontScale}{.75}
```

SVG math copy/paste

For SVG math, text copy/paste from the HTML `<alt>` tags lists the equation number or tag for single equations, along with the LaTeX code for the math expression. For $\mathcal{AMS}$ environments with multiple numbers in the same environment, only the first and last is copy/pasted, as a range. No tags are listed inside a starred $\mathcal{AMS}$ environment, although the `\tag` macro will still appear inside the LaTeX math expression.

⚠ SVG math size, baseline

SVG math sizing and baselines are improved if the graphics or graphicx package is loaded. An almost-invisible marker is placed at either end of the image to assist in cropping and computing the baseline. A warning is issued at the end of the compile if graphics or graphicx are not used.

[14] See section 656 regarding fonts and fractions.

⚠ svg math in TEX boxes

svg math does not work inside TEX boxes, since a \newpage is required before and after each image.

### 8.7.4 MathJax option

MathJax math option

Prog MathJax

The MathJax (mathjax.org) LATEX-math to html converter may be used to display math.

When MathJax is enabled, math is rendered twice:

1. As regular LATEX pdf output placed inside an html comment, allowing equation numbering and cross referencing to be almost entirely under the control of LATEX, and
2. As detokenized printed LATEX commands placed directly into the html output for interpretation by the MathJax display scripts. An additional script is used to pre-set the equation number format and value according to the current LATEX values, and the MathJax equation numbering system is ignored in favor of the LATEX internal system, seamlessly integrating with the rest of the html output, including any math appearing in non-MathJax svg output.

### 8.7.5 Customizing MathJax

equation numbering

lwarp detects and adjusts MathJax equation numbering format for article and book style equations as well as amsmath \numberwithin for chapters, sections, and subsections. Custom equation number formats may be set as follows, for example:

```
\renewcommand*{\theequation}{\Alph{section}.\arabic{equation}}
\AtBeginDocument{
  \renewcommand*{\theMathJaxsection}{\Alph{section}.}
}
```

⚠ subequation

The amsmath subequations environment is supported, but only with \alpha subequation numbering.

global customizations

MathJax does not have preexisting support every possible math function. Additional MathJax function definitions may be defined in the preamble. These will be declared at the start of each html page, and thus will have a global effect across all html pages.

Examples:

```
\begin{warpMathJax}
\CustomizeMathJax{
    \newcommand{\expval}[1]{\langle#1\rangle}
    \newcommand{\abs}[1]{\lvert#1\rvert}
}
\CustomizeMathJax{\newcommand{\arcsinh}{\text{arcsinh}}}
\CustomizeMathJax{\newcommand{\arccosh}{\text{arccosh}}}
\CustomizeMathJax{\newcommand{\NN}{\mathbb{N}}}
\end{warpMathJax}
```

⚠ slow compilation

To avoid a slowdown in compile speed, use the warpMathJax environment to prevent its contents from being processed in print or svg math output. Also, place each new definition

inside its own \CustomizeMathJax. A warning to this effect is issued if an overly-long definition is attempted.

lwarp already provides MathJax customizations for some packages.

siunitx When using siunitx, a similar process may be used to add custom units:

```
\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\myunit}{\mathrm{WXYZ}}}
\CustomizeMathJax{\newcommand{\umyunit}{\mathrm{\micro\myunit}}}
\end{warpMathJax}
```

advanced control For more advanced control over dynamically creating custom definitions, see as an example the lwarp definition for \DeclarePairedDelimiterX, in section 386, mathtools.

local customizations For customizations local to the current HTML page only, macros may be defined as follows:

```
\begin{warpMathJax}
\( \newcommand{\macroname}{. . . } \)
\( \newcommand{\anothername}{. . . } \)
\end{warpMathJax}
```

To maintain compile speed, use the warpMathJax environment, and use a separate math environment for each definition.

\ifstar For MathJax, use \ifstar instead of \@ifstar:

```
\CustomizeMathJax{
  \def\myname{
    \ifstar\starredaction\unstarredaction
    % (Do not place anything after!)
  } }
```

\ifnextchar For MathJax, use \ifnextchar instead of \@ifnextchar:

```
\CustomizeMathJax{\def\myname{\ifnextchar X \found\notfound}}
```

"X" may be a single ASCII character, or a hex number inside braces, ex:

```
\CustomizeMathJax{\def\myname{\ifnextchar{0x7B}\found\notfound}}
```

Use "(" or "{0x28}" for a left parenthesis, "{0x7B}" for a left brace, "{0x7D}" for a right brace, or "{0x5C}" for a backslash.

### 8.7.6 MathJax limitations

MathJax limitations Limitations when using MathJax include:

Prog MathJax

⚠ \multicolumn, multirow

- MathJax does not support \multicolumn or multirow. These may be used in text tabulars or SVG math, but in MathJax math arrays they are emulated. \multicolumn only fills a single cell, resulting in a short row. \multirow simply prints its text on the first line.

⚠ footnotes

- Footnotes are emulated when used inside a MathJax expression. For an equation with a single footnote, the correct footnote number is used. For non-equations,

\footnotename is used instead, since the actual number cannot be tracked. See section 8.5.4 regarding the use of footnotes with MathJax.

⚠ references

- Inside a MathJax expression, references to equations work within the same HTML web page, but do not work when referring to an equation in a different HTML web page. Outside of a MathJax expression, in the text body, references work as expected.

lateximage

- Math appearing inside a lateximage, and therefore also inside a Ti*k*z or picture environment, is rendered as SVG math even if MathJax is used in the rest of the document.

siunitx

- For siunitx, see siunitx package, section 8.7.12.

physics

- For physics, see physics package, section 8.7.14.

tabbing

- A tabbing environment is emulated using an HTML <pre>. While MathJax is enabled inside tabbing, the browser may not correctly render the horizontal alignment of the math and text following after on the same line.

\text

- MathJax includes the *textmacros* extension, which supports various macros which are commonly used inside \text, such as \textbf and text accents. Lwarp supports this extension.

⚠ other macros and packages

- Many other math-related macros and packages are not directly supported by MathJax, including \ensuremath and occasionally-used macros such as \relax. While using MathJax, lwarp provides emulation for many of these macros, as well as for footnotes and emulation for dozens of packages (see table 2). In many cases these emulations simply ignore the package in a source-compatible way. Others produce a result which represents the meaning, even if they don't look exact. Look up each package in this document for a description of the limitations of each.

### 8.7.7 Catcode changes

preamble macros with math

The math shift character $ is not set for HTML output until after the preamble. Macros defined in the preamble which contain $ must be enclosed between \StartDefiningMath and \StopDefiningMath to temporarily change to the HTML meaning of $:

```
\StartDefiningMath
\newcommand{. . .}
\StopDefiningMath
```

As an alternative, use \( and \) instead of $, in which case \StartDefiningMath and \StopDefiningMath are not necessary.

If a package defines macros using $, it may be nessary to use \StartDefiningMath and \StopDefiningMath before and after loading the package.

### 8.7.8 Complicated inline math objects

\inlinemathnormal
\inlinemathother

changing contents

An inline math expression is usually converted to a reusable hashed SVG math image, or a MathJax expression. The hash or expression depends on the contents of the math expression. In most cases this math expression is static, such as $x+1$, so the image can be reused for multiples instances of the same expression. In some cases, the math

complicated alt tag
MathJax limitations

expression includes a counter or other object which may change between uses. Another problem is complicated contents which do not expand well in an alt tag. Yet another problem is math packages which are only partially emulated in MathJax. The macro \inlinemathother may be used before a sequence of dynamic or complicated math expressions, and \inlinemathnormal after. Doing so tells lwarp to use unhashed SVG math images for those particular expressins, even if MathJax is otherwise in use. See section 44.

### 8.7.9 Complicated display math objects

\displaymathnormal

By default, or when selecting \displaymathnormal, MathJax math display environments print their contents as text into HTML for MathJax to interpret, and SVG display math environments render their contents as SVG images and use their contents as the alt tag of HTML output. To do so, the contents are loaded into a macro for reuse. In some cases, such as complicated Ti*k*z pictures, compilation will fail.

\displaymathother
MathJax unsupported
complicated alt tag

When selecting \displaymathother, it is assumed that the contents are more complicated than "pure" math. An example is an elaborate Ti*k*z picture, which will not render in MathJax and will not make sense as an HTML alt tag. In this mode, MathJax is turned off, math display environments become SVG images, even if MathJax is selected, and the HTML alt tags become simple messages. The contents are internally processed as an environment instead of a macro argument, so complicated objects such as Ti*k*z pictures are more likely to compile successfully.

### 8.7.10 ntheorem package

Pkg ntheorem

⚠ Font control

This conversion is not total. Font control is via CSS, and the custom LaTeX font settings are ignored.

⚠ cref reference format undefined

If the print version does not use cleveref, place all \theoremstyle and \newtheorem declarations in the preamble inside \AtBeginDocument.[15] For some theorems, it may also be required to add inside \AtBeginDocument something such as:

```
\AtBeginDocument{ % if not using cleveref package
  \theoremstyle{definition}
  \newtheorem{dtheorem}{Definition}
  . . .
  \usepackage{etoolbox} % for \ifdef
  \ifdef{\cref}{
    \crefname{Proof}{Proof}{Proofs}
  }{}
}
```

⚠ Equation numbering

ntheorem has a bug with equation numbering in $\mathcal{AMS}$ environments when the option thref is used. lwarp does not share this bug, so equations with \split, etc, are numbered correctly with lwarp's HTML output, but not with the print output. It is recommended to use cleveref instead of ntheorem's thref option.

[15] lwarp uses cleveref for the HTML conversion, and loads cleveref \AtEndPreamble, just before \AtBeginDocument.

### 8.7.11 mathtools package

Pkg mathtools

⚠ equation numbering

`showonlyrefs` is disabled, as it conflicts with cleveref, which is used by lwarp. Equation numbers may not match the print version.

⚠ italic correction

`mathic` is not emulated for HTML.

⚠ MathJax

If using MathJax:

- mathtools `disallowspaces` does not work for MathJax. Protect brackets which are not optional arguments, such as:

```
\begin{gathered}{}
[p]=1 . . .
\end{gathered}
```

- `showonlyrefs` does not work in MathJax, and will result in a difference in equation numbering compared to the print version.
- Due to MathJax limitations, the following do not render well: `\overbracket`, `\underbracket`, `\overbrace`, `\underbrace`, `rcases`, `drcases`, `\Aboxed`, and `\ArrowBetweenLines`.
- For the new `cases`-like environments, `\text` must be used to set the normal roman font if desired.
- `alignat` in MathJax requires math mode, but in LaTeX it doesn't. It may be required to use `warpHTML` and `warpprint` to isolate a version for each mode.
- `\DeclarePairedDelimiter` and related must be in the preamble before `\begin{document}`.

### 8.7.12 siunitx package

Pkg siunitx

fractions

Due to *pdftotext* limitations, fraction output is replaced by symbol output for `per-mode` and `quotient-mode`.

⚠ math mode required

Some units will require that the expression be placed inside math mode.

⚠ tabular

Tabular `S` columns are rendered as simple `c` columns, and tabular `s` columns are not supported. These may be replaced by `c` columns with each cell contained in `\num` or `\si`.

⚠ MathJax

For math mode with SVG display, the original siunitx code is used while generating the SVG image. For text mode, lwarp uses an emulation which provides a very effective HTML interpretation of siunitx. For math expressions while using MathJax, a limited emulation is used. Most functions work reasonably well, but many options cannot be emulated. Complicated parsing such as for `\ang` is not supported. The result usually looks fine, and otherwise is enough to get the meaning across.

Document modifications required for MathJax:

custom units

- Custom units may be added with `\CustomizeMathJax`. See the lwarp-siunitx code for examples.

⚠ unit spacing

- Units work better using ~ between units instead of using periods.

⚠ \square, \cubic

- To square or cube compound units, enclose the following compound units in braces:

```
\cubic{\centi\meter}
```

  Single units do not require braces.

Also see MathJax option, section 8.7.4.

### 8.7.13 units and nicefrac packages

Pkg units
Pkg nicefrac

units and nicefrac work with lwarp, but MathJax does not have an extension for units or nicefrac. These packages do work with lwarp's option svgmath.

### 8.7.14 physics package

Pkg physics

physics works as-is for HTML with SVG math.

For MathJax, the MathJax v3 physics extension is used.

## 8.8 Graphics

Pkg graphics
Pkg graphicx
⚠ scale

Avoid using the \includegraphics scale option. Change:

```
\includegraphics[scale=<xx>]{ . . . }
```

to:

```
\includegraphics[width=<yy>\linewidth]{ . . . }
```

\includegraphics file formats

For \includegraphics with .pdf or .eps files, the user must provide a .pdf or .eps image file for use in print mode, and also a .svg, .png, or .jpg version of the same image for use in HTML.

```
\includegraphics{filename} % print:.pdf/.eps HTML:.svg, etc.
```

For print output, lwarp will automatically choose the .pdf or .eps format if available, or some other format otherwise. For HTML, one of the other formats is used instead.

If a .pdf or .eps image is referred to with its file extension, the extension will be changed to .svg for HTML:

```
\includegraphics{filename.pdf} % uses .svg in html
\includegraphics{filename.eps} % uses .svg in html
```

Prog pdftocairo
PDF to SVG

To convert a PDF image to SVG, use the utility *pdftocairo*:

Enter ⇒ **pdftocairo -svg filename.pdf**

Prog lwarpmk pdftosvg

For a large number of images, use *lwarpmk*:

Enter ⇒ **`lwarpmk pdftosvg *.pdf`** **(or a list of filenames)**

Prog `lwarpmk epstopdf` For EPS images converted to PDF using the package epstopdf, use

Prog epstopdf
epstopdf package

Enter ⇒ **`lwarpmk pdftosvg *.PDF`**

to convert to SVG images.

DVI LaTeX When using DVI *latex*, it is necessary to convert EPS to PDF and then to SVG:

Enter ⇒ **`lwarpmk epstopdf *.eps`** **(or a list of filenames)**

Enter ⇒ **`lwarpmk pdftosvg *.pdf`** **(or a list of filenames)**

PNG and JPG For PNG or JPGwhile using *pdflatex*, *lualatex*, or *xelatex*, the same file may be used in both print or HTML versions, and may be used with a file extension, but will also be used without the file extension if it is the only file of its base name.

GIF GIF files may be used for HTML, but another format must also be provided for print output.

file extension priorities If a file extension is not used, for HTML the file extension priorities are: SVG, GIF, PNG, then JPG.

⚠ graphics vs. graphicx If using the older graphics syntax, use both optional arguments for `\includegraphics`. A single optional parameter is interpreted as the newer graphicx syntax. Note that viewports are not supported by lwarp — the entire image will be shown.

⚠ viewport

⚠ viewport units For `\includegraphics`, avoid `px` and `%` units for width and height, or enclose them inside `warpHTML` environments. For font-proportional image sizes, use `ex` or `em`. For fixed-sized images, use `cm`, `mm`, `in`, `pt`, or `pc`. Use the keys `width=.5\linewidth`, or similar for `\textwidth` or `\textheight` to give fixed-sized images proportional to a 6 by 9 inch text area. Do not use the `scale` option, since it is not well supported by HTML browsers.

options `\includegraphics` accepts `width` and `height`, `origin`, `rotate` and `scale`, plus new `class` and `alt` keys.

HTML class With HTML output, `\includegraphics` accepts an optional `class=xyz` keyval combination, and if this is given then the HTML output will include that class for the image. The class is ignored for print output.

HTML `alt` tags Likewise, the `\includegraphics` `alt` key adds an HTML `alt` tag to an image, and is ignored for print output. If not assigned, each image is given an `alt` tag according to `\ImageAltText`.

`\rotatebox` `\rotatebox` accepts the optional `origin` key.

⚠ browser support `\rotatebox`, `\scalebox`, and `\reflectbox` depend on modern browser support. The CSS3 standard declares that when an object is transformed the whitespace which they occupied is preserved, unlike LaTeX, so expect some ugly results for scaling and rotating.

### 8.8.1 tikz package

Pkg `tikz` If using display math with `tikzpicture` or `\tikz`, along with matrices with the & character,

⚠ displaymath and matrices the document must be modified as follows:

```
\usepackage{tikz}
\tikzset{every picture/.style={ampersand replacement=\&}}
```

and each instance of & in the tikz expression must be replaced with \&.

### 8.8.2 grffile package

Pkg grffile

⚠ matching PDF and SVG

grffile is supported as-is. File types known to the browser are displayed, and unknown file types are given a link. Each PDF image for print mode should be accompanied by an SVG, PNG, or JPG version for HTML.

### 8.8.3 color package

Pkg color

color is superceded by xcolor, and lwarp requires several of the features of xcolor. When color is requested, xcolor is loaded as well.

### 8.8.4 xcolor package

Pkg xcolor

\colorboxBlock and \fcolorboxBlock

\colorboxBlock and \fcolorboxBlock are provided for increased HTML compatibility, and they are identical to \colorbox and \fcolorbox in print mode. In HTML mode they place their contents into a  instead of a . These s are set to display: inline-block so adjacent \colorboxBlocks appear side-by-side in HTML, although text is placed before or after each.

Print-mode definitions for \colorboxBlock and \fcolorboxBlock are created by lwarp's core if xcolor is loaded.

background: none

\fcolorbox and \fcolorboxBlock allow a background color of none, in which case only the frame is drawn, which can be useful for HTML.

color support

Color definitions, models, and mixing are fully supported without any changes required.

colored tables

\rowcolors is supported, except that the optional argument is ignored so far.

colored text and boxes

\textcolor, \colorbox, and \fcolorbox are supported.

\color and \pagecolor

\color and \pagecolor are ignored. Use CSS or \textcolor where possible.

### 8.8.5 epstopdf package

Pkg epstopdf

⚠ convert to .svg

Images with an .eps extension will be converted to .pdf. The HTML output uses the .svg version, so use

Enter ⇒ **lwarpmk pdftosvg <listofPDFfiles>**

to generate .svg versions.

### 8.8.6 pstricks package

Pkg pstricks

⚠ use pspicture

All pstricks content should be contained inside a pspicture environment.

### 8.8.7 pdftricks package

Pkg pdftricks

⚠ convert image files

The pdftricks image files <jobname>-fig*.pdf must be converted to .svg, or else a missing file error will occur. The image files must also be converted again whenever they change. To convert the images:

Enter ⇒ **lwarpmk pdftosvg <jobname>-fig*.pdf**

### 8.8.8 psfrag package

Pkg psfrag

⚠ use psfrags

The psfrags environment is modified to use lateximage to encapsulate the image. Always use a psfrags environment to contain any local \psfrag macros and the associated \includegraphics or \epsfig calls. Outside of a psfrags environment, psfrags adjustments will not be seen by lwarp.

⚠ Tip: Use a mono-spaced font for the tags in the EPS file.

### 8.8.9 pstool package

Pkg pstool

⚠ path and filename

\graphicspath is ignored, and the file directory must be stated.

The filename must not have a file extension.

Use

Enter ⇒ **lwarpmk html**

followed by

Enter ⇒ **lwarpmk limages**

.

### 8.8.10 asymptote package

Pkg asymptote

To compile:

```
pdflatex project.tex
asy project-*.asy
pdflatex project.tex

lwarpmk print
asy project-*.asy
lwarpmk print1
lwarpmk print1

lwarpmk html
asy project_html-*.asy
lwarpmk html1
lwarpmk html1
lwarpmk limages
```

### 8.8.11 overpic package

Pkg overpic

⚠ scaling

The macros `\overpicfontsize` and `\overpicfontskip` are used during HTML generation. These are sent to `\fontsize` to adjust the font size for scaling differences between the print and HTML versions of the document. Renew these macros before using the `overpic` and `Overpic` environments.

### 8.8.12 Multimedia packages

Pkg multimedia

Pkg movie15

Pkg media9

The packages multimedia, movie15, and media9 are supported.

HTML5 <audio> and <video> objects are created for `.mp3` and `.mp4` files.

HTML5 <embed> objects are created for `http` and `ftp` links.

`\href` links are created for other media types. (Unfortunately, there is not much overlap between the file types supported for print output and the file types supported by HTML5.)

For media9, a multimedia object is inserted for each `addresource=`, as well as each `flashvars` `source=` and `src=`. This may result in duplicate objects.

Undesired objects may be nullified by placing them inside `\warpprintonly` or the `warpprint` environment.

Each HTML multimedia object includes the poster text, except for <embed> objects. For movie15, the `text` option is supported to specify the poster text.

The `width`, `height`, and `totalheight` options are supported. The HTML object is scaled according to the display width, correctly compensating for either tall or wide viewports.

Other options are ignored.

media9 \addmediapath is supported. It is assumed that the same path structure will exist for the HTML document.

HTML5 media controls are always specified for each <audio> and <video> object.

media9 slideshows are not supported.

\hyperlinkmovie, \movieref, and \mediabutton are not supported.

3D objects are not supported.

If using a YouTube™ video, use an "embedded" URL with .../embed/... instead of .../v/...

## 8.9 Tabbing

The tabbing environment works, except that SVG math and lateximages do not yet work inside the environment.

⚠ math in tabbing

If math is used inside tabbing, place tabbing inside a lateximage environment, which will render the entire environment as a single SVG image.

## 8.10 Tabular

### 8.10.1 tabular environment

Tabular mostly works as expected, but pay special attention to the following, especially if working with environments, macros inside tabulars, multirows, siunitx S columns, or the packages multirow, longtable, supertabular, or xtab.

**Defining macros and environments:**

⚠ Misplaced alignment tab character &

- When defining environments or macros which include tabular and instances of the & character, it may be necessary to make & active before the environment or macro is defined, then restore & to its default catcode after, using the following commands. These are are ignored in print mode.

```
\StartDefiningTabulars
<define macros or environments using tabular and & here>
\StopDefiningTabulars
```

⚠ floatrow

This includes before and after defining any macro which used \ttabbox from floatrow.

⚠ tabular inside another environment

- When creating a new environment which contains a tabular environment, lwarp's emulation of the tabular does not automatically resume when the containing enviroment ends, resulting in corrupted HTML rows. To fix this, use \ResumeTabular as follows. This is ignored in print mode.

```
\StartDefiningTabulars %   (& is used in a definition)
\newenvironment{outerenvironment}
{
  \tabular{cc}
  left & right \\
}
{
  \TabularMacro\ResumeTabular
  left & right \\
  \endtabular
}
\StopDefiningTabulars
```

For developers:

- To automate the use of \StartDefiningTabulars and \EndDefiningTabulars, these macros may be embedded inside an HTML environment definition to automatically change the catcode of & before absorbing the arguments. Another environment may be embedded as well.

```
% Does the work after the catcode has been changed:
\newcommand*{\LWR@HTML@subsomename}[2]{%
  . . .
  \otherenvironmentname [<args>] {<args>}  % for example
}
% Change catcode before absorbing arguments:
\newcommand*{\LWR@HTML@somename{%
  \StartDefiningTabulars
  \LWR@HTML@subsomename
}
% Change catcode again at the end:
\newcommand*{\LWR@HTML@endsomename}{%
  . . .
  \endotherenvironmentname   % for example
  \StopDefiningTabulars
}
% Combine with the existing print definition:
\LWR@formattedenv{somename}
```

**Cell contents:**

⚠ macro in a table

- Using a custom macro inside a tabular data cell may result in an extra HTML data cell tag, corrupting the HTML table. To avoid this, use \TabularMacro just before the macro. This is ignored in print mode.

```
\TabularMacro\somemacro & more row contents \\
```

**Column specifiers:**

@ and !

- Only one each of @ and ! is used at each column, and they are used in that order.

\multirow

- In \multirow cells, the print version may have extra instances of <, >, @, and ! cells on the second and later rows in the \multirow which do not appear in the HTML version.

⚠ \newcolumntype

- \newcolumntype is ignored; unknown column types are set to l.

**Rules:**

- Doubled `\hlines`, `\midrules`, and vertical rules are supported.

vertical rules

- Vertical rules next to either side of an `@` or `!` column are displayed on both sides of the column.

width and trim

- Width options are honored. Trim options are converted to rounded top corners. Trim corners are not rounded with `@` or `!` columns, and full-width rules ignore trim. When given an optional width, each cell is styled to create the custom border. Without an optional width, the entire row is given a class to assign the standard border.

combined rules

- If you wish to use `\cmidrule` followed by `\bottomrule`, it may be necessary to use:

```
\cmidrule{2-3} \\[-2ex]
\bottomrule
```

The optional `-2ex` is ignored in HTML, but improves the visual formatting in the print output.

⚠ `\warpprintonly`
⚠ Misplaced `\noalign`

- For `\toprule` and `\bottomrule`, when combined with a `warpprint` or `warpHTML` environment, if a "Misplaced `\noalign`" error occurs, change

```
This & That \endhead
```

to

```
\warpprintonly{This & That \endhead}
```

and likewise with the other `\end` headings. Keep the `\endfirsthead` row unchanged, as it is still relevent to HTML output.

**Other:**

- tabularx ignores the width, but `X` columns do produce paragraph columns or multicolumns.

`longtable` headings

- For longtable, place headings and footings which do not apply to HTML inside `\warpprintonly{}`.

⚠ S columns

- For S columns (from the siunitx package), while producing print output, anything non-numeric must be placed inside { } braces, including commands such as `\multirow`. While producing HTML output, though, anything placed inside braces is not seen by lwarp's tabular handling algorithm. To resolve this problem, make a copy of the row, with one version for print output, containing the extra braces, and another version for HTML output, without the extra braces, such as:

```
\warpprintonly{1 & 2 & {\multirow{2}{2cm}{Text}} & 3 \\}
\warpHTMLonly{1 & 2 & \multirow{2}{2cm}{Text} & 3 \\}
```

⚠ `tabular` inside a `<span>`

- In LaTeX, a `tabular` may be placed inside a `minipage`, but in HTML a `<table>` may not be inside a `<span>`. If this situation is detected, a warning is printed instructing the user to isolate the `<span>` using `\warpprintonly` or the `warpprint` environment.

### 8.10.2 multirow package

vposn

- Note that recent versions of multirow include a new optional vposn argument.

multirow cells

- For multirow, insert `\mrowcell` into any empty multi-row cells. This will be a null function for the print output, and is a placeholder for parsing the table for HTML output. An error is generated if this is missed.

```
. . . &   \multirow{2}{.5in}{text}   & . . .
. . . &   \mrowcell                  & . . .
```

colored cells

- The multirow documentation regarding colored cells recommends using a negative number of rows. This will not work with lwarp, so \warpprintonly and \warpHTMLonly must be used to make versions for print and HTML.

with \multicolumn

- See section 416.2 for \multicolumnrow.

⚠ \multicolumn & \multirow

lwarp does not support directly combining \multicolumn and \multirow. Use \multicolumnrow instead. To create a 2 column, 3 row cell:

```
\multicolumnrow{2}{c}[c]{3}[0]{1in}[0pt]{Text}
```

The two arguments for \multicolumn come first, followed by the five arguments for \multirow, many of which are optional, followed by the contents.

⚠ skipped cells

As per \multirow, skipped cells to the right of the \multicolumnrow statement are not included in the source code on the same line. On the following lines,

⚠ empty cells

\mcolrowcell must be used for each cell of each column and each row to be skipped. An error is generated if this is missed.

```
. . . &   \multicolumnrow{2}{c}[c]{3}[0]{1in}[0pt]{Text}   & . . .
. . . &   \mcolrowcell          &          \mcolrowcell     & . . .
. . . &   \mcolrowcell          &          \mcolrowcell     & . . .
```

⚠ MathJax

- MathJax does not support multirow, so it is emulated to only print its text on the first row. \multirow works as expected in text tabulars or SVG math.

### 8.10.3 longtable package

Pkg longtable

Use one of either \endhead or \endfirsthead for both print and HTML, and use a \warpprintonly macro to disable the other head phrase, and also the \endfoot and \endfirstfoot phrases. (See section 8.10.4 if using threeparttablex.)

```
\begin{longtable}{ [column specifiers] }
[ . . . ] \endfirsthead   % or \endhead, for print and HTML
\warpprintonly{          % not used in HTML
  [ . . . ] \endhead     % or \endfirsthead
  [ . . . ] \endfoot
  [ <lastfoot macros> ] \endlastfoot
}
. . .  table contents . . .
\warpHTMLonly{
  [ <lastfoot macros> ]   % HTML last footer, without \endfoot
                                                % or \endlastfoot.
}
\end{longtable}
```

⚠ Misplaced \noalign

Use the \warpprintonly macro instead of the warpprint environment. Doing so helps avoid "Misplaced \noalign." when using \begin{warpprint}.

⚠ \kill

\kill is ignored, place a \kill line inside

```
\begin{warpprint} . . .  \end{warpprint}
```

or place it inside \warpprintonly.

⚠ lateximage longtable is not supported inside a lateximage.

### 8.10.4 threeparttablex package

Pkg threeparttablex threeparttablex is used with longtable and booktabs as follows:

```
\begin{longtable}{ [column specifiers] }
[ . . . ] \endfirsthead   % or \endhead, for print and HTML
\warpprintonly{          % not used in HTML
  [ . . . ] \endhead     % or \endfirsthead
  [ . . . ] \endfoot
  \bottomrule \insertTableNotes \endlastfoot
}
. . .  table contents . . .
\warpHTMLonly{   % HTML last footer
  \bottomrule
  \UseMinipageWidths     % optional
  \insertTableNotes
  \endlastfoot
}
\end{longtable}
```

table width The table notes are created using a \multicolumn. By default the width is not specified to the browser, so long table notes can cause the table to be spread out horizontally. For HTML output, lwarp guesses the width of the table depending on the number of columns, then restricts its guess to a min/max range. To use this guess for the width of the table notes, use \UseMinipageWidths before \insertTableNotes. The width is then specified, and in many cases the result is an improvement in overall table layout.

### 8.10.5 supertabular and xtab packages

Pkg supertabular For \tablefirsthead, etc., enclose them as follows:

Pkg xtab

⚠ Misplaced alignment tab character &

```
\StartDefiningTabulars
\tablefirsthead
. . .
\StopDefiningTabulars
```

See section 8.10.1.

⚠ lateximage supertabular and xtab are not supported inside a lateximage.

### 8.10.6 colortbl package

Pkg colortbl Only use \rowcolor and \cellcolor at the start of a row, in that order.

⚠ row/cell color colortbl ignores the overhang arguments.

### 8.10.7 ctable package

⚠ Misplaced alignment tab character & Use\StartDefiningTabulars before one or more\ctable s, and\StopDefiningTabulars after. These change the meaning of the ampersand&character.

### 8.10.8 bigdelim package

Pkg bigdelim

⚠ use\mrowcell

\ldelim and\rdelim use\multirow , so\mrowcell must be used in the proper number of empty cells in the same column below\ldelim or \rdelim , but not in cells which are above or below the delimiter:

```
\begin{tabular}{lll}
<empty> & a & b \\
\ldelim{\{}{3}{.25in}[left ] & c & d \\
\mrowcell & e & f \\
\mrowcell & g & h \\
<empty> & i & j \\
\end{tabular}
```

| | | |
|---|---|---|
| <-> | a | b |
| | c | d |
| left | e | f |
| | g | h |
| <-> | i | j |

For MathJax , limited emulation is provided which merely prints the delimter and optional text in the rst row.

## 8.11 Floats

### 8.11.1 Float contents alignment

⚠ figure & table alignment

\centering , etc. are honored in a figure or table if they are the rst command inside the oat:

```
\begin{table*}
\centering
\caption{A Table}
. . .
```

### 8.11.2 float , trivfloat , and/or algorithmicx together

Pkg float

Pkg trivfloat

Pkg algorithmicx

⚠ package con icts

If using \newfloat , trivfloat, and/or algorithmicx together, see section 616.1.

```
\ifxetexorluatex
\else
    \ifdefstring{\f@family}{cmr}{
        \IfFileExists{type1ec.sty}% found in cm-super
        {}
        {% cm-super not installed
            \IfFileExists{lmodern.sty}{
                \PackageInfo{lwarp}{cm-super not installed, loading lmodern}
                \RequirePackage{lmodern}
            }{
                \PackageError{lwarp}
                {%
                    Lwarp requires a vector font.\MessageBreak
                   Install and load cm-super, lmodern, or another\MessageBreak
                    Type-1 vector font before loading lwarp.\MessageBreak
                    Enter 'H' for possible solutions%
                }
                {%
                    Install cm-super or lmodern.\MessageBreak
                    If lmodern, load it before lwarp:\MessageBreak
                        \space\space\protect\usepackage{lmodern}\MessageBreak
                        \space\space\protect\usepackage{lwarp}%
                }
            }
        }% cm-super not installed
    }{}% f@family
\fi
```

# 25 Upright quotes

In pdfTeX, preserve upright quotes in verbatim text. upquote also loads textcomp.

```
\ifPDFTeX
\RequirePackage{upquote}
\fi

\ifpTeX
    \RequirePackage{upquote}
\fi
```

# 26 Avoid bad font combinations

For XeLaTeX and LuaLaTeX, certain font combinations cause problems with lwarp.

libertinus-otf has special handling for `\textquotedbl`. Search for `\LWR@orig@textquotedbl`.

```
\ifxetexorluatex
    \AtBeginDocument{
        \@ifpackageloaded{kpfonts}{
            \PackageError{lwarp}
```

```
                {%
                    When using XeLaTeX or LuaLaTeX,\MessageBreak
                    use kpfonts-otf instead of kpfonts%
                }
                {%
                    Replace: \protect\usepackage{kpfonts}\MessageBreak
                    with: \protect\usepackage{kpfonts-otf}
                }
        }{}
    }
\fi
```

# 27 Miscellaneous tools

## 27.1 Variables

```
\newlength{\LWR@templengthone}
\newlength{\LWR@templengthtwo}

```

## 27.3 Counters

\defaddtocounter {⟨*name*⟩} {⟨*value*⟩}

Locally add to a counter.

```
\providecommand*{\defaddtocounter}[2]{%
    \defcounter{#1}{\value{#1}+#2}%
}
```

## 27.4 Patching

\LWR@patcherror {⟨*packagename*⟩} {⟨*macroname*⟩}

Prints an error if could not patch a macro.

```
\newcommand*{\LWR@patcherror}[2]{%
    \PackageError{lwarp}%
        {%
            Unable to patch package #1,\MessageBreak
            macro \LWRbackslash #2.\MessageBreak
            Lwarp or #1 may need to be updated%
        }%
        {Please contact the maintainer of the Lwarp package.}%
}
```

## 27.5 Chinese text isolation

\LWR@isolate {⟨*text*⟩} Isolates Chinese characters from the surrounding text. This is required to avoid extra spaces on either side of the Chinese characters, especially when written to a file.

```
\newcommand{\LWR@isolate}[1]{#1}%

\@ifpackageloaded{ctexpatch}{
    \renewcommand{\LWR@isolate}[1]{\null#1\null}%
}{}

\@ifpackageloaded{xeCJK}{
    \renewcommand{\LWR@isolate}[1]{\null#1\null}%
}{}
```

\LWR@disablepinyin Disable xpinyin during file, sideTOC, and footnote generation. Set by xpinyin.

```
\newcommand*{\LWR@disablepinyin}{}
```

## 27.6 Inserting vertical space

\LWR@forceemptyline Extra vertical space in the HTML output. Use after \LWR@stoppars.

```
\newcommand*{\LWR@forceemptyline}{%
    \LWR@origrule{0pt}{1\baselineskip}%
    \LWR@orignewline%
}
```

## 27.7 Argument selection

\LWR@firstoffour {⟨*first*⟩} {⟨*second*⟩} {⟨*third*⟩} {⟨*fourth*⟩}

\LWR@secondoffour {⟨*first*⟩} {⟨*second*⟩} {⟨*third*⟩} {⟨*fourth*⟩}

\LWR@thirdoffour {⟨*first*⟩} {⟨*second*⟩} {⟨*third*⟩} {⟨*fourth*⟩}

\LWR@fourthoffour {⟨*first*⟩} {⟨*second*⟩} {⟨*third*⟩} {⟨*fourth*⟩}

Expands to the nth of the four arguments. Used for extra cross referencing.

```
\long\def\LWR@firstoffour#1#2#3#4{#1}
\long\def\LWR@secondoffour#1#2#3#4{#2}
\long\def\LWR@thirdoffour#1#2#3#4{#3}
\long\def\LWR@fourthoffour#1#2#3#4{#4}
```

## 27.8 Inside boxes

Greater than zero if currently inside a TEX box, thus should not use \LWR@orignewpage. See section 13.2.

```
\newcounter{LWR@texboxdepth}
\setcounter{LWR@texboxdepth}{0}
```

\LWR@maybe@orignewpage Only do \LWR@orignewpage if not inside a TEX box.

```
\newcommand*{\LWR@maybe@orignewpage}{%
    \LWR@traceinfo{LWR@maybe@orignewpage}%
    \ifnumgreater{\value{LWR@texboxdepth}}{0}
        {}%
        {\LWR@orignewpage}%
    \LWR@traceinfo{LWR@maybe@orignewpage done}%
}
```

## 27.9 Global boxes

\LWR@gsavebox {⟨*macroname*⟩} {⟨*contents*⟩}

From https://tex.stackexchange.com/questions/288702/savebox-forgets-its-content-across-columns-inside-align

```
\DeclareRobustCommand\LWR@gsavebox[1]{%
```

```
  \@ifnextchar(%)
    {\LWR@@gsavepicbox#1}{\@ifnextchar[{\LWR@@gsavebox#1}{\LWR@gsbox#1}}}%
\long\def\LWR@gsbox#1#2{\global\setbox#1\hbox{%
  \color@setgroup#2\color@endgroup}}
\def\LWR@@gsavebox#1[#2]{%
  \@ifnextchar [{\LWR@@igsavebox#1[#2]}{\LWR@@igsavebox#1[#2][c]}}
\long\def\LWR@@igsavebox#1[#2][#3]#4{%
  \LWR@gsbox#1{\@imakebox[#2][#3]{#4}}}
\def\LWR@@gsavepicbox#1(#2,#3){%
  \@ifnextchar[%]
    {\LWR@@igsavepicbox#1(#2,#3)}{\LWR@@igsavepicbox#1(#2,#3)[]}}
\long\def\LWR@@igsavepicbox#1(#2,#3)[#4]#5{%
  \LWR@gsbox#1{\@imakepicbox(#2,#3)[#4]{#5}}}
```

Env `LWR@glrbox` {⟨*macroname*⟩}

```
\def\LWR@glrbox#1{%
  \edef\reserved@a{%
    \endgroup
    \global\setbox#1\hbox{%
      \begingroup\aftergroup}%
        \def\noexpand\@currenvir{\@currenvir}%
        \def\noexpand\@currenvline{\on@line}}%
  \reserved@a
    \@endpefalse
    \color@setgroup
      \ignorespaces}
\let\LWR@endglrbox\LWR@endlrbox
```

## 27.10 Converting a macro name to a cs name

`\macrotocsname` {⟨*macro name with backslash*⟩}

Results in the macro name without the leading backslash.

Ref: https://tex.stackexchange.com/questions/42318/removing-a-backslash-from-a-character-sequence

```
\newcommand*{\macrotocsname}[1]{%
  \ifcat\relax\noexpand#1%
    \expandafter\expandafter\expandafter\@gobble\expandafter\string
  \fi
  #1%
}
```

## 27.11 Title case

`\LWRtexttitlecase`

```
\ExplSyntaxOn
\newcommand*{\LWRtexttitlecase}[1]{%
```

The literal $ character:

```
\catcode`\$=12
\def\LWRdollar{$}
\catcode`\$=3
```

The literal & character:

```
\catcode`\&=12
\def\LWRamp{&}
\catcode`\&=4
```

The literal \ character. The ampersand is temporarily set to the escape character during the definition of the backslash macro.

```
\catcode`\&=0
&catcode`&\=12
&def&LWRbackslash{\}
&catcode`&\=0
\catcode`\&=4
```

The literal { character. The ampersand is temporarily set to the begin group character during the definition of the leftbrace macro.

```
\catcode`\&=1
\catcode`\{=12
\def\LWRleftbrace&{}
\catcode`\{=1
\catcode`\&=4
```

The literal } character. The ampersand is temporarily set to the end group character during the definition of the leftbrace macro.

```
\catcode`\&=2
\catcode`\}=12
\def\LWRrightbrace{}&
\catcode`\}=2
\catcode`\&=4
```

The literal # character:

```
\catcode`\#=12
\def\LWRhash{#}
\catcode`\#=6
```

`\LWRopquote` The operating system's quote mark, Unix default. For Windows, see `\LWR@setOSWindows`, below.

```
\def\LWRopquote{'}
```

`\LWRopseq` The operating system's sequential execution command, Unix default. For Windows, see `\LWR@setOSWindows`, below.

```
\def\LWRopseq{\space\LWRamp\LWRamp\space\space}
```

## 28.2 Common portability code

Bool usingOSWindows Set if the OSWindows option is used, or if Windows is automatically detected.

```
\newbool{usingOSWindows}
\boolfalse{usingOSWindows}
```

## 28.3 Unix, Linux, and Mac OS

\OSPathSymbol Symbol used to separate directories in a path.

```
\newcommand*{\OSPathSymbol}{/}
```

## 28.4 MS-Windows

For MS-Windows:

\LWR@setOSWindows Set defaults for the MS-Windows operating system. lwarp attempts to auto-detect the operatings system, and the OSWindows option may also be used to force MS-Windows compatibility.

```
\newcommand*{\LWR@setOSWindows}
{
\booltrue{usingOSWindows}
\renewcommand*{\OSPathSymbol}{\@backslashchar}
\def\LWRopquote{"}
\def\LWRopseq{\space\LWRamp\space\space}
}
```

Test for windows during compile. The user may also specify OSWindows package option in case this test fails.

```
\ifwindows
\LWR@setOSWindows
\fi
```

# 29 Package options

Pkg kvoptions Allows key/value package options.

```
\RequirePackage{kvoptions}
\SetupKeyvalOptions{family=LWR,prefix=LWR@}
```

\lwarpsetup A user interface to set the keys:

```
\newcommand{\lwarpsetup}[1]{\setkeys{LWR}{#1}}
```

Bool warpingprint
Bool warpingHTML
Bool mathjax
Bool LWR@origmathjax

Set to true/false depending on the package option selections for print/HTML/EPUB output and mathsvg/mathjax.

LWR@origmathjax remembers the original setting to be restored by \displaymathnormal.

```
\newbool{warpingprint}
\newbool{warpingHTML}
\newbool{mathjax}
\newbool{LWR@origmathjax}
```

defaults The default is print output, and SVG math if the user chose HTML output.

```
\booltrue{warpingprint}%
\boolfalse{warpingHTML}%
\boolfalse{mathjax}%
```

Opt warpprint If the warpprint option is given, boolean warpingprint is true and boolean warpingHTML is false, and may be used for \ifbool tests.

```
\DeclareVoidOption{warpprint}{%
    \PackageInfo{lwarp}{Using option 'warpprint'}
    \booltrue{warpingprint}%
    \boolfalse{warpingHTML}%
}
```

Opt warpHTML Anything in the warpHTML environment will be generated for HTML output only.

Opt warpHTML If the warpHTML option is given, boolean warpingHTML is true and boolean warpingprint is false, and may be used for \ifbool tests.

```
\DeclareVoidOption{warpHTML}{%
    \PackageInfo{lwarp}{Using option 'warpHTML'}%
    \booltrue{warpingHTML}%
    \boolfalse{warpingprint}%
}
```

Opt mathsvg Option mathsvg selects SVG math display: If the mathsvg option is given, boolean mathjax is false, and may be used for \ifbool tests.

```
\DeclareVoidOption{mathsvg}{%
    \PackageInfo{lwarp}{Using option 'mathsvg'}
    \boolfalse{mathjax}%
    \boolfalse{LWR@origmathjax}%

}
```

Opt mathjax Option mathjax selects MathJax math display: If the mathjax option is given, boolean mathjax is true, may be used for \ifbool tests.

```
\DeclareVoidOption{mathjax}{%
    \PackageInfo{lwarp}{Using option 'mathjax'}
    \booltrue{mathjax}%
    \booltrue{LWR@origmathjax}%
```

```
982 }
```

Opt BaseJobname
Default: \jobname

Option BaseJobname sets the \BaseJobname for this document.

This is the \jobname of the printed version, even if currently compiling the HTML version. I.e. this is the \jobname without _html appended. This is used to set \HomeHTMLFilename if the user did not provide one.

```
983 \DeclareStringOption[\jobname]{BaseJobname}
```

Opt ImagesDirectory
Default: \jobname-images

Option ImagesDirectory sets the name of the directory to use for the lateximage images.

```
984 \DeclareStringOption[\BaseJobname-images]{ImagesDirectory}
```

Opt ImagesName
Default: image-

Option ImagesName sets the prefix to use for the lateximage images.

```
985 \DeclareStringOption[image-]{ImagesName}
```

Opt makeindexStyle
Default: lwarp.ist

Selects a custom .ist file. A customized file should be based on lwarp.ist. See section 8.6.20.

```
986 \DeclareStringOption[lwarp.ist]{makeindexStyle}
```

Opt xindyStyle
Default: lwarp.xdy

Selects a custom .xdy file. A customized file should be based on lwarp.xdy. See section 8.6.21.

```
987 \DeclareStringOption[lwarp.xdy]{xindyStyle}
```

Opt xindyLanguage
Default: english

Sets the *xindy* language to be assigned in *lwarpmk*'s configuration files. This is then used by *lwarpmk* while processing the index and glossary.

```
988 \DeclareStringOption[english]{xindyLanguage}
```

Opt xindyCodepage
Default: utf8

Sets the *xindy* codepage to be assigned in *lwarpmk*'s configuration files. This is then used by *lwarpmk* while processing the index.

```
989 \DeclareStringOption[utf8]{xindyCodepage}
```

Opt xindexConfig
Default: <empty>

Selects a custom xindex-*.lua file. A customized file should be based on xindex-cfg.lua. See section 8.6.22.

```
990 \DeclareStringOption[]{xindexConfig}
```

Opt pdftotextEnc
Default: UTF-8

The option pdftotextEnc sets the encoding used by *pdftotext*. This is passed to *pdftotext* using its -enc option, and is used when converting LaTeX PDF output with HTML tags into a plain-text file with HTML tags.

```
991 \DeclareStringOption[UTF-8]{pdftotextEnc}
```

Opt lwarpmk

Tells lwarp to generate a local copy of *lwarpmk* called `lwarpmk.lua`. Useful for archiving for future use. This file may be made executable and acts just like *lwarpmk*.

If `lwarpmk` option, creates a local copy of `lwarpmk.lua`:

```
\newbool{LWR@creatinglwarpmk}
\boolfalse{LWR@creatinglwarpmk}

\DeclareVoidOption{lwarpmk}{
    \PackageInfo{lwarp}{Using option 'lwarpmk'}
    \booltrue{LWR@creatinglwarpmk}
}
```

Opt OSWindows

Tells lwarp to use MS-Windows compatibility. Auto-detection of the operating system is attempted, and this option is only necessary if the auto-detection fails. See the automatically-generated `lwarpmk.conf` file to find out whether the operating system was detected correctly.

```
\DeclareVoidOption{OSWindows}{
    \PackageInfo{lwarp}{Using option 'OSWindows'}
    \LWR@setOSWindows
}
```

Opt HomeHTMLFilename
Default: \BaseJobname

The filename of the homepage. The default is the jobname. This option is stored into `\LWR@HomeHTMLFilename`, and later transferred into `\HomeHTMLFilename` for internal use.

```
\DeclareStringOption[]{HomeHTMLFilename}
```

Opt HTMLFilename
Default: <empty>

The filename prefix of web pages after the homepage. The default is empty, no prefix. This option is stored into `\LWR@HTMLFilename`, and later transferred into `\HTMLFilename` for internal use.

```
\DeclareStringOption[]{HTMLFilename}
```

Opt PrintLatexCmd
Default: <automatic>

The shell commands to use to compile the print document.

```
\DeclareStringOption[]{PrintLatexCmd}
```

Opt HTMLLatexCmd
Default: <automatic>

The shell commands to use to compile the HTML document.

```
\DeclareStringOption[]{HTMLLatexCmd}
```

Opt PrintIndexCmd
Default: <empty>

The shell commands to use to compile the print indexes.

```
\DeclareStringOption[]{PrintIndexCmd}
```

Opt HTMLIndexCmd
Default: <empty>

The shell commands to use to compile the HTML indexes.

```
\DeclareStringOption[]{HTMLIndexCmd}
```

Opt LatexmkIndexCmd
Default: <empty>

The shell commands to by used by *latexmk* to compile the print indexes. Unlike

`PrintIndexCmd` and `HTMLIndexCmd`, `LatexmkIndexCmd` does not include the filename, which will be provided by *latexmk*.

```
\DeclareStringOption[]{LatexmkIndexCmd}
```

Opt `makeindex` Tells lwarp to use *makeindex* for index generation. When `lwarpmk.conf` and `*.lwarpmkconf` are generated, `PrintIndexCmd` and `HTMLIndexCmd` will be set for *makeindex* with a single index file.

```
\DeclareBoolOption[false]{makeindex}
```

Opt `xindy` Tells lwarp to use *xindy* for index generation. When `lwarpmk.conf` and `*.lwarpmkconf` are generated, `PrintIndexCmd` and `HTMLIndexCmd` will be set for *xindy* with a single index file.

```
\DeclareBoolOption[false]{xindy}
```

Opt `xindex` Tells lwarp to use *xindex* for index generation. When `lwarpmk.conf` and `*.lwarpmkconf` are generated, `PrintIndexCmd` and `HTMLIndexCmd` will be set for *xindex* with a single index file.

```
\DeclareBoolOption[false]{xindex}
```

Opt `IndexRef` Tells lwarp how to display the index entries in HTMLoutput. See section 7.5.
Default: `cref`

```
\DeclareStringOption[cref]{IndexRef}
```

Opt `GlossaryCmd` The shell command to use to compile the glossary. The print or HTML version of the glossary filename will be appended to this command.
Default: `makeglossaries`

```
\DeclareStringOption[makeglossaries]{GlossaryCmd}
```

Opt `latexmk` Option `latexmk` tells *lwarpmk* to use *latexmk* when compiling documents.

```
\DeclareBoolOption[false]{latexmk}
```

Opt `dvips` Option `dvips` tells *lwarpmk* to use *dvips* when compiling DVI *latex* documents.

```
\DeclareBoolOption[false]{dvips}
```

Opt `dvipdfm` Option `dvipdfm` tells *lwarpmk* to use *dvipdfm* when compiling DVI *latex* documents.

```
\DeclareBoolOption[false]{dvipdfm}
```

Opt `dvipdfmx` Option `dvipdfmx` tells *lwarpmk* to use *dvipdfmx* when compiling DVI *latex* documents.

```
\DeclareBoolOption[false]{dvipdfmx}
```

Execute options Execute the package options, with the defaults which have been set just above:

```
\ProcessKeyvalOptions*\relax
```

```
\def\LWR@includecomment
#1#2{\message{Lwarp: Including comment '#1'}%
    \csarg\def{After#1Comment}{%
        \CloseAndInputCutFile%
        \csundef{LWR@#1commentused}%
    }
    \csarg\def{#1}{%
        \endgroup
        \ifcsdef{LWR@#1commentused}{
            \PackageError{lwarp}%
                {Nested #1 environment}%
                {%
                    Environment #1 cannot be nested.\MessageBreak
                    This can happen when a package is loaded
                    from inside a\MessageBreak
                    #1 environment.%
                }%
        }{\relax}
        \csdef{LWR@#1commentused}{}
        \message{Including '#1' comment.}%
        \def\CommentCutFile{comment_#2.cut}
        \SetUpCutFile
        \ProcessComment{#1}
    }%
    \CommentEndDef{#1}
}

\def\LWR@excludecomment
#1#2{\message{Lwarp: Excluding comment '#1'}%
    \csarg\def{#1}{
        \endgroup
        \message{Excluding '#1' comment.}%
        \begingroup
           \def\CommentCutFile{comment_#2.cut}
            \def\ProcessCutFile{}%
           \def\ThisComment####1{}%
            \ProcessComment{#1}
    }%
    \csarg\def{After#1Comment}{\CloseAndInputCutFile \endgroup}
    \CommentEndDef{#1}}
```

Env warpall Anything in the warpall environment will be generated for print or HTML outputs.

```
\LWR@includecomment{warpall}{all}
```

Env warpHTML For HTML output:

```
\ifbool{warpingHTML}
    {\LWR@includecomment{warpHTML}{html}}
    {\LWR@excludecomment{warpHTML}{html}}
```

Env warpprint Anything in the warpprint environment will be generated for print output only.

```
\ifbool{warpingprint}
```

```
1172     {\LWR@includecomment{warpprint}{print}}
1173     {\LWR@excludecomment{warpprint}{print}}
```

Env warpMathJax Only if MathJax is being used along with HTML.

```
1174 \begin{warpprint}
1175 \LWR@excludecomment{warpMathJax}{mathjax}
1176 \end{warpprint}
1177
1178 \begin{warpHTML}
1179 \ifbool{mathjax}
1180     {\LWR@includecomment{warpMathJax}{mathjax}}
1181     {\LWR@excludecomment{warpMathJax}{mathjax}}
1182 \end{warpHTML}
```

Env LWRcreatelwarpmk Optionally generate a local copy of *lwarpmk*. Default to no.

```
1183 \ifbool{LWR@creatinglwarpmk}
1184     {\LWR@includecomment{LWRcreatelwarpmk}{lwarpmk}}
1185     {\LWR@excludecomment{LWRcreatelwarpmk}{lwarpmk}}
```

# 30 Required packages

These packages are automatically loaded by lwarp when generating HTML output. Some of them are also automatically loaded when generating print output, but some are not.

**for HTML output:**

```
1186 \begin{warpHTML}
```

Pkg fontspec Load fontspec if necessary:

```
1187 \ifxetexorluatex
1188
```

```
\microtypesetup{
    protrusion=false,
    expansion=false,
    tracking=false,
    kerning=false,
    spacing=false}
%    \begin{macrocode}
%
% Disable ligatures for typewriter fonts.
% The comma was causing issues with \brand{MathJax} and \cs{,} followed by a comma.
% Ligatures for f, q, t, etc used to be disabled for non-typewriter fonts, but
% are now allowed.
% \changes{v0.89}{2020/08/01}{Disable typewriter ligatures.}
% ^^A \DisableLigatures[{,},f,q,t,T,Q]{encoding = *,family = *}% previous
%    \begin{macrocode}
\DisableLigatures{encoding = *,family = tt*}

\fi

\end{warpHTML}
```

Pkg geometry Tactics to avoid unwanted page breaks and margin overflow:

- Uses a very long and wide page to minimize page breaks and margin overflow.
- Uses a scriptsize font.
- Uses extra space at the margin to avoid HTML tag overflow off the page.
- Forces a new PDF page before some environments.
- Forces line break between major pieces of long tags.

**for HTML output:**

```
\begin{warpHTML}
```

If geometry has not yet been loaded, use the preexising page and text sizes to be preserved for later reuse. These will be replaced by lwarp `\AtBeginDocument` with a very large page size to reduce HTML tag overflow off the page.

```
\@ifpackageloaded{geometry}
{}{
    \RequirePackage[
        reset,
        paperwidth=\paperwidth,
        paperheight=\paperheight,
        textwidth=\textwidth,
        textheight=\textheight,
        left=\oddsidemargin,
        top=\topmargin,
        marginparsep=\marginparsep,
        marginparwidth=\marginparwidth,
    ]{geometry}
}
```

```
\LWR@origgeometry{
    reset,
    paperheight=190in,
    paperwidth=20in,
    left=2in,
    right=6in,
    top=1in,
    bottom=1in,
    heightrounded,%
}
```

The lwarp page geometry is saved for future restore:

```
\LWR@origsavegeometry{LWR@lwarpgeometry}
```

No longer adjust the page layout when lwarp-geometry is loaded `\AtBeginDocument`:

```
\boolfalse{LWR@allowanothergeometry}%
```

ltjsbook and other classes can print vertically, and require these to be reset by lwarp:

```
\setlength{\textheight}{0.8\paperheight}
\setlength{\textwidth}{0.7\paperwidth}

\@twosidefalse
\@mparswitchfalse
}% \AtEndPreamble

\end{warpHTML}
```

**for HTML & PRINT:**

```
\begin{warpall}
```

Pkg xparse

LaTeX3 command argument parsing

```
\RequirePackage{xparse}
```

Pkg calc

```
\RequirePackage{calc}
```

```
\end{warpall}
```

**for HTML output:**

```
\begin{warpHTML}
```

Pkg expl3

LaTeX3 programming

```
\RequirePackage{expl3}
```

Pkg gettitlestring

Used to emulate \nameref.

```
\RequirePackage{gettitlestring}
```

Pkg everyhook

everyhook is used to patch paragraph handling.

```
\@ifundefined{bxjs@everypar}{}{\let\everypar\bxjs@everypar}

\RequirePackage{everyhook}
\end{warpHTML}
```

**for HTML & PRINT:**

```
\begin{warpall}
```

Pkg filecontents

Used to write helper files while creating the print version.

Recent versions of LaTeX (as of Fall 2019) now include the functionality of the filecontents package, but with a new optional argument used to specify whether to force the overwriting of an existing file. If an older LaTeX kernel is used, the original filecontents package is used, but it is patched to throw away the new optional argument.

```
\@ifundefined{filec@ntents@opt}{% older kernel, discard optional args

    \RequirePackage{filecontents}

    \LetLtxMacro\LWR@orig@filec@ntents\filec@ntents

    \@ifpackagelater{filecontents}{2011/10/08}
    {
```

For a newer version of the filecontents package, simply discard the optional argument.

```
        \renewcommand*{\filec@ntents}[1][]{\LWR@orig@filec@ntents}
    }
    {% patch older package for morewrites
```

For an older version of filecontents, discard the optional argument, and also patch to work with morewrites, per https://tex.stackexchange.com/questions/312830/does-morewrites-not-support-filecontents-and-can-i-write-body-of-environment-us/312910

```
        \newwrite\fcwrite
        \renewcommand*{\filec@ntents}[1][]{%
            \def\chardef##1\write{\let\reserved@c\fcwrite}%
            \LWR@orig@filec@ntents%
        }
    }

}% older kernel
{% newer kernel
```

`\LWR@findword` `[`⟨*1: separator*⟩`]` {⟨*2: list*⟩} {⟨*3: index*⟩} `[`⟨*4: destination*⟩`]`

Note that argument 4 is passed directly to `\StrBetween`.

```
\newcommand*\LWR@findword[3][,]{%
    \StrBetween[#3,\numexpr#3+1]{#1#2#1}{#1}{#1}%
}
```

`\LWR@checkloadfilename` {⟨*filename*⟩} Checks if this filename should be loaded after lwarp, or never at all.

The following should never be loaded:

```
\newcommand*{\LWR@checkloadfilename}[1]{%
\LWR@checkloadnever{#1}{ae}{cm-super, lmodern}
\LWR@checkloadnever{#1}{aecc}{cm-super, lmodern}
\LWR@checkloadnever{#1}{aecompl}{cm-super, lmodern}
\LWR@checkloadnever{#1}{alg}{algorithm2e, algorithmicx}
\LWR@checkloadnever{#1}{algorithmic}{algorithm2e, algorithmicx}
\LWR@checkloadnever{#1}{bitfield}{bytefield}
\LWR@checkloadnever{#1}{caption2}{caption}
\LWR@checkloadnever{#1}{ccaption}{caption}% might be preloaded by memoir
\LWR@checkloadnever{#1}{colortab}{colortbl}
\LWR@checkloadnever{#1}{csvtools}{datatool}
\LWR@checkloadnever{#1}{doublespace}{setspace}
\LWR@checkloadnever{#1}{fancyheadings}{fancyhdr}
\LWR@checkloadnever{#1}{fncylab}{cleveref}
\LWR@checkloadnever{#1}{formula}{siunitx}
\LWR@checkloadnever{#1}{glossary}{glossaries}
\LWR@checkloadnever{#1}{hyper}{hyperref}
\LWR@checkloadnever{#1}{libgreek}{libertinust1math, newtx}
\LWR@checkloadnever{#1}{newthm}{ntheorem}
\LWR@checkloadnever{#1}{pdfcprot}{microtype}
\LWR@checkloadnever{#1}{picins}{floatflt, wrapfig}
\LWR@checkloadnever{#1}{rplain}{fancyhdr}
\LWR@checkloadnever{#1}{si}{siunitx}
\LWR@checkloadnever{#1}{sistyle}{siunitx}
\LWR@checkloadnever{#1}{slashbox}{diagbox}
\LWR@checkloadnever{#1}{statex}{statex2}
\LWR@checkloadnever{#1}{t1enc}{fontenc, inputenc, inputenx}
\LWR@checkloadnever{#1}{ucs}{inputenc, inputencx}
\LWR@checkloadnever{#1}{wasysym}{textcomp, amssymb, amsfonts, mnsymbol, fdsymbol}
\LWR@checkloadnever{#1}{bxcjkjatype}{upLaTeX, bxjsarticle, ujarticle, utarticle}
\LWR@checkloadnever{#1}{hangul}{kotex, xetexko, luatexko}
```

The following should only be loaded before lwarp:

```
\LWR@checkloadbefore{#1}{ctex}
\LWR@checkloadbefore{#1}{fontspec}
\LWR@checkloadbefore{#1}{inputenc}
\LWR@checkloadbefore{#1}{inputenx}
\LWR@checkloadbefore{#1}{nfssext-cfr}
\LWR@checkloadbefore{#1}{fontaxes}
\LWR@checkloadbefore{#1}{kotex}
\LWR@checkloadbefore{#1}{kpfonts}% textcomp option clash
\LWR@checkloadbefore{#1}{luatexja}
```

```
\LWR@checkloadbefore{#1}{luatexja-fontspec}
\LWR@checkloadbefore{#1}{luatexko}
\LWR@checkloadbefore{#1}{morewrites}
\LWR@checkloadbefore{#1}{newclude}
\LWR@checkloadbefore{#1}{newunicodechar}
\LWR@checkloadbefore{#1}{plext}
\LWR@checkloadbefore{#1}{xeCJK}
\LWR@checkloadbefore{#1}{xetexko}
\LWR@checkloadbefore{#1}{zxjatype}
}
```

`\LWR@lookforpackagename` `{⟨index⟩}`

If HTML, and if this is an lwarp-supported package name, re-direct it to the lwarp version by renaming it `lwarp-` followed by the original name.

Looks `index` deep into the list of package names, `\LWR@requirepackagenames`, and builds `\LWR@parsedrequirepackagenames` which is the modified list of names.

```
\newcommand*{\LWR@lookforpackagename}[1]{%
```

Find the `index`'th package name from the list:

```
\LWR@findword{\LWR@requirepackagenames}{#1}[\LWR@strresult]%
```

Remove blanks. The original name with blanks is in `LWR@strresult` and the final name with no blanks goes into `LWR@strresulttwo`.

```
\StrSubstitute[100]{\LWR@strresult}{ }{}[\LWR@strresulttwo]%
```

See if the package name was found:

```
\IfStrEq{\LWR@strresulttwo}{}%
{}% no filename
{% yes filename was found
```

Possible adjustments before loading the package. Maybe nullify the `comment` environment if the new package will be redefining it for a new purpose.

```
    \ifdefstring{\LWR@strresulttwo}{easyReview}{\LWR@nullifycomment}{}%
    \ifdefstring{\LWR@strresulttwo}{changes}{\LWR@nullifycomment}{}%
```

If HTML, check if the package should be loaded before lwarp, or never at all:

```
    \ifbool{warpingHTML}{\LWR@checkloadfilename{\LWR@strresulttwo}}{}%
```

If HTML, and if found, and if an lwarp-equivalent name exists, use `lwarp-*` instead.

```
    \ifboolexpr{
        bool{warpingHTML} and
        test{\IfFileExists{lwarp-\LWR@strresulttwo.sty}}
    }%
    {% lwarp-* file found
        \ifdefvoid{\LWR@parsedrequirepackagenames}{%
```

```
            \edef\LWR@parsedrequirepackagenames{lwarp-\LWR@strresulttwo}%
        }{%
            \edef\LWR@parsedrequirepackagenames{%
                \LWR@parsedrequirepackagenames,lwarp-\LWR@strresulttwo%
            }%
        }%
    }%
    {%
```

Otherwise, use the current package name.

```
        \ifdefvoid{\LWR@parsedrequirepackagenames}{%
            \edef\LWR@parsedrequirepackagenames{\LWR@strresulttwo}%
        }{%
            \edef\LWR@parsedrequirepackagenames{%
                \LWR@parsedrequirepackagenames,\LWR@strresulttwo%
            }%
        }%
    }% no lwarp-* file
}% yes filename
}
```

\RequirePackage `[`⟨*1: options*⟩`]` `{`⟨*2: package names*⟩`}` `[`⟨*3: version*⟩`]`

For each of many package names in a comma-separated list, if an lwarp version of a package exists, select it instead of the LaTeX version.

```
\RenewDocumentCommand{\RequirePackage}{o m o}{%
```

Redirect up to twenty names:[17]

```
\renewcommand*{\LWR@requirepackagenames}{#2}%
\renewcommand*{\LWR@parsedrequirepackagenames}{}%
\LWR@lookforpackagename{1}%
\LWR@lookforpackagename{2}%
\LWR@lookforpackagename{3}%
\LWR@lookforpackagename{4}%
\LWR@lookforpackagename{5}%
\LWR@lookforpackagename{6}%
\LWR@lookforpackagename{7}%
\LWR@lookforpackagename{8}%
\LWR@lookforpackagename{9}%
\LWR@lookforpackagename{10}%
\LWR@lookforpackagename{11}%
\LWR@lookforpackagename{12}%
\LWR@lookforpackagename{13}%
\LWR@lookforpackagename{14}%
\LWR@lookforpackagename{15}%
\LWR@lookforpackagename{16}%
\LWR@lookforpackagename{17}%
\LWR@lookforpackagename{18}%
\LWR@lookforpackagename{19}%
\LWR@lookforpackagename{20}%
```

[17] This was originally nine names, but then I came across a package which used twelve...

\RequirePackage depending on the options and version:

```
\IfValueTF{#1}%
{% options given
    \IfValueTF{#3}% version given?
        {\LWR@origRequirePackage[#1]{\LWR@parsedrequirepackagenames}[#3]}%
        {\LWR@origRequirePackage[#1]{\LWR@parsedrequirepackagenames}}%
}%
{% no options given
    \IfValueTF{#3}% version given?
        {\LWR@origRequirePackage{\LWR@parsedrequirepackagenames}[#3]}%
        {\LWR@origRequirePackage{\LWR@parsedrequirepackagenames}}%
}%
}
\LetLtxMacro\usepackage\RequirePackage
\@onlypreamble\RequirePackage
\@onlypreamble\usepackage

\end{warpall}
```

**for HTML output:**

```
\begin{warpHTML}
```

\LWR@ProvidesPackagePass {⟨*pkgname*⟩} [⟨*version*⟩]

Uses the original package, including options.

```
\NewDocumentCommand{\LWR@ProvidesPackagePass}{m o}{
    \PackageInfo{lwarp}{%
        Using package ‘#1’,\MessageBreak
        and adding lwarp modifications, including options,\MessageBreak%
    }%
    \IfValueTF{#2}%
        {\ProvidesPackage{lwarp-#1}[#2]}%
        {\ProvidesPackage{lwarp-#1}}%
    \DeclareOption*{%
        \PassOptionsToPackage{\CurrentOption}{#1}%
    }%
    \ProcessOptions\relax%
```

If using catoptions, an error occurs if a package is loaded with an option then loaded again with no options. lwarp does this if a package is preloaded then later patched. To avoid an error while using catoptions, if a package has already been loaded, it is loaded again with its original options.

```
    \@ifpackageloaded{#1}{%
        \edef\LWR@tempone{\csuse{opt@#1.sty}}%
        \IfValueTF{#2}%
            {%
                \expandafter\LWR@origRequirePackage%
                    \expandafter[\LWR@tempone]{#1}[#2]%
            }%
            {%
                \expandafter\LWR@origRequirePackage%
                    \expandafter[\LWR@tempone]{#1}%
```

```
            }%
    }{%
        \IfValueTF{#2}%
            {\LWR@origRequirePackage{#1}[#2]}%
            {\LWR@origRequirePackage{#1}}%
    }%
```

In some cases, the following seems to be required to avoid an "unknown option" error, such as when loading xcolor with options.

```
    \DeclareOption*{}%
    \ProcessOptions\relax%
}
```

`\LWR@ProvidesPackageDropA` {⟨*name*⟩} {⟨*date or -NoValue-*⟩}

Declares the package. Factored for reuse.

```
\newcommand*{\LWR@ProvidesPackageDropA}[2]{%
    \PackageInfo{lwarp}{%
        Replacing package ‘#1’ with the lwarp version,\MessageBreak
        and discarding options,%
    }%
    \IfValueTF{#2}
    {\ProvidesPackage{lwarp-#1}[#2]}
    {\ProvidesPackage{lwarp-#1}}
}
```

`\LWR@ProvidesPackageDropB` Nullifies then processes the options.

Seems to be required when options contain curly braces, which were causing "`Missing \begin{document}`".

```
\newcommand*{\LWR@ProvidesPackageDropB}{%
% \ProcessOptions\relax% original LaTeX code
\let\ds@\@empty%         from the original \ProcessOptions
\edef\@curroptions{}%    lwarp modification to \ProcessOptions
\@process@ptions\relax%  from the original \ProcessOptions
}
```

`\LWR@ProvidesPackageDrop` {⟨*pkgname*⟩} [⟨*version*⟩]

Ignores the original package and uses lwarp's version instead. Drops/discards all options.

```
\NewDocumentCommand{\LWR@ProvidesPackageDrop}{m o}{
```

Declare the package:

```
\LWR@ProvidesPackageDropA{#1}{#2}
```

Ignore all options:

```
\DeclareOption*{}
```

```
\immediate\write\LWR@quickfile{\string\input{#1.tex}}% lwarp
\immediate\closeout\LWR@quickfile% lwarp
\LWR@maybe@orignewpage% changed from clearpage
\if@filesw
    \immediate\write\@mainaux{\string\@input{#1_html_inc.aux}}% changed
\fi
\@tempswatrue
\if@partsw
    \@tempswafalse
    \edef\reserved@b{#1}%
    \@for\reserved@a:=\@partlist\do
    {\ifx\reserved@a\reserved@b\@tempswatrue\fi}%
\fi
\if@tempswa
    \let\@auxout\@partaux
    \if@filesw
        \immediate\openout\@partaux #1_html_inc.aux % changed
        \immediate\write\@partaux{\relax}%
    \fi
    \@input@{#1_html_inc.tex}% changed
    \LWR@maybe@orignewpage% changed from clearpage
    \@writeckpt{#1}%
    \if@filesw
        \immediate\closeout\@partaux
    \fi
\else
    \deadcycles\z@
    \@nameuse{cp@#1}%
\fi
\let\@auxout\@mainaux%
}

\end{warpHTML}
```

# 34 Copying a file

**for HTML output:**

```
\begin{warpHTML}
```

`\LWR@copyfile` {⟨*source filename*⟩} {⟨*destination filename*⟩}

Used to copy the `.toc` file to `.sidetoc` to re-print the TOC in the sideTOC navigation pane.

```
\newwrite\LWR@copyoutfile   % open the file to write to
\newread\LWR@copyinfile     % open the file to read from

\newcommand*{\LWR@copyfile}[2]{%
    \LWR@traceinfo{LWR@copyfile: copying #1 to #2}

    \immediate\openout\LWR@copyoutfile=#2
    \openin\LWR@copyinfile=#1
    \begingroup\endlinechar=-1
    \makeatletter
```

```
1575
1576     \LWR@traceinfo{LWR@copyfile: about to loop}
1577
1578     \loop\unless\ifeof\LWR@copyinfile
1579         \LWR@traceinfo{LWR@copyfile: one line}
1580      \read\LWR@copyinfile to\LWR@fileline  % Read one line and store it into \LWR@fileline
1581 %   \LWR@fileline\par                   % print the content into the pdf
1582 % print the content:
1583      \immediate\write\LWR@copyoutfile{\unexpanded\expandafter{\LWR@fileline}}%
1584     \repeat
1585     \immediate\closeout\LWR@copyoutfile
1586     \LWR@traceinfo{LWR@copyfile: done}
1587     \endgroup
1588 }

1589 \end{warpHTML}
```

# 35 Debugging messages

HTML comments

To have the HTML output include additional HTML comments, such as which  is closing, use

```
\booltrue{HTMLDebugComments}
```

To have debug information 500(62sTJ/33(it)-500(tht)-5losing,)-250(use)]TJ0.7gq0.7[30702250(debugging)-25

```
\begin{warpHTML}
\newenvironment{LWR@HTML@name}{...}% may also use xparse

\LWR@formattedenv{name}
\end{warpHTML}
```

**If the original used** xparse**:** A copy must be made using a new name:

```
\begin{warpHTML}
\NewDocumentCommand{\LWR@print@name}{..}{..}% copy the original

\NewDocumentCommand{\LWR@HTML@name}{..}{..}% or use \newcommand

\LWR@formatted{name}
\end{warpHTML}
```

Similar for an environment, using `\LWR@formattedenv`. (`\LWR@formatted` and `\LWR@formattedenv` use `\LetLtxMacro` to copy the original print definiton, which may not work with macros and environments created by xparse, so the print version must be manually recreated in the lwarp source.)

**For a new macro or environment, not using** xparse **for the print version:**

```
\begin{warpall}
\newcommand{\name}{...}% NOT xparse!
\end{warpall}

\begin{warpHTML}
\newcommand{\LWR@HTML@name}{...}% may use xparse for HTML

\LWR@formatted{name}
\end{warpHTML}
```

Similar for an environment. The plain `\name` or environment `name` is used for the printed version, and is placed inside `warpall`. xparse may be used for the `\LWR@HTML@<name>` version. expl3 syntax may be used for the print and HTML versions.

**For a new macro or environment, using** xparse**:** It is possible to use xparse for an entirely new macro or environment by defining the `\LWR@print@<name>` version with xparse, along with `\name` defined without xparse to refer directly to the `\LWR@print` version:

**for HTML output:**

```
\begin{warpHTML}
```

`\LWR@formatting` Remembers if selected print/HTML formatting.

Used while `\LWR@restoreorigformatting`, such as in an `lateximage`. May be set to either "`print`" or "`HTML`".

```
\newcommand*{\LWR@formatting}{HTML}
```

`\LWR@formatted@checkname` {⟨*name*⟩}

```
\newcommand*{\LWR@formatted@checkname}[1]{%
    \ifcsundef{LWR@HTML@#1}{%
        \PackageError{lwarp}
        {%
            \protect\LWR@HTML@#1 is not defined%
        }
        {Perhaps it is misspelled.}
    }{\relax}%
}
```

`\LWR@formatted@checkendname` {⟨*name*⟩}

```
\newcommand*{\LWR@formatted@checkendname}[1]{%
    \ifcsundef{endLWR@HTML@#1}{%
        \PackageError{lwarp}
        {%
            \protect\endLWR@HTML@#1 is not defined%
        }
        {Perhaps it is misspelled.}
    }{\relax}%
}
```

`\LWR@formatted` {⟨*macroname*⟩} No backslash in the macro name.

If not yet defined, defines `\LWR@print@<name>` as the original print-mode `\<name>`. Also redefines `\<name>` to use `\LWR@<format>@<name>`, where <format> is set by `\LWR@formatting`, and is `print` or `HTML`.

```
\newcommand*{\LWR@formatted}[1]{%
    \LWR@formatted@checkname{#1}%
    \ifcsundef{LWR@print@#1}{%
        \expandafter\LetLtxMacro\csname LWR@print@#1\expandafter\endcsname%
            \csname#1\endcsname%
    }{}%
    \ifcsundef{#1}{%
        \expandafter\newrobustcmd\csname #1\endcsname{%
            \@nameuse{LWR@\LWR@formatting @#1}%
        }%
    }{%
        \expandafter\renewrobustcmd\csname #1\endcsname{%
            \@nameuse{LWR@\LWR@formatting @#1}%
        }%
```

```
    }%
}
```

`\LWR@expandableformatted` {⟨*macroname*⟩} No backslash in the macro name.

An expandable version of `\LWR@formatted`.

```
\newcommand*{\LWR@expandableformatted}[1]{%
    \LWR@formatted@checkname{#1}%
    \ifcsundef{LWR@print@#1}{%
        \expandafter\LetLtxMacro\csname LWR@print@#1\expandafter\endcsname%
            \csname#1\endcsname%
    }{}%
    \ifcsundef{#1}{%
        \expandafter\newcommand\csname #1\endcsname{%
            \@nameuse{LWR@\LWR@formatting @#1}%
        }%
    }{%
        \expandafter\renewcommand\csname #1\endcsname{%
            \@nameuse{LWR@\LWR@formatting @#1}%
        }%
    }%
}
```

`\LWR@formattedenv` {⟨*environmentname*⟩}

If not yet defined, defines the environment `LWR@print@<name>` as the original print-mode `<name>`. Also redefines the environment `<name>` to use environment `LWR@<format>@<name>`, where `<format>` is set by `\LWR@formatting`, and is `print` or `HTML`.

```
\newcommand*{\LWR@formattedenv}[1]{%
    \LWR@formatted@checkname{#1}%
    \LWR@formatted@checkendname{#1}%
    \ifcsundef{LWR@print@#1}{%
        \expandafter\LetLtxMacro\csname LWR@print@#1\expandafter\endcsname%
            \csname#1\endcsname%
        \csletcs{endLWR@print@#1}{end#1}%
    }{}%
    \DeclareDocumentEnvironment{#1}{}%
    {%
        \@nameuse{LWR@\LWR@formatting @#1}%
    }%
    {%
        \@nameuse{endLWR@\LWR@formatting @#1}%
    }%
}
```

`\LWR@expandableformattedenv` {⟨*environmentname*⟩}

An expandable version of `LWR@formattedenv`.

```
\newcommand*{\LWR@expandableformattedenv}[1]{%
    \LWR@formatted@checkname{#1}%
```

```
    \LWR@formatted@checkendname{#1}%
    \ifcsundef{LWR@print@#1}{%
        \expandafter\LetLtxMacro\csname LWR@print@#1\expandafter\endcsname%
            \csname#1\endcsname%
        \csletcs{endLWR@print@#1}{end#1}%
    }{}%
    \DeclareExpandableDocumentEnvironment{#1}{}%
    {%
        \@nameuse{LWR@\LWR@formatting @#1}%
    }%
    {%
        \@nameuse{endLWR@\LWR@formatting @#1}%
    }%
}
\end{warpHTML}
```

# 37 HTML-conversion output modifications

These booleans modify the HTML output in various ways to improve conversion to EPUB or word processor imports.

**for HTML & PRINT:**

```
\begin{warpall}
```

## 37.1 User-level controls

Bool `FormatEPUB`
Default: `false`

Changes HTML output for easy EPUB conversion via an external program. Removes per-file headers, footers, and nav. Adds footnotes per chapter/section.

```
\newbool{FormatEPUB}
\boolfalse{FormatEPUB}
```

Bool `FormatWP`
Default: `false`

Changes HTML output for easier conversion by a word processor. Removes headers and nav, prints footnotes per section, and also forces single-file output and turns off HTML debug comments.

```
\newbool{FormatWP}
\boolfalse{FormatWP}
```

Bool `WPMarkFloats`
Default: `false`

Adds

```
=== begin table ===
. . .
=== end ===
```

or

```
=== begin figure ===
. . .
=== end ===
```

around floats while formatting for word processors. This helps identify boundaries of floats to be manually converted to word-processor frames and captions. [18]

```
\newbool{WPMarkFloats}
\boolfalse{WPMarkFloats}
```

Bool `WPMarkMinipages` Default: `false`

Adds

```
=== begin minipage ===
. . .
=== end minipage ===
```

around minipages while formatting for word processors. This helps identify boundaries of minipages to be manually converted to word-processor frames.

```
\newbool{WPMarkMinipages}
\boolfalse{WPMarkMinipages}
```

Bool `WPMarkTOC` Default: `true`

While formatting for word processors, adds

```
=== table of contents ===
```

where the Table of Contents would have been. This helps identify where to insert the actual TOC.

*If set* `false`*, the actual* TOC *is printed instead.*

```
\newbool{WPMarkTOC}
\booltrue{WPMarkTOC}
```

Bool `WPMarkLOFT` Default: `false`

While formatting for word processors, adds

```
=== list of figures ===    and/or
=== list of tables ===
```

where each of these lists would have been. This helps identify where to insert the actual lists.

*If set* `false`*, the actual lists are printed instead.*

```
\newbool{WPMarkLOFT}
\boolfalse{WPMarkLOFT}
```

Bool `WPMarkMath` Default: `false`

While formatting for word processors, prints math as LaTeX code instead of creating SVG images or MathJax. This is useful for cut/paste into the ***LibreOffice Writer TeXMaths*** extension.

```
\newbool{WPMarkMath}
\boolfalse{WPMarkMath}
```

Bool `WPTitleHeading` Default: `false`

While formatting for word processors, `true` sets the document title to `<h1>`, which is expected for HTML documents, but also causes the lower-level section headings to start at

[18] Perhaps some day word processors will have HTML import options for identifying `<figure>` and caption tags for figures and tables.

Heading 2 when imported into LibreOffice. Set to `false` to cause the title to be plain text, and the section headings to begin at Heading 1.

See table 10 on page 184.

```
\newbool{WPTitleHeading}
\boolfalse{WPTitleHeading}

\end{warpall}
```

## 37.2 Heading adjustments

If formatting the HTML for a word processor, adjust heading levels.

If `WPTitleHeading` is true, adjust so that `part` is Heading 1.

If `WPTitleHeading` is false, use <h1> for the title, and set `part` to Heading 2.

**for HTML output:**

```
\begin{warpHTML}

\AtBeginDocument{
\ifbool{FormatWP}{
\@ifundefined{chapter}{
\ifbool{WPTitleHeading}{% part and section starting at h2
\renewcommand*{\LWR@tagtitle}{h1}
\renewcommand*{\LWR@tagtitleend}{/h1}
\renewcommand*{\LWR@tagpart}{h2}
\renewcommand*{\LWR@tagpartend}{/h2}
\renewcommand*{\LWR@tagsection}{h3}
\renewcommand*{\LWR@tagsectionend}{/h3}
\renewcommand*{\LWR@tagsubsection}{h4}
\renewcommand*{\LWR@tagsubsectionend}{/h4}
\renewcommand*{\LWR@tagsubsubsection}{h5}
\renewcommand*{\LWR@tagsubsubsectionend}{/h5}
\renewcommand*{\LWR@tagparagraph}{h6}
\renewcommand*{\LWR@tagparagraphend}{/h6}
\renewcommand*{\LWR@tagsubparagraph}{span class=\textquotedbl{}subparagraph\textquotedbl}
\renewcommand*{\LWR@tagsubparagraphend}{/span}
}% WPTitleHeading
{% not WPTitleHeading, part and section starting at h1
\renewcommand*{\LWR@tagtitle}{div class=\textquotedbl{}title\textquotedbl}
\renewcommand*{\LWR@tagtitleend}{/div}
\renewcommand*{\LWR@tagpart}{h1}
\renewcommand*{\LWR@tagpartend}{/h1}
\renewcommand*{\LWR@tagsection}{h2}
\renewcommand*{\LWR@tagsectionend}{/h2}
\renewcommand*{\LWR@tagsubsection}{h3}
\renewcommand*{\LWR@tagsubsectionend}{/h3}
\renewcommand*{\LWR@tagsubsubsection}{h4}
\renewcommand*{\LWR@tagsubsubsectionend}{/h4}
\renewcommand*{\LWR@tagparagraph}{h5}
\renewcommand*{\LWR@tagparagraphend}{/h5}
\renewcommand*{\LWR@tagsubparagraph}{h6}
\renewcommand*{\LWR@tagsubparagraphend}{/h6}
```

```
}% not WPTitleHeading
}% chapter undefined
{% chapter defined
\ifbool{WPTitleHeading}{}
{% not WPTitleHeading, part and chapter starting at h1
\renewcommand*{\LWR@tagtitle}{div class=\textquotedbl{}title\textquotedbl}
\renewcommand*{\LWR@tagtitleend}{/div}
\renewcommand*{\LWR@tagpart}{h1}
\renewcommand*{\LWR@tagpartend}{/h1}
\renewcommand*{\LWR@tagchapter}{h2}
\renewcommand*{\LWR@tagchapterend}{/h2}
\renewcommand*{\LWR@tagsection}{h3}
\renewcommand*{\LWR@tagsectionend}{/h3}
\renewcommand*{\LWR@tagsubsection}{h4}
\renewcommand*{\LWR@tagsubsectionend}{/h4}
\renewcommand*{\LWR@tagsubsubsection}{h5}
\renewcommand*{\LWR@tagsubsubsectionend}{/h5}
\renewcommand*{\LWR@tagparagraph}{h6}
\renewcommand*{\LWR@tagparagraphend}{/h6}
\renewcommand*{\LWR@tagsubparagraph}{span class=\textquotedbl{}subparagraph\textquotedbl}
\renewcommand*{\LWR@tagsubparagraphend}{/span}
}% not WPTitleHeading
}% chapter defined
}{}% FormatWP
}% AtBeginDocument

\end{warpHTML}
```

# 38 Remembering original formatting macros

**for HTML output:**

```
\begin{warpHTML}
```

Remember original definitions of formatting commands. Will be changed to HTML commands for most uses. Will be temporarily restored to original meaning inside any lateximage environment. Also nullify unused commands.

Some packages redefine \#, which is used to generate HTML, so the original must be remembered here.

```
\chardef\LWR@origpound=`\#

\let\LWR@origcomma\,
\let\LWR@origthinspace\thinspace
\let\LWR@orignegthinspace\negthinspace
\let\LWR@origtilde~
\let\LWR@origenskip\enskip
\let\LWR@origquad\quad
\let\LWR@origqquad\qquad
\let\LWR@orighfil\hfil
\let\LWR@orighss\hss
\let\LWR@origllap\llap
\let\LWR@origrlap\rlap
```

```
\let\LWR@orighfilneg\hfilneg
\let\LWR@orighspace\hspace

\let\LWR@origrule\rule

\let\LWR@origmedskip\medskip
\let\LWR@origbigskip\bigskip

\let\LWR@origtextellipsis\textellipsis


\let\LWR@origvdots\vdots
```

libertinus-otf has too much kerning for `\textquotedbl`, causing an extra space.

```
\LetLtxMacro\LWR@orig@@textquotedbl\textquotedbl
\LetLtxMacro\LWR@orig@textquotedbl\LWR@orig@@textquotedbl

\AtEndPreamble{
\@ifpackageloaded{libertinus-otf}{
    \renewcommand{\LWR@orig@textquotedbl}{\LWR@orig@@textquotedbl\kern-.15em}
    \LetLtxMacro\textquotedbl\LWR@orig@textquotedbl
}{}
}

\LetLtxMacro\LWR@origttfamily\ttfamily

\LetLtxMacro\LWR@origem\em

\LetLtxMacro\LWR@orignormalfont\normalfont

\let\LWR@origonecolumn\onecolumn

\let\LWR@origsp\sp
\let\LWR@origsb\sb

\LetLtxMacro\LWR@origunderline\underline

\let\LWR@orignewpage\newpage

\let\LWR@origpagestyle\pagestyle
\let\LWR@origthispagestyle\thispagestyle
\LetLtxMacro\LWR@origpagenumbering\pagenumbering

\let\LWR@orignewline\newline

\AtBeginDocument{% in case packages change definition
\let\LWR@orig@trivlist\@trivlist
\let\LWR@origtrivlist\trivlist
\let\LWR@origendtrivlist\endtrivlist
\LetLtxMacro\LWR@origitem\item
\LetLtxMacro\LWR@origitemize\itemize
\LetLtxMacro\LWR@endorigitemize\enditemize
\LetLtxMacro\LWR@origenumerate\enumerate
\LetLtxMacro\LWR@endorigenumerate\endenumerate
```

```
\LetLtxMacro\LWR@origdescription\description
\LetLtxMacro\LWR@endorigdescription\enddescription
\let\LWR@orig@mklab\@mklab
\let\LWR@origmakelabel\makelabel
\let\LWR@orig@donoparitem\@donoparitem
\LetLtxMacro\LWR@orig@item\@item
\let\LWR@orig@nbitem\@nbitem
}

\let\LWR@origpar\par

\LetLtxMacro\LWR@origfootnote\footnote
\let\LWR@orig@mpfootnotetext\@mpfootnotetext


\AtBeginDocument{% in case packages change definition
\LetLtxMacro\LWR@orighline\hline%
\LetLtxMacro\LWR@origcline\cline%
}

\end{warpHTML}
```

# 39 Accents

Native LaTeX accents such as \" will work, but many more kinds of accents are available when using Unicode-aware XeLaTeX and LuaLaTeX. If using accents in section names which will become file names, it is recommended to use the LaTeX accents such as \" and \v instead of Unicode accents. The LaTeX accents will have the accents stripped when creating the filenames, whereas the Unicode accents will appear in the file names, which may cause issues with some operating systems.

**for HTML output:**

```
\begin{warpHTML}
```

Without `\AtBeginDocument`, `\t` was being re-defined somewhere.

```
\AtBeginDocument{
```

The following are restored for print when inside a `lateximage`.

For Unicode engines, only `\t` needs to be redefined:

```
\LetLtxMacro\LWR@origtie\t
```

For pdfLaTeX, additional work is required:

```
\ifPDFTeX% pdflatex or dvi latex
\LetLtxMacro\LWR@origgraveaccent\‘
\LetLtxMacro\LWR@origacuteaccent\’
\LetLtxMacro\LWR@origcircumflexaccent\^
\LetLtxMacro\LWR@origtildeaccent\~
\LetLtxMacro\LWR@origmacronaccent\=
\LetLtxMacro\LWR@origbreve\u
```

```
\LetLtxMacro\LWR@origdotaccent\.
\LetLtxMacro\LWR@origdiaeresisaccent\"
\LetLtxMacro\LWR@origdoubleacuteaccent\H
\LetLtxMacro\LWR@origcaronaccent\v
\LetLtxMacro\LWR@origdotbelowaccent\d
\LetLtxMacro\LWR@origcedillaaccent\c
\LetLtxMacro\LWR@origmacronbelowaccent\b
```

The HTML redefinitions follow.

For pdfLaTeX, Unicode diacritical marks are used:

```
\renewcommand*{\‘}[1]{#1\HTMLunicode{0300}}
\renewcommand*{\’}[1]{#1\HTMLunicode{0301}}
\renewcommand*{\^}[1]{#1\HTMLunicode{0302}}
\renewcommand*{\~}[1]{#1\HTMLunicode{0303}}
\renewcommand*{\=}[1]{#1\HTMLunicode{0304}}
\renewcommand*{\u}[1]{#1\HTMLunicode{0306}}
\renewcommand*{\.}[1]{#1\HTMLunicode{0307}}
\renewcommand*{\"}[1]{#1\HTMLunicode{0308}}
\renewcommand*{\H}[1]{#1\HTMLunicode{030B}}
\renewcommand*{\v}[1]{#1\HTMLunicode{030C}}
\renewcommand*{\d}[1]{#1\HTMLunicode{0323}}
\renewcommand*{\c}[1]{#1\HTMLunicode{0327}}
\renewcommand*{\b}[1]{#1\HTMLunicode{0331}}
\fi
```

For all engines, a Unicode diacritical tie is used:

```
\def\LWR@t#1#2{#1\HTMLunicode{0361}#2}
\renewcommand*{\t}[1]{\LWR@t#1}
```

`\LWR@restoreorigaccents` Called from `\restoreoriginalformatting` when a `latexmage` is begun.

```
\ifPDFTeX% pdflatex or dvi latex
\newcommand*{\LWR@restoreorigaccents}{%
    \LetLtxMacro\‘\LWR@origgraveaccent%
    \LetLtxMacro\’\LWR@origacuteaccent%
    \LetLtxMacro\^\LWR@origcircumflexaccent%
    \LetLtxMacro\~\LWR@origtildeaccent%
    \LetLtxMacro\=\LWR@origmacronaccent%
    \LetLtxMacro\u\LWR@origbreve%
    \LetLtxMacro\.\LWR@origdotaccent%
    \LetLtxMacro\"\LWR@origdiaeresisaccent%
    \LetLtxMacro\H\LWR@origdoubleacuteaccent%
    \LetLtxMacro\v\LWR@origcaronaccent%
    \LetLtxMacro\t\LWR@origtie%
    \LetLtxMacro\d\LWR@origdotbelowaccent%
    \LetLtxMacro\c\LWR@origcedillaaccent%
    \LetLtxMacro\b\LWR@origmacronbelowaccent%
}%
\else% XeLaTeX, LuaLaTeX:
\newcommand*{\LWR@restoreorigaccents}{%
    \LetLtxMacro\t\LWR@origtie%
}%
```

```
\fi%
}% AtBeginDocument

\end{warpHTML}
```

# 40 Configuration files

## 40.1 Decide whether to generate configuration files

Configuration files are only written if processing the print version of the document, and not processing a pstool image. pstool uses an additional compile for each image using the original document's preamble, which includes lwarp, so the lwarp configuration files are turned off if `-pstool` is part of the `\jobname`.

Default to no configuration files:

```
\LWR@excludecomment{LWRwriteconf}{writeconf}
```

Generate configuration files if print mode and not `-pstool`:

**for PRINT output:**

```
\begin{warpprint}
\fullexpandarg%
\IfSubStr*{\jobname}{-pstool}
    {
        \PackageInfo{lwarp}{%
            Jobname with -pstool is found.\MessageBreak
            Not generating lwarp configuration files,%
        }
    }
    {
        \PackageInfo{lwarp}{Generating lwarp configuration files,}%
        \LWR@includecomment{LWRwriteconf}{writeconf}
    }
\end{warpprint}
```

## 40.2 <project>_html.tex

File `*_html.tex` Used to allow an HTML version of the document to exist alongside the print version.

**Config file:**

```
\begin{LWRwriteconf}
\immediate\openout\LWR@quickfile=\jobname_html.tex
\immediate\write\LWR@quickfile{%
\detokenize{\PassOptionsToPackage}%
{warpHTML,BaseJobname=\jobname}{lwarp}%
}
\immediate\write\LWR@quickfile{%
\detokenize{\input}\string{\jobname.tex\string }%
}
\immediate\closeout\LWR@quickfile
\end{LWRwriteconf}
```

## 40.3 *lwarpmk* configuration files

**Config file:** 1938 `\begin{LWRwriteconf}`

`\LWR@lwarpconfversion` The version number of the configuration file, allowing *lwarpmk* to detect an obsolete configuration file format. Incremented by one each time the configuration file format changes. (This is NOT the same as the lwarp version number.)

1939 `\newcommand*{\LWR@lwarpconfversion}{2}% also in lwarpmk.lua`

### 40.3.1 Helper ma303(c2{2})-L{2-187.397 22.101 Td[(1939)]TJ/F798.9664 Tf14.7158 Td[(\newcom.645G F14

For *xelatex* with `--shell-escape`:

```
[[latexmk   -xelatex   --shell-escape  -recorder
    -e '$makeindex = q/makeindex -s lwarp.ist/'  <jobname>_html]]
```

For *dvipdfmx*:

```
[[latexmk   -pdfdvi  -e '$dvipdf=q/dvipdfmx %O -o %D %S/'
    -recorder
    -e '$makeindex=q/makeindex -s lwarp.ist/'   <jobname>_html]]
```

For the following, temporary values are computed, but the permanent values are only set if the originals were not assigned by the user.

```
\ifbool{LWR@latexmk}{
```

For *latexmk* with *pdflatex* or *lualatex*:

```
    \ifpdf
```

For *latexmk* with *pdflatex*:

```
        \ifPDFTeX
            \def\LWR@latexcmd{\LWR@latexmkcmd{-pdf -dvi- -ps-}}
        \else
```

For *latexmk* with *lualatex*:

```
            \ifLuaTeX
                \def\LWR@latexcmd{\LWR@latexmkcmd{-lualatex}}
            \else
                \LWR@unknownengine
            \fi
        \fi
    \else% \ifpdf
```

For *latexmk* with *xelatex* or DVI *latex*:

```
        \ifXeTeX
```

For *latexmk* with *xelatex*:

```
            \def\LWR@latexcmd{\LWR@latexmkcmd{-xelatex}}
        \else% \ifXeTeX
```

For *latexmk* with DVI *latex*:

```
            \ifbool{LWR@dvipdfm}{
                \def\LWR@latexcmd{%
```

```
                    \LWR@latexmkcmd{%
                        \LWR@latexmkdvipdfm{dvipdfm}%
                    }
                }
            }{
                \ifbool{LWR@dvipdfmx}{
                    \def\LWR@latexcmd{%
                        \LWR@latexmkcmd{%
                            \LWR@latexmkdvipdfm{dvipdfmx}%
                        }
                    }
                }{
                    \def\LWR@latexcmd{\LWR@latexmkcmd{-pdfps}}
                }
            }
        \fi
    \fi% \ifpdf
```

The final assignment if *latexmk*:

```
    \def\LWR@tempprintlatexcmd{\LWR@latexcmd \space \jobname}
    \def\LWR@tempHTMLlatexcmd{\LWR@latexcmd \space \jobname_html}
}% latexmk
```

Without *latexmk*, the compiling command is simply the compiler name and the optional shell escape:

```
{% not latexmk
    \ifpdf
```

For *pdflatex* or *lualatex*:

```
        \ifPDFTeX
```

For *pdflatex*:

```
            \def\LWR@tempprintlatexcmd{\LWR@compilecmd{pdflatex}{}}
            \def\LWR@tempHTMLlatexcmd{\LWR@compilecmd{pdflatex}{_html}}
        \else
            \ifLuaTeX
```

For *lualatex*:

```
                \def\LWR@tempprintlatexcmd{\LWR@compilecmd{lualatex}{}}
                \def\LWR@tempHTMLlatexcmd{\LWR@compilecmd{lualatex}{_html}}
            \else
                \LWR@unknownengine
            \fi
        \fi
    \else% \ifpdf
```

For DVI *latex* or *xelatex*:

```
        \ifXeTeX
```

For *xelatex*:

```
            \def\LWR@tempprintlatexcmd{\LWR@compilecmd{xelatex}{}}
            \def\LWR@tempHTMLlatexcmd{\LWR@compilecmd{xelatex}{_html}}
        \else
```

For DVI *latex*. Default to *dvips*, unless told to use *dvipdfm* or *dvipdfmx*:

```
            \ifbool{LWR@dvipdfm}{
```

For DVI *latex* with *dvipdfm*:

```
                \def\LWR@tempprintlatexcmd{%
                    \LWR@compilecmd{latex}{}
                    \LWR@addcompilecmd{dvipdfm}{}
                }
                \def\LWR@tempHTMLlatexcmd{%
                    \LWR@compilecmd{latex}{_html}
                    \LWR@addcompilecmd{dvipdfm}{_html}
                }
            }{
                \ifbool{LWR@dvipdfmx}{
```

For DVI *latex* with *dvipdfmx*:

```
                    \def\LWR@tempprintlatexcmd{%
                        \LWR@compilecmd{latex}{}
                        \LWR@addcompilecmd{dvipdfmx}{}
                    }
                    \def\LWR@tempHTMLlatexcmd{%
                        \LWR@compilecmd{latex}{_html}
                        \LWR@addcompilecmd{dvipdfmx}{_html}
                    }
                }{% dvips
```

For DVI *latex* with *dvips* and *ps2pdf*:

```
                    \def\LWR@tempprintlatexcmd{%
                        \LWR@compilecmd{latex}{}
                        \LWR@addcompilecmd{dvips}{}
                        \LWR@addcompilecmd{ps2pdf}{}.ps
                    }
                    \def\LWR@tempHTMLlatexcmd{%
                        \LWR@compilecmd{latex}{_html}
                        \LWR@addcompilecmd{dvips}{_html}
                        \LWR@addcompilecmd{ps2pdf}{_html}.ps
                    }
                }
            }
        \fi% \ifXeTeX
    \fi% \ifpdf
}% latexmk
```

For ujarticle, utarticle, and related, using upLaTeX and *dvipdfmx*:

```
\@ifclassloaded{ujarticle}{\LWR@compileuplatex}{}
\@ifclassloaded{ujbook}{\LWR@compileuplatex}{}
\@ifclassloaded{ujreport}{\LWR@compileuplatex}{}
\@ifclassloaded{utarticle}{\LWR@compileuplatex}{}
\@ifclassloaded{utbook}{\LWR@compileuplatex}{}
\@ifclassloaded{utreport}{\LWR@compileuplatex}{}
```

Only make the setting permanent if the original was empty:

```
\ifdefempty{\LWR@PrintLatexCmd}{
    \def\LWR@PrintLatexCmd{\LWR@tempprintlatexcmd}
}{}
\ifdefempty{\LWR@HTMLLatexCmd}{
    \def\LWR@HTMLLatexCmd{\LWR@tempHTMLlatexcmd}
}{}
```

`\LWR@writeconf` {⟨*filename*⟩}

Common code for each of `lwarpmk.conf` and `<project>.lwarpmkconf`. Each entry is a variable name, the equal sign, and a quoted string inside `[[` and `]]`, which are *lua*'s long quote characters, allowing the use of single and double quotes inside.

```
\newcommand{\LWR@writeconf}[1]{
\ifcsdef{LWR@quickfile}{}{\newwrite{\LWR@quickfile}}
\immediate\openout\LWR@quickfile=#1
\immediate\write\LWR@quickfile{confversion = [[\LWR@lwarpconfversion]]}
\ifbool{usingOSWindows}{
    \immediate\write\LWR@quickfile{opsystem = [[Windows]]}
}{
    \immediate\write\LWR@quickfile{opsystem = [[Unix]]}
}
\immediate\write\LWR@quickfile{sourcename = [[\jobname]]}
\immediate\write\LWR@quickfile{homehtmlfilename = [[\HomeHTMLFilename]]}
\immediate\write\LWR@quickfile{htmlfilename = [[\HTMLFilename]]}
\immediate\write\LWR@quickfile{imagesdirectory = [[\LWR@ImagesDirectory]]}
\immediate\write\LWR@quickfile{imagesname = [[\LWR@ImagesName]]}
\immediate\write\LWR@quickfile{latexmk = [[\ifbool{LWR@latexmk}{true}{false}]]}
\immediate\write\LWR@quickfile{printlatexcmd = [[\LWR@PrintLatexCmd]]}
\immediate\write\LWR@quickfile{HTMLlatexcmd = [[\LWR@HTMLLatexCmd]]}
\immediate\write\LWR@quickfile{printindexcmd = [[\LWR@PrintIndexCmd]]}
\immediate\write\LWR@quickfile{HTMLindexcmd = [[\LWR@HTMLIndexCmd]]}
\immediate\write\LWR@quickfile{latexmkindexcmd = [[\LWR@LatexmkIndexCmd]]}
\immediate\write\LWR@quickfile{glossarycmd = [[\LWR@GlossaryCmd]]}
\immediate\write\LWR@quickfile{pdftotextenc = [[\LWR@pdftotextEnc]]}
\immediate\closeout\LWR@quickfile
}


\end{LWRwriteconf}
```

### 40.3.2 `lwarpmk.conf`

File `lwarpmk.conf` `lwarpmk.conf` is automatically (re-)created by the lwarp package when executing

```
a.tocsection {display: inline-block ; margin-left: 1em ;
    text-indent: -.5em ; font-weight: bold ; }
a.tocsubsection {display: inline-block ; margin-left: 2em ;
    text-indent: -.5em ; }
a.tocsubsubsection {display: inline-block ; margin-left: 3em ;
    text-indent: -.5em ; }
a.tocparagraph {display: inline-block ; margin-left: 4em ;
    text-indent: -.5em ; }
a.tocsubparagraph {display: inline-block ; margin-left: 5em ;
    text-indent: -.5em ; }
a.tocfigure {margin-left: 0em}
a.tocsubfigure {margin-left: 2em}
a.toctable {margin-left: 0em}
a.tocsubtable {margin-left: 2em}
a.toctheorem {margin-left: 0em}
a.toclstlisting {margin-left: 0em}

body {
    font-family: "DejaVu Serif", "Bitstream Vera Serif",
        "Lucida Bright", Georgia, serif;
    background: #FAF7F4 ;
    color: black ;
    margin:0em ;
    padding:0em ;
    font-size: 100% ;
    line-height: 1.2 ;
}

p {margin: 1.5ex 0em 1.5ex 0em ;}
table p {margin: .5ex 0em .5ex 0em ;}

/* Holds a section number */
span.sectionnumber { margin-right: 0em }

/* Inserted in front of index lines */
span.indexitem {margin-left: 0em}
span.indexsubitem {margin-left: 2em}
span.indexsubsubitem {margin-left: 4em}
div.indexheading {margin-top: 2ex ; font-weight: bold}

div.hidden, span.hidden { display: none ; }

kbd, span.texttt, p span.texttt {
    font-family: "DejaVu Mono", "Bitstream Vera Mono", "Lucida Console",
        "Nimbus Mono L", "Liberation Mono", "FreeMono", "Andale Mono",
        "Courier New", monospace;
    font-size: 100% ;
}

pre { padding: 3pt ; }

span.strong, span.textbf, div.strong, div.textbf { font-weight: bold; }

span.textit, div.textit { font-style: italic; }

```

```
span.textmd, div.textmd { font-weight: normal; }

span.textup, div.textup {
    font-style: normal;
    font-variant: normal;
    font-variant-numeric: normal ;
}

span.textsc, div.textsc {
    font-variant: small-caps;
    font-variant-numeric: oldstyle-nums ;
}

span.textulc, div.textulc {
    font-variant: normal ;
    font-variant-numeric: normal ;
}

span.textsl, div.textsl { font-style: oblique; }

span.textrm, div.textrm {
    font-family: "DejaVu Serif", "Bitstream Vera Serif",
    "Lucida Bright", Georgia, serif;
}

span.textsf, div.textsf {
     font-family: "DejaVu Sans", "Bitstream Vera Sans",
        Geneva, Verdana, sans-serif ;
}

/* nfssext-cfr lining figures */
span.textln, div.textln {
    font-variant-numeric: lining-nums ;
}

/* nfssext-cfr proportional figures */
span.textp, div.textp {
    font-variant-numeric: proportional-nums ;
}

/* nfssext-cfr tabular figures */
span.textt, div.textt {
    font-variant-numeric: tabular-nums ;
}

/* nfssext-cfr font weights */
span.textdb, div.textdb {
    font-weight: 500 ;
}

span.textsb, div.textsb {
    font-weight: 600 ;
}

span.texteb, div.texteb {
```

```
    font-weight: 800 ;
}

span.textub, div.textub {
    font-weight: 900 ;
}

span.textlg, div.textlg {
    font-weight: 300 ;
}

span.textel, div.textel {
    font-weight: 200 ;
}

span.textul, div.textul {
    font-weight: 100 ;
}



span.textcircled { border: 1px solid black ; border-radius: 1ex ; }

span.underline {
    text-decoration: underline ;
    text-decoration-skip: auto ;
}

span.overline {
    text-decoration: overline ;
    text-decoration-skip: auto ;
}

div.hrule { border-top: 1px solid silver }


/* for vertical text: */
div.verticalrl { writing-mode: vertical-rl }
div.horizontaltb { writing-mode: horizontal-tb }


/* for diagbox */
div.diagboxtitleN { border-bottom: 1px solid gray }
div.diagboxtitleS { border-top: 1px solid gray }

div.diagboxE {
    padding-left: 2em ;
    text-align: right ;
}

div.diagboxW {
    padding-right: 2em ;
    text-align: left ;
}

```

```
2317
2318
2319 /* For realscripts */
2320 .supsubscript {
2321     display: inline-block;
2322     text-align:left ;
2323 }
2324
2325 .supsubscript sup,
2326 .supsubscript sub {
2327     position: relative;
2328     display: block;
2329     font-size: .7em;
2330     line-height: 1;
2331 }
2332
2333 .supsubscript sup {
2334     top: .3em;
2335 }
2336
2337 .supsubscript sub {
2338     top: .3em;
2339 }
2340
2341 div.attribution p {
2342     text-align: right ;
2343     font-size: 80%
2344 }
2345
2346 span.poemtitle {
2347   font-size: 120% ; font-weight: bold;
2348 }
2349
2350 pre.tabbing {
2351     font-family: "Linux Libertine Mono O", "Lucida Console",
2352         "Droid Sans Mono", "DejaVu Mono", "Bitstream Vera Mono",
2353         "Liberation Mono", "FreeMono", "Andale Mono",
2354         "Nimbus Mono L", "Courier New", monospace;
2355 }
2356
2357 blockquote {
2358     display: block ;
2359     margin-left: 2em ;
2360     margin-right: 2em ;
2361 }
2362
2363 /* quotchap is for the quotchap package */
2364 div.quotchap {
2365     display: block ;
2366     font-style: oblique ;
2367     overflow-x: auto ;
2368     margin-left: 2em ;
2369     margin-right: 2em ;
2370 }
2371
```

```
blockquote p, div.quotchap p {
    line-height: 1.5;
    text-align: left ;
    font-size: .85em ;
}

/* qauthor is for the quotchap package */
div.qauthor {
  display: block ;
  text-align: right ;
  margin-left: auto ;
  margin-right: 2em ;
  font-size: 80% ;
  font-variant: small-caps;
}

div.qauthor p {
  text-align: right ;
}

div.epigraph, div.dictum {
  line-height: 1.2;
    text-align: left ;
    padding: 3ex 1em 0ex 1em ;
/*     margin: 3ex auto 3ex auto ; */ /* Epigraph centered */
    margin: 3ex 1em 3ex auto ; /* Epigraph to the right */
/*    margin: 3ex 1em 3ex 1em ; */ /* Epigraph to the left */
    font-size: .85em ;
    max-width: 27em ;
}

div.epigraphsource, div.dictumauthor {
    text-align:right ;
    margin-left:auto ;
/*     max-width: 50% ; */
    border-top: 1px solid #A0A0A0 ;
    padding-bottom: 3ex ;
    line-height: 1.2;
}

div.epigraph p, div.dictum p { padding: .5ex ; margin: 0ex ;}
div.epigraphsource p, div.dictumauthor p { padding: .5ex 0ex 0ex 0ex ; margin: 0ex ;}
div.dictumauthor { font-style:italic }


/* copyrightbox package: */
div.copyrightbox { margin: .5ex .5em }
div.copyrightbox p {margin: 0px .5em ; padding: 0px}
div.copyrightboxnote {text-align: left ; font-size: 60%}


/* lettrine package: */
span.lettrine { font-size: 4ex ; float: left ; }
span.lettrinetext { font-variant: small-caps ; }

```

```
/* ulem, soul, umoline packages: */
span.uline {
    text-decoration: underline ;
    text-decoration-skip: auto ;
}

span.uuline {
    text-decoration: underline ;
    text-decoration-skip: auto ;
    text-decoration-style: double ;
}

span.uwave {
    text-decoration: underline ;
    text-decoration-skip: auto ;
    text-decoration-style: wavy ;
}

span.sout {
    text-decoration: line-through ;
}

span.oline {
    text-decoration: overline ;
    text-decoration-skip: auto ;
}

span.xout {
    text-decoration: line-through ;
}

span.dashuline {
    text-decoration: underline ;
    text-decoration-skip: auto ;
    text-decoration-style: dashed ;
}

span.dotuline {
    text-decoration: underline ;
    text-decoration-skip: auto ;
    text-decoration-style: dotted ;
}

span.letterspacing { letter-spacing: .2ex ; }

span.capsspacing {
    font-variant: small-caps ;
    letter-spacing: .1ex ;
}

span.highlight { background: #F8E800 ; }


/* keystroke package: */
span.keystroke {
```

```
}

h1 {
  margin: 0ex 0em 0ex 0em ;
  line-height: 1.3;
  text-align: center ;
}

h2 {
  margin: 1ex 0em 1ex 0em ;
  line-height: 1.3;
  text-align: center ;
}

h3 {
  margin: 3ex 0em 1ex 0em ;
  line-height: 1.3;
}

h4 {
  margin: 3ex 0em 1ex 0em ;
  line-height: 1.3;
}

h5 {
  margin: 3ex 0em 1ex 0em ;
  line-height: 1.3;
}

h6 {
  margin: 3ex 0em 1ex 0em ;
  line-height: 1.3;
}


div.titlepage {
  text-align: center ;
}

.footnotes {
    text-align: left ;
    font-size: .85em ;
    margin: 3ex 2em 0ex 2em ;
    border-top: 1px solid silver ;
}

.marginpar, .marginparblock {
    max-width: 50%;
    float: right ;
    clear: both ;
    text-align: left ;
    margin: 1ex 0.5em 1ex 1em ;
    padding: 1ex 0.5em 1ex 0.5em ;
    font-size: 85% ;
    border-top: 1px solid silver ;
```

```
    border-bottom: 1px solid silver ;
    overflow-x: auto ;
}

.marginpar br { margin-bottom: 2ex ; }

div.marginblock, div.marginparblock {
    max-width:50%;
    min-width: 10em; /* room for caption */
    float:right;
    text-align:left;
    margin: 1ex 0.5em 1ex 1em ;
    padding: 1ex 0.5em 1ex 0.5em ;
    overflow-x: auto;
}

div.marginblock div.minipage,
div.marginparblock div.minipage {
    display: inline-block ;
    margin: 0pt auto 0pt auto ;
}

div.marginblock div.minipage p ,
div.marginparblock div.minipage p
    { font-size: 85%}

div.marginblock br ,
div.marginparblock br
    { margin-bottom: 2ex ; }

div.bodycontainer {
    float: left ;
    width: 80% ;
}

div.bodywithoutsidetoc div.bodycontainer {
    float: none ;
    width: 100% ;
}

section.textbody div.footnotes{
    margin: 3ex 2em .5ex 2em ;
    border-bottom: 2px solid silver ;
}

.footnoteheader {
    border-top: 2px solid silver ;
    margin-top: 3ex ;
    padding-top: 1ex ;
    font-weight: bold ;
}

.mpfootnotes {
    text-align: left ;
    font-size: .85em ;
```

```
    margin-left: 1em ;
    border-top: 1px solid silver ;
}

/* Remove footnote top border in the title page. */
div.titlepage div.mpfootnotes {
    border-top: none ;
}



ul, ol {
  margin: 1ex 1em 1ex 0em;
  line-height: 1.2;
}

body dir, body menu {
  margin: 3ex 1em 3ex 0em;
  line-height: 1.2;
}

li { margin: 0ex 0em 1ex 0em; }

html {
  margin: 0;
  padding: 0;
}

.programlisting {
  font-family: "DejaVu Mono", "Bitstream Vera Mono", "Lucida Console",
        "Nimbus Mono L", "Liberation Mono", "FreeMono", "Andale Mono",
        "Courier New", monospace;
  margin: 1ex 0ex 1ex 0ex ;
  padding: .5ex 0pt .5ex 0pt ;
  overflow-x: auto;
}

section.textbody>pre.programlisting {
border-top: 1px solid silver ;
border-bottom: 1px solid silver ;
}


div.displaymath {
    text-align: center ;
}

div.displaymathnumbered {
    text-align: right ;
    margin-left: 5% ;
    margin-right: 5% ;
    min-width: 2.5in ;
}

@media all and (min-width: 400px) {
```

```
    div.displaymathnumbered {
        margin-left: 10% ;
        margin-right: 10% ;
    }
}

@media all and (min-width: 800px) {
    div.displaymathnumbered {
        margin-right: 20% ;
    }
}

@media all and (min-width: 1200px) {
    div.displaymathnumbered {
        margin-right: 30% ;
    }
}


.inlineprogramlisting {
  font-family: "DejaVu Mono", "Bitstream Vera Mono", "Lucida Console",
        "Nimbus Mono L", "Liberation Mono", "FreeMono", "Andale Mono",
        "Courier New", monospace;
  overflow-x: auto;
}

span.listinglabel {
    display: inline-block ;
    font-size: 70% ;
    width: 4em ;
    text-align: right ;
    margin-right: 2em ;
}

div.abstract {
  margin: 2em 5% 2em 5% ;
  padding: 1ex 1em 1ex 1em ;
/*  font-weight: bold ; */
  font-size: 90% ;
    text-align: left ;
}

div.abstract dl {line-height:1.5;}
div.abstract dt {color:#304070;}

div.abstracttitle{
    font-family: "URW Classico", Optima, "Linux Biolinum O",
        "Linux Libertine O", "Liberation Serif", "Nimbus Roman No 9 L",
        "FreeSerif", "Hoefler Text", Times, "Times New Roman", serif;
    font-weight:bold;
    font-size:1.25em;
    text-align: center ;
}

span.abstractrunintitle{
```

```
    font-family: "URW Classico", Optima, "Linux Biolinum O",
        "Linux Libertine O", "Liberation Serif", "Nimbus Roman No 9 L",
        "FreeSerif", "Hoefler Text", Times, "Times New Roman", serif;
    font-weight:bold;
}


.verbatim {
    overflow-x: auto ;
}

.alltt {
    overflow-x: auto ;
}


.bverbatim {
    margin: 1ex 0pt 1ex 0pt ;
    padding: .5ex 0pt .5ex 0pt ;
    overflow-x: auto ;
}

.lverbatim {
    margin: 1ex 0pt 1ex 0pt ;
    padding: .5ex 0pt .5ex 0pt ;
    overflow-x: auto ;
}

.fancyvrb {
    font-size:.85em ;
    margin: 3ex 0pt 3ex 0pt
}

.fancyvrblabel {
    font-size: .85em ;
    text-align: center ;
    font-weight: bold ;
    margin-top: 1ex ;
    margin-bottom: 1ex ;
}


.verse {
    font-family: "Linux Libertine Mono O", "Lucida Console",
        "Droid Sans Mono", "DejaVu Mono", "Bitstream Vera Mono",
        "Liberation Mono", "FreeMono", "Andale Mono",
        "Nimbus Mono L", "Courier New", monospace;
    margin-left: 1em ;
}


div.singlespace { line-height: 1.2 ; }
div.onehalfspace { line-height: 1.5 ; }
div.doublespace { line-height: 2 ; }

```

```
2812
2813 /* Word processor format output: */
2814 div.wpfigure { border: 1px solid red ; margin: .5ex ; padding: .5ex ; }
2815 div.wptable { border: 1px solid blue ; margin: .5ex ; padding: .5ex ; }
2816 div.wpminipage { border: 1px solid green ; margin: .5ex ; padding: .5ex ;}
2817
2818
2819
2820
2821 /* Minipage environments, vertically aligned to top, center, bottom: */
2822 .minipage, .fminipage, .fcolorminipage {
2823     /* display: inline-block ; */
2824         /* Mini pages which follow each other will be tiled. */
2825     text-align:left;
2826     margin: .25em .25em .25em .25em;
2827     padding: .25em .25em .25em .25em;
2828     display: inline-flex;
2829     flex-direction: column ;
2830     overflow: auto;
2831 }
2832
2833 .inlineminipage {
2834     display: inline-block ;
2835     text-align: left
2836 }
2837
2838 /* Paragraphs in the flexbox did not collapse their margins. */
2839 /* Have not yet researched this. */
2840 .minipage p {margin: .75ex 0em .75ex 0em ;}
2841
2842 .fboxBlock .minipage, .colorbox .minipage, .colorboxBlock .minipage,
2843 .fcolorbox .minipage, .fcolorboxBlock .minipage
2844     {border: none ; background: none: none ; background: none:
    283728422842
2830
```

```
}

.ovalbox, .Ovalbox {
   border: 1px solid black;
     border-radius: 1ex ;
    padding: .4ex .3em .4ex .3em ;
    margin: 0pt .3ex 0pt .3ex ;
  display: inline-block ;
}

.Ovalbox { border-width: 2px ; }

.framebox {
   border: 1px solid black;
     border-radius: 0px ;
    padding: .3ex .2em 0ex .2em ;
    margin: 0pt .1ex 0pt .1ex ;
  display: inline-block ;
}


/* mdframed, tcolorbox, shadebox packages */
.mdframed, .tcolorbox, .shadebox {
    padding: 0ex ;
    margin: 2ex 0em 2ex 0em ;
    border: 1px solid black ;
}

.tcolorbox {
    border-radius: 10pt ;
    margin: 2ex 1em 2ex 1em ;
}

.mdframed p, .tcolorbox p { padding: 0ex .5em 0ex .5em ; }

.mdframed dl, .tcolorbox dl { padding: 1ex .5em 0ex .5em ; }

.mdframedtitle, .tcolorboxtitle {
    padding: .5ex 0pt 0pt 0pt ;
    border-radius: 10pt 10pt 0pt 0pt ;
    display: block ;
    margin-bottom: 1ex ;
    border-bottom: 1px solid silver ;
}

.tcolorboxsubtitle .tcolorbox {
    margin: 2ex 0em 2ex 0em ;
    border-radius: 0pt ;
}

.mdframedsubtitle {
    display: block ;
}

.mdframedsubsubtitle {
```

```
    display: block ;
}

.mdtheorem {
    padding: 0ex .5em 0ex .5em ;
    margin: 3ex 5% 3ex 5% ;
}


/* framed package */
.framed, pre.boxedverbatim, fcolorbox {
    margin: 3ex 0em 3ex 0em ;
   border: 1px solid black;
     border-radius: 0px ;
    padding: .3ex 1em 0ex 1em ;
  display: block ;
}

.shaded {
    margin: 3ex 0em 3ex 0em ;
    padding: .3ex 1em .3ex 1em ;
    display: block ;
}

.snugframed {
    margin: 3ex 0em 3ex 0em ;
   border: 1px solid black;
     border-radius: 0px ;
  display: block ;
}

.framedleftbar {
    margin: 3ex 0em 3ex 0em ;
   border-left: 3pt solid black;
     border-radius: 0px ;
    padding: .3ex .2em .3ex 1em ;
  display: block ;
}

.framedtitle {
    margin: 0em ;
    padding: 0em ;
    font-size: 130%
}

.framedtitle p { padding: .3em }


/* For the niceframe package: */

div.niceframe, div.curlyframe, div.artdecoframe, div.generalframe {
    padding: 1ex ;
    margin: 2ex auto ;
    border-radius: 2ex ;
}
```

```
2977
2978 div.niceframe {
2979     border: 6px groove black ;
2980 }
2981
2982 div.curlyframe {
2983     border-left: 3px dotted black ;
2984     border-right: 3px dotted black ;
2985     border-radius: 6ex ;
2986 }
2987
2988 div.artdecoframe {
2989     border-left: 10px double black ;
2990     border-right: 10px double black ;
2991     border-radius: 6ex ;
2992 }
2993
2994 div.generalframe {
2995     border: 6px groove black ;
2996 }
2997
2998
2999
3000 dl {
3001   margin: 1ex 2em 1ex 0em;
3002   line-height: 1.3;
3003 }
3004
3005 dl dt {
3006     display: block ;
3007     float:left ;
3008     font-weight: bold;
3009     padding-right: 1em ;
3010 }
3011
3012 dl dd { display: block ; }
3013
3014 dl dd:after { content: "" ; display: block ; clear: both }
3015
3016 dl dd p { margin-top: 0em; }
3017
3018 dd ul, dd ol, dd dl {
3019     clear: both ;
3020 /*    padding-top: 1ex ; */
3021 }
3022
3023
3024 nav {
3025     font-family: "URW Classico", Optima, "Linux Biolinum O",
3026         "DejaVu Sans", "Bitstream Vera Sans",
3027         Geneva, Verdana, sans-serif ;
3028     margin-bottom: 4ex ;
3029 }
3030
3031 nav p {
```

```
    line-height: 1.2 ;
    margin-top:.5ex ;
    margin-bottom:.5ex;
    font-size: .9em ;
}


img, img.hyperimage, img.borderimage {
    max-width: 600px;
    border: 1px solid silver;
    box-shadow: 3px 3px 3px #808080 ;
    padding: .5% ;
    margin: .5% ;
    background: none ;
}

img.inlineimage{
    padding: 0px ;
    box-shadow: none ;
    border: none ;
    background: none ;
    margin: 0px ;
    display: inline-block ;
    border-radius: 0px ;
}

img.logoimage{
    max-width: 300px ;
    box-shadow: 3px 3px 3px #808080 ;
    border: 1px solid black ;
    background:none ;
    padding:0 ;
    margin:.5ex ;
    border-radius: 10px ;
}


.section {
/*
    To have each section float relative to each other:
*/
/*
    display: block ;
    float: left ;
    position: relative ;
    background: white ;
    border: 1px solid silver ;
    padding: .5em ;
*/
    margin: 0ex .5em 0ex .5em ;
    padding: 0 ;
}


```

```
figure {
    margin: 5ex auto 5ex auto ;
    padding: 1ex 1em 1ex 1em ;
    overflow-x: auto ;
}


/* To automatically center images in figures: */
/*
figure img.inlineimage {
    margin: 0ex auto 0ex auto ;
    display: block ;
}
*/

/* To automatically center minipages in figures: */
/*
figure div.minipage, figure div.minipage div.minipage {
    margin: 1ex auto 1ex auto ;
    display: block ;
}
*/

figure figure { margin: 0pt }

figure div.minipage p { font-size: 85% ; }

figure.subfigure, figure.subtable  {
    display: inline-block ; margin: 3ex 1em 3ex 1em ;
}

div.figurecaption .minipage { margin:0 ; padding: 0 }

div.minipage figure { border: none ; box-shadow: none ; }
div.minipage figure.table { margin: 0ex }
div.minipage div.footnotes { margin: 1ex 2em 0ex 2em }

div.floatrow { text-align: center; }

div.floatrow figure { display: inline-block ; margin: 1ex 2% ; }

div.floatfoot { font-size: .85em ;
    border-top: 1px solid silver ; line-height: 1.2 ; }

div.figurecaption , .lstlistingtitle {
    font-size: .85em ;
    text-align: center ;
    font-weight: bold ;
    margin-top: 1ex ;
    margin-bottom: 1ex ;
}

figure.subfigure div.figurecaption, figure.subtable div.figurecaption  {
    border-bottom: none ; background: none ;
}
```

```
3142
3143 div.nonfloatcaption {
3144     margin: 1ex auto 1ex auto ;
3145     font-size: .85em ;
3146     text-align: center ;
3147     font-weight: bold ;
3148 }
3149
3150 /* For a \RawCaption inside a minipage inside a figure's floatrow: */
3151 figure div.floatrow div.minipage div.figurecaption {
3152     border: none ;
3153     background: none ;
3154 }
3155
3156
3157 /* For packages such as float, rotfloat, and algorithm2e: */
3158
3159 figure.boxed, figure.boxruled {
3160     border: 1px solid black ;
3161 }
3162
3163 figure.ruled {
3164     border-top: 1px solid black ;
3165     border-bottom: 1px solid black ;
3166     border-left: 0px ;
3167     border-right: 0px ;
3168     border-radius: 0px ;
3169     background: none ;
3170     box-shadow: none ;
3171 }
3172
3173 figure.ruled div.figurecaption, figure.boxruled div.figurecaption {
3174     border-top: 1px solid silver ;
3175     border-bottom: 1px solid silver ;
3176 }
3177
3178
3179 table {
3180     margin: 1ex auto 1ex auto ;
3181     border-collapse: separate ;
3182     border-spacing: 0px ;
3183     line-height: 1.3 ;
3184     }
3185
3186 table > tbody > tr.hline > td {border-top: 1px solid #808080 ; margin-top: 0ex ;
3187     margin-bottom: 0ex ; } /* for \hline */
3188
3189 tr.tbrule td {border-top: 1px solid black ; margin-top: 0ex ;
3190     margin-bottom: 0ex ; } /* for \toprule, \bottomrule */
3191
3192 td {padding: .5ex .5em .5ex .5em ;}
3193
3194 table td.tdl { text-align: left ; vertical-align: middle ; }
3195 table td.tdc { text-align: center ; vertical-align: middle ; }
3196 table td.tdat { text-align: center ; vertical-align: middle ; padding: 0px ; margin: 0px ; }
```

```
table td.tdbang { text-align: center ; vertical-align: middle ; }
table td.tdr { text-align: right ; vertical-align: middle ; }
table td.tdp { text-align: left ; vertical-align: bottom ; }
table td.tdm { text-align: left ; vertical-align: middle ; }
table td.tdb { text-align: left ; vertical-align: top ; }
table td.tdP { text-align: center ; vertical-align: bottom ; }
table td.tdM { text-align: center ; vertical-align: middle ; }
table td.tdB { text-align: center ; vertical-align: top ; }

table td.tvertbarl { border-left: 1px solid black }
table td.tvertbarldouble { border-left: 4px double black }
table td.tvertbarr { border-right: 1px solid black }
table td.tvertbarrdouble { border-right: 4px double black }

table td.tvertbarldash { border-left: 1px dashed black }
table td.tvertbarldoubledash { border-left: 2px dashed black }
table td.tvertbarrdash { border-right: 1px dashed black }
table td.tvertbarrdoubledash { border-right: 2px dashed black }


/* for cmidrules: */
table td.tdrule {
    border-top: 1px solid #A0A0A0 ;
}

table td.tdrulel {
    border-top-left-radius:.5em ;
    border-top: 1px solid #A0A0A0 ;
}

table td.tdruler {
    border-top-right-radius:.5em ;
    border-top: 1px solid #A0A0A0 ;
}

table td.tdrulelr {
    border-top-left-radius:.5em ;
    border-top-right-radius:.5em ;
    border-top: 1px solid #A0A0A0 ;
}


/* Margins of paragraphs inside table cells: */
td.tdp p , td.tdprule p , td.tdP p , td.tdPrule p { padding-top: 1ex ;
    padding-bottom: 1ex ; margin: 0ex ; }
td.tdm p , td.tmbrule p , td.tdM p , td.tdMrule p { padding-top: 1ex ;
    padding-bottom: 1ex ; margin: 0ex ; }
td.tdb p , td.tdbrule p , td.tdB p , td.tdBrule p { padding-top: 1ex ;
    padding-bottom: 1ex ; margin: 0ex ; }

td.tdp , td.tdprule , td.tdP , td.tdPrule
    { padding: 0ex .5em 0ex .5em ; }
td.tdm , td.tdmrule , td.tdM , td.tdMrule
    { padding: 0ex .5em 0ex .5em ; }
td.tdb , td.tdbrule , td.tdB , td.tdBrule
```

```
    { padding: 0ex .5em 0ex .5em ; }


/* table notes: */
.tnotes {
    margin: 0ex 5% 1ex 5% ;
    padding: 0.5ex 1em 0.5ex 1em;
    font-size:.80em;
    text-align: left ;
}

.minipage .tnotes {
    margin: 0pt ;
    padding: 0pt ;
}

.tnotes dl dt p {margin-bottom:0px;}

.tnoteitemheader {margin-right: 1em;}


/* for colortbl and cell color */
div.cellcolor {
    width: 100% ;
    padding: .5ex .5em .5ex .5em ;
    margin: -.5ex -.5em -.5ex -.5em ;
}


/* for lyluatex */
span.lyluatex {
    display: inline-block ;
}

div.lyluatex p span.lateximagesource img {
    display: block ;
    margin-top: 3ex ;
    margin-bottom: 3ex ;
}


/* for bigdelim */
.ldelim, .rdelim { font-size: 200% }


/* center, flushleft, flushright environments */
div.center{text-align:center;}
div.center table {margin-left:auto;margin-right:auto;}
div.flushleft{text-align:left;}
div.flushleft table {margin-left:0em ; margin-right:auto;}
div.flushright{text-align:right;}
div.flushright table {margin-left:auto ; margin-right: 0em ;}


/* Fancybox */
```

```
div.Btrivlist table tr td {
    padding: .2ex 0em ;
}


/* program listing callouts: */
span.callout {
     font-family: "DejaVu Sans", "Bitstream Vera Sans",

```

```
    font-size: 1em ;
    margin: 1ex 0em 1ex 0em ;
}

div.subtitle
{
    text-align: center ;
    font-variant: normal ;
    font-style: italic ;
    font-size: 1.25em ;
    margin: 1ex 0em 1ex 0em ;
}

div.subtitle p { margin: 1ex ; }

div.author
{
    font-variant: normal ;
    font-style: normal ;
    font-size: 1em ;
    margin: 1ex 0em 1ex 0em ;
}

div.oneauthor {
    display: inline-block ;
    margin: 0ex 1em 0ex 1em ;
}

/*
div.author table {
    margin: 1ex auto 0ex auto ;
    background: none ;
}

div.author table tbody tr td { padding: .25ex ; }
*/

span.affiliation {font-size: .85em ; font-variant: small-caps; }

div.titledate {
    text-align: center ;
    font-size: .85em ;
    font-style: italic;
    margin: 1ex 0em 1ex 0em ;
}


nav.topnavigation{
    text-align: left ;
    padding: 0.5ex 1em 0.5ex 1em ;
/*     margin: 2ex 0em 3ex 0em ; */
    margin: 0 ;
    border-bottom: 1px solid silver ;
    border-top: 1px solid silver ;
    clear:both ;
```

```
}

nav.botnavigation{
    text-align: left ;
    padding: 0.5ex 1em 0.5ex 1em ;
/*     margin: 3ex 0em 2ex 0em ; */
    margin: 0 ;
    border-top: 1px solid silver ;
    border-bottom: 1px solid silver ;
    clear:both ;
}


header {
    line-height: 1.2 ;
    font-size: 1em ;
    border-bottom: 1px solid silver ;
    margin: 0px ;
    padding: 2ex 1em 2ex 1em ;
    text-align:left ;
}


footer {
    font-size: .85em ;
    line-height: 1.2 ;
    margin-top: 1ex ;
    border-top: 1px solid silver ;
    padding: 2ex 1em 2ex 1em ;
    clear:both ;
    text-align:left ;
}


/* for \LinkHome, \LinkPrevious, and \LinkNext: */
a.linkhome { font-weight:bold ; font-size: 1em ;}


div.lateximagesource { padding: 0px ; margin: 0px ; display: none; }

img.lateximage{
    padding: 0pt ;
    margin: 0pt ;
    box-shadow: none ;
    border: none ;
    background: none ;
    max-width: 100% ;
    border-radius: 0ex ;
    border: none ;
}


/* The -1px right margin compensates for the 1px right border. */
/* Without this -1px margin, the body container appears below instead */
/* of floating to the side. */
```

```
3472 div.sidetoccontainer {
3473     font-family: "DejaVu Serif", "Bitstream Vera Serif",
3474         "Lucida Bright", Georgia, serif;
3475     float: left ;
3476     width: 20%;
3477     margin: 0pt -1px 3ex 0pt ;
3478     border-right: 1px solid silver;
3479     border-bottom: 1px solid silver;
3480     background: #FAF7F4 ;
3481     font-size:.9em ;
3482     border-radius: 0px 0px 20px 0px ;
3483 }
3484
3485 div.sidetoccontents {
3486     overflow-y: auto ;
3487     width: 100% ;
3488     text-align: left ;
3489 }
3490
3491
3492 nav.sidetoc p {line-height:1.2 ; margin: 1ex .5em 1ex .5em ;
3493     text-indent: 0 ; }
3494
3495 nav.sidetoc p a {color:black ; font-size: .7em ;}
3496
3497 div.sidetoctitle {font-size: 1.2em; font-weight:bold; text-align:center;
3498     border-bottom: 1px solid silver ;    }
3499
3500 nav.sidetoc a:hover {text-decoration: underline ; }
3501
3502
3503
3504 section.textbody { margin: 0ex 1em 0ex 1em ;}
3505
3506
3507 div.multicolsheading { -webkit-column-span: all;
3508     -moz-column-span: all; column-span: all; }
3509 div.multicols { -webkit-columns: 3 380px ;
3510     -moz-columns: 3 380px ; columns: 3 380px ; }
3511 div.multicols p {margin-top: 0ex}
3512
3513
3514 /* Used for xfrac and nicefrac: */
3515 span.numerator {
3516     font-size: 60% ;
3517     vertical-align: .4em ;
3518 }
3519
3520 span.denominator {
3521     font-size: 60%
3522 }
3523
3524
3525 /* Used for algorithm2e: */
3526 div.alg2evline{
```

```
    margin-left: 1em ;
    padding-left: 1em ;
    border-left: 1px solid black ;
    border-radius: 0px 0px 0px 1ex ;
}

div.alg2evsline{
    margin-left: 1em ;
    padding-left: 1em ;
    border-left: 1px solid black ;
}

div.alg2enoline{
    margin-left: 1em ;
    padding-left: 1em ;
}

span.alg2elinenumber{
    margin-right: .5em ;
    font-size: 50% ;
    color: red ;
}


/* Used for algorithmicx: */
span.floatright { float: right ; }


/* keyfloat and tocdata: */
.floatnotes {
    margin: 0ex 5% 0ex 5% ;
    padding: 0ex 1em 0ex 1em ;
    font-size:.80em ;
    text-align: left ;
}

.authorartist{
    display:block ;
    font-size:.70em ;
    font-style: italic;
}

nav .authorartist{ display:inline; }



/* Native LaTeX theorems: */

.theoremcontents {
    font-style: italic; margin-top: 3ex ; margin-bottom: 3ex ;
}

.theoremlabel {
    font-style: normal; font-weight: bold ; margin-right: .5em ;
}
```

```
3582
3583
3584
3585 /* theorem, amsthm, and ntheorem packages */
3586
3587 span.theoremheader,
3588 span.theoremheaderplain,
3589 span.theoremheaderdefinition,
3590 span.theoremheaderbreak,
3591 span.theoremheadermarginbreak,
3592 span.theoremheaderchangebreak,
3593 span.theoremheaderchange,
3594 span.theoremheadermargin
3595 {
3596     font-style:normal ; font-weight: bold ; margin-right: 1em ;
3597 }
3598
3599 span.amsthmnameplain,
3600 span.amsthmnamedefinition,
3601 span.amsthmnumberplain,
3602 span.amsthmnumberdefinition
3603 {
3604     font-style:normal ; font-weight: bold ;
3605 }
3606
3607
3608 span.amsthmnameremark,
3609 span.amsthmnumberremark
3610 {font-style:italic ; font-weight: normal ; }
3611
3612
3613 span.amsthmnoteplain,
3614 span.amsthmnotedefinition
3615 {font-style:normal ;}
3616
3617
3618 span.theoremheaderremark,
3619 span.theoremheaderproof,
3620 span.amsthmproofname
3621 {font-style:italic ; font-weight: normal ; margin-right: 1em ; }
3622
3623 span.theoremheadersc
3624 {
3625     font-style:normal ;
3626     font-variant: small-caps ;
3627     font-weight: normal ;
3628     margin-right: 1em ;
3629 }
3630
3631 .theoremendmark {float:right}
3632
3633 div.amsthmbodyplain, div.theorembodyplain, div.theorembodynonumberplain,
3634 div.theorembodybreak, div.theorembodynonumberbreak,
3635 div.theorembodymarginbreak,
3636 div.theorembodychangebreak,
```

```
div.theorembodychange,
div.theorembodymargin
{
    font-style:italic;
    margin-top: 3ex ; margin-bottom: 3ex ;
}

div.theorembodydefinition, div.theorembodyremark, div.theorembodyproof,
div.theorembodyplainupright, nonumberplainuprightsc,
div.amsthmbodydefinition, div.amsthmbodyremark,
div.amsthmproof
{
    font-style: normal ;
    margin-top: 3ex ; margin-bottom: 3ex ;
}

span.amsthmnoteremark {}


/* thmbox */

.thmbox {
    font-style: italic; margin-top: 3ex ; margin-bottom: 3ex ;
    border: 1px solid gray ;
    padding: 1ex ;
}

.thmboxtitle {
    font-style: normal; font-weight: bold ; margin-right: .5em ;
    border-bottom: 1px solid gray ;
}

span.thmboxproofname, span.thmboxexamplename {
    font-weight: bold ;
}

div.thmboxproof, div.thmboxexample {
    font-size: 0.85em ;
    margin: 2ex ;
}

div.thmboxleftbar {
    border-left: 2px solid black ;
    padding-left: 1em ;
}



/* For the backnaur package: */
div.backnaur {
    display: block ;
    margin: 2ex 2em 2ex 2em ;
}

div.backnaur p {
```

```
    margin: .25ex 0ex .25ex 0ex ;
}

div.backnaurprod {
    display: inline-block ;
    min-width: 8em ;
    text-align:right ;
}

div.backnaurdesc {
    display: inline-block ;
}


/* For the notes package: */
div.notesimportantnote, div.noteswarningnote, div.notesinformationnote {
    clear: both ;
    margin: 2ex 2em 2ex 2em ;
    border: 1px solid silver ;
}

div.notesicon {
    float:left ;
    display: inline-block ;
    background: gold ;
    padding: 0ex 1em 0ex 1em ;
    margin-right: 1em ;
    font-weight: bold ;
}

div.notescontents { font-style: italic }


/* nolbreaks package: */
span.nolbreaks { white-space: nowrap ; }


/*
For CSS LaTeX and related logos:
Based on spacing demonstrated by the metafont package.

The subscripts are shrunk instead of lowered below the baseline,
to avoid browser rendering errors with the line height in lists, etc.
*/

.latexlogofont {
    font-family: "Linux Libertine O", "Nimbus Roman No 9 L",
        "FreeSerif", "Hoefler Text", Times, "Times New Roman", serif;
    font-variant: normal ;
}

.latexlogo {
    font-family: "Linux Libertine O", "Nimbus Roman No 9 L",
        "FreeSerif", "Hoefler Text", Times, "Times New Roman", serif;
}
```

```
3747
3748 .latexlogosup {
3749   text-transform: uppercase;
3750   letter-spacing: .03em ;
3751   font-size: 0.7em;
3752   vertical-align: 0.25em;
3753   margin-left: -0.4em;
3754   margin-right: -0.15em;
3755 }
3756
3757 .latexlogosub {
3758   text-transform: uppercase;
3759 /*  vertical-align: -0.27ex; */
3760   margin-left: -0.08em;
3761   margin-right: -0.07em;
3762 /*  font-size: 1em; */
3763     font-size: .7em ;
3764 }
3765
3766 .latexlogotwoe {
3767   text-transform: none ;
3768   font-variant-numeric: oldstyle-nums ;
3769 }
3770
3771 .latexlogotwoesub {
3772   font-style:italic ;
3773 /*  vertical-align: -0.27ex; */
3774   margin-left: -0.11em;
3775   margin-right: -0.1em;
3776 /*  font-size: 1em; */
3777     font-size: .7em ;
3778 }
3779
3780 .xelatexlogo {
3781     font-family: "Linux Libertine O", "Nimbus Roman No 9 L",
3782         "FreeSerif", "Hoefler Text", Times, "Times New Roman", serif;
3783     letter-spacing: .03em ;
3784 }
3785
3786 .xelatexlogosub {
3787 /*  vertical-align: -0.27ex; */
3788   margin-left: -0.0667em;
3789   margin-right: -.05em;
3790 /*  font-size: 1em; */
3791     font-size: .7em ;
3792   letter-spacing: .03em ;
3793 }
3794
3795 .amslogo {
3796     font-family: "TeXGyreChorus","URW Chancery L",
3797         "Apple Chancery","ITC Zapf Chancery","Monotype Corsiva",
3798         "Linux Libertine O", "Nimbus Roman No 9 L",  "FreeSerif",
3799         "Hoefler Text", Times, "Times New Roman", serif ;
3800     font-style: italic ;
3801 }
```

```
3802
3803 .lyxlogo {
3804     font-family: "URW Classico", Optima, "Linux Biolinum O",
3805         "DejaVu Sans", "Bitstream Vera Sans", Geneva,
3806         Verdana, sans-serif ;
3807 }
3808
3809
3810 /* Only display top and bottom navigation if a small screen: */
3811 /* Hide the sidetoc if a small screen: */
3812 nav.topnavigation { display:none; }
3813 nav.botnavigation { display:none; }
3814
3815 /* Only display the sidetoc's webpage title if a small screen */
3816 span.sidetocthetitle { display: none }
3817
3818 @media screen and (max-width: 50em) {
3819     div.sidetoccontainer {
3820         float: none ;
3821         width: 100% ;
3822         padding: 0 ;
3823         border-radius: 0 ;
3824         border-bottom: 1px solid black ;
3825         border-top: 1px solid black ;
3826         box-shadow: none ;
3827     }
3828     span.sidetocthetitle { display: inline }
3829     nav.topnavigation { display:block }
3830     nav.botnavigation { display:block }
3831     div.bodycontainer { width: 100% }
3832     .marginpar {
3833         max-width: 100%;
3834         float: none;
3835         display:block ;
3836         margin: 1ex 1em 1ex 1em ;
3837     }
3838 }
3839
3840 @media print {
3841     body {
3842         font-family: "Linux Libertine O",
3843         "DejaVu Serif", "Bitstream Vera Serif",
3844         "Liberation Serif", "Nimbus Roman No 9 L",
3845         "FreeSerif", "Hoefler Text", Times, "Times New Roman", serif;
3846     }
3847     div.sidetoccontainer { display:none; }
3848     nav.topnavigation { display: none; }
3849     nav.botnavigation { display: none; }
3850     div.bodycontainer { width: 100% }
3851 }
3852
3853 @media handheld {
3854     div.sidetoccontainer { display:none; }
3855     nav.topnavigation { display:block }
3856     nav.botnavigation { display:block }
```

```
    div.bodycontainer { width: 100% }
}

@media projection {
    div.sidetoccontainer { display:none; }
    nav.topnavigation { display:block }
    nav.botnavigation { display:block }
    div.bodycontainer { width: 100% }
}
\end{filecontents*}
% \end{Verbatim}% for syntax highlighting
\end{LWRwriteconf}
```

## 40.5 lwarp_sagebrush.css

File lwarp_sagebrush.css An optional CSS which may be used for a semi-modern appearance.

If used, this must be present both when compiling the project and also when distributing the HTML files.

**Config file:**

```
\begin{LWRwriteconf}
\begin{filecontents*}[overwrite]{lwarp_sagebrush.css}
@import url("lwarp.css") ;


A:link {color:#105030 ; text-decoration: none ; }
A:visited {color:#705030 ; text-shadow:1px 1px 2px #a0a0a0;}
A:hover {color:#006000 ; text-decoration: underline ; text-shadow:0px 0px 2px #a0a0a0;}
A:active {color:#00C000 ; text-shadow:1px 1px 2px #a0a0a0;}



div.book, h1, h2, h3, h4, h5, h6, span.paragraph, span.subparagraph
{
    font-family: "URW Classico", Optima, "Linux Biolinum O",
        "Linux Libertine O", "Liberation Serif",
        "Nimbus Roman No 9 L",  "FreeSerif",
        "Hoefler Text", Times, "Times New Roman", serif;
    font-variant: small-caps ;
    font-weight: normal ;
    color: #304070 ;
    text-shadow: 2px 2px 3px #808080;
}

h1 {    /* title of the entire website, used on each page */
    font-variant: small-caps ;
    color: #304070 ;
    text-shadow: 2px 2px 3px #808080;
    background-color: #F7F7F0 ;
    background-image: linear-gradient(to bottom, #F7F7F0, #C0C0C4);
}

h1 {
  border-bottom: 1px solid #304070;
```

```
/*  border-top: 2px solid #304070; */
}

h2 {
  border-bottom: 1px solid #304070;
/*  border-top: 2px solid #304070; */
    background-color: #F7F7F0 ;
    background-image: linear-gradient(to bottom, #F7F7F0, #DAD0C0);
}



div.abstract {
    background: #f5f5eb ;
    background-image: linear-gradient(to bottom, #f5f5eb, #C8C8B8);

  border: 1px solid silver;
    border-radius: 1em ;
}

div.abstract dl {line-height:1.5;}
div.abstract dt {color:#304070;}

div.abstracttitle{
    font-family: "URW Classico", Optima, "Linux Biolinum O",
        "Linux Libertine O", "Liberation Serif", "Nimbus Roman No 9 L",
        "FreeSerif", "Hoefler Text", Times, "Times New Roman", serif;
    font-weight:bold;
    font-variant: small-caps ;
    font-size:1.5em;
    border-bottom: 1px solid silver ;
    color: #304070 ;
    text-align: center ;
    text-shadow: 1px 1px 2px #808080;
}

span.abstractrunintitle{
    font-family: "URW Classico", Optima, "Linux Biolinum O",
        "Linux Libertine O", "Liberation Serif", "Nimbus Roman No 9 L",
        "FreeSerif", "Hoefler Text", Times, "Times New Roman", serif;
    font-weight:bold;
}


div.epigraph, div.dictum {
    background: #f5f5eb ;
    background-image: linear-gradient(to bottom, #f5f5eb, #C8C8B8);

    border: 1px solid silver ;
    border-radius: 1ex ;
    box-shadow: 3px 3px 3px #808080 ;
}


.example {
```

```
    background-color: #f5f5eb ;
    background-image: linear-gradient(to bottom, #f5f5eb, #C8C8B8);

}

div.exampletitle{
    font-family: "URW Classico", Optima, "Linux Biolinum O",
        "Linux Libertine O", "Liberation Serif", "Nimbus Roman No 9 L",
        "FreeSerif", "Hoefler Text", Times, "Times New Roman", serif;
    font-weight:bold;
    font-variant: small-caps ;
    border-bottom: 1px solid silver ;
    color: #304070 ;
    text-align: center ;
    text-shadow: 1px 1px 2px #808080;
}


.sidebar {
    background-color: #f5f5eb ;
    background-image: linear-gradient(to bottom, #f5f5eb, #C8C8B8);

}

div.sidebartitle{
    font-family: "URW Classico", Optima, "Linux Biolinum O",
        "Linux Libertine O", "Liberation Serif", "Nimbus Roman No 9 L",
        "FreeSerif", "Hoefler Text", Times, "Times New Roman", serif;
    font-weight:bold;
    font-variant: small-caps ;
    border-bottom: 1px solid silver ;
    color: #304070 ;
    text-align: center ;
    text-shadow: 1px 1px 2px #808080;
}


.fancyvrblabel {
    font-family: "URW Classico", Optima, "Linux Biolinum O",
        "Linux Libertine O", "Liberation Serif", "Nimbus Roman No 9 L",
        "FreeSerif", "Hoefler Text", Times, "Times New Roman", serif;
    font-weight:bold;
    font-variant: small-caps ;
    font-size: 1.5em ;
    color: #304070 ;
    text-align: center ;
    text-shadow: 1px 1px 2px #808080;
}

div.minipage {
    background-color: #eeeee7 ;
    border: 1px solid silver ;
    border-radius: 1ex ;
}

```

```
table div.minipage { background: none ; border: none ; }

div.framebox div.minipage {border:none ; background:none}

section.textbody > div.minipage {
    box-shadow: 3px 3px 3px #808080 ;
}

div.fboxBlock div.minipage { box-shadow: none ; }

.framed .minipage , .framedleftbar .minipage {
    border: none ;
    background: none ;
    padding: 0ex ;
    margin: 0ex ;
}

figure.figure .minipage, div.figurecaption .minipage { border: none; }

div.marginblock div.minipage ,
div.marginparblock div.minipage
    { border: none; }

figure , div.marginblock {
    background-color: #eeeee7 ;
    border: 1px solid silver ;
    border-radius: 1ex ;
    box-shadow: 3px 3px 3px #808080 ;
}

figure figure {
    border: 1px solid silver ;
    margin: 0em ;
    box-shadow: none ;
}

/*
div.figurecaption {
    border-top: 1px solid silver ;
    border-bottom: 1px solid silver ;
    background-color: #e8e8e8 ;
}
*/


div.table {
    box-shadow: 3px 3px 3px #808080 ;
}

/*
.tnotes {
    background: #e8e8e8;
    border: 1px solid silver;
}
*/
```

```
4068
4069
4070 nav.topnavigation{
4071     background-color: #b0b8b0 ;
4072     background-image: linear-gradient(to bottom,#e0e0e0,#b0b8b0) ;
4073 }
4074
4075 nav.botnavigation{
4076     background-color: #b0b8b0 ;
4077     background-image: linear-gradient(to top,#e0e0e0,#b0b8b0) ;
4078 }
4079
4080
4081
4082 header{
4083     background-color: #F7F7F0 ;
4084     background-image: linear-gradient(to top, #F7F7F0, #b0b8b0);
4085 }
4086
4087 footer{
4088     background-color: #F7F7F0 ;
4089     background-image: linear-gradient(to bottom, #F7F7F0, #b0b8b0);
4090 }
4091
4092
4093
4094 div.sidetoccontainer {
4095     background-color: #F7F7F0 ;
4096     background-image: linear-gradient(to bottom, #F7F7F0, #C0C0C0);
4097     box-shadow: 3px 3px 3px #808080 ;
4098     }
4099
4100 div.sidetoctitle {color: #304070 ; }
4101
4102 nav.sidetoc a:hover {
4103     color:#006000 ;
4104     text-decoration: none ;
4105     text-shadow:0px 0px 2px #a0a0a0;
4106 }
4107
4108
4109 @media screen and (max-width: 45em) {
4110     div.sidetoccontainer { border-radius: 0 ; }
4111 }
4112
4113
4114 \end{filecontents*}
4115 % \end{Verbatim}% for syntax highlighting
4116 \end{LWRwriteconf}
```

## 40.6 lwarp_formal.css

File `lwarp_formal.css` An optional css which may be used for a more formal appearance.

If used, this must be present both when compiling the project and also when distributing the HTML files.

**Config file:**

```
\begin{LWRwriteconf}
\begin{filecontents*}[overwrite]{lwarp_formal.css}
@import url("lwarp.css") ;



A:link {color:#802020 ; text-decoration:none; }
A:visited {color:#802020 ; text-shadow:none ;}
A:hover {color:#400000 ; text-shadow:none ;}
A:active {color:#C00000 ; text-shadow:none ;}


body {
    font-family: "Linux Libertine O", "Hoefler Text", "Garamond",
        "Bembo", "Janson", "TeX Gyre Pagella", "Palatino",
        "Liberation Serif", "Nimbus Roman No 9 L",  "FreeSerif", Times,
        "Times New Roman", serif;
    background: #fffcf5;
}

span.textrm {
    font-family: "Linux Libertine O", "Hoefler Text", "Garamond",
        "Bembo", "Janson", "TeX Gyre Pagella", "Palatino",
        "Liberation Serif", "Nimbus Roman No 9 L",  "FreeSerif", Times,
        "Times New Roman", serif;
}

span.textsf {
     font-family: "DejaVu Sans", "Bitstream Vera Sans",
        Geneva, Verdana, sans-serif ;
}



div.book, h1, h2, h3, h4, h5, h6, span.paragraph, span.subparagraph
{
    font-family: "Linux Libertine O", "Hoefler Text", "Garamond",
        "Bembo", "Janson", "TeX Gyre Pagella", "Palatino",
        "Liberation Serif", "Nimbus Roman No 9 L",  "FreeSerif", Times,
        "Times New Roman", serif;
    color: #800000 ;
    text-shadow: none ;
}

h1, h2 {
    background-color: #fffcf5 ;
    background-image: none ;
    border-bottom: 1px solid #808080;
/*    border-top: 2px solid #808080; */
}

div.abstracttitle {
    font-family: "Linux Libertine O", "Hoefler Text", "Garamond",
```

```
        "Bembo", "Janson", "TeX Gyre Pagella", "Palatino",
        "Liberation Serif", "Nimbus Roman No 9 L",  "FreeSerif", Times,
        "Times New Roman", serif;
    color: black ;
    text-shadow: none ;
}

span.abstractrunintitle {
    font-family: "Linux Libertine O", "Hoefler Text", "Garamond",
        "Bembo", "Janson", "TeX Gyre Pagella", "Palatino",
        "Liberation Serif", "Nimbus Roman No 9 L",  "FreeSerif", Times,
        "Times New Roman", serif;
    color: black ;
    text-shadow: none ;
}

div.abstract { font-size: 100% }

.sidebar {
    background: #fffcf5;
    background-image: none ;
  margin: 2em 5% 2em 5%;
  padding: 0.5em 1em;
  border: none ;
  border-top : 1px solid silver;
  border-bottom : 1px solid silver;
  font-size: 90% ;
}

div.sidebartitle{
    font-family: "Linux Libertine O", "Hoefler Text", "Garamond",
        "Bembo", "Janson", "TeX Gyre Pagella", "Palatino",
        "Liberation Serif", "Nimbus Roman No 9 L",  "FreeSerif", Times,
        "Times New Roman", serif;
    color: #800000 ;
    text-shadow: none ;
    border: none ;
}

.example {
    background: #fffcf5;
    background-image: none ;
  margin: 2em 5% 2em 5%;
  padding: 0.5em 1em;
  border: none ;
  border-top : 1px solid silver;
  border-bottom : 1px solid silver;
}

div.exampletitle{
    font-family: "Linux Libertine O", "Hoefler Text", "Garamond",
        "Bembo", "Janson", "TeX Gyre Pagella", "Palatino",
        "Liberation Serif", "Nimbus Roman No 9 L",  "FreeSerif", Times,
        "Times New Roman", serif;
    color: #800000 ;
```

```
4225     text-shadow: none ;
4226     border: none ;
4227 }
4228
4229 div.fancyvrblabel{
4230     font-family: "Linux Libertine O", "Hoefler Text", "Garamond",
4231         "Bembo", "Janson", "TeX Gyre Pagella", "Palatino",
4232         "Liberation Serif", "Nimbus Roman No 9 L",  "FreeSerif", Times,
4233         "Times New Roman", serif;
4234     color: #800000 ;
4235     text-shadow: none ;
4236     border: none ;
4237 }
4238
4239
4240
4241 figure {
4242     margin: 5ex 5% 5ex 5% ;
4243     padding: 1ex 1em 1ex 1em ;
4244     background-color: #fffcf5 ;
4245     overflow-x: auto ;
4246     border: none ;
4247 /*     border-top: 1px solid silver; */
4248 /*     border-bottom: 1px solid silver; */
4249 }
4250
4251
4252 div.figurecaption , .lstlisting {
4253     border: none ;
4254 /*     border-top: 1px solid silver ; */
4255 /*     border-bottom: 1px solid silver ; */
4256     background-color: #fffcf5 ;
4257 }
4258
4259 .tnotes {
4260     background: #fffcf5 ;
4261     border-top: 1px solid silver ;
4262     border-bottom: 1px solid silver ;
4263 }
4264
4265 .theorem {
4266         background: none ;
4267 }
4268
4269 .minipage {
4270     background-color: #fffcf5 ;
4271     border: none ;
4272 }
4273
4274 div.floatrow figure { border: none ; }
4275
4276 figure figure { border: none ; }
4277
4278
4279 nav.toc, nav.lof, nav.lot, nav.lol {
```

```
/* @import url("lwarp_sagebrush.css") ; */

/* Project-specific CSS setting follow here. */
/* . . . */

/* ( --- End of project.css --- ) */
\end{filecontents*}
% \end{Verbatim}% for syntax highlighting
\end{LWRwriteconf}
```

## 40.8 lwarp.ist

File `lwarp.ist` Used to modify the index for lwarp.

This must be present when compiling the project, but does not need to be present when distributing the resulting HTML files.

The page compositor line is for memoir's `\specialindex`.

**Config file:**

```
\begin{LWRwriteconf}
\begin{filecontents*}[overwrite]{lwarp.ist}
preamble
"\\begin{theindex}
  \\providecommand*\\lettergroupDefault[1]{}
  \\providecommand*\\lettergroup[1]{%
      \\par\\textbf{#1}\\par
      \\nopagebreak
  }
"
headings_flag 1
heading_prefix "
  \\lettergroup{"
heading_suffix "}"
delim_0 ", \\hyperindexref{"
delim_1 ", \\hyperindexref{"
delim_2 ", \\hyperindexref{"
delim_n "}, \\hyperindexref{"
delim_r "} -- \\hyperindexref{"
delim_t "}"
page_compositor "."
\end{filecontents*}
% \end{Verbatim}% for syntax highlighting
\end{LWRwriteconf}
```

## 40.9 lwarp.xdy

File `lwarp.xdy` Used to modify the index for lwarp.

This must be present when compiling the project, but does not need to be present when distributing the resulting HTML files.

See:
https://tex.stackexchange.com/questions/80300/
how-can-i-convince-hyperref-and-xindy-to-play-together-nicely

**Config file:**
```
\begin{LWRwriteconf}
\begin{filecontents*}[overwrite]{lwarp.xdy}
(require "tex/inputenc/latin.xdy")
(merge-rule "\\PS *" "Postscript")
(require "texindy.xdy")
(require "page-ranges.xdy")
(require "book-order.xdy")
(define-location-class "arabic-page-numbers"
    ("arabic-numbers") :min-range-length 1)
(require "makeindex.xdy")
(define-attributes (("hyperindexref")))
(markup-locref :open "\hyperindexref{" :close "}")
(markup-locref :open "\hyperindexref{" :close "}" :attr "hyperpage")
(markup-locref :open "\textbf{\hyperindexref{" :close "}}" :attr "textbf")
(markup-locref :open "\textit{\hyperindexref{" :close "}}" :attr "textit")
(define-location-class-order ("roman-page-numbers"
                  "arabic-page-numbers"
                  "alpha-page-numbers"
                  "Roman-page-numbers"
                  "Alpha-page-numbers"
                  "see"
                  "seealso"))
\end{filecontents*}
% \end{Verbatim}% for syntax highlighting
\end{LWRwriteconf}
```

## 40.10 lwarp_one_limage.cmd

File lwarp_one_limage.cmd

Used by lwarp to help make lateximages when using Windows.

This must be present when compiling the project, but does not need to be present when distributing the resulting HTML files.

The arguments are each of the three fields from <project>-images.txt, and also the base name of the source file.

*MiKTeX* does not allow file lwarp_one_limage.cmd to be created directly by *lwarpmk*, so lwarp_one_limage.txt is created instead, then copied to lwarp_one_limage.cmd by *lwarpmk*. This occurs each time *lwarpmk* used to create lateximages.

**Config file:**
```
\begin{LWRwriteconf}
\immediate\openout\LWR@quickfile=lwarp_one_limage.txt
\immediate\write\LWR@quickfile{%
    pdfseparate -f \LWRpercent 1 -l \LWRpercent 1 \LWRpercent 4_html.pdf %
   \LWR@ImagesDirectory\OSPathSymbol lateximagetemp-\LWRpercent\LWRpercent d.pdf%
}
\immediate\write\LWR@quickfile{%
   pdfcrop --hires  \LWR@ImagesDirectory\OSPathSymbol lateximagetemp-\LWRpercent 1.pdf %
    \LWR@ImagesDirectory\OSPathSymbol\LWRpercent 3.pdf%
}
```

```
\immediate\write\LWR@quickfile{%
  pdftocairo -svg -noshrink \LWR@ImagesDirectory\OSPathSymbol\LWRpercent 3.pdf %
   \LWR@ImagesDirectory\OSPathSymbol\LWRpercent 3.svg%
}
\immediate\write\LWR@quickfile{%
   del \LWR@ImagesDirectory\OSPathSymbol\LWRpercent 3.pdf%
}
\immediate\write\LWR@quickfile{%
   del \LWR@ImagesDirectory\OSPathSymbol lateximagetemp-\LWRpercent 1.pdf%
}
\immediate\write\LWR@quickfile{exit}
\immediate\closeout\LWR@quickfile
\end{LWRwriteconf}
```

## 40.11 lwarp_mathjax.txt

(*Emulates or patches code by* Davide P. Cervone.)

File lwarp_mathjax.txt

The default MathJax script used by lwarp when using MathJax. A recent version of MathJax is used, as served by the recommended repository. Adjustments are made to allow LaTeX to control the equation tags and provide for starred macros.

\MathJaxFilename determines which script file is copied into the HTML pages, and defaults to lwarp_mathjax.txt. The script files must be present when compiling the project, but do not need to be present when distributing the resulting HTML files.

custom script

To generate a custom script, such as to use a local repository, copy lwarp_mathjax.txt to a new file, make changes while keeping lwarp's adjustments for equation numbering and starred macros, and use \MathJaxFilename to select the new filename.

**Config file:**

```
\begin{LWRwriteconf}
\begin{filecontents*}[overwrite]{lwarp_mathjax.txt}
<script>
// Lwarp MathJax emulation code
//
// Based on code by Davide P. Cervone.
// Equation numbering: https://github.com/mathjax/MathJax/issues/2427
// Starred and ifnextchar macros: https://github.com/mathjax/MathJax/issues/2428
// \left, \right delimiters: https://github.com/mathjax/MathJax/issues/2535
//
// Modified by Brian Dunn to adjust equation numbering and add subequations.
//
// LaTeX can use \seteqnumber{subequations?}{section}{number} before each equation.
// subequations? is 0 usually, 1 if inside subequations.
// section is a string printed as-is, or empty.
// number is auto-incremented by MathJax between equations.
//
MathJax = {
  subequations: "0",
  section: "",
  loader: {
    load: ['[tex]/tagformat', '[tex]/textmacros'],
  },
  startup: {
```

```
4431    ready() {
4432      //  These would be replaced by import commands if you wanted to make
4433      //  a proper extension.
4434      const Configuration = MathJax._.input.tex.Configuration.Configuration;
4435      const CommandMap = MathJax._.input.tex.SymbolMap.CommandMap;
4436      const Macro = MathJax._.input.tex.Symbol.Macro;
4437      const TexError = MathJax._.input.tex.TexError.default;
4438      const ParseUtil = MathJax._.input.tex.ParseUtil.default;
4439      const expandable = MathJax._.util.Options.expandable;
4440
4441      //  Insert the replacement string into the TeX string, and check
4442      //  that there haven't been too many maxro substitutions (prevents
4443      //  infinite loops).
4444      const useArgument = (parser, text) => {
4445       parser.string = ParseUtil.addArgs(parser, text, parser.string.slice(parser.i));
4446         parser.i = 0;
4447         if (++parser.macroCount > parser.configuration.options.maxMacros) {
4448           throw new TexError('MaxMacroSub1',
4449           'MathJax maximum macro substitution count exceeded; ' +
4450           'is there a recursive macro call?');
4451         }
4452       }
4453
4454      //  Create the command map for:
4455      //    \ifstar, \ifnextchar, \ifblank, \ifstrequal, \seteqnumber
4456       new CommandMap('Lwarp-macros', {
4457         ifstar: 'IfstarFunction',
4458         ifnextchar: 'IfnextcharFunction',
4459         ifblank: 'IfblankFunction',
4460         ifstrequal: 'IfstrequalFunction',
4461         seteqnumber: 'SeteqnumberFunction'
4462       }, {
4463         //  This function implements an ifstar macro.
4464         IfstarFunction(parser, name) {
4465           const resultstar = parser.GetArgument(name);
4466           const resultnostar = parser.GetArgument(name);
4467          const star = parser.GetStar();                // true if there is a *
4468           useArgument(parser, star ? resultstar : resultnostar);
4469         },
4470
4471         //  This function implements an ifnextchar macro.
4472         IfnextcharFunction(parser, name) {
4473           let whichchar = parser.GetArgument(name);
4474           if (whichchar.match(/^(?:0x[0-9A-F]+|[0-9]+)$/i)) {
4475             // $ syntax highlighting
4476             whichchar = String.fromCodePoint(parseInt(whichchar));
4477           }
4478           const resultnextchar = parser.GetArgument(name);
4479           const resultnotnextchar = parser.GetArgument(name);
4480           const gotchar = (parser.GetNext() === whichchar);
4481           useArgument(parser, gotchar ? resultnextchar : resultnotnextchar);
4482         },
4483
4484         // This function implements an ifblank macro.
4485         IfblankFunction(parser, name) {
```

```
4486          const blankarg = parser.GetArgument(name);
4487          const resultblank = parser.GetArgument(name);
4488          const resultnotblank = parser.GetArgument(name);
4489          const isblank = (blankarg.trim() == "");
4490          useArgument(parser, isblank ? resultblank : resultnotblank);
4491        },
4492
4493        // This function implements an ifstrequal macro.
4494        IfstrequalFunction(parser, name) {
4495          const strequalfirst = parser.GetArgument(name);
4496          const strequalsecond = parser.GetArgument(name);
4497          const resultequal = parser.GetArgument(name);
4498          const resultnotequal = parser.GetArgument(name);
4499          const isequal = (strequalfirst == strequalsecond);
4500          useArgument(parser, isequal ? resultequal : resultnotequal);
4501        },
4502
4503        //  This function modifies the equation numbers.
4504        SeteqnumberFunction(parser, name) {
4505            //  Get the macro parameters
4506           const star = parser.GetStar();                // true if there is a *
4507        const optBrackets = parser.GetBrackets(name);  // contents of optional brackets
4508        const newsubequations = parser.GetArgument(name);  // the subequations argument
4509        const neweqsection = parser.GetArgument(name);  // the eq section argument
4510        const neweqnumber = parser.GetArgument(name);  // the eq number argument
4511        MathJax.config.subequations=newsubequations ;  // a string with boolean meaning
4512        MathJax.config.section=neweqsection ;       // a string with numeric meaning
4513            parser.tags.counter = parser.tags.allCounter = neweqnumber ;
4514        }
4515
4516      });
4517
4518      //  Create the Lwarp-macros package
4519      Configuration.create('Lwarp-macros', {
4520        handler: {macro: ['Lwarp-macros']}
4521      });
4522
4523      MathJax.startup.defaultReady();
4524
4525      // For forward references:
4526      MathJax.startup.input[0].preFilters.add(({math}) => {
4527        if (math.inputData.recompile){
4528           MathJax.config.subequations = math.inputData.recompile.subequations;
4529            MathJax.config.section = math.inputData.recompile.section;
4530        }
4531      });
4532      MathJax.startup.input[0].postFilters.add(({math}) => {
4533        if (math.inputData.recompile){
4534           math.inputData.recompile.subequations = MathJax.config.subequations;
4535            math.inputData.recompile.section = MathJax.config.section;
4536        }
4537      });
4538
4539        // For \left, \right with unicode-math:
4540        const {DelimiterMap} = MathJax._.input.tex.SymbolMap;
```

```
4541        const {Symbol} = MathJax._.input.tex.Symbol;
4542        const {MapHandler} = MathJax._.input.tex.MapHandler;
4543        const delimiter = MapHandler.getMap('delimiter');
4544        delimiter.add('\\lBrack', new Symbol('\\lBrack', '\u27E6'));
4545        delimiter.add('\\rBrack', new Symbol('\\rBrack', '\u27E7'));
4546        delimiter.add('\\lAngle', new Symbol('\\lAngle', '\u27EA'));
4547        delimiter.add('\\rAngle', new Symbol('\\rAngle', '\u27EB'));
4548        delimiter.add('\\lbrbrak', new Symbol('\\lbrbrak', '\u2772'));
4549        delimiter.add('\\rbrbrak', new Symbol('\\rbrbrak', '\u2773'));
4550        delimiter.add('\\lbag', new Symbol('\\lbag', '\u27C5'));
4551        delimiter.add('\\rbag', new Symbol('\\rbag', '\u27C6'));
4552     delimiter.add('\\llparenthesis', new Symbol('\\llparenthesis', '\u2987'));
4553     delimiter.add('\\rrparenthesis', new Symbol('\\rrparenthesis', '\u2988'));
4554        delimiter.add('\\llangle', new Symbol('\\llangle', '\u2989'));
4555        delimiter.add('\\rrangle', new Symbol('\\rrangle', '\u298A'));
4556        delimiter.add('\\Lbrbrak', new Symbol('\\Lbrbrak', '\u27EC'));
4557        delimiter.add('\\Rbrbrak', new Symbol('\\Rbrbrak', '\u27ED'));
4558        delimiter.add('\\lBrace', new Symbol('\\lBrace', '\u2983'));
4559        delimiter.add('\\rBrace', new Symbol('\\rBrace', '\u2984'));
4560        delimiter.add('\\lParen', new Symbol('\\lParen', '\u2985'));
4561        delimiter.add('\\rParen', new Symbol('\\rParen', '\u2986'));
4562        delimiter.add('\\lbrackubar', new Symbol('\\lbrackubar', '\u298B'));
4563        delimiter.add('\\rbrackubar', new Symbol('\\rbrackubar', '\u298C'));
4564      delimiter.add('\\lbrackultick', new Symbol('\\lbrackultick', '\u298D'));
4565      delimiter.add('\\rbracklrtick', new Symbol('\\rbracklrtick', '\u298E'));
4566      delimiter.add('\\lbracklltick', new Symbol('\\lbracklltick', '\u298F'));
4567      delimiter.add('\\rbrackurtick', new Symbol('\\rbrackurtick', '\u2990'));
4568        delimiter.add('\\langledot', new Symbol('\\langledot', '\u2991'));
4569        delimiter.add('\\rangledot', new Symbol('\\rangledot', '\u2992'));
4570        delimiter.add('\\lparenless', new Symbol('\\lparenless', '\u2993'));
4571        delimiter.add('\\rparengtr', new Symbol('\\rparengtr', '\u2994'));
4572        delimiter.add('\\Lparengtr', new Symbol('\\Lparengtr', '\u2995'));
4573        delimiter.add('\\Rparenless', new Symbol('\\Rparenless', '\u2996'));
4574        delimiter.add('\\lblkbrbrak', new Symbol('\\lblkbrbrak', '\u2997'));
4575        delimiter.add('\\rblkbrbrak', new Symbol('\\rblkbrbrak', '\u2998'));
4576        delimiter.add('\\lvzigzag', new Symbol('\\lvzigzag', '\u29D8'));
4577        delimiter.add('\\rvzigzag', new Symbol('\\rvzigzag', '\u29D9'));
4578        delimiter.add('\\Lvzigzag', new Symbol('\\Lvzigzag', '\u29DA'));
4579        delimiter.add('\\Rvzigzag', new Symbol('\\Rvzigzag', '\u29DB'));
4580        delimiter.add('\\lcurvyangle', new Symbol('\\lcurvyangle', '\u29FC'));
4581        delimiter.add('\\rcurvyangle', new Symbol('\\rcurvyangle', '\u29FD'));
4582        delimiter.add('\\Vvert', new Symbol('\\Vvert', '\u2980'));
4583    }   // ready
4584  },    // startup
4585
4586  tex: {
4587    packages: {'[+]': ['tagformat', 'Lwarp-macros', 'textmacros']},
4588    tags: "ams",
4589        tagformat: {
4590            number: function (n) {
4591                if(MathJax.config.subequations==0)
4592                    return(MathJax.config.section + n);
4593                else
4594                   return(MathJax.config.section + String.fromCharCode(96+n));
4595            },
```

```
        },
  }
}
</script>

<script
    id="MathJax-script"
    src="https://cdn.jsdelivr.net/npm/mathjax@3/es5/tex-chtml.js"
></script>
\end{filecontents*}
% \end{Verbatim}% for syntax highlighting
\end{LWRwriteconf}
```

## 40.12 `lwarpmk.lua` — `lwarpmk` option

Opt `lwarpmk` Creates a local copy of *lwarpmk*.

Prog `lwarpmk` Command-line utility to process lwarp files and images.

parallel processing `latexi`mages and SVG math images are generated using multiple processes in parallel. For Unix and Linux, every 32 images the `wait` command is issued to wait for the previous batch of images to finish processing before starting a new batch. For Windows, every 32 images one task is dispatched with

```
START /B /WAIT /BELOWNORMAL
```

which causes the operating system to wait until this lesser-priority tasks finishes, hopefully also waiting for the normal priority tasks which were already in progress to also complete. Afterwards, the next batch of images is started.

The following is only generated if the `lwarpmk` option was given to lwarp.

```
\begin{LWRcreatelwarpmk}

\begin{filecontents*}[overwrite]{lwarpmk.lua}
#!/usr/bin/env texlua

-- Copyright 2016-2021 Brian Dunn


printversion = "v0.895"
requiredconfversion = "2" -- also at *lwarpmk.conf

function printhelp ()
print ("lwarpmk: Use lwarpmk -h or lwarpmk --help for help.") ;
end


function printusage ()
--
-- Print the usage of the lwarpmk command:
--
print ( [[

```

```
local sfile = io.open(sourcefile)
io.output(destfile)
for line in sfile:lines() do
i,j,copen,cstart,newfilename = string.find (line,"(.*)|(.*)|(.*)|") ;
if ( (i~= nil) and (copen == "<!--") and (cstart == "Start file")) then
    -- split the file
    io.output(newfilename) ;
else
    -- not a splitpoint
    io.write (line .. "\n") ;
end
end -- do
io.close(sfile)
end -- function


function cvalueerror ( line, linenum , cvalue )
--
-- Incorrect value, so print an error and exit.
--
    print ("lwarpmk: ===")
    print ("lwarpmk: " .. linenum .. " : " .. line ) ;
    print (
        "lwarpmk: incorrect variable value \"" .. cvalue ..
        "\" in lwarpmk.conf.\n"
    ) ;
    print ("lwarpmk: ===")
--    printconf () ;
    os.exit(1) ;
end


function printhowtorecompile ()
-- Tells the user how to recompile to regenerate the configuration files.
  print ("lwarpmk: The configuration files lwarpmk.conf and "..sourcename..".lwarpmkconf" )
    print ("lwarpmk:   must be updated.  To do so, recompile" )
    print ("lwarpmk:   " , sourcename..".tex" )
    if ( printlatexcmd == "" ) then
        print ("lwarpmk:   using xe/lua/pdflatex," )
    else
        print ("lwarpmk:   using the command:")
        print ("lwarpmk:   " , printlatexcmd )
    end
    print ("lwarpmk:   then use lwarpmk again.")
end -- printhowtorecompile


function ignoreconf ()
-- Global argument index
argindex = 2
end

function loadconf ()
--
-- Load settings from the project's "lwarpmk.conf" file:
```

```
--
-- Default configuration filename:
local conffile = "lwarpmk.conf"
local confroot = "lwarpmk"
-- Global argument index
argindex = 2
-- Optional configuration filename:
if ( arg[argindex] == "-p" ) then
    argindex = argindex + 1
    confroot = arg[argindex]
    conffile = confroot..".lwarpmkconf"
    argindex = argindex + 1
end
-- Additional defaults:
confversion = "0"
opsystem = "Unix"
imagesdirectory = "lateximages"
imagesname = "image-"
latexmk = "false"
printlatexcmd = ""
HTMLlatexcmd = ""
printindexcmd = ""
HTMLindexcmd = ""
latexmkindexcmd = ""
-- to be removed:
-- indexprog = "makeindex"
-- makeindexstyle = "lwarp.ist"
-- xindylanguage = "english"
-- xindycodepage = "utf8"
-- xindystyle = "lwarp.xdy"
-- pdftotextenc = "UTF-8"
glossarycmd = "makeglossaries"
-- Verify the file exists:
if (lfs.attributes(conffile,"mode")==nil) then
    -- file not exists
    print ("lwarpmk: ===")
    print ("lwarpmk: File \"" .. conffile .."\" does not exist.")
    print ("lwarpmk: Move to the project's source directory,")
    print ("lwarpmk: recompile using pdflatex, xelatex, or lualatex,")
    print ("lwarpmk: then try using lwarpmk again.")
    if ( arg[argindex] ~= nil ) then
        print (
            "lwarpmk: (\"" .. confroot ..
            "\" does not appear to be a project name.)"
        )
    end
    print ("lwarpmk: ===")
    printhelp () ;
    os.exit(1) -- exit the entire lwarpmk script
else -- file exists
-- Read the file:
print ("lwarpmk: Reading " .. conffile ..".")
local cfile = io.open(conffile)
-- Scan each line, parsing each line as: name = [[string]]
local linenum = 0
```

```
4849     print ("lwarpmk: In your project directory, recompile your project")
4850     print ("lwarpmk: using pdf/lua/xelatex <projectname>.")
4851    print ("lwarpmk: After a recompile, \"lwarpmk.conf\" will be set for your project,")
4852     print ("lwarpmk: and you may again use lwarpmk.")
4853     print ("lwarpmk: ===")
4854     os.exit(1)
4855 end -- sourcename of "lwarp"
4856 -- Select some operating-system commands:
4857 if opsystem=="Unix" then  -- For Unix / Linux / Mac OS:
4858     rmname = "rm"
4859     mvname = "mv"
4860     cpname = "cp"
4861     touchnamepre = "touch"
4862     touchnamepost = ""
4863     newtouchname = "touch"
4864     dirslash = "/"
4865     opquote= "\'"
4866     cmdgroupopenname = " ( "
4867     cmdgroupclosename = " ) "
4868     seqname = " && "
4869     bgname = " &"
4870 elseif opsystem=="Windows" then -- For Windows
4871     rmname = "DEL"
4872     mvname = "MOVE"
4873     cpname = "COPY"
4874     touchnamepre = "COPY /b"
4875     touchnamepost = "+,,"
4876     newtouchname = "echo empty >"
4877     dirslash = "\\"
4878     opquote= "\""
4879     cmdgroupopenname = ""
4880     cmdgroupclosename = ""
4881     seqname = " & "
4882     bgname = ""
4883 else
4884     print ("lwarpmk: ===")
4885     print ("lwarpmk: Select Unix or Windows for opsystem." )
4886     print ("lwarpmk: ===")
4887     os.exit(1)
4888 end --- for Windows
4889 -- Warning if the operating system does not appear to be correct,
4890 -- in case files were transferred to another system.
4891 if ( (package.config:sub(1,1)) ~= dirslash ) then
4892     print ("lwarpmk: ===")
4893    print ("lwarpmk: It appears that lwarpmk.conf is for a different operating system." )
4894     printhowtorecompile ()
4895     print ("lwarpmk: ===")
4896     os.exit(1)
4897 end
4898 -- Error if the configuration file's version is not current:
4899 if ( confversion ~= requiredconfversion ) then
4900     print ("lwarpmk: ===")
4901     printhowtorecompile ()
4902     print ("lwarpmk: ===")
4903     os.exit(1)
```

```
end
end -- loadconf


function executecheckerror ( executecommands , errormessage )
--
-- Execute an operating system call,
-- and maybe exit with an error message.
--
local err
err = os.execute ( executecommands )
if ( err ~= 0 ) then
    print ("lwarpmk: ===")
    print ("lwarpmk: " .. errormessage )
    print ("lwarpmk: ===")
    os.exit(1)
end
end -- executecheckerror


function refreshdate ()
os.execute(touchnamepre .. " " .. sourcename .. ".tex " .. touchnamepost)
end



function reruntoget (filesource)
--
-- Scan the LaTeX log file for the phrase "Rerun to get",
-- indicating that the file should be compiled again.
-- Return true if found.
--
local fsource = io.open(filesource)
for line in fsource:lines() do
if ( string.find(line,"Rerun to get") ~= nil ) then
    io.close(fsource)
    return true
end -- if
end -- do
io.close(fsource)
return false
end



function onetime (latexcmd, fsuffix)
--
-- Compile one time, return true if should compile again.
-- fsuffix is "" for print, "_html" for HTML output.
--
print("lwarpmk: Compiling with: " .. latexcmd)
executecheckerror (
    latexcmd ,
    "Compile error."
)
```

```
return (reruntoget(sourcename .. fsuffix .. ".log") ) ;
end


function manytimes (latexcmd, fsuffix)
--
-- Compile up to five times.
-- fsuffix is "" for print, "_html" for HTML output
--
if onetime(latexcmd, fsuffix) == true then
if onetime(latexcmd, fsuffix) == true then
if onetime(latexcmd, fsuffix) == true then
if onetime(latexcmd, fsuffix) == true then
if onetime(latexcmd, fsuffix) == true then
end end end end end
end


function verifyfileexists (filename)
--
-- Exit if the given file does not exist.
--
if (lfs.attributes ( filename , "modification" ) == nil ) then
    print ("lwarpmk: ===")
    print ("lwarpmk: " .. filename .. " not found." ) ;
    print ("lwarpmk: ===")
    os.exit (1) ;
end
end



function pdftohtml ()
--
-- Convert <project>_html.pdf into HTML files:
--
-- Convert to text:
print ("lwarpmk: Converting " .. sourcename
    .."_html.pdf to " .. sourcename .. "_html.html")
os.execute("pdftotext  -enc " .. pdftotextenc .. "  -nopgbrk  -layout "
    .. sourcename .. "_html.pdf " .. sourcename .. "_html.html")
-- Split the result into individual HTML files:
splitfile (homehtmlfilename .. ".html" , sourcename .. "_html.html")
end


function removeaux ()
--
-- Remove auxiliary files:
-- All .aux files are removed since there may be many bbl*.aux files.
-- Also removes sourcename_html.pdf, sourcename_html.html,
-- and sourcename_html.sidetoc, plus comment_*.cut.
--
os.execute ( rmname .. " *.aux " ..
    sourcename ..".toc " .. sourcename .. "_html.toc " ..
```

```
5014     sourcename ..".lof " .. sourcename .. "_html.lof " ..
5015     sourcename ..".lot " .. sourcename .. "_html.lot " ..
5016     sourcename ..".bbl " .. sourcename .. "_html.bbl " ..
5017     " *.idx " ..
5018     " *.ind " ..
5019     sourcename ..".ps " .. sourcename .."_html.ps " ..
5020     sourcename ..".log " .. sourcename .. "_html.log " ..
5021     sourcename ..".gl* " .. sourcename .. "_html.gl* " ..
5022     sourcename .. "_html.pdf " ..
5023     sourcename .. "_html.html " ..
5024     sourcename .. "_html.sidetoc " ..
5025     " *_html_inc.* " ..
5026     " comment_*.cut"
5027     )
5028 end
5029
5030 function checkhtmlpdfexists ()
5031 --
5032 -- Error if the HTML document does not exist.
5033 -- The lateximages are drawn from the HTML PDF version of the document,
5034 -- so "lwarpmk html" must be done before "lwarpmk limages".
5035 --
5036 local htmlpdffile = io.open(sourcename .. "_html.pdf", "r")
5037 if ( htmlpdffile == nil ) then
5038     print ("")
5039     print ("lwarpmk: ===")
5040     print ("lwarpmk: The HTML version of the document does not exist.")
5041     print ("lwarpmk: Enter \"lwarpmk html\" to compile the HTML version.")
5042     print ("lwarpmk: ===")
5043     os.exit(1)
5044 end
5045 io.close (htmlpdffile)
5046 end -- checkhtmlpdfexists
5047
5048
5049 function warnlimages ()
5050 --
5051 -- Warning of a missing <sourcename>-images.txt file:
5052     print ("lwarpmk: ===")
5053     print ("lwarpmk: \"" .. sourcename .. "-images.txt\" does not exist.")
5054     print ("lwarpmk: Your project does not use SVG math or other lateximages,")
5055     print ("lwarpmk: or the file has been deleted somehow.")
5056     print ("lwarpmk: Use \"lwarpmk html1\" to recompile your project")
5057     print ("lwarpmk: and recreate \"" .. sourcename .. "-images.txt\".")
5058    print ("lwarpmk: If your project does not use SVG math or other lateximages,")
5059    print ("lwarpmk: then \"" .. sourcename .. "-images.txt\" will never exist, and")
5060     print ("lwarpmk: \"lwarpmk limages\" will not be necessary.")
5061     print ("lwarpmk: ===")
5062 end -- warnlimages
5063
5064
5065 function warnlimagesrecompile ()
5066 -- Warning if must recompile before creating limages:
5067     print ("")
5068     print ("lwarpmk: ===")
```

```
5069     print ("lwarpmk: Cross-references are not yet correct.")
5070   print ("lwarpmk: The document must be recompiled before creating the lateximages.")
5071   print ("lwarpmk: Enter \"lwarpmk html1\" again, then try \"lwarpmk limages\" again.")
5072     print ("lwarpmk: ===")
5073 end --warnlimagesrecompile
5074
5075
5076 function checklimages ()
5077 --
5078 -- Check <sourcename>.txt to see if need to recompile first.
5079 -- If any entry has a page number of zero, then there were incorrect images.
5080 --
5081 print ("lwarpmk: Checking for a valid " .. sourcename .. "-images.txt file.")
5082 local limagesfile = io.open(sourcename .. "-images.txt", "r")
5083 if ( limagesfile == nil ) then
5084     warnlimages ()
5085     os.exit(1)
5086 end
5087 -- Track warning to recompile if find a page 0
5088 local pagezerowarning = false
5089 -- Scan <sourcename>.txt
5090 for line in limagesfile:lines() do
5091     -- lwimgpage is the page number in the PDF which has the image
5092     -- lwimghash is true if this filename is a hash
5093     -- lwimgname is the lateximage filename root to assign for the image
5094     i,j,lwimgpage,lwimghash,lwimgname = string.find (line,"|(.*)|(.*)|(.*)|")
5095     -- For each entry:
5096     if ( (i~=nil) ) then
5097         -- If the page number is 0, image references are incorrect
5098         --  and must recompile the soure document:
5099         if ( lwimgpage == "0" ) then
5100             pagezerowarning = true
5101         end
5102     end -- if i~=nil
5103 end -- do
5104 -- The last line should be |end|end|end|.
5105 -- If not, the compile must have aborted, and the images are incomplete.
5106 if ( lwimgpage ~= "end" ) then
5107     warnlimagesrecompile()
5108     os.exit(1) ;
5109 end
5110 if ( pagezerowarning ) then
5111     warnlimagesrecompile()
5112     os.exit(1) ;
5113 end -- pagezerowarning
5114 end -- checklimages
5115
5116
5117 function createuniximage ( lwimgfullname )
5118 --
5119 -- Create one lateximage for Unix / Linux / Mac OS.
5120 --
5121 executecheckerror (
5122     cmdgroupopenname ..
5123     "pdfseparate -f " .. lwimgpage .. " -l " .. lwimgpage .. " " ..
```

```
5124         sourcename .."_html.pdf " ..
5125         imagesdirectory .. dirslash .."lateximagetemp-%d" .. ".pdf" ..
5126         seqname ..
5127     -- Crop the image:
5128     "pdfcrop  --hires  " .. imagesdirectory .. dirslash .. "lateximagetemp-" ..
5129         lwimgpage .. ".pdf " ..
5130         imagesdirectory .. dirslash .. lwimgname .. ".pdf" ..
5131         seqname ..
5132     -- Convert the image to svg:
5133    "pdftocairo -svg  -noshrink  " .. imagesdirectory .. dirslash .. lwimgname .. ".pdf " ..
5134         imagesdirectory .. dirslash .. lwimgname ..".svg" ..
5135         seqname ..
5136     -- Remove the temporary files:
5137    rmname .. " " .. imagesdirectory .. dirslash .. lwimgname .. ".pdf" .. seqname ..
5138    rmname .. " " .. imagesdirectory .. dirslash .. "lateximagetemp-" .. lwimgpage .. ".pdf" ..
5139     cmdgroupclosename .. " >/dev/null " .. bgname
5140     ,
5141     "File error trying to convert " .. lwimgfullname
5142 )
5143 -- Every 32 images, wait for completion at below normal priority,
5144 --  allowing other image tasks to catch up.
5145 numimageprocesses = numimageprocesses + 1
5146 if ( numimageprocesses > 32 ) then
5147     numimageprocesses = 0
5148     print ( "lwarpmk: waiting" )
5149     executecheckerror ( "wait" , "File error trying to wait.")
5150 end
5151 end -- createuniximage
5152
5153
5154 function createwindowsimage ( lwimgfullname )
5155 --
5156 -- Create one lateximage for Windows.
5157 --
5158 -- Every 32 images, wait for completion at below normal priority,
5159 --  allowing other image tasks to catch up.
5160 numimageprocesses = numimageprocesses + 1
5161 if ( numimageprocesses > 32 ) then
5162     numimageprocesses = 0
5163     thiswaitcommand = "/WAIT /BELOWNORMAL"
5164     print ( "lwarpmk: waiting" )
5165 else
5166     thiswaitcommand = ""
5167 end
5168 -- Execute the image generation command
5169 executecheckerror (
5170     "start /B " .. thiswaitcommand .. " \"\" lwarp_one_limage " ..
5171     lwimgpage .. " " ..
5172     lwimghash .. " " ..
5173     lwimgname .. " " ..
5174     sourcename .. " <nul >nul"
5175     ,
5176     "File error trying to create image."
5177 )
5178 end -- createwindowsimage
```

```
5179
5180
5181 function createonelateximage ( line )
5182 --
5183 -- Given the next line of <sourcename>.txt, convert a single image.
5184 --
5185 -- lwimgpage is the page number in the PDF which has the image
5186 -- lwimghash is true if this filename is a hash
5187 -- lwimgname is the lateximage filename root to assign for the image
5188 i,j,lwimgpage,lwimghash,lwimgname = string.find (line,"|(.*)|(.*)|(.*)|")
5189 -- For each entry:
5190 if ( (i~=nil) ) then
5191     -- Skip if the page number is 0:
5192     if ( lwimgpage == "0" ) then
5193         pagezerowarning = true
5194     -- Skip if the page number is "end":
5195     else if ( lwimgpage == "end" ) then
5196     else
5197         -- Skip is this image is hashed and already exists:
5198        local lwimgfullname = imagesdirectory .. dirslash .. lwimgname .. ".svg"
5199         if (
5200             (lwimghash ~= "true") or
5201             (lfs.attributes(lwimgfullname,"mode")==nil) -- file not exists
5202         )
5203         then -- not hashed or not exists:
5204             -- Print the name of the file being generated:
5205             print ( "lwarpmk: " .. lwimgname )
5206           -- Touch/create the dest so that only once instance tries to build it:
5207             executecheckerror (
5208                 newtouchname .. " " .. lwimgfullname ,
5209                 "File error trying to touch " .. lwimgfullname
5210             )
5211             -- Separate out the image into its own single-page pdf:
5212             if opsystem=="Unix" then
5213                 createuniximage (lwimgfullname)
5214             elseif opsystem=="Windows" then
5215                 createwindowsimage (lwimgfullname)
5216             end
5217         end -- not hashed or not exists
5218     end -- not page "end"
5219     end -- not page 0
5220 end -- not nil
5221 end -- createonelateximage
5222
5223
5224 function createlateximages ()
5225 --
5226 -- Create lateximages based on <sourcename>-images.txt:
5227 --
5228 -- See if the document must be recompiled first:
5229 checklimages ()
5230 -- See if the HTML version exists:
5231 checkhtmlpdfexists ()
5232 -- Attempt to create the lateximages:
5233 print ("lwarpmk: Creating lateximages.")
```

```
local limagesfile = io.open(sourcename .. "-images.txt", "r")
if ( limagesfile == nil ) then
    warnlimages ()
    os.exit(1)
end
-- Create the lateximages directory, ignore error if already exists
err = os.execute("mkdir " .. imagesdirectory)
-- For Windows, create lwarp_one_limage.cmd from lwarp_one_limage.txt:
if opsystem=="Windows" then
    executecheckerror (
        cpname .. " lwarp_one_limage.txt lwarp_one_limage.cmd" ,
       "File error trying to copy lwarp_one_limage.txt to lwarp_one_limage.cmd"
    )
end -- create lwarp_one_limage.cmd
-- Track the number of parallel processes
numimageprocesses = 0
-- Track warning to recompile if find a page 0
pagezerowarning = false
-- Scan <sourcename>.txt
for line in limagesfile:lines() do
    createonelateximage ( line )
end -- do
io.close(limagesfile)
print ( "lwarpmk limages: ===")
print ( "lwarpmk limages: Wait a moment for the images to complete" )
print ( "lwarpmk limages:   before reloading the page." )
print ( "lwarpmk limages: ===")
print ( "lwarpmk limages: Done." )
if ( pagezerowarning == true ) then
    print ( "lwarpmk limages: WARNING: Images will be incorrect." )
    print ( "lwarpmk limages:   Enter \"lwarpmk cleanlimages\", then" )
    print ( "lwarpmk limages:   recompile the document one more time, then" )
    print ( "lwarpmk limages:   repeat \"lwarpmk images\" again." )
end -- pagezerowarning
end -- function


function convertepstopdf ()
--
-- Converts EPS files to PDF files.
-- The filenames are arg[argindex] and up.
-- arg[1] is the command "epstopdf".
--
ignoreconf ()
for i = argindex , #arg do
    if (lfs.attributes(arg[i],"mode")==nil) then
        print ("lwarpmk: File \"" .. arg[i] .. "\" does not exist.")
    else
        print ("lwarpmk: Converting \"" .. arg[i] .. "\"")
        thispath, thisfilename, thisextension = splitfilename(arg[i])
        if ( thispath == nil ) then
            os.execute ( "epstopdf " .. arg[i] )
        else
            os.execute (
                "epstopdf " ..
```

```
5344
5345 -- print intro:
5346
5347 print ("lwarpmk: " .. printversion .. "  Automated make for the LaTeX Lwarp package.")
5348
5349
5350 -- lwarpmk print:
5351
5352 if arg[1] == "print" then
5353 loadconf ()
5354 if ( latexmk == "true" ) then
5355     print ("lwarpmk: Compiling with: " .. printlatexcmd)
5356     executecheckerror (
5357         printlatexcmd ,
5358         "Compile error."
5359     )
5360     print ("lwarpmk: Done.")
5361 else -- not latexmk
5362     verifyfileexists (sourcename .. ".tex") ;
5363     -- See if up to date:
5364     if (
5365         ( lfs.attributes ( sourcename .. ".pdf" , "modification" ) == nil ) or
5366         (
5367             lfs.attributes ( sourcename .. ".tex" , "modification" ) >
5368             lfs.attributes ( sourcename .. ".pdf" , "modification" )
5369         )
5370     ) then
5371         -- Recompile if not yet up to date:
5372         manytimes(printlatexcmd, "")
5373         print ("lwarpmk: Done.") ;
5374     else
5375         print ("lwarpmk: " .. sourcename .. ".pdf is up to date.") ;
5376     end
5377 end -- not latexmk
5378
5379
5380 -- lwarpmk print1:
5381
5382 elseif arg[1] == "print1" then
5383     loadconf ()
5384     verifyfileexists (sourcename .. ".tex") ;
5385     onetime(printlatexcmd, "")
5386     print ("lwarpmk: Done.") ;
5387
5388
5389 -- lwarpmk printindex:
5390 -- Compile the index then touch the source
5391 -- to trigger a recompile of the document:
5392
5393 elseif arg[1] == "printindex" then
5394 loadconf ()
5395 os.execute ( printindexcmd )
5396 print ("lwarpmk: -------")
5397 updateanddone ()
5398
```

```
5399
5400 -- lwarpmk printglossary:
5401 -- Compile the glossary then touch the source
5402 -- to trigger a recompile of the document:
5403
5404 elseif arg[1] == "printglossary" then
5405 loadconf ()
5406 print ("lwarpmk: Processing the glossary.")
5407
5408 os.execute(glossarycmd .. " " .. sourcename)
5409 updateanddone ()
5410
5411
5412 -- lwarpmk html:
5413
5414 elseif arg[1] == "html" then
5415 loadconf ()
5416 if ( latexmk == "true" ) then
5417     print ("lwarpmk: Compiling with: " .. HTMLlatexcmd)
5418     executecheckerror (
5419         HTMLlatexcmd ,
5420         "Compile error."
5421     )
5422     pdftohtml ()
5423     print ("lwarpmk: Done.")
5424 else -- not latexmk
5425     verifyfileexists ( sourcename .. ".tex" ) ;
5426     -- See if exists and is up to date:
5427     if (
5428       ( lfs.attributes ( homehtmlfilename .. ".html" , "modification" ) == nil ) or
5429         (
5430             lfs.attributes ( sourcename .. ".tex" , "modification" ) >
5431             lfs.attributes ( homehtmlfilename .. ".html" , "modification" )
5432         )
5433     ) then
5434         -- Recompile if not yet up to date:
5435         manytimes(HTMLlatexcmd, "_html")
5436         pdftohtml ()
5437         print ("lwarpmk: Done.")
5438     else
5439         print ("lwarpmk: " .. homehtmlfilename .. ".html is up to date.")
5440     end
5441 end -- not latexmk
5442
5443
5444 -- lwarpmk html1:
5445
5446 elseif arg[1] == "html1" then
5447     loadconf ()
5448     verifyfileexists ( sourcename .. ".tex" ) ;
5449     onetime(HTMLlatexcmd, "_html")
5450     pdftohtml ()
5451     print ("lwarpmk: Done.")
5452
5453
```

```
-- lwarpmk pdftohtml:
elseif arg[1] == "pdftohtml" then
    loadconf ()
    pdftohtml ()


-- lwarpmk htmlindex:
-- Compile the index then touch the source
-- to trigger a recompile of the document:

elseif arg[1] == "htmlindex" then
loadconf ()
os.execute ( HTMLindexcmd )
print ("lwarpmk: -------")
updateanddone ()


-- lwarpmk htmlglossary:
-- Compile the glossary then touch the source
-- to trigger a recompile of the document.
-- The <sourcename>.xdy file is created by the glossaries package.

elseif arg[1] == "htmlglossary" then
loadconf ()
print ("lwarpmk: Processing the glossary.")
os.execute(glossarycmd .. " " .. sourcename .. "_html")
updateanddone ()


-- lwarpmk limages:
-- Scan the <sourcename>.txt file to create lateximages.

elseif arg[1] == "limages" then
loadconf ()
print ("lwarpmk: Processing images.")
createlateximages ()
print ("lwarpmk: Done.")


-- lwarpmk again:
-- Touch the source to trigger a recompile.

elseif arg[1] == "again" then
loadconf ()
updateanddone ()


-- lwarpmk clean:
-- Remove project.aux, .toc, .lof, .lot, .log, *.idx, *.ind, *_html_inc.*, .gl*

elseif arg[1] == "clean" then
loadconf ()
removeaux ()
print ("lwarpmk: Done.")

```

```
5509
5510 -- lwarpmk cleanall
5511 -- Remove project.aux, .toc, .lof, .lot, .log, *.idx, *.ind, *_html_inc.*, .gl*
5512 --    and also project.pdf, project.dvi, *.html
5513
5514 elseif arg[1] == "cleanall" then
5515 loadconf ()
5516 removeaux ()
5517 os.execute ( rmname .. " " ..
5518     sourcename .. ".pdf " .. sourcename .. "_html.pdf " ..
5519     sourcename .. ".dvi " .. sourcename .. "_html.dvi " ..
5520     "*.html"
5521     )
5522 print ("lwarpmk: Done.")
5523
5524
5525 -- lwarpmk cleanlimages
5526 -- Remove images from the imagesdirectory.
5527
5528 elseif arg[1] == "cleanlimages" then
5529 loadconf ()
5530 os.execute ( rmname .. " " .. imagesdirectory .. dirslash .. "*" )
5531 print ("lwarpmk: Done.")
5532
5533 -- lwarpmk epstopdf <list of file names>
5534 -- Convert EPS files to PDF using epstopdf
5535 elseif arg[1] == "epstopdf" then
5536 convertepstopdf ()
5537 print ("lwarpmk: Done.")
5538
5539
5540 -- lwarpmk pdftosvg <list of file names>
5541 -- Convert PDF files to SVG using pdftocairo
5542 elseif arg[1] == "pdftosvg" then
5543 convertpdftosvg ()
5544 print ("lwarpmk: Done.")
5545
5546
5547 -- lwarpmk with no argument :
5548
5549 elseif (arg[1] == nil) then
5550 printhelp ()
5551
5552
5553 -- lwarpmk -v:
5554
5555 elseif (arg[1] == "-v" ) then
5556 -- The version number has already been printed
5557 -- by the lwarpmk intro.
5558
5559 -- lwarpmk -h or lwarpmk --help :
5560
5561 elseif (arg[1] == "-h" ) or (arg[1] == "--help") then
5562 printusage ()
5563
```

```
\newcommand*{\LWR@depthlist}{6}
```

Used by `\item`:

```
\newcommand*{\LWR@depthlistitem}{7}
\let\LWR@depthdescitem\LWR@depthlistitem
```

## 41.2 Closing actions

A stack to record the action to take to close each nesting level: Add more levels of stack if necessary for a very deeply nested document, adding to `\pushclose` and `\popclose` as well.

```
\newcommand*{\LWR@closeone}{}% top of the stack
\newcommand*{\LWR@closetwo}{}
\newcommand*{\LWR@closethree}{}
\newcommand*{\LWR@closefour}{}
\newcommand*{\LWR@closefive}{}
\newcommand*{\LWR@closesix}{}
\newcommand*{\LWR@closeseven}{}
\newcommand*{\LWR@closeeight}{}
\newcommand*{\LWR@closenine}{}
\newcommand*{\LWR@closeten}{}
\newcommand*{\LWR@closeeleven}{}
\newcommand*{\LWR@closetwelve}{}
```

## 41.3 Closing depths

A stack to record the depth of each level:

Note that nested LaTeX structures may push depths which are non-sequential.

*Ex:*

```
\begin{itemize}
   \item{A}
   \begin{description}
      \item{B}
   \end{description}
\end{itemize}
```

```
\newcommand*{\LWR@closedepthone}{\LWR@depthnone}% top of the stack
\newcommand*{\LWR@closedepthtwo}{\LWR@depthnone}
\newcommand*{\LWR@closedepththree}{\LWR@depthnone}
\newcommand*{\LWR@closedepthfour}{\LWR@depthnone}
\newcommand*{\LWR@closedepthfive}{\LWR@depthnone}
\newcommand*{\LWR@closedepthsix}{\LWR@depthnone}
\newcommand*{\LWR@closedepthseven}{\LWR@depthnone}
\newcommand*{\LWR@closedepteight}{\LWR@depthnone}
```

```
\newcommand*{\LWR@closedepthnine}{\LWR@depthnone}
\newcommand*{\LWR@closedepththen}{\LWR@depthnone}
\newcommand*{\LWR@closedeptheleven}{\LWR@depthnone}
\newcommand*{\LWR@closedepthtwelve}{\LWR@depthnone}
```

## 41.4 Pushing and popping the stack

`\LWR@pushclose` {⟨*sectiontype*⟩}

Pushes one return action and its LaTeX depth onto the stacks.

```
\NewDocumentCommand{\LWR@pushclose}{m}
{%
\global\let\LWR@closetwelve\LWR@closeeleven%
\global\let\LWR@closeeleven\LWR@closeten%
\global\let\LWR@closeten\LWR@closenine%
\global\let\LWR@closenine\LWR@closeeight%
\global\let\LWR@closeeight\LWR@closeseven%
\global\let\LWR@closeseven\LWR@closesix%
\global\let\LWR@closesix\LWR@closefive%
\global\let\LWR@closefive\LWR@closefour%
\global\let\LWR@closefour\LWR@closethree%
\global\let\LWR@closethree\LWR@closetwo%
\global\let\LWR@closetwo\LWR@closeone%
\global\csletcs{LWR@closeone}{LWR@printclose#1}%
\global\let\LWR@closedepthtwelve\LWR@closedeptheleven%
\global\let\LWR@closedeptheleven\LWR@closedepththen%
\global\let\LWR@closedepththen\LWR@closedepthnine%
\global\let\LWR@closedepthnine\LWR@closedeptheight%
\global\let\LWR@closedeptheight\LWR@closedepthseven%
\global\let\LWR@closedepthseven\LWR@closedepthsix%
\global\let\LWR@closedepthsix\LWR@closedepthfive%
\global\let\LWR@closedepthfive\LWR@closedepthfour%
\global\let\LWR@closedepthfour\LWR@closedepththree%
\global\let\LWR@closedepththree\LWR@closedepthtwo%
\global\let\LWR@closedepthtwo\LWR@closedepthone%
\global\csletcs{LWR@closedepthone}{LWR@depth#1}%
}
```

`\LWR@popclose` Pops one action and its depth off the stacks.

```
\newcommand*{\LWR@popclose}
{%
\global\let\LWR@closeone\LWR@closetwo%
\global\let\LWR@closetwo\LWR@closethree%
\global\let\LWR@closethree\LWR@closefour%
\global\let\LWR@closefour\LWR@closefive%
\global\let\LWR@closefive\LWR@closesix%
\global\let\LWR@closesix\LWR@closeseven%
\global\let\LWR@closeseven\LWR@closeeight%
\global\let\LWR@closeeight\LWR@closenine%
\global\let\LWR@closenine\LWR@closeten%
\global\let\LWR@closeten\LWR@closeeleven%
```

```
\global\let\LWR@closeeleven\LWR@closetwelve%
\global\let\LWR@closedepthone\LWR@closedepthtwo%
\global\let\LWR@closedepthtwo\LWR@closedepththree%
\global\let\LWR@closedepththree\LWR@closedepthfour%
\global\let\LWR@closedepthfour\LWR@closedepthfive%
\global\let\LWR@closedepthfive\LWR@closedepthsix%
\global\let\LWR@closedepthsix\LWR@closedepthseven%
\global\let\LWR@closedepthseven\LWR@closedeptheight%
\global\let\LWR@closedeptheight\LWR@closedepthnine%
\global\let\LWR@closedepthnine\LWR@closedepthten%
\global\let\LWR@closedepthten\LWR@closedepthteleven%
\global\let\LWR@closedepthteleven\LWR@closedepthtwelve%
}

\end{warpHTML}
```

# 42 Data arrays

These macros are similar to the arrayjobx package, except that `\LWR@setexparray`'s argument is expanded only once when assigned.

`name` has no backslash, `index` can be a number or a text name, and an empty `value` must be `\relax` instead of empty.

To assign an empty value:

```
\LWR@setexparray{name}{index}{}
```

**for HTML output:**

```
\begin{warpHTML}
```

`\LWR@setexparray` {⟨*name*⟩} {⟨*index*⟩} {⟨*contents*⟩}

```
\NewDocumentCommand{\LWR@setexparray}{m m m}{%
    \let\LWR@temp@par\par%
    \let\par\relax%
    \edef\LWR@thisexparrayname{#1#2}%
    \ifstrempty{#3}%
        {\csdef{\LWR@thisexparrayname}{}}%
        {\csedef{\LWR@thisexparrayname}{#3}}%
    \let\par\LWR@temp@par%
}
```

`\LWR@getexparray` {⟨*name*⟩} {⟨*index*⟩}

```
\newcommand*{\LWR@getexparray}[2]{%
    \@nameuse{#1#2}%
}

\end{warpHTML}
```

# 44 Localizing dynamic math

Inline SVG math usually uses a hash of its contents to generate `latex`images which are reusable for multiple instances with the same contents. If the contents may change for each use, such as depending on the current value of a counter, then `\inlinemathother` must be used before the inline math expression, and `\inlinemathnormal` must be used after.

For MathJax, the inline math expression is usually printed for MathJax to interpret. When marked as dynamic math, the following inline math expression will be displayed as an unhashed inline SVG image instead.

For existing code and packages, it may be possible to patch macros after they have been defined, using the xpatch package, which is pre-loaded by lwarp:

```
\xpatchcmd{\macroname}
    {$math expression$}
    {\inlinemathother$math expression$\inlinemathnormal}
    {}
    {\typeout{Error patching macroname.}}
```

**for HTML & PRINT:**

```
\begin{warpall}
```

Bool `LWR@dynamicmath` Default: `false`

True to mark inline math which is dynamic in nature, thus should not be hashed for reuse.

```
\newbool{LWR@dynamicmath}
\boolfalse{LWR@dynamicmath}
```

`\inlinemathother`

Place before using $ … $ or \( … \) if the contents of the math are not static, depending on counters or dynamic macros.

```
\newcommand{\inlinemathother}{%
\LWR@traceinfo{inlinemathother}%
\booltrue{LWR@dynamicmath}%
}
```

`\inlinemathnormal`

Place after using $ … $ or \( … \) with dynamic contents.

```
\newcommand{\inlinemathnormal}{%
\LWR@traceinfo{inlinemathnormal}%
\boolfalse{LWR@dynamicmath}%
}
```

```
\end{warpall}
```

# 45 HTML entities

**for HTML output:**

```
\begin{warpHTML}
```

\HTMLFilename The prefix for all generated HTML files other than the home page, defaulting to empty. See section 7.6.1.

```
\providecommand*{\HTMLFilename}{}
```

\HomeHTMLFilename The filename of the home page, defaulting to the \BaseJobname. See section 7.6.1.

```
\providecommand*{\HomeHTMLFilename}{\BaseJobname}
```

\SetHTMLFileNumber {⟨*number*⟩}

Sets the file number for the next file to be generated. 0 is the home page. Use just before the next sectioning command, and set it to one less than the desired number of the next section. May be used to generate numbered groups of nodes such as 100+ for one chapter, 200+ for another chapter, etc.

```
\newcommand*{\SetHTMLFileNumber}[1]{%
    \setcounter{LWR@htmlfilenumber}{#1}%
}
```

Bool FileSectionNames Selects how to create HTML file names.

Defaults to use section names in the filenames.

```
\newbool{FileSectionNames}
\booltrue{FileSectionNames}
```

```
\end{warpall}
```

**for HTML output:**

```
\begin{warpHTML}
```

Updated each time a new HTML file is begun. Used to provide HTML previous/next web page links.

```
\newcounter{LWR@HTMLpagenum}
\setcounter{LWR@HTMLpagenum}{0}
```

Ctr LWR@htmlseqfilenumber A sequential count of the number of each HTML file as it is being created. Number 0 is the home page. Unlike \LWR@htmlfilenumber, this one is known to increment by one for each file. This is used to generate previous /next links for each web page, via labels called \BaseJobname-autofile-*, and the last page is also labelled \BaseJobname-autofile-last.

```
\newcounter{LWR@htmlseqfilenumber}
\setcounter{LWR@htmlseqfilenumber}{0}
```

Bool LWR@setseqfilelabel At each new HTML file, this is false until a sectional unit is used, at which point this is set true and a label is placed. In this way, the previous/next labels will point to a named section.

```
\newbool{LWR@setseqfilelabel}
\setbool{LWR@setseqfilelabel}{false}
```

Ctr LWR@htmlfilenumber

Records the number of each HTML file as it is being created. Number 0 is the home page. This might not be sequential, as the user may use \SetHTMLFileNumber to create groups of numbered nodes.

```
\newcounter{LWR@htmlfilenumber}
\setcounter{LWR@htmlfilenumber}{0}
```

\LWR@htmlsectionfilename {⟨*htmlfilenumber or name*⟩}

Prints the filename for a given section: \HTMLFilename{}filenumber/name.html

```
\newcommand*{\LWR@htmlsectionfilename}[1]{%
\LWR@traceinfo{LWR@htmlsectionfilename A !\detokenize{#1}!}%
\begingroup%
```

Disable CJK xpinyin while generating file names.

```
\LWR@disablepinyin%
```

Section 0 or empty is given the home filename. The filename must be detokenized for underscores.

```
% \LWR@traceinfo{about to assign temp}%
\LWR@sanitize{#1}%
\LWR@traceinfo{about to compare with ??}%
\ifdefstring{\LWR@sanitized}{??}
    {\LWR@traceinfo{found ??}}%
    {\LWR@traceinfo{not found ??}}%
\LWR@traceinfo{about to compare with zero or empty}%
\ifboolexpr{
    test {\ifdefstring{\LWR@sanitized}{0}} or
    test {\ifdefstring{\LWR@sanitized}{}} or
    test {\ifdefstring{\LWR@sanitized}{??}}
}
{%
    \LWR@traceinfo{LWR@htmlsectionfilename B \HomeHTMLFilename.html}%
    \HomeHTMLFilename.html%
}%
```

For a LaTeX section named “Index” or “index” without a prefix, create a filename with a trailing -0 to avoid colliding with the HTML filename index.html:

```
{%
    \LWR@traceinfo{LWR@htmlsectionfilename C \LWR@sanitized}%
    \ifboolexpr{
            test{\ifdefvoid{\HTMLFilename}} and
            (
                test{\ifdefstring{\LWR@sanitized}{Index}} or
                test{\ifdefstring{\LWR@sanitized}{index}}
            )
    }%
    {%
        \LWR@traceinfo{Adding a zero to the index filename.}%
        \LWR@sanitized-0.html%
    }%
```

Otherwise, create a filename with the chosen prefix:

```
    {%
        \HTMLFilename\LWR@isolate{\LWR@sanitized}.html%
    }%
}%
\LWR@traceinfo{LWR@htmlsectionfilename Z}%
\endgroup%
}
```

`\LWR@htmlrefsectionfilename` {⟨*label*⟩}

Prints the filename for the given label

```
\newcommand*{\LWR@htmlrefsectionfilename}[1]{%
    \LWR@traceinfo{LWR@htmlrefsectionfilename: !\detokenize{#1}!}%
```

`\LWR@nullfonts` to allow math in a section name.

```
    \begingroup%
    \LWR@nullfonts%
    \LWR@htmlsectionfilename{\LWR@htmlfileref{#1}}%
    \endgroup%
    \LWR@traceinfo{LWR@htmlrefsectionfilename: done}%
}
```

```
\end{warpHTML}
```

# 47 Homepage link

**for HTML & PRINT:**

```
\begin{warpall}
```

`\linkhomename` Holds the default name for the home link.

```
\newcommand{\linkhomename}{Home}
```

```
\end{warpall}
```

**for HTML output:**

```
\begin{warpHTML}
```

`\LinkHome` May be used wherever you wish to place a link back to the homepage. The filename must be detokenized for underscores.

```
\newcommand*{\LinkHome}{%
    \LWR@subhyperrefclass{\HomeHTMLFilename.html}{\linkhomename}{linkhome}%
}
```

```
\end{warpHTML}
```

**for PRINT output:**

```
\begin{warpprint}
```

\LinkHome May be used wherever you wish to place a link back to the homepage. For print output, if hyperref is available a hyperlink to the first page is used, named by \linkhomename. If hyperref is not available, a pageref is used instead.

\BaseJobname is included in the link label in case multiple documents are cross-referenced.

```
\AtBeginDocument{
\@ifundefined{hyperref}{
    \newcommand*{\LinkHome}{%
        \linkhomename\ --- page \pageref{\BaseJobname-page-LWRfirstpage}%
    }
}{
    \newcommand*{\LinkHome}{%
        \hyperref[\BaseJobname-page-LWRfirstpage]{\linkhomename}%
    }
}
}

\AfterEndPreamble{\label{\BaseJobname-page-LWRfirstpage}}

\end{warpprint}
```

**for HTML output:**

```
\begin{warpHTML}
```

\LWR@topnavigation Creates a link to the homepage at the top of the page for use when the window is too narrow for the sideTOC.

```
\newcommand*{\LWR@topnavigation}{%
    \LWR@htmlelementclassline{nav}{topnavigation}{\LinkHome}
}
```

\LWR@botnavigation Creates a link to the homepage at the bottom of the page for use when the window is too narrow for the sideTOC.

```
\newcommand*{\LWR@botnavigation}{%
    \LWR@htmlelementclassline{nav}{botnavigation}{\LinkHome}
}

\end{warpHTML}
```

# 48 Previous/next navigation links

**for HTML & PRINT:**

```
\begin{warpall}
```

\linkpreviousname What to call the link to the previous web page.

```
\newcommand*{\linkpreviousname}{Previous}
```

\linknextname What to call the link to the next web page.

```
\newcommand*{\linknextname}{Next}
```

```
\end{warpall}
```

**for PRINT output:**

```
\begin{warpprint}
```

`\LinkPrevious` Creates a link to the previous web page if there is one.

```
\newcommand*{\LinkPrevious}{}
```

`\LinkNext` Creates a link to the next web page if there is one.

```
\newcommand*{\LinkNext}{}
```

```
\end{warpprint}
```

**for HTML output:**

```
\begin{warpHTML}
```

`\LinkPrevious` Creates a link to the previous web page if there is one.

The links refer to the LaTeX labels `\Basejobname-autofile-*`

```
\newcommand*{\LinkPrevious}{%
    \ifnumless{\value{LWR@htmlseqfilenumber}}{1}{}{%
        \setcounter{LWR@tempcountone}{\value{LWR@htmlseqfilenumber}-1}%
        \LWR@subhyperrefclass{%
            \LWR@htmlrefsectionfilename{%
                \BaseJobname-autofile-\arabic{LWR@tempcountone}%
            }%
        }{\linkpreviousname}{linkhome}%
    }%
}
```

`\LinkNext` Creates a link to the next web page if there is one.

The links refer to the LaTeX labels `\Basejobname-autofile-*`
and the last is the label `\Basejobname-autofile-last`

```
\newcommand*{\LinkNext}{%
    \ifcsdef{r@\BaseJobname-autofile-last@lwarp}{%
        \edef\LWR@tempone{%
        \LWR@htmlfileref{\BaseJobname-autofile-\arabic{LWR@htmlseqfilenumber}}%
        }%
        \edef\LWR@temptwo{%
            \LWR@htmlfileref{\BaseJobname-autofile-last}%
        }%
        \ifdefequal{\LWR@tempone}{\LWR@temptwo}{}{%
            \setcounter{LWR@tempcountone}{\value{LWR@htmlseqfilenumber}+1}%
            \LWR@subhyperrefclass{%
                \LWR@htmlrefsectionfilename{%
                    \BaseJobname-autofile-\arabic{LWR@tempcountone}%
                }%
            }{\linknextname}{linkhome}%
        }%
```

```
    }{}%
}
```

```
\end{warpHTML}
```

# 49 \LWRPrintStack diagnostic tool

⚠ Diagnostics tool: Prints the LaTeX nesting depth values for the stack levels. `\LWR@startpars` is used before printing the stack, so that `\LWRPrintStack` may be called from anywhere in the normal text flow.

**for HTML output:**

```
\begin{warpHTML}
```

`\LWRPrintStack` Prints the closedepth stack.

```
\newcommand*{\LWR@subprintstack}{
\LWR@closedepthone\ \LWR@closedepththwo\ \LWR@closedepththree\
\LWR@closedepthfour\ \LWR@closedepthfive\ \LWR@closedepthsix\
\LWR@closedepthseven\ \LWR@closedeptheight\ \LWR@closedepthnine\
\LWR@closedepthten\ \LWR@closedeptheleven\ \LWR@closedepthtwelve\
}

\newcommand*{\LWRPrintStack}{
\LWR@startpars
\LWR@subprintstack
}
```

```
\end{warpHTML}
```

**for PRINT output:**

```
\begin{warpprint}
```

```
\newcommand*{\LWRPrintStack}{}
```

```
\end{warpprint}
```

# 50 Closing stack levels

**for HTML output:**

```
\begin{warpHTML}
```

Close one nested level:

```
\newcommand*{\LWR@closeoneprevious}{%

\LWR@closeone

\LWR@popclose
}
```

\LWR@closeprevious {⟨*sectintype*⟩} Close everything up to the given depth:

```
\newcommand*{\LWR@closeprevious}[1]{
\LWR@traceinfo{%
    LWR@closeprevious to depth \csuse{LWR@depth#1}, %
    depths are \LWR@subprintstack%
}%
```

Close any pending paragraph:

```
\LWR@stoppars%
```

Close anything nested deeper than the desired depth. First close anything deeper, then at most one of the same level.

```
\whileboolexpr{test{\ifnumcomp{\LWR@closedepthone}{>}{\csuse{LWR@depth#1}}}}%
{%
    \LWR@traceinfo{LWR@closeprevious: closing out depth \LWR@closedepthone}%
    \LWR@closeoneprevious%
}%
\ifboolexpr{test{\ifnumcomp{\LWR@closedepthone}{=}{\csuse{LWR@depth#1}}}}%
{%
    \LWR@traceinfo{LWR@closeprevious: closing out depth \LWR@closedepthone}%
    \LWR@closeoneprevious%
}{}%
\LWR@traceinfo{LWR@closeprevious: done, depths are \LWR@subprintstack}%
}

\end{warpHTML}
```

# 51 PDF pages and styles

**for HTML output:**

```
\begin{warpHTML}
```

\LWR@forcenewpage New PDF page a before major environment.

This is used just before major environments, such as verse. Reduces the chance of an environment overflowing the HTML PDF output page.

```
\newcommand{\LWR@forcenewpage}{%
\LWR@traceinfo{LWR@forcenewpage}%
\ifinner\else%
    \LWR@traceinfo{LWR@forcenewpage A}%

```

\pagestyle, etc. are nullified for HTML output.

\pagestyle {⟨*style*⟩}

```
\renewcommand*{\pagestyle}[1]{}
```

\thispagestyle {⟨*style*⟩}

```
\renewcommand*{\thispagestyle}[1]{}
```

\markboth {⟨*left*⟩} {⟨*right*⟩}

```
\renewcommand*{\markboth}[2]{}
```

\markright {⟨*right*⟩}

```
\renewcommand*{\markright}[1]{}
```

\raggedbottom

```
\renewcommand*{\raggedbottom}{}
```

\flushbottom

```
\renewcommand*{\flushbottom}{}
```

\sloppy

```
\renewcommand*{\sloppy}{}
```

\fussy

```
\renewcommand*{\fussy}{}
```

\pagenumbering * {⟨*commands*⟩}

```
\RenewDocumentCommand{\pagenumbering}{s m}{}
\end{warpHTML}
```

# 52 HTML tags, spans, divs, elements

**for HTML output:**

```
\begin{warpHTML}
```

```
\@ifundefined{frenchbsetup}%
{}%
{%
    \frenchbsetup{FrenchFootnotes=false}%

%
    \renewrobustcmd*{\FBcolonspace}{%
        \begingroup%
        \LWR@hook@processingtags%
        \LWR@origampersand{}nbsp;%
        \endgroup%
    }%
    \renewrobustcmd*{\FBthinspace}{%
        \begingroup%
        \LWR@hook@processingtags%
        \LWR@origampersand\LWR@origpound{}x202f;% \,
        \endgroup%
    }%
    \renewrobustcmd*{\FBguillspace}{%
        \begingroup%
        \LWR@hook@processingtags%
        \LWR@origampersand{}nbsp;% ~,  for \og xyz \fg{}
        \endgroup%
    }%
    \DeclareDocumentCommand{\FBmedkern}{}{%
        \begingroup%
        \LWR@hook@processingtags%
        \LWR@origampersand\LWR@origpound{}x202f;% \,
        \endgroup%
    }%
    \DeclareDocumentCommand{\FBthickkern}{}{%
        \begingroup%
        \LWR@hook@processingtags%
        \LWR@origampersand{}nbsp;% ~
        \endgroup%
    }%
    \renewrobustcmd*{~}{\HTMLentity{nbsp}}% was overwritten by babel-french
    \ifFBunicode%
    \else%
        \DeclareTextSymbol{\FBtextellipsis}{LY1}{133}%
        \DeclareTextCommandDefault{\FBtextellipsis}{\textellipsis\xspace}%
    \fi%
}%
}
```

## 52.4 HTML output formatting

Helps format the output HTML code for human readability.

`\LWR@indentHTML` Newline and indent the output HTML code.

```
\newcommand*{\LWR@indentHTML}{%
```

```
    \LWR@orignewline\LWR@origrule{2em}{0pt}%
}
```

`\LWR@indentHTMLtwo` Newline and indent the output HTML code.

```
\newcommand*{\LWR@indentHTMLtwo}{%
    \LWR@orignewline\LWR@origrule{4em}{0pt}%
}
```

## 52.5 HTML tags

`\LWR@htmltagc` {⟨*tag*⟩} Break ligatures and use upright apostrophes in HTML tags.

`\protect` is in case the tag appears in TOC, LOF, LOT.

```
\newcommand*{\LWR@htmltagc}[1]{%
\LWR@traceinfo{LWR@htmltagc !\detokenize{#1}!}%
\begingroup%
\LWR@hook@processingtags%
\ifmmode\else\protect\LWR@print@normalfont\protect\LWR@origttfamily\fi%
\protect\LWR@origtextless%
\LWR@isolate{#1}%
\protect\LWR@origtextgreater%
\endgroup%
}
```

`\LWR@spanwarnformat` {⟨*object*⟩}

Warns if the given object is used inside a span.

```
\newcommand*{\LWR@spanwarnformat}[1]{%
    \ifnumcomp{\value{LWR@spandepth}}{>}{0}{%
        \PackageWarning{lwarp}{%
            A #1 is being used inside a span.\MessageBreak
            Formatting may be lost,%
        }%
    }{}%
}
```

`\LWR@spanwarninvalid` {⟨*object*⟩}

Warns if the given object is used inside a span.

```
\newcommand*{\LWR@spanwarninvalid}[1]{%
    \ifnumcomp{\value{LWR@spandepth}}{>}{0}{%
        \PackageWarning{lwarp}{%
            A #1 is being used inside a span.\MessageBreak
            This generates invalid HTML,%
        }%
    }{}%
}
```

Env LWR@nestspan Disable minipage, \parbox, and HTML s inside a .

⚠ \begin{LWR@nestspan} must follow the opening  tag to allow a paragraph to start if the span is at the beginning of a new paragraph.

⚠ \end{LWR@nestspan} must follow the  or a <p> may appear inside the span.

```
\newcommand*{\LWR@nestspanitem}{%
\if@newlist\else{\LWR@htmltagc{br /}}\fi%
\LWR@origitem%
}

\newenvironment*{LWR@nestspan}
{%
\LWR@traceinfo{LWR@nestspan starting}%
\ifnumcomp{\value{LWR@lateximagedepth}}{>}{0}%
{%
    \LWR@traceinfo{LWR@nestspan: inside a lateximage}%
}%
{% not in a lateximage
    \LWR@traceinfo{LWR@nestspan: NOT inside a lateximage}%
    \addtocounter{LWR@spandepth}{1}%
```

Nullify several objects inside the span:

```
    \RenewDocumentEnvironment{minipage}{O{t} o O{t} m}%
        {\LWR@spanwarnformat{minipage or \protect\parbox}}%
        {}%
    \RenewDocumentEnvironment{BlockClass}{o m}%
        {\LWR@spanwarnformat{multi-paragraph object}}%
        {}%
    \renewcommand{\BlockClassSingle}[2]{%
        {\LWR@spanwarnformat{multi-paragraph object}}%
        ##2%
    }%
    \renewcommand{\LWR@forcenewpage}{}%
    \renewcommand{\LWR@liststart}{%
        \let\item\LWR@nestspanitem%
    }%
    \renewcommand{\LWR@listend}{\LWR@htmltagc{br /}\LWR@htmltagc{br /}}%
    \renewenvironment{quote}{\LWR@htmltagc{br /}}{\LWR@htmltagc{br /}}%
    \renewenvironment{quotation}{\LWR@htmltagc{br /}}{\LWR@htmltagc{br /}}%
}% not in a lateximage
\LWR@traceinfo{LWR@nestspan starting: done}%
}% starting env
{% ending env
\LWR@traceinfo{LWR@nestspan ending}%
\ifnumcomp{\value{LWR@lateximagedepth}}{>}{0}%
{}%
{\addtocounter{LWR@spandepth}{-1}}%
\LWR@traceinfo{LWR@nestspan ending: done}%
}

\AfterEndEnvironment{LWR@nestspan}{\global\let\par\LWR@closeparagraph}
```

```
}%
}

\newcommand*{\LWR@htmlclosecomment}{%
{%
%  \LWR@traceinfo{LWR@htmlclosecomment}%
\begingroup%
\LWR@hook@processingtags%
\ifmmode\else\protect\LWR@print@normalfont\protect\LWR@origttfamily\fi%
\LWR@print@mbox{-\/-\LWR@origtextgreater}%
\endgroup%
}%
}
```

\LWR@htmlcomment{ *htmlcomment* }

```
\newcommand{\LWR@htmlcomment}[1]{%
\ifmmode%
\else%
    \LWR@htmlopencomment{}%
    {%
        \LWR@print@normalfont%
        \LWR@origttfamily%  break  ligatures
        #1%
    }%
    \LWR@htmlclosecomment{}%
\fi%
}
```

\LWR@htmlblockcomment{ *htmlcomment* }

```
\newcommand{\LWR@htmlblockcomment}[1]
{\LWR@stoppars\LWR@htmlcomment{#1}\LWR@startpars}
```

\LWR@htmlblocktag { *htmltag* } print a stand-alone html tag

```
\newcommand*{\LWR@htmlblocktag}[1]{%
\LWR@stoppars%
\LWR@htmltag{#1}%
\LWR@startpars%
}
```

## 52.7 Div class and element class

\LWR@subhtmlelementclass { *htmlelement* } [ *htmlstyle* ] { *htmlclass* }

Factored and reused in several places.

The trailing spaces allow more places for a line break.

The use of \textquotedbl instead of " provides improved compatibility with xeCJK.

```
}%
}

\newcommand*{\LWR@htmlclosecomment}{%
{%
%  \LWR@traceinfo{LWR@htmlclosecomment}%
\begingroup%
\LWR@hook@processingtags%
\ifmmode\else\protect\LWR@print@normalfont\protect\LWR@origttfamily\fi%
\LWR@print@mbox{-\/-\LWR@origtextgreater}%
\endgroup%
}%
}
```

\LWR@htmlcomment{ *htmlcomment* }

```
\newcommand{\LWR@htmlcomment}[1]{%
\ifmmode%
\else%
    \LWR@htmlopencomment{}%
    {%
        \LWR@print@normalfont%
        \LWR@origttfamily%  break  ligatures
        #1%
    }%
    \LWR@htmlclosecomment{}%
\fi%
}
```

\LWR@htmlblockcomment{ *htmlcomment* }

```
\newcommand{\LWR@htmlblockcomment}[1]
{\LWR@stoppars\LWR@htmlcomment{#1}\LWR@startpars}
```

\LWR@htmlblocktag { *htmltag* } print a stand-alone html tag

```
\newcommand*{\LWR@htmlblocktag}[1]{%
\LWR@stoppars%
\LWR@htmltag{#1}%
\LWR@startpars%
}
```

## 52.7 Div class and element class

\LWR@subhtmlelementclass { *htmlelement* } [ *htmlstyle* ] { *htmlclass* }

Factored and reused in several places.

The trailing spaces allow more places for a line break.

The use of \textquotedbl instead of " provides improved compatibility with xeCJK.

```
}%
}

\newcommand*{\LWR@htmlclosecomment}{%
{%
%  \LWR@traceinfo{LWR@htmlclosecomment}%
\begingroup%
\LWR@hook@processingtags%
\ifmmode\else\protect\LWR@print@normalfont\protect\LWR@origttfamily\fi%
\LWR@print@mbox{-\/-\LWR@origtextgreater}%
\endgroup%
}%
}
```

\LWR@htmlcomment{ *htmlcomment* }

```
\newcommand{\LWR@htmlcomment}[1]{%
\ifmmode%
\else%
    \LWR@htmlopencomment{}%
    {%
        \LWR@print@normalfont%
        \LWR@origttfamily%  break  ligatures
        #1%
    }%
    \LWR@htmlclosecomment{}%
\fi%
}
```

\LWR@htmlblockcomment{ *htmlcomment* }

```
\newcommand{\LWR@htmlblockcomment}[1]
{\LWR@stoppars\LWR@htmlcomment{#1}\LWR@startpars}
```

\LWR@htmlblocktag { *htmltag* } print a stand-alone html tag

```
\newcommand*{\LWR@htmlblocktag}[1]{%
\LWR@stoppars%
\LWR@htmltag{#1}%
\LWR@startpars%
}
```

## 52.7 Div class and element class

\LWR@subhtmlelementclass { *htmlelement* } [ *htmlstyle* ] { *htmlclass* }

Factored and reused in several places.

The trailing spaces allow more places for a line break.

The use of \textquotedbl instead of " provides improved compatibility with xeCJK.

```
}%
}

\newcommand*{\LWR@htmlclosecomment}{%
{%
%  \LWR@traceinfo{LWR@htmlclosecomment}%
\begingroup%
\LWR@hook@processingtags%
\ifmmode\else\protect\LWR@print@normalfont\protect\LWR@origttfamily\fi%
\LWR@print@mbox{-\/-\LWR@origtextgreater}%
\endgroup%
}%
}
```

\LWR@htmlcomment{ *htmlcomment* }

```
\newcommand{\LWR@htmlcomment}[1]{%
\ifmmode%
\else%
    \LWR@htmlopencomment{}%
    {%
        \LWR@print@normalfont%
        \LWR@origttfamily%  break  ligatures
        #1%
    }%
    \LWR@htmlclosecomment{}%
\fi%
}
```

\LWR@htmlblockcomment{ *htmlcomment* }

```
\newcommand{\LWR@htmlblockcomment}[1]
{\LWR@stoppars\LWR@htmlcomment{#1}\LWR@startpars}
```

\LWR@htmlblocktag { *htmltag* } print a stand-alone html tag

```
\newcommand*{\LWR@htmlblocktag}[1]{%
\LWR@stoppars%
\LWR@htmltag{#1}%
\LWR@startpars%
}
```

## 52.7 Div class and element class

\LWR@subhtmlelementclass { *htmlelement* } [ *htmlstyle* ] { *htmlclass* }

Factored and reused in several places.

The trailing spaces allow more places for a line break.

The use of \textquotedbl instead of " provides improved compatibility with xeCJK.

```
        {\detokenize{-}}[\LWR@thisnewfilename]%
}
}
```

\LWR@simplifycustom User-defined filename simplifications. Redefine with \newcommand.

```
\newcommand*{\LWR@simplifycustom}{}
```

\FilenameSimplify *{⟨*phrase*⟩} Assign a user-defined filename simplification. Appends to \LWR@simplifycustom.

```
\NewDocumentCommand{\FilenameSimplify}{s m}{%
\IfBooleanTF{#1}{%
    \appto{\LWR@simplifycustom}{%
        \LWR@simplifyname*{#2}%
    }%
}{%
    \appto{\LWR@simplifycustom}{%
        \LWR@simplifyname{#2}%
    }%
}%
}
```

\LWR@avoiddupfilenames Instructions for how to avoid duplicate filenames. This is used in a warning in \LWR@filenamenoblanks, and in an error in \LWR@newhtmlfile.

```
\newcommand*{\LWR@avoiddupfilenames}{%
    To avoid duplicate filenames, use the optional\MessageBreak
    short Table of Contents entry:\MessageBreak
    \space\space\protect\section[Unique name, no math]{Name with math}%
        \MessageBreak
    or use \protect\texorpdfstring, from the hyperref package:\MessageBreak
    \space\space%
        \protect\section{\MessageBreak
            \space\space\space\space\protect\texorpdfstring\MessageBreak
                \space\space\space\space\space\space%
                {Name with math}{Unique name, no math}\MessageBreak
        \space\space}
}
```

\LWR@filenamenoblanks {⟨*filename*⟩}

Convert blanks into dashes, removes short words, store result in \LWR@thisfilename.

Also see \LWR@nullfonts for nullified macros.

```
\newcommand*{\LWR@filenamenoblanks}[1]{%
\begingroup
```

Locally temporarily disable direct-formatting commands, not used in filenames:

```
\LWR@nullfonts%
\renewcommand*{\LWR@htmltagc}[1]{}%

\edef\LWR@thisnewfilename{#1}%
```

Replaces common macros with hyphens. (\& is done by \LWR@nullfonts.)

```
\RenewDocumentCommand{\LWR@subsingledollar}{s m m m}{}%
\LWR@simplifyname{\_}
\LWR@simplifyname{\#}
\LWR@simplifyname{\textbackslash}
\LWR@simplifyname{\protect}
\LWR@simplifyname{\ }
\LWR@simplifyname{\textless}
\LWR@simplifyname{\textgreater}

\edef\LWR@thisnewfilename{\detokenize\expandafter{\LWR@thisnewfilename}}%
```

Warn if there is dollar math in the section name:

```
\ifbool{FileSectionNames}{%
    \IfSubStr{\LWR@thisnewfilename}{\LWRdollar}{%
        \PackageWarning{lwarp}
        {%
            This section name:\MessageBreak
            \space\space``\detokenize\expandafter{#1}''\MessageBreak
            at the line number listed below,\MessageBreak
            is using $dollar-delimited math$,
            which generates\MessageBreak
            complicated file names.  It is better to use\MessageBreak
            \space\space%
              \protect\section{Name with \protect\(parenthesis math\protect\)}%
                 \MessageBreak
            The math then will be removed from the file name.\MessageBreak
            \MessageBreak
            \LWR@avoiddupfilenames%
            \MessageBreak
            This section is found before or%
        }
    }{}%
}{}

\LWR@traceinfo{LWR@filenamenoblanks edef: !\LWR@thisnewfilename!}%
\fullexpandarg%
```

Convert spaces into hyphens:

```
\LWR@simplifyname*{ }
```

Convert punctutation into hyphens:

```
\LWR@simplifyname*{*}
\LWR@simplifyname*{(}
\LWR@simplifyname*{)}
```

```
\LWR@simplifyname*{.}
\LWR@simplifyname*{!}
\LWR@simplifyname*{,}
\LWR@simplifyname*{'}
\LWR@simplifyname*{+}
\LWR@simplifyname*{/}
\LWR@simplifyname*{:}
\LWR@simplifyname*{;}
\LWR@simplifyname*{=}
\LWR@simplifyname*{?}
\LWR@simplifyname*{@}
\LWR@simplifyname*{^}
\LWR@simplifyname*{&}
\LWR@simplifyname*{"}
\LWR@simplifyname*{<}
\LWR@simplifyname*{>}

\LWR@simplifyname{\LWRbackslash}
```

Braces are removed entirely to avoid extra dashes in the result.

```
\StrSubstitute{\LWR@thisnewfilename}%
    {\LWRleftbrace}{}[\LWR@thisnewfilename]%
\StrSubstitute{\LWR@thisnewfilename}%
    {\LWRrightbrace}{}[\LWR@thisnewfilename]%

\LWR@simplifyname{\LWRpercent}
\LWR@simplifyname{\LWRdollar}

\LWR@simplifyname*{|}
\LWR@simplifyname*{^}
\LWR@simplifyname*{~}
\LWR@simplifyname*{[}
\LWR@simplifyname*{]}
\LWR@simplifyname*{`}
```

Convert short words:

```
\LWR@simplifyname*{-s-}
\LWR@simplifyname*{-S-}
\LWR@simplifyname*{-a-}
\LWR@simplifyname*{-A-}
\LWR@simplifyname*{-an-}
\LWR@simplifyname*{-AN-}
\LWR@simplifyname*{-to-}
\LWR@simplifyname*{-TO-}
\LWR@simplifyname*{-by-}
\LWR@simplifyname*{-BY-}
\LWR@simplifyname*{-of-}
\LWR@simplifyname*{-OF-}
\LWR@simplifyname*{-and-}
\LWR@simplifyname*{-AND-}
\LWR@simplifyname*{-for-}
\LWR@simplifyname*{-FOR-}
```

```
\LWR@simplifyname*{-the-}
\LWR@simplifyname*{-THE-}
```

Convert custom words:

```
\LWR@simplifycustom%
```

If pdfLaTeX and not `utf8` encoding, don't try to convert emdash, endash:

```
\ifPDFTeX% pdflatex or dvi latex
\ifdefstring{\inputencodingname}{utf8}{%
    \LWR@simplifyname*{-}
%     emdash
    \LWR@simplifyname*{-}
%     endash
}{}%
\else% not PDFTeX
    \LWR@simplifyname*{-}
    \LWR@simplifyname*{-}
\fi%
```

Convert multiple hyphens:

```
\LWR@simplifyname*{-----}
\LWR@simplifyname*{----}
\LWR@simplifyname*{---}
\LWR@simplifyname*{--}
```

If starts with a dash, remove the leading dash:

```
\IfBeginWith{\LWR@thisnewfilename}{\detokenize{-}}{%
    \StrGobbleLeft{\LWR@thisnewfilename}{1}[\LWR@thisnewfilename]%
}{}%
```

If ends with a dash, remove the trailing dash:

```
\IfEndWith{\LWR@thisnewfilename}{\detokenize{-}}{%
    \StrGobbleRight{\LWR@thisnewfilename}{1}[\LWR@thisnewfilename]%
}{}%
```

Limits the length of the filename:

```
\StrLeft{\LWR@thisnewfilename}{\FilenameLimit}[\LWR@thisnewfilename]%
```

Return the global result:

```
\global\let\LWR@thisfilename\LWR@thisnewfilename%
\endgroup%
\LWR@traceinfo{LWR@filenamenoblanks: result is \LWR@thisfilename}%
}
```

Ctr `LWR@previousautopagelabel`

Remembers which autopage label was most recently generated. Used to avoid duplicates.

```
\newcounter{LWR@previousautopagelabel}
\setcounter{LWR@previousautopagelabel}{-1}
```

File *_html.aux A new entry in the *_html.aux file is used to help cross-references:

```
\newlabel{autopage-<nnn>}{{<x>}{<y>}}
```

\LWR@newautopagelabel {⟨*pagenumber counter*⟩}

\BaseJobname is added to the label in case xr or xr-hyper are used.

```
\newcommand*{\LWR@newautopagelabel}[1]{%
\ifnumequal{\value{LWR@previousautopagelabel}}{\value{page}}%
{}% no action if this autopage label has already been defined
{%
    \label{\BaseJobname-autopage-\arabic{#1}}%
    \setcounter{LWR@previousautopagelabel}{\value{page}}
}%
}
```

## 62.1 Sanitizing expressions for HTML

Math expressions are converted to lateximages, and some math environments may contain &, <, or >, which should not be allowed inside an HTML <alt> tag, so must convert them to HTML entities.

\LWR@replacestrings {⟨*search*⟩} {⟨*replace*⟩}

Replaces strings inside \tmpb.

Modified from the original, by Petr Olsak, from the opmac package.

```
\bgroup
\catcode`!=3 \catcode`?=3

\long\gdef\LWR@replacestrings@addto#1#2{%
    \expandafter\def\expandafter#1\expandafter{#1#2}%
}

\gdef\LWR@replacestrings#1#2{%
    \long\def\LWR@replacestringsA##1#1{\def\tmpb{##1}\LWR@replacestringsB}%
   \long\def\LWR@replacestringsB##1#1{%
        \ifx!##1\relax \else\LWR@replacestrings@addto\tmpb{#2##1}%
        \expandafter\LWR@replacestringsB\fi%
    }%                                      improved version <May 2016> inspired
   \expandafter\LWR@replacestringsA\tmpb?#1!#1% from pysyntax.tex by Petr Krajnik
    \long\def\LWR@replacestringsA##1?{%
        \def\tmpb{##1}%
    }\expandafter\LWR@replacestringsA\tmpb%
}
\egroup
```

Bool LWR@MathJax@silentquotes If true, double quotes (\" and ") are removed (used for mathspec). This unfortunately includes double quotes used inside \text with MathJax. If false, double quotes are escaped.

```
\newbool{LWR@MathJax@silentquotes}
\boolfalse{LWR@MathJax@silentquotes}
```

\LWR@subHTMLsanitize

\LWR@strresult must first be set by \LWR@HTMLsanitize, \LWR@HTMLsanitizeexpand, or \CustomizeMathJax.

```
\catcode`\#=12
\catcode`\&=12
\newcommand{\LWR@subHTMLsanitize}{%
```

The &, <, and > may be interpreted by the browser:

```
    \edef\tmpb{\detokenize\expandafter{\LWR@strresult}}%
    \LWR@replacestrings{&}{&amp;}%
    \LWR@replacestrings{<}{&lt;}%
    \LWR@replacestrings{>}{&gt;}%
```

The quotes occasionally causes problems. For mathspec, also allow neutralization of \" and the " character.

```
    \ifbool{LWR@MathJax@silentquotes}
        {%
            \expandafter\LWR@replacestrings\expandafter{\LWRbackslash"}{}%
            \LWR@replacestrings{"}{}%
        }%
        {\LWR@replacestrings{"}{&quot;}}%
    \LWR@replacestrings{'}{&apos;}%
    \LWR@replacestrings{`}{&grave;}%
```

MathJax allows expressions to be defined with \newcommand. These expressions would appear with ## for each argument, and each must be changed to a single #. This must be done after all the above changes. Attempting another conversion after this causes an error upon further expansion.

```
    \LWR@replacestrings{##}{#}%
    \edef\LWR@strresult{\detokenize\expandafter{\tmpb}}%
}
\catcode`\#=6
\catcode`\&=4
```

\LWR@HTMLsanitize {⟨*text*⟩}

```
\newrobustcmd{\LWR@HTMLsanitize}[1]{%
```

Cancel French babel character handling, and fully expand the strings:

```
    \begingroup%
    \LWR@hook@processingtags%
    \edef\LWR@strresult{\detokenize{#1}}%
    \LWR@subHTMLsanitize%
    \LWR@strresult%
    \endgroup%
}
```

\LWR@HTMLsanitizeexpand {⟨*text*⟩}

This version expands the argument before sanitizing it. This is only used for adding math to MathJax expressions or `lateximage` `alt` tags.

```
\edef\LWR@beginspaceleftbrace{begin \LWRleftbrace}
\edef\LWR@beginspaceleftbrace{\detokenize\expandafter{\LWR@beginspaceleftbrace}}
\edef\LWR@beginleftbrace{begin\LWRleftbrace}
\edef\LWR@beginleftbrace{\detokenize\expandafter{\LWR@beginleftbrace}}

\edef\LWR@endspacerightbrace{end \LWRrightbrace}
\edef\LWR@endspacerightbrace{\detokenize\expandafter{\LWR@endspacerightbrace}}
\edef\LWR@endrightbrace{end\LWRrightbrace}
\edef\LWR@endrightbrace{\detokenize\expandafter{\LWR@endrightbrace}}

\newrobustcmd{\LWR@HTMLsanitizeexpand}[1]{%
```

Cancel French babel character handling, and fully expand the strings:

```
    \begingroup%
    \LWR@hook@processingtags%
```

The difference between this and `\LWR@HTMLsanitize` (without "expand") is the following `\expandafter`:

```
    \edef\LWR@strresult{\detokenize\expandafter{#1}}%
```

The math expression may includes spaces between tokens, but MathJax does not want a space between `\begin` or `\end` and the following brace. This space is removed here.

```
    \protect\StrSubstitute{\LWR@strresult}%
        {\LWR@beginspaceleftbrace}{\LWR@beginleftbrace}[\LWR@strresult]%
    \protect\StrSubstitute{\LWR@strresult}%
        {\LWR@endspacerightbrace}{\LWR@endrightbrace}[\LWR@strresult]%

    \LWR@subHTMLsanitize%
    \LWR@strresult%
    \endgroup%
}
```

## 62.2 Customizing MathJax

\LWR@customizedMathJax Additional MathJax definitions to be added to the start of each HTML page.

```
\newcommand*{\LWR@customizedMathJax}{}
```

Bool \LWR@warnedcustomizemathjax Used to issue only one warning about using a `\CustomizeMathJax` per macro.

```
\newbool{LWR@warnedcustomizemathjax}
\boolfalse{LWR@warnedcustomizemathjax}
```

`\LWR@subcustomizedmathjax` {⟨*macro definition*⟩}

```
\newcommand*{\LWR@subcustomizedmathjax}[1]{%
    \begingroup%
    \LWR@hook@processingtags%
    \edef\LWR@strresult{\detokenize{#1}}%
    \LWR@subHTMLsanitize%
    \xdef\LWR@customizedMathJax{%
        \LWR@customizedMathJax%
            \LWR@strresult%
    }%
    \endgroup%
}
\@onlypreamble\LWR@subcustomizedmathjax
```

`\CustomizeMathJax` {⟨*macro definition*⟩}

A warning is issued if a very long argument is given.

```
\newcommand*{\CustomizeMathJax}[1]{%
    \ifbool{LWR@warnedcustomizemathjax}{}{%
        \StrLen{\detokenize{#1}}[\LWR@tempone]%
        \ifnumgreater{\LWR@tempone}{350}{%
            \AtEndDocument{%
                \PackageWarningNoLine{lwarp}{%
                  To ensure faster MathJax compilation, place each\MessageBreak
                custom macro in its own \protect\CustomizeMathJax.\MessageBreak
                 See the Lwarp documentation regarding customizing\MessageBreak
                    MathJax%
                }%
            }%
            \booltrue{LWR@warnedcustomizemathjax}%
        }{}%
    }%
    \appto\LWR@customizedMathJax{\LWRbackslash(}%
    \LWR@subcustomizedmathjax{#1}%
    \appto\LWR@customizedMathJax{\LWRbackslash)\par}%
}
\@onlypreamble\CustomizeMathJax
```

`\LWR@infoprocessingmathjax` {⟨*package name*⟩}

```
\newcommand*{\LWR@infoprocessingmathjax}[1]{%
\typeout{---}
\typeout{Package lwarp: Processing MathJax customizations for #1.}
\typeout{\space\space This may take a moment.}
\typeout{---}
}
```

defaults Default customizations:

In the MathJax code, footnotes are only referenced. For equations, they are also generated in the HTML when the LaTeX math is generated inside the HTML comment. For other math

⚠ \footnotemark

environments, the \footnotemark/\footnotetext method must be used. See section 8.5.4 regarding \footnotemark.

For footnotes, \footnotename is used in most cases, however for equation the footnote is picked up from LaTeXin \LWR@doendequation.

First, \footnotename for MathJax is copied from LaTeX.

```
\providecommand{\footnotename}{footnote}

% due to warpMathJax:
\end{warpHTML}

\begin{warpMathJax}
\xdef\LWR@customizedMathJax{\LWR@customizedMathJax%
    \LWRbackslash(%
    \LWRbackslash{}newcommand%
    \{\LWRbackslash{}footnotename\}%
    \{\footnotename\}%
    \LWRbackslash)\par%
}
\end{warpMathJax}
```

\LWRfootnote is set per equation if a footnote is detected in the equation's math expression, otherwise it defaults to \footnotename.

```
\begin{warpMathJax}
\CustomizeMathJax{\def\LWRfootnote{1}}
\CustomizeMathJax{\newcommand{\footnote}[2][\LWRfootnote]{{}^{\mathrm{#1}}}}
\CustomizeMathJax{\newcommand{\footnotemark}[1][\LWRfootnote]{{}^{\mathrm{#1}}}}
```

\hspace is modified to accept and ignore a star:

```
\CustomizeMathJax{\let\LWRorighspace\hspace}
\CustomizeMathJax{\renewcommand{\hspace}{\ifstar\LWRorighspace\LWRorighspace}}
```

Various other customizations:

```
\CustomizeMathJax{\newcommand{\mathnormal}[1]{{#1}}}
\CustomizeMathJax{\newcommand\ensuremath[1]{#1}}
\CustomizeMathJax{% absorb two optional arguments
    \newcommand{\LWRframebox}[2][]{\fbox{#2}}
    \newcommand{\framebox}[1][]{\LWRframebox}
}
\CustomizeMathJax{\newcommand{\setlength}[2]{}}
\CustomizeMathJax{\newcommand{\addtolength}[2]{}}
\CustomizeMathJax{\newcommand{\setcounter}[2]{}}
\CustomizeMathJax{\newcommand{\addtocounter}[2]{}}
\CustomizeMathJax{\newcommand{\arabic}[1]{}}
\CustomizeMathJax{\newcommand{\number}[1]{}}
\CustomizeMathJax{\newcommand{\noalign}[1]{\text{#1}\notag \\}}
\CustomizeMathJax{\newcommand{\cline}[1]{}}
\CustomizeMathJax{\newcommand{\directlua}[1]{\text{(directlua)}}}
\CustomizeMathJax{\newcommand{\luatexdirectlua}[1]{\text{(directlua)}}}
```

**for HTML output:**

```
\begin{warpHTML}
```

`\LWR@createfooter` If specified, create the first or later web page footer.

```
\newcommand*{\LWR@createfooter}{%
    \ifnumless{\value{LWR@htmlseqfilenumber}}{1}{%
        \ifdefempty{\LWR@firstpagebottom}{}{%
            \LWR@htmlelement{footer}

            \LWR@firstpagebottom

            \LWR@htmlelementend{footer}
        }%
    }{%
        \ifdefempty{\LWR@pagebottom}{}{%
            \LWR@htmlelement{footer}

            \LWR@pagebottom

            \LWR@htmlelementend{footer}
        }%
    }%
}
```

`\LWR@newhtmlfile` {⟨*section name*⟩}

Finishes the current HTML page with footnotes, footer, navigation, then starts a new HTML page with an HTML comment telling where to split the page and what the new filename and CSS are, then adds navigation, side TOC, header, and starts the text body.

```
\newcommand*{\LWR@newhtmlfile}[1]{
\LWR@traceinfo{LWR@newhtmlfile}
```

At the bottom of the ending file:

```
\LWR@htmlelementclassend{section}{textbody}
\LWR@htmlelementclassend{div}{bodycontainer}
\LWR@htmlelementclassend{div}{bodyandsidetoc}

\LWR@printpendingfootnotes

```

No footer between files if EPUB:

```
\ifbool{FormatEPUB}{}{\LWR@createfooter}
```

No bottom navigation if are finishing the home page or formatting for EPUB or a word-processor.

```
\ifthenelse{\boolean{FormatEPUB}\OR\boolean{FormatWP}}
    {}
    {\ifnumcomp{\value{LWR@htmlfilenumber}}{>}{0}{\LWR@botnavigation}{}}
```

End of this HTML file:

```
\LWR@stoppars
\LWR@htmltag{/body}\LWR@orignewline
\LWR@htmltag{/html}\LWR@orignewline
\LWR@traceinfo{LWR@newhtmlfile: about to LWR@orignewpage}
\LWR@maybe@orignewpage


\addtocounter{LWR@htmlfilenumber}{1}%
\addtocounter{LWR@htmlseqfilenumber}{1}%
```

If using a filename based on section name, create a version without blanks. The filename without blanks will be placed into `\LWR@thisfilename`. Duplicates will be detected using MD5 hashes.

If not using a filename, the file number will be used instead.

```
\ifbool{FileSectionNames}%
{%
```

Convert the section name to a filename with blanks and common words removed. The resulting filename is in `\LWR@thisfilename`.

```
    \LWR@filenamenoblanks{#1}%
```

Create a macro name from the MD5 hash of the file name, to detect duplicates:

```
    \edef\LWR@hashedname{\LWR@mdfive{\LWR@thisfilename}}%
```

If the macro name is not yet defined, this filename is unique.

```
    \ifcsundef{LWR@filename\LWR@hashedname}{%
```

If the filename is unique, create a macro using the hashed name, to be used to test for additional duplicates in the future.

```
        \csdef{LWR@filename\LWR@hashedname}{}%
    }{%
```

If the filename is not unique, create an error.

```
        \PackageError{lwarp}%
            {%
                The section name:\MessageBreak
                ``#1'',\MessageBreak
                at the line number listed below,\MessageBreak
                generates the filename\MessageBreak
                ``\LWR@thisfilename'',\MessageBreak
                which appears to be a duplicate.  There is a\MessageBreak
               previous section with an identical or similar name.\MessageBreak
                While generating file names, Lwarp sanitizes math,\MessageBreak
                most symbols, and a few common short words,\MessageBreak
                and this may cause a conflict.\MessageBreak
```

```
                Enter 'H' for possible solutions%
            }%
            {%
                \LWR@avoiddupfilenames%
            }%
    }%
}%
```

If using file numbers instead of names, the name is set to the next file number.

```
{\renewcommand*{\LWR@thisfilename}{\arabic{LWR@htmlfilenumber}}}
```

Include an HTML comment to instruct lwarpmk where to split the files apart. Uses pipe-separated fields for `split_html.gawk`. Uses monospaced font with ligatures disabled for everything except the title.

```
\LWR@traceinfo{LWR@newhtmlfile: about to print start file}%
```

`\LWR@nullfonts` to allow math in a section name.

```
\begingroup%
\LWR@nullfonts%
\LWR@htmlblockcomment{%
|Start file|%
\LWR@htmlsectionfilename{\LWR@thisfilename}|%
}
\endgroup%
```

At the top of the starting file:

```
\LWR@stoppars

```

Start a new file with the given section name:

```
\LWR@filestart[#1]

```

Track the PDF page numbers of the HTML output:

```
\setcounter{LWR@latestautopage}{\value{page}}%
\LWR@newautopagelabel{LWR@latestautopage}%
```

No navigation between files if formatting for an EPUB or word processor:

```
\ifthenelse{\boolean{FormatEPUB}\OR\boolean{FormatWP}}
    {}
    {\LWR@topnavigation}

```

No header if between files if formatting for an EPUB or word processor:

```
\ifthenelse{\boolean{FormatEPUB}\OR\boolean{FormatWP}}
    {}
    {
```

```
        \ifdefempty{\LWR@pagetop}{}{
            \LWR@htmlelement{header}

            \LWR@pagetop

            \LWR@htmlelementend{header}
        }
    }

```

The container for the sidetoc and text body:

```
\LWR@htmlelementclass{div}{bodyandsidetoc}
```

No sideTOC if formatting for an EPUB or word processor:

```
\ifthenelse{\boolean{FormatEPUB}\OR\boolean{FormatWP}}
    {}
    {\LWR@sidetoc}

```

Start of the <textbody>:

```
\LWR@htmlelementclass{div}{bodycontainer}
\LWR@htmlelementclass{section}{textbody}
```

Not yet found a new section in this file. Once one is found, a label will be placed for previous/next links.

```
\boolfalse{LWR@setseqfilelabel}
```

Print title only if there is one. Skip if formatting for an EPUB or word processor:

```
\ifthenelse{\boolean{FormatEPUB}\OR\boolean{FormatWP}}%
    {}%
    {%
        \ifcsvoid{thetitle}{}{%
            \LWR@printthetitle%
        }%
    }%

```

Keep paragraph tags disabled for now:

```
\LWR@stoppars

```

If using MATHJAX, print the customizations here.

```
\LWR@customizeMathJax

\LWR@traceinfo{LWR@newhtmlfile: done}
}

\end{warpHTML}
```

# 63 Sectioning

Sectioning and cross-references have been emulated from scratch, rather than try to patch several layers of existing LaTeX code and packages. Formatting is handled by CSS, so the emulated code has much less work to do than the print versions.

Unicode

⚠ accents in filenames

Section names and the resulting filenames with accented characters are partially supported, depending on the ability of *pdflatex* to generate characters and *pdftotext* to read them. If extra symbols appear in the text, it may be that *pdflatex* is actually producing a symbol over or under a character, resulting in *pdftotext* picking up the accent symbol separately.

XeLaTeX and LuaLaTeX directly support accented section and file names, but it may be necessary to use LaTeX accents instead of native Unicode accents. LaTeX accents will have the accents stripped when creating file names, whereas using Unicode accents will create filenames which include accents, which may cause issues with some operating systems.

**for HTML output:**

```
\begin{warpHTML}
```

## 63.1 User-level starred section commands

`\ForceHTMLPage`

For HTML output, forces the next section to be on its own HTML page, if `FileDepth` allows, even if starred. For use with `\printindex` and others which generate a starred section which should be on its own HTML page. Also see `\ForceHTMLTOC`.

For print output, no effect.

```
\newbool{LWR@forcinghtmlpage}
\boolfalse{LWR@forcinghtmlpage}

\newcommand*{\ForceHTMLPage}{%
\global\booltrue{LWR@forcinghtmlpage}%
}
```

`\ForceHTMLTOC`

For HTML output, forces the next section to have a TOC entry, even if starred. For use with `\printindex` and others which generate a starred section which should be in the TOC so that it may be accessed via HTML. Not necessary if used with tocbibind. Also see `\ForceHTMLPage`.

For print output, no effect.

```
\newbool{LWR@forcinghtmltoc}
\boolfalse{LWR@forcinghtmltoc}

\newcommand*{\ForceHTMLTOC}{%
\global\booltrue{LWR@forcinghtmltoc}%
}

\end{warpHTML}
```

**for PRINT output:**

```
\begin{warpprint}
\newcommand*{\ForceHTMLPage}{}
```

```
\newcommand*{\ForceHTMLTOC}{}
\end{warpprint}
```

**for HTML output:**

```
\begin{warpHTML}
```

## 63.2 Book class commands

`\mainmatter` Declare the main matter section of the document. Does not reset the page number, which must be consecutive arabic numbers for the HTML conversion.

```
\newbool{LWR@mainmatter}
\DeclareDocumentCommand{\mainmatter}{}{%
\booltrue{LWR@mainmatter}%
}
```

`\frontmatter` Declare the front matter section of the document, using arabic numbering for the internal numbering. Does not reset the page number.

```
\DeclareDocumentCommand{\frontmatter}{}{%
\boolfalse{LWR@mainmatter}%
}
```

`\backmatter` Declare the back matter section of the document. Does not reset the page number.

```
\DeclareDocumentCommand{\backmatter}{}{%
\boolfalse{LWR@mainmatter}
}
```

## 63.3 Sectioning support macros

`\LWR@sectionumber` {⟨*section type*⟩}

Typeset a section number and its trailing space with CSS formatting:

```
\newcommand*{\LWR@sectionnumber}[1]{%
\InlineClass{sectionnumber}{#1}%
}
```

`autosec` A tag used by the TOC and index.

`\LWR@createautosec` {⟨*section type*⟩}

Create an autosection tag.

The use of `\textquotedbl` instead of " provides improved compatibility with xeCJK.

```
\newcommand*{\LWR@createautosec}[1]{%
\LWR@htmltag{%
    #1 % space
```

```
7164     id=\textquotedbl\LWR@print@mbox{autosec-\arabic{page}}\textquotedbl%
7165 }%
7166 }
```

`\LWR@pushoneclose` {⟨*sectiontype*⟩} Stacks the new sectioning level's closing tag, to be used when this section is closed some time later.

⚠ `\LWR@stoppars` must be executed first.

7167

Start a new HTML file unless starred, and if is a shallow sectioning depth.

Exception: Also start a new HTML file for \part*, for appendix.

Generate a new LaTeX page so that TOC and index page number points to the section:

```
\LWR@traceinfo{LWR@section: testing whether to start a new HTML file}%
\IfBooleanT{#1}{\LWR@traceinfo{LWR@section: starred}}%
\ifbool{LWR@forcinghtmlpage}{\LWR@traceinfo{LWR@section: forcinghtmlpage}}{}%
\ifthenelse{%
    \(%
        \(\NOT\equal{#1}{\BooleanTrue}\)\OR%
        \(\cnttest{\@nameuse{LWR@depth#4}}{=}{\LWR@depthpart}\)\OR%
        \(\boolean{LWR@forcinghtmlpage}\)%
    \)%
    \AND%
    \cnttest{\@nameuse{LWR@depth#4}}{<=}{\value{FileDepth}}%
    \AND%
    \(%
        \NOT\boolean{CombineHigherDepths}\OR%
        \cnttest{\@nameuse{LWR@depth#4}}{<=}{\value{LWR@prevFileDepth}}%
    \)%
    \AND%

    \(% phantomsection
        \NOT\isempty{#3}%
        \OR%
        \(\NOT\equal{#1}{\BooleanTrue}\)%
    \)%
}%
```

If so: start a new HTML file:

```
{% new file
    \LWR@traceinfo{LWR@section: new HTML file}%
```

See if there was an optional TOC name entry:

```
    \IfNoValueTF{#2}%
```

If no optional entry

```
        {\LWR@newhtmlfile{#3}}%
```

If yes an optional entry

```
        {\LWR@newhtmlfile{#2}}%
}% new file
```

Else: No new HTML file:

```
{% not new file
```

Generate a new LaTeX page so that TOC and index page number points to the section:

```
    \LWR@traceinfo{LWR@section: not a new HTML file, about to LWR@orignewpage}%
    \LWR@maybe@orignewpage%
}% not new file

```

Remember this section's name for \nameref:

```
\IfValueT{#3}{%
    \LWR@traceinfo{LWR@section: about to LWR@setlatestname}%
    \IfValueTF{#2}{\LWR@setlatestname{#2}}{\LWR@setlatestname{#3}}%
}%
```

Print an opening comment with the level and the name; ex: "section" "Introduction" Footnotes may be used in section names, which would also appear in the HTML section opening comments, so the short TOC entry is used if possible, and a limited opening comment is made if the sectional unit is starred.

```
\ifbool{HTMLDebugComments}{%
    \begingroup%
    \LWR@nullfonts%
    \IfBooleanTF{#1}% starred
    {\LWR@htmlcomment{Opening #4*}}%
    {%
        \IfNoValueTF{#2}% short TOC
            {\LWR@htmlcomment{Opening #4 ``#3''}}%
            {\LWR@htmlcomment{Opening #4 ``#2''}}%
    }\LWR@orignewline%
    \endgroup%
}{}
```

For inline sections paragraph and subparagraph, start a new paragraph now:

```
\ifthenelse{%
    \cnttest{\@nameuse{LWR@depth#4}}{>=}{\LWR@depthparagraph}%
}%
    {\LWR@startpars}%
    {}%
```

Create the opening tag with an autosec:

```
\LWR@traceinfo{LWR@section: about to LWR@createautosec}%
\LWR@createautosec{\@nameuse{LWR@tag#4}}%

\setcounter{LWR@currentautosec}{\value{page}}%
```

Check if starred:

```
\IfBooleanTF{#1}%
{%
    \LWR@traceinfo{LWR@section: starred}%
```

Starred, but also forcing a TOC entry, so add unnumbered TOC name or regular name:

```
    \ifbool{LWR@forcinghtmltoc}%
```

```
    {%
        \addcontentsline{toc}{#4}{%
            \IfValueTF{#2}{\LWR@isolate{#2}}{\LWR@isolate{#3}}%
        }%
    }%
    {}%
}% starred
```

Not starred, so step counter and add to TOC:

```
{% not starred
```

Only add a numbered TOC entry if section number is not too deep:

```
    \ifthenelse{%
        \cnttest{\@nameuse{LWR@depth#4}}{<=}{\value{secnumdepth}}%
    }%
    {% if secnumdepth
```

If in the main matter, step the counter and add the TOC entry. For `article` class, lwarp assumes that all is mainmatter.

```
        \LWR@traceinfo{LWR@section: about to test main matter}%
        \ifbool{LWR@mainmatter}%
        {%
            \LWR@traceinfo{LWR@section: yes mainmatter}%
            \refstepcounter{#4}%
```

Add main matter numbered TOC entry with the TOC name or the regular name:

```
            \LWR@traceinfo{LWR@section: about to addcontentsline}%
            \addcontentsline{toc}{#4}%
            {%
                \protect\numberline{%
                    \@nameuse{pre#4name}%
                    \@nameuse{the#4}%
                    \@nameuse{post#4name}%
                }%
                {%
                    \ignorespaces%
              \IfValueTF{#2}{\LWR@isolate{#2}}{\LWR@isolate{#3}}\protect\relax%
                }%
            }%
            \LWR@traceinfo{LWR@section: finished addcontentsline}%
        }% end of if main matter
```

If not main matter, add unnumbered TOC name or regular name:

```
        {% not main matter
            \LWR@traceinfo{LWR@section: no main matter}%
            \addcontentsline{toc}{#4}{%
                \IfValueTF{#2}{\LWR@isolate{#2}}{\LWR@isolate{#3}}%
            }%
        }% end of not main matter
    }% end of secnumdepth
```

Deeper than secnumdepth, so add an unnumbered TOC entry:

```
    {%
        \addcontentsline{toc}{#4}{%
            \IfValueTF{#2}{\LWR@isolate{#2}}{\LWR@isolate{#3}}%
        }%
    }%
```

For part, print “Part”:

```
    \ifbool{LWR@mainmatter}%
    {%
        \ifthenelse{%
            \(\cnttest{\@nameuse{LWR@depth#4}}{<=}%
                {\value{secnumdepth}}\) \AND%
            \(\cnttest{\@nameuse{LWR@depth#4}}{=}{\LWR@depthpart}\)%
        }%
            {\@partnameformat}%
            {}%
```

Print the section number:

```
        \LWR@traceinfo{LWR@section: about to print section number}%
        \ifthenelse{%
            \cnttest{\@nameuse{LWR@depth#4}}{<=}{\value{secnumdepth}}%
        }%
            {%
                \ifstrequal{#4}{part}%
                {\protect\LWR@sectionnumber{\@partcntformat{#4}}}%
                {%
                    \ifstrequal{#4}{chapter}%
                        {%

                            \LWR@printchaptername%
                            \protect\LWR@sectionnumber{\@chapcntformat{#4}}%
                        }%
                        {\protect\LWR@sectionnumber{\@seccntformat{#4}}}%
                }%
            }%
            {}%
        \LWR@traceinfo{LWR@section: finished print section number}%
    }{}%
}% not starred
```

Print the section name:

```
\LWR@traceinfo{LWR@section: about to print the section name}%
\LWR@isolate{#3}%
```

Close the heading tag, such as /H2:

```
\LWR@traceinfo{LWR@section: about to close the heading tag}%
\LWR@htmltag{\@nameuse{LWR@tag#4end}}%
\LWR@orignewline%
```

Generate a LaTeX label.

Track the PDF page numbers of the HTML output.

```
\LWR@traceinfo{LWR@section: about to create the LaTeX label}%
\setcounter{LWR@latestautopage}{\value{page}}%
\LWR@newautopagelabel{LWR@currentautosec}\LWR@orignewline%
```

If this is the first section found in this file, create a label for prevous/next links:

```
\ifbool{LWR@setseqfilelabel}{}{%
    \label{\BaseJobname-autofile-\arabic{LWR@htmlseqfilenumber}}%
    \booltrue{LWR@setseqfilelabel}%
}%
```

Start paragraph handing unless is an inline paragraph or subparagraph:

```
\ifthenelse{%
    \cnttest{\@nameuse{LWR@depth#4}}{<}{\LWR@depthparagraph}%
}%
    {\LWR@startpars}%
    {}%
```

If not starred, remember the previous depth to possibly trigger a new HTML page.

HOWEVER, allow a `\part*` to start a new HTML page. This is used by appendix.

A starred section does not trigger a new HTML page at the beginning of this macro, so it should not affect it here at the end either. This became an issue when a `\listoftables` was tested in the middle of the document. The `\chapter*` for the list was not allowing a new HTML page for the section following it while `CombineHigherDepths` was true.

```
\ifthenelse{%
    \NOT\equal{#1}{\BooleanTrue}\OR%
    \cnttest{\@nameuse{LWR@depth#4}}{=}{\LWR@depthpart}%
}%
    {% not starred
        \setcounter{LWR@prevFileDepth}{\@nameuse{LWR@depth#4}}%
    }% not starred
    {}%
```

Reset to defaults if not a phantomsection:

```
\ifstrempty{#3}%
    {}%
    {%
        \global\boolfalse{LWR@forcinghtmlpage}%
        \global\boolfalse{LWR@forcinghtmltoc}%
    }%
%
\LWR@traceinfo{LWR@section: done}%
}
```

## 63.4 Pre- and post- sectioning names

\prebookname
\postbookname

Usually null, but is used by uj* and ut* Japanese classes.

```
\providecommand*{\prebookname}{}
\providecommand*{\postbookname}{}
```

\prepartname
\postpartname

Usually null, but is used by uj* and ut* Japanese classes.

```
\providecommand*{\prepartname}{}
\providecommand*{\postpartname}{}
```

\prechaptername
\postchaptername

Usually null, but is used by uj* and ut* Japanese classes.

```
\providecommand*{\prechaptername}{}
\providecommand*{\postchaptername}{}
```

\presectionname
\postsectionname

Always null, but provided here for algorithmic simplicity in \LWR@section.

```
\providecommand*{\presectionname}{}
\let\postsectionname\presectionname

\let\presubsectionname\presectionname
\let\postsubsectionname\postsectionname

\let\presubsubsectionname\presectionname
\let\postsubsubsectionname\postsectionname

\let\preparagraphname\presectionname
\let\postparagraphname\postsectionname

\let\presubparagraphname\presectionname
\let\postsubparagraphname\postsectionname
```

## 63.5 \section and friends

For memoir, a second optional argument is allowed.

For hypbmsec, a second optional argument or either parenthesis argument is allowed.

Each of these additional arguments are for headers or PDF bookmarks, and are ignored for HTML output.

\part * (⟨2:PDF name⟩) [⟨3:TOC name⟩] [⟨4:PDF name⟩] (⟨5:PDF name⟩) {⟨6:name⟩}

```
\newcommand{\part@preamble}{}% for koma-script

\DeclareDocumentCommand{\part}{s d() o o d() m}{%
    \LWR@section{#1}{#3}{#6}{part}%

```

```
7390     \part@preamble% for koma-script
7391     \renewcommand{\part@preamble}{}%
7392 }
```

\chapter * (⟨2:PDF name⟩) [⟨3:TOC name⟩] [⟨4:PDF name⟩] (⟨5:PDF name⟩) {⟨6:name⟩}

```
7393 \let\@printcites\relax% for quotchap package
7394
7395 \newcommand{\chapter@preamble}{}% for koma-script
7396
7397 \@ifundefined{chapter}
7398 {}
7399 {%
7400     \DeclareDocumentCommand{\chapter}{s d() o o d() m}{%
7401         \LWR@section{#1}{#3}{#6}{chapter}%
7402
7403         \@printcites% for quotchap package
7404
7405         \chapter@preamble% for koma-script
7406         \renewcommand{\chapter@preamble}{}%
7407     }
7408 }
```

\section * (⟨2:PDF name⟩) [⟨3:TOC name⟩] [⟨4:PDF name⟩] (⟨5:PDF name⟩) {⟨6:name⟩}

```
7409 \DeclareDocumentCommand{\section}{s d() o o d() m}{%
7410     \LWR@section{#1}{#3}{#6}{section}%
7411 }
```

\subsection * (⟨2:PDF name⟩) [⟨3:TOC name⟩] [⟨4:PDF name⟩] (⟨5:PDF name⟩) {⟨6:name⟩}

```
7412 \DeclareDocumentCommand{\subsection}{s d() o o d() m}{%
7413     \LWR@section{#1}{#3}{#6}{subsection}%
7414 }
```

\subsubsection * (⟨2:PDF name⟩) [⟨3:TOC name⟩] [⟨4:PDF name⟩] (⟨5:PDF name⟩) {⟨6:name⟩}

```
7415 \DeclareDocumentCommand{\subsubsection}{s d() o o d() m}{%
7416     \LWR@section{#1}{#3}{#6}{subsubsection}%
7417 }
```

\paragraph * (⟨2:PDF name⟩) [⟨3:TOC name⟩] [⟨4:PDF name⟩] (⟨5:PDF name⟩) {⟨6:name⟩}

```
7418 \DeclareDocumentCommand{\paragraph}{s d() o o d() m}{%
7419     \LWR@section{#1}{#3}{#6}{paragraph}%
7420 }
```

\subparagraph * (⟨2:PDF name⟩) [⟨3:TOC name⟩] [⟨4:PDF name⟩] (⟨5:PDF name⟩) {⟨6:name⟩}

```
7421 \DeclareDocumentCommand{\subparagraph}{s d() o o d() m}{%
7422     \LWR@section{#1}{#3}{#6}{subparagraph}%
7423 }
```

```
\end{warpHTML}
```

# 64 Starting a new file

**for HTML & PRINT:**

```
\begin{warpall}
```

`\HTMLLanguage` Default language for the HTML `lang` tag.

```
\newcommand*{\LWR@currentHTMLLanguage}{en-US}

\newcommand*{\HTMLLanguage}[1]{%
    \renewcommand*{\LWR@currentHTMLLanguage}{#1}%
}
```

`\theHTMLTitleSeparator` May be used inside `\theHTMLTitleSection` to separate the website's overall HTML title and the particular page's section name.

```
\ifPDFTeX% pdflatex or dvi latex
    \ifdefstring{\inputencodingname}{utf8}{%
        \newcommand*{\theHTMLTitleSeparator}{ —\ }% EMdash
    }{%
        \newcommand*{\theHTMLTitleSeparator}{ -\ }% hyphen
    }%
\else%
    \ifpTeX
        \newcommand*{\theHTMLTitleSeparator}{ -\ }% hyphen
    \else
        \newcommand*{\theHTMLTitleSeparator}{ —\ }% EMdash
    \fi%
\fi%
```

`\HTMLTitleBeforeSection` Sets the HTML page's meta `title` tag to show the website title before the section name.

```
\newcommand*{\HTMLTitleBeforeSection}{%
    \def\theHTMLTitleSection{%
        \theHTMLTitle\theHTMLTitleSeparator\theHTMLSection%
    }%
}
```

`\HTMLTitleAfterSection` Sets the HTML page's meta `title` tag to show the section name before the website title.

```
\newcommand*{\HTMLTitleAfterSection}{%
    \def\theHTMLTitleSection{%
        \theHTMLSection\theHTMLTitleSeparator\theHTMLTitle%
    }%
}
```

`\theHTMLTitleSection` Forms the HTML page's meta `title` tag. The default is to show the website title before the section name.

```
\HTMLTitleBeforeSection
```

\theHTMLSection The section name is passed to \LWR@filestart, which then sets \theHTMLSection for use inside \theHTMLTitleSection to create an HTML meta title tag.

```
\newcommand*{\theHTMLSection}{}
\end{warpall}
```

**for HTML output:**

```
\begin{warpHTML}
```

\LWR@filestart [⟨*section name*⟩] Creates the opening HTML tags.

```
\newcommand*{\LWR@filestart}[1][]{%
\LWR@traceinfo{LWR@filestart !#1!}%
```

Locally temporarily disable direct-formatting commands:

```
\begingroup%
\LWR@nullfonts%
```

Save the section name for use while creating the HTML meta title tag:

```
\edef\theHTMLSection{#1}%
```

Remove extra material:

```
\StrSubstitute{\theHTMLSection}{\protect}{\detokenize{-}}[\theHTMLSection]
\StrSubstitute{\theHTMLSection}{\detokenize{-----}}{\detokenize{-}}[\theHTMLSection]
\StrSubstitute{\theHTMLSection}{\detokenize{----}}{\detokenize{-}}[\theHTMLSection]
\StrSubstitute{\theHTMLSection}{\detokenize{---}}{\detokenize{-}}[\theHTMLSection]
\StrSubstitute{\theHTMLSection}{\detokenize{--}}{\detokenize{-}}[\theHTMLSection]
```

If starts with a dash, remove the leading dash:

```
\IfBeginWith{\theHTMLSection}{\detokenize{-}}{%
    \StrGobbleLeft{\theHTMLSection}{1}[\theHTMLSection]%
}{}%
```

Create the page's HTML header:

```
\LWR@htmltag{!DOCTYPE html}\LWR@orignewline
```

The language is user-adjustable:

NOTE: \LWR@orig@textquotedbl is used here because \textquotedbl is nullified by \LWR@nullfonts while starting the new file.

```
\LWR@htmltag{%
  html lang=\LWR@orig@textquotedbl\LWR@currentHTMLLanguage\LWR@orig@textquotedbl%
}\LWR@orignewline
```

Start of the meta data:

```
\LWR@htmltag{head}\LWR@orignewline
```

Charset is fixed at UTF-8:

```
\LWR@htmltag{%
    meta charset=\LWR@orig@textquotedbl{}UTF-8\LWR@orig@textquotedbl\ /%
}\LWR@orignewline
```

Author:

```
\ifthenelse{\equal{\theHTMLAuthor}{}}%
    {}%
    {%
        \LWR@htmltag{%
        meta name=\LWR@orig@textquotedbl{}author\LWR@orig@textquotedbl\ % space
         content=\LWR@orig@textquotedbl\theHTMLAuthor\LWR@orig@textquotedbl\ /%
        }\LWR@orignewline%
    }%
```

lwarp is the generator:

```
\LWR@htmltag{%
    meta % space
    name=\LWR@orig@textquotedbl{}generator\LWR@orig@textquotedbl\ % space
   content=\LWR@orig@textquotedbl{}LaTeX Lwarp package\LWR@orig@textquotedbl\ /%
}\LWR@orignewline%
```

If there is a description, add it now:

```
\ifdefempty{\LWR@currentHTMLDescription}{}{%
    \LWR@htmltag{%
      meta name=\LWR@orig@textquotedbl{}description\LWR@orig@textquotedbl\ % space
      content=\LWR@orig@textquotedbl\LWR@currentHTMLDescription\LWR@orig@textquotedbl\ /%
    }\LWR@orignewline
}%
```

Mobile-friendly viewport:

```
\LWR@htmltag{%
    meta % space
    name=\LWR@orig@textquotedbl{}viewport\LWR@orig@textquotedbl\ % space
   content=\LWR@orig@textquotedbl{}width=device-width, initial-scale=1.0\LWR@orig@textquotedbl\ /%
}\LWR@orignewline
```

IE patch:

```
\LWR@htmltag{!-\/-[if lt IE 9]}\LWR@orignewline
\LWR@htmltag{%
    script % space
    src=\LWR@orig@textquotedbl{}%
        http://html5shiv.googlecode.com/svn/trunk/html5.js%
    \LWR@orig@textquotedbl%
}%
\LWR@htmltag{/script}\LWR@orignewline
\LWR@htmltag{![endif]-\/-}\LWR@orignewline
```

The page's title, if there is one. A section name is also added if given.

```
\ifthenelse{\equal{\theHTMLTitle}{}}%
    {}%
    {%
        \LWR@htmltag{title}%
        \ifdefempty{\theHTMLSection}%
            {\theHTMLTitle}%
            {\theHTMLTitleSection}%
        \LWR@htmltag{/title}\LWR@orignewline%
    }%
```

The page's stylesheet:

```
\LWR@htmltag{%
    link % space
    rel=\LWR@orig@textquotedbl{}stylesheet\LWR@orig@textquotedbl\ % space
    type=\LWR@orig@textquotedbl{}text/css\LWR@orig@textquotedbl\ % space
    href=\LWR@orig@textquotedbl\LWR@currentcss\LWR@orig@textquotedbl\ /%
}%
\LWR@orignewline
```

Optional MathJax support. The HTML tags must be turned off during the verbatim input, and the paragraph handling which was turned on at the end of verbatim input must be immediately turned off again.

```
\ifbool{mathjax}%
{%
    \begingroup%
    \LWR@restoreoriglists%
    \boolfalse{LWR@verbtags}%

        \IfFileExists{\LWR@mathjaxfilename}%
            {\verbatiminput{\LWR@mathjaxfilename}}%
            {%
                \PackageError{lwarp}%
                    {%
                     \protect\MathJaxFilename\space specified the file\MessageBreak
                           \space\space\LWR@mathjaxfilename\MessageBreak
                           which does not exist%
                    }%
                {Specify an existing file, or remove \protect\MathJaxFilename.}%
            }%

    \booltrue{LWR@verbtags}%
    \endgroup%
    \LWR@stoppars%
}% end of mathjax
{}%
```

End of the header:

```
\LWR@htmltag{/head}\LWR@orignewline
```

```
\begingroup%
\let\LWR@orig@desc@makelabel\makelabel
\renewcommand*{\makelabel}[1]{%
    \LWR@htmltag{dt}%
    \LWR@orig@desc@makelabel{#1}%
    \LWR@htmltag{/dt}%
}
\LWR@select@html@nohspace%
\LWR@origitem[#1]%
\endgroup%
\LWR@orignewline%
\LWR@htmltag{dd}%
\LWR@startpars%
}
```

Env `description` [⟨*options*⟩]

```
\newcommand*{\LWR@descriptionstart}{%
\renewcommand*{\LWR@printcloselist}{\LWR@printclosedescription}
\renewcommand*{\LWR@printopenlist}{dl}
\let\item\LWR@descitem%
\LWR@nulllistfills%
}
```

## 73.5 Patching the lists

`\LWR@patchlists` Patches list environments.

`\LWR@patchlists` remembers `\item` as defined by whatever packages have been loaded, then patches the `itemize`, `enumerate`, and `description` environments and `\item`. This works with the native LaTeX environments, as well as those provided by enumitem, enumerate, and paralist.

```
\newcommand*{\LWR@patchlists}{%
    \LetLtxMacro\item\LWR@listitem%
    \LetLtxMacro\@item\LWR@HTML@item%
    \renewcommand*{\@trivlist}{%
        \LWR@traceinfo{@trivlist start}%
        \LWR@liststart%
        \LWR@orig@trivlist%
        \LWR@traceinfo{@trivlist done}%
    }%
    \renewcommand*{\trivlist}{%
        \LWR@traceinfo{trivlist}%
        \LWR@origtrivlist%
    }%
    \renewcommand*{\endtrivlist}{%
        \LWR@traceinfo{endtrivlist start}%
        \LWR@origendtrivlist\LWR@listend%
        \LWR@traceinfo{endtrivlist done}%
    }%
    \renewcommand*{\itemize}{%
        \LWR@itemizestart\LWR@origitemize%
```

```
    }%
    \renewcommand*{\enumerate}{%
        \LWR@enumeratestart\LWR@origenumerate%
    }%
    \renewcommand*{\description}{%
        \LWR@descriptionstart\LWR@origdescription%
    }%
}
```

`\LWR@restoreoriglists` Restores the original `trivlist` environment.

```
\newcommand*{\LWR@restoreoriglists}{%
    \LWR@traceinfo{LWR@restoreoriglists}%
    \LetLtxMacro\item\LWR@origitem%
    \LetLtxMacro\@item\LWR@orig@item%
    \let\@trivlist\LWR@orig@trivlist%
    \let\trivlist\LWR@origtrivlist%
    \let\endtrivlist\LWR@origendtrivlist%
    \LetLtxMacro\itemize\LWR@origitemize%
    \LetLtxMacro\enditemize\LWR@endorigitemize%
    \LetLtxMacro\enumerate\LWR@origenumerate%
    \LetLtxMacro\endenumerate\LWR@endorigenumerate%
    \LetLtxMacro\description\LWR@origdescription%
    \LetLtxMacro\enddescription\LWR@endorigdescription%
    \let\@mklab\LWR@orig@mklab%
    \let\makelabel\LWR@origmakelabel%
    \let\@donoparitem\LWR@orig@donoparitem%
    \let\@nbitem\LWR@orig@nbitem%
}

\end{warpHTML}
```

# 74 Tabular

This is arguably the most complicated part of the entire package. Numerous tricks are employed to handle the syntax of the LaTeX core and the various tabular-related packages.

## 74.1 Limitations

Tabular mostly works as expected, but pay special attention to the following, especially if working with environments, macros inside tabulars, multirows, siunitx `S` columns, or the packages multirow, longtable, supertabular, or xtab.

**Defining macros and environments:**

⚠ Misplaced alignment tab character &

- When defining environments or macros which include `tabular` and instances of the & character, it may be necessary to make & active before the environment or macro is defined, then restore & to its default catcode after, using the following commands. These are are ignored in print mode.

@ and !
- Only one each of `@` and `!` is used at each column, and they are used in that order.

\multirow
- In `\multirow` cells, the print version may have extra instances of `<`, `>`, `@`, and `!` cells on the second and later rows in the `\multirow` which do not appear in the HTML version.

⚠ \newcolumntype
- `\newcolumntype` is ignored; unknown column types are set to `l`.

**Rules:**

- Doubled `\hlines`, `\midrules`, and vertical rules are supported.

vertical rules
- Vertical rules next to either side of an `@` or `!` column are displayed on both sides of the column.

width and trim
- Width options are honored. Trim options are converted to rounded top corners. Trim corners are not rounded with `@` or `!` columns, and full-width rules ignore trim. When given an optional width, each cell is styled to create the custom border. Without an optional width, the entire row is given a class to assign the standard border.

combined rules
- If you wish to use `\cmidrule` followed by `\bottomrule`, it may be necessary to use:
```
\cmidrule{2-3} \\[-2ex]
\bottomrule
```
The optional `-2ex` is ignored in HTML, but improves the visual formatting in the print output.

⚠ \warpprintonly
⚠ Misplaced \noalign
- For `\toprule` and `\bottomrule`, when combined with a `warpprint` or `warpHTML` environment, if a "Misplaced `\noalign`" error occurs, change
```
This & That \endhead
```
to
```
\warpprintonly{This & That \endhead}
```
and likewise with the other `\end` headings. Keep the `\endfirsthead` row unchanged, as it is still relevent to HTML output.

**Other:**

- tabularx ignores the width, but `X` columns do produce paragraph columns or multicolumns.

longtable headings
- For longtable, place headings and footings which do not apply to HTML inside `\warpprintonly{}`.

⚠ S columns
- For S columns (from the siunitx package), while producing print output, anything non-numeric must be placed inside { } braces, including commands such as `\multirow`. While producing HTML output, though, anything placed inside braces is not seen by lwarp's tabular handling algorithm. To resolve this problem, make a copy of the row, with one version for print output, containing the extra braces, and another version for HTML output, without the extra braces, such as:
```
\warpprintonly{1 & 2 & {\multirow{2}{2cm}{Text}} & 3 \\}
\warpHTMLonly{1 & 2 & \multirow{2}{2cm}{Text} & 3 \\}
```

⚠ tabular inside a 
- In LaTeX, a `tabular` may be placed inside a `minipage`, but in HTML a `<table>` may not be inside a `<span>`. If this situation is detected, a warning is printed instructing the user to isolate the `<span>` using `\warpprintonly` or the `warpprint` environment.

**for HTML output:**
```
\begin{warpHTML}
```

## 74.2 Temporary package-related macros

These macros are temporary placeholders for macros defined by various packages. If the relevent package is not loaded, these placeholders are used instead.

### 74.2.1 arydshln

Emualated by the original LaTeX non-dashed versions.

```
\LetLtxMacro\hdashline\hline
\LetLtxMacro\cdashline\cline
\LetLtxMacro\firsthdashline\hline
\LetLtxMacro\lasthdashline\hline
```

## 74.3 Token lookahead

Used by `\LWR@futurenonspacelet` to look at the next token.

`\LWR@mynexttoken`

```
\newcommand\LWR@mynexttoken\relax
```

`\futurelet` copies the next token then executes a function to analyze it.

`\LWR@futurenonspacelet` does the same, but ignores intervening white space

Based on the booktabs style:

`\LWR@futurenonspacelet`

```
\def\LWR@futurenonspacelet#1{\def\LWR@cs{#1}%
\afterassignment\LWR@fnslone\let\nexttoken= }

\def\LWR@fnslone{\expandafter\futurelet\LWR@cs\LWR@fnsltwo}

\def\LWR@fnsltwo{%
\expandafter\ifx\LWR@cs\@sptoken\let\next=\LWR@fnslthree%
\else\let\next=\nexttoken\fi\next}

\def\LWR@fnslthree{\afterassignment\LWR@fnslone\let\next= }
```

`\LWR@getmynexttoken` Looks ahead and copies the next token into `\LWR@mynexttoken`.

```
\newcommand*{\LWR@getmynexttoken}{%
    \LWR@traceinfo{LWR@getmynexttoken}%
% nothing must follow this next line
    \LWR@futurenonspacelet\LWR@mynexttoken\LWR@tabledatacolumntag
}
```

## 74.4 Tabular variables

In order to support nested tabulars, each of these is used locally. For local counters, etoolbox's \defcounter and lwarp's new \defaddtocounter are used.

Bool LWR@startedrow — True if should print a row tag before this column.

```
\newbool{LWR@startedrow}
\boolfalse{LWR@startedrow}
```

Bool LWR@tabularcelladded — True if have added a data cell for this position.

```
\newbool{LWR@tabularcelladded}
\boolfalse{LWR@tabularcelladded}
```

Ctr LWR@hlines — Number of \hlines or \midrules above the next row.

```
\newcounter{LWR@hlines}
```

Ctr LWR@hdashedlines — Number of arydshln dashed lines above the next row.

```
\newcounter{LWR@hdashedlines}
```

Bool LWR@doingtbrule — True if the next row will have a top/bottom rule above it.

```
\newbool{LWR@doingtbrule}
\boolfalse{LWR@doingtbrule}
```

Bool LWR@doingcmidrule — True if the next row will have a cmidrule above it.

This is used by \LWR@tabularfinishrow to force a final empty row to create the border for the \cmidrule.

```
\newbool{LWR@doingcmidrule}
\boolfalse{LWR@doingcmidrule}
```

Bool LWR@tableparcell — True if are handling a paragraph inside a table cell, so must close the paragraph tag before moving on.

```
\newbool{LWR@tableparcell}
```

Bool LWR@skippingmrowcell — True if are doing an empty \multirow cell, and thus there is no data tag to close.

```
\newbool{LWR@skippingmrowcell}
```

Bool LWR@skippingmcolrowcell — True if are doing an empty \multicolumnrow cell, and thus there is no data tag to close, and do not print @ and ! columns.

```
\newbool{LWR@skippingmcolrowcell}
```

Bool LWR@usedmultirow — Used to error if used \multirow or \multicolumnrow without using \mrowcell or \mcolrowcell.

```
\newbool{LWR@usedmultirow}
```

Bool LWR@foundmrowcell Used to error if used \multirow or \multicolumnrow without using \mrowcell or \mcolrowcell.

```
\newbool{LWR@foundmrowcell}
```

Bool LWR@skipatbang True if just finished a \multicolumn so should not create the trailing @ or ! columns table data cells.

```
\newbool{LWR@skipatbang}
```

Bool LWR@emptyatbang True if finishing a row and should print empty @ or ! column table data cells.

```
\newbool{LWR@emptyatbang}
```

Bool LWR@intabularmetadata True if are in a tabular but not in a data cell. Used to prevent extra HTML breaks if not inside table data.

```
\newbool{LWR@intabularmetadata}
\boolfalse{LWR@intabularmetadata}
```

Bool LWR@exitingtabular When \end is found, turns off the next opening data tag.

```
\newbool{LWR@exitingtabular}
```

Bool LWR@tabularmutemods Mutes HTML output for @, !, < and >.

This is used while printing the final row to generate \bottomrules.

```
\newbool{LWR@tabularmutemods}
```

Bool LWR@validtablecol True if found a valid table column type.

```
\newbool{LWR@validtablecol}
```

Bool LWR@opttablecol True if found a table column optional argument.

```
\newbool{LWR@opttablecol}
```

Used to add a style to a table data cell:

```
\newbool{LWR@tdhavecellstyle}
```

Ctr LWR@tabularDepth Tracks whether & is being used inside a tabular.

```
\newcounter{LWR@tabulardepth}
\setcounter{LWR@tabulardepth}{0}
```

Ctr LWR@tabularpardepth Tracks whether should look ahead at the next token when encountering a \par while processing tabular contents.

When LWR@tabularpardepth is deeper than LWR@tabulardepth then lwarp has started looking at the contents of the tabular, and thus any \pars encountered must be followed by another token lookahead.

```
\newcounter{LWR@tabularpardepth}
\setcounter{LWR@tabularpardepth}{0}

\newcommand*{\LWR@colsresult}{}%temp storage for column format results
\newcommand*{\LWR@pposition}{}
\newcommand*{\LWR@pleft}{}
\newcommand*{\LWR@pright}{}
```

`LWR@tablecolspec` Holds the parsed column specification, of total width `LWR@tabletotalLaTeXcols`, not counting `@` and `!` columns.

Will contain a string such as `llrrccpc`, exactly one letter per LaTeX table column, without `@`, `!`, `>`, `<`, or the vertical bar.

`\LWR@strresult` Holds the result of `Str` functions.

```
\providecommand*{\LWR@strresult}{}
\providecommand*{\LWR@strresulttwo}{}
```

`\LWR@origcolspec` Holds the original column specs given to `tabular`.

```
\newcommand*{\LWR@origcolspec}{}
```

Ctr `LWR@tablecolspecwidth` Holds the number of tokens in the table columns specification.

This is includes one for each `@`, `!`, `<`, `>` column, and also one for each of the parameters of `p`, `@`, `!`, `<`, `>` columns, and three for each `D` column.

(This is not the total # of LaTeX columns in the table.)

```
\newcounter{LWR@tablecolspecwidth}
```

Ctr `LWR@tablecolspecindex` While parsing the LaTeX table column specification, starts at 1 and is incremented per token of the specification.

```
\newcounter{LWR@tablecolspecindex}
```

Ctr `LWR@tableLaTeXcolindex` While producing the table, resets to 1 at the start of the table and also at each end of line, and is incremented by 1 by each ampersand.

```
\newcounter{LWR@tableLaTeXcolindex}
```

Ctr `LWR@tabletotalLaTeXcols` While parsing a table column specification, begins at 0 and increments by 1 per LaTeX table column. Eventually holds the final number of LaTeX table columns in each row, not counting `@` and `!` columns. (In HTML, `@` and `!` cells become their own columns, but are not included in `LWR@tabletotalLaTeXcols`.)

```
\newcounter{LWR@tabletotalLaTeXcols}
```

Ctr `LWR@tabletotalLaTeXcolsnext` Holds the next LaTeX table column index while parsing, equal to one more than `LWR@tabletotalLaTeXcols`.

```
\newcounter{LWR@tabletotalLaTeXcolsnext}
```

LWR@colatspec A data array of specifications for @ columns. The leftmost's index is leftedge, the others are counter values. See section 42.

LWR@colbangspec A data array of specifications for ! columns. The leftmost's index is leftedge, the others are counter values. See section 42.

LWR@colbeforespec A data array of specifications for > columns.

LWR@colafterspec A data array of specifications for < columns.

LWR@colbarspec A data array of specifications for vertical rules.

Ctr LWR@cellcolordepth Counts how many cell color s were added to the current tabular data cell.

```
\newcounter{LWR@cellcolordepth}
```

### 74.4.1 Multicolumn variables

```
\newcounter{LWR@tablemulticolswidth}
```

Indexes into the multicolumn specification:

```
\newcounter{LWR@tablemulticolspos}
```

Remembers multicolumn vertical rules if found in the column spec.

```
\newcounter{LWR@mcolvertbarsl}
\newcounter{LWR@mcolvertbarsr}
\newcounter{LWR@mcolvertbarsldash}
\newcounter{LWR@mcolvertbarsrdash}
\newbool{LWR@mcolvertbaronleft}
```

### 74.4.2 Longtable variables

Bool LWR@starredlongtable Per the caption package, step the counter if longtable*.

```
\newbool{LWR@starredlongtable}
\boolfalse{LWR@starredlongtable}
```

### 74.4.3 Midrule variables

Ctr LWR@midrulecounter Indexes across the LWR@midrules and LWR@trim<l/r>rules data arrays.

```
\newcounter{LWR@midrulecounter}
```

## 74.5 Handling &, @, !, and bar

For technical discussion regarding problems redefining \&, See:
http://tex.stackexchange.com/questions/11638/
where-do-i-find-futurelets-nasty-behaviour-documented/11860#11860

\LWR@instertatbangcols

```
\newcommand*{\LWR@insertatbangcols}{%
    \ifbool{LWR@skipatbang}%
    {}%
    {%
        \LWR@printatbang{at}{\arabic{LWR@tableLaTeXcolindex}}%
        \LWR@printatbang{bang}{\arabic{LWR@tableLaTeXcolindex}}%
    }%
}
```

\LWR@closetabledatacell If LWR@skippingmrowcell or LWR@skippingmcolrowcell then there is no data tag to close. Otherwise, close any paragraphs, then close the data tag.

```
\newcommand*{\LWR@closetabledatacell}{%
    \booltrue{LWR@intabularmetadata}%
    \ifbool{LWR@exitingtabular}%
    {%


        \LWR@stoppars%
    }%
    {% not exiting tabular
      \ifboolexpr{bool{LWR@skippingmrowcell} or bool{LWR@skippingmcolrowcell}}%
        {%


            \LWR@stoppars%
```

If not skipping a \multicolumnrow cell, insert the @ and ! columns after this non-existant column.

```
            \ifbool{LWR@skippingmcolrowcell}%
                {}%
                {\LWR@insertatbangcols}%
        }%
        {% not skippingmrowcell
```

Insert any < then any @ and ! column contents, unless muted for the \bottomrule or a \multicolumn:

```
            \unskip%
            \ifboolexpr{%
                bool{LWR@tabularmutemods} or
                bool{LWR@skipatbang} or
                bool{LWR@emptyatbang}
            }%
                {}%
                {%
                    \LWR@getexparray{LWR@colafterspec}%
                        {\arabic{LWR@tableLaTeXcolindex}}%
                }%
```

Close paragraphs:

```
            \LWR@stoppars%
            \boolfalse{LWR@tableparcell}%
```

Close the table data cell.

Close any color s.

```
         \whileboolexpr{test {\ifnumcomp{\value{LWR@cellcolordepth}}{>}{0}}}{%
               \LWR@htmltag{/div}\LWR@orignewline%
               \defaddtocounter{LWR@cellcolordepth}{-1}%
            }%
```

Skip the @ and ! cells if are closing a multicolumn cell.

```
            \leavevmode\unskip\LWR@htmltag{/td}\LWR@orignewline%
            \global\booltrue{LWR@tabularcelladded}%
            \LWR@insertatbangcols%
         }% not skipping mrowcell
    }% not exiting tabular
    \boolfalse{LWR@skippingmrowcell}%
    \boolfalse{LWR@skippingmcolrowcell}%
    \boolfalse{LWR@skipatbang}%
```

Color control. Column is set by >{} for each cell, so it must be cleared here.

```
    \def\LWR@cellHTMLcolor{}%
    \def\LWR@columnHTMLcolor{}%
    \defcounter{LWR@cellcolordepth}{0}%
}
```

When not used inside a tabular, & performs its original function as recorded here ( with catcode 4 ).

```
\let\LWR@origampmacro&
```

```
\end{warpHTML}
```

### 74.5.1 Handling &

**for HTML output:**

```
\begin{warpHTML}
```

& Will behave depending on whether it is being used inside tabular.

& is redefined to test whether it is inside a tabular environment, in which case it performs special processing for HTML conversion. If not, it behaves normally.

```
\newcommand*{\LWR@tabularampersand}{%
    \LWR@traceinfo{LWR@tabularampersand}%
    \ifnumcomp{\value{LWR@tabulardepth}}{>}{0}%
    {%
```

If not skipping a multirow cell, close the current data cell.

```
        \unskip%
        \LWR@closetabledatacell%
```

Move to the next column.

```
        \defaddtocounter{LWR@tableLaTeXcolindex}{1}%
```

Have not yet added data in this column:

```
        \global\boolfalse{LWR@tabularcelladded}%
```

Look at the next token to decide multi or single column data tag.

```
        \LWR@getmynexttoken%
    }%
```

If not inside a tabular, performs the original action:

```
    {%
        \LWR@origampmacro%
    }%
}
```

& is left with its original catcode for now.

tikz package seems to require & be left alone until after tikz has been loaded. Also, cleveref uses the ampersand in one of its options.

& is made active inside a `tabular`.

& is left alone when in math alignments.

### 74.5.2 Filling an unfinished row

`\LWR@tabularfinishrow` Adds empty table cells if necessary to finish the row.

At the end of the table, if any bottom rules are requested then an empty row must be generated to form the borders which show the rules.

```
\newcommand*{\LWR@tabularfinishrow}{%
```

If not exiting the tabular, or doing a rule, or have already started a row, finish this row:

```
    \ifboolexpr{%
        not bool {LWR@exitingtabular} or%
        bool{LWR@doingtbrule} or%
        bool{LWR@doingcmidrule} or%
        test{\ifnumcomp{\value{LWR@hlines}}{>}{0}} or%
        test{\ifnumcomp{\value{LWR@hdashedlines}}{>}{0}} or%
        bool{LWR@startedrow}%
    }{%
```

To temporarily turn off LWR@exitingtabular so that table data tags will still be generated:

If generating a final row for the \bottomrule borders, turn off the @, !, <, and > column output:

```
\ifbool{LWR@exitingtabular}{%
    \booltrue{LWR@tabularmutemods}%
}{%
    \boolfalse{LWR@tabularmutemods}%
}%
```

Locally reenable the table data tags until finished with the final row:

```
\boolfalse{LWR@exitingtabular}%
```

Generate table data tags and ampersands until the right edge:

```
\whileboolexpr{%
    test {
        \ifnumcomp{\value{LWR@tableLaTeXcolindex}}{<}
            {\value{LWR@tabletotalLaTeXcols}}
    } or %
    (%
        bool{LWR@intabularmetadata} and%
        not bool{LWR@tabularcelladded} and%
        test {
            \ifnumcomp{\value{LWR@tableLaTeXcolindex}}{=}
                {\value{LWR@tabletotalLaTeXcols}}
        }%
    )%
}%
{%
    \LWR@tabledatasinglecolumntag%
```

The following is essentially \LWR@tabularampersand with LWR@emptyatbang added to empty the following cells:

```
    \LWR@closetabledatacell%
    \defaddtocounter{LWR@tableLaTeXcolindex}{1}%
    \global\boolfalse{LWR@tabularcelladded}%
    \booltrue{LWR@emptyatbang}%
```

Starts the next cell:

```
    \ifnumcomp{\value{LWR@tableLaTeXcolindex}}{<}
            {\value{LWR@tabletotalLaTeXcols}}%
        {\LWR@getmynexttoken}%
        {}%
}%
```

Reenable the original LWR@exitingtabular to close the entire table:

```
\ifbool{LWR@tabularmutemods}{%
    \booltrue{LWR@exitingtabular}%
}{%
```

```
        \boolfalse{LWR@exitingtabular}%
    }%
    \boolfalse{LWR@tabularmutemods}%

    \boolfalse{LWR@emptyatbang}%
    }{}% ifboolexpr
}
```

## 74.6 Handling \\

Inside tabular, \\ is redefined to \LWR@tabularendofline

Throws away options \\[dim] or *

\LWR@tabularendofline

```
\NewDocumentCommand{\LWR@tabularendofline}{s o}{%
```

Finish the row:

```
    \ifnumcomp{\value{LWR@tableLaTeXcolindex}}{<}
            {\value{LWR@tabletotalLaTeXcols}}%
        {\LWR@tabularfinishrow}%
        {\LWR@closetabledatacell}%
    \LWR@htmltag{/tr}\LWR@orignewline%
```

xcolor row color support:

```
    \@rowc@lors%
```

No longer inside a data cell:

```
    \booltrue{LWR@intabularmetadata}%
```

Not yet started a table row:

```
    \boolfalse{LWR@startedrow}%
```

Additional setup:

```
    \defcounter{LWR@hlines}{0}%
    \defcounter{LWR@hdashedlines}{0}%
    \boolfalse{LWR@doingtbrule}%
    \boolfalse{LWR@doingcmidrule}%
    \LWR@clearmidrules%

    \def\LWR@rowHTMLcolor{}%
```

Start at first column:

```
    \defcounter{LWR@tableLaTeXcolindex}{1}%
```

Have not yet added data in this column:

```
    \global\boolfalse{LWR@tabularcelladded}%
```

Allow TEX to flush the pending paragraph. Not doing so causes a slowdown for very large tables.

```
    \LWR@stoppars%
    \LWR@origpar%
```

Look at the next token to decide between single column data tag or a special case:

```
    \LWR@getmynexttoken%
}
```

## 74.7 Looking ahead in the column specifications

`\LWR@columnspeclookahead` {⟨*offset*⟩}

Looks `offset` tokens ahead in the column specification, setting `\LWR@strresulttwo`.

The `w` column alignment will be seen as a single unit such as `{c}`.

```
\newcommand*{\LWR@columnspeclookahead}[1]{%
    \setcounter{LWR@tempcountone}{\value{LWR@tablecolspecindex}}%
    \addtocounter{LWR@tempcountone}{#1}%
    \fullexpandarg%
    \StrChar{\LWR@origcolspec}{\arabic{LWR@tempcountone}}[\LWR@strresulttwo]%
```

Get the contents of the first group in `\LWR@strresulttwo`:

```
        \exploregroups%
        \StrChar{\LWR@strresulttwo}{1}[\LWR@strresulttwo]%
        \noexploregroups%
}
```

## 74.8 Parsing @, >, <, !, bar columns

Holds the parsed argument for `@`, `>`, `<`, or `!` columns:

```
\newcommand*{\LWR@colparameter}{}
```

`\LWR@parseatcolumn` Handles `@{text}` columns.

```
\newcommand*{\LWR@parseatcolumn}{%
```

Move to the next token after the '@':

```
    \LWR@traceinfo{at column}%
    \defaddtocounter{LWR@tablecolspecindex}{1}%
```

```
        \LWR@traceinfo{at the left edge}%
        \LWR@setexparray{LWR@colbangspec}%
            {leftedge}%
            {\expandafter\@firstofone\LWR@colparameter}%
    }%
    {% not at the left edge:
        \LWR@traceinfo{not at the left edge}%
        \LWR@setexparray{LWR@colbangspec}%
            {\arabic{LWR@tabletotalLaTeXcols}}%
            {\expandafter\@firstofone\LWR@colparameter}%
      \LWR@traceinfo{bang \arabic{LWR@tabletotalLaTeXcols}: \LWR@colparameter!}%
    }%
    \let\LWR@colparameter\relax%
    \booltrue{LWR@validtablecol}%
}
```

\LWR@parsebeforecolumn Handles >{text} columns.

```
\newcommand*{\LWR@parsebeforecolumn}{%
```

Move to the next token after the '>':

```
    \defaddtocounter{LWR@tablecolspecindex}{1}%
```

Read the next token, expanding once into \LWR@colparameter:

```
    \expandarg%
    \StrChar{\LWR@origcolspec}%
        {\arabic{LWR@tablecolspecindex}}[\LWR@colparameter]%
    \fullexpandarg%
```

Store the result into a data array, expanding once out of \LWR@colparameter:

```
    \LWR@setexparray{LWR@colbeforespec}%
        {\arabic{LWR@tabletotalLaTeXcolsnext}}%
        {\expandafter\@firstofone\LWR@colparameter}%
    \let\LWR@colparameter\relax%
    \booltrue{LWR@validtablecol}%
}
```

\LWR@parseaftercolumn Handles <{text} columns.

```
\newcommand*{\LWR@parseaftercolumn}{%
```

Move to the next token after the '<':

```
    \defaddtocounter{LWR@tablecolspecindex}{1}%
```

Read the next token, expanding once into \LWR@colparameter:

```
    \expandarg%
    \StrChar{\LWR@origcolspec}%
        {\arabic{LWR@tablecolspecindex}}[\LWR@colparameter]%
    \fullexpandarg%
```

Store the result into a data array, expanding once out of \LWR@colparameter:

```
    \LWR@setexparray{LWR@colafterspec}%
        {\arabic{LWR@tabletotalLaTeXcols}}%
        {\expandafter\@firstofone\LWR@colparameter}%
    \let\LWR@colparameter\relax%
    \booltrue{LWR@validtablecol}%
}
```

\LWR@parsebarcolumn Handles vertical rules.

```
\newcommand*{\LWR@parsebarcolumn}{%
    \LWR@traceinfo{LWR@parsebarcolumn}%
```

Remember the bar at this position:

```
    \ifnumcomp{\value{LWR@tabletotalLaTeXcols}}{=}{0}%
    {% left edge of the table:
        \edef\LWR@tempone{\LWR@getexparray{LWR@colbarspec}{leftedge}}%
        \ifdefstring{\LWR@tempone}{tvertbarl}%
        {\LWR@setexparray{LWR@colbarspec}{leftedge}{tvertbarldouble}}%
        {\LWR@setexparray{LWR@colbarspec}{leftedge}{tvertbarl}}%
    }%
    {% not at the left edge:
        \edef\LWR@tempone{%
           \LWR@getexparray{LWR@colbarspec}{\arabic{LWR@tabletotalLaTeXcols}}%
        }%
        \ifdefstring{\LWR@tempone}{tvertbarr}%
        {%
            \LWR@setexparray{LWR@colbarspec}%
                {\arabic{LWR@tabletotalLaTeXcols}}{tvertbarrdouble}%
        }%
        {%
            \LWR@setexparray{LWR@colbarspec}%
                {\arabic{LWR@tabletotalLaTeXcols}}{tvertbarr}%
        }%
    }%
    \booltrue{LWR@validtablecol}%
}
```

\LWR@parsecoloncolumn Handles vertical rules.

```
\newcommand*{\LWR@parsecoloncolumn}{%
    \LWR@traceinfo{LWR@parsecoloncolumn}%
```

Remember the bar at this position:

```
    \ifnumcomp{\value{LWR@tabletotalLaTeXcols}}{=}{0}%
    {% left edge of the table:
        \edef\LWR@tempone{\LWR@getexparray{LWR@colbarspec}{leftedge}}%
        \ifdefstring{\LWR@tempone}{tvertbarldash}%
        {\LWR@setexparray{LWR@colbarspec}{leftedge}{tvertbarldoubledash}}%
        {\LWR@setexparray{LWR@colbarspec}{leftedge}{tvertbarldash}}%
```

```
    }%
    {% not at the left edge:
        \edef\LWR@tempone{%
           \LWR@getexparray{LWR@colbarspec}{\arabic{LWR@tabletotalLaTeXcols}}%
        }%
        \ifdefstring{\LWR@tempone}{tvertbarrdash}%
        {\LWR@setexparray{LWR@colbarspec}%
            {\arabic{LWR@tabletotalLaTeXcols}}{tvertbarrdoubledash}}%
        {\LWR@setexparray{LWR@colbarspec}%
            {\arabic{LWR@tabletotalLaTeXcols}}{tvertbarrdash}}%
    }%
    \booltrue{LWR@validtablecol}%
}
```

`\LWR@parsesemicoloncolumn` Handles vertical rules.

```
\newcommand*{\LWR@parsesemicoloncolumn}{%
```

Treat ; as a : column:

```
    \LWR@parsecoloncolumn%
```

Skip the following width token:

```
    \defaddtocounter{LWR@tablecolspecindex}{1}%
}
```

## 74.9 Parsing 'l', 'c', or 'r' columns

`\LWR@parsenormalcolumn` {⟨*thiscolumn*⟩}

Add to the accumulated column specs, advance counters, and pre-clear another column of at, before, and after specs.

```
\newcommand*{\LWR@parsenormalcolumn}[1]{%
    \defaddtocounter{LWR@tabletotalLaTeXcols}{1}%
    \defaddtocounter{LWR@tabletotalLaTeXcolsnext}{1}%

    \LWR@setexparray{LWR@tablecolspec}{\arabic{LWR@tabletotalLaTeXcols}}{#1}%

    \LWR@traceinfo{normal column \arabic{LWR@tabletotalLaTeXcols}: #1}%
    \LWR@setexparray{LWR@colatspec}{\arabic{LWR@tabletotalLaTeXcolsnext}}{}%
    \LWR@setexparray{LWR@colbangspec}{\arabic{LWR@tabletotalLaTeXcolsnext}}{}%
   \LWR@setexparray{LWR@colbeforespec}{\arabic{LWR@tabletotalLaTeXcolsnext}}{}%
   \LWR@setexparray{LWR@colafterspec}{\arabic{LWR@tabletotalLaTeXcolsnext}}{}%
    \LWR@setexparray{LWR@colbarspec}{\arabic{LWR@tabletotalLaTeXcolsnext}}{}%
    \booltrue{LWR@validtablecol}%
}
```

Skips the following three parameters.

```
    \defaddtocounter{LWR@tablecolspecindex}{3}%
}
```

## 74.14 Expanding the star column specifications

Ctr LWR@starcount — Internal count for duplicating star columns.

```
\newcount\LWR@starcount
```

\LWR@expcolspec — Temporary storage used to build the expanded column specifier.

```
\newcommand*{\LWR@expcolspec}{}
```

Ctr LWR@splitstarindex — Indexes into the column specifiers.

```
\newcounter{LWR@splitstarindex}
```

Ctr LWR@splitstarcopies — Number of copies.

```
\newcounter{LWR@splitstarcopies}
```

\LWR@splitstarcontents — Contents to duplicate.

```
\newcommand*{\LWR@splitstarcontents}{}
```

\expandcolspec — Expands \LWR@origcolspec for star columns.

```
\newcommand*{\expandcolspec}{%
```

Find the position of any star token.

```
    \StrPosition{\LWR@origcolspec}{*}[\LWR@tempone]%
```

Expand until no stars are found:

```
    \whileboolexpr{ test {\ifnumgreater{\LWR@tempone}{0}}}%
    {%
```

Begin with any characters to the left of the star.

```
        \setcounter{LWR@splitstarindex}{\LWR@tempone}%
        \addtocounter{LWR@splitstarindex}{-1}%
      \StrLeft{\LWR@origcolspec}{\value{LWR@splitstarindex}}[\LWR@expcolspec]%
```

Move past the star to remember its number of copies.

```
        \addtocounter{LWR@splitstarindex}{2}%
        \StrChar{\LWR@origcolspec}{\value{LWR@splitstarindex}}[\LWR@tempone]%
       \setcounter{LWR@splitstarcopies}{\expandafter\@firstofone\LWR@tempone}%
```

Move past the number of copies and remember the contents.

```
        \addtocounter{LWR@splitstarindex}{1}%
    \StrChar{\LWR@origcolspec}{\value{LWR@splitstarindex}}[\LWR@splitstarcontents]%
```

For each copy, append the contents.

```
        \ifnumgreater{\value{LWR@splitstarcopies}}{0}%
        {%
            \LWR@starcount=\value{LWR@splitstarcopies}%
            \loop
                \appto\LWR@expcolspec{%
```

(Remove the enclosing braces.)

```
                    \expandafter\@firstofone\LWR@splitstarcontents%
                }%
                \advance \LWR@starcount -1
            \ifnum \LWR@starcount>0 \repeat
        }{}%
```

Remove any token to the left, and append the rightmost remainding tokens.

```
    \StrGobbleLeft{\LWR@origcolspec}{\value{LWR@splitstarindex}}[\colspecremainder]%
        \appto{\LWR@expcolspec}{\colspecremainder}%
```

Remember the final result.

```
        \edef\LWR@origcolspec{\LWR@expcolspec}%
```

See if more stars exist.

```
        \StrPosition{\LWR@origcolspec}{*}[\LWR@tempone]%
    }%
}
```

## 74.15 Parsing the column specifications

⚠ tabular baselines

HTML CSS cannot exactly match the LaTeX concept of a baseline for a table row. Table 12 shows the LaTeX results for various vertical-alignment choices, with the baseline of the first column drawn across all the columns for comparison. See the p column specification in table 13 for details.

Table 13 describes how each kind of column is converted to HTML.

`\LWR@parsetablecols` {⟨*colspecs*⟩}

Scans the column specification left to right.

Builds `\LWR@tablecolspec` with the final specification, one LaTeX column per entry. The final number of LaTeX columns in each row is stored in `LWR@tabletotalLaTeXcols`, which

Table 12: Tabular baseline

| l | p | m | b | r |
|---|---|---|---|---|
| | | | bot | |
| | | mid | bot | |
| l | par | mid | bot | r |
| | par | mid | | |
| | par | | | |

Table 13: Tabular HTML column conversions

**l, r, c:** Converted to table cells without paragraph tags.
Uses CSS `vertical-align:middle` so that top or bottom-aligned cells may go above or below this cell.

**p:** Converted to table cells with paragraph tags. Ref: Table 12, LaTeX places the top line of a parbox aligned with the rest of the text line, so CSS `vertical-align:bottom` is used to have the HTML result appear with the paragraph extending below the L, R, C cells at the middle, if possible. This may be confusing as a P cell may not top-align with an L,R,C cell in the HTML conversion, especially in the presence of a B cell, and two P cells side-by-side will be aligned at the bottom instead of the top. Some adjustment of the CSS may be desired, changing `td.tdp`, `td.tdP`, `td.tdprule`, and `td.tdPrule` to `vertical-align: middle`. Another possibility is to change L,R,C, and P to `vertical-align: top` and not worry about the alignment of B and M cells or trying to approximate LaTeX baselines.

**m:** With paragraph tags, CSS `vertical-align:middle`.

**b:** With paragraph tags, CSS `vertical-align:top` so that the bottom of the text is closest to the middle of the text line.

**P, M, B:** Horizontally-centered versions.

**S:** Converted to 'r'. Ignores optional argument. From the siunitx package.

**D:** Converted to 'c'. From the dcolumn package.

**@, !, >, <:** One each, in that order.

**|:** Vertical rule.

**Unknown:** Converted to 'l'.

**`\newcolumn`:** Currently treated as unknown.

is the number of & and \\ in each line, but which does not include @, !, <, > specifications in the count.

```
\newcommand*{\LWR@parsetablecols}[1]{%
    \LWR@traceinfo{LWR@parsetablecols}%
```

Remember the original supplied column spec:

```
    \renewcommand*{\LWR@origcolspec}{#1}%
```

Remove spaces:

```
    \expandarg%
    \StrSubstitute{\LWR@origcolspec}{ }{}[\LWR@origcolspec]%
```

Expand any star columns:

```
    \expandcolspec%
```

The parsed column spec data array, LWR@tablecolspec, will be overwritten with new values.

Total number of columns found so far. Also pre-initialize the first several columns of specs:

```
    \defcounter{LWR@tabletotalLaTeXcols}{0}%
    \defcounter{LWR@tabletotalLaTeXcolsnext}{1}%
    \LWR@setexparray{LWR@colatspec}{leftedge}{}%
    \LWR@setexparray{LWR@colatspec}{1}{}%
    \LWR@setexparray{LWR@colatspec}{2}{}%
    \LWR@setexparray{LWR@colatspec}{3}{}%
    \LWR@setexparray{LWR@colbangspec}{leftedge}{}%
    \LWR@setexparray{LWR@colbangspec}{1}{}%
    \LWR@setexparray{LWR@colbangspec}{2}{}%
    \LWR@setexparray{LWR@colbangspec}{3}{}%
    \LWR@setexparray{LWR@colbeforespec}{1}{}%
    \LWR@setexparray{LWR@colbeforespec}{2}{}%
    \LWR@setexparray{LWR@colbeforespec}{3}{}%
    \LWR@setexparray{LWR@colafterspec}{1}{}%
    \LWR@setexparray{LWR@colafterspec}{2}{}%
    \LWR@setexparray{LWR@colafterspec}{3}{}%
    \LWR@setexparray{LWR@colbarspec}{leftedge}{}%
    \LWR@setexparray{LWR@colbarspec}{1}{}%
    \LWR@setexparray{LWR@colbarspec}{2}{}%
    \LWR@setexparray{LWR@colbarspec}{3}{}%
```

Starting at the first column specification:

```
    \defcounter{LWR@tablecolspecindex}{1}%
```

Place the colspecs string length into \LWR@strresult, and remember the number of characters in the column specification:

```
    \expandarg%
    \StrLen{\LWR@origcolspec}[\LWR@strresult]%
```

```
    \fullexpandarg%
    \LWR@traceinfo{original column spec length: \LWR@strresult}%
    \defcounter{LWR@tablecolspecwidth}{\LWR@strresult}%
```

Haven't seen any optional arguments so far

```
    \boolfalse{LWR@opttablecol}%
```

Scan through the column specifications:

```
    \whileboolexpr{%
        not test{%
            \ifnumcomp{\value{LWR@tablecolspecindex}}{>}%
                {\value{LWR@tablecolspecwidth}}%
        }%
    }%
    {%
```

Place the next single-character column type into `\LWR@strresult`:

```
    \expandarg%
   \StrChar{\LWR@origcolspec}{\arabic{LWR@tablecolspecindex}}[\LWR@strresult]%
    \LWR@traceinfo{position \arabic{LWR@tablecolspecindex}: \LWR@strresult}%
    \fullexpandarg%
```

Not yet found a valid column type:

```
    \boolfalse{LWR@validtablecol}%
```

Skip over any optional arguments, such as siunitx `S` column:

```
    \IfStrEq{\LWR@strresult}{[}{\booltrue{LWR@opttablecol}}{}%
```

Throw away anything found inside the optional argument:

```
    \ifbool{LWR@opttablecol}%
    {}% inside an optional argument
    {% not an optional tabular argument
```

Not inside an optional argument, so consider the column type:

```
    \IfStrEq{\LWR@strresult}{l}{\LWR@parsenormalcolumn{l}}{}%
    \IfStrEq{\LWR@strresult}{c}{\LWR@parsenormalcolumn{c}}{}%
    \IfStrEq{\LWR@strresult}{r}{\LWR@parsenormalcolumn{r}}{}%
    \IfStrEq{\LWR@strresult}{L}{\LWR@parsenormalcolumn{l}}{}%
    \IfStrEq{\LWR@strresult}{C}{\LWR@parsenormalcolumn{c}}{}%
    \IfStrEq{\LWR@strresult}{R}{\LWR@parsenormalcolumn{r}}{}%
    \IfStrEq{\LWR@strresult}{J}{\LWR@parsenormalcolumn{l}}{}%

    \IfStrEq{\LWR@strresult}{S}{\LWR@parsenormalcolumn{c}}{}%
    \IfStrEq{\LWR@strresult}{s}{\LWR@parsenormalcolumn{c}}{}%

    \IfStrEq{\LWR@strresult}{\detokenize{@}}{\LWR@parseatcolumn}{}%
    \IfStrEq{\LWR@strresult}{!}{\LWR@parsebangcolumn}{}%
```

```
    \IfStrEq{\LWR@strresult}{>}{\LWR@parsebeforecolumn}{}%
    \IfStrEq{\LWR@strresult}{<}{\LWR@parseaftercolumn}{}%
    \IfStrEq{\LWR@strresult}{|}{\LWR@parsebarcolumn}{}%
    \IfStrEq{\LWR@strresult}{:}{\LWR@parsecoloncolumn}{}%
    \IfStrEq{\LWR@strresult}{;}{\LWR@parsesemicoloncolumn}{}%

    \IfStrEq{\LWR@strresult}{p}{\LWR@parsepcolumn{p}}{}%
    \IfStrEq{\LWR@strresult}{m}{\LWR@parsepcolumn{m}}{}%
    \IfStrEq{\LWR@strresult}{b}{\LWR@parsepcolumn{b}}{}%


    \IfStrEq{\LWR@strresult}{w}{\LWR@parsewcolumn}{}%
    \IfStrEq{\LWR@strresult}{W}{\LWR@parsewcolumn}{}%
```

A star column:

```
    \IfStrEq{\LWR@strresult}{*}{\LWR@parsestarcolumn}{}%
```

From the dcolumn package:

```
    \IfStrEq{\LWR@strresult}{D}{\LWR@parseDcolumn{c}}{}%
```

From the tabularx package. X column has no parameter, but will be given paragraph tags.

```
    \IfStrEq{\LWR@strresult}{X}{\LWR@parsenormalcolumn{X}}{}%
```

---

Many people define centered versions "P", "M", and "B":

```
  \newcolumntype{P}[1]{>{\centering\arraybackslash}p{#1}}
```

---

```
    \IfStrEq{\LWR@strresult}{P}{\LWR@parsepcolumn{P}}{}%
    \IfStrEq{\LWR@strresult}{M}{\LWR@parsepcolumn{M}}{}%
    \IfStrEq{\LWR@strresult}{B}{\LWR@parsepcolumn{B}}{}%
```

If this column was an invalid column type, convert it to an `l` column:

```
    \ifbool{LWR@validtablecol}{}{%
        \LWR@traceinfo{invalid column type: \LWR@strresult}%
        \LWR@parsenormalcolumn{l}%
    }%
    }% not an optional column argument
```

If read the closing bracket, no longer inside the optional argument:

```
    \IfStrEq{\LWR@strresult}{]}{\boolfalse{LWR@opttablecol}}{}%
```

Move to the next character:

```
    \defaddtocounter{LWR@tablecolspecindex}{1}%
    }% whiledo
}%
```

## 74.16 colortbl and xcolor tabular color support

These macros provide a minimal emulation of some colortbl macros which might appear between table cells. If colortbl is loaded, these macros will be replaced with functional versions.

For each of the HTML colors below, the text for the HTML color is set if requested, but the macro is empty if none has been set.

`\rownum` Reserve a counter register.

```
\@ifundefined{rownum}{\newcount\rownum}{}
```

`\@rowcolors` Emulated in case xcolor is not used.

```
\newcommand*{\@rowcolors}{}
```

`\@rowc@lors` Emulated in case xcolor is not used.

```
\newcommand*{\@rowc@lors}{}
```

`\LWR@xcolorrowHTMLcolor` Emulated xcolor row color.

```
\newcommand*{\LWR@xcolorrowHTMLcolor}{}
```

`\LWR@columnHTMLcolor` HTMLstyle code for the column color.

```
\def\LWR@columnHTMLcolor{}
```

`\LWR@rowHTMLcolor` HTMLstyle code for the row color.

```
\def\LWR@rowHTMLcolor{}
```

`\LWR@cellHTMLcolor` HTMLstyle code for the cell color.

```
\def\LWR@cellHTMLcolor{}
```

`\LWR@ruleHTMLcolor` HTMLstyle code for the rule color.

```
\newcommand*{\LWR@ruleHTMLcolor}{}
```

`\rowcolor` `[`⟨*model*⟩`]` `{`⟨*color*⟩`}` `[`⟨*left overhang*⟩`]` `[`⟨*right overhang*⟩`]` Print version. The HTML version is in lwarp-colortbl. Used before starting a tabular data cell, thus `\LWR@getmynexttoken`.

```
\newcommand*{\rowcolor}{\LWR@getmynexttoken}%
```

`\arrayrulecolor` `[`⟨*model*⟩`]` `{`⟨*color*⟩`}`

\arrayrulecolornexttoken [⟨*model*⟩] {⟨*color*⟩}

Print versions for use outside and inside a `tabular`:

```
\newcommand{\arrayrulecolor}[2][named]{}
\newcommand{\arrayrulecolornexttoken}[2][named]{\LWR@getmynexttoken}
```

\doublerulesepcolor [⟨*model*⟩] {⟨*color*⟩}

\doublerulesepcolornexttoken [⟨*model*⟩] {⟨*color*⟩}

Print versions for use inside and outside a `tabular`:

```
\newcommand{\doublerulesepcolor}[2][named]{}
\newcommand{\doublerulesepcolornexttoken}[2][named]{\LWR@getmynexttoken}
```

## 74.17 Starting a new row

\LWR@maybenewtablerow If have not yet started a new table row, begin one now. Creates a new row tag, adding a class for `hline` or `tbrule` if necessary.

```
\newcommand*{\LWR@maybenewtablerow}
{%
    \ifbool{LWR@startedrow}%
    {}% started the row
    {% not started the row
```

Remember that now have started the row:

```
        \booltrue{LWR@startedrow}%
```

Create the row tag, with a class if necessary.

```
        \booltrue{LWR@intabularmetadata}%
        \ifboolexpr{%
            test{\ifnumcomp{\value{LWR@hlines}}{>}{0}} or%
            test{\ifnumcomp{\value{LWR@hdashedlines}}{>}{0}}%
        }%
        {%
            \LWR@htmltag{tr class=\textquotedbl{}hline\textquotedbl }%
            \LWR@orignewline%
        }%
        {% not doing hline
            \ifbool{LWR@doingtbrule}%
            {%
                \ifdefvoid{\LWR@ruleHTMLcolor}{%
                    \LWR@htmltag{tr class=\textquotedbl{}tbrule\textquotedbl}%
                }{%
                    \LWR@htmltag{%
                        tr class=\textquotedbl{}tbrule\textquotedbl\ % space
                        style=\textquotedbl{}border-top: 1px solid % space
                            \LWR@origpound\LWR@ruleHTMLcolor \textquotedbl{}%
```

```
                    }%
                }%
                \LWR@orignewline%
            }%
            {\LWR@htmltag{tr}\LWR@orignewline}%
        }% end of not doing hline
    }% end of not started the row
}
```

## 74.18 Printing vertical bar tags

`\LWR@printbartag` {⟨*index*⟩}

Adds to a tabular data cell an HTML class name for a left/right vertical bar.

```
\newcommand*{\LWR@printbartag}[1]{%
    \LWR@traceinfo{LWR@printbartag !#1!}%
    \ifboolexpr{bool{LWR@tabularmutemods} or bool{LWR@emptyatbang}}%
    {}% muting or empty
    {% not muting
        \edef\LWR@tempone{\LWR@getexparray{LWR@colbarspec}{#1}}%
        \ifdefempty{\LWR@tempone}{}{ \LWR@tempone}%
    }% not muting
    \LWR@traceinfo{LWR@printbartag done}%
}
```

## 74.19 Printing @ or ! tags

`\LWR@printatbang` {⟨*at — or — bang*⟩} {⟨*index*⟩}

```
\newcommand*{\LWR@printatbang}[2]{%
```

Fetch the column at or bang spec:

```
    \xdef\LWR@atbangspec{\LWR@getexparray{LWR@col#1spec}{#2}}%
    \LWR@traceinfo{atbang: #2 !\LWR@atbangspec!}%
```

Only generate if is not empty;

```
    \ifdefempty{\LWR@atbangspec}%
    {}%
    {% not empty
        \LWR@htmltag{%
            td class=\textquotedbl{}td#1%
            \LWR@subaddcmidruletrim{}{}%
            \LWR@printbartag{#2}%
            \textquotedbl{}%
            \LWR@tdstartstyles%
            \LWR@addcmidrulewidth%
            \LWR@addcdashline%
            \LWR@addtabularrulecolors%
```

```
            \LWR@tdendstyles%
        }%
```

Create an empty cell if muting for the \bottomrule:

```
        \ifboolexpr{bool{LWR@tabularmutemods} or bool{LWR@emptyatbang}}%
        {}%
        {\LWR@atbangspec}%
%
        \LWR@htmltag{/td}\LWR@orignewline%
        \global\booltrue{LWR@tabularcelladded}%
    }% not empty
}%
```

\LWR@addleftmostbartag

```
\newcommand*{\LWR@addleftmostbartag}{%
    \ifnumcomp{\value{LWR@tableLaTeXcolindex}}{=}{1}{%
        \LWR@printbartag{leftedge}%
    }{}%
}
```

\LWR@tabularleftedge

```
\newcommand*{\LWR@tabularleftedge}{%
    \ifnumcomp{\value{LWR@tableLaTeXcolindex}}{=}{1}%
    {%
        \LWR@printatbang{at}{leftedge}%
        \LWR@printatbang{bang}{leftedge}%
    }% left edge
    {}% not left edge
}
```

## 74.20 Data opening tag

\LWR@thiscolspec Temporary storage.

```
\newcommand*{\LWR@thiscolspec}{}
```

\LWR@tabledatasinglecolumntag Print a table data opening tag with style for alignment and color.

```
\newcommand*{\LWR@tabledatasinglecolumntag}%
{%
    \LWR@traceinfo{LWR@tabledatasinglecolumntag}%
    \LWR@maybenewtablerow%
```

Don't start a new paragraph tag if have already started one:

```
    \ifbool{LWR@intabularmetadata}%
    {%
```

If have found the end of tabular command, do not create the next data cell:

```
        \ifbool{LWR@exitingtabular}{}%
        {% not exiting tabular
```

Print the `@` and `!` contents before first column:

```
            \LWR@tabularleftedge%
```

Fetch the current column's alignment character into `\LWR@strresult`:

```
            \xdef\LWR@strresult{%
           \LWR@getexparray{LWR@tablecolspec}{\arabic{LWR@tableLaTeXcolindex}}%
            }%
```

Print the start of a new table data cell:

```
           \LWR@traceinfo{LWR@tabledatasinglecolumntag: about to print td tag}%
            \LWR@htmltag{%
                td class=\textquotedbl{}td%
```

Append this column's spec:

```
                \LWR@strresult%
```

If this column has a cmidrule, add "rule" to the end of the HTML class tag. Also add vertical bar tags.

```
                \LWR@addcmidruletrim%
                \LWR@addleftmostbartag%
                \LWR@printbartag{\arabic{LWR@tableLaTeXcolindex}}%
                \textquotedbl{}%
```

Add styles for rules, alignment:

```
                \LWR@tdstartstyles%
                \LWR@addcmidrulewidth%
                \LWR@addcdashline%


                \xdef\LWR@thiscolspec{%
                    \LWR@getexparray{LWR@tablecolspec}%
                        {\arabic{LWR@tableLaTeXcolindex}}%
                }%
                \LWR@addformatwpalignment{\LWR@thiscolspec}%
```

Add styles for cell and rule colors:

```
                \LWR@addtabularrowcolor%
                \LWR@addtabularrulecolors%

                \LWR@tdendstyles%
            }% HTML td
           \LWR@traceinfo{LWR@tabledatasinglecolumntag: done printing td tag}%
```

If this is a p, m, b, or X column, allow paragraphs:

```
            \ifboolexpr{%
                test{ \ifdefstring{\LWR@strresult}{p} } or
                test{ \ifdefstring{\LWR@strresult}{m} } or
                test{ \ifdefstring{\LWR@strresult}{b} } or
                test{ \ifdefstring{\LWR@strresult}{P} } or
                test{ \ifdefstring{\LWR@strresult}{M} } or
                test{ \ifdefstring{\LWR@strresult}{B} } or
                test{ \ifdefstring{\LWR@strresult}{X} }
            }%
            {% allow pars
           \LWR@traceinfo{LWR@tabledatasinglecolumntag: about to LWR@startpars}%
                \booltrue{LWR@tableparcell}%
                \LWR@startpars%
           \LWR@traceinfo{LWR@tabledatasinglecolumntag: done with LWR@startpars}%
            }% allow pars
            {}% no pars
```

Print the > contents unless muted for the \bottomrule:

```
            \ifboolexpr{bool{LWR@tabularmutemods} or bool{LWR@emptyatbang}}%
            {}%
            {%
           \LWR@getexparray{LWR@colbeforespec}{\arabic{LWR@tableLaTeXcolindex}}%
            }%
            \boolfalse{LWR@intabularmetadata}%
        }% not exiting tabular
    }{}% in tabular metadata
    \LWR@traceinfo{LWR@tabledatasinglecolumntag: done}%
}%
```

## 74.21 Midrules

LWR@midrules — LWR@midrules is a data array (section 42) of columns each containing a non-zero width if a midrule should be created for this column.

LWR@trimlrules — LWR@trimlrules is a data array (section 42) of columns containing l if a midrule should be left trimmed for each column.

LWR@trimrrules — LWR@trimrrules is a data array (section 42) of columns containing r if a midrule should be right trimmed for each column.

LWR@cdashlines — LWR@cdashlines is a data array (section 42) of columns each containing a Y if an arydshln package "cdashed line" should be created for this column.

Len \LWR@heavyrulewidth — The default width of the rule.

```
\newlength{\LWR@heavyrulewidth}
\setlength{\LWR@heavyrulewidth}{.08em}
```

Len \LWR@lightrulewidth — The default width of the rule.

```
\newlength{\LWR@lightrulewidth}
```

```
\setlength{\LWR@lightrulewidth}{.05em}
```

Len `\LWR@cmidrulewidth` The default width of the rule.

```
\newlength{\LWR@cmidrulewidth}
\setlength{\LWR@cmidrulewidth}{.03em}
```

Len `\LWR@thiscmidrulewidth` The width of the next rule, defaulting to `\LWR@cmidrulewidth`.

If not `\LWR@cmidrulewidth`, a style will be used to generate the custom width.

Assigned from the `LWR@midrules` array.

```
\newlength{\LWR@thiscmidrulewidth}
\setlength{\LWR@thiscmidrulewidth}{\LWR@cmidrulewidth}
```

`\LWR@clearmidrules` Start new midrules. Called at beginning of tabular and also at `\\`.

Clears all `LWR@midrules` and `LWR@trimrules` markers for this line.

```
\newcommand*{\LWR@clearmidrules}
{%
    \defcounter{LWR@midrulecounter}{1}%
    \whileboolexpr{%
        not test{%
            \ifnumcomp{\value{LWR@midrulecounter}}{>}%
                {\value{LWR@tabletotalLaTeXcols}}%
        }%
    }%
    {%
        \LWR@setexparray{LWR@midrules}{\arabic{LWR@midrulecounter}}{0pt}%
        \setlength{\LWR@thiscmidrulewidth}{\LWR@cmidrulewidth}%
        \LWR@setexparray{LWR@trimlrules}{\arabic{LWR@midrulecounter}}{}%
        \LWR@setexparray{LWR@trimrrules}{\arabic{LWR@midrulecounter}}{}%
        \LWR@setexparray{LWR@cdashlines}{\arabic{LWR@midrulecounter}}{N}%
        \defaddtocounter{LWR@midrulecounter}{1}%
    }%
}
```

`\LWR@subcmidrule` {⟨*width*⟩} {⟨*trim*⟩} {⟨*leftcolumn*⟩} {⟨*rightcolumn*⟩}

Marks `LWR@midrules` data array elements to be non-zero widths from left to right columns. Also marks trimming for the L and/or R columns.

`LWR@doingcmidrule` is set to force an empty row at the end of the tabular to create the rule.

```
\newcommand*{\LWR@subcmidrule}[4]{%
    \defcounter{LWR@midrulecounter}{#3}%
    \whileboolexpr{%
        not test {%
            \ifnumcomp{\value{LWR@midrulecounter}}{>}{#4}%
        }%
    }%
```

```
    {%
        \LWR@setexparray{LWR@midrules}{\arabic{LWR@midrulecounter}}{#1}%
        \defaddtocounter{LWR@midrulecounter}{1}%
    }% whiledo
    \IfSubStr{#2}{l}{\LWR@setexparray{LWR@trimlrules}{#3}{l}}{}%
    \IfSubStr{#2}{r}{\LWR@setexparray{LWR@trimrrules}{#4}{r}}{}%
    \booltrue{LWR@doingcmidrule}%
}
```

`\LWR@docmidrule` `[`⟨*width*⟩`]` `(`⟨*trim*⟩`)` `{`⟨*leftcolumn-rightcolumn*⟩`}`

Marks `LWR@midrules` array elements to be a non-zero width from left to right columns. Also marks trimming for the L and/or R columns.

```
\NewDocumentCommand{\LWR@docmidrule}
    {O{\LWR@cmidrulewidth} D(){} >{\SplitArgument{1}{-}}m}
    {\LWR@subcmidrule{#1}{#2}#3}
```

`\LWR@subcdashline` `{`⟨*leftcolumn*⟩`}` `{`⟨*rightcolumn*⟩`}`

Marks `LWR@cdashlines` data array elements to be `Y` from left to right columns.

`LWR@doingcmidrule` is set to force an empty row at the end of the tabular to create the rule.

```
\newcommand*{\LWR@subcdashline}[2]{%
    \defcounter{LWR@midrulecounter}{#1}%
    \whileboolexpr{%
        not test {%
            \ifnumcomp{\value{LWR@midrulecounter}}{>}{#2}%
        }%
    }%
    {%
        \LWR@setexparray{LWR@cdashlines}{\arabic{LWR@midrulecounter}}{Y}%
        \defaddtocounter{LWR@midrulecounter}{1}%
    }% whiledo
    \booltrue{LWR@doingcmidrule}%
}
```

`\LWR@docdashline` `{`⟨*leftcolumn-rightcolumn*⟩`}`

Marks `LWR@cdashlines` data array elements to be `Y` from left to right columns.

```
\NewDocumentCommand{\LWR@docdashline}
    {>{\SplitArgument{1}{-}}m}%
    {%
        \LWR@subcdashline#1%
    }
```

`\LWR@tdstartstyles` Begins possibly adding a table data cell style.

```
\newcommand*{\LWR@tdstartstyles}{\boolfalse{LWR@tdhavecellstyle}}
```

`\LWR@tdaddstyle` Starts adding a table data cell style.

```
\newcommand*{\LWR@tdaddstyle}{%
    \ifbool{LWR@tdhavecellstyle}%
        {; }%
        { style=\textquotedbl}%
    \booltrue{LWR@tdhavecellstyle}%
}
```

`\LWR@tdendstyles` Finishes possibly adding a table data cell style. Prints the closing quote.

```
\newcommand*{\LWR@tdendstyles}{%
    \ifbool{LWR@tdhavecellstyle}%
        {%
            \textquotedbl%
            \boolfalse{LWR@tdhavecellstyle}%
        }{}%
}
```

`\LWR@subaddcmidruletrim` {⟨*lefttrim*⟩} {⟨*righttrim*⟩} Adds a `\cmidrule` with optional trim.

```
\newcommand*{\LWR@subaddcmidruletrim}[2]{%
    \setlength{\LWR@templengthone}{%
            \LWR@getexparray{LWR@midrules}{\arabic{LWR@tableLaTeXcolindex}}%
    }%
    \ifdimcomp{\LWR@templengthone}{>}{0pt}%
        {%
```

Print the class with left and right trim letters appended:

```
            \LWR@origtilde tdrule#1#2%
```

Remember the width of the rule:

```
            \setlength{\LWR@thiscmidrulewidth}{\LWR@templengthone}%
        }%
        {%
            \setlength{\LWR@thiscmidrulewidth}{0pt}%
        }%
}
```

`\LWR@addcmidruletrim` Adds left or right trim to a `\cmidrule`.

```
\newcommand*{\LWR@addcmidruletrim}{%
    \LWR@subaddcmidruletrim%
        {\LWR@getexparray{LWR@trimlrules}{\arabic{LWR@tableLaTeXcolindex}}}%
        {\LWR@getexparray{LWR@trimrrules}{\arabic{LWR@tableLaTeXcolindex}}}%
}
```

`\LWR@addrulewidth` {⟨*thiswidth*⟩} {⟨*defaultwidth*⟩}

If not default width, add a custom style with width and color depending on `thiswidth`.

Must be placed between \LWR@tdstartstyles and \LWR@tdendstyles.

```
\newcommand{\LWR@addrulewidth}[2]{%
```

Only add a custom width if thiswidth is different than the defaultwidth, or if a color is being used:

```
    \ifboolexpr{%
        test{\ifdimcomp{#1}{=}{0pt}} or
        (
            ( test{\ifdimcomp{#1}{=}{#2}} and not bool{FormatWP} )
            and ( test {\ifdefvoid{\LWR@ruleHTMLcolor}} )
        )
    }%
    {}% default width and color
    {% custom width and/or color
```

Ensure that the width is wide enough to display in the browser:

```
        \LWR@forceminwidth{#1}%
```

Begin adding another style:

```
        \LWR@tdaddstyle%
```

The style itself:

```
        border-top:\LWR@printlength{\LWR@atleastonept} solid % space
```

If default gray, the darkness of the color depends on the thickness of the rule:

```
        \ifdefvoid{\LWR@ruleHTMLcolor}{%
            \ifdimcomp{#1}{<}{\LWR@lightrulewidth}%
            {\LWR@origpound{}A0A0A0}%
            {% lightrule or heaver
                \ifdimcomp{#1}{<}{\LWR@heavyrulewidth}%
                {\LWR@origpound{}808080}%
                {black}%
            }% lightrule or heavier
        }{%
            \LWR@origpound\LWR@ruleHTMLcolor%
        }%
    }% custom width and/or color
}
```

\LWR@addcmidrulewidth Adds a style for the rule width.

Must be placed between \LWR@tdstartstyles and \LWR@tdendstyles.

```
\newcommand{\LWR@addcmidrulewidth}{%
    \LWR@addrulewidth{\LWR@thiscmidrulewidth}{\LWR@cmidrulewidth}%
}9101
```

```
                background:\LWR@origpound\LWR@xcolorrowHTMLcolor%
            }%
        }%
        {% explicit row color
            \LWR@tdaddstyle%
            background:\LWR@origpound\LWR@rowHTMLcolor%
        }%
    }%
}
```

`\LWR@addtabularhrulecolor` Adds a cell's horizontal rule color style, if needed.

```
\newcommand*{\LWR@addtabularhrulecolor}{%
```

If either form of horizontal rule is requested:

```
    \ifboolexpr{%
        test{\ifnumcomp{\value{LWR@hlines}}{>}{0}} or%
        test{\ifnumcomp{\value{LWR@hdashedlines}}{>}{0}} or%
        bool{LWR@doingtbrule}%
    }{%
```

If there is a no custom color:

```
        \ifdefvoid{\LWR@ruleHTMLcolor}%
        {%
            \ifnumcomp{\value{LWR@hlines}}{>}{1}%
            {%
                \LWR@tdaddstyle%
                border-top: 4px double%
            }{% else
            \ifnumcomp{\value{LWR@hdashedlines}}{>}{1}%
            {%
                \LWR@tdaddstyle%
                border-top: 2px dashed%
            }{% else
            \ifnumcomp{\value{LWR@hdashedlines}}{=}{1}%
            {%
                \LWR@tdaddstyle%
                border-top: 1px dashed%
            }{}}}%
```

If no color and not doubled or dashed, then add nothing, since a simpler rule is the default.

```
        }%
```

If there is a custom color:

```
        {%
            \ifnumcomp{\value{LWR@hlines}}{>}{1}%
            {%
                \LWR@tdaddstyle%
                border-top: 4px double \LWR@origpound\LWR@ruleHTMLcolor%
            }{% else
```

```
            \ifnumcomp{\value{LWR@hdashedlines}}{>}{1}%
            {%
                \LWR@tdaddstyle%
                border-top: 2px dashed \LWR@origpound\LWR@ruleHTMLcolor%
            }{% else
            \ifnumcomp{\value{LWR@hdashedlines}}{=}{1}%
            {%
                \LWR@tdaddstyle%
                border-top: 1px dashed \LWR@origpound\LWR@ruleHTMLcolor%
            }{% else
                \LWR@tdaddstyle%
                border-top: 1px solid \LWR@origpound\LWR@ruleHTMLcolor%
            }}}%
        }%
    }{}%
}
```

`\LWR@addtabularrulecolors` Adds a cell's rule color styles, if needed.

No color is added for the final row of empty cells which finishes each `tabular`.

```
\newcommand*{\LWR@addtabularrulecolors}{%
```

Custom horizonal rule color:

```
    \LWR@addtabularhrulecolor%
```

No vertical rules if finishing the `tabular` with a row of empty cells:

```
    \ifbool{LWR@tabularmutemods}{}{%
```

If at the leftmost cell, possibly add a leftmost vertical rule:

```
        \ifnumequal{\value{LWR@tableLaTeXcolindex}}{1}{%
```

Fetch the left edge's vertical bar specification:

```
            \edef\LWR@tempone{\LWR@getexparray{LWR@colbarspec}{leftedge}}%
```

Add a custom style if a vertical bar was requested:

```
            \ifdefstring{\LWR@tempone}{tvertbarl}{%
                    \LWR@tdaddstyle%
                    border-left: 1px solid % space
                        \LWR@vertruleHTMLcolor%
            }{}%
            \ifdefstring{\LWR@tempone}{tvertbarldouble}{%
                    \LWR@tdaddstyle%
                    border-left: 4px double % space
                        \LWR@vertruleHTMLcolor%
            }{}%
            \ifdefstring{\LWR@tempone}{tvertbarldash}{%
                    \LWR@tdaddstyle%
                    border-left: 1px dashed % space
```

```
                        \LWR@vertruleHTMLcolor%
            }{}%
            \ifdefstring{\LWR@tempone}{tvertbarldoubledash}{%
                    \LWR@tdaddstyle%
                    border-left: 2px dashed % space
                        \LWR@vertruleHTMLcolor%
            }{}%
        }{}%
```

Possibly add a right vertical rule for this cell:

```
        \edef\LWR@tempone{%
            \LWR@getexparray{LWR@colbarspec}{\arabic{LWR@tableLaTeXcolindex}}%
        }%
        \ifdefstring{\LWR@tempone}{tvertbarr}{%
```

Add a custom style if a vertical bar was requested:

```
                \LWR@tdaddstyle%
                border-right: 1px solid \LWR@vertruleHTMLcolor%
        }{}%
        \ifdefstring{\LWR@tempone}{tvertbarrdouble}{%
                \LWR@tdaddstyle%
                border-right: 4px double \LWR@vertruleHTMLcolor%
        }{}%
        \ifdefstring{\LWR@tempone}{tvertbarrdash}{%
                \LWR@tdaddstyle%
                border-right: 1px dashed \LWR@vertruleHTMLcolor%
        }{}%
        \ifdefstring{\LWR@tempone}{tvertbarrdoubledash}{%
                \LWR@tdaddstyle%
                border-right: 2px dashed \LWR@vertruleHTMLcolor%
        }{}%
    }%
}
```

`\LWR@subaddtabularcellcolor` {⟨*HTML color*⟩}

```
\newcommand*{\LWR@subaddtabularcellcolor}[1]{%
    \LWR@htmltag{div class=\textquotedbl{}cellcolor\textquotedbl\ % space
        style=\textquotedbl{}%
        background:\LWR@origpound{}{}#1 %
        \textquotedbl\ %
    }% space
    \defaddtocounter{LWR@cellcolordepth}{1}%
}
```

`\LWR@addtabularcellcolor` Adds a cell color style, if needed.

```
\newcommand*{\LWR@addtabularcellcolor}{%
    \ifdefvoid{\LWR@cellHTMLcolor}%
    {%
        \ifdefvoid{\LWR@rowHTMLcolor}%
        {%
```

```
            \ifdefvoid{\LWR@xcolorrowHTMLcolor}%
            {%
                \ifdefvoid{\LWR@columnHTMLcolor}%
                {}%
                {\LWR@subaddtabularcellcolor{\LWR@columnHTMLcolor}}%
            }%
            {\LWR@subaddtabularcellcolor{\LWR@xcolorrowHTMLcolor}}%
        }%
        {\LWR@subaddtabularcellcolor{\LWR@rowHTMLcolor}}%
    }%
    {\LWR@subaddtabularcellcolor{\LWR@cellHTMLcolor}}%
}
```

## 74.23 Multicolumns

### 74.23.1 Parsing multicolumns

`\LWR@printmccoltype` {⟨*colspec*⟩} Print any valid column type found. Does not print `@`, `!`, `>`, or `<` columns or their associated tokens.

This is printed as part of the table data tag's `class`.

```
\newcommand*{\LWR@printmccoltype}[1]{%
    \LWR@traceinfo{lwr@printmccoltype -#1-}%
```

Get one token of the column spec:

```
    \StrChar{#1}{\arabic{LWR@tablemulticolspos}}[\LWR@strresult]%
```

Add to the HTML tag depending on which column type is found:

```
    \IfStrEq{\LWR@strresult}{l}{l}{}%
    \IfStrEq{\LWR@strresult}{c}{c}{}%
    \IfStrEq{\LWR@strresult}{r}{r}{}%
    \IfStrEq{\LWR@strresult}{p}{p}{}%
    \IfStrEq{\LWR@strresult}{m}{m}{}%
    \IfStrEq{\LWR@strresult}{b}{b}{}%
    \IfStrEq{\LWR@strresult}{P}{P}{}%
    \IfStrEq{\LWR@strresult}{M}{M}{}%
    \IfStrEq{\LWR@strresult}{B}{B}{}%

    \IfStrEq{\LWR@strresult}{w}{w}{}%
    \IfStrEq{\LWR@strresult}{W}{W}{}%

    \IfStrEq{\LWR@strresult}{S}{c}{}%
    \IfStrEq{\LWR@strresult}{s}{c}{}%

    \IfStrEq{\LWR@strresult}{X}{p}{}%

    \IfStrEq{\LWR@strresult}{|}%
    {%
        \ifbool{LWR@mcolvertbaronleft}%
```

```
            {\defaddtocounter{LWR@mcolvertbarsl}{1}}% left edge
            {\defaddtocounter{LWR@mcolvertbarsr}{1}}% not left edge
    }%
    {%
        \IfStrEq{\LWR@strresult}{:}%
        {%
            \ifbool{LWR@mcolvertbaronleft}%
                {\defaddtocounter{LWR@mcolvertbarsldash}{1}}% left edge
                {\defaddtocounter{LWR@mcolvertbarsrdash}{1}}% not left edge
        }%
        {%
            \IfStrEq{\LWR@strresult}{;}%
            {%
                \ifbool{LWR@mcolvertbaronleft}%
                    {\defaddtocounter{LWR@mcolvertbarsldash}{1}}% left edge
                   {\defaddtocounter{LWR@mcolvertbarsrdash}{1}}% not left edge
            }%
            {\boolfalse{LWR@mcolvertbaronleft}}%
        }%
    }%
    \LWR@traceinfo{lwr@printmccoltype done}%
}
```

`\LWR@multicolpartext` {⟨*num parameters*⟩} Print the data with paragraph tags, advance to bypass the given number of parameters.

```
\newcommand*{\LWR@multicolpartext}[1]{%
    \LWR@startpars%
    \LWR@multicoltext%
    \defaddtocounter{LWR@tablemulticolspos}{#1}%
    \LWR@stoppars%
}
```

`\LWR@multicolother` {⟨*colspec*⟩} For `@`, `!`, `>`, `<`, print the next token without paragraph tags:

```
\newcommand*{\LWR@multicolother}[1]{%
    \defaddtocounter{LWR@tablemulticolspos}{1}%
    \StrChar{#1}{\arabic{LWR@tablemulticolspos}}[\LWR@strresult]%
    \LWR@strresult%
```

A valid column data type was found:

```
    \booltrue{LWR@validtablecol}%
}
```

`\LWR@multicolskip` Nothing to print for this column type.

```
\newcommand*{\LWR@multicolskip}{%
```

A valid column data type was found:

```
    \booltrue{LWR@validtablecol}%
}
```

\LWR@printmccoldata {⟨*colspec*⟩} Print the data for any valid column type found.

```
\newcommand*{\LWR@printmccoldata}[1]{%
    \LWR@traceinfo{lwr@printmccoldata -#1}%
```

Not yet found a valid column type:

```
    \boolfalse{LWR@validtablecol}%
```

Get one token of the column spec, into a local copy in case nested.

```
    \StrChar{#1}{\arabic{LWR@tablemulticolspos}}[\LWR@strresult]%
    \edef\LWR@printmccoldatatoken{\LWR@strresult}%
```

Print the text depending on which column type is found. Also handles @, >, < as it comes to them.

```
    \IfStrEq{\LWR@printmccoldatatoken}{l}{\LWR@multicoltext}{}%
    \IfStrEq{\LWR@printmccoldatatoken}{c}{\LWR@multicoltext}{}%
    \IfStrEq{\LWR@printmccoldatatoken}{r}{\LWR@multicoltext}{}%
    \IfStrEq{\LWR@printmccoldatatoken}{D}{%
        \defaddtocounter{LWR@tablemulticolspos}{3}% skip parameters
        \LWR@multicoltext%
    }{}%

    \IfStrEq{\LWR@printmccoldatatoken}{p}{\LWR@multicolpartext{2}}{}%
    \IfStrEq{\LWR@printmccoldatatoken}{m}{\LWR@multicolpartext{2}}{}%
    \IfStrEq{\LWR@printmccoldatatoken}{b}{\LWR@multicolpartext{2}}{}%
    \IfStrEq{\LWR@printmccoldatatoken}{P}{\LWR@multicolpartext{2}}{}%
    \IfStrEq{\LWR@printmccoldatatoken}{M}{\LWR@multicolpartext{2}}{}%
    \IfStrEq{\LWR@printmccoldatatoken}{B}{\LWR@multicolpartext{2}}{}%

    \IfStrEq{\LWR@printmccoldatatoken}{w}{\LWR@multicolpartext{3}}{}%
    \IfStrEq{\LWR@printmccoldatatoken}{W}{\LWR@multicolpartext{3}}{}%

    \IfStrEq{\LWR@printmccoldatatoken}{S}{\LWR@multicoltext}{}%
    \IfStrEq{\LWR@printmccoldatatoken}{s}{\LWR@multicoltext}{}%

    \IfStrEq{\LWR@printmccoldatatoken}{X}{\LWR@multicolpartext{1}}{}%
    \IfStrEq{\LWR@printmccoldatatoken}{|}{\LWR@multicolskip}{}%
    \IfStrEq{\LWR@printmccoldatatoken}{:}{\LWR@multicolskip}{}%
    \IfStrEq{\LWR@printmccoldatatoken}{;}{%
        \LWR@multicolskip%
        \defaddtocounter{LWR@tablemulticolspos}{1}% skip parameter
    }{}%
   \IfStrEq{\LWR@printmccoldatatoken}{\detokenize{@}}{\LWR@multicolother{#1}}{}%
   \IfStrEq{\LWR@printmccoldatatoken}{\detokenize{!}}{\LWR@multicolother{#1}}{}%
   \IfStrEq{\LWR@printmccoldatatoken}{\detokenize{>}}{\LWR@multicolother{#1}}{}%
   \IfStrEq{\LWR@printmccoldatatoken}{\detokenize{<}}{\LWR@multicolother{#1}}{}%
```

If an invalid column type:

```
    \ifbool{LWR@validtablecol}{}{\LWR@multicoltext{}}%
```

Tracing:

```
    \LWR@traceinfo{lwr@printmccoldata done}%
}
```

\parsemulticolumnalignment {⟨*1: colspec*⟩} {⟨*2: printresults*⟩}

Scan the multicolumn specification and execute the printfunction for each entry.

Note that the spec for a p{spec} column, or @, >, <, is a token list which will NOT match l, c, r, or p.

```
\newcommand*{\LWR@parsemulticolumnalignment}[2]{%
    \defcounter{LWR@tablemulticolspos}{1}%
    \StrLen{#1}[\LWR@strresult]%
    \defcounter{LWR@tablemulticolswidth}{\LWR@strresult}%
```

Scan across the tokens in the column spec:

```
    \whileboolexpr{%
        not test {%
            \ifnumcomp{\value{LWR@tablemulticolspos}}{>}%
                {\value{LWR@tablemulticolswidth}}%
        }%
    }%
    {%
```

Execute the assigned print function for each token in the column spec:

```
        #2{#1}%
```

Move to the next token in the column spec:

```
        \defaddtocounter{LWR@tablemulticolspos}{1}%
    }%
}
```

### 74.23.2 Multicolumn factored code

\LWR@addmulticolvertrulecolor

```
\newcommand*{\LWR@addmulticolvertrulecolor}{%
```

No vertical rules if finishing the tabular with a row of empty cells:

```
    \ifbool{LWR@tabularmutemods}{}{%
```

Left side:

```
        \ifnumcomp{\value{LWR@mcolvertbarsl}}{=}{1}{%
            \LWR@tdaddstyle%
            border-left: 1px solid \LWR@vertruleHTMLcolor%
        }{}%
```

```
        \ifnumcomp{\value{LWR@mcolvertbarsl}}{>}{1}{%
            \LWR@tdaddstyle%
            border-left: 4px double \LWR@vertruleHTMLcolor%
        }{}%
        \ifnumcomp{\value{LWR@mcolvertbarsldash}}{=}{1}{%
            \LWR@tdaddstyle%
            border-left: 1px dashed \LWR@vertruleHTMLcolor%
        }{}%
        \ifnumcomp{\value{LWR@mcolvertbarsldash}}{>}{1}{%
            \LWR@tdaddstyle%
            border-left: 2px dashed \LWR@vertruleHTMLcolor%
        }{}%
```

Right side:

```
        \ifnumcomp{\value{LWR@mcolvertbarsr}}{=}{1}{%
            \LWR@tdaddstyle%
            border-right: 1px solid \LWR@vertruleHTMLcolor%
        }{}%
        \ifnumcomp{\value{LWR@mcolvertbarsr}}{>}{1}{%
            \LWR@tdaddstyle%
            border-right: 4px double \LWR@vertruleHTMLcolor%
        }{}%
        \ifnumcomp{\value{LWR@mcolvertbarsrdash}}{=}{1}{%
            \LWR@tdaddstyle%
            border-right: 1px dashed \LWR@vertruleHTMLcolor%
        }{}%
        \ifnumcomp{\value{LWR@mcolvertbarsrdash}}{>}{1}{%
            \LWR@tdaddstyle%
            border-right: 2px dashed \LWR@vertruleHTMLcolor%
        }{}%
    }%
}

\newcommand{\LWR@multicoltext}{}
```

To find multicolumn right trim:

```
\newcounter{LWR@lastmulticolumn}
```

`\LWR@domulticolumn` [⟨*1: vpos*⟩] [⟨*2: #rows*⟩] {⟨*3: numLaTeXcols*⟩} {⟨*4: numHTMLcols*⟩} {⟨*5: colspec*⟩} {⟨*6: text*⟩}

```
\NewDocumentCommand{\LWR@domulticolumn}{o o m m m +m}{%
    \LWR@traceinfo{LWR@domulticolumn -#1- -#2- -#4- -#5-}%
```

Remember the text to be inserted, and remember that a valid column type was found:

```
    \renewcommand{\LWR@multicoltext}{%
        #6%
        \booltrue{LWR@validtablecol}%
    }%
```

Compute the rightmost column to be included. This is used to create the right trim.

```
    \defcounter{LWR@lastmulticolumn}{\value{LWR@tableLaTeXcolindex}}%
    \defaddtocounter{LWR@lastmulticolumn}{#3}%
    \defaddtocounter{LWR@lastmulticolumn}{-1}%
```

Row processing:

```
    \LWR@maybenewtablerow%
```

Begin the opening table data tag:

```
    \LWR@htmltag{%
        td colspan=\textquotedbl#4\textquotedbl\ %

        \IfValueT{#2}{ % rows?
            rowspan=\textquotedbl#2\textquotedbl\ %
        }%

        class=\textquotedbl{}td%
```

Print the column type and vertical bars:

```
        \defcounter{LWR@mcolvertbarsl}{0}%
        \defcounter{LWR@mcolvertbarsr}{0}%
        \defcounter{LWR@mcolvertbarsldash}{0}%
        \defcounter{LWR@mcolvertbarsrdash}{0}%
        \booltrue{LWR@mcolvertbaronleft}%
        \LWR@parsemulticolumnalignment{#5}{\LWR@printmccoltype}%
```

If this column has a cmidrule, add "rule" to the end of the HTML class tag.

If this position had a "Y" then add "rule" for a horizontal rule:

```
        \LWR@subaddcmidruletrim%
            {%
                \LWR@getexparray{LWR@trimlrules}%
                    {\arabic{LWR@tableLaTeXcolindex}}%
            }%
            {%
                \LWR@getexparray{LWR@trimrrules}%
                    {\arabic{LWR@lastmulticolumn}}%
            }%
```

Also add vertical bar class.

```
        \ifnumcomp{\value{LWR@mcolvertbarsl}}{=}{1}{ tvertbarl}{}%
        \ifnumcomp{\value{LWR@mcolvertbarsl}}{>}{1}{ tvertbarldouble}{}%
        \ifnumcomp{\value{LWR@mcolvertbarsr}}{=}{1}{ tvertbarr}{}%
        \ifnumcomp{\value{LWR@mcolvertbarsr}}{>}{1}{ tvertbarrdouble}{}%
        \ifnumcomp{\value{LWR@mcolvertbarsldash}}{=}{1}{ tvertbarldash}{}%
        \ifnumcomp{\value{LWR@mcolvertbarsldash}}{>}{1}%
            { tvertbarldoubledash}{}%
        \ifnumcomp{\value{LWR@mcolvertbarsrdash}}{=}{1}{ tvertbarrdash}{}%
```

```
        \ifnumcomp{\value{LWR@mcolvertbarsrdash}}{>}{1}%
            { tvertbarrdoubledash}{}%
```

Close the class tag's opening quote:

```
        \textquotedbl{}%

        \LWR@tdstartstyles%
```

Style for vertical position:

```
        \IfValueT{#1}{% vpos?
            \ifstrequal{#1}{b}%
                {%
                    \LWR@tdaddstyle%
                    \LWR@print@mbox{vertical-align:bottom}%
                }{}%
            \ifstrequal{#1}{t}%
                {%
                    \LWR@tdaddstyle%
                    \LWR@print@mbox{vertical-align:top}%
                }{}%
        }% vpos?
```

Style for row colors:

```
        \LWR@addtabularrowcolor%
```

Other styles:

```
        \LWR@addcmidrulewidth%
        \LWR@addcdashline%
        \LWR@addtabularhrulecolor%
        \LWR@addmulticolvertrulecolor%
        \LWR@addformatwpalignment{#5}%
        \LWR@tdendstyles%
    }% end of the opening table data tag
    \boolfalse{LWR@intabularmetadata}%
    \LWR@parsemulticolumnalignment{#5}{\LWR@printmccoldata}%
}
```

### 74.23.3 Multicolumn

`\LWR@htmlmulticolumn` {⟨*numcols*⟩} {⟨*alignment*⟩} {⟨*text*⟩}

```
\NewDocumentCommand{\LWR@htmlmulticolumn}{m m +m}%
{%
```

Figure out how many extra HTML columns to add for `@` and `!` columns:

```
    \LWR@tabularhtmlcolumns{\arabic{LWR@tableLaTeXcolindex}}{#1}%
```

Create the multicolumn tag:

```
\LWR@domulticolumn{#1}{\arabic{LWR@tabhtmlcoltotal}}{#2}{#3}%
```

Move to the next LaTeX column:

```
\defaddtocounter{LWR@tableLaTeXcolindex}{#1}%
\defaddtocounter{LWR@tableLaTeXcolindex}{-1}%
```

Skip any trailing `@` or `!` columns for this cell:

```
\booltrue{LWR@skipatbang}%
}
```

### 74.23.4 Longtable captions

longtable captions use `\multicolumn`.

Per the caption package. User-redefinable float type.

```
\providecreP71.373 -2L
```

Star version, show a caption but do not make a LOT entry:

```
    {% yes star
        \LWR@figcaption%
        \LWR@isolate{#3}%
        \endLWR@figcaption%
    }%
    {% No star:
```

Not the star version:

Don't step the counter if `\caption[]{A caption.}`

```
        \ifbool{LWR@starredlongtable}%
        {%
            \ifblank{#2}% TOC entry
            {}%
            {%
                \refstepcounter{\LTcaptype}%
                \protected@edef\@currentlabel{%
                    \@nameuse{p@\LTcaptype}\@nameuse{the\LTcaptype}%
                }%
            }%
        }{}%
```

Create an HTML caption. Afterwards, maybe make a LOT entry.

```
        \LWR@figcaption%
        \LWR@isolate{\@nameuse{fnum@\LTcaptype}}%
        \CaptionSeparator%
        \LWR@isolate{#3}%
        \endLWR@figcaption%
```

See if an optional caption was given:

```
        \ifblank{#2}% TOC entry empty
```

if the optional caption was given, but empty, do not form a TOC entry

```
        {}%
```

If the optional caption was given, but might only be `[]`:

```
        {% TOC entry not empty
            \IfNoValueTF{#2}% No TOC entry?
```

The optional caption is `[]`:

```
            {% No TOC entry
                \addcontentsline%
                {\@nameuse{ext@\LTcaptype}}%
                {\LTcaptype}%
                {%
                    \protect\numberline%
              {\LWR@isolate{\@nameuse{p@\LTcaptype}}\@nameuse{the\LTcaptype}}%
```

```
                    {\ignorespaces \LWR@isolate{#3}\protect\relax}%
                }%
            }% end of No TOC entry
```

The optional caption has text enclosed:

```
            {% yes TOC entry
                \addcontentsline%
                {\@nameuse{ext@\LTcaptype}}%
                {\LTcaptype}%
                {%
                    \protect\numberline%
              {\LWR@isolate{\@nameuse{p@\LTcaptype}}\@nameuse{the\LTcaptype}}%
                    {\ignorespaces \LWR@isolate{#2}\protect\relax}%
                }%
            }% end of yes TOC entry
        }% end of TOC entry not empty
    }% end of no star
```

Skip any trailing `@` or `!` columns for this cell:

```
    \booltrue{LWR@skipatbang}%
    }% end of \LWR@domulticolumn
    \defaddtocounter{LWR@tableLaTeXcolindex}{\value{LWR@tabletotalLaTeXcols}}%
    \defaddtocounter{LWR@tableLaTeXcolindex}{-1}

}
```

### 74.23.5 Counting HTML tabular columns

The LaTeX specification for a table includes a number of columns separated by the `&` character. These columns differ in content from line to line. Additional virtual columns may be specified by the special `@` and `!` columns. These columns are identical from line to line, but may be skipped during a multicolumn cell.

For HTML output, `@` and `!` columns are placed into their own tabular columns. Thus, a LaTeX `\multicolumn` command may span several additional `@` and `!` columns in HTML output. These additional columns must be added to the total number of columns spanned by an HTML multi-column data cell.

```
\newcounter{LWR@tabhtmlcolindex}
\newcounter{LWR@tabhtmlcolend}
\newcounter{LWR@tabhtmlcoltotal}
```

`\LWR@subtabularhtmlcolumns` {⟨*index*⟩}

Factored from `\LWr@tabularhtmlcolumns`, which follows.

```
\newcommand*{\LWR@subtabularhtmlcolumns}[1]{%
```

Temporarily define a macro equal to the `@` specification for this column:

```
    \edef\LWR@atbangspec{\LWR@getexparray{LWR@colatspec}{#1}}%
```

If the @ specification is not empty, add to the count:

```
    \ifdefempty{\LWR@atbangspec}%
        {}%
        {\defaddtocounter{LWR@tabhtmlcoltotal}{1}}%
```

Likewise for the ! columns:

```
    \edef\LWR@atbangspec{\LWR@getexparray{LWR@colbangspec}{#1}}%
    \ifdefempty{\LWR@atbangspec}%
        {}%
        {\defaddtocounter{LWR@tabhtmlcoltotal}{1}}%
}
```

`\LWR@tabularhtmlcolumns` {⟨*starting LaTeX column*⟩} {⟨*number LaTeX columns*⟩}

Compute the total number of HTML columns being spanned, considering the starting LaTeX table column and the number of LaTeX tabular columns being spanned. Any @ and ! columns within this span are included in the total count. The resulting number of HTML columns is returned in the counter `LWR@tabhtmlcoltotal`.

```
\newcommand*{\LWR@tabularhtmlcolumns}[2]{%
```

Count the starting index, compute ending index, and begin with the count being the LaTeX span, to which additional @ and ! columns may be added:

```
    \defcounter{LWR@tabhtmlcolindex}{#1}%
    \defcounter{LWR@tabhtmlcoltotal}{#2}%
    \defcounter{LWR@tabhtmlcolend}{#1}%
    \defaddtocounter{LWR@tabhtmlcolend}{#2}%
```

If at the left edge, add the at/bang columns for the left edge:

```
    \ifnumcomp{\value{LWR@tabhtmlcolindex}}{=}{1}{%
        \LWR@subtabularhtmlcolumns{leftedge}%
    }{}%
```

Walk across the LaTeX columns looking for @ and ! columns:

```
    \whileboolexpr{%
        test {%
        \ifnumcomp{\value{LWR@tabhtmlcolindex}}{<}{\value{LWR@tabhtmlcolend}}%
        }%
    }%
    {%
        \LWR@subtabularhtmlcolumns{\arabic{LWR@tabhtmlcolindex}}%
        \defaddtocounter{LWR@tabhtmlcolindex}{1}%
    }% whiledo
}
```

```
\end{warpHTML}
```

## 74.24 Multirow if not loaded

A default defintion in case multirow is not loaded. This is used during table parsing.

```
\begin{warpHTML}
\newcommand{\multirow}[2][c]{}
\end{warpHTML}
```

## 74.25 Multicolumnrow

A print-mode version is defined here, and is also used during HTML output while inside a `lateximage`.

See section 416 for the HTML versions.

**for HTML & PRINT:**

```
\begin{warpall}
```

`\multicolumnrow` {⟨*1:cols*⟩} {⟨*2:halign*⟩} [⟨*3:vpos*⟩] {⟨*4:numrows*⟩} [⟨*5:bigstruts*⟩] {⟨*6:width*⟩} [⟨*7:fixup*⟩] {⟨*8:text*⟩}

For discussion of the use of `\DeclareExpandableDocumentCommand`, see:
https://tex.stackexchange.com/questions/168434/problem-with-abbreviation-of-multirow-and-multicolumn-latex

`\AtBeginDocument` to adjust after the user may have loaded multirow, which requires several tests to determine which version is loaded and thus which options are available.

```
\AtBeginDocument{
```

`\@ifundefined{@xmultirow}` determines if multirow was never loaded.

Null action if not loaded:

```
\@ifundefined{@xmultirow}
{
\DeclareExpandableDocumentCommand{\LWR@print@multicolumnrow}%
    {+m +m +O{c} +m +O{0} +m +O{0pt} +m}%
    {}%
}% no version of multirow was loaded
{% \@xmultirow defined, so some version of multirow was loaded
```

`\@ifpackageloaded{multirow}` determines if v2.0 or later of multirow was used, which included the `\ProvidesPackage` macro.

The print version:

```
\@ifpackageloaded{multirow}{% v2.0 or newer
\@ifpackagelater{multirow}{2016/09/01}% 2016/09/27 for v2.0
{% v2.0+:
\DeclareExpandableDocumentCommand{\LWR@print@multicolumnrow}%
    {+m +m +O{c} +m +O{0} +m +O{0pt} +m}%
    {\multicolumn{#1}{#2}{\@xmultirow[#3]{#4}[#5]{#6}[#7]{#8}}}%
}
```

```
{% loaded but older, probably not executed:
\DeclareExpandableDocumentCommand{\LWR@print@multicolumnrow}%
    {+m +m +O{c} +m +O{0} +m +O{0pt} +m}%
    {\multicolumn{#1}{#2}{\@xmultirow{#4}[#5]{#6}[#7]{#8}}}%
}
}% packageloaded{multirow}
```

If not `\@ifpackageloaded{multirow}` but `\@xmultirow` is defined, then this must be v1.6 or earlier, which did not `\ProvidesPackage{multirow}`, and did not have the `vposn` option.

```
{% v1.6 or older did not \ProvidePackage
\DeclareExpandableDocumentCommand{\LWR@print@multicolumnrow}%
    {+m +m +O{c} +m +O{0} +m +O{0pt} +m}%
    {\multicolumn{#1}{#2}{\@xmultirow{#4}[#5]{#6}[#7]{#8}}}%
}

}% \@ifundefined{@xmultirow}

\providecommand*{\multicolumnrow}{\LWR@print@multicolumnrow}

}% AtBeginDocument

\end{warpall}
```

## 74.26 Utility macros inside a table

**for HTML output:**

```
\begin{warpHTML}
```

Used to prevent opening a tabular data cell if the following token is one which does not create tabular data:

```
\newcommand*{\LWR@donothing}{}
```

In case array is not loaded:

```
\let\firsthline\relax
\let\lasthline\relax
\newcommand*{\firsthline}{}
\newcommand*{\lasthline}{}
```

In case bigdelim is not loaded:

```
\newcommand*{\ldelim}{}
\newcommand*{\rdelim}{}

\end{warpHTML}
```

## 74.27 Special-case tabular markers

**for HTML & PRINT:**

```
\begin{warpall}
```

```
\newcommand*{\LWR@tabledatacolumntag}%
{%
    \LWR@traceinfo{LWR@tabledatacolumntag}%
```

\show\LWR@mynexttoken to see what tokens to look for

If not any of the below, start a new table cell:

```
    \global\let\LWR@mynextaction\LWR@tabledatasinglecolumntag%
```

If exiting the tabular:

```
    \ifdefequal{\LWR@mynexttoken}{\end}%
        {\booltrue{LWR@exitingtabular}}{}%
```

longtable can have a caption in a cell

```
    \ifdefequal{\LWR@mynexttoken}{\caption}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%
```

Look for other things which would not start a table cell:

```
    \ifdefequal{\LWR@mynexttoken}{\multicolumn}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%
    \ifdefequal{\LWR@mynexttoken}{\multirow}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%
    \ifdefequal{\LWR@mynexttoken}{\multicolumnrow}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%
    \ifdefequal{\LWR@mynexttoken}{\noalign}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%
```

If an \mrowcell, this is a cell to be skipped over:

```
    \ifdefequal{\LWR@mynexttoken}{\mrowcell}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%
```

If an \mcolrowcell, this is a cell to be skipped over:

```
    \ifdefequal{\LWR@mynexttoken}{\mcolrowcell}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%

    \ifdefequal{\LWR@mynexttoken}{\TabularMacro}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%

    \ifdefequal{\LWR@mynexttoken}{\hline}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%

    \ifdefequal{\LWR@mynexttoken}{\firsthline}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%

    \ifdefequal{\LWR@mynexttoken}{\lasthline}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%
```

```
    \ifdefequal{\LWR@mynexttoken}{\toprule}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%

    \ifdefequal{\LWR@mynexttoken}{\midrule}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%

    \ifdefequal{\LWR@mynexttoken}{\cmidrule}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%

    \ifdefequal{\LWR@mynexttoken}{\morecmidrules}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%

    \ifdefequal{\LWR@mynexttoken}{\specialrule}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%

    \ifdefequal{\LWR@mynexttoken}{\cline}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%

    \ifdefequal{\LWR@mynexttoken}{\bottomrule}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%

    \ifdefequal{\LWR@mynexttoken}{\hhline}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%

    \ifdefequal{\LWR@mynexttoken}{\rowcolor}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%

    \ifdefequal{\LWR@mynexttoken}{\arrayrulecolor}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%

    \ifdefequal{\LWR@mynexttoken}{\doublerulesepcolor}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%

    \ifdefequal{\LWR@mynexttoken}{\warpprintonly}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%

    \ifdefequal{\LWR@mynexttoken}{\warpHTMLonly}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%

    \ifdefequal{\LWR@mynexttoken}{\ldelim}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%

    \ifdefequal{\LWR@mynexttoken}{\rdelim}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%
```

For arydshln:

```
    \ifdefequal{\LWR@mynexttoken}{\hdashline}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%

    \ifdefequal{\LWR@mynexttoken}{\cdashline}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%
```

```
    \ifdefequal{\LWR@mynexttoken}{\firsthdashline}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%

    \ifdefequal{\LWR@mynexttoken}{\lasthdashline}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%
```

Ignore an empty line between rows:

```
    \ifdefequal{\LWR@mynexttoken}{\par}%
        {\global\let\LWR@mynextaction\LWR@donothing}{}%
```

No action for an \end token.

Add similar to the above for any other non-data tokens which might appear in the table.

Start the new table cell if was not any of the above:

```
    \LWR@traceinfo{LWR@tabledatacolumntag: about to do mynext}%
    \LWR@mynextaction%
    \LWR@traceinfo{LWR@tabledatacolumntag: done}%
}
```

```
\end{warpHTML}
```

## 74.29 \mrowcell

**for HTML & PRINT:**

```
\begin{warpall}
```

\mrowcell
⚠ multirow cells

The user must insert \mrowcell into any \multirow cells which must be skipped. This command has no action during print output.

```
\newcommand*{\mrowcell}{}
```

```
\end{warpall}
```

## 74.30 \mcolrowcell

**for HTML & PRINT:**

```
\begin{warpall}
```

\mcolrowcell
⚠ multirow cells

The user must insert \mcolrowcell into any \multicolumnrow cells which must be skipped. This command has no action during print output.

```
\newcommand*{\mcolrowcell}{}
```

```
\end{warpall}
```

\LWR@HTMLcline {⟨*columns*⟩}

```
\NewDocumentCommand{\LWR@HTMLcline}{m}%
    {\LWR@docmidrule{#1}\LWR@getmynexttoken}%
```

\LWR@tabular@warpprintonly {⟨*contents*⟩}

Only process the contents if producing printed output. Modified inside a `tabular` to grab the next token.

```
\newcommand{\LWR@tabular@warpprintonly}[1]{%
    \ifbool{warpingprint}{#1}{}%
    \LWR@getmynexttoken%
}
```

\LWR@nullifyNoAutoSpacing For babel-french, turn off auto spacing at the start of the tabular, then nullify the autospacing commands inside the tabular, since they were not compatible with the tabular parsing code for each cell, which uses xstring.

```
\AtBeginDocument{
\@ifundefined{NoAutoSpacing}%
{% no babel-french
    \newcommand*{\LWR@nullifyNoAutoSpacing}{}
}% no babel-french
{% yes babel-french
    \newcommand*{\LWR@nullifyNoAutoSpacing}{%
        \NoAutoSpacing%
        \renewcommand*{\NoAutoSpacing}{}%
        \renewcommand*{\LWR@FBcancel}{}%
    }
}% yes babel-french
}% AtBeginDocument
```

Env tabular <direction> [⟨*vertposition*⟩] {⟨*colspecs*⟩}

The <direction> is from plext for Japanese documents, and is ignored.

```
\StartDefiningTabulars

\NewDocumentCommand{\LWR@HTML@@tabular}{d<> o m}
{%
    \LWR@traceinfo{LWR@HTML@@tabular started}%
```

⚠ <table> inside  In LaTeX, a `tabular` may be placed inside a `minipage`, but in HTML a <table> may not be inside a . Since there may be several nested s, with an unknown number of other objects between, it is hard to undo all these s before the <table> then redo them after. The broswer probably compensates for this situation, but formatting may be lost inside the <table> because several things are neutralized inside a . Furthermore, in the HTML output, the entire <table> is placed on a single line of HTML code, since the line breaking commands are neutralized inside a . Since this is such a sloppy situation, a warning is issued here instructing the user to please isolate the  to print-only.

```
    \LWR@spanwarnformat{tabular}%
    \addtocounter{LWR@tabulardepth}{1}%
```

Not yet started a table row:

```
    \boolfalse{LWR@startedrow}%
```

Not yet doing any rules:

```
    \defcounter{LWR@hlines}{0}%
    \defcounter{LWR@hdashedlines}{0}%
    \boolfalse{LWR@doingtbrule}%
    \boolfalse{LWR@doingcmidrule}%
```

For babel-french, turn off auto spacing one time, then nullify the autospacing commands since were not compatible with the tabular parsing code.

```
    \LWR@nullifyNoAutoSpacing%
```

Have not yet found the end of tabular command. Unmute the `@` and `!` columns.

```
    \boolfalse{LWR@exitingtabular}%
    \boolfalse{LWR@tabularmutemods}%
```

Error if failed to use `\mrowcell` or `\mcolrowcell` when needed.

```
    \boolfalse{LWR@usedmultirow}%
    \boolfalse{LWR@foundmrowcell}%

    \renewcommand*{\LWR@multicoltext}{}%
```

Create the `table` tag:

```
    \booltrue{LWR@intabularmetadata}%
    \LWR@traceinfo{LWR@@tabular: About to LWR@forecenewpage.}%
    \LWR@forcenewpage
    \LWR@htmlblocktag{table}%
```

Parse the table columns:

```
    \LWR@parsetablecols{#3}%
```

Table col spec is: `\LWR@tablecolspec` which is a string of `llccrr`, etc.

Do not place the table inside a paragraph:

```
    \LWR@stoppars%
```

Track column #:

```
    \defcounter{LWR@tableLaTeXcolindex}{1}%
```

Have not yet added data in this column:

```
    \global\boolfalse{LWR@tabularcelladded}%
```

Start looking for midrules:

```
    \LWR@clearmidrules%
```

\\ becomes a macro to end the table row:

```
    \LetLtxMacro{\\}{\LWR@tabularendofline}%
```

\warpprintonly inside a tabular must grab the next token.

```
    \LetLtxMacro\warpprintonly\LWR@tabular@warpprintonly%
```

The following adjust for colortbl.

```
    \LetLtxMacro\arrayrulecolor\arrayrulecolornexttoken%
    \LetLtxMacro\doublerulesepcolor\doublerulesepcolornexttoken%
    \def\LWR@columnHTMLcolor{}%
    \def\LWR@rowHTMLcolor{}%
    \def\LWR@cellHTMLcolor{}%
    \@rowcolors%
```

The vertical rules are set to the color active at the start of the tabular. \arrayrulecolor will then affect horizontal rules inside the tabular, but not the vertical rules.

```
    \ifdefvoid{\LWR@ruleHTMLcolor}%
        {\edef\LWR@vertruleHTMLcolor{black}}%
        {\edef\LWR@vertruleHTMLcolor{\LWR@origpound\LWR@ruleHTMLcolor}}%
```

Tracking the depth of cell color s:

```
    \defcounter{LWR@cellcolordepth}{0}%
```

The following may appear before a data cell is created, so after doing their actions, we look ahead with \LWR@getmynextoken to see if the next token might create a new data cell:

The optional parameter for \hline supports the tabls package.

```
    \LWR@traceinfo{LWR@@HTML@tabular: redefining macros}%
    \LetLtxMacro\noalign\LWR@tabularnoalign%
    \LetLtxMacro\hline\LWR@HTMLhline%
    \LetLtxMacro\cline\LWR@HTMLcline%

    \DeclareDocumentCommand{\hdashline}{o}{%
        \ifbool{FormatWP}%
            {\LWR@docdashline{1-\arabic{LWR@tabletotalLaTeXcols}}}%
            {\defaddtocounter{LWR@hdashedlines}{1}}%
        \LWR@getmynexttoken%
    }%

    \DeclareDocumentCommand{\cdashline}{m}{%
        \LWR@docdashline{##1}\LWR@getmynexttoken%
    }%

    \DeclareDocumentCommand{\firsthdashline}{o}{%
```

```
        \ifbool{FormatWP}%
            {\LWR@docdashline{1-\arabic{LWR@tabletotalLaTeXcols}}}%
            {\defaddtocounter{LWR@hdashedlines}{1}}%
        \LWR@getmynexttoken%
    }%

    \DeclareDocumentCommand{\lasthdashline}{o}{%
        \ifbool{FormatWP}%
            {\LWR@docdashline{1-\arabic{LWR@tabletotalLaTeXcols}}}%
            {\defaddtocounter{LWR@hdashedlines}{1}}%
        \LWR@getmynexttoken%
    }%
```

The following create data cells and will have no more data in this cell, so we do not want to look ahead for a possible data cell, so do not want to use `\LWR@getmynexttoken`.

```
    \renewcommand{\multicolumn}{\LWR@htmlmulticolumn}%
    \renewcommand*{\mrowcell}{%
        \LWR@maybenewtablerow%
        \LWR@tabularleftedge%
        \booltrue{LWR@skippingmrowcell}%
        \booltrue{LWR@foundmrowcell}%
    }%
    \renewcommand*{\mcolrowcell}{%
        \LWR@maybenewtablerow%
        \booltrue{LWR@skippingmcolrowcell}%
        \booltrue{LWR@foundmrowcell}%
    }%
    \LetLtxMacro\caption\LWR@longtabledatacaptiontag%
```

Reset for new processing:

```
    \boolfalse{LWR@tableparcell}%
    \boolfalse{LWR@skippingmrowcell}%
    \boolfalse{LWR@skippingmcolrowcell}%
    \boolfalse{LWR@skipatbang}%
    \boolfalse{LWR@emptyatbang}%
```

Set `&` for its special meaning inside the tabular:

```
    \StartDefiningTabulars%
    \protected\gdef&{\LWR@tabularampersand}%
```

Locally force any minipages to be fullwidth, until the end of the `tabular`:

```
    \booltrue{LWR@forceminipagefullwidth}%
```

Nest one level deeper of tabular paragraph handling:

```
    \addtocounter{LWR@tabularpardepth}{1}%
```

Look ahead for a possible table data cell:

```
    \LWR@traceinfo{LWR@@HTML@tabular: about to LWR@getmynexttoken}%
```

```
    \LWR@getmynexttoken%
}%
```

Ending the environment:

```
\newcommand*{\LWR@HTML@endtabular}
{%
    \LWR@traceinfo{LWR@HTML@endtabular}%
```

Unnest one level of tabular paragraph handling:

```
    \addtocounter{LWR@tabularpardepth}{-1}%
    \ifboolexpr{%
        test {%
            \ifnumcomp{\value{LWR@tableLaTeXcolindex}}{<}%
                {\value{LWR@tabletotalLaTeXcols}}
        } or %
        (%
            bool{LWR@intabularmetadata} and%
            not bool{LWR@tabularcelladded} and%
            test {%
                \ifnumcomp{\value{LWR@tableLaTeXcolindex}}{=}%
                    {\value{LWR@tabletotalLaTeXcols}}%
            }%
        )%
    }%
    {%
        \LWR@tabularfinishrow%
    }%
    {%
        \LWR@closetabledatacell%
    }%
    \LWR@htmlblocktag{/tr}%
```

xcolor row color support:

```
    \@rowc@lors%

    \LWR@htmlblocktag{/table}%
    \boolfalse{LWR@intabularmetadata}%
```

Unnest one level of tabular:

```
    \addtocounter{LWR@tabulardepth}{-1}%
```

Restore & to its usual meaning:

```
    \ifnumequal{\value{LWR@tabulardepth}}{0}{%
        \protected\gdef&{\LWR@origampmacro}%
        \StopDefiningTabulars%
    }{}%
```

Error if used `\multirow` or `\multicolumnrow` without using `\mrowcell` or `\mcolrowcell`.

```
    \ifbool{LWR@usedmultirow}{%
        \ifbool{LWR@foundmrowcell}%
            {\relax}%
            {%
                \PackageError{lwarp}%
                {%
             When using \protect\multirow, \protect\multicolumnrow,\MessageBreak
                    or the bigdelim package,\MessageBreak
             place \protect\mrowcell\space or \protect\mcolrowcell\MessageBreak
                    in empty cells which are to be skipped.\MessageBreak
                    See the Lwarp package documentation:\MessageBreak
                    "Special cases and limitations" -> "Tabular"
                }%
                {%
                    See the Lwarp package documentation:\MessageBreak
                    "Special cases and limitations" -> "Tabular".
                }%
            }%
    }{}%

    \LWR@traceinfo{LWR@HTML@endtabular finished}%
}

\csletcs{LWR@HTML@endtabular*}{LWR@HTML@endtabular}

\StopDefiningTabulars
```

siunitx may redefine `tabular`, so set the following later:

```
\AtBeginDocument{
    \LetLtxMacro\LWR@origendtabular\endtabular
    \csletcs{LWR@origendtabular*}{endtabular*}
    \LWR@formatted{@tabular}
    \LWR@formatted{endtabular}
    \LWR@formatted{endtabular*}
}

\end{warpHTML}
```

# 75 Cross-references

Sectioning commands have been emulated from scratch, so the cross-referencing commands are custom-written for them. Emulating both avoids several layers of patches.

File `*_html.aux` A new entry in `*_html.aux` is used to remember section name, file, and lateximage depth and number for each label:

```
\newlabel{<labelname>@lwarp}{{<section name>}{<filename>}
                                {<limagedepth>}{<limagenumber>}}
```

Table 14 shows the data structures related to cross-referencing.

**for HTML output:**

```
\begin{warpHTML}
```

Table 14: Cross-referencing data structures

**Original LaTeX:** (print and HTML)

**\refstepcounter:** Steps the couunter and sets \@currentlabel.

**\@currentlabel:** \p@<ctr>\the<ctr> Updated by \refstepcounter.

**\label:** Writes to the .aux file:
\newlabel{<label>}{{\@currentlabel}{\thepage}}

**\newlabel:** When the .aux file is read, sets \r@<label>.

**\r@<label>:** Set to: {{\@currentlabel}{\thepage}}

**\ref:** Returns the first part of \r@<label>.

**\pageref:** Returns the second part of \r@<label>.

**Added by lwarp:** (HTML only)

**\label:** Adds HTML tags (section 75.3), and another .aux entry (section 75.2). If memoir is used, its \@mem@old@label points to lwarp's version, and cleveref patches.

**\newlabel:** Unchanged. When the .aux file is read, sets \r@<label>@lwarp.

**\r@<label>@lwarp:** Set to {{section_name}{file_name}{depth}{number}}:

**\LWR@nameref:** The section name for this label.

**\LWR@htmlfileref:** The filenumber or name for this label.

**\LWR@lateximagedepthref:** The lateximagedepth for this label.

**\LWR@lateximagenumberref:** The lateximagenumber for this label.

**\nameref:** Emualted from hyperref for lwarp. See section 75.4.

**\ref and \nameref:** Adds HTML tags. See section 75.4.

**Added by amsmath:** (print and HTML)

**\label:** Execution is delayed until the math environment is completed.

**\ltx@label:** LaTeX \label, (HTML: patched by lwarp,) later patched by cleveref.

**Added by cleveref:** (print and HTML)

**\refstepcounter:** Added: sets \cref@currentlabel.

**\cref@currentlabel:** (<type>=<ctr> unless an alias is used):
[<type>][\arabic{<ctr>}][<parent ctrs>]{\p@<ctr>\the<ctr>} Also see section 60.4 for use with footnotes.

**\label:** Writes to the .aux file:
\newlabel{<label>@cref}{{\cref@currentlabel}{\thepage}}

**\newlabel:** Unchanged. When the .aux file is read, sets \r@<label>@cref.

**\r@<label>@cref:** Set to: {{\cref@currentlabel}{\thepage}}

**Utility functions:** See \cref@getlabel, \cref@gettype, \cref@getcounter, \cref@getprefix.

**Cross-referencing names:** \crefname and \Crefname assign human-readable names for references to this counter type.

**Additionally patched by lwarp:** (HTML only)

**\cref, etc.:** Modified for lwarp. See section 196.

**\label inside math:** See section 82.7.1.

**Footnotes:** See \noteentry in section 60.4.

\LWR@nameref {⟨*label*⟩} Returns the section name for this label:

```
\newcommand*{\LWR@nameref}[1]{%
    \expandafter\LWR@setref\csname r@#1@lwarp\endcsname\LWR@firstoffour{#1}%
}
```

\LWR@htmlfileref {⟨*label*⟩} Returns the file number or name for this label:

```
\newcommand*{\LWR@htmlfileref}[1]{%
    \expandafter\LWR@setref\csname r@#1@lwarp\endcsname\LWR@secondoffour{#1}%
}
```

\LWR@lateximagedepthref {⟨*label*⟩} Returns the `lateximagedepth` for this label:

```
\newcommand*{\LWR@lateximagedepthref}[1]{%
    \expandafter\LWR@setref\csname r@#1@lwarp\endcsname\LWR@thirdoffour{#1}%
}
```

\LWR@lateximagenumberref {⟨*label*⟩} Returns the `lateximagenumber` for this label:

```
\newcommand*{\LWR@lateximagenumberref}[1]{%
    \expandafter\LWR@setref\csname r@#1@lwarp\endcsname\LWR@fourthoffour{#1}%
}
```

\LWR@write@lwarplabel {⟨*label*⟩} Sanitize the name and then creates the label:

```
\newcommand*{\LWR@write@lwarplabel}[1]{%
    \LWR@traceinfo{LWR@write@lwarplabel !#1!}%
    \LWR@setlatestname{\@currentlabelname}%
        \@bsphack%
        \protected@write\@auxout{}%
            {%
                \string\newlabel{#1@lwarp}{%
                    {\@currentlabelname}%
                    {%
                        \ifbool{FileSectionNames}%
                            {\LWR@thisfilename}%
                            {\arabic{LWR@htmlfilenumber}}%
                    }%
                    {\arabic{LWR@lateximagedepth}}%
                    {\arabic{LWR@lateximagenumber}}%
                }%
            }%
        \@esphack%
}
```

## 75.3 Labels

\LWR@label@subcreatetag Creates the tag from \LWR@sanitized.

```
\newcommand*{\LWR@label@subcreatetag}{%
```

```
    \LWR@htmltag{a \LWR@print@mbox{id=\textquotedbl\LWR@sanitized\textquotedbl}}%
     \LWR@htmltag{/a}%
}
```

\LWR@label@inmathcomment

```
\newcommand*{\LWR@label@inmathcomment}{%
    \ifboolexpr{bool{mathjax} or ( bool{FormatWP} and bool{WPMarkMath} ) }%
    {%
```

The combined LaTeX & HTML label is printed in a \mbox field:

```
        \mbox{%
```

Shift the label over to the right side of the environment to avoid over-printing the math:

```
        \ifdef{\totwidth@}{\ifbool{LWR@amsmultline}{}{\hspace*{\totwidth@}}}{}%
```

Temporarily end the HTML comment, insert the LaTeX & HTML label, then resume the HTML comment. \@firstofone is required to remove extra braces introduced by the amsmath package.)

```
            \LWR@htmlclosecomment%
            \LWR@label@subcreatetag%
            \LWR@htmlopencomment%
        }% mbox
    }% mathjax
    {%
        \LWR@label@subcreatetag%
    }%
}
```

\LWR@label@createtag {⟨*label*⟩} Creates an HTML id tag.

Used by \LWR@new@label and \hyperdef.

\detokenize is used to allow underscores in the labels.

```
\newcommand*{\LWR@label@createtag}[1]{%
    \LWR@traceinfo{LWR@label@createtag !#1!}%
```

Create an HTML id tag unless are inside a lateximage, since it would appear in the image:

```
    \ifnumcomp{\value{LWR@lateximagedepth}}{>}{0}%
    {}%
    {% not lateximage
```

If not doing a lateximage, create an HTML ID tag.

```
        \LWR@sanitize{#1}%
        \ifbool{LWR@insidemathcomment}%
        {% inside HTML math comment
            \LWR@label@inmathcomment%
```

```
        }% inside HTML math comment
        {% not inside HTML math comment
            \ifbool{LWR@doingstartpars}%
            {% pars allowed
                \ifbool{LWR@doingapar}%
                {% par started
                    \LWR@label@subcreatetag%
                }% par started
                {% par not started
                    \LWR@stoppars%
                    \LWR@label@subcreatetag%
                    \LWR@startpars%
                }% par not started
            }% pars allowed
            {% pars not allowed
                    \LWR@label@subcreatetag%
            }% pars not allowed
        }% not inside HTML math comment
    }% not lateximage
}
```

`\LWR@new@label` {⟨*label*⟩}

`\label` during HTML output when not in SVG math mode, removing extra spaces around the label, as done by a regular LaTeX `\label`.

The is also used during a `lateximage`, including SVG math, since the special label handling is required, but `\LWR@label@createtag` does not generate HTML tags inside a `lateximage`.

If memoir is used, it's `\@mem@old@label` is pointed here.

clevereref later encases this to add its own cross-referencing, and also patches memoir.

```
\NewDocumentCommand{\LWR@new@label}{m}{%
    \LWR@traceinfo{LWR@new@label: starting}%
    \LWR@traceinfo{LWR@new@label: !#1!}%
% \@bsphack%
```

Create a traditional LaTeX label, as modified by cleveref:

```
    \LWR@orig@label{#1}%
```

Create a special label which holds the section number, `LWR@htmlfilenumber`, `LWR@lateximagedepth`, and `LWR@lateximagenumber`:

```
    \LWR@traceinfo{%
        LWR@new@label: filesectionnames is %
        \ifbool{FileSectionNames}{true}{false}%
    }%
    \LWR@traceinfo{%
        LWR@new@label: LWR@thisfilename is !\LWR@thisfilename!%
    }%
    \LWR@traceinfo{%
        LWR@new@label: LWR@htmlfilenumber is \arabic{LWR@htmlfilenumber}%
    }%
```

```
    \LWR@write@lwarplabel{#1}%
    \LWR@label@createtag{#1}%
    % \@esphack%
    \LWR@traceinfo{LWR@new@label: done}%
}
```

## 75.4 References

\LWR@addlinktitle

```
\newcommand*{\LWR@addlinktitle}{%
    \ifdefvoid{\LWR@ThisAltText}{}{ % space
        title=\textquotedbl\LWR@ThisAltText\textquotedbl\ % space
        \gdef\LWR@ThisAltText{}%
    }%
}
```

\LWR@startref {⟨*label*⟩} (Common code for \ref and \nameref.)

Open an HTML tag reference to a filename, # character, and a label.

```
\newcommand*{\LWR@startref}[1]
{%
    \LWR@sanitize{#1}%
    \LWR@traceinfo{LWR@startref A: !#1!}%
```

Create the filename part of the link:

```
    \LWR@htmltag{a href=\textquotedbl%
    \LWR@traceinfo{LWR@startref B}%
    \LWR@print@mbox{\LWR@htmlrefsectionfilename{#1}}%
    \LWR@traceinfo{LWR@startref C}%
    \LWR@origpound%
```

Create the destination id:

See if LWR@lateximagedepth is unknown:

```
    \LWR@traceinfo{LWR@startref D: !#1!}%
    \ifcsundef{r@#1@lwarp}%
```

"??" if LWR@lateximagedepth is unknown, so create a link with an unknown destination:

```
    {%
        \LWR@traceinfo{LWR@startref D0: ??}%
        ??%
    }%
```

If LWR@lateximagedepth is known. Use a lateximage if the depth is greater than zero, or a regular link otherwise:

```
    {%
```

```
        \ifthenelse{\cnttest{\LWR@lateximagedepthref{#1}}{>}{0}}%
            {%
                lateximage-\BaseJobname-\LWR@lateximagenumberref{#1}%
            }%
            {%
                \LWR@traceinfo{LWR@startref D3}%
```

\detokenize is used to allow underscores in the labels:

```
                \LWR@print@mbox{\LWR@sanitized}%
            }%
    }%
    \LWR@traceinfo{LWR@startref E}%
```

Closing quote:

```
    \textquotedbl%
```

Maybe add a title:

```
    \LWR@addlinktitle%
    }%
    \LWR@traceinfo{LWR@startref F}%
}
```

\LWR@subnewref {⟨*label*⟩} {⟨*label or sub@label*⟩}

Factored for the subfig package. Uses the original label for the hyper-reference, but prints its own text, such as "1(b)".

```
\NewDocumentCommand{\LWR@subnewref}{m m}{%
    \LWR@traceinfo{LWR@subnewref #1 #2}%
    \LWR@startref{#1}%
    \LWR@print@ref{#2}%
    \LWR@htmltag{/a}%
}
```

\ref * {⟨*label*⟩} \ref is redefined to \LWR@HTML@ref, except inside the text part of a \hyperref, where it is redefined to \LWR@ref@ignorestar.

\LWR@HTML@ref * {⟨*label*⟩} Create an internal document reference link, or without a link if starred per hyperref.

hyperref defines a starred version. Since hyperref is only emulated, the starred version is defined here for print mode, in case \ref is used inside SVG math:

```
\LWR@absorbstar{ref}%
```

The HTML version:

```
\NewDocumentCommand{\LWR@HTML@ref}{s m}{%
```

```
    \LWR@traceinfo{LWR@HTML@ref !#2!}%
    \IfBooleanTF{#1}%
        {\LWR@print@ref{#2}}%
        {\LWR@subnewref{#2}{#2}}%
}

\LWR@formatted{ref}
```

For MathJax:

```
\CustomizeMathJax{\let\LWRref\ref}
\CustomizeMathJax{\renewcommand{\ref}{\ifstar\LWRref\LWRref}}
```

\pagerefPageFor Text for page references.

```
\newcommand*{\pagerefPageFor}{see }
```

\pageref *{label} Create an internal document reference, or just the unlinked number if starred, per hyperref.

```
\NewDocumentCommand{\LWR@new@pageref}{s m}{%
    \IfBooleanTF{#1}%
        {(\pagerefPageFor\LWR@print@ref{#2})}%
        {(\cpageref{#2})}%
}
```

\nameref *{label}

```
\newrobustcmd*{\nameref}[1]{%
    \LWR@traceinfo{nameref}%
    \LWR@startref{#1}%
    \LWR@traceinfo{nameref B}%
    \LWR@nameref{#1}%
    \LWR@traceinfo{nameref C}%
    \LWR@htmltag{/a}%
    \LWR@traceinfo{nameref: done}%
}
```

\Nameref *{label} In print, adds the page number. In html, does not.

```
\LetLtxMacro\Nameref\nameref
```

## 75.5 Hyper-references

⚠ Note that the code currently only sanitizes the underscore character. Additional characters should be rendered inert as well. See the hyperref.sty definition of \gdef\hyper@normalise for an example.

Pkg hyperref

```
    \renewrobustcmd{\textup}[1]{\LWR@HTML@textup{\LWR@doindexentry{##1}}}%
    \renewrobustcmd{\textsc}[1]{\LWR@HTML@textsc{\LWR@doindexentry{##1}}}%
    \renewrobustcmd{\textulc}[1]{\LWR@HTML@textulc{\LWR@doindexentry{##1}}}%
    \renewrobustcmd{\textsi}[1]{\LWR@HTML@textsi{\LWR@doindexentry{##1}}}%
    \renewrobustcmd{\textit}[1]{\LWR@HTML@textit{\LWR@doindexentry{##1}}}%
    \renewrobustcmd{\textsl}[1]{\LWR@HTML@textsl{\LWR@doindexentry{##1}}}%
}
```

`\hyperindexref` {⟨*list of LWR@autoindex, commas, and ranges*⟩}

`\hyperindexref{LWR@autoindex}` is inserted into `*.ind` by the ***makeindex*** style file `lwarp.ist` or the ***xindy*** style file `lwarp.xdy`. For ***xindex***, `\hyperpage` is inserted, which is `\let` to `\hyperindexref`. For ***gindex***, `\addindexitem` and related are inserted, which are defined to use `\hyperindexref`.

The argument is split at commas, and also for ranges, then passed to `\LWR@hyperindexrefsub`.

```
\newcommand*{\hyperindexref}[1]{%
    \relax% required
    \expandafter\LWR@hyperindexref@comma\expandafter{\IndexPageSeparator}{#1}%
}
```

`\LWR@hyperindexref@comma` {⟨*separator*⟩} {⟨*list of args*⟩}

The list is split at commas, and passed to `\LWR@hyperindexref@@comma`.

```
\NewDocumentCommand{\LWR@hyperindexref@comma}
    {m >{\SplitList{#1}} m}
    {%
```

Used to place the separtor between each entry, but not before the first.

```
        \def\LWR@hyperindexref@thiscomma{}%
        \def\LWR@hyperindexref@nextcomma{#1}%
```

Each comma-delimited entry is now passed individually to `\LWR@hyperindexref@@comma`.

```
        \ProcessList{#2}\LWR@hyperindexref@@comma%
    }
```

`\LWR@hyperindexref@@comma` {⟨*arg, perhaps with a range*⟩}

A comma separator is placed if not the first item, then the range is parsed.

```
\newcommand*{\LWR@hyperindexref@@comma}[1]{%
    \LWR@hyperindexref@thiscomma%
    \renewcommand{\LWR@hyperindexref@thiscomma}{\LWR@hyperindexref@nextcomma}%
   \expandafter\LWR@hyperindexref@range\expandafter{\IndexRangeSeparator}{#1}%
}
```

`\LWR@hyperindexref@range` {⟨*range delimiter*⟩} {⟨*arg*⟩}

```
\NewDocumentCommand{\LWR@hyperindexref@range}
    {m >{\SplitArgument{1}{#1}} m}
    {\LWR@hyperindexrefsub#2}
```

`\LWR@hyperindexrefsub` {⟨*range start: LWR@autoindex*⟩} {⟨*range end, or* -NoValue-⟩}

Handles the start and end of a range, if applicable.

```
\newcommand*{\LWR@hyperindexrefsub}[2]{%
    \LWR@hyperindexrefsubtwo{#1}%
    \IfValueT{#2}{%
        \IndexRangeSeparator%
        \LWR@hyperindexrefsubtwo{#2}%
    }%
}
```

`\LWR@hyperindexrefsubtwo` {⟨*LWR@autoindex*⟩}

```
\newcommand*{\LWR@hyperindexrefsubtwo}[1]{%
```

In long index lines with numerous entries, *makeindex* can insert a newline before the page number, resulting in an extra space before the first digit. If the first character is a space, remove it first.

```
    \edef\LWR@tempone{#1}%
    \IfBeginWith{\LWR@tempone}{ }{%
        \StrGobbleLeft{\LWR@tempone}{1}[\LWR@tempone]%
    }{}%
```

If a numeric entry, create a link. If not numeric, such as `\see`, use the entry as-is. `\emph`, `\textit`, etc. have been redefined above to create and format the entry.

```
    \IfInteger{\LWR@tempone}%
        {\LWR@indexnameref{\LWR@tempone}}%
        {%
            \begingroup%
            \LWR@hyperindexrefnullified%
            #1%
            \endgroup%
        }%
}
```

`\hyperpage` Emulate hyperref.

```
\LetLtxMacro\hyperpage\hyperindexref
```

`\nohyperpage` Emulate hyperref.

```
\def\nohyperpage#1{}
```

`\hyperindexformat` Emulate hyperref.

```
\def\hyperindexformat#1#2{%
    #1{\hyperpage{#2}}%
}%

\end{warpHTML}
```

**for PRINT output:** A null command for print mode, in case hyperref was not used:

```
\begin{warpprint}
\newcommand{\hyperindexref}[1]{#1}
\end{warpprint}
```

**for HTML & PRINT:** For the glossaries package, try to prevent an error where `\glo@name` was not found:

```
\begin{warpall}
\providecommand{\glo@name}{}
\end{warpall}
```

# 79 Bibliography presentation

**for HTML output:**

```
\begin{warpHTML}
```

`\bibliography` {⟨*filenames*⟩} At one time this was modified to read `\BaseJobname.bbl`, which meant the HTML version could not resolve until the print version was also present. This also confused multibib. It has been reverted to the original to use `\jobname.bbl`.

`\@biblabel` {⟨*text-refnumber*⟩}

```
\renewcommand{\@biblabel}[1]{[#1]\quad}
```

Env `thebibliography` To emphasize document titles in the bibliography, the following redefines `\em` inside `thebibliography` to gather everything until the next closing brace, then display these tokens with `\textit`.

*Adapted from* `embracedef.sty`, *which is by* Takayuki YATO*:*
https://gist.github.com/zr-tex8r/b72555e3e7ad2f0a37f1

```
\AtBeginDocument{

\AtBeginEnvironment{thebibliography}{

\providecommand*{\LWR@newem}[1]{\textit{#1}}

\renewrobustcmd{\em}{%
  \begingroup
    \gdef\LWR@em@after{\LWR@em@finish\LWR@newem}%
    \afterassignment\LWR@em@after
    \toks@\bgroup
}

```

```
\def\LWR@em@finish#1{%
    \xdef\LWR@em@after{\noexpand#1{\the\toks@}}%
  \endgroup
  \LWR@em@after\egroup
}

}% \AtBeginEnvironment{thebibliography}

}% \AtBeginDocument
```

```
\end{warpHTML}
```

# 80 Restoring original formatting

**for HTML output:**

```
\begin{warpHTML}
```

`\LWR@restoreMathJaxformatting`

A few macros (ref: tcolorbox) must be treated separately while printing the HTML comment for a MathJax expression. These are set here, to which other functions may be appended.

```
\newcommand*{\LWR@restoreMathJaxformatting}{}
```

`\LWR@restoreorigformatting`

Used to temporarily restore the print-mode meaning of a number of formatting, graphics, and symbols-related macros while generating SVG math or a `lateximage`.

Must be used inside a group.

Sets `\LWR@formatting` to `print` until the end of the group.

A number of packages will `\appto` additional actions to this macro.

Various packages add to this macro using `\appto`.

```
\newcommand*{\LWR@restoreorigformatting}{%
    \LWR@traceinfo{LWR@restoreorigformatting}%
```

Numerous macros change their print/HTML meaning depending on `\LWR@formatting`:

```
    \renewcommand*{\LWR@formatting}{print}%
    \linespread{1}%

    \let\par\LWR@origpar%

    \LWR@select@print@hspace%

    \LetLtxMacro\hfil\LWR@orighfil%
    \let\hss\LWR@orighss%
    \let\llap\LWR@origllap%
    \let\rlap\LWR@origrlap%
    \let\hfilneg\LWR@orighfilneg%
```

```
    \let\,\LWR@origcomma% disable HTML short unbreakable space
    \let\thinspace\LWR@origthinspace% disable HTML short unbreakable space
  \let\negthinspace\LWR@orignegthinspace% disable HTML negative short unbreakable space
    \let\textellipsis\LWR@origtextellipsis%

    \let\vdots\LWR@origvdots%

    \let\textless\LWR@origtextless%
    \let\textgreater\LWR@origtextgreater%

    \let\&\LWR@origampersand%

    \LetLtxMacro\em\LWR@origem%
    \LetLtxMacro\normalfont\LWR@orignormalfont%
    \let\sp\LWR@origsp%
    \let\sb\LWR@origsb%
    \LetLtxMacro\underline\LWR@origunderline%
    \let~\LWR@origtilde%
    \let\enskip\LWR@origenskip%
    \let\quad\LWR@origquad%
    \let\qquad\LWR@origqquad%
```

`\endtabular` must be restored to its original, instead of relying on lwarp's `\LWR@formatted` mechanism:

```
    \LetLtxMacro\endtabular\LWR@origendtabular%
    \csletcs{endtabular*}{LWR@origendtabular*}%

    \LetLtxMacro\noalign\LWR@orignoalign%
    \LetLtxMacro\hline\LWR@orighline%

    \let\newline\LWR@orignewline%
    \LetLtxMacro\includegraphics\LWR@origincludegraphics%

    \LetLtxMacro\@ensuredmath\LWR@origensuredmath%

    \let\math\LWR@orig@math%
    \let\endmath\LWR@orig@endmath%
    \let\displaymath\LWR@orig@displaymath%
    \let\enddisplaymath\LWR@orig@enddisplaymath%
%
    \LWR@restoreorigaccents%
    \LWR@restoreoriglists%
%
    \LWR@hook@processingtags%
```

To enable MathJax-specific nullification, used for tcolorbox:

```
    \ifboolexpr{bool{mathjax} or ( bool{FormatWP} and bool{WPMarkMath} ) }%
        {\LWR@restoreMathJaxformatting}%
        {}%
}
```

```
\end{warpHTML}
```

# 81 Nullifying filename formatting

The following are used to nullify certain macros and environments while converting section names to file names.

**for HTML output:**

```
\begin{warpHTML}
```

Also commonly used are `\@empty`, `\@gobble`, and `\@firstofone`.

```
\newcommand*{\LWR@dash}{-}
```

`\LWR@nullfonts` Removes formatting during filename operations, file references, and HTML comments.

⚠ Use only inside a group.

The following are *not* made robust, since they must be expanded to their nullified versions.

```
\catcode`\$=\active% redefining $ below
\catcode`\_=12% redefining \_ below
\newcommand*{\LWR@nullfonts}{%
```

Various built-in symbols.

```
    \renewcommand*{\$}{-}%
    \renewcommand*{\%}{-}%
    \renewcommand*{\_}{-}%
    \renewcommand*{\}}{-}%
    \renewcommand*{\{}{-}%
    \renewcommand*{\&}{-}% used to be 'and'
    \renewcommand*{\#}{-}%
    \renewcommand*{\,}{-}%
    \renewcommand*{~}{-}%
%
% accents:
    \renewcommand*{\`}[1]{##1}%
    \renewcommand*{\'}[1]{##1}%
    \renewcommand*{\^}[1]{##1}%
    \renewcommand*{\~}[1]{##1}%
    \renewcommand*{\=}[1]{##1}%
    \renewcommand*{\u}[1]{##1}%
    \renewcommand*{\.}[1]{##1}%
    \renewcommand*{\"}[1]{##1}%
    \renewcommand*{\H}[1]{##1}%
    \renewcommand*{\v}[1]{##1}%
    \renewcommand*{\d}[1]{##1}%
    \renewcommand*{\c}[1]{##1}%
    \renewcommand*{\b}[1]{##1}%
    \renewcommand*{\t}[1]{##1}%
%
    \let\newline\LWR@dash%
```

```
    \let\textasciicircum\LWR@dash%
    \let\textasciitilde\LWR@dash%
    \let\textasteriskcentered\LWR@dash%
    \let\textbackslash\LWR@dash%
    \let\textbar\LWR@dash%
    \let\textbardbl\LWR@dash%
    \let\textbigcircle\LWR@dash%
    \let\textbraceleft\LWR@dash%
    \let\textbraceright\LWR@dash%
    \let\textbullet\LWR@dash%
    \let\textcopyright\LWR@dash%
    \let\textdagger\LWR@dash%
    \let\textdaggerdbl\LWR@dash%
    \let\textdollar\LWR@dash%
    \let\textellipsis\LWR@dash%
    \let\textemdash\LWR@dash%
    \let\textendash\LWR@dash%
    \let\textexclamdown\LWR@dash%
    \let\textgreater\LWR@dash%
    \let\textless\LWR@dash%
    \let\textordfeminine\LWR@dash%
    \let\textordmasculine\LWR@dash%
    \let\textparagraph\LWR@dash%
    \let\textperiodcentered\LWR@dash%
    \let\textpertenthousand\LWR@dash%
    \let\textperthousand\LWR@dash%
    \let\textquestiondown\LWR@dash%
    \let\textquotedblleft\LWR@dash%
    \let\textquotedblright\LWR@dash%
    \let\textquoteleft\LWR@dash%
    \let\textquoteright\LWR@dash%
    \let\textregistered\LWR@dash%
    \let\textsection\LWR@dash%
    \let\textsterling\LWR@dash%
    \let\texttrademark\LWR@dash%
    \let\textunderscore\LWR@dash%
    \let\textvisiblespace\LWR@dash%
    \let\copyright\LWR@dash%
    \let\dag\LWR@dash%
    \let\ddag\LWR@dash%
    \let\dots\LWR@dash%
    \let\P\LWR@dash%
    \let\pounds\LWR@dash%
    \let\S\LWR@dash%
%
    \renewcommand*{\aa}{a}%
    \renewcommand*{\AA}{A}%
    \renewcommand*{\AE}{AE}%
    \renewcommand*{\ae}{ae}%
    \renewcommand*{\dh}{d}%
    \renewcommand*{\DH}{D}%
    \renewcommand*{\DJ}{D}%
    \renewcommand*{\dj}{d}%
    \renewcommand*{\IJ}{IJ}%
    \renewcommand*{\ij}{ij}%
```

```
    \renewcommand*{\L}{L}%
    \renewcommand*{\l}{l}%
    \renewcommand*{\NG}{NG}%
    \renewcommand*{\ng}{ng}%
    \renewcommand*{\O}{O}%
    \renewcommand*{\o}{o}%
    \renewcommand*{\oe}{oe}%
    \renewcommand*{\OE}{OE}%
    \renewcommand*{\ss}{ss}%
    \renewcommand*{\SS}{SS}%
    \renewcommand*{\th}{th}%
    \renewcommand*{\TH}{TH}%
%
    \let\guillemotleft\@empty%
    \let\guilsinglleft\@empty%
    \let\quotedblbase\@empty%
    \let\textquotedbl\@empty%
    \let\guillemotright\@empty%
    \let\guilsinglright\@empty%
    \let\quotesinglbase\@empty%

    \renewcommand*{\HTMLunicode}[1]{}%
    \renewcommand*{\HTMLentity}[1]{}%

    \renewcommand{\textsuperscript}[1]{##1}%
    \renewcommand{\textsubscript}[1]{##1}%


    \renewcommand{\underline}[1]{##1}%


    \RenewDocumentCommand{\hspace}{s m}{}%

    \RenewDocumentCommand{\LWR@htmlspanclass}{o m +m}{##3}%
    \DeclareExpandableDocumentCommand{\InlineClass}{D{(}{)}{} o m +m}{##4}%
```

Nullify math macros.

```
    \def\(##1\){}%
    \def\[##1\]{}%
    \RenewDocumentCommand{\LWR@subsingledollar}{s m m m}{}%
```

Nullify logos:

```
    \renewcommand*{\TeX}{TeX}%
    \renewcommand*{\LaTeX}{LaTeX}%
    \renewcommand*{\LaTeXe}{LaTeX2e}%
    \renewcommand*{\LuaTeX}{LuaTeX}%
    \renewcommand*{\LuaLaTeX}{LuaLaTeX}%
    \renewcommand*{\XeTeX}{XeTeX}%
    \renewcommand*{\XeLaTeX}{XeLaTeX}%
    \renewcommand*{\ConTeXt}{ConTeXt}%
    \renewcommand*{\BibTeX}{BibTeX}%
    \renewcommand*{\MakeIndex}{MakeIndex}%
    \renewcommand*{\AmS}{AmS}%
```

\MathImageAltText — The HTML `alt` tag for an SVG math image.
Default: "math image"

```
\newcommand*{\MathImageAltText}{math image}
```

\LWR@ThisAltText — The HTML `alt` tag for the next image. Cleared after use, and also after each `lateximage`, `\LWR@subsingledollar`, and each use of MathJax.

```
\newcommand*{\LWR@ThisAltText}{}
```

\ThisAltText {⟨*text*⟩}

Assigns the HTML `alt` tag for the next image generated by lwarp, such as a `lateximage`, `picture`, or SVG math.

```
\newcommand*{\ThisAltText}[1]{%
    \renewcommand{\LWR@ThisAltText}{#1}%
}
```

\PackageDiagramAltText — Appended to the `lateximage` HTML `alt` tag for the images generated by many packages.
Default: "diagram"

```
\newcommand*{\PackageDiagramAltText}{diagram}
```

```
\end{warpall}
```

## 82.3 Inline and display math

**for HTML output:**

```
\begin{warpHTML}
```

Ctr LWR@externalfilecnt — Counter for the external files which are generated and then referenced from the HTML:

```
\newcounter{LWR@externalfilecnt}
```

Bool LWR@indisplaymathimage — True if processing display math for SVG output. Inside a `lateximage`, display math is only set to print-mode output if `LWR@indisplaymathimage` is false. Used to avoid nullifying display math before it has been completed.

```
\newbool{LWR@indisplaymathimage}
```

Bool LWR@insidemathcomment — True while inside an HTML comment which is displaying a math environment. Used to undo the comment for a moment while creating a `\label`, so that the label's HTML tags will be seen by HTML.

```
\newbool{LWR@insidemathcomment}
\boolfalse{LWR@insidemathcomment}
```

Bool LWR@xfakebold — True if xfakebold `\setBold` is in use.

```
\newbool{LWR@xfakebold}
\boolfalse{LWR@xfakebold}
```

baseline or width of the inline math image. The best results are obtained when using graphicx.

\LWR@addbaselinemarker Places a small marker in an SVG inline image. If graphics or graphicx are loaded, the marker is a mostly transparent image. If neither is loaded, no marker is used.

```
\AtBeginDocument{

\ifpdf
    \newcommand*{\LWR@baselinename}{lwarp_baseline_marker.png}
\else
    \ifXeTeX
        \newcommand*{\LWR@baselinename}{lwarp_baseline_marker.png}
    \else
        \newcommand*{\LWR@baselinename}{lwarp_baseline_marker.eps}
    \fi
\fi

\IfFileExists{\LWR@baselinename}%
{
    \@ifpackageloaded{graphicx}{
        \newcommand*{\LWR@addbaselinemarker}{%
            \LWR@origincludegraphics{\LWR@baselinename}%
        }
    }{
        \@ifpackageloaded{graphics}{
            \newcommand*{\LWR@addbaselinemarker}{%
                \LWR@origincludegraphics{\LWR@baselinename}%
            }
        }{
            \newcommand*{\LWR@addbaselinemarker}{%
                \global\booltrue{LWR@warnbaselinemarker}%
            }
            \AtEndDocument{
                \ifbool{LWR@warnbaselinemarker}{
                    \PackageWarningNoLine{lwarp}{%
                        Load graphicx or graphics for improved\MessageBreak
                        SVG math sizing and baselines%
                    }
                }{}
            }
        }
    }
}{% lwarp_baseline_marker.png or .eps is not present
    \newcommand*{\LWR@addbaselinemarker}{%
        \global\booltrue{LWR@warnbaselinemarker}%
    }
    \AtEndDocument{
        \ifbool{LWR@warnbaselinemarker}{
            \PackageWarningNoLine{lwarp}{%
                File \LWR@baselinename\space is not installed\MessageBreak
                alongside the lwarp-*.sty files, so\MessageBreak
                SVG math sizing and baselines may not be accurate}
        }{}
    }
```

```
}

}% AtBeginDocument
```

Bool LWR@warnbaselinemarker — True if the math baseline marker was ever called for, but graphics or graphicx were not loaded.

```
\newbool{LWR@warnbaselinemarker}
\boolfalse{LWR@warnbaselinemarker}
```

Bool LWR@unknownmathsize — If Ti*k*z or other objects are used inside math mode, the resulting image may exceed the TEX box, resulting in an incorrect measurement of the size of the resulting image. If this is so, the HTML styles for image size and depth will be neutralized.

```
\newbool{LWR@unknownmathsize}
```

\LWR@singledollarmeasure {⟨*math expression*⟩}

Measures the size of the image of the math expression.

(In some circumstances SVG math is used even if MathJax is preferred.)

**SVG math:** \LWR@origensuredmath is part of argument #4.

**SVG math \ensuremath:** \LWR@origensuredmath is part of argument #4.

**SVG dynamic math:** \LWR@origensuredmath is part of argument #4.

**MathJax:** Argument #4 is the contents of the math expression without \LWR@origensuredmath. This case is handled above.

**MathJax \ensuremath:** \LWR@origensuredmath is part of argument #4.

**MathJax dynamic math:** Argument #4 is the contents of the math expression without \LWR@origensuredmath, so \LWR@origensuredmath is added below.

**\ifmmode:** Included "just in case".

Factored from \LWR@subsingledollarsvg.

```
\newcommand*{\LWR@singledollarmeasure}[1]{%
    \begingroup%
```

Temporarily disable formatting while measuring the image parameters:

```
    \LWR@restoreorigformatting%
    \RenewDocumentEnvironment{lateximage}{s o s o o}{}{}% inside group
    \LWR@print@normalsize%
```

Temporarily set font for the HTML PDF output:

```
    \LWR@setcurrentfont%
```

```
    \setlength{\LWR@singledollarwidth}{%
        \LateximageFontScale\wd\LWR@singledollarbox%
    }%
    \global\LWR@singledollarwidth=\LWR@singledollarwidth%
```

Likewise for total height:

```
    \setlength{\LWR@singledollarheight}{%
        \LateximageFontScale\ht\LWR@singledollarbox%
    }%
    \addtolength{\LWR@singledollarheight}{%
        \LateximageFontScale\dp\LWR@singledollarbox%
    }%
    \global\LWR@singledollarheight=\LWR@singledollarheight%

    \endgroup%
}
```

`\LWR@subsingledollarsvg` * {⟨*2: alt text*⟩} {⟨*3: add'l hashing*⟩} {⟨*4: math expression*⟩}

For inline math. Uses SVG math. The image is measured and ajusted to the baseline of the HTML output, and placed inside a `lateximage`.

(In some circumstances SVG math is used even if MathJax is preferred.)

Factored from `\LWR@subsingledollar`.

```
\newcommand*{\LWR@subsingledollarsvg}[4]{%
```

Measure the depth, width, and height of the math image:

```
    \LWR@singledollarmeasure{#4}%
```

Set a style for the the height or width. The `em` unit is used so that the math scales according to the user's selected font size.

Start with the greater of the width or the height, biased towards the width:

```
    \ifdimgreater{\LWR@singledollarwidth}{.7\LWR@singledollarheight}{%
        \def\LWR@singledollarstyle{%
            width:\LWR@convertto{em}{\the\LWR@singledollarwidth} em%
        }%
    }{%
        \def\LWR@singledollarstyle{%
            height:\LWR@convertto{em}{\the\LWR@singledollarheight} em%
        }%
    }%
```

If a very narrow width, use the height.

```
    \ifdimless{\LWR@singledollarwidth}{.2em}%
    {%
        \def\LWR@singledollarstyle{%
            height:\LWR@convertto{em}{\the\LWR@singledollarheight} em%
```

```
        }%
    }%
    {}%
```

If very wide and short, use the width:

```
    \ifdimless{\LWR@singledollarheight}{.2em}%
    {%
        \def\LWR@singledollarstyle{%
            width:\LWR@convertto{em}{\the\LWR@singledollarwidth} em%
        }%
    }%
    {}%
```

If there is significant text depth, add the depth to the style.

```
    \ifdimgreater{\LWR@singledollardepth}{0.05ex}{%
        \def\LWR@singledollardepthstyle{%
            \ ; % extra space
            \LWR@print@mbox{%
            vertical-align:-\LWR@convertto{em}{\the\LWR@singledollardepth} em%
            } % extra space
        }%
    }{%
        \def\LWR@singledollardepthstyle{}%
    }%
```

If using certain Ti*k*z actions inside math, the resulting image may exceed the TEX boundaries, so the HTML size styles may be incorrect, and must be neutralized.

```
    \ifbool{LWR@unknownmathsize}{%
        \def\LWR@singledollarstyle{}%
        \def\LWR@singledollardepthstyle{}%
    }{}%
```

Create the `lateximage` using the alternate tag and the computed size and depth. The star causes `lateximage` to use an MD5 hash as the filename. When hashing, also include the current font and color in the hash.

```
    \ifbool{LWR@dynamicmath}{%
        \LWR@traceinfo{subsingledollar: dynamic}%
        \begin{lateximage}% no hashing
            [\MathImageAltText]% alt tag
            []% no add'l hashing
            [\LWR@singledollarstyle \LWR@singledollardepthstyle]% CSS
    }{% not dynamic math
        \LWR@traceinfo{subsingledollar: static}%
        \IfValueTF{#1}{% #1 True
            \LWR@findcurrenttextcolor% sets \LWR@tempcolor
```

Support for xfakebold:

```
            \ifbool{LWR@xfakebold}%
                {\def\LWR@tempone{Y}}%
                {\def\LWR@tempone{N}}%
```

```
            \begin{lateximage}*% use hashing
                [#2]% alt
                *% do not add open/closing braces
                [% addl' hashing
                    #3%
                    FM\LWR@f@family%
                    SR\LWR@f@series%
                    SH\LWR@f@shape%
                    SHC\LWR@f@shapecaps%
                    CL\LWR@tempcolor%
                    FB\LWR@tempone% xfakebold
                ]%
                [\LWR@singledollarstyle \LWR@singledollardepthstyle]% CSS
        }{% #1 False
            \begin{lateximage}% no hashing
                [#2]% alt
                []% no add'l hashing
                [\LWR@singledollarstyle \LWR@singledollardepthstyle]% CSS
        }%
    }% not dynamic math
```

Place small and almost transparent markers on the baseline at the left and right edges of the image. These markers are seen by *pdfcrop*, and force vertically-centered objects such as a dash to be raised off the baseline in the cropped image, and also force the total width and left/right margins to be correct. (Except that in some fonts a character may exceed the bounding box, and thus may appear wider than expected when converted to an image.)

```
    \LWR@addbaselinemarker%
```

Support for xfakebold:

```
    \LWR@applyxfakebold%
```

Typeset the contents:

```
    \usebox{\LWR@singledollarbox}%
```

The closing baseline marker:

```
    \LWR@addbaselinemarker%

    \end{lateximage}%
%
}
```

`\LWR@subsingledollar` * {⟨*2: alt text*⟩} {⟨*3: add'l hashing*⟩} {⟨*4: math expression*⟩}

For inline math. Uses MathJax, or for SVG math the image is measured and ajusted to the baseline of the HTML output, and placed inside a `lateximage`.

**SVG math:** `\LWR@origensuredmath` is part of argument #4.

**SVG math `\ensuremath`:** `\LWR@origensuredmath` is part of argument #4.

**SVG dynamic math:** `\LWR@origensuredmath` is part of argument #4.

**MathJax:** Argument #4 is the contents of the math expression without `\LWR@origensuredmath`. This case is handled above.

**MathJax `\ensuremath`:** `\LWR@origensuredmath` is part of argument #4.

**MathJax dynamic math:** Argument #4 is the contents of the math expression without `\LWR@origensuredmath`, so `\LWR@origensuredmath` is added below.

image filename hashing

If starred, a hashed filename is used.If so, the hash is based on the `alt` tag and also the additional hashing argument.

This may be used to provide an expression with a simple `alt` tag but also enough additional information to provide a unique hash.

An example is when the expression is a complicated TeX expression, which would not copy/paste well. A simplified tag may be used, while the complicated expression is duplicated in the additional hashing argument.

Another example is when the expression is simple, but the image depends on options. These options may be decoded into text form and included in the additional hashing argument in order to make the hash unique according to the set of options, even if the simple `alt` tag is still the same.

```
\newlength{\LWR@singledollarwidth}
\newlength{\LWR@singledollarheight}
\newlength{\LWR@singledollardepth}

\newsavebox{\LWR@singledollarbox}

\NewDocumentCommand{\LWR@subsingledollar}{s m m m}{%
    \LWR@traceinfo{LWR@subsingledollar}%

    \ifnumcomp{\value{LWR@lateximagedepth}}{>}{0}%
    {%
        \LWR@traceinfo{LWR@subsingledollar: already in a lateximage}%
            #4% contents
    }%
    {% not in a lateximage
        \begingroup%
```

Support for xfakebold:

```
        \LWR@applyxfakebold%
```

MathJax cannot parse the often complicated TeX expressions which appear in the various uses of `\ensuredmath`. `\ensuremath` forces the `alt` tag to "`(math image)`", as translated according to `\MathImageAltText`. If this is the case, force the use of a `lateximage` even if MathJax. Likewise for siunitx if `parse-numbers=false`.

If MathJax, or if formatting math for a word processor, and not `\ensuredmath`, and not a dynamic math expression, print the math expression:

Clear the single-use `alt` text:

```
\gdef\LWR@ThisAltText{}%
}%
```

`\LWR@singledollar` {⟨*alt text*⟩} {⟨*math expression*⟩}

```
\protected\gdef\LWR@singledollar#1${%
\ifbool{mathjax}{%
    \LWR@subsingledollar*%
    {% alt tag
        \textbackslash( %
        \LWR@HTMLsanitize{#1} % extra space
        \textbackslash)%
    }%
    {singledollar}% add'l hashing
    {#1}% contents
}{% not mathjax
    \LWR@subsingledollar*%
    {% alt tag
        \textbackslash( %
        \LWR@HTMLsanitize{#1} % extra space
        \textbackslash)%
    }%
    {singledollar}% add'l hashing
    {\LWR@origensuredmath{#1}}% contents
}% not mathjax
```

Clear the single-use `alt` text:

```
\gdef\LWR@ThisAltText{}%
}
```

`\(` `\[` Redefine to the above dollar macros.

```
\AtBeginDocument{
    \protected\gdef\(#1\){$#1$}
    \protected\gdef\[#1\]{$$#1$$}
}

\endgroup% active $


\AtBeginDocument{
\LetLtxMacro\LWR@openbracketnormal\[
\LetLtxMacro\LWR@closebracketnormal\]
}
```

`\@ensuredmath` {⟨*expression*⟩}

If MathJax, a `lateximage` is used, since `\ensuremath` is often used for complex TEX expressions which MathJax may not render. If SVG math, a hashed file is used with a simple `alt` tag, but additional hashing provided by the contents.

```
\LetLtxMacro\LWR@origensuredmath\@ensuredmath

\renewcommand{\@ensuredmath}[1]{%
    \ifbool{mathjax}{%
        \LWR@subsingledollar*{\AltTextOpen\MathImageAltText\AltTextClose}%
        {%
            \protect\LWR@HTMLsanitize{\detokenize\expandafter{#1}}%
        }%
        {%
            \relax%
            \LWR@origensuredmath{#1}%
        }%
    }{% SVG math
```

If already inside a `lateximage` in math mode, continue as-is.

```
        \ifmmode%
            \LWR@origensuredmath{#1}%
        \else%
```

Create an inline math `lateximage` with a simple `alt` tag and additional hashing according to the contents.

```
            \ifnumcomp{\value{LWR@lateximagedepth}}{>}{0}%
                {\LWR@origensuredmath{#1}}%
                {%
                    \LWR@subsingledollar*%
                        {\AltTextOpen\MathImageAltText\AltTextClose}%
                     {\protect\LWR@HTMLsanitize{\detokenize\expandafter{#1}}}%
                        {\LWR@origensuredmath{#1}}%
                }%
        \fi%
    }%
```

Clear the single-use `alt` text:

```
    \gdef\LWR@ThisAltText{}%
}
```

Remember then remove the old `math` and `displaymath` environments:

```
\let\LWR@orig@math\math
\let\LWR@orig@endmath\endmath
\let\LWR@orig@displaymath\displaymath
\let\LWR@orig@enddisplaymath\enddisplaymath

\let\math\relax
\let\endmath\relax
\let\displaymath\relax
\let\enddisplaymath\relax
```

Env `math` Set math mode then typeset the body of what was between the begin/end. See the environ package for `\BODY`.

```
\NewEnviron{math}{\expandafter\(\BODY\)}
```

Env LWR@displaymathnormal Set math mode then typeset the body of what was between the begin/end. See the environ package for \BODY.

```
\NewEnviron{LWR@displaymathnormal}{\expandafter\[\BODY\]\@ignoretrue}
```

Set the default displaymath to the normal version:

```
\LetLtxMacro\displaymath\LWR@displaymathnormal%
\LetLtxMacro\enddisplaymath\endLWR@displaymathnormal%
```

Env LWR@displaymathother A version of displaymath which can handle complicated objects, but does not supply MathJax or HTML alt tags.

```
\newenvironment{LWR@displaymathother}
{%
    \begin{BlockClass}{displaymath}%
    \LWR@newautoidanchor%
    \booltrue{LWR@indisplaymathimage}%
    \begin{lateximage}%
    [\MathImageAltText]%
    \LWR@origdollar\LWR@origdollar%
}
{%
    \LWR@origdollar\LWR@origdollar%
    \end{lateximage}%
    \end{BlockClass}%
}
```

Env LWR@equationother A version of displaymath which can handle complicated objects, but does not supply MathJax or HTML alt tags.

```
\newenvironment{LWR@equationother}
{%
    \begin{BlockClass}{displaymathnumbered}%
    \LWR@newautoidanchor%
    \booltrue{LWR@indisplaymathimage}%
    \begin{lateximage}[\MathImageAltText]%
    \LWR@origequation%
}
{%
    \LWR@origendequation%
    \end{lateximage}%
    \end{BlockClass}%
}
```

## 82.4 MathJax support

Ctr LWR@nextequation Used to add one to compute the next equation number.

```
\newcounter{LWR@nextequation}
```

Determing how to set MathJax section and equation numbers. Adjusts for various kinds of \theequation to determine \theMathJaxsection and \theMathJaxequation.

```
\newcommand\LWR@article@theequation{\@arabic\c@equation}

\newcommand\LWR@book@theequation
  {\ifnum \c@chapter>\z@ \thechapter.\fi \@arabic\c@equation}


\newcommand\LWR@chapter@theequation{\thechapter.\arabic{equation}}
\newcommand\LWR@section@thequation{\thesection.\arabic{equation}}
\newcommand\LWR@subsection@thequation{\thesubsection.\arabic{equation}}

\AtBeginDocument{
    % default per article class:
    \newcommand*{\theMathJaxsubequations}{0}
    \newcommand*{\theMathJaxsection}{}
    \newcommand*{\theMathJaxequation}{\arabic{equation}}

    \ifdefstrequal{\theequation}{\LWR@article@theequation}
    {}{
    \ifdefstrequal{\theequation}{\LWR@book@theequation}{
      \renewcommand*{\theMathJaxsection}{\ifnum \c@chapter>\z@ \thechapter.\fi}
    }{
    \ifdefstrequal{\theequation}{\LWR@subsection@thequation}{
        \renewcommand*{\theMathJaxsection}{\thesubsection{}.}
    }{
    \ifdefstrequal{\theequation}{\LWR@section@thequation}{
        \renewcommand*{\theMathJaxsection}{\thesection{}.}
    }{
    \ifdefstrequal{\theequation}{\LWR@chapter@theequation}{
        \renewcommand*{\theMathJaxsection}{\thechapter{}.}
    }{% unknown format
        \PackageWarningNoLine{lwarp}
        {%
            Unknown equation tag format for \protect\theequation.\MessageBreak
            Article-style equation numbering will be used%
        }
    }}}}}
}
```

\LWR@syncmathjax Sets the MathJax equation format and number for the following equations.

These MathJax commands are printed inside "\(" and "\)" characters. They are printed to HTML output, not interpreted by LaTeX.

```
\newcommand*{\LWR@syncmathjax}{%
```

Tell MathJax that the next equation number is the current LaTeX equation number.

Before each equation, lwarp inserts into the HTML code:

```
\seteqnumber{subequations?}{section}{number}
```

**subequations?** is 0 usually, 1 if inside amsmath subequations.

**section** is a string printed as-is, or empty.

**number** is auto-incremented by MathJax between equations.

Place the MathJax command inside "\(" and "\)" characters, to be printed to HTML, not interpreted by LaTeX.

```
        \LWR@stoppars%
        \InlineClass{hidden}{
            \textbackslash(%
            \textbackslash{}seteqnumber%
            \{\theMathJaxsubequations\}%
            \{\theMathJaxsection\}%
            \{\theMathJaxequation\}%
            \textbackslash)%
        }
        \LWR@startpars%
}
```

`\LWR@hidelatexequation` {⟨*environment*⟩} {⟨*contents*⟩}

Creates the LaTeX version of the equation inside an HTML comment.

```
\NewDocumentCommand{\LWR@hidelatexequation}{m +m}{%
```

Stop HTML paragraph handling and open an HTML comment:

```
    \LWR@stoppars
    \LWR@htmlopencomment

```

Start the LaTeX math environment inside the HTML comment:

```
    \begingroup
    \@nameuse{LWR@orig#1}
```

While in the math environment, restore various commands to their LaTeX meanings.

```
    \LWR@restoreorigformatting
    \booltrue{LWR@insidemathcomment}
```

See `\LWR@htmlmathlabel` in section 82.7.1.

Print the contents of the equation:

```
    #2
```

End the LaTeX math environment inside the HTML comment:

```
    \@nameuse{LWR@origend#1}
    \endgroup

```

```
\newcommand*{\LWR@doequation}[2]{%
```

If `mathjax` or `FormatWP`, print the LaTeX expression:

```
    \ifboolexpr{bool{mathjax} or ( bool{FormatWP} and bool{WPMarkMath} ) }%
```

MathJax output:

```
    {
```

Print commands to syncronize MathJax's equation number and format to the current LaTeX chapter/section and equation number:

```
        \LWR@syncmathjax%
```

Print the LaTeX math inside an HTML comment:

```
        \LWR@hidelatexequation{#2}{#1}
    }
```

SVG output: Create the `lateximage` along with an HTML `<alt>` tag having an equation number, the LaTeX equation environment commands, and the contents of the environment's `\BODY`.

```
    {% not mathjax
```

Begin the `lateximage` with an `<alt>` tag containing the math source:

```
        \ifstrequal{#2}{equation*}{%
            \begin{BlockClass}{displaymath}%
        }{%
            \begin{BlockClass}{displaymathnumbered}%
        }%
        \LWR@newautoidanchor%
        \booltrue{LWR@indisplaymathimage}%
        \begin{lateximage}[%
            \ifstrequal{#2}{equation*}{%
                \ifdefequal{\LWR@equationtag}{\theequation}{%
    %                                   no tag was given
                }{%
                    (\LWR@equationtag) % tag was given
                }%
            }{%
                (\LWR@equationtag) % automatic numbering
            }%
            \textbackslash{begin\{#2\}} % extra space
            \LWR@HTMLsanitizeexpand{\detokenize\expandafter{#1}} % extra space
            \textbackslash{end\{#2\}}%
        ]*% alt tag
```

Support for xfakebold:

```
        \LWR@applyxfakebold%
```

Create the actual LaTeX-formatted equation inside the `lateximage` using the contents of the environment.

```
        \@nameuse{LWR@orig#2}%
        #1% contents collected by \collect@body
        \@nameuse{LWR@origend#2}%
        \end{lateximage}%
        \end{BlockClass}%
    }% not mathjax
```

Clear the single-use `alt` text:

```
    \gdef\LWR@ThisAltText{}%
}
```

After the environment, if MathJax, print the math to the HTML output for MathJax processing. If a footnote is used, sync the `footnote` counter before, then unsync after for non-equation environments, as defined next.

```
\newcommand*{\LWR@doendequation}[1]{%
    \ifboolexpr{bool{mathjax} or ( bool{FormatWP} and bool{WPMarkMath} ) }%
    {%
        \IfSubStr{\detokenize\expandafter{\BODY}}{\detokenize{note}}{%
            \InlineClass{hidden}{\LWR@syncnotenumbers}%
            \LWR@addmathjax{#1}{\BODY}%
            \InlineClass{hidden}{\LWR@syncnotenames}%
        }{%
            \LWR@addmathjax{#1}{\BODY}%
        }%
    }{}%

```

Clear the single-use `alt` text:

```
    \gdef\LWR@ThisAltText{}%
}
```

The following are used to syncronize footnote marks and related to MathJax if `*note*` is used inside the MathJax expression. The counter is read from LaTeX then defined into MathJax for use during the following equation. After the equation, the MathJax value is returned to the text from `\footnotename`. Other notes may be added by appending to `\LWR@syncnotenumbers` and `\LWR@syncnotenames`.

`\LWR@synconenotenumber` {⟨*MathJax variable*⟩} {⟨*mark*⟩}

```
\newcommand*{\LWR@synconenotenumber}[2]{%
    \textbackslash(
    \textbackslash{}def\textbackslash{}#1\{#2\}
    \textbackslash)
}
```

`\LWR@syncnotenumbers` Assignments to make.

```
\newcommand*{\LWR@syncnotenumbers}{\LWR@synconenotenumber{LWRfootnote}{\thefootnote}}
```

`\LWR@synconenotename` {⟨*MathJax variable*⟩} {⟨*text*⟩}

```
\newcommand*{\LWR@synconenotename}[2]{%
    \textbackslash(
    \textbackslash{}def\textbackslash{}#1\{#2\}
    \textbackslash)
}
```

`\LWR@syncnotenames` Assignments to make.

```
\newcommand*{\LWR@syncnotenames}{\LWR@synconenotename{LWRfootnote}{\footnotename}}
```

Remove existing `equation` environment:

```
\AtBeginDocument{
    \let\equation\relax
    \let\endequation\relax
    \csletcs{equation*}{relax}
    \csletcs{endequation*}{relax}
}
```

Env `equation` The new `equation` environment is created with `\NewEnviron` (from the environ package), which stores the contents of its environment in a macro called `\BODY`.

```
\AtBeginDocument{
    \NewEnviron{equation}%
        {\LWR@doequation{\BODY}{equation}}%
        [\LWR@doendequation{equation}]

    \LetLtxMacro\LWR@equationnormal\equation
    \LetLtxMacro\endLWR@equationnormal\endequation
}% AtBeginDocument
```

Env `equation*`

```
\AtBeginDocument{
    \NewEnviron{equation*}%
        {\LWR@doequation{\BODY}{equation*}}%
        [\LWR@doendequation{equation*}]

    \csletcs{LWR@equationnormalstar}{equation*}
    \csletcs{LWR@endequationnormalstar}{endequation*}
}% AtBeginDocument
```

Remember the "less" version of `equation`, which uses MathJax and `alt` tags, but does not support complicated contents such as some Ti*k*z expressions.

```
\AtBeginDocument{
    \LetLtxMacro\LWR@equationless\equation
```

```
    \LetLtxMacro\endLWR@equationless\endequation
    \csletcs{LWR@equationlessstar}{equation*}
    \csletcs{LWR@endequationlessstar}{endequation*}
}
```

## 82.6 \displaymathnormal and \displaymathother

\displaymathnormal

By default, or when selecting \displaymathnormal, MathJax math display environments print their contents as text into HTML for MathJax to interpret, and SVG display math environments render their contents as SVG images and use their contents as the alt tag of HTML output. To do so, the contents are loaded into a macro for reuse. In some cases, such as complicated Ti*k*z pictures, compilation will fail.

\displaymathother
MathJax unsupported complicated alt tag

When selecting \displaymathother, it is assumed that the contents are more complicated than "pure" math. An example is an elaborate Ti*k*z picture, which will not render in MathJax and will not make sense as an HTML alt tag. In this mode, MathJax is turned off, math display environments become SVG images, even if MathJax is selected, and the HTML alt tags become simple messages. The contents are internally processed as an environment instead of a macro argument, so complicated objects such as Ti*k*z pictures are more likely to compile successfully.

\displaymathnormal
simple math objects

Use when display math environments have simple math which is to sent to MathJax or included in HTML alt tags.

```
\newcommand*{\displaymathnormal}{%
    \ifbool{LWR@origmathjax}{\booltrue{mathjax}}{\boolfalse{mathjax}}%
    \LetLtxMacro\[\LWR@openbracketnormal%
    \LetLtxMacro\]\LWR@closebracketnormal%
    \LetLtxMacro\displaymath\LWR@displaymathnormal%
    \LetLtxMacro\enddisplaymath\endLWR@displaymathnormal%
    \LetLtxMacro\equation\LWR@equationnormal%
    \LetLtxMacro\endequation\endLWR@equationnormal%
    \csletcs{equation*}{LWR@equationnormalstar}%
    \csletcs{endequation*}{LWR@endequationnormalstar}%
}
```

\displaymathother
complicated math objects

Use when display math environments have complicated objects which will not work with MathJax or should not be included in HTML alt tags. Complicated contents are more likely to compile correctly.

```
\newcommand*{\displaymathother}{%
    \boolfalse{mathjax}%
    \LetLtxMacro\displaymath\LWR@displaymathother%
    \LetLtxMacro\enddisplaymath\endLWR@displaymathother%
    \LetLtxMacro\[\LWR@displaymathother%
    \LetLtxMacro\]\endLWR@displaymathother%
    \LetLtxMacro\equation\LWR@equationother%
    \LetLtxMacro\endequation\endLWR@equationother%
    \csletcs{equation*}{displaymath}%
    \csletcs{endequation*}{enddisplaymath}%
}
```

```
\end{warpHTML}
```

**for PRINT output:**

```
\begin{warpprint}
```

Print-mode versions:

```
\newcommand*{\displaymathnormal}{}
\newcommand*{\displaymathother}{}
```

```
\end{warpprint}
```

**for HTML output:**

```
\begin{warpHTML}
```

## 82.7 AMS Math environments

### 82.7.1 Support macros

Bool `LWR@amsmultline` True if processing a multline environment.

To compensate for `multline`-spefific code, `LWR@amsmultline` is used to add extra horizontal space in `\LWR@htmlmathlabel` if is used in an amsmath environment which is not a `multline` environment and not an `equation`.

```
\newbool{LWR@amsmultline}
\boolfalse{LWR@amsmultline}
```

`\LWR@beginhideamsmath` Starts hiding LaTeX math inside an HTML comment.

```
\newcommand*{\LWR@beginhideamsmath}{
    \LWR@stoppars
    \LWR@origtilde\LWR@orignewline
    \LWR@htmlopencomment

    \begingroup
    \LWR@restoreorigformatting
    \booltrue{LWR@insidemathcomment}
}
```

`\LWR@endhideamsmath` Ends hiding LaTeX math inside an HTML comment.

```
\newcommand*{\LWR@endhideamsmath}{
    \endgroup

    \LWR@htmlclosecomment
    \boolfalse{LWR@insidemathcomment}
    \LWR@orignewline
    \LWR@startpars
}
```

### 82.7.2 Environment patches

The amsmath environments already collect their contents in \@envbody for further processing. eqnarray is not an $\mathcal{AMS}$ package, and thus requires special handling.

For SVG math: Each envrionment is encapsulated inside a lateximage environment, along with a special optional argument of \LWR@amsmathbody or \LWR@amsmathbodynumbered telling lateximage to use as the HTML <alt> tag the environment's contents which were automatically captured by the $\mathcal{AMS}$ environment.

For MathJax: Each environment is syched with LaTeX's equation numbers, typeset with LaTeX inside an HTML comment, then printed to HTML output for MathJax to process.

Env eqnarray This environmnet is not an $\mathcal{AMS}$ environment and thus its body is not automatically captured, so the environ package is used to capture the environment into \BODY.

```
\let\LWR@origeqnarray\eqnarray
\let\LWR@origendeqnarray\endeqnarray
```

To remember whether the starred environment was used, and thus whether to number the equations:

```
\newbool{LWR@numbereqnarray}
\booltrue{LWR@numbereqnarray}
```

Common code used by eqnarray and Beqnarray (from fancybox):

```
\newcommand{\LWR@eqnarrayfactor}{%
```

If mathjax or FormatWP, print the LaTeX expression:

```
    \ifboolexpr{bool{mathjax} or ( bool{FormatWP} and bool{WPMarkMath} ) }%
    {%
```

If MathJax, the environment contents (the \BODY) are executed in a HTML comment to trigger the correct equation number increment (if not starred), then are included verbatim in the output for MathJax to interpret:

```
        \LWR@syncmathjax%
        \boolfalse{LWR@amsmultline}%
        \ifbool{LWR@numbereqnarray}%
        {%
```

If numbering the equations, execute a copy inside an HTML comment block:

```
            \LWR@beginhideamsmath%
            \LWR@origeqnarray%
            \BODY%
            \LWR@origendeqnarray%
            \LWR@endhideamsmath%
```

Then print the (sanitized) contents to the output for MathJax to interpret:

Default to number equations in the future:

```
    \booltrue{LWR@numbereqnarray}%
```

Clear the single-use `alt` text:

```
    \gdef\LWR@ThisAltText{}%
}
```

`eqnarray` itself is made with a blank line before and after to force it to be on its own line:

```
\RenewEnviron{eqnarray}
{%

\LWR@eqnarrayfactor

}
```

The starred version is patched to turn off the numbering:

```
\csgpreto{eqnarray*}{\boolfalse{LWR@numbereqnarray}}

\end{warpHTML}
```

# 83 Lateximages

## 83.1 Description

Env `lateximage` A `lateximage` is a piece of the document which is typeset in LaTeX then included in the HTML output as an image. This is used for math if SVG math is chosen, and also for the `picture`, `tikzpicture`, and other environments.

Before typesetting the `lateximage` a large number of formatting, graphics, and symbols-related macros are temporarily restored to their print-mode meaning by `\LWR@restoreorigformatting`. (See section 80.)

A `lateximage` is typeset on its own PDF page inside an HTML comment which starts on the preceeding page and ends on following page, and instructions are written to `lateximage.txt` for *lwarpmk* to extract the `lateximage` from the page of the PDF file then generate an accompanying `.svg` file image file. Meanwhile, instructions to show this image are placed into the HTML file after the comment.

An HTML `<span>` is created to hold both the HTML comment, which will have the *pdftotext* conversion, and also the link to the final `.svg` image.

A LaTeX label is used to remember which PDF page has the image. A label is used because footnotes, endnotes, and pagenotes may cause the image to appear at a later time. The label is declared along with the image, and so it correctly remembers where the image finally ended up.

HTML `alt` tag The HTML `alt` tag is set to the LaTeX source for SVG math, some chemistry expressions,

\LWR@startingequationtag Prints the starting equation number or tag.

```
\let\LWR@startingequationtag\theLWR@startingequation
```

\LWR@equationtag Prints the ending equation number or tag.

This is reset by lateximage, may be temporarily overwritten by \tag calling \LWR@remembertag.

```
\newcommand*{\LWR@equationtag}{}
```

Only if SVG math, patch \tag after packages have loaded, in case someone else modified \tag.

```
\AtBeginDocument{

\ifbool{mathjax}{}{% not mathjax
```

\LWR@remembertag {⟨*tag*⟩}

For use inside the math environments while using SVG math. Sets \theLWR@startingequation and \theequation to the given tag.

```
\NewDocumentCommand{\LWR@remembertag}{m}{%
    \ifbool{LWR@isstartingequation}%
    {%
        \global\boolfalse{LWR@isstartingequation}%
        \xdef\LWR@startingequationtag{#1}%
    }{}%
    \xdef\LWR@equationtag{#1}%
}%

}% not mathjax
}% AtBeginDocument
```

## 83.5 HTML alt tags

\LWR@amsmathbody {⟨*envname*⟩} For use inside the optional argument to a lateximage to add the contents of a AMS math environment to the <alt> tag.

```
\newcommand*{\LWR@amsmathbody}[1]
{%
    \textbackslash\{begin\}\{#1\} % extra space
    \LWR@HTMLsanitizeexpand{\detokenize\expandafter{\the\@envbody}}%
    \textbackslash\{end\}\{#1\}%
}
```

\LWR@amsmathbodynumbered {⟨*envname*⟩} For use inside the optional argument to a lateximage to add the contents of a AMS math environment to the alt tag, prefixed by the equation numbers.

```
\newcommand*{\LWR@amsmathbodynumbered}[1]
```

This may be used to provide an expression with a simple `alt` tag but also enough additional information to provide a unique hash.

An example is when the expression is a complicated TEX expression, which would not copy/paste well. A simplified tag may be used, while the complicated expression is duplicated in the additional hashing argument.

Another example is when the expression is simple, but the image depends on options. These options may be decoded into text form and included in the additional hashing argument in order to make the hash unique according to the set of options, even if the simple `alt` tag is still the same.

File `*_html.aux` A new label is placed into the file `*_html.aux`:

```
\newlabel{LWRlateximage-<BaseJobname>-<number>}{{<x>}{<y>}}
```

This is used to find the image in the PDF file, according to its name.

File `*-images.txt` A list of images to generate is created in `<jobname>-images.txt`. Each line has three pipe-delimited fields, containing the PDF page number from `<jobname>_html.pdf`, where the image is located, a boolean indicating whether the image is hashed, and the filename of the image. The last line has "end" in each field, and is used to detect an incomplete compile.

```
\catcode`\$=\active%

\NewDocumentEnvironment{lateximage}{s O{\ImageAltText} s O{} O{}}
{%
\LWR@traceinfo{lateximage: starting on \jobname.pdf page \arabic{page}}%
\LWR@traceinfo{lateximage: entering depth is \arabic{LWR@lateximagedepth}}%
```

Nested `lateximages` remain one large `lateximage`:

```
\ifnumcomp{\value{LWR@lateximagedepth}}{>}{0}%
```

If nesting inside an already-existing lateximage, simply record one more level. $\mathcal{AMS}$ packages redefine `\addtocounter` to do nothing if inside a `\text`, so lower-level TEX macros are used for tracking nested `lateximages`.

```
{%
%     \addtocounter{LWR@lateximagedepth}{1}%
    \global\advance\c@LWR@lateximagedepth 1\relax% Due to AmS \text macro.
}%
```

Otherwise, this is the outer-most lateximage:

```
{% start of outer-most lateximage
```

Remember the next equation number to be allocated, in case it must be printed in a multi-equation environment:

```
    \LWR@traceinfo{lateximage: starting outer-most lateximage}%
    \setcounter{LWR@startingequation}{\value{equation}}%
```

```
    \addtocounter{LWR@startingequation}{1}%
    \booltrue{LWR@isstartingequation}%
    \let\LWR@startingequationtag\theLWR@startingequation%
```

The default equation tag, unless overwritten by `\tag`:

```
    \let\LWR@equationtag\theequation%
```

Starting a new lateximage:

```
    \addtocounter{LWR@lateximagenumber}{1}%
  \LWR@traceinfo{lateximage: LWR@lateximagenumber is \arabic{LWR@lateximagenumber}}%
```

While inside a lateximage, locally do not use mathjax:

```
    \boolfalse{mathjax}%
```

Be sure that are doing a paragraph:

```
    \LWR@ensuredoingapar%
```

Next file:

```
    \addtocounter{LWR@externalfilecnt}{1}%
  \LWR@traceinfo{lateximage: LWR@externalfilecnt is \arabic{LWR@externalfilecnt}}%
```

Figure out what the next page number will be. `\setcounterpageref` assigns `LWR@LIpage` to the page number for the reference `LWRlateximage-BaseJobname-XXX`:

```
    \setcounterpageref{LWR@LIpage}{%
        LWRlateximage-\BaseJobname-\arabic{LWR@lateximagenumber}%
    }%
    \LWR@traceinfo{lateximage: LWR@LIpage is \arabic{LWR@LIpage}}%
```

Create an HTML span which will hold the comment which contains the ***pdftotext*** translation of the image's page, and also will hold the link to the `.svg` file:

```
    \LWR@htmltag{span\LWR@indentHTML%
        id=\textquotedbl{}%
            lateximage-\BaseJobname-\arabic{LWR@lateximagenumber}%
            \textquotedbl\LWR@indentHTML
        class=\textquotedbl{}lateximagesource\textquotedbl\LWR@orignewline
    }%
```

Write instructions to the `<ImagesDirectory>.txt` file:

```
    \LWR@traceinfo{lateximage: about to write to \BaseJobname-images.txt}%
    \IfBooleanTF{#1}% starred
    {% hash
```

Compute and save the hashed file name for later use:

```
        \ifdefvoid{\LWR@ThisAltText}{%
            \IfBooleanTF{#3}{%
```

```
                \edef\LWR@hashedname{%
                    \LWR@mdfive{\detokenize\expandafter{#2}-!-#4}%
                }%
            }{%
                \edef\LWR@hashedname{%
             \LWR@mdfive{\detokenize\expandafter{\AltTextOpen#2\AltTextClose}-!-#4}%
                }%
            }%
        }{%
            \edef\LWR@hashedname{%
           \LWR@mdfive{\detokenize\expandafter{\AltTextOpen\LWR@ThisAltText\AltTextClose}-!-#4}%
            }%
        }%
        \LWR@traceinfo{lateximage: hash is \LWR@hashedname}%
```

Write the page, hashing, and hashed name:

```
        \immediate\write\LWR@lateximagesfile{%
            |\arabic{LWR@LIpage}|true|\LWR@hashedname|%
        }%
    }% hash
    {% no hash
```

No hash, so write the page, no hashing, and the image number:

```
        \LWR@traceinfo{lateximage: hash false}%
        \immediate\write\LWR@lateximagesfile{%
        |\arabic{LWR@LIpage}|false|\LWR@ImagesName\arabic{LWR@externalfilecnt}|%
        }%
    }% no hash
```

Place an open comment tag. This will hide any traces of the lateximage PDF page which were picked up by *pdftotext*.

```
    \LWR@traceinfo{lateximage: about to create open comment}%
    \LWR@htmlopencomment%
```

One level deeper. At this outer-most `lateximage`, it is known that this is not being used inside an $\mathcal{AMS}$ `\text`, since the outer-most level will never be in math mode.

```
     \addtocounter{LWR@lateximagedepth}{1}%
```

Start the new PDF page:

```
    \LWR@traceinfo{lateximage: about to create a new page}%
    \LWR@maybe@orignewpage%
```

If the current page is larger, typeset the image in a "standard" width page and font size:

```
    \LWR@traceinfo{lateximage: about to create minipage}%
    \ifdimless{\linewidth}{6in}{%
        \LWR@print@minipage{\linewidth}%
    }{%
        \LWR@print@minipage{6in}%
    }%
```

```
    \@nameuse{LWR@print@\LateximageFontSizeName}%
```

Temporarily restore formatting to its PDF definitions: Do not produce HTML tags for \hspace, etc. inside a lateximage.

```
    \LWR@traceinfo{lateximage: about to temporarily restore formatting}%
    \LWR@restoreorigformatting%
```

Use full-page footnotes instead of minipage footnotes. These become HTML footnotes.

```
    \def\@mpfn{footnote}%
    \def\thempfn{\thefootnote}%
    \LetLtxMacro\@footnotetext\LWR@footnotetext%
```

Create the LWRlateximage<number> label:

```
    \LWR@traceinfo{lateximage: about to create label}%
    \LWR@orig@label{LWRlateximage-\BaseJobname-\arabic{LWR@lateximagenumber}}%
    \LWR@traceinfo{lateximage: finished creating the label}%
```

Adjust the rule color to match HTML:

```
    \ifdefvoid{\LWR@ruleHTMLcolor}{}{%
        \LWR@print@arrayrulecolor[HTML]{\LWR@ruleHTMLcolor}%
    }%
```

Enable print-mode math functions:

```
    \LetLtxMacro$\LWR@origdollar%
    \catcode`\$=3% math shift
    \LetLtxMacro\(\LWR@origopenparen%
    \LetLtxMacro\)\LWR@origcloseparen%
```

Only enable print-mode display math if are not already inside display math:

```
    \ifbool{LWR@indisplaymathimage}{}{% not in display math
        \LetLtxMacro\[\LWR@origopenbracket%
        \LetLtxMacro\]\LWR@origclosebracket%
        \let\equation\LWR@origequation%
        \let\endequation\LWR@origendequation%
        \csletcs{equation*}{LWR@origequation*}%
        \csletcs{endequation*}{LWR@origendequation*}%
    }% not in display math
```

For chemformula:

```
    \LetLtxMacro\LWR@newsingledollar$%
    \LetLtxMacro\LWR@newsingledollar$% syntax highlighting

}% end of outer-most lateximage
\LWR@traceinfo{lateximage: finished start of environment}%
}% end of \begin{lateximage}
```

\endlateximage When the lateximage environment closes:

```
{% start of \end{lateximage}
\LWR@traceinfo{lateximage: starting end of lateximage}%
```

Nested more than one deep?

```
\LWR@traceinfo{lateximage: internal depth was \arabic{LWR@lateximagedepth}}%
\ifnumcomp{\value{LWR@lateximagedepth}}{>}{1}%
```

If nesting inside an already existing lateximage, simply record one less level. Uses a lower-level TEX macro due to $\mathcal{AMS}$ \text change of \addtocounter.

```
{%
    \LWR@traceinfo{lateximage: unnesting}%
    \global\advance\c@LWR@lateximagedepth -1\relax%
}%
```

If this is the outer-most lateximage:

```
{% end of outer-most lateximage
```

Finish the lateximage minipage and start a new PDF page:

```
\LWR@traceinfo{lateximage: ending outer-most lateximage}%
    \endLWR@print@minipage%
    \LWR@maybe@orignewpage%
```

Close the HTML comment which encapsulated any traces of the lateximage picked up by *pdftotext*:

```
    \LWR@print@vspace*{.5\baselineskip}%
    \LWR@htmlclosecomment%
    \LWR@traceinfo{lateximage: The page after the image is \arabic{page}}%
```

Create a link to the lateximage, allowing its natural height:

```
    \IfBooleanTF{#1}% starred
    {% hash
        \LWR@lateximage@oneimage{#2}{\LWR@hashedname}{#5}{#3}%
    }% hash
    {% no hash
     \LWR@lateximage@oneimage{#2}{\LWR@ImagesName\theLWR@externalfilecnt}{#5}{#3}%
    }% no hash
```

Be sure that are doing a paragraph:

```
    \LWR@ensuredoingapar%
```

Close the HTML span which has the *pdftotext* comment and also the link to the .svg image:

```
    \LWR@htmltag{/span}%
    \ifbool{HTMLDebugComments}{%
        \LWR@htmlcomment{End of lateximage}%
    }{}%
```

Undo one lateximage level. This is not inside an $\mathcal{AMS}$ `\text`, so regular `\addtocounter` may be used here.

```
    \addtocounter{LWR@lateximagedepth}{-1}%
```

Clear the single-use `alt` text:

```
    \gdef\LWR@ThisAltText{}%
}% end of outer-most lateximage
\LWR@traceinfo{lateximage: exiting depth is \arabic{LWR@lateximagedepth}}%
\LWR@traceinfo{lateximage: done}%
}%
\catcode`\$=3% math shift
\end{warpHTML}
```

**for PRINT output:**

```
\begin{warpprint}
```

Env `lateximage` * [⟨<alt> *tag*⟩] * [⟨*add'l hashing*⟩] [⟨*css style*⟩]

`varwidth` is used to create a box of the natural width of its contents.

```
\NewDocumentEnvironment{lateximage}{s o s o o}
    {\begin{varwidth}[b]{\linewidth}}
    {\end{varwidth}}
```

```
\end{warpprint}
```

## 84 `center`, `flushleft`, `flushright`

**for HTML output:**

```
\begin{warpHTML}
```

Env `center` Replace `center` functionality with css tags:

```
\newenvironment*{LWR@HTML@center}
{
    \LWR@forcenewpage
    \ifbool{FormatWP}
        {\BlockClass[\LWR@print@mbox{text-align:center}]{center}}
        {\BlockClass{center}}
}
{\endBlockClass}

\LWR@formattedenv{center}
```

Env `flushright`

```
\newenvironment*{LWR@HTML@flushright}
{
    \LWR@forcenewpage
    \ifbool{FormatWP}
```

```
        {\BlockClass[\LWR@print@mbox{text-align:right}]{flushright}}
        {\BlockClass{flushright}}
}
{\endBlockClass}

\LWR@formattedenv{flushright}
```

Env flushleft

```
\newenvironment*{LWR@HTML@flushleft}
{
    \LWR@forcenewpage
    \ifbool{FormatWP}
        {\BlockClass[\LWR@print@mbox{text-align:left}]{flushleft}}
        {\BlockClass{flushleft}}
}
{\endBlockClass}

\LWR@formattedenv{flushleft}
```

\centering, \raggedleft, and \raggedright usually have no effect on the HTML output, but they may be used to compare with the next token to identify their use at the start of a float. See \LWR@floatalignment.

\centering

```
\newcommand*{\LWR@HTML@centering}{%
    \ifbool{HTMLDebugComments}{%
        \LWR@htmlcomment{centering}%
    }{}%
}
\LWR@formatted{centering}
```

\raggedleft

```
\newcommand*{\LWR@HTML@raggedleft}{%
    \ifbool{HTMLDebugComments}{%
        \LWR@htmlcomment{raggedleft}%
    }{}%
}
\LWR@formatted{raggedleft}
```

\raggedright

```
\newcommand*{\LWR@HTML@raggedright}{%
    \ifbool{HTMLDebugComments}{%
        \LWR@htmlcomment{raggedright}%
    }{}%
}
\LWR@formatted{raggedright}
```

\leftline {⟨*text*⟩}

```
12096 \renewcommand{\leftline}[1]{\begin{flushleft}#1\end{flushleft}}
```

\centerline {⟨*text*⟩}

```
12097 \renewcommand{\centerline}[1]{\begin{center}#1\end{center}}
```

\rightline {⟨*text*⟩}

```
12098 \renewcommand{\rightline}[1]{\begin{flushright}#1\end{flushright}}
12099 \end{warpHTML}
```

# 85 Preloaded packages

**for HTML output:**
```
12100 \begin{warpHTML}
```

If the given package was loaded before or by lwarp, load the lwarp version as well.

\LWR@PreloadedPackage {⟨*packagename*⟩}

```
12101 \newcommand*{\LWR@PreloadedPackage}[1]{%
12102     \@ifpackageloaded{#1}%
12103         {%
12104             \AtBeginDocument{
12105                 \LWR@origRequirePackage{lwarp-#1}%
12106             }
12107         }%
12108         {}%
12109 }
```

If inputtrc was loaded before lwarp, as is usually done, explicitly load the lwarp patches now:

```
12110 \LWR@PreloadedPackage{inputtrc}
```

If textcomp was loaded before lwarp, perhaps as part of the font-related packages, explicitly load the lwarp patches now:

```
12111 \LWR@PreloadedPackage{textcomp}
```

If xunicode was loaded before lwarp, perhaps as part of the font-related packages, explicitly load the lwarp patches now:

```
12112 \LWR@PreloadedPackage{xunicode}
```

If graphics or graphicx were loaded before lwarp, perhaps by xunicode, explicitly load the lwarp patches now:

```
12113 \LWR@PreloadedPackage{graphics}
12114 \LWR@PreloadedPackage{graphicx}
```

scalefnt may have been preloaded by babel

```
\LWR@PreloadedPackage{scalefnt}
```

fontaxes must be preloaded so that lwarp may patch it for HTML.

```
\LWR@PreloadedPackage{fontaxes}
```

Various font packages which may be loaded before lwarp:

```
\LWR@PreloadedPackage{cmbright}
\LWR@PreloadedPackage{fourier}
\LWR@PreloadedPackage{kpfonts}
\LWR@PreloadedPackage{kpfonts-otf}
\LWR@PreloadedPackage{libertinust1math}
\LWR@PreloadedPackage{pxfonts}
\LWR@PreloadedPackage{txfonts}
\LWR@PreloadedPackage{txgreeks}
\LWR@PreloadedPackage{newpxmath}
\LWR@PreloadedPackage{newtxmath}
\LWR@PreloadedPackage{newtxsf}
\LWR@PreloadedPackage{mathalpha}
\LWR@PreloadedPackage{unicode-math}
```

nfssext-cfr may be preloaded by cfm-lm or related font packages.

```
\LWR@PreloadedPackage{nfssext-cfr}
```

ulem may be preloaded by ctex, ctexart, and related classes.

```
\LWR@PreloadedPackage{ulem}
```

xetexko-vertical may be preloaded by xetexko.

```
\LWR@PreloadedPackage{xetexko-vertical}
```

geometry is preloaded by lwarp, and perhaps by various classes.

```
\LWR@PreloadedPackage{geometry}
```

plext is preloaded by some CJK classes.

```
\LWR@PreloadedPackage{plext}
```

stfloats is preloaded by ltj* classes.

```
\LWR@PreloadedPackage{stfloats}
```

lltjext is preloaded by ltj* classes.

```
\LWR@PreloadedPackage{lltjext}
```

luatexko must be loaded before lwarp.

```
\LWR@PreloadedPackage{luatexko}
```

```
\end{warpHTML}
```

# 86 siunitx

Pkg siunitx

The lwarp core passes a few options to siunitx.

fractions

Due to *pdftotext* limitations, fraction output is replaced by symbol output for `per-mode` and `quotient-mode`.

⚠ math mode required

Some units will require that the expression be placed inside math mode.

⚠ tabular

Tabular `S` columns are rendered as simple `c` columns, and tabular `s` columns are not supported. These may be replaced by `c` columns with each cell contained in `\num` or `\si`.

⚠ MathJax

For math mode with SVG display, the original siunitx code is used while generating the SVG image. For text mode, lwarp uses an emulation which provides a very effective HTML interpretation of siunitx. For math expressions while using MathJax, a limited emulation is used. Most functions work reasonably well, but many options cannot be emulated. Complicated parsing such as for `\ang` is not supported. The result usually looks fine, and otherwise is enough to get the meaning across.

Document modifications required for MathJax:

custom units

- Custom units may be added with `\CustomizeMathJax`. See the lwarp-siunitx code for examples.

⚠ unit spacing

- Units work better using ~ between units instead of using periods.

⚠ `\square`, `\cubic`

- To square or cube compound units, enclose the following compound units in braces:

  ```
  \cubic{\centi\meter}
  ```

  Single units do not require braces.

Also see MathJax option, section 8.7.4.

**for HTML output:**

```
\begin{warpHTML}
```

Options for siunitx:

```
\newrobustcmd{\LWR@siunitx@textcelsius}{\HTMLentity{deg}C}
\newrobustcmd{\LWR@siunitx@textdegree}{\HTMLentity{deg}}
\newrobustcmd{\LWR@siunitx@textprime}{\HTMLunicode{2032}}
\newrobustcmd{\LWR@siunitx@textdblprime}{\HTMLunicode{2033}}
\newrobustcmd{\LWR@siunitx@textplanckbar}{\text{\textit{\HTMLunicode{210F}}}}

\appto\LWR@restoreorigformatting{%
\renewrobustcmd{\LWR@siunitx@textcelsius}{\text{\ensuremath{^\circ}C}}%
\renewrobustcmd{\LWR@siunitx@textdegree}{\text{\ensuremath{^\circ}}}%
\renewrobustcmd{\LWR@siunitx@textprime}{\text{\ensuremath{^\prime}}}%
\renewrobustcmd{\LWR@siunitx@textdblprime}{\text{\ensuremath{^{\prime\prime}}}}%
\renewrobustcmd{\LWR@siunitx@textplanckbar}{\text{\ensuremath{\hbar}}}%
}
```

```
12153
12154 \PassOptionsToPackage{
12155     detect-mode=true,
12156     per-mode=symbol,% fraction is not seen by pdftotext
12157     text-celsius = {\LWR@siunitx@textcelsius},
12158     text-degree = {\LWR@siunitx@textdegree},
12159     text-arcminute = {\LWR@siunitx@textprime} ,
12160     text-arcsecond = {\LWR@siunitx@textdblprime} ,
12161 }{siunitx}

12162 \end{warpHTML}
```

# 87 Graphics print-mode modifications

## 87.1 General limitations

⚠ scale

Avoid using the `\includegraphics` `scale` option. Change:

```
\includegraphics[scale=<xx>]{ . . . }
```

to:

```
\includegraphics[width=<yy>\linewidth]{ . . . }
```

`\includegraphics` file formats

For `\includegraphics` with `.pdf` or `.eps` files, the user must provide a `.pdf` or `.eps` image file for use in print mode, and also a `.svg`, `.png`, or `.jpg` version of the same image for use in HTML.

```
\includegraphics{filename} % print:.pdf/.eps HTML:.svg, etc.
```

For print output, lwarp will automatically choose the `.pdf` or `.eps` format if available, or some other format otherwise. For HTML, one of the other formats is used instead.

If a `.pdf` or `.eps` image is referred to with its file extension, the extension will be changed to `.svg` for HTML:

```
\includegraphics{filename.pdf} % uses .svg in html
\includegraphics{filename.eps} % uses .svg in html
```

Prog pdftocairo

PDF to SVG

To convert a PDF image to SVG, use the utility *pdftocairo*:

Enter ⇒ **`pdftocairo -svg filename.pdf`**

Prog lwarpmk pdftosvg

For a large number of images, use *lwarpmk*:

Enter ⇒ **`lwarpmk pdftosvg *.pdf`** **(or a list of filenames)**

Prog lwarpmk epstopdf

Prog epstopdf

epstopdf package

For EPS images converted to PDF using the package epstopdf, use

Enter ⇒ **`lwarpmk pdftosvg *.PDF`**

to convert to SVG images.

DVI LaTeX

When using DVI *latex*, it is necessary to convert EPS to PDF and then to SVG:

Enter ⇒ **`lwarpmk epstopdf *.eps`** **(or a list of filenames)**

Enter ⇒ **`lwarpmk pdftosvg *.pdf`** **(or a list of filenames)**

PNG and JPG — For PNG or JPGwhile using *pdflatex*, *lualatex*, or *xelatex*, the same file may be used in both print or HTML versions, and may be used with a file extension, but will also be used without the file extension if it is the only file of its base name.

GIF — GIF files may be used for HTML, but another format must also be provided for print output.

file extension priorities — If a file extension is not used, for HTML the file extension priorities are: SVG, GIF, PNG, then JPG.

⚠ graphics vs. graphicx — If using the older graphics syntax, use both optional arguments for `\includegraphics`. A single optional parameter is interpreted as the newer graphicx syntax. Note that viewports are not supported by lwarp — the entire image will be shown.

⚠ viewport

⚠ viewport units — For `\includegraphics`, avoid `px` and `%` units for width and height, or enclose them inside `warpHTML` environments. For font-proportional image sizes, use `ex` or `em`. For fixed-sized images, use `cm`, `mm`, `in`, `pt`, or `pc`. Use the keys `width=.5\linewidth`, or similar for `\textwidth` or `\textheight` to give fixed-sized images proportional to a 6 by 9 inch text area. Do not use the `scale` option, since it is not well supported by HTML browsers.

options — `\includegraphics` accepts `width` and `height`, `origin`, `rotate` and `scale`, plus new `class` and `alt` keys.

HTML class — With HTML output, `\includegraphics` accepts an optional `class=xyz` keyval combination, and if this is given then the HTML output will include that class for the image. The class is ignored for print output.

HTML `alt` tags — Likewise, the `\includegraphics` `alt` key adds an HTML `alt` tag to an image, and is ignored for print output. If not assigned, each image is given an `alt` tag according to `\ImageAltText`.

`\rotatebox` — `\rotatebox` accepts the optional `origin` key.

⚠ browser support — `\rotatebox`, `\scalebox`, and `\reflectbox` depend on modern browser support. The CSS3 standard declares that when an object is transformed the whitespace which they occupied is preserved, unlike LaTeX, so expect some ugly results for scaling and rotating.

## 87.2 Print-mode modifications

**for PRINT output:** For print output, accept and then discard the new `class` key:

```
\begin{warpprint}
\define@key{Gin}{class}{}
\define@key{Gin}{alt}{}
```

Print-mode additions for the overpic package. See section 445 for the HTML version.

```
\AtBeginDocument{
\@ifpackageloaded{overpic}{
\newcommand*{\overpicfontsize}{12}
\newcommand*{\overpicfontskip}{14}
```

```
\begin{lrbox}{\LWR@colorminipagebox}%
#5%
\end{lrbox}%
```

Sort out the various optional arguments and the background color of none. In each case, the LRbox is placed inside a \fcolorbox.

The current color is remembered, then set to the frame, then the current color is used for the contents.

```
\ifstrequal{#4}{none}%
{% #4 none
    \LWR@traceinfo{background is none}%
    {% scope the \colorlet
        \colorlet{LWR@currentcolor}{.}%
        \color{#2}%
        \fbox{%
            \color{LWR@currentcolor}%
            \usebox{\LWR@colorminipagebox}%
        }% fbox
    }% colorlet
}% #4 none
{% #4 not none
\LWR@traceinfo{background not none}%
\IfValueTF{#1}%
{%
    \IfValueTF{#3}%
   {\LWR@orig@print@fcolorbox[#1]{#2}[#3]{#4}{\usebox{\LWR@colorminipagebox}}}%
    {\LWR@orig@print@fcolorbox[#1]{#2}{#4}{\usebox{\LWR@colorminipagebox}}}%
}%
{% no value #1
    \IfValueTF{#3}%
    {\LWR@orig@print@fcolorbox{#2}[#3]{#4}{\usebox{\LWR@colorminipagebox}}}%
    {\LWR@orig@print@fcolorbox{#2}{#4}{\usebox{\LWR@colorminipagebox}}}%
}% no value #1
}% #4 not none
\LWR@traceinfo{LWR@print@fcolorbox done}%
}
```

```
\renewrobustcmd*{\fcolorbox}{\LWR@print@fcolorbox}%
```

\fcolorboxBlock [⟨*framemodel*⟩] {⟨*framecolor*⟩} [⟨*boxmodel*⟩] {⟨*boxcolor*⟩} {⟨*text*⟩}

In print mode, \fcolorboxBlock is the same as \fcolorbox.

```
\newcommand*{\LWR@print@fcolorboxBlock}{\LWR@print@fcolorbox}
```

```
\newrobustcmd*{\fcolorboxBlock}{\LWR@print@fcolorboxBlock}
```

Env fcolorminipage [⟨*1:framemodel*⟩] {⟨*2:framecolor*⟩} [⟨*3:boxmodel*⟩] {⟨*4:boxcolor*⟩} [⟨*5:align*⟩] [⟨*6:height*⟩] [⟨*7:inner-align*⟩] {⟨*8:width*⟩}

In print mode, becomes a \fcolorbox containing a minipage:

```
\NewDocumentEnvironment{LWR@print@fcolorminipage}{o m o m O{c} O{} o m}
{%
\LWR@traceinfo{*** fcolorminipage: #2 #4 #8}%
```

Pre-load the contents into an LR box so that they can be used inside a `\fcolorbox`::

`\AtEndPreable` forces cleveref to be loaded last, if it has not yet been loaded by the user.

**for HTML output:**

```
\begin{warpHTML}

\AtEndPreamble{
    \RequirePackage{cleveref}
}

\end{warpHTML}
```

# 91 Preexisting label and reference definitions

Remember and patch some label-related defintions. These will be further encased and patched by other packages later.

`\label` and `\pageref` do NOT change their behavior according to print or HTML output, and thus do not use the `\LWR@formatted` system.

**for HTML output:**

```
\begin{warpHTML}

\LetLtxMacro\LWR@orig@label\label% includes memoir, before cleveref
\LetLtxMacro\label\LWR@new@label

\LetLtxMacro\LWR@orig@pageref\pageref
\LetLtxMacro\pageref\LWR@new@pageref

\end{warpHTML}
```

# 92 `picture` environment

Env `picture` The `picture` environment is enclosed inside a `\lateximage`.

**for HTML output:**

```
\begin{warpHTML}
```

Env `picture`

```
\BeforeBeginEnvironment{picture}{\begin{lateximage}[picture]}

\AfterEndEnvironment{picture}{\end{lateximage}}
```

```
\end{warpHTML}
```

# 93 Minipages and Boxes

A css flexbox is used for minipages and parboxes, allowing external and internal vertical positioning.

⚠ inline — A line of text with an inline `minipage` or `\parbox` will have the `minipage` or `\parbox` placed onto its own line, because a paragraph is a block element and cannot be made `inline-block`.

placement — `minipages` and `\parboxes` will be placed side-by-side in HTML unless you place a `\newline` between them.

side-by-side — Side-by-side `minipages` may be separated by `\quad`, `\qquad`, `\enskip`, `\hspace`, `\hfill`, or a `\rule`. When inside a `center` environment, the result is similar in print and HTML. Paragraph tags are suppressed between side-by-side `minipages` and these spacing commands, but not at the start or end of the paragraph.

⚠ minipage in a span — There is limited support for `minipages` inside an HTML `<span>`. An HTML `<div>` cannot appear inside a `<span>`. While in a `<span>`, `minipages`, and `\parboxes`, and any enclosed lists have limited HTML tags, resulting in an "inline" format, without markup except for HTML breaks. Use `\newline` or `\par` for an HTML break.

⚠ minipage size — When using `minipage`, `\parbox`, and `fminipage`, a virtual $6 \times 9$ inch text area is used for `\linewidth`, `\textwidth`, and `\textheight`, both for sizing the minipage, and also for its contents.

if width is `\linewidth` — If a `minipage` or `\parbox` is assigned a width of exactly `\linewidth`, in HTML it is automatically given no HTML width, thus allowed to fill the line as needed, similar to how it

## 93.2 Virtual page size

Ctr LWR@virtualpagedepth Used to only reset the line width at the outermost minipage.

```
\newcounter{LWR@virtualpagedepth}
\setcounter{LWR@virtualpagedepth}{0}
```

Env LWR@setvirtualpage * [⟨*columns*⟩]

If not nesting a minipage, adjust \linewidth, \textwidth, and \textheight for a virtual $6 \times 9$ page, and start on a new PDF page to help prevent page overflows.

If starred, force a new page in the PDF before generating more HTML. This may be done to reduce the chance of page overflow when starting a new minipage.

The optional number of columns defaults to 1.

```
\NewDocumentEnvironment{LWR@setvirtualpage}{s O{1}}{%
    \ifnumequal{\value{LWR@virtualpagedepth}}{0}{%
        \IfBooleanT{#1}{\LWR@maybe@orignewpage}%
        \setlength{\linewidth}{6in/#2}%
        \setlength{\textwidth}{6in}%
        \setlength{\textheight}{9in}%
    }{}%
    \addtocounter{LWR@virtualpagedepth}{1}%
}
{\addtocounter{LWR@virtualpagedepth}{-1}}
```

## 93.3 Footnote handling

Also see section 60 for other forms of footnotes. Minipage footnotes are gathered in section 60.5, and then placed into the document in section 93.4.

## 93.4 Minipage handling

Bool LWR@minipagefullwidth Should the next minipage have no HTML width?

```
\newbool{LWR@minipagefullwidth}
\boolfalse{LWR@minipagefullwidth}
```

Bool LWR@forceminipagefullwidth Should the next minipage have no HTML width? Used to force full width for all minipages in an environment such as tabular or multicols, where the actual width depends on the browser width. Controlled by \useminipagewidths and \ignoreminipagewidths.

```
\newbool{LWR@forceminipagefullwidth}
\boolfalse{LWR@forceminipagefullwidth}
```

\minipagefullwidth Requests that the next minipage have no width tag in HTML:

**for HTML output:**

```
\newcommand*{\minipagefullwidth}{\global\booltrue{LWR@minipagefullwidth}}
```

\UseMinipageWidths Locally requests that minipage widths be honored.

```
\newcommand*{\UseMinipageWidths}{\boolfalse{LWR@forceminipagefullwidth}}
```

\IgnoreMinipageWidths Locally requests that minipage widths be ignored.

```
\newcommand*{\IgnoreMinipageWidths}{\booltrue{LWR@forceminipagefullwidth}}
\end{warpHTML}
```

**for PRINT output:**

```
\begin{warpprint}
\newcommand*{\minipagefullwidth}{}
\newcommand*{\UseMinipageWidths}{}
\newcommand*{\IgnoreMinipageWidths}{}
\end{warpprint}
```

**for HTML output:**

```
\begin{warpHTML}
```

Bool LWR@minipagethispar Has a minipage been seen this paragraph? If true, prevents paragraph tags around horizontal space between minipages.

```
\newbool{LWR@minipagethispar}
\boolfalse{LWR@minipagethispar}
```

Env minipage [⟨*vert position*⟩] [⟨*height*⟩] [⟨*inner vert position*⟩] {⟨*width*⟩}

The vertical positions may be 'c', 't', or 'b'. The inner position may also be 's'.

When using \linewidth, \textwidth, or \textheight, these are scaled proportionally to a 6×9 inch text area.

```
\NewDocumentEnvironment{LWR@HTML@sub@minipage}{m m m m}
{%
\LWR@traceinfo{minipage}%
```

Start an environment, in which width and height is computed based on a virtual page size instead of the extra-large PDF page used during HTML tag generation.

```
\begin{LWR@setvirtualpage}*%
```

Save the requested width now that \linewidth, etc. are adjusted to virtual size.

```
\setlength{\LWR@minipagewidth}{#4}%
\ifnumequal{\value{LWR@virtualpagedepth}}{1}{%
    \addtolength{\LWR@minipagewidth}{3em}% room for frames
}{}%
\LWR@traceinfo{computed width is \LWR@printlength{\LWR@minipagewidth}}%
```

Compute height:

```
\setlength{\LWR@minipageheight}{\textheight}% default unless specified
\ifblank{#2}{}{\setlength{\LWR@minipageheight}{#2}}%
```

LaTeX wants to start a paragraph for the virtual minipage, then start a paragraph again for the contents of the minipage, so cancel the paragraph tag handling until the minipage has begun.

```
\ifbool{FormatWP}{\newline}{}%
\LWR@stoppars%
```

If `FormatWP`, add a text frame:

```
\ifbool{FormatWP}{%

\addtocounter{LWR@thisautoidWP}{1}%
\LWR@htmltag{%
    div id=\textquotedbl%
        \LWR@print@mbox{autoidWP-\arabic{LWR@thisautoidWP}}%
    \textquotedbl\ % space
    class=\textquotedbl{}wpminipage\textquotedbl%
}%

}{}%
```

Create the  tag with optional alignment style:

```
\LWR@traceinfo{minipage: creating div class}%
\LWR@htmltag{div class=\textquotedbl{}minipage\textquotedbl\ style=\textquotedbl%
\ifthenelse{\equal{#1}{t}}{\LWR@print@mbox{vertical-align:bottom} ; }{}%
\ifthenelse{\equal{#1}{c}}{\LWR@print@mbox{vertical-align:middle} ; }{}%
\ifthenelse{\equal{#1}{b}}{\LWR@print@mbox{vertical-align:top} ; }{}%
\ifthenelse{\equal{#3}{t}}{\LWR@print@mbox{justify-content:flex-start} ; }{}%
\ifthenelse{\equal{#3}{c}}{\LWR@print@mbox{justify-content:center} ; }{}%
\ifthenelse{\equal{#3}{b}}{\LWR@print@mbox{justify-content:flex-end} ; }{}%
\ifthenelse{\equal{#3}{s}}{\LWR@print@mbox{justify-content:space-between} ; }{}%
```

Print the width and optional height styles:

```
\LWR@traceinfo{minipage: about to print the width of \LWR@printlength{\LWR@minipagewidth}}%
\ifbool{LWR@minipagefullwidth}%
{\global\boolfalse{LWR@minipagefullwidth}}%
{%
    \ifbool{LWR@forceminipagefullwidth}%
        {}%
        {%
            \ifdimequal{#4}{\linewidth}%
                {}%
                {width:\LWR@printlength{\LWR@minipagewidth} ; }%
        }%
}%
\LWR@traceinfo{minipage: about to print the height}%
\ifblank{#2}{}{height:\LWR@printlength{\LWR@minipageheight} ; }%
\textquotedbl%
}%
```

Finish with an empty line to start the contents on a new line.

```

```

```
% The preceding empty line is required.
```

Set the user-accessible line and text width and height values inside the virtual minipage. These do not affect the actual size of the PDF output, but are used by any reference to `\linewidth`, etc. inside the virtual minipage being created here. `\LWR@minipagewidth` was the original then padded by 3em, which is restored here. This is done instead of settings back to #4, in case #4 was `\linewidth`, which was changed to 6in above.

```
\ifnumequal{\value{LWR@virtualpagedepth}}{1}{%
    \addtolength{\LWR@minipagewidth}{-3em}% undo frame padding
}{}%
\setlength{\linewidth}{\LWR@minipagewidth}%
```

`\raggedright` cancels hyphenation, which will be done by HTML instead.

```
\LWR@print@raggedright%
```

Set minipage footnotes:

```
\def\@mpfn{mpfootnote}%
\def\thempfn{\thempfootnote}\c@mpfootnote\z@%
\let\@footnotetext\@mpfootnotetext%
```

```
\end{LWR@setvirtualpage}%
\LWR@startpars%
\ifbool{FormatWP}{\newline}{}%
```

Prevent paragraph tags around horizontal white space until the start of the next paragraph:

```
\global\booltrue{LWR@minipagethispar}%
\LWR@traceinfo{LWR@minipage: done}%
}

\NewDocumentEnvironment{LWR@HTML@minipage}{O{t} O{} O{t} m}
    {\LWR@HTML@sub@minipage{#1}{#2}{#3}{#4}}
    {\endLWR@HTML@sub@minipage}

\LWR@formattedenv{minipage}
```

## 93.5 \parbox, \mbox, \makebox, \framebox, \fbox, \raisebox

**for HTML output:**

\parbox [⟨*pos*⟩] [⟨*height*⟩] [⟨*inner-pos*⟩] {⟨*width*⟩} {⟨*text*⟩}

A parbox uses the minipage code:

```
\NewDocumentCommand{\LWR@HTML@parbox}{O{t} O{} O{t} m +m}
{
\LWR@traceinfo{parbox of width #4}%
\begin{minipage}[#1][#2][#3]{#4}%
#5
\end{minipage}%
}

\LWR@formatted{parbox}
```

\mbox {⟨*text*⟩} Nullified for HTML.

```
\newcommand*{\LWR@HTML@mbox}[1]{#1}

\LWR@formatted{mbox}
```

\LWR@@makebox@paren {⟨*width*⟩}, {⟨*height*⟩}

Adds to the style in \LWR@temptwo.

```
\NewDocumentCommand{\LWR@@makebox@paren}{m m}{%
\IfValueTF{#2}{%
    \setlength{\LWR@tempwidth}{#1\unitlength}%
    \setlength{\LWR@tempheight}{#2\unitlength}%
    \appto{\LWR@temptwo}{%
        \LWR@print@mbox{width:\LWR@printlength{\LWR@tempwidth}} ; % space
        \LWR@print@mbox{height:\LWR@printlength{\LWR@tempheight}} ; % space
    }%
```

```
}{%
    \PackageError{lwarp}%
        {(width,height) is missing a comma ',' character}%
        {\protect\makebox\space and \protect\framebox\space accept
            a size in the format (width,height).}%
}%
}
```

\LWR@@makebox@align {⟨*alignment character*⟩}

Adds to the style in \LWR@temptwo.

```
\newcommand*{\LWR@@makebox@align}[1]{%
    \def\LWR@align{center}%
    \ifstrequal{#1}{l}{\def\LWR@align{left}}{}%
    \ifstrequal{#1}{r}{\def\LWR@align{right}}{}%
    \ifstrequal{#1}{s}{\def\LWR@align{justify}}{}%
    \appto{\LWR@temptwo}{%
        \LWR@print@mbox{text-align:\LWR@align} ; %
    }%
}
```

\makebox (⟨*width,height*⟩) [⟨*width*⟩] [⟨*pos*⟩] {⟨*text*⟩}

```
\NewDocumentCommand{\LWR@HTML@makebox}{>{\SplitArgument{1}{,}}d() o o +m}{%
```

Build the style depending on arguments:

```
    \begin{LWR@setvirtualpage}%
        \def\LWR@temptwo{}%
        \IfValueTF{#1}%
        {% (width,height) ..
            \LWR@@makebox@paren #1%
            \IfValueT{#2}%
            {% (width,height) [posn]
                \LWR@@makebox@align{#2}%
            }%
        }%
        {% [width]
            \IfValueT{#2}% [width]
            {%
                \setlength{\LWR@tempwidth}{#2}%
                \ifdimgreater{\LWR@tempwidth}{0pt}{%
                    \appto{\LWR@temptwo}{%
                        width:\LWR@printlength{\LWR@tempwidth} ; % space
                    }%
                }{}%
            }%
        }%
        \IfValueT{#3}%
        {% [width] [posn]
            \LWR@@makebox@align{#3}%
        }%
        \InlineClass[%
```

```
            \LWR@print@mbox{display:inline-block} ; %
            \LWR@temptwo%
        ]%
        {makebox}%
        {#4}%
    \end{LWR@setvirtualpage}%
}
\LWR@formatted{makebox}
```

\framebox (⟨*width,height*⟩) [⟨*width*⟩] [⟨*pos*⟩] {⟨*text*⟩}

```
\NewDocumentCommand{\LWR@HTML@framebox}{d() o o +m}{%
    \fbox{\makebox(#1)[#2][#3]{#4}}%
}

\LWR@formatted{framebox}
```

\LWR@forceminwidth {⟨*legth*⟩}

Sets \LWR@atleastonept to be at least 1pt.

```
\newlength{\LWR@atleastonept}

\newcommand*{\LWR@forceminwidth}[1]{%
\setlength{\LWR@atleastonept}{#1}%
\ifthenelse{%
    \lengthtest{\LWR@atleastonept>0pt}\AND%
    \lengthtest{\LWR@atleastonept<1pt}%
}%
    {\setlength{\LWR@atleastonept}{1pt}}%
    {}%
}
```

\LWR@fboxstyle Prints the HTML attributes for a black border and padding.

\LWR@forceminwidth must be used first in order to set the border width.

```
\newcommand*{\LWR@fboxstyle}{%
\LWR@findcurrenttextcolor%
border:\LWR@printlength{\LWR@atleastonept} solid \LWR@origpound\LWR@tempcolor ; %
padding:\LWR@printlength{\fboxsep} ; %
color:\LWR@origpound\LWR@tempcolor%
}
```

\fbox {⟨*text*⟩}

Creates a framed inline span enclosing the text.

Create a new HTML version, but don't use it until after xcolor may have loaded:

```
\newcommand{\LWR@HTML@fbox}[1]{%
\LWR@traceinfo{HTML fbox}%
\LWR@forceminwidth{\fboxrule}%
```

If the optional inner alignment is not given, use the outer instead:

```
\IfValueTF{#3}%
{\def\LWR@thisalign{#3}}
{\def\LWR@thisalign{#1}}%
```

Form the outer minipage depending on whether a height was given. Make the outer minipage larger to compensate for the frame.

```
\IfValueTF{#2}%
{\minipage[#1][#2+2\fboxsep+2\fboxrule][\LWR@thisalign]{#4+2\fboxsep+2\fboxrule}}%
{\minipage[#1]{#4+2\fboxsep+2\fboxrule}}%
```

Capture the contents of the environment:

```
\begin{lrbox}{\LWR@fminipagebox}%
```

Nest the contents inside an inner minipage of the desired size:

```
\IfValueTF{#2}%
{\minipage[#1][#2][\LWR@thisalign]{#4}}%
{\minipage[#1]{#4}}%
}
{%
```

Close the inner minipage and the LR box with the contents:

```
\endminipage%
\end{lrbox}%
```

Create a frame around the contents of the environment:

```
\fbox{\usebox{\LWR@fminipagebox}}%
```

The entire thing is placed inside the outer minipage:

```
\endminipage%
}

\LetLtxMacro\fminipage\LWR@print@fminipage
\LetLtxMacro\endfminipage\endLWR@print@fminipage
% \newenvironment{fminipage}{\LWR@print@fminipage}{\endLWR@print@fminipage}

\end{warpall}
```

HTML version:

**for HTML output:**

```
\begin{warpHTML}

\NewDocumentEnvironment{LWR@HTML@fminipage}{O{t} o O{t} m}
{%
\LWR@traceinfo{fminipage #1 #2 #3 #4}%
```

Locally change to the virtual page size before processing the requested sizes:

```
\begin{LWR@setvirtualpage}*%
\setlength{\LWR@tempwidth}{#4}%
\IfValueT{#2}{\setlength{\LWR@tempheight}{#2}}%
```

Use a rule of at least one pixel in width:

```
\LWR@forceminwidth{\fboxrule}%

\LWR@stoppars%

\begin{BlockClass}[%
\LWR@fboxstyle ; %
\IfValueT{#2}{height:\LWR@printlength{\LWR@tempheight} ; }%
\ifbool{LWR@minipagefullwidth}%
{\global\boolfalse{LWR@minipagefullwidth}}%
{%
    \ifbool{LWR@forceminipagefullwidth}%
        {}%
        {%
            \ifdimequal{\LWR@tempwidth}{\linewidth}%
                {}%
                {width:\LWR@printlength{\LWR@tempwidth} ; }%
        }%
}%
]{fminipage}%
}
{%
\end{BlockClass}%
\end{LWR@setvirtualpage}%
```

Prevent paragraph tags around horizontal white space until the start of the next paragraph:

```
\global\booltrue{LWR@minipagethispar}%
\LWR@traceinfo{fminipage done}%
}

\LWR@formattedenv{fminipage}
```

`\raisebox` `{`⟨*raiselen*⟩`}` `[`⟨*height*⟩`]` `[`⟨*depth*⟩`]` `{`⟨*text*⟩`}`

```
\NewDocumentCommand{\LWR@HTML@raisebox}{m o o m}{%
#4%
}

\LWR@formatted{raisebox}

\end{warpHTML}
```

# 94 Direct formatting

⚠ `\bfseries, etc.` `\textbf`, etc. are supported, but `\bfseries`, etc. work only in some situations.

```
12634         \LWR@htmlspan{b}{#1}%
12635     }%
12636 }
12637
12638 \LWR@formatted{textbf}
```

\texteb {⟨*text*⟩} From nfssext-cfr.

```
12639 \DeclareRobustCommand{\LWR@HTML@texteb}[1]{%
12640     {%
12641         \LWR@HTML@ebweight%
12642         \InlineClass{texteb}{#1}%
12643     }%
12644 }
12645
12646 \LWR@formatted{texteb}
```

\textlg {⟨*text*⟩} From nfssext-cfr.

```
12647 \DeclareRobustCommand{\LWR@HTML@textlg}[1]{%
12648     {%
12649         \LWR@HTML@lgweight%
12650         \InlineClass{textlg}{#1}%
12651     }%
12652 }
12653
12654 \LWR@formatted{textlg}
```

\textrm {⟨*text*⟩}

```
12655 \DeclareRobustCommand{\LWR@HTML@textrm}[1]{%
12656     {%
12657         \LWR@HTML@rmfamily%
12658         \InlineClass(font-family:serif){textrm}{#1}%
12659     }%
12660 }
12661
12662 \LWR@formatted{textrm}
```

\textsf {⟨*text*⟩}

```
12663 \DeclareRobustCommand{\LWR@HTML@textsf}[1]{%
12664     {%
12665         \LWR@HTML@sffamily%
12666         \InlineClass(font-family:sans){textsf}{#1}%
12667     }%
12668 }
12669
12670 \LWR@formatted{textsf}
```

\texttt {⟨*text*⟩}

```
\DeclareRobustCommand{\LWR@HTML@texttt}[1]{%
    {%
        \LWR@HTML@ttfamily%
        \LWR@htmlspan{kbd}{#1}%
    }%
}

\LWR@formatted{texttt}
```

`\textup {⟨text⟩}`

```
\DeclareRobustCommand{\LWR@HTML@textup}[1]{%
    {%
        \LWR@HTML@upshape%
        \InlineClass(font-style:normal){textup}{#1}%
    }%
}

\LWR@formatted{textup}
```

`\textit {⟨text⟩}`

```
\DeclareRobustCommand{\LWR@HTML@textit}[1]{%
    {%
        \LWR@HTML@itshape%
        \LWR@htmlspan{i}{#1}%
    }%
}

\LWR@formatted{textit}
```

`\textsc {⟨text⟩}`

```
\DeclareRobustCommand{\LWR@HTML@textsc}[1]{%
    {%
        \LWR@HTML@scshape%
        \InlineClass{textsc}{#1}%
    }%
}

\LWR@formatted{textsc}
```

`\textulc {⟨text⟩}` From fontaxes.

```
\DeclareRobustCommand{\LWR@HTML@textulc}[1]{%
    {%
        \LWR@HTML@ulcshape%
        \InlineClass{textulc}{#1}%
    }%
}

\LWR@formatted{textulc}
```

\textsi {⟨*text*⟩}

```
\@ifundefined{textsi}{
    \LetLtxMacro\LWR@print@textsi\LWR@print@textsc
}{}

\DeclareRobustCommand{\LWR@HTML@textsi}[1]{%
    {%
        \LWR@HTML@sishape%
        \textsc{\textit{#1}}%
%         \InlineClass(
%             font-style: italic;
%             font-variant: small-caps ;
%             font-variant-numeric: oldstyle-nums ;
%         ){textsi}{#1}%
    }%
}

\LWR@formatted{textsi}
```

\textsl {⟨*text*⟩}

```
\DeclareRobustCommand{\LWR@HTML@textsl}[1]{%
    {%
        \slshape%
        \InlineClass(font-style:oblique){textsl}{#1}%
    }%
}

\LWR@formatted{textsl}
```

\textssc {⟨*text*⟩}

```
\newrobustcmd{\LWR@HTML@textssc}[1]{\textsc{#1}}
\LWR@formatted{textssc}
```

\textnormal {⟨*text*⟩}

```
\DeclareRobustCommand{\LWR@HTML@textnormal}[1]{\textmd{\textrm{\textup{#1}}}}

\LWR@formatted{textnormal}

\FilenameNullify{%
    \LetLtxMacro\emph\@firstofone%
    \LetLtxMacro\textmd\@firstofone%
    \LetLtxMacro\textbf\@firstofone%
    \LetLtxMacro\texteb\@firstofone%
    \LetLtxMacro\textlg\@firstofone%
    \LetLtxMacro\textrm\@firstofone%
    \LetLtxMacro\textsf\@firstofone%
    \LetLtxMacro\texttt\@firstofone%
    \LetLtxMacro\textup\@firstofone%
    \LetLtxMacro\textit\@firstofone%
```

```
    \LetLtxMacro\textsc\@firstofone%
    \LetLtxMacro\textulc\@firstofone%
    \LetLtxMacro\textsi\@firstofone%
    \LetLtxMacro\textsl\@firstofone%
    \LetLtxMacro\textssc\@firstofone%
    \LetLtxMacro\textnormal\@firstofone%
}
```

Remembers the current font family, series, and shape. fontaxes support is integrated here.

```
\newcommand*{\LWR@f@family}{rm}
\newcommand*{\LWR@f@series}{md}
\newcommand*{\LWR@f@shape}{up}
\newcommand*{\LWR@f@shapecaps}{ulc}
```

`\LWR@textcurrentfont` {⟨*text*⟩}

Prints the text with the current font choices. Avoids nesting repeated font selections.

```
\newcounter{LWR@textcurrentfontdepth}
\setcounter{LWR@textcurrentfontdepth}{0}

\newcommand*{\LWR@textcurrentfont}[1]{%
    \ifnumcomp{\value{LWR@textcurrentfontdepth}}{>}{0}%
        {%
            \addtocounter{LWR@textcurrentfontdepth}{1}%
            #1%
            \addtocounter{LWR@textcurrentfontdepth}{-1}%
        }%
        {%
            \addtocounter{LWR@textcurrentfontdepth}{1}%
            \InlineClass{%
                    text\LWR@f@family\LWR@origtilde{}%
                    text\LWR@f@series\LWR@origtilde{}%
                    text\LWR@f@shape\LWR@origtilde{}%
                    text\LWR@f@shapecaps%
                }%
                {#1}%
            \addtocounter{LWR@textcurrentfontdepth}{-1}%
        }%
}
```

Env `LWR@blocktextcurrentfont` Prints the contents with the current font choices.

```
\newenvironment*{LWR@blocktextcurrentfont}{%
\LWR@stoppars%
\BlockClass{%
        text\LWR@f@family\LWR@origtilde{}%
        text\LWR@f@series\LWR@origtilde{}%
        text\LWR@f@shape\LWR@origtilde{}%
        text\LWR@f@shapecaps%
    }%
}{\endBlockClass\LWR@startpars}
```

\mdseries

```
\newrobustcmd*{\LWR@HTML@mdseries}{%
    \LWR@print@mdseries%
    \renewcommand*{\LWR@f@series}{md}%
}
\LWR@formatted{mdseries}
```

\bfseries

```
\newrobustcmd*{\LWR@HTML@bfseries}{%
    \LWR@print@bfseries%
    \renewcommand*{\LWR@f@series}{bf}%
}
\LWR@formatted{bfseries}
```

\ebweight From nfssext-cfr.

```
\newrobustcmd*{\LWR@HTML@ebweight}{%
    \LWR@print@ebweight%
    \renewcommand*{\LWR@f@series}{eb}%
}
\LWR@formatted{ebweight}
```

\lgweight From nfssext-cfr.

```
\newrobustcmd*{\LWR@HTML@lgweight}{%
    \LWR@print@lgweight%
    \renewcommand*{\LWR@f@series}{lg}%
}
\LWR@formatted{lgweight}
```

\rmfamily

```
\newrobustcmd*{\LWR@HTML@rmfamily}{%
    \LWR@print@rmfamily%
    \renewcommand*{\LWR@f@family}{rm}%
}
\LWR@formatted{rmfamily}
```

\sffamily

```
\newrobustcmd*{\LWR@HTML@sffamily}{%
    \LWR@print@sffamily%
    \renewcommand*{\LWR@f@family}{sf}%
}
\LWR@formatted{sffamily}
```

\ttfamily

```
\newrobustcmd*{\LWR@HTML@ttfamily}{%
```

```
    \LWR@print@ttfamily%
    \renewcommand*{\LWR@f@family}{tt}%
}
\LWR@formatted{ttfamily}
```

The following use `\AtBeginDocument` due to the LaTeX core `\reinstall@nfss@defs`, which redefines these `\AtBeginDocument`. See **texdoc source2e**.

`\upshape`

```
\newrobustcmd*{\LWR@HTML@upshape}{%
    \LWR@print@upshape%
    \renewcommand*{\LWR@f@shape}{up}%
}
\AtBeginDocument{\LWR@formatted{upshape}}
```

`\itshape`

```
\newrobustcmd*{\LWR@HTML@itshape}{%
    \LWR@print@itshape%
    \renewcommand*{\LWR@f@shape}{it}%
}
\AtBeginDocument{\LWR@formatted{itshape}}
```

`\scshape` Note: `\LWR@print@scshape` is not used here since some fonts, such as erewhon, copy/paste as all-caps.

```
\newrobustcmd*{\LWR@HTML@scshape}{%
    \ifbool{FixSmallCaps}{}{%
        \LWR@print@scshape%
    }%
    \renewcommand*{\LWR@f@shapecaps}{sc}%
}
\AtBeginDocument{\LWR@formatted{scshape}}
```

`\ulcshape` From fontaxes.

```
\@ifundefined{ulcshape}{
    \LetLtxMacro\ulcshape\upshape
}{}
\newrobustcmd*{\LWR@HTML@ulcshape}{%
    \LWR@print@ulcshape%
    \renewcommand*{\LWR@f@shapecaps}{ulc}%
}
\AtBeginDocument{\LWR@formatted{ulcshape}}
```

`\sishape`

```
\@ifundefined{sishape}{
    \LetLtxMacro\sishape\scshape
}{}
```

```
\newrobustcmd*{\LWR@HTML@sishape}{%
    \ifbool{FixSmallCaps}{}{%
        \LWR@print@sishape%
    }%
    \renewcommand*{\LWR@f@shape}{it}
    \renewcommand*{\LWR@f@shapecaps}{sc}%
}
\AtBeginDocument{\LWR@formatted{sishape}}
```

\slshape

```
\newrobustcmd*{\LWR@HTML@slshape}{%
    \LWR@print@slshape%
    \renewcommand*{\LWR@f@shape}{sl}%
}
\AtBeginDocument{\LWR@formatted{slshape}}
```

\sscshape

```
\newrobustcmd{\LWR@HTML@sscshape}{\LWR@HTML@scshape}
\AtBeginDocument{\LWR@formatted{sscshape}}
```

\normalfont

```
\newrobustcmd*{\LWR@HTML@normalfont}{\rmfamily\mdseries\upshape\ulcshape}
\LWR@formatted{normalfont}

\FilenameNullify{%
    \LetLtxMacro\rmfamily\@empty%
    \LetLtxMacro\sffamily\@empty%
    \LetLtxMacro\ttfamily\@empty%
    \LetLtxMacro\bfseries\@empty%
    \LetLtxMacro\ebweight\@empty%
    \LetLtxMacro\lgweight\@empty%
    \LetLtxMacro\mdseries\@empty%
    \LetLtxMacro\upshape\@empty%
    \LetLtxMacro\slshape\@empty%
    \LetLtxMacro\sishape\@empty%
    \LetLtxMacro\scshape\@empty%
    \LetLtxMacro\itshape\@empty%
    \LetLtxMacro\ulcshape\@empty%
    \LetLtxMacro\sscshape\@empty%
    \LetLtxMacro\normalfont\@empty%
}
```

\sp {⟨*text*⟩}

For siunitx. Must work in math mode.

```
\renewcommand{\sp}[1]{\text{<sup>#1</sup>}{}}
```

\sb {⟨*text*⟩}

For siunitx. Must work in math mode.

```
\renewcommand{\sb}[1]{\text{<sub>#1</sub>}{}}
```

`\textsuperscript` {⟨*text*⟩}

```
\newrobustcmd{\LWR@HTML@textsuperscript}[1]{\LWR@htmlspan{sup}{#1}}
\LWR@formatted{textsuperscript}
```

`\@textsuperscript` {⟨*text*⟩}

```
\newcommand{\LWR@HTML@@textsuperscript}[1]{\LWR@htmlspan{sup}{#1}}
\LWR@formatted{@textsuperscript}
```

`\textsubscript` {⟨*text*⟩}

```
    \newrobustcmd{\LWR@HTML@textsubscript}[1]{\LWR@htmlspan{sub}{#1}}
    \LWR@formatted{textsubscript}
```

`\@textsubscript` {⟨*text*⟩}

```
    \newcommand{\LWR@HTML@@textsubscript}[1]{\LWR@htmlspan{sub}{#1}}
    \LWR@formatted{@textsubscript}
```

`\up` {⟨*text*⟩} Prints superscript.

This is `\let` at the beginning of the document in case some other package has changed the definition.

```
\AtBeginDocument{\let\up\textsuperscript}
```

`\fup` {⟨*text*⟩} Prints superscript.

Supports fmtcount package.

This is `\let` at the beginning of the document in case some other package has changed the definition.

```
\AtBeginDocument{\let\fup\textsuperscript}
```

`\underline` {⟨*text*⟩}

```
\renewcommand{\underline}[1]{%
    \InlineClass%
        (text-decoration:underline; text-decoration-skip: auto)%
        {underline}{#1}%
}
```

`\LWR@overline` {⟨*text*⟩}

```
\newcommand{\LWR@overline}[1]{%
    \InlineClass%
        (text-decoration:overline; text-decoration-skip: auto)%
        {overline}{#1}%
}
```

`\LWR@currenttextcolor` The color to use for text and `\rule`, defaulting to black:

```
\newcommand*{\LWR@currenttextcolor}{black}
```

`\LWR@tempcolor` `\LWR@tempcolortwo` The color converted to HTML colorspace.

```
\newcommand*{\LWR@tempcolor}{}
\newcommand*{\LWR@tempcolortwo}{}
```

`\LWR@findcurrenttextcolor` Sets `\LWR@tempcolor` to the current color.

```
\newcommand*{\LWR@findcurrenttextcolor}{%
\renewcommand{\LWR@tempcolor}{000000}%
}
```

`\LWR@textcurrentcolor` {⟨*text*⟩} Like `\textcolor` but uses the current `\color` instead.

```
\NewDocumentCommand{\LWR@textcurrentcolor}{m}{%
    \renewcommand*{\LWR@currenttextcolor}{black}%
    #1%
}
```

```
\end{warpHTML}
```

**for PRINT output:**

```
\begin{warpprint}
```

`\LWR@textcurrentfont` {⟨*text*⟩}

Prints the text with the current font choices.

```
\newcommand*{\LWR@textcurrentfont}[1]{#1}
```

Env `LWR@blocktextcurrentfont` Prints the contents with the current font choices.

```
\newenvironment*{LWR@blocktextcurrentfont}{}{}
```

`\FilenameNullify` {⟨*macros to nullify*⟩}

```
\newcommand*{\FilenameNullify}[1]{}
```

```
\end{warpprint}
```

# 95 Skips, spaces, font sizes

**for HTML output:**

```
\begin{warpHTML}
```

`\,` and `\thinspace` may be redefined by other packages, so are redefined `\AtBeginDocument` here.

Direct-formatting space commands become HTML entities:

```
\AtBeginDocument{
\renewrobustcmd*{\,}{\HTMLunicode{202f}} % HTML thin non-breakable space
\renewrobustcmd*{\thinspace}{\HTMLunicode{202f}}   % HTML thin non-breakable space
\renewrobustcmd*{\negthinspace}{\HTMLunicode{202f}}   % HTML thin non-breakable space
\renewrobustcmd*{~}{\HTMLentity{nbsp}}
\renewrobustcmd*{\textellipsis}{\HTMLunicode{2026}}
\renewrobustcmd*{\vdots}{\HTMLunicode{22EE}}
}
```

Direct-formatting font sizes are remembered for future use:

```
\newcommand*{\LWR@font@size}{normalsize}

\newrobustcmd*{\LWR@HTML@normalsize}{\renewcommand*{\LWR@font@size}{normalsize}}
\LWR@formatted{normalsize}

\newrobustcmd*{\LWR@HTML@small}{\renewcommand*{\LWR@font@size}{small}}
\LWR@formatted{small}

\newrobustcmd*{\LWR@HTML@footnotesize}{\renewcommand*{\LWR@font@size}{footnotesize}}
\LWR@formatted{footnotesize}

\newrobustcmd*{\LWR@HTML@scriptsize}{\renewcommand*{\LWR@font@size}{scriptsize}}
\LWR@formatted{scriptsize}

\newrobustcmd*{\LWR@HTML@tiny}{\renewcommand*{\LWR@font@size}{tiny}}
\LWR@formatted{tiny}

\newrobustcmd*{\LWR@HTML@large}{\renewcommand*{\LWR@font@size}{large}}
\LWR@formatted{large}

\newrobustcmd*{\LWR@HTML@Large}{\renewcommand*{\LWR@font@size}{Large}}
\LWR@formatted{Large}

\newrobustcmd*{\LWR@HTML@LARGE}{\renewcommand*{\LWR@font@size}{LARGE}}
\LWR@formatted{LARGE}

\newrobustcmd*{\LWR@HTML@huge}{\renewcommand*{\LWR@font@size}{huge}}
\LWR@formatted{huge}

\newrobustcmd*{\LWR@HTML@Huge}{\renewcommand*{\LWR@font@size}{Huge}}
\LWR@formatted{Huge}


\DeclareDocumentCommand{\onecolumn}{}{}
```

```
12970
12971 \DeclareDocumentCommand{\twocolumn}{O{}}{
12972
12973 #1
12974
12975 }
```

\hfill

```
12976 \newcommand*{\LWR@HTML@hfill}{\qquad}
12977 \LWR@formatted{hfill}
```

\hrulefill

```
12978 \newcommand*{\LWR@HTML@hrulefill}{%
12979     \ifbool{LWR@doingapar}%
12980         {\rule{1in}{1pt}}%
12981         {%
12982             \LWR@findcurrenttextcolor%
12983             \ifdefstring{\LWR@tempcolor}{000000}%
12984             {%
12985                 \begin{BlockClass}{hrule}%
12986                 \end{BlockClass}%
12987             }%
12988             {%
12989                 \begin{BlockClass}[%
12990                     border-top: 1px solid \LWR@origpound\LWR@tempcolor % space
12991                 ]{hrule}%
12992                 \end{BlockClass}%
12993             }%
12994         }%
12995 }%
12996 \LWR@formatted{hrulefill}
```

\dotfill

```
12997 \newcommand*{\LWR@HTML@dotfill}{\dots}
12998 \LWR@formatted{dotfill}
```

\newpage

```
12999 \renewcommand*{\newpage}{
13000
13001 }
```

\newline Uses the HTML <br /> element.

```
13002 \newrobustcmd*{\LWR@newlinebr}{\unskip\LWR@htmltag{br /}\LWR@orignewline}%
13003 \LetLtxMacro\newline\LWR@newlinebr
```

\\ Redefined to \LWR@endofline or \LWR@tabularendofline.

\qquad Handles special minipage & horizontal space interactions.

```
\renewrobustcmd*{\qquad}{\quad\quad}
```

\enskip Handles special minipage & horizontal space interactions.

```
\renewrobustcmd*{\enskip}{%
    \LWR@minipagestoppars%
    \HTMLunicode{2002}%
    \LWR@minipagestartpars%
}
```

Len \LWR@tempwidth Used to compute span width, height, raise for \hspace and \rule:

Len \LWR@tempheight

Len \LWR@tempraise

```
\newlength{\LWR@tempwidth}
\newlength{\LWR@tempheight}
\newlength{\LWR@tempraise}
```

\LWR@select@html@hspace * {⟨*length*⟩} * {⟨*length*⟩}

\hspace

Handles special minipage & horizontal space interactions.

Prints a span of a given width. Ignores the optional star.

\hspace{\fill} is converted to \hspace{2em}, equal to \qquad.

```
\newcommand{\LWR@select@html@hspace}{%
\RenewDocumentCommand{\hspace}{s m}{%
\setlength{\LWR@tempwidth}{##2}%
```

If \fill, change to \qquad:

```
\ifnum\gluestretchorder\LWR@tempwidth>0%
\setlength{\LWR@tempwidth}{2em}%
\fi%
```

Only if the width is greater than zero:

```
\ifdimcomp{\LWR@tempwidth}{>}{0pt}{%
```

If had a minipage this paragraph, try to inline the white space without generating paragraph tags:

```
    \LWR@minipagestoppars%
```

Support the HTML thin wrappable space:

```
    \ifdimcomp{\LWR@tempwidth}{=}{.16667em}%
    {%
        \HTMLunicode{2009}% thin breakable space
    }%
```

Print the span with the converted width. Not rounded.

```
    {%
        \LWR@htmltagc{%
        span style=\textquotedbl{}width:\LWR@printlength{\LWR@tempwidth}; % extra space
                display:inline-block\textquotedbl%
        }%
```

If formatting for a word processor, approximate with a number of \quads, in case a span of a given width is not supported:

```
        \ifbool{FormatWP}{%
            \setlength{\LWR@templengthone}{\LWR@tempwidth}%
            \whiledo{\lengthtest{\LWR@templengthone>1em}}{%
                \quad%
                \addtolength{\LWR@templengthone}{-1em}%
            }%
        }%
```

If NOT formatting for a word processor, include an empty comment to avoid an empty span:

```
        {\LWR@htmlcomment{}}%
```

Close the span:

```
        \LWR@htmltagc{/span}%
    }%
```

If had a minipage this paragraph, try to inline the white space without generating paragraph tags:

```
    \LWR@minipagestartpars%
}{}% width greater than 0
}%
}
```

\LWR@select@html@nohspace
\hspace * {⟨*length*⟩}

Used to disable \hspace while creating description \items.

```
\newcommand{\LWR@select@html@nohspace}{%
    \RenewDocumentCommand{\hspace}{s m}{}%
}
```

\LWR@select@print@hspace

```
\newcommand*{\LWR@select@print@hspace}{%
    \renewrobustcmd\hspace{\@ifstar\@hspacer\@hspace}%
}
```

\hspace * {⟨*length*⟩}

Handles special minipage & horizontal space interactions.

```
\LWR@select@html@hspace
```

`\LWR@vspace` * {⟨*length*⟩} Nullified vspace.

```
13069 \NewDocumentCommand{\LWR@HTML@vspace}{s m}{}
13070
13071 \LWR@formatted{vspace}
```

`\linebreak` [⟨*num*⟩] Inserts an HTML br tag.

```
13072 \renewcommand*{\linebreak}[1][]{\newline}
```

`\nolinebreak` [⟨*num*⟩]

```
13073 \renewcommand*{\nolinebreak}[1][]{}
```

`\pagebreak` [⟨*num*⟩] Starts a new paragraph.

```
13074 \renewcommand*{\pagebreak}[1][]{
13075
13076 }
```

`\nopagebreak` [⟨*num*⟩]

```
13077 \renewcommand*{\nopagebreak}[1][]{}
```

`\enlargethispage` * {⟨*len*⟩}

```
13078 \RenewDocumentCommand{\enlargethispage}{s m}{}
```

`\clearpage`
`\cleardoublepage`

```
13079 \renewcommand*{\clearpage}{}
13080 \renewcommand*{\cleardoublepage}{}
```

`\rule` [⟨*raise*⟩] {⟨*width*⟩} {⟨*height*⟩}

Handles special minipage & horizontal space interactions.

Creates a span of a given width and height. Ignores the optional star.

`\fill` is zero-width, so `\hspace{\fill}` is ignored.

```
13081 \newcommand*{\LWR@HTML@rule}[3][]{%
```

The width is copied into a temporary LaTeX length, from which comparisons and conversions may be made:

```
13082 \setlength{\LWR@tempwidth}{#2}%
```

If it's zero-width then skip the entire rule:

```
\ifthenelse{\lengthtest{\LWR@tempwidth=0pt}}%
{}% zero- width
{% non-zero width
```

If it's non-zero width, set a minimal thickness so that it more reliably shows in the browser:

```
    \ifthenelse{%
        \lengthtest{\LWR@tempwidth>0pt}\AND%
        \lengthtest{\LWR@tempwidth<1pt}%
    }%
        {\setlength{\LWR@tempwidth}{1pt}}%
        {}%
```

Likewise with height:

```
    \setlength{\LWR@tempheight}{#3}%
    \ifthenelse{%
        \lengthtest{\LWR@tempheight>0pt}\AND%
        \lengthtest{\LWR@tempheight<1pt}%
    }%
        {\setlength{\LWR@tempheight}{1pt}}%
        {}%
```

If had a minipage this paragraph, try to inline the rule without generating paragraph tags:

```
    \LWR@minipagestoppars%
```

Print the span with the converted width and height. The width and height are NOT rounded, since a height of less than 1pt is quite common in LaTeX code.

```
    \LWR@findcurrenttextcolor%
    \LWR@htmltagc{%
    span\LWR@indentHTML%
    style=\textquotedbl%
```

The HTML background color is used to draw the filled rule according to the LaTeX foreground color set by `\textcolor`.

```
    \ifbool{FormatWP}{}{background:\LWR@currenttextcolor ; }%
```

The width and height are printed, converted to PT:

```
    width:\LWR@printlength{\LWR@tempwidth} ; %
    height:\LWR@printlength{\LWR@tempheight} ; %
```

The raise height is converted to a CSS transform. The `*2` raise multiplier is to approximately match HTML output's X height. Conversion to a LaTeX length allows a typical LaTeX expression to be used as an argument for the raise, whereas printing the raise argument directly to HTML output without conversion to a LaTeX length limits the allowable syntax. To do: A superior method would compute a ratio of LaTeX ex height, then print that to HTML with an ex unit.

```
    \ifblank{#1}%
    {}%
```

```
    {%
        \setlength{\LWR@tempraise}{0pt-#1}%
        \setlength{\LWR@tempraise}{\LWR@tempraise*2}%
        \LWR@indentHTML%
        -ms-transform: translate(0pt,\LWR@printlength{\LWR@tempraise}); %
        \LWR@indentHTML%
        -webkit-transform: translate(0pt,\LWR@printlength{\LWR@tempraise}); %
        \LWR@indentHTML%
        transform: translate(0pt,\LWR@printlength{\LWR@tempraise}); %
        \LWR@indentHTML%
    }%
```

Display inline-block to place the span inline with the text:

```
    display:inline-block;\textquotedbl\LWR@orignewline%
    }%
```

If formatting for a word processor, approximate with a number of underscores, in case a span of a given width is not supported:

```
        \ifbool{FormatWP}{%
            \setlength{\LWR@templengthone}{\LWR@tempwidth}%
            \whiledo{\lengthtest{\LWR@templengthone>1em}}{%
                \_{}%
                \addtolength{\LWR@templengthone}{-1em}%
            }%
        }%
```

If NOT formatting for a word processor, add a comment to avoid an empty :

```
        {\LWR@htmlcomment{}}%
```

Close the span:

```
    \LWR@htmltagc{/span}%
```

If had a minipage this paragraph, try to inline the white space without generating paragraph tags:

```
    \LWR@minipagestartpars%
}% non-zero width
}

\LWR@formatted{rule}

\end{warpHTML}
```

## 96 \phantomsection

**for HTML output:**

```
\begin{warpHTML}
```

\LWR@phantomsection Emulate the hyperref \phantomsection command, often used to insert the bibliography into the table of contents. Ignores \ForceHTMLTOC.

```
\newrobustcmd*{\LWR@phantomsection}{%
    \begingroup%
    \boolfalse{LWR@forcinghtmltoc}%
    \section*{}%
    \endgroup%
}
```

```
\end{warpHTML}
```

# 97 \LaTeX and other logos

Logos for HTML and print modes:

Some of these logos may be redefined in a later package, so after loading other packages, and at the beginning of the document, their definitions are finally set by \LWR@formatted.

For CSS conversions, see:
http://edward.oconnor.cx/2007/08/tex-poshlet
http://nitens.org/taraborelli/texlogo
and the spacing described in the metafont package documentation.

**for HTML & PRINT:**

```
\begin{warpall}
\newbool{LWR@warnXe}
\boolfalse{LWR@warnXe}

\newrobustcmd*{\Xe}
    {%
        X\hspace{-.1667em}\raisebox{-.5ex}{E}%
        \global\booltrue{LWR@warnXe}%
    }

\AtBeginDocument{
    \@ifpackageloaded{graphics}{
        \@ifpackageloaded{metalogo}{}{
            \renewrobustcmd*{\Xe}
                {X\hspace{-.1667em}\raisebox{-.5ex}{\reflectbox{E}}}
        }
    }{}
}

\AtEndDocument{
    \ifbool{LWR@warnXe}{
        \PackageWarningNoLine{lwarp}{Load graphicx or graphics
            for improved XeTeX logo}
    }{}
}

\providerobustcmd*{\XeTeX}{\mbox{\Xe\hspace{-.125em}\TeX}}
\providerobustcmd*{\XeLaTeX}{\mbox{\Xe\hspace{-.125em}\LaTeX}}
\providerobustcmd*{\AmS}{%
```

```
    \leavevmode\hbox{$\mathcal A\kern-.2em\lower.376ex%
    \hbox{$\mathcal M$}\kern-.2em\mathcal S$}%
}
\newrobustcmd*{\LyX}{\textsf{LyX}}
\providerobustcmd*{\LuaTeX}{\mbox{Lua\TeX}}
\providerobustcmd*{\LuaLaTeX}{\mbox{Lua\LaTeX}}
\providerobustcmd*{\BibTeX}{\mbox{B\textsc{ib}\TeX}}
\providerobustcmd*{\MakeIndex}{\mbox{\textit{MakeIndex}}}
\providerobustcmd*{\ConTeXt}{\mbox{Con\TeX{}t}}
\providerobustcmd*{\MiKTeX}{\mbox{MiK\TeX}}
\end{warpall}
```

**for HTML output:**

```
\begin{warpHTML}
```

The print-mode versions of the following may be changed by metalogo, so their print formatting is recorded `\AtBeginDocument`.

`\TeX` TEX

`latexlogo` is a css class used to properly typeset the E and A in LATEX and friends.

`latexlogofont` is a css class used to select the font for the rest of the logo in LATEX, LuaTEX, ConTEXt, etc.

```
\newrobustcmd*{\LWR@HTML@TeX}
{%
    \InlineClass{latexlogofont}%
    {%
        \InlineClass{latexlogo}%
        {%
            T%
            \InlineClass{latexlogosub}{e}%
            X%
        }%
    }%
}
\AtBeginDocument{\LWR@formatted{TeX}}% may have been patched by metalogo
```

`\LaTeX` LATEX, LATEX $2_\varepsilon$
`\LaTeXe`

```
\newrobustcmd*{\LWR@HTML@LaTeX}
{%
    \InlineClass{latexlogofont}%
    {%
        \InlineClass{latexlogo}%
        {%
            L%
            \InlineClass{latexlogosup}{a}%
            T%
            \InlineClass{latexlogosub}{e}%
            X%
        }%
    }%
}
```

```
13213
13214 \AtBeginDocument{\LWR@formatted{LaTeX}}% may have been patched by metalogo
13215
13216
13217 \newrobustcmd*{\LWR@HTML@LaTeXe}
13218 {%
13219     \LaTeX%
13220     \InlineClass{latexlogofont}{%
13221         \InlineClass{latexlogotwoe}{%
13222             2%
13223             \InlineClass{latexlogotwoesub}{\HTMLunicode{03B5}}%
13224         }%
13225     }%
13226 }
13227 \AtBeginDocument{\LWR@formatted{LaTeXe}}% may have been patched by metalogo
```

\LuaTeX \LuaLaTeX LuaTeX, LuaLaTeX

```
13228 \newrobustcmd*{\LWR@HTML@LuaTeX}{\InlineClass{latexlogofont}{Lua}\TeX}
13229 \AtBeginDocument{\LWR@formatted{LuaTeX}}% may have been patched by metalogo
13230
13231 \newrobustcmd*{\LWR@HTML@LuaLaTeX}{\InlineClass{latexlogofont}{Lua}\LaTeX}
13232 \AtBeginDocument{\LWR@formatted{LuaLaTeX}}% may have been patched by metalogo
```

\XeTeX \XeLaTeX XeTeX, XeLaTeX

xetexlogo is a css class which aligns the backwards E in XeTeX and spaces TeX appropriately.

xelatexlogo is a css class which aligns the backwards E in XeLaTeX and spaces LaTeX appropriately.

```
13233 \newrobustcmd*{\LWR@HTML@Xe}
13234     {%
13235         X%
13236         \InlineClass{xelatexlogosub}{\HTMLunicode{18e}}%
13237     }
13238 \AtBeginDocument{\LWR@formatted{Xe}}% may have been patched by metalogo
13239
13240 \newrobustcmd*{\LWR@HTML@XeTeX}{\InlineClass{xelatexlogo}{\Xe}\TeX}
13241 \AtBeginDocument{\LWR@formatted{XeTeX}}% may have been patched by metalogo
13242
13243 \newrobustcmd*{\LWR@HTML@XeLaTeX}{\InlineClass{xelatexlogo}{\Xe}\LaTeX}
13244 \AtBeginDocument{\LWR@formatted{XeLaTeX}}% may have been patched by metalogo
```

\ConTeXt ConTeXt

```
13245 \newrobustcmd*{\LWR@HTML@ConTeXt}{%
13246     \InlineClass{latexlogofont}{Con}\TeX{}%
13247     \InlineClass{latexlogofont}{t}%
13248 }
13249 \LWR@formatted{ConTeXt}
```

\BibTeX \MakeIndex BibTeX, *MakeIndex*

```
\newrobustcmd*{\LWR@HTML@BibTeX}
    {\InlineClass{latexlogofont}{B\textsc{ib}}\TeX}
\LWR@formatted{BibTeX}

\newrobustcmd*{\LWR@HTML@MakeIndex}
    {\InlineClass{latexlogofont}{\textit{MakeIndex}}}
\LWR@formatted{MakeIndex}
```

\AmS $\mathcal{AMS}$

amslogo is a css class used for the $\mathcal{AMS}$ logo.

```
\AtBeginDocument{%
\newrobustcmd*{\LWR@HTML@AmS}
{%
    \InlineClass{amslogo}{%
        \textit{%
            A%
            \InlineClass{latexlogosub}{M}%
            S%
        }%
    }%
}%
\LWR@formatted{AmS}
}
```

\MiKTeX MiKTeX

```
\newrobustcmd*{\LWR@HTML@MiKTeX}{\InlineClass{latexlogofont}{MiK}\TeX}
\LWR@formatted{MiKTeX}
```

\LyX LyX

lyxlogo is a css class used for the LyX logo.

```
\newrobustcmd*{\LWR@HTML@LyX}{\InlineClass{lyxlogo}{LyX}}
\LWR@formatted{LyX}

\end{warpHTML}
```

# 98 Starting and stopping lwarp

**for HTML output:**

```
\begin{warpHTML}
```

\LWR@LwarpStart \LWR@LwarpEnd Automatically sets up the HTML-related actions for the start and end of the document.

```
\AfterEndPreamble{\LWR@LwarpStart}
\AtEndDocument{\LWR@LwarpEnd}

\end{warpHTML}
```

## 99 Loading everyshi patches

everyshi is emulated by the LaTeX core, so its patches are loaded here. `\AtBeginDocument` is used in case an older verison of LaTeX is used.

for HTML output:
```
\begin{warpHTML}
\AtBeginDocument{
    \@ifpackageloaded{everyshi}{
        \RequirePackage{lwarp-everyshi}
    }{}
}
\end{warpHTML}
```

## 100 Loading textcomp patches

textcomp has now been integrated into the LaTeX core, so its patches are loaded now.

for HTML output:
```
\begin{warpHTML}
\RequirePackage{lwarp-textcomp}
\end{warpHTML}
```

## 101 Loading amsmath, amsthm patches, centernot

amsmath, amsthm, and centernot may have been preloaded, such as by newtx, so their patches are loaded now.

for HTML output:
```
\begin{warpHTML}
\@ifpackageloaded{amsthm}{
    \RequirePackage{lwarp-amsthm}
}{}

\@ifpackageloaded{amsmath}{
    \RequirePackage{lwarp-amsmath}
}{}
```

amsthm may load centernot, so centernot must be checked second.

```
\@ifpackageloaded{centernot}{
    \RequirePackage{lwarp-centernot}
}{}
\end{warpHTML}
```

## 102 Loading Koma-script class patches

Load patches to koma-script.

for HTML output:
```
\begin{warpHTML}
```

```
    \@ifundefined{chapter}{
        \renewcommand{\thesection}{\@arabic\c@section}
    }{
        \renewcommand{\thechapter}{\@arabic\c@chapter}
        \renewcommand{\thesection}{\thechapter.\@arabic\c@section}
    }
    \renewcommand{\thesubsection}{\thesection.\@arabic\c@subsection}
    \renewcommand{\thesubsubsection}{%
    \thesubsection.\@arabic\c@subsubsection}
    \renewcommand{\theparagraph}{%
    \thesubsubsection.\@arabic\c@paragraph}
    \renewcommand{\thesubparagraph}{%
    \theparagraph.\@arabic\c@subparagraph}
    \@ifundefined{chapter}{
        \renewcommand{\thefigure}{\@arabic\c@figure}
        \renewcommand{\thetable}{\@arabic\c@table}
    }{
        \renewcommand{\thefigure}{%
        \ifnum\c@chapter>\z@\thechapter.\fi\@arabic\c@figure}
        \renewcommand{\thetable}{%
        \ifnum\c@chapter>\z@\thechapter.\fi\@arabic\c@table}
    }
}

\@ifclassloaded{ujarticle}{\LWR@patchujtclasses}{}
\@ifclassloaded{ujbook}{\LWR@patchujtclasses}{}
\@ifclassloaded{ujreport}{\LWR@patchujtclasses}{}
\@ifclassloaded{utarticle}{\LWR@patchujtclasses}{}
\@ifclassloaded{utbook}{\LWR@patchujtclasses}{}
\@ifclassloaded{utreport}{\LWR@patchujtclasses}{}
\@ifclassloaded{ltjarticle}{\LWR@patchujtclasses}{}
\@ifclassloaded{ltjbook}{\LWR@patchujtclasses}{}
\@ifclassloaded{ltjreport}{\LWR@patchujtclasses}{}
\@ifclassloaded{ltjsarticle}{\LWR@patchujtclasses}{}
\@ifclassloaded{ltjsbook}{\LWR@patchujtclasses}{}
\@ifclassloaded{ltjsreport}{\LWR@patchujtclasses}{}
\@ifclassloaded{ltjskiyou}{\LWR@patchujtclasses}{}
\@ifclassloaded{ltjspf}{\LWR@patchujtclasses}{}
\@ifclassloaded{ltjtarticle}{\LWR@patchujtclasses}{}
\@ifclassloaded{ltjtbook}{\LWR@patchujtclasses}{}
\@ifclassloaded{ltjtreport}{\LWR@patchujtclasses}{}

\end{warpHTML}
```

## 105 CTEX patches

Patches for ctex and related classes, which are loaded before lwarp.

All CTEX classes and the ctex package seem to load ctexpatch, so its presence is used to decide whether to have lwarp patch CTEX.

**for HTML output:**

```
\begin{warpHTML}
```

\AtBeginDocument in case the user set FileSectionNames in the preamble.

```
\AtBeginDocument{
    \@ifpackageloaded{ctexpatch}{%
        \def\@partcntformat#1{%
            \LWR@isolate{\CTEX@partname}~%
            \CTEX@part@aftername%
        }%

        \def\@partnameformat{}

        \def\@chapcntformat#1{%
            \LWR@isolate{\CTEX@chaptername}~%
            \CTEX@chapter@aftername%
        }%

        \renewcommand*{\LWR@printchaptername}{}
    }{}
}
```

```
\end{warpHTML}
```

# 106 kotexutf patches

Patch for kotexutf, which is loaded before lwarp.

kotexutf's \@setref was conflicting with lwarp's cross references.

**for HTML output:**

```
\begin{warpHTML}
```

If kotexutf's version of \@setref is detected, it is reverted to the original.

```
\AtBeginDocument{
\@ifpackageloaded{kotexutf}{%
    \def\LWR@kotexutf@setref#1#2#3{%
        \@setref@dhucs@orig{#1}{#2}{#3}%
      \ifx#1\relax\else
        \bgroup
        \dhucs@make@cjkchar@null
        \edef\@temp{\expandafter#2#1}\global\josatoks\expandafter{\@temp}%
        \egroup
      \fi%
    }%

    \ifdefequal{\@setref}{\LWR@kotexutf@setref}{
        \let\@setref\@setref@dhucs@orig
    }{}
}{}
}
```

```
\end{warpHTML}
```

# 107 babel and polyglossia warnings

lwarp prints a message instructing the user how to avoid the following error.

(These are not \PackageWarnings because there may not be a problem.)

lwarp uses cleveref, which has some limitations when using polyglossia, possibly resulting in the error

```
! Undefined control sequence. . . . \__hook begindocument
```

To test compatibility, add

```
\usepackage{cleveref}
```

near the end of the preamble (as the last package to be loaded), and try to compile the print version. It may be necessary to set

```
\setdefaultlanguage{english}
```

or some other language supported by cleveref, then select other languages using \setotherlanguages.

Once the print version works with cleveref and polyglossia, the HTML version should work as well using lwarp.

**for HTML output:**

```
\begin{warpHTML}
\AtBeginDocument{

\@ifpackageloaded{polyglossia}{
    \PackageWarningNoLine{lwarp}
    {%
        Polyglossia has been loaded.  Lwarp also uses cleveref.\MessageBreak
        See the cleveref documentation regarding\MessageBreak
        polyglossia support.  Some languages are not supported%
    }
    \typeout{---}
    \typeout{Package lwarp:}
    \typeout{If the error}
    \typeout{\space\space``! Undefined control sequence.
        \space ... \space \protect\__hook begindocument''}
    \typeout{occurs here, use the polyglossia macro:}
    \typeout{\space\space\protect\setmainlanguage\protect{...\protect}}
    \typeout{---}
}{
    \@ifpackageloaded{babel}{
        \PackageWarningNoLine{lwarp}
        {%
            Babel has been loaded.  Lwarp also uses cleveref.\MessageBreak
            See the cleveref documentation regarding\MessageBreak
            babel support.  Some languages are not supported%
        }
    }{}
}

```

```
}
\end{warpHTML}
```

# 108 MathJax warnings

\LWR@mathjaxwarn {⟨*packagename*⟩} {⟨*More text.*⟩}

To be done \AtBeginDocument.

```
\newcommand*{\LWR@mathjaxwarn}[2]{%
    \@ifpackageloaded{lwarp-#1}{%
        \ifblank{#2}{%
            \PackageWarningNoLine{lwarp}
                {%
                   Lwarp provides emulation for MathJax when used\MessageBreak
                    with the #1 package%
                }
        }{%
            \PackageWarningNoLine{lwarp}
                {%
                   Lwarp provides emulation for MathJax when used\MessageBreak
                    with the #1 package.\MessageBreak
                    #2%
                }
        }%
    }{}%
}

% \begin{macro}{\LWR@nomathjaxwarn} \marg{packagename} \marg{More text.}
%
% To be done \cs{AtBeginDocument}.
%
% \changes{v0.894}{2020/12/22}{Warn if using packages not supported by \brand{MathJax}.}
% \changes{v0.895}{2021/01/08}{Improved \brand{MathJax} warning.}
%    \begin{macrocode}
\newcommand*{\LWR@nomathjaxwarn}[2]{%
    \@ifpackageloaded{lwarp-#1}{%
        \ifblank{#2}{%
            \PackageWarningNoLine{lwarp}
                {%
                   Lwarp does not provide MathJax support for #1.\MessageBreak
                    Use SVG math by removing the Lwarp mathjax option%
                }
        }{%
            \PackageWarningNoLine{lwarp}
                {%
                   Lwarp does not provide MathJax support for #1.\MessageBreak
                    #2%
                }
        }%
    }{}%
}
```

```
13534             }
13535         \LWR@nomathjaxwarn{jkmath}
13536             {\LWR@forceSVGmessage{jkmath}}
13537         \LWR@mathjaxwarn{libertinust1math}
13538         {Some of the symbol font macros such as \protect\mathsfbfit\MessageBreak
13539                do not use a sans font because MathJax does not yet\MessageBreak
13540                 have sans Greek.  Tensors may look like vectors%
13541             }
13542         \LWR@mathjaxwarn{mathtools}
13543             {See the Lwarp manual regarding the disallowspaces\MessageBreak
13544             and showonlyrefs options, the alignat environment,\MessageBreak
13545             and \protect\DeclarePairedDelimiter\space and related%
13546             }
13547         \LWR@mathjaxwarn{mathspec}
13548             {Double quotes are removed, even inside \protect\text}
13549         \LWR@mathjaxwarn{multirow}
13550             {Multirow works as expected in text mode, but\MessageBreak
13551             limited emulation is provided for MathJax math.\MessageBreak
13552             \protect\multirow\space ignores all arguments except\MessageBreak
13553             the text}
13554         \LWR@mathjaxwarn{nicematrix}
13555             {Keys/values are ignored in MathJax.\MessageBreak
13556             \protect\Cdots, etc. do not span multiple cells.\MessageBreak
13557             AutoNiceMatrix, etc. are not supported for MathJax.\MessageBreak
13558             \LWR@forceSVGmessage{nicematrix}%
13559             }
13560         \LWR@nomathjaxwarn{pb-diagram}
13561             {\LWR@forceSVGmessage{pb-diagram}}
13562 %         \LWR@mathjaxwarn{physics}
13563 % %             {The third-party extension is not used.\MessageBreak
13564 %             {The MathJax v3 extension is used.\MessageBreak
13565 %             See the Lwarp manual for details}
13566         \LWR@nomathjaxwarn{tensind}{}
13567         \LWR@mathjaxwarn{unicode-math}
13568             {Do not use embedded Unicode characters.\MessageBreak
13569             (Not all characters are encoded correctly.)\MessageBreak
13570             Some symbol fonts are not supported by MathJax,\MessageBreak
13571             and are only approximated.\MessageBreak
13572         Greek macros such as \protect\alpha\space respond to the math-style\MessageBreak
13573             option.  Latin symbols does not, per MathJax\MessageBreak
13574            limitations, unless placed inside \protect\symbit\space or similar}
13575         \LWR@nomathjaxwarn{unitsdef}{}
13576         \LWR@mathjaxwarn{witharrows}
13577             {Arrows can only point to the next line.\MessageBreak
13578             Text is only placed on a single line}
13579         \LWR@nomathjaxwarn{xy}
13580           {In text, xy works as-is.  SVG images will be generated.\MessageBreak
13581             \LWR@forceSVGmessage{xy}}
13582     }{}
13583 }
```

File 2 **lwarp-2in1.sty**

## § 109 Package 2in1

Pkg 2in1 2in1 is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{2in1}
```

File 3 **lwarp-2up.sty**

## § 110 Package 2up

Pkg 2up 2up is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{2up}[2010/05/15]

\def\source#1#2#3{}
\def\target#1#2#3{}
\def\targetlayout#1{}
\newdimen\pageseplength
\newdimen\pagesepwidth
\newdimen\pagesepoffset
\def\twoupemptypage{}
\def\twoupclearpage{}
\def\twoupeject{}
\def\twouparticle{}
\def\twoupplain{}
\def\twouplegaltarget{}
\def\twouplandscape{}
\def\TwoupWrites{}
```

File 4 **lwarp-a4.sty**

## § 111 Package a4

Pkg a4 a4 is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{a4}[2004/04/15]

\newcommand*{\WideMargins}{}
```

File 5 **lwarp-a4wide.sty**

## § 112 Package a4wide

Pkg a4wide a4wide is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{a4wide}[1994/08/30]
```

---

File 6 **lwarp-a5comb.sty**

## § 113 Package a5comb

Pkg a5comb a5comb is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{a5comb}
```

---

File 7 **lwarp-abstract.sty**

## § 114 Package abstract

(*Emulates or patches code by* Peter Wilson.)

Pkg abstract abstract is supported and patched by lwarp.

⚠ missing toc If using the number option with file splits, be sure to place the table of contents before the abstract. The number option causes a section break which may cause a file split, which would put a table of contents out of the home page if it is after the abstract.

**for HTML output:** memoir provides an abstract environment even though it is not an article or report class. Meanwhile, lwarp loads book to emulate memoir, but book does not have an abstract environment, so when the abstract package is loaded for emulation there is no pre-existing abstract to redefine, which would cause an error. Thus, a null abstract is provide here:

```
\ProvideDocumentEnvironment{abstract}{}{}{}
```

Accept all options for lwarp-abstract:

```
\LWR@ProvidesPackagePass{abstract}[2009/06/08]

\AtBeginDocument{
\BeforeBeginEnvironment{abstract}{
\LWR@forcenewpage
\BlockClass{abstract}
}
\AfterEndEnvironment{abstract}{\endBlockClass}
}

\renewcommand{\@bsrunintitle}{%
\hspace*{\abstitleskip}%
{\abstractnamefont%
\InlineClass{abstractrunintitle}{\abstractname}%
\@bslabeldelim}%
}
```

```
\@ifclassloaded{memoir}
{
  \renewenvironment{abstract}{%
% %     \titlepage
%     \null\vfil
%     \@beginparpenalty\@lowpenalty
  \setup@bstract
    \if@bsrunin
    \else
%       \if@bsstyle
%         \abstitlestyle{\BlockClassSingle{abstracttitle}{\abstractname}}
%       \else
        \ifnumber@bs
          \num@bs
        \else
          \begin{\absnamepos}%
  \abstractnamefont \BlockClassSingle{abstracttitle}{\abstractname}
%             \@endparpenalty\@M
          \end\absnamepos%
       \vspace{\abstitleskip}%
        \fi
%       \fi
%       \vspace{\abstitleskip}%
    \fi
    \put@bsintoc%
    \begin{@bstr@ctlist}\if@bsrunin\@bsrunintitle\fi\abstracttextfont}%
    {\par\end{@bstr@ctlist}%\vfil\null%\endtitlepage
    }
}{% not memoir
\if@titlepage
  \renewenvironment{abstract}{%
%     \titlepage
    \null\vfil
    \@beginparpenalty\@lowpenalty
    \if@bsrunin
    \else
      \if@bsstyle
        \abstitlestyle{\BlockClassSingle{abstracttitle}{\abstractname}}
      \else
        \ifnumber@bs
          \num@bs
        \else
          \begin{\absnamepos}%
  \abstractnamefont \BlockClassSingle{abstracttitle}{\abstractname}
            \@endparpenalty\@M
          \end\absnamepos%
%%        \vspace{\abstitleskip}%
        \fi
      \fi
      \vspace{\abstitleskip}%
    \fi
    \put@bsintoc%
    \begin{@bstr@ctlist}\if@bsrunin\@bsrunintitle\fi\abstracttextfont}%
    {\par\end{@bstr@ctlist}\vfil\null%\endtitlepage
    }
```

```
\else
  \renewenvironment{abstract}{%
    \if@bsrunin
    \else
      \if@bsstyle
        \abstitlestyle{\BlockClassSingle{abstracttitle}{\abstractname}}
      \else
        \ifnumber@bs
          \num@bs
        \else
\begin{\absnamepos}%
\abstractnamefont\BlockClassSingle{abstracttitle}{\abstractname}%
\end\absnamepos%
%%        \vspace{\abstitleskip}%
        \fi
      \fi
      \vspace{\abstitleskip}%
    \fi
    \put@bsintoc%
    \begin{@bstr@ctlist}\if@bsrunin\@bsrunintitle\fi\abstracttextfont}%
    {\par\end{@bstr@ctlist}}
\fi
}% not memoir
```

File 8 **lwarp-academicons.sty**

# § 115 Package academicons

(*Emulates or patches code by* Diogo A. B. Fernandes.)

Pkg academicons academicons is patched for use by lwarp.

If \aiicon is used, the name of the icon is used in the alt tag. Otherwise, for each of the individual icon macros, a generic alt tag is used.

**for HTML output:**

```
\LWR@ProvidesPackagePass{academicons}[2018/06/27]

\LetLtxMacro\LWR@orig@symbol\symbol

\let\LWR@academicons@orig@AI\AI

\newcommand*{\LWR@academicons@symbol}[1]{%
    \begin{lateximage}*[academicon][academicons#1]%
    \begingroup%
    \LWR@academicons@orig@AI%
    \LWR@orig@symbol{#1}%
    \endgroup%
    \end{lateximage}%
}

\renewcommand*{\AI}{%
    \LetLtxMacro\symbol\LWR@academicons@symbol%
}
```

```
\renewcommand*{\aiicon}[1]
{%
    \begin{lateximage}*[#1 icon][academicons#1]%
    \AI\csname aiicon@#1\endcsname%
    \end{lateximage}%
}
```

File 9 **lwarp-accents.sty**

§ 116 Package

# accents

(*Emulates or patches code by* Javier Bezos.)

Pkg accents accents is used as-is for SVG math, and is emulated for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{accents}[2006/05/12]
```

For MathJax:

```
\begin{warpMathJax}
\LWR@infoprocessingmathjax{accents}

\CustomizeMathJax{\newcommand{\ring}[1]{\mathring{#1}}}
\CustomizeMathJax{\newcommand{\accentset}[2]{\overset{#1{}}{#2}}}
```

As of this writing, MathJax v3 does not yet support groups for macros, so for \underaccent, the originals are remembered here, then they are temporarily redefined and used inside \underaccent, then restored to their originals. \LARGE gives a reasonable size, and \raise is used to adjust vertically without introducing extra line space.

```
\CustomizeMathJax{\let\LWRgrave\grave}
\CustomizeMathJax{\let\LWRacute\acute}
\CustomizeMathJax{\let\LWRcheck\check}
\CustomizeMathJax{\let\LWRbreve\breve}
\CustomizeMathJax{\let\LWRbar\bar}
\CustomizeMathJax{\let\LWRhat\hat}
\CustomizeMathJax{\let\LWRdot\dot}
\CustomizeMathJax{\let\LWRtilde\tilde}
\CustomizeMathJax{\let\LWRddot\ddot}
\CustomizeMathJax{\let\LWRvec\vec}
\CustomizeMathJax{\let\LWRwidetilde\widetilde}

\CustomizeMathJax{\newcommand{\underaccent}[2]{%
    {%
    \renewcommand{\grave}[1]{{\LARGE\LWRgrave{##1}}}%
    \renewcommand{\acute}[1]{{\LARGE\LWRacute{##1}}}%
    \renewcommand{\check}[1]{{\LARGE\LWRcheck{##1}}}%
    \renewcommand{\breve}[1]{{\LARGE\LWRbreve{##1}}}%
    \renewcommand{\bar}[1]{{\LARGE\LWRbar{##1}}}%
    \renewcommand{\hat}[1]{{\LARGE\LWRhat{##1}}}%
    \renewcommand{\dot}[1]{{\LARGE\LWRdot{##1}}}%
```

```
    \renewcommand{\tilde}[1]{{\LARGE\LWRtilde{##1}}}%
    \renewcommand{\ddot}[1]{{\LARGE\LWRddot{##1}}}%
    \renewcommand{\vec}[1]{{\LARGE\LWRvec{##1}}}%
    \renewcommand{\widetilde}[1]{{\LARGE\LWRwidetilde{\hphantom{#2}}}}%
    \underset{\raise 2pt {#1{}}}{#2}%
    \let\grave\LWRgrave%
    \let\acute\LWRacute%
    \let\check\LWRcheck%
    \let\breve\LWRbreve%
    \let\bar\LWRbar%
    \let\hat\LWRhat%
    \let\dot\LWRdot%
    \let\tilde\LWRtilde%
    \let\ddot\LWRddot%
    \let\vec\LWRvec%
    \let\widetilde\LWRwidetilde%
    }%
}}

\CustomizeMathJax{\newcommand{\undertilde}[1]{%
    \underset{\raise 3pt {\widetilde{\hphantom{#1}}}}{#1}%
}}
\end{warpMathJax}
```

File 10 **lwarp-accessibility.sty**

## § 117 Package accessibility

Pkg accessibility accessibility is emulated.

**for HTML output:** Discard all options for lwarp-accessibility:

```
\LWR@ProvidesPackageDrop{accessibility}[2019/10/14]

\newcommand{\alt}[1]{\ThisAltText{#1}}
\newcommand{\newhref}[3]{\ThisAltText{#2}\LWR@href{#1}{#3}}%
\providecommand{\thead}[1]{\textbf{#1}}
```

For MathJax:

```
\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\alt}[1]{}}
\CustomizeMathJax{\newcommand{\thead}[1]{\text{\textbf{#1}}}}
\end{warpMathJax}
```

File 11 **lwarp-accsupp.sty**

## § 118 Package accsupp

Pkg accsupp accsupp is ignored.

```
{% before v3
\@ifpackagelater{acro}{2019/09/23}%
{% v2.10 or later
\cs_gset_protected:Npn \__acro_typeset:nn #1#2
  {
    \mode_if_horizontal:F { \leavevmode }
    \group_begin:
      \use:x
        {
          \bool_if:cTF {l__acro_custom_#1_format_bool}
            { \exp_not:v {l__acro_custom_#1_format_tl} }
            { \exp_not:v {l__acro_#1_format_tl} }
            {\exp_not:N\LWR@textcurrentfont{#2}}%   lwarp
        }
    \group_end:
  }

\cs_gset_protected:Npn \__acro_ending_format:nn #1#2
  {
    \bool_if:NTF \l__acro_include_endings_format_bool
      {
        \str_case:nn {#1}
          {
            {long}
            {
              \bool_if:NTF \l__acro_custom_long_format_bool
                { \l__acro_custom_long_format_tl }
                {
                  \bool_if:NTF \l__acro_first_instance_bool
                    { \l__acro_first_long_format_tl }
                    { \l__acro_long_format_tl }
                }
            }
            {short}
            {
              \bool_if:NTF \l__acro_custom_short_format_bool
                { \l__acro_custom_short_format_tl }
                { \l__acro_short_format_tl }
            }
            {alt}
            {
              \bool_if:NTF \l__acro_custom_alt_format_bool
                { \l__acro_custom_alt_format_tl }
                { \l__acro_alt_format_tl }
            }
          }
      }
      { \use:n }
      {\exp_not:N\LWR@textcurrentfont{#2}}% lwarp
  }
}% v2.10 or later
{% before v2.10
\cs_gset_protected:Npn \acro_write_short:nn #1#2
  {
    \mode_if_horizontal:F { \leavevmode }
```

```
    \group_begin:
      \bool_if:NTF \l__acro_custom_format_bool
        { \l__acro_custom_format_tl }
        { \l__acro_short_format_tl }
      {\LWR@textcurrentfont{#2}}% lwarp
    \group_end:
  }

\cs_gset_protected:Npn \acro_write_alt:nn #1#2
  {
    \mode_if_horizontal:F { \leavevmode }
    \group_begin:
      \bool_if:NTF \l__acro_custom_format_bool
        { \l__acro_custom_format_tl }
        { \l__acro_alt_format_tl }
      {\LWR@textcurrentfont{#2}}% lwarp
    \group_end:
  }

\cs_gset_protected:Npn \acro_write_long:nn #1#2
  {
    \mode_if_horizontal:F { \leavevmode }
    \group_begin:
      \bool_if:NTF \l__acro_custom_long_format_bool
        { \l__acro_custom_long_format_tl }
        { \use:n }
      {
        \use:x
          {
            \exp_not:n {#1}
            {
              \bool_if:NTF \l__acro_first_upper_bool
                { \exp_not:N \__acro_first_upper_case:n { \exp_not:n {
                    \LWR@textcurrentfont{#2}% lwarp
                } } }
                { \exp_not:n {\LWR@textcurrentfont{#2}} }% lwarp
            }
          }
      }
    \group_end:
  }
}% before v2.10
}% before v3
\ExplSyntaxOff
```

File 13 **lwarp-acronym.sty**

§ 120 Package

# acronym

(*Emulates or patches code by* Tobias Oetiker.)

Pkg acronym acronym is patched for use by lwarp.

⚠ multiply-defined labels `\acresetall` does not work with cleveref, causing multiply-defined labels. lwarp patches

acronym for HTML, but not for print mode.

**for HTML output:**

```
\LWR@ProvidesPackagePass{acronym}[2015/03/21]
```

Uses \textit instead of \itshape:

```
\renewcommand{\acfia}[1]{%
  {\textit{\AC@acl{#1}}} (\ifAC@starred\acs*{#1}\else\acs{#1}\fi)}
```

Removes the mbox to allow math inside:

```
\renewcommand*\AC@acs[1]{%
%     \mbox{
 \expandafter\AC@get\csname fn@#1\endcsname\@firstoftwo{#1}}
% }
```

Fix for acronym labels in the captions of floats.

```
\renewcommand{\@starttoc}[1]{
\LWR@htmlelementclass{nav}{#1}
\LetLtxMacro\@verridelabel\@gobble
\LWR@orig@starttoc{#1}
\LWR@htmlelementclassend{nav}{#1}
}
```

Modified for cleveref and lwarp:

```
\renewcommand*\AC@und@newl@bel[3]{%
    \@ifundefined{#1@#3}%
    {%
        \global\expandafter\let\csname#2@#3\endcsname\@nnil
        \global\expandafter\let\csname#2@#3@lwarp\endcsname\@nnil% lwarp
        \global\expandafter\let\csname#2@#3@cref\endcsname\@nnil% lwarp
    }%
    {%
        \global\expandafter\let\csname#1@#3\endcsname\relax
        \global\expandafter\let\csname#1@#3@lwarp\endcsname\relax% lwarp
        \global\expandafter\let\csname#1@#3@cref\endcsname\relax% lwarp
    }%
}%
```

---

File 14 **lwarp-adjmulticol.sty**

## § 121 Package adjmulticol

(*Emulates or patches code by* Boris Veytsmanage

**for HTML output:**

```
\LWR@ProvidesPackageDrop{adjmulticol}[2012/01/20]
\RequirePackage{multicol}
```

adjmulticols * {⟨*numcols*⟩} {⟨*left margi*⟩} {⟨*right margin*⟩}

```
\NewDocumentEnvironment{adjmulticols}{s m m m}
{%
```

Compute the margins, and limit to positive only:

```
\setlength{\LWR@templengthone}{#3}%
\ifdimcomp{\LWR@templengthone}{<}{0pt}{\setlength{\LWR@templengthone}{0pt}}{}%
\setlength{\LWR@templengthtwo}{#4}
\ifdimcomp{\LWR@templengthtwo}{<}{0pt}{\setlength{\LWR@templengthtwo}{0pt}}{}%
```

If one column is specified, use a  of class singlecolumn, else use multicols:

```
\newcommand*{\LWR@mcolstype}{multicols}%
\ifnumcomp{#2}{=}{1}{\renewcommand*{\LWR@mcolstype}{singlecolumn}}{}%
```

Help avoid page overflow:

```
\LWR@forcenewpage%
```

Create the  with the given margin and class:

```
\BlockClass[%
    \LWR@print@mbox{margin-left:\LWR@printlength{\LWR@templengthone}} ; %
    \LWR@print@mbox{margin-right:\LWR@printlength{\LWR@templengthtwo}}%
]{\LWR@mcolstype}%
}
{\endBlockClass}
```

---

File 15 **lwarp-addlines.sty**

§ 122 Package

# addlines

(*Emulates or patches code by* Will Robertson.)

Pkg addlines addlines is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{addlines}[2018/12/05]
\newcommand\addlines{\@ifstar\addlines@a\addlines@a}
\newcommand\addlines@a[1][1]{}
\let\addline\addlines
\newcommand\removelines{\@ifstar\removelines@a\removelines@a}
\newcommand\removelines@a[1][1]{}
\let\removeline\removelines
\newcommand\squeezepage[1][0]{}
```

File 16 **lwarp-afterpage.sty**

## § 123 Package afterpage

(*Emulates or patches code by* David Carlisle.)

Pkg afterpage afterpage is emulated.

**for HTML output:** Discard all options for lwarp-afterpage:

```
\LWR@ProvidesPackageDrop{afterpage}[2014/10/28]
\newcommand{\afterpage}[1]{#1}
```

File 17 **lwarp-algorithm2e.sty**

## § 124 Package algorithm2e

(*Emulates or patches code by* Christophe Fiorio.)

Pkg algorithm2e algorithm2e is patched for use by lwarp.

For print output, captions are placed according to package options, but for HTML output captions are placed where used. Therefore, to have captions appear at the top of the algorithms for both print and HTML, place each captions at the top of each algorithm.

**for HTML output:**

```
\LWR@ProvidesPackagePass{algorithm2e}[2017/07/18]
```

For the list-of entries:

```
\renewcommand{\l@algocf}[2]{\hypertocfloat{1}{algocf}{loa}{#1}{#2}}
```

Select the lwarp float style according to the algorithm2e style:

```
\newcommand*{\LWR@floatstyle@algocf}{ruled}

\ifdefstring{\algocf@style}{boxed}{%
\renewcommand*{\LWR@floatstyle@algocf}{boxed}
}{}

\ifdefstring{\algocf@style}{boxruled}{%
\renewcommand*{\LWR@floatstyle@algocf}{boxruled}
}{}

\ifdefstring{\algocf@style}{plain}{%
\renewcommand*{\LWR@floatstyle@algocf}{plain}
}{}
```

Paragraph handling to allow line numbers under certain conditions:

```
\newbool{LWR@algocf@dopars}
\booltrue{LWR@algocf@dopars}

\renewcommand{\algocf@everypar}{%
\ifbool{LWR@algocf@dopars}{%
    \ifbool{LWR@doingstartpars}{%
        \ifnumcomp{\value{LWR@lateximagedepth}}{>}{0}%
            {}%
            {%
                \algocf@everyparnl\algocf@everyparhanging%
            }%
    }{}%
}{}%
}
```

lwarp caption handling:

```
\renewcommand{\algocf@makecaption}[2]{%
\LWR@HTML@caption@begin{algocf}%
\LWR@isolate{\algocf@captiontext{#1}{#2}}%
\LWR@HTML@caption@end%
}
```

Print any caption where it is declared:

```
\renewcommand{\algocf@makecaption@plain}[2]{%
    \LWR@HTML@caption@begin{algocf}%
    \LWR@isolate{\algocf@captiontext{#1}{#2}}%
    \LWR@HTML@caption@end%
}

\renewcommand{\algocf@makecaption@boxed}[2]{%
    \LWR@HTML@caption@begin{algocf}%
    \LWR@isolate{\algocf@captiontext{#1}{#2}}%
    \LWR@HTML@caption@end%
}

\renewcommand{\algocf@makecaption@ruled}[2]{%
    \LWR@HTML@caption@begin{algocf}%
    \LWR@isolate{\algocf@captiontext{#1}{#2}}%
    \LWR@HTML@caption@end%
}
```

Turn off line numbering while making the caption:

```
\long\def\algocf@latexcaption#1[#2]#3{% original definition of caption
\boolfalse{LWR@algocf@dopars}%  lwarp
  \par%
  \addcontentsline{\csname ext@#1\endcsname}{#1}%
 {\protect\numberline{\csname the#1\endcsname}{\ignorespaces \LWR@isolate{#2}}}%
  \begingroup%
  \@parboxrestore%
  \if@minipage%
```

```
        {\algocf@seteveryparnl{\relax}}%
    {%
            \KwSty{#2\algocf@typo:}%
        ~##1\par%
    }%
    \algocf@linesnumbered% reset the numbering of the lines
    \ifthenelse{\boolean{algocf@hanginginout}}%
        {\relax}%
        {\algocf@reseteveryparhanging}%
  }%
}%

\renewcommand{\ResetInOut}[1]{}%
```

Each of the following creates a  of a given class, and turns off line numbering while creating the  tags:

```
\renewcommand{\algocf@Vline}[1]{%
    \boolfalse{LWR@algocf@dopars}%
    \begin{BlockClass}{alg2evline}
    \booltrue{LWR@algocf@dopars}%
    #1
    \boolfalse{LWR@algocf@dopars}%
    \end{BlockClass}
    \booltrue{LWR@algocf@dopars}%
}

\renewcommand{\algocf@Vsline}[1]{%
    \boolfalse{LWR@algocf@dopars}%
    \begin{BlockClass}{alg2evsline}
    \booltrue{LWR@algocf@dopars}%
    #1
    \boolfalse{LWR@algocf@dopars}%
    \end{BlockClass}
    \booltrue{LWR@algocf@dopars}%
}

\renewcommand{\algocf@Noline}[1]{%
    \boolfalse{LWR@algocf@dopars}%
    \begin{BlockClass}{alg2enoline}
    \booltrue{LWR@algocf@dopars}%
    #1
    \boolfalse{LWR@algocf@dopars}%
    \end{BlockClass}
    \booltrue{LWR@algocf@dopars}%
}
```

The [H] environment is converted to a regular float, which in HTML is placed where declared. Reusing the regular float allows the [H] version to reuse the ruled and boxed options.

```
\LetLtxMacro\algocf@Here\algocf
\LetLtxMacro\endalgocf@Here\endalgocf
```

File 18 **lwarp-algorithmicx.sty**

## § 125 Package algorithmicx

(*Emulates or patches code by* Szász János.)

Pkg algorithmicx algorithmicx is supported with minor adjustments.

**for HTML output:**

```
\LWR@ProvidesPackagePass{algorithmicx}[2005/04/27]
```

Inside the algorithmic environment, level indenting is converted to a  of the required length, and comments are placed inside a  which is floated right.

⚠ package conflicts If using \newfloat, trivfloat, and/or algorithmicx together, see section 616.1.

```
\AtBeginEnvironment{algorithmic}{%
%
\let\origALG@doentity\ALG@doentity%
%
\renewcommand*{\ALG@doentity}{%
\origALG@doentity%
\LWR@htmltagc{%
    span style=\textquotedbl{}%
        width:\LWR@printlength{\ALG@thistlm}; display:inline-block;%
    \textquotedbl%
}%
\ifbool{FormatWP}{%
\setlength{\LWR@templengthone}{\the\ALG@thistlm}%
\whiledo{\lengthtest{\LWR@templengthone>1em}}{%
\quad%
\addtolength{\LWR@templengthone}{-1em}%
}%
}{}%
\LWR@htmltagc{/span}%
}%

\let\LWR@origComment\Comment%

\renewcommand{\Comment}[1]{%
    \InlineClass{floatright}{\LWR@origComment{#1}}%
}%
}

\renewcommand\algorithmiccomment[1]{%
\hfill\HTMLunicode{25B7} #1% white right triangle
}%
```

File 19 **lwarp-alltt.sty**

## § 126 Package alltt

(*Emulates or patches code by* Johannes Braams.)

Pkg alltt alltt is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{alltt}[1997/06/16]

\AfterEndPreamble{
\LWR@traceinfo{Patching alltt.}

\AtBeginEnvironment{alltt}{%
    \ifnumcomp{\value{LWR@lateximagedepth}}{>}{0}%
        {}%
        {%
            \LWR@forcenewpage
```

Vertical spacing changes if inside a list.

```
            \LWR@atbeginverbatim{alltt}%
        }%
}

\AfterEndEnvironment{alltt}{%
    \ifnumcomp{\value{LWR@lateximagedepth}}{>}{0}%
        {}%
        {%
```

Vertical spacing changes if inside a list.

```
            \LWR@afterendverbatim%
        }%
}

}
```

---

File 20 **lwarp-amscdx.sty**

## § 127 Package amscdx

(*Emulates or patches code by* Martin Vermeer.)

Pkg amscdx amscdx is used as-is for SVG math.

⚠ MathJax For MathJax, a warning notes that the CD environment must be enclosed between \displaymathother and \displaymathnormal.

**for HTML output:**

```
\LWR@ProvidesPackagePass{amscdx}[2019/07/02]

\begin{warpMathJax}
\CustomizeMathJax{%
    \renewenvironment{CD}
```

```
\newcounter{LWR@amsmathdepth}
\setcounter{LWR@amsmathdepth}{0}
```

The following $\mathcal{AMS}$ environments are patched in-place:

`\LWR@amsmathenv@@before` * {⟨*environment name*⟩}

* if the environment was starred.

Embeds the environment inside a `lateximage`.

```
\NewDocumentCommand{\LWR@amsmathenv@@before}{s m}{%
    \IfBooleanTF{#1}{
        \begin{BlockClass}{displaymath}
    }{
        \begin{BlockClass}{displaymathnumbered}
    }
    \LWR@newautoidanchor%
    \booltrue{LWR@indisplaymathimage}%
    \begin{lateximage}[\LWR@amsmathbodynumbered{#2}]*%
    \LWR@applyxfakebold%
}
```

`\LWR@amsmathenv@before` * {⟨*environment name*⟩}

* if the environment was starred.

Embeds the environment with MathJax or a `lateximage`.

```
\NewDocumentCommand{\LWR@amsmathenv@before}{s m}{%
    \ifnumequal{\value{LWR@amsmathdepth}}{0}{%
        \LWR@stoppars%
       \ifboolexpr{bool{mathjax} or ( bool{FormatWP} and bool{WPMarkMath} ) }%
        {
            \LWR@syncmathjax
            \boolfalse{LWR@amsmultline}
            \ifstrequal{#2}{multline}{\booltrue{LWR@amsmultline}}{}
            \ifstrequal{#2}{multline*}{\booltrue{LWR@amsmultline}}{}
```

⚠ autonum's "+" environments are not supported by MathJax.

```
            \LWR@beginhideamsmath
        }
        {
            \IfBooleanTF{#1}{
                \LWR@amsmathenv@@before*{#2}
            }{
                \LWR@amsmathenv@@before{#2}
            }
        }
    }{}
    \addtocounter{LWR@amsmathdepth}{1}
}
```

`\LWR@amsmathenv@@after`

Embeds the environment inside a `lateximage`.

```
\newcommand*{\LWR@amsmathenv@@after}{%
```

```
    \end{lateximage}\end{BlockClass}\LWR@startpars%
}
```

\LWR@amsmathenv@after * {⟨*environment name*⟩}

* if the environment was starred. Ignored here, only used for a consistent syntax.

Embeds the environment with MathJax or a `lateximage`.

```
\NewDocumentCommand{\LWR@amsmathenv@after}{s m}{%
    \ifnumequal{\value{LWR@amsmathdepth}}{1}{%
        \ifboolexpr{bool{mathjax} or ( bool{FormatWP} and bool{WPMarkMath} ) }%
        {
            \LWR@endhideamsmath
            \boolfalse{LWR@amsmultline}
            \LWR@addmathjax{#2}{\the\@envbody}
        }
        {\LWR@amsmathenv@@after}
```

Clear the single-use `alt` text:

```
        \gdef\LWR@ThisAltText{}%
    }{}
    \addtocounter{LWR@amsmathdepth}{-1}
}
```

Env multline

```
\BeforeBeginEnvironment{multline}{\LWR@amsmathenv@before{multline}}

\AfterEndEnvironment{multline}{\LWR@amsmathenv@after{multline}}
```

Env multline*

```
\BeforeBeginEnvironment{multline*}{\LWR@amsmathenv@before*{multline*}}

\AfterEndEnvironment{multline*}{\LWR@amsmathenv@after*{multline*}}

```

Env gather

```
\BeforeBeginEnvironment{gather}{\LWR@amsmathenv@before{gather}}

\AfterEndEnvironment{gather}{\LWR@amsmathenv@after{gather}}
```

Env gather*

```
\BeforeBeginEnvironment{gather*}{\LWR@amsmathenv@before*{gather*}}

\AfterEndEnvironment{gather*}{\LWR@amsmathenv@after*{gather*}}
```

Env align

```
\BeforeBeginEnvironment{align}{\LWR@amsmathenv@before{align}}
```

```
86
87 \AfterEndEnvironment{align}{\LWR@amsmathenv@after{align}}
```

Env align*

```
88 \BeforeBeginEnvironment{align*}{\LWR@amsmathenv@before*{align*}}
89
90 \AfterEndEnvironment{align*}{\LWR@amsmathenv@after*{align*}}
```

Env flalign

```
91 \BeforeBeginEnvironment{flalign}{\LWR@amsmathenv@before{flalign}}
92
93 \AfterEndEnvironment{flalign}{\LWR@amsmathenv@after{flalign}}
```

Env flalign*

```
94 \BeforeBeginEnvironment{flalign*}{\LWR@amsmathenv@before*{flalign*}}
95
96 \AfterEndEnvironment{flalign*}{\LWR@amsmathenv@after*{flalign*}}
```

Env alignat

```
97 \BeforeBeginEnvironment{alignat}{\LWR@amsmathenv@before{alignat}}
98
99 \AfterEndEnvironment{alignat}{\LWR@amsmathenv@after{alignat}}
```

Env alignat*

```
100 \BeforeBeginEnvironment{alignat*}{\LWR@amsmathenv@before*{alignat*}}
101
102 \AfterEndEnvironment{alignat*}{\LWR@amsmathenv@after*{alignat*}}


103 \AtBeginEnvironment{subequations}{
104     \renewcommand*{\theMathJaxsubequations}{1}
105     \renewcommand*{\theMathJaxsection}{\theparentequation}
106     \renewcommand*{\theMathJaxequation}{\arabic{equation}}
107 }
```

For MathJax:

```
108 \begin{warpMathJax}
109 \CustomizeMathJax{\newcommand{\intertext}[1]{\text{#1}\notag \\}}
110 \CustomizeMathJax{\let\Hat\hat}
111 \CustomizeMathJax{\let\Check\check}
112 \CustomizeMathJax{\let\Tilde\tilde}
113 \CustomizeMathJax{\let\Acute\acute}
114 \CustomizeMathJax{\let\Grave\grave}
115 \CustomizeMathJax{\let\Dot\dot}
116 \CustomizeMathJax{\let\Ddot\ddot}
117 \CustomizeMathJax{\let\Breve\breve}
```

```
\CustomizeMathJax{\let\Bar\bar}
\CustomizeMathJax{\let\Vec\vec}
\end{warpMathJax}
```

File 22 **lwarp-amsthm.sty**

§ 129 Package

# amsthm

(*Emulates or patches code by* Publications Technical Group — American Mathematical Society.)

The original source code is located in amsclass.dtx, and printed in amsclass.pdf.

Pkg amsthm amsthm is patched for use by lwarp.

Table 17: amsthm package — css styling of theorems and proofs

**Theorem:**  of class amsthmbody<theoremstyle>

**Theorem Name:**  of class amsthmname<theoremtyle>

**Theorem Number:**  of class amsthmnumber<theoremstyle>

**Theorem Note:**  of class amsthmnote<theoremstyle>

**Proof:**  of class amsthmproof

**Proof Name:**  of class amsthmproofname

where <theoremstyle> is plain, definition, etc.

**for HTML output:** amsthm must be loaded before mdframed:

```
\@ifpackageloaded{mdframed}{
    \PackageError{lwarp}
    {%
        Package mdframed must be loaded after package amsthm.\MessageBreak
        Enter 'H' for solutions%
    }
    {%
        Move ``\protect\usepackage{amsthm}'' before
        ``\protect\usepackage{mdframed}''.\MessageBreak
        Package amsthm may be loaded by something else,\MessageBreak
        which must also be moved before mdframed.%
    }
}
{\relax}
```

Necessary for \text, used by \openbox, etc., below:

```
\RequirePackage{amsmath}
```

```
\LWR@ProvidesPackagePass{amsthm}[2017/10/31]
```

Storage for the style being used for new theorems:

```
\newcommand{\LWR@newtheoremstyle}{plain}
```

Patched to remember the style being used for new theorems:

```
\renewcommand{\theoremstyle}[1]{%
  \@ifundefined{th@#1}{%
    \PackageWarning{amsthm}{Unknown theoremstyle `#1'}%
    \thm@style{plain}%
    \renewcommand{\LWR@newtheoremstyle}{plain}% lwarp
  }{%
    \thm@style{#1}%
    \renewcommand{\LWR@newtheoremstyle}{#1}% lwarp
  }%
}
```

Patched to remember the style for this theorem type:

```
\def\@xnthm#1#2{%
  \csedef{LWR@thmstyle#2}{\LWR@newtheoremstyle}% lwarp
  \let\@tempa\relax
  \@xp\@ifdefinable\csname #2\endcsname{%
    \global\@xp\let\csname end#2\endcsname\@endtheorem
    \ifx *#1% unnumbered, need to get one more mandatory arg
      \edef\@tempa##1{%
        \gdef\@xp\@nx\csname#2\endcsname{%
          \@nx\@thm{\@xp\@nx\csname th@\the\thm@style\endcsname}%
            {}{##1}}}%
    \else % numbered theorem, need to check for optional arg
      \def\@tempa{\@oparg{\@ynthm{#2}}[]}%
    \fi
    \AtBeginEnvironment{#2}{%
        \edef\LWR@thisthmstyle{\@nameuse{LWR@thmstyle#2}}%
    }%          lwarp
  }%
  \@tempa
}
```

Patched to enclose with css:

```
\newcommand{\LWR@haveamsthmname}{
    \renewcommand{\thmname}[1]{%
        \InlineClass{amsthmname\LWR@thisthmstyle}{##1}%
    }
}

\newcommand{\LWR@haveamsthmnumber}{
    \renewcommand{\thmnumber}[1]{%
        \InlineClass{amsthmnumber\LWR@thisthmstyle}{##1}%
    }
}

\newcommand{\LWR@haveamsthmnote}{
    \renewcommand{\thmnote}[1]{%
```

```
        \InlineClass{amsthmnote\LWR@thisthmstyle}{##1}%
    }
}

\LWR@haveamsthmname
\LWR@haveamsthmnumber
\LWR@haveamsthmnote
```

Patched for css:

```
\def\@begintheorem#1#2[#3]{%

    \GetTitleString{#3}%                                lwarp
    \let\@currentlabelname\GetTitleStringResult%        lwarp

    \item[
%   \deferred@thm@head{
%     \the\thm@headfont \thm@indent
    \@ifempty{#1}{\let\thmname\@gobble}{\LWR@haveamsthmname}%       lwarp
    \@ifempty{#2}{\let\thmnumber\@gobble}{\LWR@haveamsthmnumber}%   lwarp
    \@ifempty{#3}{\let\thmnote\@gobble}{\LWR@haveamsthmnote}%       lwarp
    \thm@swap\swappedhead\thmhead{#1}{#2}{#3}%
    \the\thm@headpunct~
    \thmheadnl % possibly a newline.
    \hskip\thm@headsep
%   }%
    ]
  \ignorespaces}
```

Patched for css:

```
\def\@thm#1#2#3{%
  \ifhmode\unskip\unskip\par\fi
  \normalfont
  \LWR@forcenewpage%                              lwarp
  \BlockClass{amsthmbody\LWR@thisthmstyle}%       lwarp
  \trivlist
  \let\thmheadnl\relax
  \let\thm@swap\@gobble
  \thm@notefont{\fontseries\mddefault\upshape}%
  \thm@headpunct{.}% add period after heading
  \thm@headsep 5\p@ plus\p@ minus\p@\relax
  \thm@space@setup
  #1% style overrides
  \@topsep \thm@preskip               % used by thm head
  \@topsepadd \thm@postskip           % used by \@endparenv
  \def\@tempa{#2}\ifx\@empty\@tempa
    \def\@tempa{\@oparg{\@begintheorem{#3}{}}[]}%
  \else
    \refstepcounter{#2}%
    \def\@tempa{\@oparg{\@begintheorem{#3}{\csname the#2\endcsname}}[]}%
  \fi
  \@tempa
}
```

cleveref patches \@thm to do \cref@thmoptarg if an optional argument is given. lwarp then patches \cref@thmoptarg \AtBeginDocument.

```
\AtBeginDocument{%
\def\cref@thmoptarg[#1]#2#3#4{%
    \ifhmode\unskip\unskip\par\fi%
    \normalfont%
    \LWR@forcenewpage%                          lwarp
    \BlockClass{amsthmbody\LWR@thisthmstyle}%   lwarp
    \trivlist%
    \let\thmheadnl\relax%
    \let\thm@swap\@gobble%
    \thm@notefont{\fontseries\mddefault\upshape}%
    \thm@headpunct{.}% add period after heading
    \thm@headsep 5\p@ plus\p@ minus\p@\relax%
    \thm@space@setup%
    #2% style overrides
    \@topsep \thm@preskip               % used by thm head
    \@topsepadd \thm@postskip           % used by \@endparenv
    \def\@tempa{#3}\ifx\@empty\@tempa%
        \def\@tempa{\@oparg{\@begintheorem{#4}{}}[]}%
    \else%
        \refstepcounter[#1]{#3}%  <<< cleveref modification
        \def\@tempa{\@oparg{\@begintheorem{#4}{\csname the#3\endcsname}}[]}%
    \fi%
    \@tempa
}%
}% AtBeginDocument

\def\@endtheorem{\endtrivlist\endBlockClass\@endpefalse }
```

Proof QED symbol:

```
\AtBeginDocument{
\@ifundefined{LWR@orig@openbox}{
\LetLtxMacro\LWR@orig@openbox\openbox
\LetLtxMacro\LWR@orig@blacksquare\blacksquare
\LetLtxMacro\LWR@orig@Box\Box

\def\openbox{\text{\HTMLunicode{25A1}}}% UTF-8 white box
\def\blacksquare{\text{\HTMLunicode{220E}}}% UTF-8 end-of-proof
\def\Box{\text{\HTMLunicode{25A1}}}% UTF-8 white box

\appto\LWR@restoreorigformatting{%
    \LetLtxMacro\openbox\LWR@orig@openbox%
    \LetLtxMacro\blacksquare\LWR@orig@blacksquare%
    \LetLtxMacro\Box\LWR@orig@Box%
}% appto
}{}% @ifundefined
}% AtBeginDocument
```

Patched for css:

```
\renewenvironment{proof}[1][\proofname]{\par
\LWR@forcenewpage% lwarp
```

File 25 **lwarp-appendix.sty**

## § 132 Package appendix

(*Emulates or patches code by* Peter Wilson.)

Pkg appendix appendix is patched for use by lwarp.

⚠ incorrect TOC link During HTML conversion, the option `toc` without the option `page` results in a TOC link to whichever section was before the `appendices` environment. It is recommended to use both `toc` and also `page` at the same time.

**for HTML output:**

```
\LWR@ProvidesPackagePass{appendix}[2009/09/02]

\renewcommand*{\@chap@pppage}{%
\part*{\appendixpagename}
 \if@dotoc@pp
 \addappheadtotoc
 \fi
}

\renewcommand*{\@sec@pppage}{%
\part*{\appendixpagename}
 \if@dotoc@pp
 \addappheadtotoc
 \fi
}
```

File 26 **lwarp-ar.sty**

## § 133 Package ar

(*Emulates or patches code by* Agostino De Marco.)

Pkg ar ar is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{ar}[2012/01/23]
```

Measure and print the width of the supplied glyph.

```
\newlength{\LWR@ar@width}

\newcommand*{\LWR@ar@printwidth}[1]{%
    \setlength{\LWR@ar@width}{\widthof{#1}}%
    width:%
    \LWR@convertto{em}{\the\LWR@ar@width}em%
}
```

The HTML version of \AR:

```
\newrobustcmd*{\LWR@HTML@AR}{%
```

Start a hashed lateximage, additionally hashed by the font series, with a width depending on the given glyph:

```
    \begin{lateximage}*[AR][\LWR@f@series][\LWR@ar@printwidth{\LWR@print@AR}]%
```

For text mode, set the font series according to the HTML font series:

```
    \ifmmode\else\csuse{LWR@orig\LWR@f@series series}\fi%
```

Print the original glyph using the newly set font series:

```
    \LWR@print@AR%
```

Done.

```
    \end{lateximage}%
}
```

Combine the print and HTML versions:

```
\LWR@formatted{AR}

\newrobustcmd*{\LWR@HTML@ARb}{%
    \begin{lateximage}*[AR][b][\LWR@ar@printwidth{\LWR@print@ARb}]%
    \LWR@print@ARb%
    \end{lateximage}%
}
\LWR@formatted{ARb}

\newrobustcmd*{\LWR@HTML@ARss}{%
   \begin{lateximage}*[ARss][\LWR@f@series][\LWR@ar@printwidth{\LWR@print@ARss}]%
    \ifmmode\else\csuse{LWR@orig\LWR@f@series series}\fi%
    \LWR@print@ARss%
    \end{lateximage}%
}
\LWR@formatted{ARss}

\newrobustcmd*{\LWR@HTML@ARssb}{%
    \begin{lateximage}*[AR][ssb][\LWR@ar@printwidth{\LWR@print@ARssb}]%
    \LWR@print@ARssb%
    \end{lateximage}%
}
\LWR@formatted{ARssb}

\newrobustcmd*{\LWR@HTML@ARtt}{%
    \begin{lateximage}*[AR][tt][\LWR@ar@printwidth{\LWR@print@ARtt}]%
    \LWR@print@ARtt%
    \end{lateximage}%
}
\LWR@formatted{ARtt}
```

For MathJax:

```
\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\AR}{\mathit{A\!\!R}}}
\CustomizeMathJax{\newcommand{\ARb}{\boldsymbol{A\!\!R}}}
\end{warpMathJax}
```

File 27 **lwarp-arabicfront.sty**

## § 134 Package arabicfront

Pkg arabicfront arabicfront is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{arabicfront}[2006/09/03]
```

File 28 **lwarp-array.sty**

## § 135 Package array

Pkg array array is used as-is for print output, and emulated for HTML.

plarray and plextarray do not affect `\firsthline` or `\lasthline`, and so are not affected by the following.

**for HTML output:** Remove the default nullfied macros:

```
\let\firsthline\relax
\let\lasthline\relax

\LWR@ProvidesPackagePass{array}[2018/12/30]

\newcommand*{\LWR@HTML@firsthline}{\LWR@HTMLhline}%
\LWR@expandableformatted{firsthline}

\newcommand*{\LWR@HTML@lasthline}{\LWR@HTMLhline}%
\LWR@expandableformatted{lasthline}

\providecommand*{\LWR@HTML@tabularnewline}{\LWR@tabularendofline}
\LWR@formatted{tabularnewline}
```

For MathJax:

```
\CustomizeMathJax{
    \newcommand{\multicolumn}[3]{#3}% only uses one cell
}
```

File 29 **lwarp-arydshln.sty**

# § 136 Package arydshln

(*Emulates or patches code by* Hiroshi Nakashima.)

Pkg arydshln

arydshln heavily patches tabular code, so the actual package is not used. arydshln is emulated for HTML `tabular`, and reverts to solid rules for SVG math `array` and `tabular` in a `lateximage`.

CSS is not able to display a double-dashed border, so a single-dashed rule is displayed as a single-dashed border, and a double-dashed rule is displayed as a thicker single-dashed border.

For MathJax, limited emulation is provided for math mode.

**for HTML output:**

array is required to allow `\newcolumn` below.

```
\RequirePackage{array}
```

```
\LWR@ProvidesPackageDrop{arydshln}[2018/09/26]
```

Ignored, but included for source compatibility:

```
\newdimen\dashlinedash \dashlinedash4pt %
\newdimen\dashlinegap \dashlinegap4pt %
\let\hdashlinewidth\dashlinedash
\let\hdashlinegap\dashlinegap

\def\ADLnullwide{}
\def\ADLsomewide{}
\def\ADLnullwidehline{}
\def\ADLsomewidehline{}

\def\ADLactivate{}
\def\ADLinactivate{}
\newcommand*{\ADLdrawingmode}[1]{}
\newcommand*{\ADLnoshorthanded}{}
\newcommand*{\dashgapcolor}[2][]{}
\newcommand*{\nodashgapcolor}{}
```

In a `lateximage`, revert to solid vertical rules:

```
\appto\LWR@restoreorigformatting{%
\newcolumntype{:}{|}%
\newcolumntype{;}[1]{|}%
\LetLtxMacro\hdashline\hline%
}
```

Some of these macros are already defined as temporary placeholders in the lwarp core, so they must be redefined here.

The emulated defaults also work for an emulated print mode inside a `lateximage`:

```
\def\hdashline{
%     \adl@hdashline\adl@ihdashline
    \adl@hdashline\adl@inactivehdl
```

```
}
\def\adl@hdashline#1{\noalign{\ifnum0=`}\fi
%         \ifadl@zwhrule \vskip-\arrayrulewidth
%         \else
%             \adl@hline\adl@connect\arrayrulewidth
                \hrule \@height \arrayrulewidth% lwarp
%         \fi
        \@ifnextchar[%
                    {#1}%
                    {#1[%
%                         \dashlinedash/\dashlinegap
                       1pt/1pt
                    ]}}
% \def\adl@ihdashline[#1/#2]{\ifnum0=`{\fi}%
%         \multispan{\adl@columns}\unskip \adl@hcline\z@[#1/#2]%
%         \noalign{\ifnum0=`}\fi
%         \futurelet\@tempa\adl@xhline}
\def\adl@inactivehdl[#1/#2]{
%         \ifadl@zwhrule \vskip-\arrayrulewidth \fi
        \hrule\@height\arrayrulewidth
        \futurelet\@tempa\adl@xhline}
\def\adl@xhline{\ifx\@tempa\hline \adl@ixhline\fi
        \ifx\@tempa\hdashline \adl@ixhline\fi
        \ifnum0=`{\fi}}
\def\adl@ixhline{\vskip\doublerulesep \adl@hline\relax\doublerulesep}
\def\adl@hline#1#2{%
% \@tempcnta#2
%         \global\advance\adl@totalheight\@tempcnta
%         \xdef\adl@rowsL{\adl@rowsL
%                 (#1/\number\@tempcnta);}%
%         \xdef\adl@rowsR{\adl@rowsR
%                 (#1/\number\@tempcnta);}
}

\def\cdashline#1{\noalign{\ifnum0=`}\fi
        \@ifnextchar[%
%                     {\adl@cdline[#1]}%
%                     {\adl@cdline[#1][\dashlinedash/\dashlinegap]}
                    {\adl@inactivecdl[#1]}%
                    {\adl@inactivecdl[#1][\dashlinedash/\dashlinegap]}
}

\def\adl@inactivecdl[#1-#2][#3]{\ifnum0=`{\fi}\cline{#1-#2}}


\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\firsthdashline}[1][]{\hdashline}}
\CustomizeMathJax{\let\lasthdashline\firsthdashline}
\CustomizeMathJax{\let\cdashline\cline}
\end{warpMathJax}
```

File 30 **lwarp-asymptote.sty**

```
\let\AtBeginShipout\relax
\let\AtBeginShipoutNext\relax
\let\AtBeginShipoutFirst\relax
\let\AtBeginShipoutDiscard\relax
\let\AtBeginShipoutInit\relax
\let\AtBeginShipoutAddToBox\relax
\let\AtBeginShipoutAddToBoxForeground\relax
\let\AtBeginShipoutUpperLeft\relax
\let\AtBeginShipoutUpperLeftForeground\relax
\let\AtBeginShipoutOriginalShipout\relax

\newcommand*{\AtBeginShipout}[1]{}
\newbox\AtBeginShipoutBox
\newcommand*{\AtBeginShipoutNext}[1]{}
\newcommand*{\AtBeginShipoutFirst}[1]{}
\newcommand*{\AtBeginShipoutDiscard}{}
\newcommand*{\AtBeginShipoutInit}{}
\newcommand*{\AtBeginShipoutAddToBox}[1]{}
\newcommand*{\AtBeginShipoutAddToBoxForeground}[1]{}
\newcommand*{\AtBeginShipoutUpperLeft}[1]{}
\newcommand*{\AtBeginShipoutUpperLeftForeground}[1]{}
\newcommand*{\AtBeginShipoutOriginalShipout}[1]{}
\def\AtBeginShipoutBoxWidth{0pt}
\def\AtBeginShipoutBoxHeight{0pt}
\def\AtBeginShipoutBoxDepth{0pt}
```

---

File 32 **lwarp-attachfile.sty**

§ 139 Package

# attachfile

(*Emulates or patches code by* Scott Pakin.)

Pkg attachfile attachfile is patched for use by lwarp.

⚠ Metadata is ignored for now.

**for HTML output:**

```
\LWR@ProvidesPackagePass{attachfile}[2016/09/18]
```

Encloses each icon:

```
\newenvironment*{LWR@attachfile@icon}
{
    \begin{lateximage}*%
        [-attachfile-]%
        [%
            \detokenize\expandafter{\atfi@icon@icon}-%
            \detokenize\expandafter{\atfi@color@rgb}%
        ]%
}
{
    \end{lateximage}
}
```

Each icon is enclosed inside a LWR@attachfile@icon environment:

```
\xpretocmd{\atfi@acroGraph}{\LWR@attachfile@icon}{}{}
\xapptocmd{\atfi@acroGraph}{\endLWR@attachfile@icon}{}{}

\xpretocmd{\atfi@acroPaperclip}{\LWR@attachfile@icon}{}{}
\xapptocmd{\atfi@acroPaperclip}{\endLWR@attachfile@icon}{}{}

\xpretocmd{\atfi@acroPushPin}{\LWR@attachfile@icon}{}{}
\xapptocmd{\atfi@acroPushPin}{\endLWR@attachfile@icon}{}{}

\xpretocmd{\atfi@acroTag}{\LWR@attachfile@icon}{}{}
\xapptocmd{\atfi@acroTag}{\endLWR@attachfile@icon}{}{}
```

Disable PDF file embedding:

```
\DeclareRobustCommand{\atfi@embedfile}[1]{}
```

The displayed output for an \attachfile reference:

```
\newcommand*{\LWR@attachfile@appearance}{}

\DeclareRobustCommand{\atfi@set@appearance}[1]{%
    \def\LWR@attachfile@appearance{#1}%
}
```

A file annotation becomes a reference:

```
\DeclareRobustCommand{\atfi@insert@file@annot}[1]{%
    \LWR@href{#1}{\LWR@attachfile@appearance}%
}
```

---

File 33 **lwarp-attachfile2.sty**

§ 140 Package

# attachfile2

(*Emulates or patches code by* Heiko Oberdiek.)

Pkg attachfile2 attachfile2 is patched for use by lwarp.

⚠ Metadata is ignored for now.

**for HTML output:**

```
\LWR@ProvidesPackagePass{attachfile2}[2016/05/16]
```

Adds memory of the selected color:

```
\def\LWR@attachfiletwo@color{}%

\define@key{AtFi}{color}{%
    \def\LWR@attachfiletwo@color{#1}%   lwarp
  \HyColor@AttachfileColor{#1}%
          \atfi@color@tex\atfi@color@inline\atfi@color@annot
          {attachfile2}{color}%
```

```
}
```

Encloses each icon:

```
\newenvironment*{LWR@attachfile@icon}
{
    \begin{lateximage}*%
        [-attachfile-]%
        [%
            \detokenize\expandafter{\atfi@icon@icon}-%
            \detokenize\expandafter{\LWR@attachfiletwo@color}%
        ]%
}
{
    \end{lateximage}
}
```

Each icon is enclosed inside a LWR@attachfile@icon environment:

```
\xpretocmd{\atfi@acroGraph}{\LWR@attachfile@icon}{}{}
\xapptocmd{\atfi@acroGraph}{\endLWR@attachfile@icon}{}{}

\xpretocmd{\atfi@acroPaperclip}{\LWR@attachfile@icon}{}{}
\xapptocmd{\atfi@acroPaperclip}{\endLWR@attachfile@icon}{}{}

\xpretocmd{\atfi@acroPushPin}{\LWR@attachfile@icon}{}{}
\xapptocmd{\atfi@acroPushPin}{\endLWR@attachfile@icon}{}{}

\xpretocmd{\atfi@acroTag}{\LWR@attachfile@icon}{}{}
\xapptocmd{\atfi@acroTag}{\endLWR@attachfile@icon}{}{}
```

Disable PDF file embedding:

```
\DeclareRobustCommand{\atfi@embedfile}[1]{}
```

The displayed output for an \attachfile reference:

```
\newcommand*{\LWR@attachfile@appearance}{}

\def\atfi@set@appearance@icon{%
    \atfi@set@appearance{\csname atfi@acro\atfi@icon@icon\endcsname}%
}

\DeclareRobustCommand{\atfi@set@appearance}[1]{%
    \def\LWR@attachfile@appearance{#1}%
}
```

A file annotation becomes a reference:

```
\DeclareRobustCommand{\atfi@insert@file@annot}[1]{%
    \LWR@href{#1}{\LWR@attachfile@appearance}%
}
```

Modified for text color:

```
\DeclareRobustCommand{\notextattachfile}[2][]{%
  \begingroup
    \atfi@setup{#1}%
    \ifatfi@print
      \leavevmode
      \begingroup
        \HyColor@UseColor\atfi@color@tex
        \LWR@textcurrentcolor{#2}%      lwarp
% \strut
      \endgroup
%     \else
%       \sbox\ltx@zero{#2\strut}%
%       \makebox[\wd0]{}%
    \fi
  \endgroup
}
```

Modified to draw the icon:

```
\DeclareRobustCommand{\noattachfile}[1][]{%
  \begingroup
    \atfi@setup{#1}%
    \atfi@set@appearance@icon
    \ifatfi@print
        \LWR@attachfile@appearance%     lwarp
%       \expandafter
%       \atfi@refxform\csname atfi@appobj@\atfi@icon@icon\endcsname
%     \else
%       \makebox[\atfi@appearancewidth]{}%
    \fi
  \endgroup
}
```

---

File 34 **lwarp-authblk.sty**

§ 141 Package

# authblk

(*Emulates or patches code by* Patrick W. Daly.)

Pkg authblk

authblk is patched for HTML.

package support

⚠ load order

lwarp supports the native LaTeX titling commands, and also supports the packages authblk and titling. If both are used, authblk should be loaded before titling.

\published and \subtitle

If using the titling package, additional titlepage fields for \published and \subtitle may be added by using \AddSubtitlePublished in the preamble. See section 68.8.

(*Emulates or patches code by* Patrick W. Daly.)

**for HTML output:**

Require that authblk be loaded before titling:

```
\@ifpackageloaded{titling}{
    \PackageError{lwarp-authblk}
        {Package authblk must be loaded before titling}
```

```
        {%
            Titling appends authblk's author macro,
            so authblk must be loaded first.%
        }
}
{\relax}
```

Load authblk:

```
\LWR@ProvidesPackagePass{authblk}[2001/02/27]
```

Patch to add a class for the affiliation:

```
\LetLtxMacro\LWRAB@affil\affil

\renewcommand{\affil}[2][]{%
\LWRAB@affil[#1]{\protect\InlineClass{affiliation}{#2}}
}
```

Create an HTML break for an \authorcr:

```
\renewcommand*{\authorcr}{\protect\LWR@newlinebr}
```

---

File 35 **lwarp-autobreak.sty**

# § 142 Package autobreak

(*Emulates or patches code by* Takahiro Ueda.)

Pkg autobreak autobreak is used as-is for SVG math, and nullified for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{autobreak}[2017/02/23]
```

For MathJax. The modified align environment is used for SVG math, but is reverted to its original for MathJax. (Extraneous commas were appearing in the result.)

```
\begin{warpMathJax}
\renewenvironment{autobreak}{\newcommand{\MoveEqLeft}[1]{}}{}
\let\start@align\@autobreak@oldstart@align
\let\endalign\@autobreak@oldendalign
\CustomizeMathJax{\newenvironment{autobreak}{}{}}
\CustomizeMathJax{\newcommand{\MoveEqLeft}[1][]{}}
\CustomizeMathJax{\newcommand{\everybeforeautobreak}[1]{}}
\CustomizeMathJax{\newcommand{\everyafterautobreak}[1]{}}
\end{warpMathJax}
```

---

File 36 **lwarp-autonum.sty**

# § 143 Package autonum

Pkg autonum autonum is ignored.

⚠ numbering All equations are numbered in HTML output.

MathJax does not support the "+" environments.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{autonum}[2015/01/18]

\RequirePackage{amsmath}


\newenvironment{equation+}{\equation}{\endequation}


\newenvironment{gather+}{\gather}{\endgather}

\BeforeBeginEnvironment{gather+}{\LWR@amsmathenv@@before{gather+}}

\AfterEndEnvironment{gather+}{\LWR@amsmathenv@@after}


\newenvironment{multline+}{\multline}{\endmultline}

\BeforeBeginEnvironment{multline+}{\LWR@amsmathenv@@before{multline+}}

\AfterEndEnvironment{multline+}{\LWR@amsmathenv@@after}


\newenvironment{flalign+}{\flalign}{\endflalign}

\BeforeBeginEnvironment{flalign+}{\LWR@amsmathenv@@before{flaline+}}

\AfterEndEnvironment{flalign+}{\LWR@amsmathenv@@after}


\newenvironment{align+}{\align}{\endalign}

\BeforeBeginEnvironment{align+}{\LWR@amsmathenv@@before{aline+}}

\AfterEndEnvironment{align+}{\LWR@amsmathenv@@after}


\newenvironment{alignat+}{\alignat}{\endalignat}

\BeforeBeginEnvironment{alignat+}{\LWR@amsmathenv@@before{alineat+}}

\AfterEndEnvironment{alignat+}{\LWR@amsmathenv@@after}


\newenvironment{split+}{\split}{\endsplit}
```

File 37 **lwarp-awesomebox.sty**

## § 144 Package awesomebox

(*Emulates or patches code by* Étienne Deparis.)

Pkg awesomebox **awesomebox** is patched for use by **lwarp**.

**for HTML output:**

```
\LWR@ProvidesPackagePass{awesomebox}[2019/07/27]

\newcommand*{\LWR@awesomebox@boxborders}{}%
\newcommand*{\LWR@awesomebox@contentsborders}{}%

\newcommand*{\LWR@awesomebox@ruleborders}{%
    border-top: 1px solid black ;
    border-bottom: 1px solid black%
}

% \awesomebox[1:vrulecolor][2:hrule][3:title]{4:vrulewidth}{5:icon}{6:iconcolor}{7:content}
\RenewDocumentCommand \awesomebox { O{abvrulecolor} O{} o m m m +m }{%
    \begin{awesomeblock}[#1][#2][#3]{#4}{#5}{#6}
    #7
    \end{awesomeblock}
}

% \begin{awesomeblock}[1:vrulecolor][2:hrule][3:title]{4:vrulewidth}{5:icon}{6:iconcolor}
% <contents>
% \end{awesomeblock}
\RenewDocumentEnvironment{awesomeblock}{ O{abvrulecolor} O{} o m m m }
{%
    \LWR@forceminwidth{#4}%
    \convertcolorspec{named}{#1}{HTML}\LWR@tempcolor%
    \renewcommand*{\LWR@awesomebox@boxborders}{}%
    \renewcommand*{\LWR@awesomebox@contentsborders}{}%
    \ifdefstrequal{\abShortLine}{#2}{%
      \renewcommand*{\LWR@awesomebox@contentsborders}{\LWR@awesomebox@ruleborders}%
    }{}%
    \ifdefstrequal{\abLongLine}{#2}{%
      \renewcommand*{\LWR@awesomebox@boxborders}{\LWR@awesomebox@ruleborders}%
    }{}%
    \begin{BlockClass}[\LWR@awesomebox@boxborders]{awesomebox}
    \begin{BlockClass}[%
        margin-left: 2\% ;
        vertical-align: top
    ]{minipage}
        \color{#6}\Huge #5
    \end{BlockClass}
    \begin{BlockClass}[%
        width:75\% ;
        vertical-align: top ;
        padding-left: 1em ;
        \LWR@awesomebox@contentsborders ;
        border-left: \LWR@printlength{\LWR@atleastonept} %
            solid \LWR@origpound\LWR@tempcolor%
    ]{minipage}
        \IfValueTF{#3}{#3\newline}{}
}
{%
    \end{BlockClass}
    \end{BlockClass}
}
```

File 38 **lwarp-axessibility.sty**

## § 145 Package axessibility

Pkg axessibility axessibility is ignored.

**for HTML output:**

```
\PackageInfo{lwarp}{Using the lwarp version of package ‘axessibility’.}%
\ProvidesPackage{lwarp-axessibility}% no date is declared by the original

\newif\iftagpdfopt

\DeclareOption{accsupp}{
  \tagpdfoptfalse
}

\DeclareOption{tagpdf}{
  \tagpdfopttrue
}

\ProcessOptions\relax

\iftagpdfopt
    \RequirePackage{tagpdf}
\else
    \RequirePackage{accsupp}
\fi

\long\def\wrap#1{}
\long\def\wrapml#1{}
\long\def\wrapmlstar#1{}
\long\def\wrapmlalt#1{}
```

For MathJax. These usually will not be needed.

```
\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\wrap}[1]{}}
\CustomizeMathJax{\newcommand{\wrapml}[1]{}}
\CustomizeMathJax{\newcommand{\wrapmlstar}[1]{}}
\CustomizeMathJax{\newcommand{\wrapmlalt}[1]{}}
\end{warpMathJax}
```

File 39 **lwarp-axodraw2.sty**

## § 146 Package axodraw2

(*Emulates or patches code by* John C. Collins, J.A.M. Vermaseren.)

Pkg axodraw2 axodraw2 is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{axodraw2}[2018/02/15]

\BeforeBeginEnvironment{axopicture}{%
    \begin{lateximage}[-axopicture-~\PackageDiagramAltText]%
}

\AfterEndEnvironment{axopicture}{\end{lateximage}}
```

---

File 40 **lwarp-backnaur.sty**

## § 147 Package backnaur

(*Emulates or patches code by* Adrian P. Robson.)

Pkg backnaur backnaur is patched for use by lwarp, and emulated for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{backnaur}[2019/06/18]

\renewenvironment{bnf}{\eqnarray}{\endeqnarray}
\renewenvironment{bnf*}{\csuse{eqnarray*}}{\csuse{endeqnarray*}}
```

For MathJax:

```
\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\bnfpn}[1]{\langle \text{\textrm{#1}} \rangle}}
\CustomizeMathJax{\newcommand{\bnfor}{\; \mid \;}}
\CustomizeMathJax{\newcommand{\bnfsp}{\;}}
\@ifpackagewith{backnaur}{perp}{
    \CustomizeMathJax{\newcommand{\bnfes}{\perp}}
}{
    \@ifpackagewith{backnaur}{epsilon}{
        \CustomizeMathJax{\newcommand{\bnfes}{\epsilon}}
    }{
        \CustomizeMathJax{\newcommand{\bnfes}{\lambda}}
    }
}
\@ifpackagewith{backnaur}{tsrm}{
    \CustomizeMathJax{\newcommand{\bnfts}[1]{\text{#1}}}
}{
    \CustomizeMathJax{\newcommand{\bnfts}[1]{\text{\texttt{#1}}}}
}
\CustomizeMathJax{\newcommand{\bnftd}[1]{\text{\textit{#1}}}}
\CustomizeMathJax{\newcommand{\bnfsk}{\dots}}
\@ifpackagewith{backnaur}{altpo}{
    \CustomizeMathJax{\newcommand{\bnfpo}{::=}}
}{
    \CustomizeMathJax{\newcommand{\bnfpo}{\models}}
}
\CustomizeMathJax{\newcommand{\bnfprod}{\ifstar{\LWRbnfprodnn}{\LWRbnfprodyn}}}
\CustomizeMathJax{\newcommand{\LWRbnfprodyn}[2]{\bnfpn{#1} & \bnfpo & #2}}
\CustomizeMathJax{\newcommand{\LWRbnfprodnn}[2]{\nonumber \bnfpn{#1} & \bnfpo & #2}}
\CustomizeMathJax{\newcommand{\bnfmore}{\ifstar{\LWRbnfmorenn}{\LWRbnfmoreyn}}}
```

```
\CustomizeMathJax{\newcommand{\LWRbnfmoreyn}[1]{ &  & #1}}
\CustomizeMathJax{\newcommand{\LWRbnfmorenn}[1]{\nonumber &  & #1}}
\end{warpMathJax}
```

File 41 **lwarp-backref.sty**

## § 148 Package backref

(*Emulates or patches code by* David Carlisle and Sebastian Rahtz.)

Pkg backref backref is patched for use by lwarp.

⚠ loading Note that backref must be explicitly loaded, and is not automatically loaded by hyperref when generating HTML output.

**for HTML output:**

```
\LWR@ProvidesPackagePass{backref}[2016/05/21]
```

Force the hyperref option:

```
\def\backref{}

\long\def\hyper@section@backref#1#2#3{%
    \ref{#3}%
}

\let\backrefxxx\hyper@section@backref
```

File 42 **lwarp-balance.sty**

## § 149 Package balance

(*Emulates or patches code by* Patrick W. Daly.)

Pkg balance balance is ignored.

**for HTML output:** Discard all options for lwarp-balance:

```
\LWR@ProvidesPackageDrop{balance}[1999/02/23]

\newcommand*{\balance}{}
\newcommand*{\nobalance}{}
```

File 43 **lwarp-bbding.sty**

## § 150 Package bbding

(*Emulates or patches code by* Karel Horak, Peter Møller Neergaard.)

Pkg bbding bbding is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{bbding}[1999/04/15]

\newcommand*{\LWR@bbdingsymbol}[2]{\HTMLunicode{#2}}

\newcommand{\LWR@HTML@ScissorRightBrokenBottom}{\LWR@bbdingsymbol{000}   {2701}}
\newcommand{\LWR@HTML@ScissorRight}{\LWR@bbdingsymbol{001}              {2702}}
\newcommand{\LWR@HTML@ScissorRightBrokenTop}{\LWR@bbdingsymbol{002}     {2703}}
\newcommand{\LWR@HTML@ScissorLeftBrokenBottom}{\LWR@bbdingsymbol{003}   {2701}}
\newcommand{\LWR@HTML@ScissorLeft}{\LWR@bbdingsymbol{004}               {2702}}
\newcommand{\LWR@HTML@ScissorLeftBrokenTop}{\LWR@bbdingsymbol{005}      {2703}}
\newcommand{\LWR@HTML@ScissorHollowRight}{\LWR@bbdingsymbol{006}        {2704}}
\newcommand{\LWR@HTML@ScissorHollowLeft}{\LWR@bbdingsymbol{007}         {2704}}
\newcommand{\LWR@HTML@Phone}{\LWR@bbdingsymbol{010}                     {260E}}
\newcommand{\LWR@HTML@PhoneHandset}{\LWR@bbdingsymbol{011}              {2706}}
\newcommand{\LWR@HTML@Tape}{\LWR@bbdingsymbol{012}                      {2707}}
\newcommand{\LWR@HTML@Plane}{\LWR@bbdingsymbol{013}                     {2708}}
\newcommand{\LWR@HTML@Envelope}{\LWR@bbdingsymbol{014}                  {2709}}
\newcommand{\LWR@HTML@HandCuffRight}{\LWR@bbdingsymbol{015}             {261B}}
\newcommand{\LWR@HTML@HandCuffLeft}{\LWR@bbdingsymbol{016}              {261A}}
\newcommand{\LWR@HTML@HandCuffRightUp}{\LWR@bbdingsymbol{017}           {261D}}
\newcommand{\LWR@HTML@HandCuffLeftUp}{\LWR@bbdingsymbol{020}            {261F}}
\newcommand{\LWR@HTML@HandRight}{\LWR@bbdingsymbol{021}                 {261E}}
\newcommand{\LWR@HTML@HandLeft}{\LWR@bbdingsymbol{022}                  {261C}}
\newcommand{\LWR@HTML@HandRightUp}{\LWR@bbdingsymbol{023}               {261D}}
\newcommand{\LWR@HTML@HandLeftUp}{\LWR@bbdingsymbol{024}                {261F}}
\newcommand{\LWR@HTML@Peace}{\LWR@bbdingsymbol{025}                     {270C}}
\newcommand{\LWR@HTML@HandPencilLeft}{\LWR@bbdingsymbol{026}            {270D}}
\newcommand{\LWR@HTML@PencilRight}{\LWR@bbdingsymbol{027}               {270F}}
\newcommand{\LWR@HTML@PencilLeft}{\LWR@bbdingsymbol{030}                {270F}}
\newcommand{\LWR@HTML@PencilRightUp}{\LWR@bbdingsymbol{031}             {2710}}
\newcommand{\LWR@HTML@PencilLeftUp}{\LWR@bbdingsymbol{032}              {2710}}
\newcommand{\LWR@HTML@PencilRightDown}{\LWR@bbdingsymbol{033}           {270E}}
\newcommand{\LWR@HTML@PencilLeftDown}{\LWR@bbdingsymbol{034}            {270E}}
\newcommand{\LWR@HTML@NibRight}{\LWR@bbdingsymbol{035}                  {2711}}
\newcommand{\LWR@HTML@NibLeft}{\LWR@bbdingsymbol{036}                   {2711}}
\newcommand{\LWR@HTML@NibSolidRight}{\LWR@bbdingsymbol{037}             {2712}}
\newcommand{\LWR@HTML@NibSolidLeft}{\LWR@bbdingsymbol{040}              {2712}}
\newcommand{\LWR@HTML@Checkmark}{\LWR@bbdingsymbol{041}                 {2713}}
\newcommand{\LWR@HTML@CheckmarkBold}{\LWR@bbdingsymbol{042}             {2714}}
\newcommand{\LWR@HTML@XSolid}{\LWR@bbdingsymbol{043}                    {2715}}
\newcommand{\LWR@HTML@XSolidBold}{\LWR@bbdingsymbol{044}                {2716}}
\newcommand{\LWR@HTML@XSolidBrush}{\LWR@bbdingsymbol{045}               {2717}}
\newcommand{\LWR@HTML@PlusOutline}{\LWR@bbdingsymbol{046}               {2719}}
\newcommand{\LWR@HTML@Plus}{\LWR@bbdingsymbol{047}                      {271A}}
\newcommand{\LWR@HTML@PlusCenterOpen}{\LWR@bbdingsymbol{050}            {271C}}
\newcommand{\LWR@HTML@PlusThinCenterOpen}{\LWR@bbdingsymbol{051}        {271B}}
\newcommand{\LWR@HTML@Cross}{\LWR@bbdingsymbol{052}                     {271D}}
\newcommand{\LWR@HTML@CrossOpenShadow}{\LWR@bbdingsymbol{053}           {271E}}
\newcommand{\LWR@HTML@CrossOutline}{\LWR@bbdingsymbol{054}              {271F}}
\newcommand{\LWR@HTML@CrossBoldOutline}{\LWR@bbdingsymbol{055}          {271F}}
\newcommand{\LWR@HTML@CrossMaltese}{\LWR@bbdingsymbol{056}              {2720}}
\newcommand{\LWR@HTML@DavidStarSolid}{\LWR@bbdingsymbol{057}            {2721}}
\newcommand{\LWR@HTML@DavidStar}{\LWR@bbdingsymbol{060}                 {2721}}
\newcommand{\LWR@HTML@FourAsterisk}{\LWR@bbdingsymbol{061}              {2722}}
\newcommand{\LWR@HTML@JackStar}{\LWR@bbdingsymbol{062}                  {2723}}
```

```
\newcommand{\LWR@HTML@JackStarBold}{\LWR@bbdingsymbol{063}              {2724}}
\newcommand{\LWR@HTML@CrossClowerTips}{\LWR@bbdingsymbol{064}           {2725}}
\newcommand{\LWR@HTML@FourStar}{\LWR@bbdingsymbol{065}                  {2726}}
\newcommand{\LWR@HTML@FourStarOpen}{\LWR@bbdingsymbol{066}              {2727}}
\newcommand{\LWR@HTML@FiveStarLines}{\LWR@bbdingsymbol{067}             {2729}}
\newcommand{\LWR@HTML@FiveStar}{\LWR@bbdingsymbol{070}                  {2605}}
\newcommand{\LWR@HTML@FiveStarOpen}{\LWR@bbdingsymbol{071}              {2729}}
\newcommand{\LWR@HTML@FiveStarOpenCircled}{\LWR@bbdingsymbol{072}       {272A}}
\newcommand{\LWR@HTML@FiveStarCenterOpen}{\LWR@bbdingsymbol{073}        {272B}}
\newcommand{\LWR@HTML@FiveStarOpenDotted}{\LWR@bbdingsymbol{074}        {272C}}
\newcommand{\LWR@HTML@FiveStarOutline}{\LWR@bbdingsymbol{075}           {272D}}
\newcommand{\LWR@HTML@FiveStarOutlineHeavy}{\LWR@bbdingsymbol{076}      {272E}}
\newcommand{\LWR@HTML@FiveStarConvex}{\LWR@bbdingsymbol{077}            {272F}}
\newcommand{\LWR@HTML@FiveStarShadow}{\LWR@bbdingsymbol{100}            {2730}}
\newcommand{\LWR@HTML@AsteriskBold}{\LWR@bbdingsymbol{101}              {2731}}
\newcommand{\LWR@HTML@AsteriskCenterOpen}{\LWR@bbdingsymbol{102}        {2732}}
\newcommand{\LWR@HTML@AsteriskThin}{\LWR@bbdingsymbol{103}              {273B}}
\newcommand{\LWR@HTML@AsteriskThinCenterOpen}{\LWR@bbdingsymbol{104}    {273C}}
\newcommand{\LWR@HTML@EightStarTaper}{\LWR@bbdingsymbol{105}            {2733}}
\newcommand{\LWR@HTML@EightStarConvex}{\LWR@bbdingsymbol{106}           {2735}}
\newcommand{\LWR@HTML@SixStar}{\LWR@bbdingsymbol{107}                   {2736}}
\newcommand{\LWR@HTML@EightStar}{\LWR@bbdingsymbol{110}                 {2737}}
\newcommand{\LWR@HTML@EightStarBold}{\LWR@bbdingsymbol{111}             {2738}}
\newcommand{\LWR@HTML@TwelweStar}{\LWR@bbdingsymbol{112}                {2739}}
\newcommand{\LWR@HTML@SixteenStarLight}{\LWR@bbdingsymbol{113}          {273A}}
\newcommand{\LWR@HTML@SixFlowerPetalRemoved}{\LWR@bbdingsymbol{114}     {273B}}
\newcommand{\LWR@HTML@SixFlowerOpenCenter}{\LWR@bbdingsymbol{115}       {273C}}
\newcommand{\LWR@HTML@Asterisk}{\LWR@bbdingsymbol{116}                  {273D}}
\newcommand{\LWR@HTML@SixFlowerAlternate}{\LWR@bbdingsymbol{117}        {273E}}
\newcommand{\LWR@HTML@FiveFlowerPetal}{\LWR@bbdingsymbol{120}           {273F}}
\newcommand{\LWR@HTML@SixFlowerPetalDotted}{\LWR@bbdingsymbol{121}      {2740}}
\newcommand{\LWR@HTML@FiveFlowerOpen}{\LWR@bbdingsymbol{122}            {2740}}
\newcommand{\LWR@HTML@EightFlowerPetal}{\LWR@bbdingsymbol{123}          {2741}}
\newcommand{\LWR@HTML@SunshineOpenCircled}{\LWR@bbdingsymbol{124}       {2742}}
\newcommand{\LWR@HTML@SixFlowerAltPetal}{\LWR@bbdingsymbol{125}         {2743}}
\newcommand{\LWR@HTML@FourClowerOpen}{\LWR@bbdingsymbol{126}            {273F}}
\newcommand{\LWR@HTML@FourClowerSolid}{\LWR@bbdingsymbol{127}           {273F}}
\newcommand{\LWR@HTML@AsteriskRoundedEnds}{\LWR@bbdingsymbol{130}       {2749}}
\newcommand{\LWR@HTML@EightFlowerPetalRemoved}{\LWR@bbdingsymbol{131}   {274A}}
\newcommand{\LWR@HTML@EightAsterisk}{\LWR@bbdingsymbol{132}             {274B}}
\newcommand{\LWR@HTML@SixFlowerRemovedOpenPetal}{\LWR@bbdingsymbol{133}  {2740}}
\newcommand{\LWR@HTML@SparkleBold}{\LWR@bbdingsymbol{134}               {2748}}
\newcommand{\LWR@HTML@Sparkle}{\LWR@bbdingsymbol{135}                   {2747}}
\newcommand{\LWR@HTML@SnowflakeChevron}{\LWR@bbdingsymbol{136}          {2744}}
\newcommand{\LWR@HTML@SnowflakeChevronBold}{\LWR@bbdingsymbol{137}      {2746}}
\newcommand{\LWR@HTML@Snowflake}{\LWR@bbdingsymbol{140}                 {2744}}
\newcommand{\LWR@HTML@CircleSolid}{\LWR@bbdingsymbol{141}               {25CF}}
\newcommand{\LWR@HTML@Ellipse}{\LWR@bbdingsymbol{142}                   {274D}}
\newcommand{\LWR@HTML@EllipseSolid}{\LWR@bbdingsymbol{143}              {25CF}}
\newcommand{\LWR@HTML@CircleShadow}{\LWR@bbdingsymbol{144}              {274D}}
\newcommand{\LWR@HTML@EllipseShadow}{\LWR@bbdingsymbol{145}             {274D}}
\newcommand{\LWR@HTML@Square}{\LWR@bbdingsymbol{146}                    {25A1}}
\newcommand{\LWR@HTML@SquareSolid}{\LWR@bbdingsymbol{147}               {25A0}}
\newcommand{\LWR@HTML@SquareShadowBottomRight}{\LWR@bbdingsymbol{150}   {2751}}
\newcommand{\LWR@HTML@SquareShadowTopRight}{\LWR@bbdingsymbol{151}      {2752}}
```

```
\newcommand{\LWR@HTML@SquareShadowTopLeft}{\LWR@bbdingsymbol{152}      {2752}}
\newcommand{\LWR@HTML@SquareCastShadowBottomRight}{\LWR@bbdingsymbol{153} {2751}}
\newcommand{\LWR@HTML@SquareCastShadowTopRight}{\LWR@bbdingsymbol{154}   {2752}}
\newcommand{\LWR@HTML@SquareCastShadowTopLeft}{\LWR@bbdingsymbol{155}   {2752}}
\newcommand{\LWR@HTML@TriangleUp}{\LWR@bbdingsymbol{156}                 {25B2}}
\newcommand{\LWR@HTML@TriangleDown}{\LWR@bbdingsymbol{157}               {25BC}}
\newcommand{\LWR@HTML@DiamondSolid}{\LWR@bbdingsymbol{160}               {25C6}}
\newcommand{\LWR@HTML@OrnamentDiamondSolid}{\LWR@bbdingsymbol{161}     {2756}}
\newcommand{\LWR@HTML@HalfCircleRight}{\LWR@bbdingsymbol{162}           {25D7}}
\newcommand{\LWR@HTML@HalfCircleLeft}{\LWR@bbdingsymbol{163}            {25D6}}
\newcommand{\LWR@HTML@RectangleThin}{\LWR@bbdingsymbol{164}             {2758}}
\newcommand{\LWR@HTML@Rectangle}{\LWR@bbdingsymbol{165}                 {2759}}
\newcommand{\LWR@HTML@RectangleBold}{\LWR@bbdingsymbol{166}             {275A}}
\newcommand{\LWR@HTML@ArrowBoldRightStrobe}{\LWR@bbdingsymbol{167}     {27A0}}
\newcommand{\LWR@HTML@ArrowBoldUpRight}{\LWR@bbdingsymbol{170}         {27A6}}
\newcommand{\LWR@HTML@ArrowBoldDownRight}{\LWR@bbdingsymbol{171}       {27A5}}
\newcommand{\LWR@HTML@ArrowBoldRightShort}{\LWR@bbdingsymbol{172}      {27A7}}
\newcommand{\LWR@HTML@ArrowBoldRightCircled}{\LWR@bbdingsymbol{173}    {27B2}}


\LWR@formatted{ScissorRightBrokenBottom}
\LWR@formatted{ScissorRight}
\LWR@formatted{ScissorRightBrokenTop}
\LWR@formatted{ScissorLeftBrokenBottom}
\LWR@formatted{ScissorLeft}
\LWR@formatted{ScissorLeftBrokenTop}
\LWR@formatted{ScissorHollowRight}
\LWR@formatted{ScissorHollowLeft}
\LWR@formatted{Phone}
\LWR@formatted{PhoneHandset}
\LWR@formatted{Tape}
\LWR@formatted{Plane}
\LWR@formatted{Envelope}
\LWR@formatted{HandCuffRight}
\LWR@formatted{HandCuffLeft}
\LWR@formatted{HandCuffRightUp}
\LWR@formatted{HandCuffLeftUp}
\LWR@formatted{HandRight}
\LWR@formatted{HandLeft}
\LWR@formatted{HandRightUp}
\LWR@formatted{HandLeftUp}
\LWR@formatted{Peace}
\LWR@formatted{HandPencilLeft}
\LWR@formatted{PencilRight}
\LWR@formatted{PencilLeft}
\LWR@formatted{PencilRightUp}
\LWR@formatted{PencilLeftUp}
\LWR@formatted{PencilRightDown}
\LWR@formatted{PencilLeftDown}
\LWR@formatted{NibRight}
\LWR@formatted{NibLeft}
\LWR@formatted{NibSolidRight}
\LWR@formatted{NibSolidLeft}
\LWR@formatted{Checkmark}
\LWR@formatted{CheckmarkBold}
```

```
\LWR@formatted{XSolid}
\LWR@formatted{XSolidBold}
\LWR@formatted{XSolidBrush}
\LWR@formatted{PlusOutline}
\LWR@formatted{Plus}
\LWR@formatted{PlusCenterOpen}
\LWR@formatted{PlusThinCenterOpen}
\LWR@formatted{Cross}
\LWR@formatted{CrossOpenShadow}
\LWR@formatted{CrossOutline}
\LWR@formatted{CrossBoldOutline}
\LWR@formatted{CrossMaltese}
\LWR@formatted{DavidStarSolid}
\LWR@formatted{DavidStar}
\LWR@formatted{FourAsterisk}
\LWR@formatted{JackStar}
\LWR@formatted{JackStarBold}
\LWR@formatted{CrossClowerTips}
\LWR@formatted{FourStar}
\LWR@formatted{FourStarOpen}
\LWR@formatted{FiveStarLines}
\LWR@formatted{FiveStar}
\LWR@formatted{FiveStarOpen}
\LWR@formatted{FiveStarOpenCircled}
\LWR@formatted{FiveStarCenterOpen}
\LWR@formatted{FiveStarOpenDotted}
\LWR@formatted{FiveStarOutline}
\LWR@formatted{FiveStarOutlineHeavy}
\LWR@formatted{FiveStarConvex}
\LWR@formatted{FiveStarShadow}
\LWR@formatted{AsteriskBold}
\LWR@formatted{AsteriskCenterOpen}
\LWR@formatted{AsteriskThin}
\LWR@formatted{AsteriskThinCenterOpen}
\LWR@formatted{EightStarTaper}
\LWR@formatted{EightStarConvex}
\LWR@formatted{SixStar}
\LWR@formatted{EightStar}
\LWR@formatted{EightStarBold}
\LWR@formatted{TwelweStar}
\LWR@formatted{SixteenStarLight}
\LWR@formatted{SixFlowerPetalRemoved}
\LWR@formatted{SixFlowerOpenCenter}
\LWR@formatted{Asterisk}
\LWR@formatted{SixFlowerAlternate}
\LWR@formatted{FiveFlowerPetal}
\LWR@formatted{SixFlowerPetalDotted}
\LWR@formatted{FiveFlowerOpen}
\LWR@formatted{EightFlowerPetal}
\LWR@formatted{SunshineOpenCircled}
\LWR@formatted{SixFlowerAltPetal}
\LWR@formatted{FourClowerOpen}
\LWR@formatted{FourClowerSolid}
\LWR@formatted{AsteriskRoundedEnds}
\LWR@formatted{EightFlowerPetalRemoved}
```

```
\LWR@formatted{EightAsterisk}
\LWR@formatted{SixFlowerRemovedOpenPetal}
\LWR@formatted{SparkleBold}
\LWR@formatted{Sparkle}
\LWR@formatted{SnowflakeChevron}
\LWR@formatted{SnowflakeChevronBold}
\LWR@formatted{Snowflake}
\LWR@formatted{CircleSolid}
\LWR@formatted{Ellipse}
\LWR@formatted{EllipseSolid}
\LWR@formatted{CircleShadow}
\LWR@formatted{EllipseShadow}
\LWR@formatted{Square}
\LWR@formatted{SquareSolid}
\LWR@formatted{SquareShadowBottomRight}
\LWR@formatted{SquareShadowTopRight}
\LWR@formatted{SquareShadowTopLeft}
\LWR@formatted{SquareCastShadowBottomRight}
\LWR@formatted{SquareCastShadowTopRight}
\LWR@formatted{SquareCastShadowTopLeft}
\LWR@formatted{TriangleUp}
\LWR@formatted{TriangleDown}
\LWR@formatted{DiamondSolid}
\LWR@formatted{OrnamentDiamondSolid}
\LWR@formatted{HalfCircleRight}
\LWR@formatted{HalfCircleLeft}
\LWR@formatted{RectangleThin}
\LWR@formatted{Rectangle}
\LWR@formatted{RectangleBold}
\LWR@formatted{ArrowBoldRightStrobe}
\LWR@formatted{ArrowBoldUpRight}
\LWR@formatted{ArrowBoldDownRight}
\LWR@formatted{ArrowBoldRightShort}
\LWR@formatted{ArrowBoldRightCircled}
```

---

File 44 **lwarp-biblatex.sty**

§ 151 Package

# biblatex

(*Emulates or patches code by* Philipp Lehman.)

Pkg biblatex When biblatex is used, modifications from newfloat may have to be undone.

**for HTML output:**

1. lwarp uses newfloat.
2. For classes with chapters which newfloat does not know about, such as CTEX-related classes, newfloat may modify `\addtocontents`.
3. biblatex, though, wants to patch `\addtocontents`, which causes an error if `\addtocontents` has been changed.
4. Therefore, `\addtocontents` is restored to its original here, since biblatex is about to be loaded.

5. This means that the newfloat's chapterlistsgaps option may no longer work.

```
\ifdef{\newfloat@addtocontents@ORI}{
    \let\addtocontents\newfloat@addtocontents@ORI
}{}
```

hyperref emulation is loaded \AtBeginDocument to avoid an options clash.

```
\AtBeginDocument{\RequirePackage{hyperref}}

\LWR@ProvidesPackagePass{biblatex}[2018/03/04]
```

The following create hyperlinks to the references. The original code to use hyperref is recreated here, because hyperref is emulated.

```
\AfterPreamble{

\let\blx@anchors\@empty
\protected\def\blx@anchor{%
    \xifinlist{\the\c@refsection @\abx@field@entrykey}{\blx@anchors}
        {}
        {\listxadd\blx@anchors{\the\c@refsection @\abx@field@entrykey}%
        \hypertarget{cite.\the\c@refsection @\abx@field@entrykey}{}}}

\protected\def\blx@imc@bibhyperref{%
    \@ifnextchar[%]
      {\blx@bibhyperref}
      {\blx@bibhyperref[\abx@field@entrykey]}}%

\long\def\blx@bibhyperref[#1]#2{%
%        \blx@sfsave
        \hyperlink{cite.\the\c@refsection @#1}{%
%             \blx@sfrest
         #2%
%        \blx@sfsave
        }%
% \blx@sfrest%
}%% \def\blx@nohyperref[#1]#2{#2}%

\protected\long\def\blx@imc@bibhyperlink#1#2{%
%        \blx@sfsave
        \hyperlink{cite.\the\c@refsection:#1}{%
%         \blx@sfrest
         #2%
%        \blx@sfsave
        }%
%         \blx@sfrest%
}%

\protected\long\def\blx@imc@bibhypertarget#1#2{%
%        \blx@sfsave%
        \hypertarget{cite.\the\c@refsection:#1}{%
%         \blx@sfrest
         #2%
%        \blx@sfsave%
```

```
        }%
%         \blx@sfrest%
}

\let\blx@imc@ifhyperref\@firstoftwo
```

The following patches are for back page references.

```
\DeclareListFormat{pageref}{%
  \ifnumless{\abx@pagerefstyle}{0}
    {\usebibmacro{list:plain}%
     \ifhyperref
       {%
%             \hyperlink{page.#1}{#1}%
            \ref{\BaseJobname-autopage-#1}%  lwarp
       }
       {#1}}
    {\ifnumequal{\value{listcount}}{1}
       {\usebibmacro{pageref:init}}
       {}%
     \usebibmacro{pageref:comp}{#1}%
     \ifnumequal{\value{listcount}}{\value{liststop}}
       {\usebibmacro{pageref:dump}}
       {}}}

\renewbibmacro*{pageref:comp}[1]{%
  \numdef\abx@range@prev{\abx@range@prev+1}%
  \ifinteger{#1}
    {\def\abx@range@num{#1}%
     \def\abx@range@this{1}%
     \ifnumequal{\abx@range@this}{\abx@range@last}
       {}
       {\def\abx@range@prev{-1}}}
    {\ifrmnum{#1}
       {\numdef\abx@range@num{\rmntonum{#1}}%
        \def\abx@range@this{2}%
        \ifnumequal{\abx@range@this}{\abx@range@last}
          {}
          {\def\abx@range@prev{-1}}}
       {\undef\abx@range@num
        \def\abx@range@this{0}%
        \def\abx@range@prev{-1}}}%
  \ifdef\abx@range@num
    {\ifnumequal{\abx@range@num}{\abx@range@prev}
       {\def\abx@range@hold{#1}%
        \numdef\abx@range@diff{\abx@range@diff+1}}
       {\usebibmacro{pageref:dump}%
        \ifnumgreater{\abx@range@last}{-1}
          {\printdelim{multilistdelim}}
          {}%
        \ifhyperref
%           {\hyperlink{page.#1}{#1}}
          {\ref{\BaseJobname-autopage-#1}}%  lwarp
          {#1}}%
     \edef\abx@range@prev{\abx@range@num}}
```

```
    {\usebibmacro{pageref:dump}%
     \ifnumgreater{\abx@range@last}{-1}
       {\printdelim{multilistdelim}}
       {}%
     \ifhyperref
%        {\hyperlink{page.#1}{#1}}
       {\ref{\BaseJobname-autopage-#1}}%  lwarp
       {#1}%
     \def\abx@range@prev{-1}}%
  \edef\abx@range@last{\abx@range@this}}

\renewbibmacro*{pageref:dump}{%
  \ifnumgreater{\abx@range@diff}{0}
    {\ifcase\abx@pagerefstyle\relax % two
       \bibrangedash
       \ifhyperref
%          {\hyperlink{page.\abx@range@hold}{\abx@range@hold}}
         {\ref{\BaseJobname-autopage-\abx@range@hold}}%  lwarp
         {\abx@range@hold}%
     \or % three
       \ifnumless{\abx@range@diff}{2}
         {\printdelim{multilistdelim}}
         {\bibrangedash}%
       \ifhyperref
%          {\hyperlink{page.\abx@range@hold}{\abx@range@hold}}
         {\ref{\BaseJobname-autopage-\abx@range@hold}}%  lwarp
         {\abx@range@hold}%
     \or % two+
       \ifnumless{\abx@range@diff}{2}
         {\sqspace
          \ifhyperref
%             {\hyperlink{page.\abx@range@hold}{\bibstring{sequens}}}
            {\ref{\BaseJobname-autopage-\abx@range@hold}}%  lwarp
            {\bibstring{sequens}}}
         {\bibrangedash
          \ifhyperref
%             {\hyperlink{page.\abx@range@hold}{\abx@range@hold}}
            {\ref{\BaseJobname-autopage-\abx@range@hold}}%  lwarp
            {\abx@range@hold}}%
     \or % three+
       \ifnumless{\abx@range@diff}{2}
         {\sqspace
          \ifhyperref
%             {\hyperlink{page.\abx@range@hold}{\bibstring{sequens}}}
            {\ref{\BaseJobname-autopage-\abx@range@hold}}%  lwarp
            {\bibstring{sequens}}}
         {\ifnumless{\abx@range@diff}{3}
            {\sqspace
             \ifhyperref
%                {\hyperlink{page.\abx@range@hold}{\bibstring{sequentes}}}
               {\ref{\BaseJobname-autopage-\abx@range@hold}}%  lwarp
               {\bibstring{sequentes}}}
            {\bibrangedash
             \ifhyperref
%                {\hyperlink{page.\abx@range@hold}{\abx@range@hold}}
```

```
              {\ref{\BaseJobname-autopage-\abx@range@hold}}%  lwarp
              {\abx@range@hold}}}%
    \else % all+
      \ifnumless{\abx@range@diff}{2}
        {\sqspace
         \ifhyperref
%            {\hyperlink{page.\abx@range@hold}{\bibstring{sequens}}}
            {\ref{\BaseJobname-autopage-\abx@range@hold}}%  lwarp
            {\bibstring{sequens}}}
        {\sqspace
         \ifhyperref
%            {\hyperlink{page.\abx@range@hold}{\bibstring{sequentes}}}
            {\ref{\BaseJobname-autopage-\abx@range@hold}}%  lwarp
            {\bibstring{sequentes}}}%
     \fi
     \def\abx@range@diff{0}}
    {}}

}% \AfterPreamble
```

File 45 **lwarp-bibunits.sty**

## § 152 Package bibunits

(*Emulates or patches code by* Thorsten Hansen.)

Pkg bibunits bibunits is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{bibunits}[2004/05/12]

\def\bu@bibdata{\BaseJobname}
```

File 46 **lwarp-bigdelim.sty**

## § 153 Package bigdelim

(*Emulates or patches code by* Piet van Oostrum, Øystein Bache, Jerry Leichter.)

Pkg bigdelim bigdelim is used as-is for print or `lateximage`, and patched for HTML.

The delimiters are displayed in HTML by printing the delimiter, the text, and a thick border across the side of the `\multirow` which indicates the actual height of the delimiter. The delimiter character is given a `<span>` class of `ldelim` or `rdelim`, and the default CSS sets this to `font-size:200%`

⚠ use \mrowcell `\ldelim` and `\rdelim` use `\multirow`, so `\mrowcell` must be used in the proper number of empty cells in the same column below `\ldelim` or `\rdelim`, but not in cells which are above or below the delimiter:

```
\CustomizeMathJax{\newcommand{\LWRrdelim}[1][]{\LWRbigdelim~\text{#1}}}
\CustomizeMathJax{\def\rdelim#1#2#3{\def\LWRbigdelim{#1}\LWRrdelim}}
\end{warpMathJax}
```

File 47 **lwarp-bigfoot.sty**

## § 154 Package bigfoot

Pkg bigfoot bigfoot is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{bigfoot}[2015/08/30]

\RequirePackage{manyfoot}
\RequirePackage{perpage}

\def\RestyleFootnote#1#2{}
\def\FootnoteSpecific#1{}
\def\DefineFootnoteStack#1{}
\def\PushFootnoteMark#1{}
\def\PopFootnoteMark#1{}
\def\hfootfraction{0.9}
\def\vtypefraction{0.7}
\def\FootnoteMinimum{1sp}
\def\FootnoteMainMinimum{0pt}
\newcount\bigfoottolerance
\bigfoottolerance=100
\providecommand\footnotecarryratio{2}
```

File 48 **lwarp-bigstrut.sty**

## § 155 Package bigstrut

(*Emulates or patches code by* Piet van Oostrum, Øystein Bache, Jerry Leichter.)

Pkg bigstrut bigstrut is used as-is for print or `lateximage`, and patched for HTML.

**for HTML output:**

```
\LWR@ProvidesPackagePass{bigstrut}[2018/08/03]

\LetLtxMacro\LWR@origbigstrut\bigstrut

\renewcommand\bigstrut[1][x]{}

\appto\LWR@restoreorigformatting{%
\LetLtxMacro\bigstrut\LWR@origbigstrut%
}


\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\bigstrut}[1][]{}}
\end{warpMathJax}
```

File 49 **lwarp-bitpattern.sty**

## § 156 Package bitpattern

(*Emulates or patches code by* Jean-Marc Bourguet.)

Pkg bitpattern bitpattern is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{bitpattern}[2015/12/11]

\xpatchcmd{\bitpattern}
    {\begingroup}
    {\begin{lateximage}[-bitpattern-~\PackageDiagramAltText]}
    {}
    {\LWR@patcherror{bitpattern}{bitpattern}}

\xpatchcmd{\bp@Done}
    {\endgroup}
    {\end{lateximage}}
    {}
    {\LWR@patcherror{bitpattern}{bp@Done}}
```

File 50 **lwarp-blowup.sty**

## § 157 Package blowup

Pkg blowup blowup is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{blowup}[2018/01/02]

\newcommand*\blowUp[1]{}
```

File 51 **lwarp-bm.sty**

## § 158 Package bm

(*Emulates or patches code by* David Carlisle, Frank Mittelbach.)

Pkg bm bm is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{bm}[2019/07/24]
```

\DeclareBoldMathCommand must only be used in the preamble, since it adds to the MathJax setup code.

```
\newcommand*{\bookmarksetup}[1]{}
\newcommand*{\bookmarksetupnext}[1]{}
\newcommand*{\bookmark}[2][]{}
\newcommand*{\bookmarkdefinestyle}[2]{}
\newcommand*{\bookmarkget}[1]{}
\newcommand{\BookmarkAtEnd}[1]{}
```

File 54 **lwarp-booktabs.sty**

§ 161 Package

# booktabs

(*Emulates or patches code by* Simon Fear.)

Pkg booktabs

booktabs is emulated during HTML output, and used as-is during print output and inside an HTML `lateximage`.

⚠ `\cmidrule`

For MathJax, emulation is provided in math mode, but `\cmidrule` trim must not be used.

**for HTML output:**

If booktabs has already been loaded before lwarp, such as by memoir, use it as-is. If not, the lwarp core will have placed some dummy macros which should be removed before loading the actual booktabs definitions.

```
\@ifpackageloaded{booktabs}{}{
    \LetLtxMacro\toprule\relax
    \LetLtxMacro\midrule\relax
    \LetLtxMacro\cmidrule\cline
    \LetLtxMacro\bottomrule\relax
    \LetLtxMacro\addlinespace\relax
    \LetLtxMacro\morecmidrules\relax
    \LetLtxMacro\specialrule\relax
}
```

Next, load the booktabs package:

```
\LWR@ProvidesPackagePass{booktabs}[2019/10/08]
```

Adjust to work even if xltabular is loaded:

```
% \def\LWR@HTML@@BLTrule{\@BTnormal}
%
% \LWR@formatted{@BLTrule}
\LetLtxMacro\@BLTrule\@BTnormal


\DeclareDocumentCommand{\LWR@HTML@toprule}{o d()}%
    {%
        \IfValueTF{#1}%
            {\LWR@docmidrule[#1](){1-\arabic{LWR@tabletotalLaTeXcols}}}%
            {%
                \ifbool{FormatWP}%
                {\LWR@docmidrule[#1](){1-\arabic{LWR@tabletotalLaTeXcols}}}%
                {\booltrue{LWR@doingtbrule}}%
            }%
    \LWR@getmynexttoken}
```

```
\LWR@expandableformatted{toprule}

\DeclareDocumentCommand{\LWR@HTML@midrule}{o d()}%
    {%
        \IfValueTF{#1}%
            {\LWR@docmidrule[#1](){1-\arabic{LWR@tabletotalLaTeXcols}}}%
            {%
                \ifbool{FormatWP}%
                {\LWR@docmidrule[#1](){1-\arabic{LWR@tabletotalLaTeXcols}}}%
                {\defaddtocounter{LWR@hlines}{1}}%
            }%
    \LWR@getmynexttoken}

\LWR@expandableformatted{midrule}

\DeclareDocumentCommand{\LWR@HTML@cmidrule}{O{\LWR@cmidrulewidth} d() m}{%
    \LWR@docmidrule[#1](#2){#3}%
    \LWR@getmynexttoken%
}%

\LWR@expandableformatted{cmidrule}

\DeclareDocumentCommand{\LWR@HTML@bottomrule}{o d()}{%
    \IfValueTF{#1}%
        {\LWR@docmidrule[#1](){1-\arabic{LWR@tabletotalLaTeXcols}}}%
        {%
            \ifbool{FormatWP}%
            {\LWR@docmidrule[#1](){1-\arabic{LWR@tabletotalLaTeXcols}}}%
            {\booltrue{LWR@doingtbrule}}%
        }%
    \LWR@getmynexttoken%
}%

\LWR@expandableformatted{bottomrule}

\DeclareDocumentCommand{\LWR@HTML@addlinespace}{o}{}%

\LWR@expandableformatted{addlinespace}

\DeclareDocumentCommand{\LWR@HTML@morecmidrules}{}{}%

\LWR@expandableformatted{morecmidrules}

\DeclareDocumentCommand{\LWR@HTML@specialrule}{m m m d()}%
  {\LWR@docmidrule[#1](){1-\arabic{LWR@tabletotalLaTeXcols}}\LWR@getmynexttoken}%

\LWR@expandableformatted{specialrule}
```

For MathJax:

```
\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\toprule}[1][]{\hline}}
\CustomizeMathJax{\let\midrule\toprule}
\CustomizeMathJax{\let\bottomrule\toprule}
```

```
\CustomizeMathJax{\def\LWRbooktabscmidruleparen(#1)#2{}}
\CustomizeMathJax{\newcommand{\LWRbooktabscmidrulenoparen}[1]{}}
\CustomizeMathJax{\newcommand{\cmidrule}[1][]{%
    \ifnextchar(\LWRbooktabscmidruleparen\LWRbooktabscmidrulenoparen%
}}
\CustomizeMathJax{\newcommand{\morecmidrules}{}}
\CustomizeMathJax{\newcommand{\specialrule}[3]{\hline}}
\CustomizeMathJax{\newcommand{\addlinespace}[1][]{}}
\end{warpMathJax}
```

File 55 **lwarp-bophook.sty**

# § 162 Package bophook

Pkg bophook bophook is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{bophook}[2001/03/29]

\newcommand*{\AtBeginPage}[1]{}
\newcommand*{\PageLayout}[1]{}
```

File 56 **lwarp-bounddvi.sty**

# § 163 Package bounddvi

Pkg bounddvi bounddvi is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{bounddvi}[2016/12/28]
```

File 57 **lwarp-boxedminipage.sty**

# § 164 Package boxedminipage

(*Emulates or patches code by* Scott Pakin.)

Pkg boxedminipage boxedminipage is emulated for HTML, and used as-is for `lateximages`.

**for HTML output:**

```
\LWR@ProvidesPackagePass{boxedminipage}[2020/04/19]

\newenvironment{LWR@HTML@boxedminipage}{%
    \LWR@stoppars%
    \begin{BlockClass}{framebox}%
    \minipage%
}
{%
    \endminipage%
    \end{BlockClass}%
```

```
    \LWR@startpars%
}
\LWR@formattedenv{boxedminipage}
```

File 58 **lwarp-boxedminipage2e.sty**

## § 165 Package boxedminipage2e

(*Emulates or patches code by* Scott Pakin.)

Pkg boxedminipage2e boxedminipage2e has been renamed boxedminipage by the author.

**for HTML output:** Automatically loads boxedminipage:

```
\LWR@ProvidesPackagePass{boxedminipage2e}
```

File 59 **lwarp-braket.sty**

## § 166 Package braket

(*Emulates or patches code by* Donald Arseneau.)

Pkg braket braket works as-is for HTML with SVG math. For MathJax, the MathJax extension is used.

**for HTML output:**

```
\LWR@ProvidesPackagePass{braket}% No date is provided by the file.

\begin{warpMathJax}
    \CustomizeMathJax{\require{braket}}
\end{warpMathJax}
```

File 60 **lwarp-breakurl.sty**

## § 167 Package breakurl

(*Emulates or patches code by* Vilar Camara Neto.)

Pkg breakurl breakurl is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{breakurl}[2013/04/10]

\LetLtxMacro\burl\LWR@url

\NewDocumentCommand{\LWR@burlaltb}{O{} +m m}{%
    \LWR@ensuredoingapar%
    \LWR@subhyperref{#2}%
    \LWR@subhyperreftext{#3}%
    \endgroup% restore catcodes
}
```

## § 170 Package bussproofs

(*Emulates or patches code by* Samuel R. Buss.)

Pkg bussproofs bussproofs is used as-is for HTML, and emulated by MathJax's extension.

⚠ \DisplayProof If not using MathJax, inline proofs with \DisplayMath must be placed inside a math expression.

If using MathJax, only the prooftree environment may be used, not \DisplayProof.

**for HTML output:**

```
\LWR@ProvidesPackagePass{bussproofs}% no date in file

\ifbool{mathjax}{
    \CustomizeMathJax{\require{bussproofs}}

    \NewEnviron{LWR@HTML@prooftree}%
        {\LWR@doequation{\BODY}{prooftree}}%
        [\LWR@doendequation{prooftree}]
    \LWR@formattedenv{prooftree}
}{% SVG HTML
    \BeforeBeginEnvironment{prooftree}{%
        \begin{lateximage}[-bussproofs-~\PackageDiagramAltText]%
    }
    \AfterEndEnvironment{prooftree}{\end{lateximage}}
}
```

---

File 64 **lwarp-bxpapersize.sty**

## § 171 Package bxpapersize

Pkg bxpapersize bxpapersize is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{bxpapersize}[2017/10/08]

\providecommand*\papersizesetup{\bxpapersizesetup}
\newcommand*\bxpapersizesetup[1]{}
```

---

File 65 **lwarp-bytefield.sty**

## § 172 Package bytefield

(*Emulates or patches code by* Scott Pakin.)

Pkg bytefield bytefield is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{bytefield}[2017/09/15]

\BeforeBeginEnvironment{bytefield}{%
    \begin{lateximage}[-bytefield-~\PackageDiagramAltText]%
```

```
}

\AfterEndEnvironment{bytefield}{\end{lateximage}}
```

File 66 **lwarp-cancel.sty**

§ 173 Package

# cancel

Pkg cancel

cancel is used as-is for SVG math, and emulated for HTML text output.

**for HTML output:**

```
\LWR@origRequirePackage{lwarp-xcolor}% for \convertcolorspec
\LWR@ProvidesPackagePass{cancel}[2013/04/12]
```

\cancelto is math-only, so is used as-is.

```
\LetLtxMacro\LWR@origcancel\cancel
\LetLtxMacro\LWR@origbcancel\bcancel
\LetLtxMacro\LWR@origxcancel\xcancel

\appto\LWR@restoreorigformatting{%
\LetLtxMacro\cancel\LWR@origcancel%
\LetLtxMacro\bcancel\LWR@origbcancel%
\LetLtxMacro\xcancel\LWR@origxcancel%
}
```

\LWR@cancelcolor {⟨*text*⟩} {⟨*color*⟩} {⟨*class*⟩} {⟨*colorstyle*⟩} {⟨*FormatWPstyle*⟩}

Add colors if not empty:

```
\newcommand{\LWR@cancelcolor}[5]{%
\ifcsempty{#2}%
{\InlineClass(#5){#3}{#1}}%
{\LWR@htmlspanclass[#5;#4:\LWR@origpound\LWR@tempcolor]{#3}{#1}}%
}
```

\cancel {⟨*text*⟩}

```
\DeclareRobustCommand{\cancel}[1]{%
\begingroup%
\CancelColor%
\LWR@findcurrenttextcolor%
\color{black}%
\LWR@cancelcolor{#1}{LWR@tempcolor}{sout}{text-decoration-color}%
    {text-decoration:line-through}%
\endgroup%
}

\LetLtxMacro\bcancel\cancel
\LetLtxMacro\xcancel\cancel
```

For MathJax:

```
    \minipagefullwidth%                 lwarp
    \parbox[t]{\linewidth}{%
      #1\relax
      \caption@setposition t%
%       #2%
            {\caption#4{#5}}%
%       \captionbox@hrule
%       \csname caption@hj@#7\endcsname
      #8%
    }%
  }{%
    \endgroup

%     \parbox[b]{#6}{%
    \minipagefullwidth%                 lwarp
    \parbox[b]{\linewidth}{%            lwarp
      #1\relax
      \caption@setposition b%
%       \csname caption@hj@#7\endcsname
      #8%
%       \captionbox@hrule
%       #3
            {\caption#4{#5}}%
    }%
  }%
}
```

\caption@makecaption

```
\long\def\caption@makecaption#1#2{%
%   \caption@make@above
  \caption@@make{#1}{#2}%
%   \caption@make@below
}

\AtBeginDocument{
    \let\@makecaption\caption@makecaption
}
```

Appended to look ahead to the next token for \centering, etc:

```
\AtBeginDocument{
\xapptocmd{\@xfloat}
    {\LWR@futurenonspacelet\LWR@mynexttoken\LWR@floatalignment}
    {}
    {\LWR@patcherror{caption}{@xfloat}}

\xapptocmd{\@xdblfloat}
    {\LWR@futurenonspacelet\LWR@mynexttoken\LWR@floatalignment}
    {}
    {\LWR@patcherror{caption}{@xdblfloat}}
}
```

Updates for late patches for scrextend:

```
\caption@AtBeginDocument{
\@ifpackageloaded{lwarp-scrextend}{
    \LetLtxMacro\captionbelow\caption
    \LetLtxMacro\captionabove\caption
    \LetLtxMacro\captionofbelow\captionof
    \LetLtxMacro\captionofabove\captionof
}{}
}
```

File 69 **lwarp-caption3.sty**

§ 176 Package

# caption3

(*Emulates or patches code by* Axel Sommerfeldt.)

Pkg caption3 caption3 is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{caption3}[2020/10/21]
```

\caption@@@make {⟨*caption label*⟩} {⟨*caption text*⟩}

```
\@ifpackagelater{caption3}{2020/08/23}{
\renewcommand\caption@@@make[2]{%
\LWR@traceinfo{caption@@@make}%
    \LWR@stoppars%                                  lwarp
%   \sbox\@tempboxa{#1}%
%   \ifdim\wd\@tempboxa=\z@
%     \caption@set{labelseparator}{none}%
%   \fi
  \caption@ifempty{#2}{%
    \caption@set{labelseparator}{none}%
    \caption@set{textformat}{simple}%
  }%
  \caption@labelseparator % defines \caption@iflabelfont,
%       \caption@labelsep and \caption@labelsep@name
%       (the latter is needed by \caption@fmt)
%
%   \@setpar{\@@par\caption@@par}\caption@@par
  \caption@applyfont
```

\caption@fmt with plain format is defined as {#1#2#3\par}:

```
%   \caption@fmt
    {\ifcaption@star\else
       \begingroup
         \captionlabelfont
         \LWR@isolate{#1}%                          lwarp
       \endgroup
     \fi}%
    {\ifcaption@star\else
```

```
      \begingroup
        \caption@iflabelfont\captionlabelfont
        \relax\caption@labelsep
      \endgroup
    \fi}%
  {{\captiontextfont
       \let\\\newline%                          lwarp
%
     \caption@textstart
%       \caption@ifstrut
%         {\vrule\@height\ht\strutbox\@width\z@}%
%         {}%
%       \nobreak\hskip\z@skip % enable hyphenation
     \LWR@isolate{\caption@textformat{#2}}%    lwarp
%       \caption@ifstrut
%         {\ifhmode\@finalstrut\strutbox\fi}%
%         {}%
     \caption@textend}}%
   \LWR@startpars%                             lwarp
\LWR@traceinfo{caption@@@make done}%
}
}% later than 2020/08/23
{% earlier than 2020/08/23
\renewcommand\caption@@@make[2]{%
\LWR@traceinfo{caption@@@make}%
   \LWR@stoppars%                              lwarp
%   \sbox\@tempboxa{#1}%
%   \ifdim\wd\@tempboxa=\z@
%     \let\caption@lsep\relax
%   \fi
  \caption@ifempty{#2}{%
    \let\caption@lsep\@empty
    \let\caption@tfmt\@firstofone
  }%
%   \@setpar{\@@par\caption@@par}\caption@@par
  \caption@applyfont
```

`\caption@fmt` with `plain` format is defined as `{#1#2#3\par}`:

```
%     \caption@fmt
    {\ifcaption@star\else
       \begingroup
        \captionlabelfont
         \LWR@isolate{#1}%                     lwarp
       \endgroup
     \fi}%
    {\ifcaption@star\else
       \begingroup
         \caption@iflf\captionlabelfont
         \relax
        \caption@lsep
       \endgroup
     \fi}%
```

```
    {{%
        \captiontextfont
        \let\\\newline%                          lwarp
%       \caption@ifstrut
%         {\vrule\@height\ht\strutbox\@width\z@}%
%         {}%
%       \nobreak\hskip\z@skip % enable hyphenation
        \LWR@isolate{\caption@tfmt{#2}}%         lwarp
%       \caption@ifstrut
%         {\ifhmode\@finalstrut\strutbox\fi}%
%         {}%
      }}%
    \LWR@startpars%                               lwarp
\LWR@traceinfo{caption@@@make done}%
}
}% earlier than 2020/08/23
```

\caption@@make@ {⟨⟩} {⟨⟩}

```
\renewcommand{\caption@@make@}[2]{%
  \caption@stepthecounter%
  \caption@beginhook%
      \caption@@@make{#1}{#2}%
  \caption@endhook%
}

\DeclareCaptionBox{none}{#2}
\DeclareCaptionBox{parbox}{%
    #2%
}

\DeclareCaptionBox{colorbox}{%
    #2%
}
```

---

File 70 **lwarp-cases.sty**

§ 177 Package

# cases

(*Emulates or patches code by* Donald Arseneau.)

Pkg cases cases is patched for use by lwarp.

While using MathJax, cases objects are converted to svg math images.

**for HTML output:**

```
\LWR@ProvidesPackagePass{cases}[2002/05/02]

\BeforeBeginEnvironment{numcases}{
    \begin{BlockClass}{displaymathnumbered}
    \LWR@newautoidanchor%
    \booltrue{LWR@indisplaymathimage}%
    \begin{lateximage}[-cases- \MathImageAltText]
```

```
}

\AfterEndEnvironment{numcases}{
    \end{lateximage}\end{BlockClass}
}

\BeforeBeginEnvironment{subnumcases}{
    \begin{BlockClass}{displaymathnumbered}
    \LWR@newautoidanchor%
    \booltrue{LWR@indisplaymathimage}%
    \begin{lateximage}[-cases- \MathImageAltText]
}

\AfterEndEnvironment{subnumcases}{
    \end{lateximage}\end{BlockClass}
}
```

File 71 **lwarp-centernot.sty**

## § 178 Package centernot

(*Emulates or patches code by* Heiko Oberdiek.)

Pkg centernot centernot is used as-is for SVG math, and emulated for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{centernot}[2016/05/16]
```

Based on https://github.com/mathjax/MathJax/issues/2107 with \textstyle removed to work with sub/super scripts.

```
\LWR@origRequirePackage{lwarp-common-mathjax-overlaysymbols}

\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\centernot}[1]{%
    \LWRoverlaysymbols{\unicode{x2215}}{#1}
}}
\end{warpMathJax}
```

File 72 **lwarp-changebar.sty**

## § 179 Package changebar

Pkg changebar changebar is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{changebar}[2018/03/09]

\newcommand*{\cbstart}{}
\newcommand*{\cbend}{}
\newenvironment*{\changebar}{}{}
\newcommand*{\cbdelete}{}
```

**for HTML output:** Discard all options for lwarp-changepage:

```
\LWR@ProvidesPackageDrop{changepage}[2009/10/20]

\newif\ifoddpage
\DeclareRobustCommand{\checkoddpage}{\oddpagetrue}
\DeclareRobustCommand{\changetext}[5]{}
\DeclareRobustCommand{\changepage}[9]{}

\@ifundefined{adjustwidth}{
\newenvironment{adjustwidth}[2]{}{}
\newenvironment{adjustwidth*}[2]{}{}
}{
\renewenvironment{adjustwidth}[2]{}{}
\renewenvironment{adjustwidth*}[2]{}{}
}

\DeclareDocumentCommand{\strictpagecheck}{}{}
\DeclareDocumentCommand{\easypagecheck}{}{}
```

---

File 75 **lwarp-changes.sty**

§ 182 Package

# changes

(*Emulates or patches code by* Ekkart Kleinod.)

Pkg changes changes is patched for use by lwarp.

⚠ \comment Use commandnameprefix=ifneeded to avoid a conflict with the \comment command when using lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{changes}[2021/02/14]
```

\BaseJobname is added to the label in case xr or xr-hyper are used.

```
\renewcommand{\ChangesListline}[4]{%
    \IfIsInList{#1}{\Changes@loc@show}{%
        \LWR@startpars%
        #2: #3 \qquad
        \nameref{\BaseJobname-autopage-#4}%
        \LWR@stoppars%
    }{}%
}

\renewcommand{\listofchanges}[1][\@empty]{%
\setkeys{Changes@loc}{#1}%
\ifbool{Changes@optiondraft}%
{%
\IfIsInList{\Changes@loc@style}{list|summary|compactsummary}%
{}%
{%
\PackageWarning{changes}{Wrong style for list of changes: '\Changes@loc@style', using 'list' instead.}%
```

```
\def\Changes@loc@style{}%
}%
\IfIsEmpty{\Changes@loc@style}%
{\def\Changes@loc@style{list}}%
{}%
\IfStrEq{\Changes@loc@show}{all}%
{\def\Changes@loc@show{added|deleted|replaced|highlight|comment}}%
{}%
\IfIsInList{\Changes@loc@show}{added|deleted|replaced|highlight|comment}%
{}%
{%
\PackageWarning{changes}{Wrong show-value for list of changes: '\Changes@loc@show', using 'all' instead.}
\def\Changes@loc@show{}%
}%
\IfIsEmpty{\Changes@loc@show}%
{\def\Changes@loc@show{added|deleted|replaced|highlight|comment}}%
{}%
\IfIsEmpty{\Changes@loc@title}%
{%
\IfStrEq{\Changes@loc@style}{list}%
{\def\Changes@heading{\listofchangesname}}{}%
\IfStrEq{\Changes@loc@style}{summary}%
{\def\Changes@heading{\summaryofchangesname}}{}%
\IfStrEq{\Changes@loc@style}{compactsummary}%
{\def\Changes@heading{\compactsummaryofchangesname}}{}%
}%
{\def\Changes@heading{\Changes@loc@title}}%
\section*{\Changes@heading}
\IfIsInList{\Changes@loc@style}{list}%
{%
\IfFileExists{\jobname.\Changes@locextension}%
{%
\newread\Changes@InFile%
\openin\Changes@InFile=\jobname.\Changes@locextension%
\loop\unless\ifeof\Changes@InFile%
\read\Changes@InFile to \Changes@Line%
\ifeof\Changes@InFile\else%
\Changes@Line%
\fi
\repeat
\closein\Changes@InFile%
}{%
\emph{\changesnoloc}%
\PackageWarning{changes}{LaTeX rerun needed for list of changes}%
}%
}{}%
\IfIsInList{\Changes@loc@style}{summary|compactsummary}%
{%
\IfFileExists{\jobname.\Changes@socextension}%
{%
\newread\Changes@InFile%
\openin\Changes@InFile = \jobname.\Changes@socextension%
\loop\unless\ifeof\Changes@InFile%
\read\Changes@InFile to \Changes@Line%
\ifeof\Changes@InFile\else%
```

```
\expandafter\changes@chopline\Changes@Line\\%
\textbf{%
\IfIsColored%
{\color{\Changes@Incolor}}%
{}%
\IfIsAnonymous{\Changes@Inid}%
{%
    \LWR@textcurrentcolor{%     lwarp
        \changesauthorname: \changesanonymousname%
    }%  lwarp
}%
{%
    \LWR@textcurrentcolor{%     lwarp
\changesauthorname: \Changes@Inid%
    }%  lwarp
\IfIsEmpty{\Changes@Inname}%
{}%
{ %
    \LWR@textcurrentcolor{%     lwarp
(\Changes@Inname)%
    }%  lwarp
}%
}%
}\\%
\numdef{\Changes@InSum}{0}%
\renewcommand*{\do}[1]{%
\numdef{\Changes@InSum}{\Changes@InSum + \csuse{Changes@In########1}}%
}%
\expandafter\dopsvlist\expandafter{\Changes@loc@show}%
\ifnumcomp{\Changes@InSum}{=}{0}%
{%
% \parbox{\Changes@summary@width}{% lwarp
    \changesnochanges%
% }%    lwarp
% \\[1ex]%    lwarp
    \par%   \lwarp
}%
{%
\numdef{\Changes@InCount}{0}%
\renewcommand*{\do}[1]{%
\numdef{\Changes@InCount}{\Changes@InCount + \csuse{Changes@In########1}}%
\ifboolexpr{%
not test {\IfStrEq{\Changes@loc@style}{compactsummary}} or%
test {\ifnumgreater{\csuse{Changes@In########1}}{0}}%
}%
{%
% \parbox{\Changes@summary@width}{%  lwarp
\csuse{changes########1name}~%
% \let\cleaders\leaders\dotfill~%   lwarp
\dotfill~%   \lwarp
\csuse{Changes@In########1}%
% }%    lwarp
% \ifnumless{\Changes@InCount}{\Changes@InSum}%     lwarp
{\\}%
% {\\[1ex]}%    lwarp
```

```
}%
{}%
}%
\expandafter\dopsvlist\expandafter{\Changes@loc@show}%
    \par%   lwarp
}%
\fi%
\repeat
\closein\Changes@InFile%
}{%
\emph{\changesnosoc}%
\PackageWarning{changes}{LaTeX rerun needed for summary of changes}%
}%
}{}%
}{}%
}


\renewcommand{\Changes@Markup@comment}[3]{%
\IfStrEq{\Changes@optioncommentmarkup}{todo}%
{%
\IfIsColored%
{\colorlet{Changes@todocolor}{authorcolor}}%
{\colorlet{Changes@todocolor}{black}}%
\todo[color=Changes@todocolor!10, bordercolor=Changes@todocolor, linecolor=Changes@todocolor!70, nolist
}{}%
\IfStrEq{\Changes@optioncommentmarkup}{margin}%
{%
\marginpar{%
\IfIsColored%
{\leavevmode\color{authorcolor}}%
{}%
    \LWR@textcurrentcolor{%     lwarp
\textbf{[\IfIsAnonymous{#2}{}{#3~}\arabic{Changes@commentCount#2}]:} #1%
    }%  lwarp
}%
}{}%
\IfStrEq{\Changes@optioncommentmarkup}{footnote}%
{%
\footnote{%
    \LWR@textcurrentcolor{%     lwarp
\textbf{[\IfIsAnonymous{#2}{}{#3~}\arabic{Changes@commentCount#2}]:} #1%
    }%  lwarp
}%
}{}%
\IfStrEq{\Changes@optioncommentmarkup}{uwave}%
{%
{%
\IfIsColored%
{\color{authorcolor}}%
{}%
\allowbreak%
\uwave{%
\textbf{[\IfIsAnonymous{#2}{}{#3~}\arabic{Changes@commentCount#2}]:} #1%
}%
```

```
}%
}{}%
}

\renewrobustcmd{\Changes@output}[7]{%
\ifbool{Changes@optiondraft}%
{%
\Changes@check@author{#2}%
\Changes@set@color{#2}%
{%
\IfIsInList{#1}{added|deleted|replaced|highlight}%
{%
\IfIsEmpty{#5}%
{%
\IfIsAuthorEmptyAtPosition{#2}{left}%
{}%
{{%
\IfIsColored%
{\color{authorcolor}}%
{}%
    \LWR@textcurrentcolor{%     lwarp
\Changes@Markup@author{\Changes@output@author{#2}{left}}%
    }%  lwarp
}}%
}{}%
{%
\IfStrEq{#1}{highlight}%
{}{%
\IfIsColored%
{\color{authorcolor}}%
{}%
}%
    \LWR@textcurrentcolor{%     lwarp
\IfStrEq{#1}{added}{\Changes@Markup@added{#3}}{}%
\IfStrEq{#1}{deleted}{\Changes@Markup@deleted{#4}}{}%
\IfStrEq{#1}{replaced}{{\Changes@Markup@added{#3}}\allowbreak\Changes@Markup@deleted{#4}}{}%
\IfStrEq{#1}{highlight}{\Changes@Markup@highlight{#3}}{}%
    }%  lwarp
}%
\IfIsEmpty{#5}%
{%
\IfIsAuthorEmptyAtPosition{#2}{right}%
{}%
{{%
\IfIsColored%
{\color{authorcolor}}%
{}%
    \LWR@textcurrentcolor{%     lwarp
\Changes@Markup@author{\Changes@output@author{#2}{right}}%
    }%  lwarp
}}%
}{}%
\stepcounter{Changes@#1Count#2}%
}{}%
\IfIsEmpty{#5}%
```

```
{}%
{%
\stepcounter{Changes@commentCount#2}%
\Changes@set@commentcount{#2}%
\Changes@Markup@comment%
{#5}%
{#2}%
{\Changes@output@author{#2}{left}\Changes@output@author{#2}{right}}%
}%
}%
\IfIsEmpty{#2}%
{\def\Changes@locid{}}%
{\def\Changes@locid{~(#2)}}%
\addtocontents{\Changes@locextension}{\protect\ChangesListline{#1}{#6\Changes@locid}{#7}{\thepage}}%
}%
{%
\IfIsEmpty{#3}%
{\@bsphack\@esphack}%
{#3}%
}%
}
```

File 76 **lwarp-chappg.sty**

## § 183 Package chappg

(*Emulates or patches code by* Robin Fairbairns.)

Pkg chappg chappg is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{chappg}[2006/05/09]

\renewcommand{\pagenumbering}[2][]{}
\providecommand{\chappgsep}{--}
```

File 77 **lwarp-chapterbib.sty**

## § 184 Package chapterbib

(*Emulates or patches code by* Donald Arseneau.)

Pkg chapterbib chapterbib is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{chapterbib}[2010/09/18]

\xdef\@savedjobname{\BaseJobname}
\let\@currentipfile\@savedjobname
```

File 78 **lwarp-chemfig.sty**

# § 185 Package chemfig

(*Emulates or patches code by* Christian Tellechea.)

Pkg chemfig chemfig is patched for use by lwarp.

If using \polymerdelim to add delimiters to a \chemfig, wrap both inside a single lateximage:

```
\begin{lateximage}[-chemfig-~\PackageDiagramAltText]
\chemfig{. . . }
\polymerdelim[. . . ]{. . . }
\end{lateximage}
```

The images are not hashed because they depend on external settings which may be changed at any time, and are unlikely to be reused inline anyhow.

**for HTML output:**

```
\LWR@ProvidesPackagePass{chemfig}[2020/03/05]

\catcode`\_=11

\@ifpackagelater{chemfig}{2020/03/05}
{
    \xpretocmd\charge{\begin{lateximage}[-chemfig-~\PackageDiagramAltText]}
        {}{\LWR@patcherror{chemfig}{charge}}
    \xpretocmd\Charge{\begin{lateximage}[-chemfig-~\PackageDiagramAltText]}
        {}{\LWR@patcherror{chemfig}{Charge}}
    \xapptocmd\charge_c{\end{lateximage}}
        {}{\LWR@patcherror{chemfig}{charge_c}}
}{}

\@ifpackagelater{chemfig}{2019/04/18}%
{% 2019/04/18 or newer


    \LetLtxMacro\LWR@chemfig@origchemfig\chemfig

    \renewcommand*{\chemfig}[2][]{%
        \begin{lateximage}[-chemfig-~\PackageDiagramAltText]%
        \LWR@chemfig@origchemfig[#1]{#2}%
        \end{lateximage}%
    }

    \GlobalLetLtxMacro\LWR@chemfig@origCF_lewisc\CF_lewisc
    \gdef\CF_lewisc#1,#2\_nil{%
    \begin{lateximage}[-chemfig-~\PackageDiagramAltText]%
    \LWR@chemfig@origCF_lewisc#1,#2\_nil
    \end{lateximage}
    }

    \gpreto{\schemestart}{%
        \begin{lateximage}[-chemfig-~\PackageDiagramAltText]%
    }
    \gappto{\CF_schemestop}{\end{lateximage}}

```

```
}% 2019/04/18 or newer
{% older than 2019/04/18

    \LetLtxMacro\LWR@chemfig@origchemfig\chemfig

    \DeclareDocumentCommand\chemfig{s O{} O{} m}{%
        \begin{lateximage}[-chemfig-~\PackageDiagramAltText]%
        \IfBooleanTF{#1}{%
            \LWR@chemfig@origchemfig*[#2][#3]{#4}%
        }{%
            \LWR@chemfig@origchemfig[#2][#3]{#4}%
        }
        \end{lateximage}%
    }

    \LetLtxMacro\LWR@chemfig@origCF@lewis@b\CF@lewis@b

    \def\CF@lewis@b#1#2{%
    \begin{lateximage}[-chemfig-~\PackageDiagramAltText]%
    \LWR@chemfig@origCF@lewis@b{#1}{#2}%
    \end{lateximage}%
    }

    \preto{\schemestart}{%
        \begin{lateximage}[-chemfig-~\PackageDiagramAltText]%
    }
    \appto{\CF@schemestop}{\end{lateximage}}

}% older than 2019/04/18

\catcode`\_=8%



\LetLtxMacro\LWR@chemfig@origchemleft\chemleft

\def\chemleft#1#2\chemright#3{%
\begin{lateximage}[-chemfig-~\PackageDiagramAltText]%
\LWR@chemfig@origchemleft#1#2\chemright#3%
\end{lateximage}%
}

\LetLtxMacro\LWR@chemfig@origchemup\chemup

\def\chemup#1#2\chemdown#3{%
\begin{lateximage}[-chemfig-~\PackageDiagramAltText]%
\LWR@chemfig@origchemup#1#2\chemdown#3%
\end{lateximage}%
}
```

File 79 **lwarp-chemformula.sty**

# § 186 Package chemformula

(*Emulates or patches code by* Clemens Niederberger.)

Pkg chemformula

chemformula is patched for use by lwarp.

The SVG images are hashed according to contents and local options. Global options are assumed to be constant document-wide.

⚠ chemformula with MathJax

chemformula works best without MathJax. If MathJax is used, `\displaymathother` must be used before `array`, and then `\displaymathnormal` may be used after. (The chemformula package adapts to `array`, but does not know about MathJax, and MathJax does not know about chemformula.)

While using MathJax, `\displaymathother` may also be used for other forms of display and inline math which contain chemformula expressions.

**for HTML output:**

```
\LWR@ProvidesPackagePass{chemformula}[2019/10/13]
\ExplSyntaxOn
```

`\ch` Enclose in an inline SVG image or MathJax. The `alt` tag is is the contents of the `\ch` expression. The filename is hashed, and also has additional hashing information based on the local options.

```
\RenewDocumentCommand \ch { O{}m }
 {%
```

To work inside `align` with `\displaymathother`, a simple version must be used to work with chemformula's adaptation to `align`.

```
   \ifnumcomp{\value{LWR@lateximagedepth}}{>}{0}%  lwarp
   {
       \chemformula_ch:nn {#1} {#2}%   original
   }
```

If used as the outer level, must temporarily ensure MathJax is disabled:

```
   {
       \begingroup%
       \boolfalse{mathjax}%
```

An inline image is used, adjusted for the baseline:

```
       \LWR@subsingledollar*{% lwarp
           \textbackslash{}ch\{\LWR@HTMLsanitize{#2}\}% alt text
       }{%
        \protect\LWR@HTMLsanitize{\detokenize\expandafter{#1}}% add'l hashing
       }%
       {%
           \chemformula_ch:nn {#1} {#2}%   original
       }%
       \endgroup%
   }
}
```

\chcpd Similar to \ch.

```
\@ifpackagelater{chemformula}{2019/10/13}{
\cs_gset_protected:Npn \chemformula_chcpd:nn #1#2
  {
    \begingroup%
    \boolfalse{mathjax}%
    \LWR@subsingledollar*{% lwarp
        \textbackslash{}chcpd\{\LWR@HTMLsanitize{#2}\}%
    }{%
        \protect\LWR@HTMLsanitize{\detokenize\expandafter{#1}}%
    }{% original
    \group_begin:
      \tl_if_blank:nF {#2}
        {
          \keys_set:nn {chemformula} {#1}
          \__chemformula_save_catcodes:
          \__chemformula_sanitize:Nn
            \l__chemformula_chemformula_tmpa_tl
            {#2}
          \__chemformula_input_compound_no_check:NV
            \l__chemformula_compound_tl
            \l__chemformula_chemformula_tmpa_tl
          \__chemformula_prepare_output:NV
            \l__chemformula_compound_tl
            \l__chemformula_catcodes_tl
          \chemformula_write:V \l__chemformula_compound_tl
        }
    \group_end:
    }
    \endgroup
  }
}% later than 2019/10/13
{% earlier than 2019/10/13
\cs_gset_protected:Npn \chemformula_chcpd:nn #1#2
  {
    \begingroup%
    \boolfalse{mathjax}%
    \LWR@subsingledollar*{% lwarp
        \textbackslash{}chcpd\{\LWR@HTMLsanitize{#2}\}%
    }{%
        \protect\LWR@HTMLsanitize{\detokenize\expandafter{#1}}%
    }{% original
    \group_begin:
      \tl_if_blank:nF {#2}
        {
          \keys_set:nn {chemformula} {#1}
          \__chemformula_save_catcodes:
          \__chemformula_sanitize:Nn
            \l__chemformula_chemformula_tmpa_tl
            {#2}
          \__chemformula_input_compound_no_check:NV
            \l__chemformula_compound_tl
            \l__chemformula_chemformula_tmpa_tl
          \__chemformula_prepare_output:N \l__chemformula_compound_tl
          \chemformula_write:V \l__chemformula_compound_tl
```

```
        }
    \group_end:
    }
    \endgroup
  }
}% earlier than 2019/10/13
```

\charrow If standalone, appears in a regular lateximage.

```
\RenewDocumentCommand \charrow { mO{}O{} }
{
    \begin{lateximage}[-chemformula- charrow]
    \group_begin:
      \__chemformula_draw_arrow:nnn {#1} {#2} {#3}
    \group_end:
    \end{lateximage}
}
```

\chname If standalone, appears in a regular lateximage, hashed according to contents.

```
\RenewDocumentCommand \chname { R(){}R(){} }
  {
    \begin{lateximage}*[%
        \textbackslash{}chname(\LWR@HTMLsanitize{#1})(\LWR@HTMLsanitize{#2})
    ]*%
        \chemformula_chwritebelow:nn {#1} {#2}
    \end{lateximage}
  }
```

\chlewis Placed inline, hashed according to contents and options.

```
\RenewDocumentCommand \chlewis { O{}mm }
  {
    \begingroup%
    \boolfalse{mathjax}%
    \LWR@subsingledollar*{\textbackslash{}chlewis\{#2\}\{#3\}}%
    {
        \protect\LWR@HTMLsanitize{\detokenize\expandafter{#1}}%
    }{
        \chemformula_lewis:nnn {#1} {#2} {#3}
    }
    \endgroup%
  }
```

lwarp redefines the $ character, so special handling is required to escape math expressions inside \ch.

This boolean tracks a new kind of escaped math:

```
\bool_new:N      \l__chemformula_first_last_LWRdollar_bool
```

\chemformula_input_escape_math

Adds additional escaping for the new dollar definition:

```
\cs_gset_protected:Npn \__chemformula_input_escape_math:n #1
  {
    \__chemformula_first_last_math:n {#1}
    \bool_if:NT \l__chemformula_first_last_dollar_bool
      {
        \bool_set_true:N \l__chemformula_first_last_math_bool
        \__chemformula_read_escape_dollar:w #1 \q_nil
      }
    \bool_if:NT \l__chemformula_first_last_mathbraces_bool
      {
        \bool_set_true:N \l__chemformula_first_last_math_bool
        \__chemformula_read_escape_mathbraces:w #1 \q_nil
      }
```

Added by lwarp:

```
    \bool_if:NT \l__chemformula_first_last_LWRdollar_bool%      lwarp
      {                                                         lwarp
        \bool_set_true:N \l__chemformula_first_last_math_bool%  lwarp
        \__chemformula_read_escape_LWRdollar:w #1 \q_nil%       lwarp
      }
  }
```

\chemformula_read_escape_LWRdollar

The following parses the contents inside the new dollars.

lwarp keeps the dollar as its original math shift until the document starts. While chemmacros is being patched, the dollar must temporarily be set to its new meaning during the following definition.

```
\begingroup
\catcode`\$=\active

\cs_new_protected:Npn \__chemformula_read_escape_LWRdollar:w $#1$ \q_nil
{
    \__chemformula_read_escape_math:n {#1}
}

\endgroup
```

\chemformula_bool_set_if_first_last

The following looks at the first and last tokens for delimiters to escape math inside \ch. The original definition is modified to look for the control sequences which are used by the new meaning of $.

```
\cs_new_protected:Npn \__chemformula_bool_cs_set_if_first_last:NnNN #1#2#3#4
  {
    \int_zero:N \l__chemformula_tmpa_int
    \int_zero:N \l__chemformula_tmpb_int
    \int_set:Nn \l__chemformula_tmpa_int { \tl_count:n {#2} }
    \tl_map_inline:nn {#2}
      {
```

```
\ExplSyntaxOff
```

File 80 **lwarp-chemgreek.sty**

§ 187 Package

# chemgreek

(*Emulates or patches code by* Clemens Niederberger.)

Pkg chemgreek chemgreek is patched for use by lwarp.

Greek symbols
⚠ package selection To use text-mode symbols, use packages textalpha or textgreek. Using the other packages supported by chemgreek will result in math-mode greek characters, which will result in SVG images being used. These images will be hashed.

⚠ XeLaTeX, LuaLaTeX If using XeLaTeX or LuaLaTeX, select the `fontspec` mapping:

```
\selectchemgreekmapping{fontspec}
```

**for HTML output:**

```
\LWR@ProvidesPackagePass{chemgreek}[2020/01/16]

\ExplSyntaxOn

\cs_gset_protected:Npn \chemgreek_text:n #1
  { { \text {#1} } }

\appto\LWR@restoreorigformatting{%
\cs_set_protected:Npn \chemgreek_text:n #1%
  { \ensuremath { \text {#1} } }%
}

\ExplSyntaxOff
```

File 81 **lwarp-chemmacros.sty**

§ 188 Package

# chemmacros

(*Emulates or patches code by* Clemens Niederberger.)

Pkg chemmacros chemmacros is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{chemmacros}[2017/08/28]
```

SVG file hashing assumes that the relevent options are constant for the entire document.

## § 188.1 Changes to the user's document

⚠ \makepolymerdelims

When using \makepolymerdelims, enclose the entire expression inside a polymerdelims environment, such as (from the chemmacros manual):

```
\begin{polymerdelims}
\chemfig{-[@{op,.75}]CH_2-CH(-[6]Cl)-[@{cl,0.25}]}
\makepolymerdelims{5pt}[27pt]{op}{cl}
\end{polymerdelims}
```

---

⚠ redox reactions

Redox reactions must be enclosed inside a redoxreaction environment. For print output, extra space must be included above and/or below the result, so they are declared as arguments to the environment, instead of being manually entered as per the chemmacros manual. For HTML output, the extra space is ignored and a lateximage is used instead.

```
\begin{redoxreaction}{7mm}{7mm}
\OX{a,Na} $\rightarrow$ \OX{b,Na}\pch\redox(a,b){oxidation}
\end{redoxreaction}
```

## § 188.2 Code

## § 188.3 Loading modules

Patching chemmacros modules must be done \AtBeginDocument, since modules are invoked by the user in the preamble, and each patch is only done if the module is loaded.

```
\ExplSyntaxOn

\newcommand{\@ifchemmacrosmoduleloaded}[1]{%
\@ifl@aded{\c__chemmacros_module_extension_tl}{\c__chemmacros_module_prefix_tl.#1}%
}

\ExplSyntaxOff
```

## § 188.4 New environments

\makepolymerdelims and redox reactions must be enclosed in a lateximage during HTML output. These environments are provided here in HTML mode, and in the lwarp core in print mode, as a high-level semantic syntax which automatically embeds the contents in a lateximage with an appropriate alt tag.

Env polymerdelims

```
\DeclareDocumentEnvironment{polymerdelims}{}
{\begin{lateximage}[-chemmacros- polymer]}
{\end{lateximage}}
```

Env redoxreaction {⟨*space above*⟩} {⟨*space below*⟩}

For HTML output, the above and below space is ignored, and a lateximage is used instead. For the print output version, see section 89.

```
\DeclareDocumentEnvironment{redoxreaction}{m m}
{\begin{lateximage}[-chemmacros- redoxreaction]}
{\end{lateximage}}

\ExplSyntaxOn
```

## § 188.5 Acid-base

```
\AtBeginDocument{
\@ifchemmacrosmoduleloaded{acid-base}{
\PackageInfo{lwarp}{Patching~chemmacros~module~acid-base}

\cs_gset_protected:Npn \chemmacros_p:n #1
  {
    \begingroup
    \boolfalse{mathjax}
    \LWR@subsingledollar*{
        \textbackslash{}p\{\LWR@HTMLsanitize{#1}\}
    }{
        chemmacrosp\protect\LWR@HTMLsanitize{\detokenize\expandafter{#1}}%
    }{
    \group_begin:
      \mbox
        {
          \chemmacros_p_style:n {p}
          \ensuremath {#1}
        }
    \group_end:
    }
    \endgroup
  }

\RenewDocumentCommand \pH  {} {
    \begingroup
    \boolfalse{mathjax}
    \LWR@subsingledollar*{\textbackslash{}pH}{chemmacros}{
        \chemmacros_p:n { \chemmacros_chemformula:n {H} }
    }
    \endgroup
}

\RenewDocumentCommand \pOH {} {
    \begingroup
    \boolfalse{mathjax}
    \LWR@subsingledollar*{\textbackslash{}pOH}{chemmacros}{
        \chemmacros_p:n { \chemmacros_chemformula:n {OH} }
    }
    \endgroup
}

\RenewDocumentCommand \pKa {O{}}
  {
    \begingroup
    \boolfalse{mathjax}
    \LWR@subsingledollar*{\textbackslash{}pKa{[}#1{]}}{chemmacros #1}{
```

```
        \chemmacros_p:n
        {
            \Ka \ifblank {#1} {}
            { {} \c_math_subscript_token { \chemmacros_bold:n {#1} } }
        }
    }
    \endgroup
  }

\RenewDocumentCommand \pKb {O{}}
  {
    \begingroup
    \boolfalse{mathjax}
    \LWR@subsingledollar*{\textbackslash{}pKb{[}#1{]}}{chemmacros #1}{
        \chemmacros_p:n
        {
            \Kb \ifblank {#1} {}
            { {} \c_math_subscript_token { \chemmacros_bold:n {#1} } }
        }
    }
    \endgroup
  }

\LetLtxMacro\LWR@chemmacros@origKa\Ka
\renewcommand*{\Ka}{%
    \begingroup
    \boolfalse{mathjax}
    \LWR@subsingledollar*{\textbackslash{}Ka}{chemmacros}{%
        \LWR@chemmacros@origKa%
    }%
    \endgroup
}

\LetLtxMacro\LWR@chemmacros@origKb\Kb
\renewcommand*{\Kb}{%
    \begingroup
    \boolfalse{mathjax}
    \LWR@subsingledollar*{\textbackslash{}Kb}{chemmacros}{%
        \LWR@chemmacros@origKb%
    }%
    \endgroup
}

\LetLtxMacro\LWR@chemmacros@origKw\Kw
\renewcommand*{\Kw}{%
    \begingroup
    \boolfalse{mathjax}
    \LWR@subsingledollar*{\textbackslash{}Kw}{chemmacros}{
        \LWR@chemmacros@origKw
    }
    \endgroup
}

}{}% \@ifchemmacrosmoduleloaded
}% AtBeginDocument
```

## § 188.6 Charges

```
\AtBeginDocument{
\@ifchemmacrosmoduleloaded{charges}{
\PackageInfo{lwarp}{Patching~chemmacros~module~charges}

\cs_gset_protected:Npn \fplus  {
    \begingroup
    \boolfalse{mathjax}
    \LWR@subsingledollar*{\textbackslash{}fplus}{chemmacros}
    { \LWR@origensuredmath{\chemformula_fplus:}  }
    \endgroup
}
\cs_gset_protected:Npn \fminus {
    \begingroup
    \boolfalse{mathjax}
    \LWR@subsingledollar*{\textbackslash{}fminus}{chemmacros}
    { \LWR@origensuredmath{\chemformula_fminus:} }
    \endgroup
}

}{}% \@ifchemmacrosmoduleloaded
}% AtBeginDocument
```

## § 188.7 Nomenclature

```
\AtBeginDocument{
\@ifchemmacrosmoduleloaded{nomenclature}{
\PackageInfo{lwarp}{Patching~chemmacros~module~nomenclature}

\cs_gset_protected:Npn \chemmacros_charge:n #1
  {
    \ifnumcomp{\value{LWR@lateximagedepth}}{>}{0}
    {\chemmacros_chemformula:n { {}^{#1} }}
    {
        \ifmmode
            {\chemmacros_chemformula:n { {}^{#1} }}
        \else
            { \textsuperscript{\ensuremath{#1}} }
        \fi
    }
  }


\LetLtxMacro\LWR@chemmacros@origchemprime\chemprime

\protected\def\chemprime { \HTMLunicode{2032} }

\appto\LWR@restoreorigformatting{%
\LetLtxMacro\chemprime\LWR@chemmacros@origchemprime%
}

\ChemCompatibilityFrom{5.8}
\cs_gset_protected:Npn \__chemmacros_cip:n #1
  {
    \tl_set:Nn \l__chemmacros_tmpa_tl {#1}
```

```
    \int_step_inline:nnnn {0} {1} {9}
      {
        \tl_replace_all:Nnn \l__chemmacros_tmpa_tl
          {##1}
          { { \l__chemmacros_cip_number_tl ##1} }
      }
    {
        \l__chemmacros_cip_inner_tl
        \LWR@textcurrentcolor{\LWR@textcurrentfont{% lwarp
            \l__chemmacros_tmpa_tl
        }}% lwarp
    }
  }
\EndChemCompatibility

\RenewDocumentCommand \Sconf { O{S} } {
\begin{lateximage}[\textbackslash{}Sconf{[}#1{]}]*
    \chemmacros_sconf:n {#1}
\end{lateximage}
}

\RenewDocumentCommand \Rconf { O{R} } {
\begin{lateximage}[\textbackslash{}Rconf{[}#1{]}]*
    \chemmacros_rconf:n {#1}
\end{lateximage}
}

\cs_gset_protected:Npn \chemmacros_hapto:n #1
  {
    \begingroup
    \boolfalse{mathjax}
    \LWR@subsingledollar*{\textbackslash{}hapto\{#1\}}{chemmacros}{
        \chemmacros_coordination_symbol:nnnn
        { \l__chemmacros_coord_use_hyphen_bool }
        {
            \chemmacros_if_compatibility:nnTF {>} {5.7}
            { \c_true_bool }
            { \c_false_bool }
        }
        { \chemeta }
        {#1}
    }
    \endgroup
  }

\cs_gset_protected:Npn \chemmacros_dento:n #1
  {
    \begingroup
    \boolfalse{mathjax}
    \LWR@subsingledollar*{\textbackslash{}dento\{#1\}}{chemmacros}{
        \chemmacros_coordination_symbol:nnnn
        { \l__chemmacros_coord_use_hyphen_bool }
        {
            \chemmacros_if_compatibility:nnTF {>} {5.7}
            { \c_true_bool }
            { \c_false_bool }
```

```
}{}% \@ifchemmacrosmoduleloaded
}% AtBeginDocument
```

## § 188.9 Phases

```
\AtBeginDocument{
\@ifchemmacrosmoduleloaded{phases}{
\PackageInfo{lwarp}{Patching~chemmacros~module~phases}

\cs_undefine:N \chemmacros_phase:n
\cs_new_protected:Npn \chemmacros_phase:n #1
  {

    \mode_leave_vertical:

    \bool_if:NTF \l__chemmacros_phases_sub_bool
      {
        \ifnumequal{\value{LWR@lateximagedepth}}{0}
        {
            \textsubscript{ (#1) }
        }
        {
            \chemformula_subscript:n { (#1) }
        }
      }
      {
        \skip_horizontal:N \l__chemmacros_phases_space_dim
        \chemmacros_text:n { (#1) }
      }
  }

}{}% \@ifchemmacrosmoduleloaded
}% AtBeginDocument
```

## § 188.10 Mechanisms

```
\AtBeginDocument{
\@ifchemmacrosmoduleloaded{mechanisms}{
\PackageInfo{lwarp}{Patching~chemmacros~module~mechanisms}

\chemmacros_define_keys:nn {textmechanisms}
  {
    type      .choice: ,
    type /    .code:n    =
      {
        \__chemmacros_set_mechanisms:nnn { S }
          {
              \textsubscript{N}
          }
          { }
      } ,
    type / 1  .code:n    =
      {
        \__chemmacros_set_mechanisms:nnn { S }
```

```
322         {
323             \textsubscript{N}
324           1
325         }
326         { }
327     } ,
328   type / 2  .code:n    =
329     {
330       \__chemmacros_set_mechanisms:nnn { S }
331         {
332             \textsubscript{N}
333           2
334         }
335         { }
336     } ,
337   type / se .code:n    =
338     {
339       \__chemmacros_set_mechanisms:nnn { S }
340         {
341             \textsubscript{E}
342         }
343         { }
344     } ,
345   type / 1e .code:n    =
346     {
347       \__chemmacros_set_mechanisms:nnn { S }
348         {
349             \textsubscript{E}
350           1
351         }
352         { }
353     } ,
354   type / 2e .code:n    =
355     {
356       \__chemmacros_set_mechanisms:nnn { S }
357         {
358             \textsubscript{E}
359           2
360         }
361         { }
362     } ,
363   type / ar .code:n    =
364     {
365       \__chemmacros_set_mechanisms:nnn { S }
366         {
367             \textsubscript{E}
368         }
369         { Ar - }
370     } ,
371   type / e  .code:n    =
372     { \__chemmacros_set_mechanisms:nnn { E } { } { } } ,
373   type / e1 .code:n    =
374     { \__chemmacros_set_mechanisms:nnn { E } { 1 } { } } ,
375   type / e2 .code:n    =
376     { \__chemmacros_set_mechanisms:nnn { E } { 2 } { } } ,
```

```
    type / cb .code:n    =
      {
        \__chemmacros_set_mechanisms:nnn { E }
          {
            1
              \textsubscript{cb}
          }
          { }
      } ,
    type      .default:n =
  }

\cs_gset_protected:Npn \chemmacros_mechanisms:n #1
  {
    \tl_if_blank:nTF {#1}
      { \chemmacros_set_keys:nn {textmechanisms} { type } }
      { \chemmacros_set_keys:nn {textmechanisms} { type = #1 } }
    \mbox
      {
        \tl_use:N \l__chemmacros_mechanisms_ar_tl
        \tl_use:N \l__chemmacros_mechanisms_type_tl
        \tl_use:N \l__chemmacros_mechanisms_mol_tl
      }
  }

\appto\LWR@restoreorigformatting{%
\cs_set_protected:Npn \chemmacros_mechanisms:n #1%
  {%
    \tl_if_blank:nTF {#1}%
      { \chemmacros_set_keys:nn {mechanisms} { type } }%
      { \chemmacros_set_keys:nn {mechanisms} { type = #1 } }%
    \mbox%
      {%
        \tl_use:N \l__chemmacros_mechanisms_ar_tl%
        \tl_use:N \l__chemmacros_mechanisms_type_tl%
        \tl_use:N \l__chemmacros_mechanisms_mol_tl%
      }%
  }%
}

}{}% \@ifchemmacrosmoduleloaded
}% AtBeginDocument
```

## § 188.11 Newman

```
\AtBeginDocument{
\@ifchemmacrosmoduleloaded{newman}{
\PackageInfo{lwarp}{Patching~chemmacros~module~newman}

\RenewDocumentCommand \newman {od()m}%
  {
    \IfValueTF{#2}
    {\begin{lateximage}[\textbackslash{}newman(#2)\{#3\}]*}
    {\begin{lateximage}[\textbackslash{}newman\{#3\}]*}
    \group_begin:
      \IfNoValueF  {#1} { \chemmacros_set_keys:nn {newman} {#1} }
```

```
      \IfNoValueTF {#2}
        { \chemmacros_newman:nn {  } {#3} }
        { \chemmacros_newman:nn {#2} {#3} }
    \group_end:
    \end{lateximage}
  }%

}{}% \@ifchemmacrosmoduleloaded
}% AtBeginDocument
```

## § 188.12 Orbital

```
\AtBeginDocument{
\@ifchemmacrosmoduleloaded{orbital}{
\PackageInfo{lwarp}{Patching~chemmacros~module~orbital}

\RenewDocumentCommand \orbital {om}
  {
    \IfValueTF{#1}
    {
        \begin{lateximage}[%
            \textbackslash{}orbital{[}\LWR@HTMLsanitize{#1}{]}\{#2\}%
        ]*[][margin-left: 1em ; margin-right: 1em]
    }
    {
        \begin{lateximage}[%
            \textbackslash{}orbital\{#2\}%
        ]*[][margin-left: 1em ; margin-right: 1em]
    }
    \group_begin:
      \chemmacros_set_keys:nn {orbital/type} {#2}
      \IfNoValueTF {#1}
        { \chemmacros_orbital:n {  } }
        { \chemmacros_orbital:n {#1} }
    \group_end:
    \end{lateximage}
  }

}{}% \@ifchemmacrosmoduleloaded
}% AtBeginDocument
```

## § 188.13 Reactions

`\chemmacros_declare_reaction_env` {⟨*chem*⟩} {⟨*math*⟩} {⟨*args number*⟩} {⟨*argument list ([#2]{#3}...)*⟩}

```
\AtBeginDocument{
\@ifchemmacrosmoduleloaded{reactions}{
\PackageInfo{lwarp}{Patching~chemmacros~module~reactions}

\cs_gset_protected:Npn \chemmacros_declare_reaction_env:nnnn #1#2#3#4
  {
   \exp_args:Nnx \DeclareDocumentEnvironment {#1} { O{} \prg_replicate:nn {#3+0} {m} }
      {
        \boolfalse{mathjax}%                          lwarp
        \ifdefvoid{\LWR@ThisAltText}{%                lwarp
```

```
            \ThisAltText{-chemmacros-~reaction}%    lwarp
        }{}%                                        lwarp
        \chemmacros_add_reaction_description:n {##1}
        \__chemmacros_begin_reaction:
        \chemmacros_reaction_read:nnw {#2} {#4}
      }
      {
        \__chemmacros_end_reaction:
        \gdef\LWR@ThisAltText{}%                    lwarp
      }
  }
\cs_generate_variant:Nn \chemmacros_declare_reaction_env:nnnn {nnnV}

\RenewChemReaction {reaction}   {equation}
\RenewChemReaction {reaction*}  {equation*}
\RenewChemReaction {reactions}  {align}
\RenewChemReaction {reactions*} {align*}

}{}% \@ifchemmacrosmoduleloaded
}% AtBeginDocument
```

## § 188.14 Redox

```
\AtBeginDocument{
\@ifchemmacrosmoduleloaded{redox}{
\PackageInfo{lwarp}{Patching~chemmacros~module~redox}

\NewDocumentCommand \LWR@chemmacros@ox { s m >{\SplitArgument{1}{,}}m }
  {
    \IfBooleanTF {#1}
      { \chemmacros_ox:nnnn {#1} {#2} #3 }
      { \chemmacros_ox:nnnn {  } {#2} #3 }
  }

\RenewDocumentCommand \ox { s O{} m }
  {
    \begingroup
    \boolfalse{mathjax}
    \IfBooleanTF {#1}
      {
        \LWR@subsingledollar*{% yes hash
            \textbackslash{}ox*\{\LWR@HTMLsanitize{#3}\}% alt
        }{%
            star \protect\LWR@HTMLsanitize{\detokenize\expandafter{#2}}%
        }{%
            \LWR@chemmacros@ox* {#2} {#3}% contents
        }%
      }
      {
        \LWR@subsingledollar*{% yes hash
            \textbackslash{}ox*\{\LWR@HTMLsanitize{#3}\}% alt
        }{%
            \protect\LWR@HTMLsanitize{\detokenize\expandafter{#2}}%
        }{%
            \LWR@chemmacros@ox {#2} {#3}% contents
        }%
```

```
      }
    \endgroup
  }

}{}% \@ifchemmacrosmoduleloaded
}% AtBeginDocument
```

## § 188.15 Scheme

Fix for chemmacros as of v5.8b, when using newfloat and babel:

```
\AtBeginDocument{
\@ifchemmacrosmoduleloaded{scheme}{
\PackageInfo{lwarp}{Patching~chemmacros~module~scheme}

\ifdefstring{\schemename}{los}{
\SetupFloatingEnvironment{scheme}{
name = \chemmacros_translate:n {scheme-name}
}
}{}

}{}% \@ifchemmacrosmoduleloaded
}% AtBeginDocument
```

## § 188.16 Spectroscopy

```
\AtBeginDocument{
\@ifchemmacrosmoduleloaded{spectroscopy}{
\PackageInfo{lwarp}{Patching~chemmacros~module~spectroscopy}

\ChemCompatibilityTo{5.8}
\cs_gset_protected:Npn \__chemmacros_nmr_base:nn #1#2
  {
    \tl_if_blank:VF \g__chemmacros_nmr_element_coupled_tl
      {
        \tl_put_left:Nn \g__chemmacros_nmr_element_coupled_tl { \{ }
        \tl_put_right:Nn \g__chemmacros_nmr_element_coupled_tl { \} }
      }
    \tl_put_left:Nn \g__chemmacros_nmr_element_coupled_tl {#2}
%     \chemmacros_chemformula:n { ^{#1} }
    \textsuperscript{#1}
    \bool_if:NTF \l__chemmacros_nmr_parse_bool
      { \chemformula_ch:nV {} \g__chemmacros_nmr_element_coupled_tl }
      { \chemmacros_chemformula:V \g__chemmacros_nmr_element_coupled_tl }
    \tl_use:N \l__chemmacros_nmr_element_method_connector_tl
    \tl_use:N \l__chemmacros_nmr_method_tl
  }
\EndChemCompatibility
\ChemCompatibilityFrom{5.8}
\cs_gset_protected:Npn \__chemmacros_nmr_base:nn #1#2
  {
    \group_begin:
      \tl_use:N \l__chemmacros_nmr_base_format_tl
      \tl_if_blank:VF \g__chemmacros_nmr_element_coupled_tl
        {
```

```
          \tl_put_left:Nn \g__chemmacros_nmr_element_coupled_tl { \{ }
          \tl_put_right:Nn \g__chemmacros_nmr_element_coupled_tl { \} }
        }
      \tl_put_left:Nn \g__chemmacros_nmr_element_coupled_tl {#2}
%       \chemmacros_chemformula:n { ^{#1} }
      \textsuperscript{#1}
      \tl_if_blank:VF \g__chemmacros_nmr_element_coupled_tl
        {
          \bool_if:NTF \l__chemmacros_nmr_parse_bool
            { \chemformula_ch:nV {} \g__chemmacros_nmr_element_coupled_tl }
           { \chemmacros_chemformula:V \g__chemmacros_nmr_element_coupled_tl }
        }
      \tl_use:N \l__chemmacros_nmr_element_method_connector_tl
      \tl_use:N \l__chemmacros_nmr_method_tl
    \group_end:
  }
\EndChemCompatibility


\cs_gset_protected:Npn \chemmacros_nmr_position:n #1
  {
    \chemmacros_chemformula:x
      {
        \exp_not:V \g__chemmacros_nmr_element_tl
        \bool_if:NF \l__chemmacros_nmr_position_side_bool
          {
            \tl_if_eq:NnTF \l__chemmacros_nmr_position_tl {^}% lwarp
            { \textsuperscript{\exp_not:n { {#1} }} }% lwarp
            { \textsubscript{\exp_not:n { {#1} }} }% lwarp
%             \exp_not:V \l__chemmacros_nmr_position_tl
%             \exp_not:n { {#1} }
          }
      }
    \bool_if:NT \l__chemmacros_nmr_position_side_bool
      {
        \tl_use:N \l__chemmacros_nmr_position_tl
        \__chemmacros_nmr_position:n {#1}
      }
  }

\cs_gset_protected:Npn \__chemmacros_nmr_coupling:w (#1;#2)
  {
    \tl_set:Nn \l__chemmacros_nmr_coupling_bonds_tl
      {
        \l__chemmacros_nmr_coupling_bonds_pre_tl
        #1
        \l__chemmacros_nmr_coupling_bonds_post_tl
      }
    \bool_if:NTF \l__chemmacros_nmr_coupling_nuclei_sub_bool
      {
        \tl_set:Nn \l__chemmacros_nmr_coupling_nuclei_tl
          {
%             \c_math_subscript_token
            \textsubscript% lwarp
              {
```

```
                \l__chemmacros_nmr_coupling_nuclei_pre_tl
                \chemmacros_chemformula:n {#2}
                \l__chemmacros_nmr_coupling_nuclei_post_tl
              }
          }
      }
      {
        \tl_set:Nn \l__chemmacros_nmr_coupling_nuclei_tl
          {
            \l__chemmacros_nmr_coupling_nuclei_pre_tl
            \chemmacros_chemformula:n {#2}
            \l__chemmacros_nmr_coupling_nuclei_post_tl
          }
      }
    \__chemmacros_nmr_coupling_aux_i:w
  }
\AfterEndPreamble{% After \AtBeginDocument
% \NMR{<num>,<elem>}(<num>,<unit>)[<solvent>] ALL arguments are optional
% \NMR* same but without ": $\delta$" at end
\cs_gset_protected:Npn \chemmacros_nmr:nnnn #1#2#3#4
    {
    \bool_if:NT \l__chemmacros_nmr_list_bool { \item \scan_stop: }
    \group_begin:

        \mode_leave_vertical:

        \bool_set_false:N \l__chemmacros_nmr_frequency_bool
        \bool_set_false:N \l__chemmacros_nmr_solvent_bool
        \tl_if_empty:nF {#3}
        { \bool_set_true:N \l__chemmacros_nmr_frequency_bool }
        \tl_if_empty:nF {#4}
        { \bool_set_true:N \l__chemmacros_nmr_solvent_bool }
        \bool_if:nT
        {
            \l__chemmacros_nmr_frequency_bool
            ||
            \l__chemmacros_nmr_solvent_bool
        }
        { \bool_set_true:N \l__chemmacros_nmr_delimiters_bool }
        \bool_if:nT
        {
            \l__chemmacros_nmr_frequency_bool
            &&
            \l__chemmacros_nmr_solvent_bool
        }
        { \bool_set_true:N \l__chemmacros_nmr_comma_bool }
        \tl_if_empty:nTF {#2}
        {
            \__chemmacros_nmr_nucleus:VV
            \l__chemmacros_nmr_isotope_default_tl
            \l__chemmacros_nmr_element_default_tl
        }
        { \__chemmacros_nmr_nucleus:w #2 \q_stop }
        \mode_if_math:TF
        {
            \text
```

```
            {
                \group_begin:
                \tl_use:N \l__chemmacros_nmr_format_tl
\LWR@textcurrentcolor{\LWR@textcurrentfont{% lwarp
                \__chemmacros_nmr_base:VV
                    \g__chemmacros_nmr_isotope_tl
                    \g__chemmacros_nmr_element_tl
                \bool_if:NT \l__chemmacros_nmr_delimiters_bool
                    { ~ ( }
                \bool_if:NT \l__chemmacros_nmr_frequency_bool
                    { \__chemmacros_nmr_frequency:n {#3} }
                \bool_if:NT \l__chemmacros_nmr_comma_bool
                    { , ~ }
                \bool_if:NT \l__chemmacros_nmr_solvent_bool
                    { \chemmacros_chemformula:n {#4} }
                \bool_if:NT \l__chemmacros_nmr_delimiters_bool
                    { ) }
                \tl_if_blank:nT {#1} {:~}
}}% lwarp
                \group_end:
            }
            \tl_if_blank:nT {#1}
            {
                \delta
                \text { \l__chemmacros_nmr_delta_tl }
                \bool_if:NT \l__chemmacros_nmr_use_equal_bool {=}
            }
        }
        {
            \group_begin:
            \tl_use:N \l__chemmacros_nmr_format_tl
\LWR@textcurrentcolor{\LWR@textcurrentfont{% lwarp
            \__chemmacros_nmr_base:VV
                \g__chemmacros_nmr_isotope_tl
                \g__chemmacros_nmr_element_tl
            \bool_if:NT \l__chemmacros_nmr_delimiters_bool
                {~(}
            \bool_if:NT \l__chemmacros_nmr_frequency_bool
                { \__chemmacros_nmr_frequency:n {#3} }
            \bool_if:NT \l__chemmacros_nmr_comma_bool
                {,~}
            \bool_if:NT \l__chemmacros_nmr_solvent_bool
                {
                \bool_if:NTF \l__chemmacros_nmr_parse_bool

%                    { \chemformula_ch:nn { } {#4} }%  original
                    {\ch{#4}}%  lwarp
                    {#4}
                }
            \bool_if:NT \l__chemmacros_nmr_delimiters_bool
                {)}
}}% lwarp
            \tl_if_blank:nT {#1} {:}
            \group_end:
            \tl_if_blank:nT {#1}
```

```
          \c_math_superscript_token
            { \chemmacros_text:V \l__chemmacros_state_sp_left_tl }
```

Only add the subscripts if they are being used. This avoids causing an incorrect depth, as the empty subscript will be measured by TEX but cropped out by *pdfcrop*.

```
          \tl_if_empty:NTF \l__chemmacros_state_sb_left_tl
          {}
          {
            \c_math_subscript_token
            { \chemmacros_text:V \l__chemmacros_state_sb_left_tl }
          }
          #2
          \c_math_superscript_token
            { \chemmacros_text:V \l__chemmacros_state_sp_right_tl }
          \tl_if_empty:NTF \l__chemmacros_state_sb_right_tl
          {}
          {
            \c_math_subscript_token
            { \chemmacros_text:V \l__chemmacros_state_sb_right_tl }
          }
          \chemmacros_text:V \l__chemmacros_state_post_tl
        }
      }
    \group_end:
  }
\cs_generate_variant:Nn \chemmacros_state:nn { nV }

\cs_gset_protected:Npn \chemmacros_declare_state:Nn #1#2
  {
    \chemmacros_define_keys:xn
      {thermodynamics/\chemmacros_remove_backslash:N #1}
      {
        pre              .meta:nn = {chemmacros/thermodynamics} { pre = ##1 } ,
        post             .meta:nn = {chemmacros/thermodynamics} { post = ##1 } ,
      superscript-left  .meta:nn = {chemmacros/thermodynamics} { superscript-left = ##1 } ,
      superscript-right .meta:nn = {chemmacros/thermodynamics} { superscript-right = ##1 } ,
        superscript       .meta:n  = { superscript-right = ##1 } ,
      subscript-left   .meta:nn = {chemmacros/thermodynamics} { subscript-left = ##1 } ,
      subscript-right  .meta:nn = {chemmacros/thermodynamics} { subscript-right = ##1 } ,
        subscript         .meta:n     = { subscript-left = ##1 } ,
        subscript-pos     .choices:nn =
          { left , right }
          { \tl_set_eq:NN \l__chemmacros_state_sb_pos_tl \l_keys_choice_tl } ,
        symbol            .tl_set:N = \l__chemmacros_state_symbol_tl ,
        unit              .tl_set:N = \l__chemmacros_state_unit_tl
      }
    \DeclareDocumentCommand #1 { sO{}D(){}m }
      {
        \group_begin:
          \chemmacros_set_keys:xn
            {thermodynamics/\chemmacros_remove_backslash:N #1}
            {#2}
          \tl_if_blank:nF {##3}
            {
```

```
              \chemmacros_set_keys:nx {thermodynamics}
                { subscript-\l__chemmacros_state_sb_pos_tl = \exp_not:n {##3} }
            }
              \chemmacros_state:nV {##2} \l__chemmacros_state_symbol_tl
             \chemmacros_set_keys_groups:nnn {thermodynamics} {variables} {##2}
            \IfBooleanF {##1} {  = ~ \SI {##4} { \l__chemmacros_state_unit_tl } }
        \group_end:
      }
  }
```

The pre-existing macros are redefined with the new definition:

```
\RenewChemState \enthalpy { symbol = H , unit = \kilo\joule\per\mole }
\RenewChemState \entropy  { symbol = S , unit = \joule\per\kelvin\per\mole , pre = }
\RenewChemState \gibbs    { symbol = G , unit = \kilo\joule\per\mole }

}{}% \@ifchemmacrosmoduleloaded
}% AtBeginDocument

\ExplSyntaxOff
```

---

File 82 **lwarp-chemnum.sty**

# § 189 Package chemnum

(*Emulates or patches code by* Clemens Niederberger.)

Pkg chemnum chemnum is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{chemnum}[2016/04/14]

\ExplSyntaxOn

\cs_gset_protected:Npn \chemnum_compound_write:n #1
  {
    \chemnum_get_compound_property:nn {#1} {pre-main-label-code}
    \group_begin:
      \bool_if:NTF \l__chemnum_compound_local_bool
        { \l__chemnum_local_label_format_tl }
        { \chemnum_get_compound_property:nn {#1} {label-format} }
      {
        \LWR@textcurrentfont{
            \chemnum_get_compound_property:nn {#1} {counter-representation}
        }
      }
    \group_end:
    \chemnum_get_compound_property:nn {#1} {post-main-label-code}
  }

\cs_gset_protected:Npn \chemnum_subcompound_write:nn #1#2
  {
    \group_begin:
      \bool_if:NTF \l__chemnum_compound_local_bool
```

```
      { \l__chemnum_local_label_format_tl }
      { \chemnum_get_compound_property:nn {#1} {label-format} }
    {
      \LWR@textcurrentfont{
          \chemnum_get_subcompound_property:nnn {#1} {#2}
          {counter-representation}
      }
    }
  \group_end:
}

\ExplSyntaxOff
```

File 83 **lwarp-chkfloat.sty**

## § 190 Package chkfloat

Pkg chkfloat chkfloat is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{chkfloat}[2012/08/19]
```

File 84 **lwarp-chngpage.sty**

## § 191 Package chngpage

(*Emulates or patches code by* Peter Wilson.)

Pkg chngpage chngpage is ignored.

**for HTML output:** Discard all options for lwarp-chngpage:

```
\LWR@ProvidesPackageDrop{chngpage}[2009/10/20]
\LWR@origRequirePackage{lwarp-changepage}
```

File 85 **lwarp-cite.sty**

## § 192 Package cite

(*Emulates or patches code by* Donald Arseneau.)

Pkg cite cite is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{cite}[2015/02/27]
```

For the [super] option, the \kern must be removed:

```
\def\LWRCT@biblabel#1{\@citess{#1}\kern-\labelsep\,}

```

```
    \ifdefequal{\@@@setcref}{\LWR@orig@@@setcref}{% as of v0.21
        \renewcommand*{\@@@setcref}[2]{%
            #1{\ref{#2}}{}{}}
    }{
        \PackageWarningNoLine{lwarp-cleveref}{
            Unknown version of cleveref.
            \protect\cref\space will fail.
        }%
    }
}
```

`\@@@setcrefrange` {⟨*text*⟩} {⟨*label*⟩} {⟨*label*⟩}

```
\def\LWR@orig@@@setcrefrange#1#2#3{%
  \cref@getlabel{#2}{\@labela}%
  \cref@getlabel{#3}{\@labelb}%
  #1{\@labela}{\@labelb}{}{}{}{}%

\ifdefequal{\@@setcrefrange}{\LWR@orig@@@setcrefrange}{
    \renewcommand{\@@setcrefrange}[3]{%
        #1{\ref{#2}}{\ref{#3}}{}{}{}{}%
    }
}{
    \ifdefequal{\@@@setcrefrange}{\LWR@orig@@@setcrefrange}{
        \renewcommand{\@@@setcrefrange}[3]{%
            #1{\ref{#2}}{\ref{#3}}{}{}{}{}%
        }
    }{
        \PackageWarningNoLine{lwarp-cleveref}{
            Unknown version of cleveref.
            \protect\crefrange\space will fail.
        }
    }
}
```

`\cpagerefFor` Redefinable word between “page(s)” and the page numbers.

```
\newcommand*{\cpagerefFor}{for}
```

`\@@@setcpageref` {⟨*typeofref*⟩} {⟨*label*⟩}, where typeofref is “page” or “pages”

```
\def\LWR@orig@@setcpageref#1#2{% before v0.21
  \cref@getpageref{#2}{\@temppage}#1{\@temppage}{}{}}%

\def\LWR@orig@@@setcpageref#1#2{% as of v0.21
  \cpageref@getlabel{#2}{\@temppage}#1{\@temppage}{}{}}%

\ifdefequal{\@@setcpageref}{\LWR@orig@@setcpageref}{
    \renewcommand*{\@@setcpageref}[2]{%
        #1{\cpagerefFor\ \cref{#2}}{}{}%
    }
}{
    \ifdefequal{\@@@setcpageref}{\LWR@orig@@@setcpageref}{
```

```
        \renewcommand*{\@@@setcpageref}[2]{%
            #1{\cpagerefFor\ \cref{#2}}{}{}%
        }
    }
    {
        \PackageWarningNoLine{lwarp-cleveref}{
            Unknown version of cleveref.
            \protect\cpageref\space will fail.
        }
    }
}

\def\LWR@orig@@setcpagerefrange#1#2#3{% before v0.21
  \cref@getpageref{#2}{\@pagea}%
  \cref@getpageref{#3}{\@pageb}%
  #1{\@pagea}{\@pageb}{}{}{}{}}%

\def\LWR@orig@@@setcpagerefrange#1#2#3{% as of v0.21
  \cpageref@getlabel{#2}{\@pagea}%
  \cpageref@getlabel{#3}{\@pageb}%
  #1{\@pagea}{\@pageb}{}{}{}{}}%

\ifdefequal{\@@setcpagerefrange}{\LWR@orig@@setcpagerefrange}{
    \renewcommand*{\@@setcpagerefrange}[3]{%
        #1{\cpagerefFor\ \cref{#2}}{\cref{#3}}{}{}{}{}%
    }
}{
    \ifdefequal{\@@@setcpagerefrange}{\LWR@orig@@@setcpagerefrange}{
        \renewcommand*{\@@@setcpagerefrange}[3]{%
            #1{\cpagerefFor\ \cref{#2}}{\cref{#3}}{}{}{}{}%
        }
    }
    {
        \PackageWarningNoLine{lwarp-cleveref}{
            Unknown version of cleveref.
            \protect\cpagerefrange\space will fail.
        }
    }
}
```

If hyperref is loaded, cleveref defines starred versions of the following, but since hyperref is only emulated, starred versions are defined here:

```
\LWR@absorbstar{cref}
\LWR@absorbstar{Cref}
\LWR@absorbstar{crefrange}
\LWR@absorbstar{Crefrange}
\LWR@absorbstar{cpageref}
\LWR@absorbstar{Cpageref}
\LWR@absorbstar{cpagerefrange}
\LWR@absorbstar{Cpagerefrange}
\LWR@absorbstar{labelcref}
\LWR@absorbstar{labelcpageref}
```

If hyperref is loaded, cleveref also defines starred versions of varioref macros, so they are defined here.

```
\@ifpackageloaded{varioref}{
    \LWR@absorbstar{vref}
    \LWR@absorbstar{Vref}
    \LWR@absorbstar{vrefrange}
    \LWR@absorbstar{Vrefrange}
    \LWR@absorbstar{fullref}
    \LWR@absorbstar{Fullref}
}{}% varioref
```

---

File 90 **lwarp-clrdblpg.sty**

# § 197 Package clrdblpg

Pkg clrdblpg clrdblpg is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{clrdblpg}[2018/04/21]
```

---

File 91 **lwarp-cmbright.sty**

# § 198 Package cmbright

(*Emulates or patches code by* Walter Schmidt.)

Pkg cmbright cmbright is used as-is for SVG math, and is emulated for MathJax.

⚠ limitations The MathJax emulation ignores all package options, except `slantedGreek` is honored, and `\mathbold` is available.

The dedicated macros for upright Greek letters do work correctly.

SVG math should appear the same as the printed output.

**for HTML output:**

```
\LWR@ProvidesPackagePass{cmbright}[2005/04/13]

\LWR@infoprocessingmathjax{cmbright}

\LWR@origRequirePackage{lwarp-common-mathjax-letters}

\begin{warpMathJax}

\@ifpackagewith{cmbright}{slantedGreek}
{
    \LWR@mathjax@addgreek@u@it*{}{}
}
{}

\LWR@mathjax@addgreek@u@up*{up}{}

```

```
\CustomizeMathJax{\newcommand{\mathbold}[1]{\boldsymbol{#1}}}

\end{warpMathJax}
```

File 92 **lwarp-cmdtrack.sty**

## § 199 Package cmdtrack

Pkg cmdtrack cmdtrack is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{cmdtrack}[2012/12/18]

\newcommand{\untrack}[1]{}
```

File 93 **lwarp-colonequals.sty**

## § 200 Package colonequals

(*Emulates or patches code by* Heiko Oberdiek.)

Pkg colonequals colonequals is used as-is for SVG math, and is emulated for MathJax.

Since Unicode symbols are not available for each of the following, only two are used for the single and double colons, and the other symbols are derived in a consistent manner. Occasional negative space is added as well. This may need to be undone for some fonts.

**for HTML output:**

```
\LWR@ProvidesPackagePass{colonequals}[2016/05/16]

\begin{warpMathJax}
\LWR@infoprocessingmathjax{colonequals}

\CustomizeMathJax{\newcommand{\ratio}{\mathrel{\unicode{x2236}}}}
\CustomizeMathJax{\newcommand{\coloncolon}{\mathrel{\unicode{x2237}}}}
\CustomizeMathJax{\newcommand{\colonequals}{\mathrel{\unicode{x2236}\!=}}}
\CustomizeMathJax{\newcommand{\coloncolonequals}{\mathrel{\unicode{x2237}\!=}}}
\CustomizeMathJax{\newcommand{\equalscolon}{\mathrel{=\!\unicode{x2236}}}}
\CustomizeMathJax{\newcommand{\equalscoloncolon}{\mathrel{=\!\unicode{x2237}}}}
\CustomizeMathJax{\newcommand{\colonminus}{\mathrel{\unicode{x2236}-}}}
\CustomizeMathJax{\newcommand{\coloncolonminus}{\mathrel{\unicode{x2237}-}}}
\CustomizeMathJax{\newcommand{\minuscolon}{\mathrel{-\unicode{x2236}}}}
\CustomizeMathJax{\newcommand{\minuscoloncolon}{\mathrel{-\unicode{x2237}}}}
\CustomizeMathJax{\newcommand{\colonapprox}{\mathrel{\unicode{x2236}\!\approx}}}
\CustomizeMathJax{\newcommand{\coloncolonapprox}{\mathrel{\unicode{x2237}\!\approx}}}
\CustomizeMathJax{\newcommand{\approxcolon}{\mathrel{\approx\!\unicode{x2236}}}}
\CustomizeMathJax{\newcommand{\approxcoloncolon}{\mathrel{\approx\!\unicode{x2237}}}}
\CustomizeMathJax{\newcommand{\colonsim}{\mathrel{\unicode{x2236}\!\sim}}}
\CustomizeMathJax{\newcommand{\coloncolonsim}{\mathrel{\unicode{x2237}\!\sim}}}
\CustomizeMathJax{\newcommand{\simcolon}{\mathrel{\sim\!\unicode{x2236}}}}
\CustomizeMathJax{\newcommand{\simcoloncolon}{\mathrel{\sim\!\unicode{x2237}}}}
\end{warpMathJax}
```

File 94 **lwarp-color.sty**

## § 201 Package color

Pkg color Allowed but ignored. xcolor is then required as well.

color is superceded by xcolor, and lwarp requires several of the features of xcolor. When color is requested, xcolor is loaded as well.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{color}[2016/07/10]
\RequirePackage{xcolor}
```

File 95 **lwarp-colortbl.sty**

## § 202 Package colortbl

Pkg colortbl colortbl is used as-is for print output, and emulated for HTML.

⚠ row/cell color Only use `\rowcolor` and `\cellcolor` at the start of a row, in that order.

colortbl ignores the overhang arguments.

**for HTML output:** A placeholder definition is forgotten first:

```
\let\rowcolor\relax

\LWR@ProvidesPackagePass{colortbl}[2018/12/12]
```

The following `\LWR@HTML` versions are used inside an HTML `tabular`.

`\columncolor` `[`⟨*model*⟩`]` `{`⟨*color*⟩`}` `[`⟨*left overhang*⟩`]` `[`⟨*right overhang*⟩`]`

`\LWR@getmynexttoken` is not used here because `\columncolor` is not used inside the data area of the tabular.

```
\NewDocumentCommand{\LWR@HTML@columncolor}{O{named} m o o}{%
    \convertcolorspec{#1}{#2}{HTML}\LWR@columnHTMLcolor%
    \LWR@addtabularcellcolor%
}

\AtBeginDocument{\LWR@formatted{columncolor}}
```

`\LWR@getmynexttoken` is used for `\rowcolor` because it is used inside the data area of the tabular.

`\rowcolor` `[`⟨*model*⟩`]` `{`⟨*color*⟩`}` `[`⟨*left overhang*⟩`]` `[`⟨*right overhang*⟩`]`

```
\NewDocumentCommand{\LWR@HTML@rowcolor}{O{named} m o o}{%
    \convertcolorspec{#1}{#2}{HTML}\LWR@rowHTMLcolor%
```

```
    \LWR@getmynexttoken%
}

\AtBeginDocument{\LWR@expandableformatted{rowcolor}}
```

\cellcolor [⟨*model*⟩] {⟨*color*⟩} [⟨*left overhang*⟩] [⟨*right overhang*⟩]

```
\NewDocumentCommand{\LWR@HTML@cellcolor}{O{named} m o o}{%
    \convertcolorspec{#1}{#2}{HTML}\LWR@cellHTMLcolor%
    \LWR@addtabularcellcolor%
}

\AtBeginDocument{\LWR@formatted{cellcolor}}
```

\arrayrulecolor [⟨*model*⟩] {⟨*color*⟩}

The HTML version for use outside a `tabular`. Inside a `tabular`, `\LWR@HTML@arrayrulecolornexttoken` is used instead.

```
\newcommand{\LWR@HTML@arrayrulecolor}[2][named]{%
    \convertcolorspec{#1}{#2}{HTML}\LWR@ruleHTMLcolor%
}

\AtBeginDocument{\LWR@expandableformatted{arrayrulecolor}}
```

[⟨*model*⟩] {⟨*color*⟩}

\LWR@arrayrulecolornexttoken

The HTML version for use inside a `tabular`.

```
\newcommand{\LWR@HTML@arrayrulecolornexttoken}[2][named]{%
    \convertcolorspec{#1}{#2}{HTML}\LWR@ruleHTMLcolor%
    \LWR@getmynexttoken%
}

\AtBeginDocument{\LWR@expandableformatted{arrayrulecolornexttoken}}
```

\doublerulesepcolor [⟨*model*⟩] {⟨*color*⟩}

The version for use outside a `tabular`.

```
\newcommand{\LWR@HTML@doublerulesepcolor}[2][named]{}

\AtBeginDocument{\LWR@expandableformatted{doublerulesepcolor}}
```

[⟨*model*⟩] {⟨*color*⟩}

\LWR@doublerulesepcolornexttoken

The version for use inside a `tabular`.

```
\newcommand{\LWR@HTML@doublerulesepcolornexttoken}[2][named]{\LWR@getmynexttoken}

\AtBeginDocument{\LWR@expandableformatted{doublerulesepcolornexttoken}}
```

For MathJax, colors are discarded.

```
\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\columncolor}[2][]{\LWRabsorbtwooptions}}
\CustomizeMathJax{\let\rowcolor\columncolor}
```

File 98 **lwarp-crop.sty**

## § 205 Package crop

(*Emulates or patches code by* Melchior FRANZ.)

Pkg crop crop is ignored.

**for HTML output:** Discard all options for lwarp-crop:

```
\LWR@ProvidesPackageDrop{crop}[2003/05/20]

\newcommand*{\crop}[1][]{}
\newcommand*{\cropdef}[6][]{}
```

File 99 **lwarp-ctable.sty**

## § 206 Package ctable

(*Emulates or patches code by* Wybo Dekker.)

Pkg ctable ctable is patched for use by lwarp.

⚠ Misplaced alignment tab character & Use `\StartDefiningTabulars` before one or more `\ctables`, and `\StopDefiningTabulars` after. These change the meaning of the ampersand & character.

**for HTML output:**

```
\LWR@ProvidesPackagePass{ctable}[2015/10/17]
```

The following is in the original:

```
\newcommand{\LWR@HTML@ctable}[4][]{%
   \let\@CTtaborfig  \@dfltCTtaborfig
   \let\@CTalign     \@dfltCTalign
   \let\@CTsideways  \@dfltCTsideways
   \let\@CTcontinued \empty
   \let\@CTpos       \@dfltCTpos
   \let\@CTcaption   \empty
   \let\@CTcap       \undefined
   \let\@CTlabel     \empty
   \let\@CTbotcap    \@dfltCTbotcap
   \let\@CTstarred   \@dfltCTstarred
   \let\@CTsuper     \@dfltCTsuper
   \let\@CTnotespar  \@dfltCTnotespar
   \let\@CTdoinside  \@dfltCTdoinside
   \let\@CTbgopacity \@dfltCTbgopacity
   \@CTframerule     \@dfltCTframerule
   \@CTcaptionskip   \@dfltCTcaptionskip
   \@CTframesep      \@dfltCTframesep
   \@CTwidth         \@dfltCTwidth
```

```
\@CTmaxwidth      \@dfltCTmaxwidth
\@CTmincapwidth   \@dfltCTmincapwidth
\@CTfooterwidth   \@dfltCTfooterwidth
\def\@CTfgactual {@dfltCTframefg}%
\def\@CTbgactual {@dfltCTframebg}%
\def\@CTbeg      {\begin{\@CTsideways\@CTtaborfig\@CTstarred}}%
\def\@CTbegin    {\@CTbeg}%
\def\@CTend      {\end{\@CTsideways\@CTtaborfig\@CTstarred}}%
\setkeys{CT}{#1}%
\ifx\@CTcap\undefined\let\@CTcap\@CTcaption\fi
\ifx\@CTcap\empty
  \if@CTcaptionloaded\else
    \PackageWarningNoLine{lwarp-ctable}{\MessageBreak
       An empty cap= option prevents lot/loc entry only\MessageBreak
       if the caption package is loaded!}
  \fi
\fi
\if@CTinmemoir\else
   \ifx\@CTbotcap\undefined
      \PackageError{lwarp-ctable}{\MessageBreak
         You can, currently, use the sidecap option only with\MessageBreak
         memoir documents. Use topcap or botcap only}
         {}
   \fi
\fi
\ifdim\@CTwidth=0pt\else
   \ifdim\@CTmaxwidth=0pt\else
      \PackageError{lwarp-ctable}{\MessageBreak
        You may not use the width and maxwidth options together\MessageBreak
         Use either width or maxwidth}
         {}
   \fi
\fi
\ifx\@CTpos\empty
   \ifx\@CTsideways\empty\else
   \PackageError{lwarp-ctable}{\MessageBreak
      You may not use the pos and sideways options together\MessageBreak
      Rotated tables and figures are always typeset on a separate page}
     {}
   \fi
\fi
\ifx\@CTcaption\empty
   \ifx\@CTlabel\empty\else
      \PackageError{lwarp-ctable}{\MessageBreak
         You may not label a captionless table\MessageBreak
         Such a label can't be referenced}
         {}
   \fi
\fi
```

Some of the original, regarding computing the width of `\CT@t`, is removed here.

```
\@CTbegin
   \ifx\@CTcontinued\empty\else\addtocounter{\@CTtaborfig}{-1}\fi
   \@CTalign
```

lwarp's patches begin here:

```
    \begin{center}
        \setlength{\fboxrule}{\@CTframerule}
        \setlength{\fboxsep}{\@CTframesep}
        \LWR@forceminwidth{\fboxrule}%  lwarp
        \convertcolorspec{named}{\@CTbgactual}{HTML}\LWR@tempcolor% lwarp
        \begin{BlockClass}[%                            lwarp
            border:
                \LWR@printlength{\LWR@atleastonept}
                solid
                \LWR@colorstyle{named}{\@CTfgactual} ; %
            padding:\LWR@printlength{\fboxsep} ; %
            \ifdefstring{\LWR@tempcolor}{FFFFFF}{}{%
                background: \LWR@colorstyle{named}{\@CTbgactual} ; %
            }%
        ]{fminipage}%       lwarp
         \ifx\@CTbotcap\@CTfalse\@CTcaption\vskip\@CTcaptionskip\fi
         \ifx\@CTbotcap\undefined%
             \begin{sidecaption}[\@CTcap]{\@CTcaption}[\@CTlabel]
         \fi
         \@CTdoinside
         \begin{tabularx}{\linewidth}{#2}%      lwarp
            #4%
         \end{tabularx}%                    lwarp
         \def\@CTfootnotes{#3}%
         \ifx#3\empty\else{% append footnotes, if any
            \begin{BlockClass}{tnotes}%     lwarp
            #3
            \end{BlockClass}%               lwarp
         }
         \fi
         \ifx\@CTbotcap\undefined\end{sidecaption}\fi
         \ifx\@CTbotcap\@CTtrue\vskip\@CTcaptionskip\@CTcaption\fi
        \end{BlockClass}
     \end{center}
    \@CTend
}
\LWR@formatted{ctable}
```

Required to properly detect the toprule:

```
\LetLtxMacro\FL\toprule
```

Table notes are redefined for HTML:

```
\newcommand{\LWR@HTML@tmark}[1][a]{%
   \textsuperscript{\textrm{\textit{#1}}}}
}
\LWR@formatted{tmark}

\newcommand{\LWR@HTML@tnote}[2][a]{%
    \tmark[#1]\,#2\par
}
\LWR@formatted{tnote}
```

File 100 **lwarp-cuted.sty**

## § 207 Package cuted

(*Emulates or patches code by* Sigitas Tolušis.)

Pkg cuted cuted is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{cuted}[2012/10/04]

\newenvironment{strip}{}{}
\newskip\stripsep
\def\oldcolsbreak#1{}
```

File 101 **lwarp-cutwin.sty**

## § 208 Package cutwin

(*Emulates or patches code by* Peter Wilson and Alan Hoenig.)

Pkg cutwin cutwin is emulated.

**for HTML output:** Discard all options for lwarp-cutwin:

```
\LWR@ProvidesPackageDrop{cutwin}[2010/09/29]

\newcommand*{\opencutleft}{}
\newcommand*{\opencutright}{}
\newcommand*{\opencutcenter}{}
\newcommand*{\cutfuzz}{}

\newenvironment{cutout}[4]
{\marginpar{\windowpagestuff}}
{}

\newcommand*{\windowpagestuff}{}

\newcommand*{\pageinwindow}{%
% \begin{minipage}{.3\linewidth}
\windowpagestuff
% \end{minipage}
}

\newenvironment{shapedcutout}[3]
{\marginpar{\picinwindow}}
{}

\newcommand*{\putstuffinpic}{}

```

Pkg decimal decimal works as-is for SVG math, and is emulated for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{decimal}[2011/06/03]

\begin{warpMathJax}
\CustomizeMathJax{\def\.{\mbox{.}}}
\end{warpMathJax}
```

File 106 **lwarp-diagbox.sty**

# § 213 Package diagbox

(*Emulates or patches code by* Leo Liu.)

Pkg diagbox diagbox is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{diagbox}[2016/12/28]
```

To restore print-mode inside a `lateximage`:

```
\LetLtxMacro\LWR@origdiagbox@double\diagbox@double
\LetLtxMacro\LWR@origdiagbox@triple\diagbox@triple

\appto\LWR@restoreorigformatting{%
\LetLtxMacro\diagbox@double\LWR@origdiagbox@double%
\LetLtxMacro\diagbox@triple\LWR@origdiagbox@triple%
}
```

\LWR@diagbox@AB {⟨*E*/*W*⟩} {⟨*A*⟩} {⟨*E*/*W*⟩} {⟨*B*⟩}

```
\newcommand{\LWR@diagbox@AB}[4]{
\begingroup%
\LetLtxMacro\\\newline%
\BlockClassSingle{diagbox#1}{#2}%
\BlockClassSingle{diagbox#3}{#4}%
\endgroup%
\LWR@stoppars%
}
```

\LWR@diagboxNW {⟨*A*⟩} {⟨*B*⟩}

```
\newcommand{\LWR@diagboxNW}[2]{%
\LWR@diagbox@AB{E}{#2}{W}{#1}%
}
```

Likewise for NE, SW, SE:

```
\newcommand{\LWR@diagboxNE}[2]{%
\LWR@diagbox@AB{W}{#1}{E}{#2}%
}

\let\LWR@diagboxSW\LWR@diagboxNE
\let\LWR@diagboxSE\LWR@diagboxNW
```

\diagbox@double {⟨*keys*⟩} {⟨*A*⟩} {⟨*B*⟩}

```
\def\diagbox@double#1#2#3{%
\setkeys{diagbox}{dir=NW,#1}%
\@nameuse{LWR@diagbox\diagbox@dir}{#2}{#3}%
}
```

\LWR@diagboxTNW {⟨*title*⟩} {⟨*A*⟩} {⟨*B*⟩}

```
\newcommand{\LWR@diagboxTNW}[3]{%
\BlockClassSingle{diagboxtitleN}{#1}
\LWR@diagboxNW{#2}{#3}
}
```

Likewise for NE, SW, SE:

```
\newcommand{\LWR@diagboxTNE}[3]{%
\BlockClassSingle{diagboxtitleN}{#1}
\LWR@diagboxNE{#2}{#3}
}

\newcommand{\LWR@diagboxTSW}[3]{%
\LWR@diagboxSW{#2}{#3}
\BlockClassSingle{diagboxtitleS}{#1}
\LWR@stoppars%
}

\newcommand{\LWR@diagboxTSE}[3]{%
\LWR@diagboxSE{#2}{#3}
\BlockClassSingle{diagboxtitleS}{#1}
\LWR@stoppars%
}
```

\diagbox@triple {⟨*keys*⟩} {⟨*A*⟩} {⟨*T*⟩} {⟨*B*⟩}

```
\def\diagbox@triple#1#2#3#4{%
\setkeys{diagbox}{dir=NW,#1}%
\@nameuse{LWR@diagboxT\diagbox@dir}{#3}{#2}{#4}%
}
```

---

File 107 **lwarp-dingbat.sty**

# § 214 Package dingbat

(*Emulates or patches code by* Scott Pakin.)

Pkg dingbat dingbat is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{dingbat}[2001/04/27]

\newcommand*{\LWR@dingbatsymbol}[1]{\HTMLunicode{#1}}

```

```
\newcommand{\LWR@HTML@rightpointright}{\LWR@dingbatsymbol{261E}}
\newcommand{\LWR@HTML@leftpointright}{\LWR@dingbatsymbol{261E}}
\newcommand{\LWR@HTML@leftthumbsdown}{\LWR@dingbatsymbol{1F44E}}
\newcommand{\LWR@HTML@leftthumbsup}{\LWR@dingbatsymbol{1F44D}}
\newcommand{\LWR@HTML@rightpointleft}{\LWR@dingbatsymbol{261C}}
\newcommand{\LWR@HTML@rightthumbsdown}{\LWR@dingbatsymbol{1F44E}}
\newcommand{\LWR@HTML@rightthumbsup}{\LWR@dingbatsymbol{1F44D}}
\newcommand{\LWR@HTML@squarewithdots}{\LWR@dingbatsymbol{25C7}}
\newcommand{\LWR@HTML@filledsquarewithdots}{\LWR@dingbatsymbol{25C6}}
\newcommand{\LWR@HTML@Sborder}{\LWR@dingbatsymbol{271A}}
\newcommand{\LWR@HTML@Zborder}{\LWR@dingbatsymbol{274B}}
\newcommand{\LWR@HTML@largepencil}{\LWR@dingbatsymbol{270E}}
\newcommand{\LWR@HTML@anchor}{\LWR@dingbatsymbol{2693}}
\newcommand{\LWR@HTML@carriagereturn}{\LWR@dingbatsymbol{23CE}}
\newcommand{\LWR@HTML@checkmark}{\LWR@dingbatsymbol{2713}}
\newcommand{\LWR@HTML@eye}{\LWR@dingbatsymbol{1F441}}
\newcommand{\LWR@HTML@satellitedish}{\LWR@dingbatsymbol{1F4E1}}
\newcommand{\LWR@HTML@smallpencil}{\LWR@dingbatsymbol{270E}}

\LWR@formatted{rightpointright}
\LWR@formatted{leftpointright}
\LWR@formatted{leftthumbsdown}
\LWR@formatted{leftthumbsup}
\LWR@formatted{rightpointleft}
\LWR@formatted{rightthumbsdown}
\LWR@formatted{rightthumbsup}
\LWR@formatted{squarewithdots}
\LWR@formatted{filledsquarewithdots}
\LWR@formatted{Sborder}
\LWR@formatted{Zborder}
\LWR@formatted{largepencil}
\LWR@formatted{anchor}
\LWR@formatted{carriagereturn}
\LWR@formatted{checkmark}
\LWR@formatted{eye}
\LWR@formatted{satellitedish}
\LWR@formatted{smallpencil}
```

File 108 **lwarp-DotArrow.sty**

§ 215 Package

# DotArrow

(*Emulates or patches code by* Sven Schneider.)

Pkg DotArrow DotArrow is patched for use by lwarp, and emulated for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{DotArrow}[2007/02/12]
```

The width must be recomputed each time, depending on print or HTML output.

```
\xpretocmd{\dotarrow}{\settowidth{\oneWidth}{\onePartX}}{}{}

\begin{warpMathJax}
```

```
\CustomizeMathJax{\newcommand{\dotarrow}[1]{\stackrel{#1}{\unicode{x21E2}}}}
\end{warpMathJax}
```

---

File 109 **lwarp-dotlessi.sty**

## § 216 Package dotlessi

(*Emulates or patches code by* Javier Bezos.)

Pkg dotlessi dotlessi is used as-is for SVG math, and is emulated for MathJax.

⚠ HTML \dotlessj Use \usepackage{cmap} if \dotlessj does not appear in HTML in text mode. See section 7.4.

⚠ not bold For MathJax, use \boldsymbol instead of \mathbf.

**for HTML output:**

```
\LWR@ProvidesPackagePass{dotlessi}[1999/10/12]
```

For MathJax:

```
\begin{warpMathJax}
\CustomizeMathJax{\let\dotlessi\imath}
\CustomizeMathJax{\let\dotlessj\jmath}
\end{warpMathJax}
```

---

File 110 **lwarp-dprogress.sty**

## § 217 Package dprogress

Pkg dprogress dprogress is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{dprogress}[2008/02/21]
```

---

File 111 **lwarp-draftcopy.sty**

## § 218 Package draftcopy

Pkg draftcopy draftcopy is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{draftcopy}[2002/02/25]
```

```
\newcommand{\draftcopyVersion}[1]{}
\newcommand{\draftcopySetGrey}[1]{}
\newcommand{\draftcopySetScale}[1]{}
\newcommand{\draftcopySetScaleFactor}[1]{}
\newcommand{\draftcopyFirstPage}[1]{}
\newcommand{\draftcopyLastPage}[1]{}
\newcommand{\draftcopyName}[2]{}
```

```
\newcommand{\draftcopyPageTransform}[1]{}
\newcommand{\draftcopyBottomTransform}[1]{}
\newcommand{\draftcopyPageX}[1]{}
\newcommand{\draftcopyPageY}[1]{}
\newcommand{\draftcopyBottomX}[1]{}
\newcommand{\draftcopyBottomY}[1]{}
```

File 112 **lwarp-draftfigure.sty**

## § 219 Package draftfigure

Pkg draftfigure draftfigure is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{draftfigure}[2017/07/19]
\RequirePackage{xkeyval}

\define@key{draftfigure}{code}{}
\define@key{draftfigure}{noframe}[true]{}
\define@key{draftfigure}{filename}[true]{}
\define@key{draftfigure}{content}[]{}
\define@key{draftfigure}{style}[normal]{}
\define@key{draftfigure}{position}[left]{}
\define@key{draftfigure}{size}[normal]{}
\newcommand\setdf[1]{\setkeys{draftfigure}{#1}}
```

File 113 **lwarp-draftwatermark.sty**

## § 220 Package draftwatermark

(*Emulates or patches code by* Sergio Callegari.)

Pkg draftwatermark draftwatermark is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{draftwatermark}[2020/03/14]

\newcommand{\DraftwatermarkOptions}[1]{}
\newcommand{\DraftwatermarkStdMark}{}
\newcommand{\SetWatermarkAngle}[1]{}
\newcommand{\SetWatermarkColor}[1]{}
\newcommand{\SetWatermarkLightness}[1]{}
\newcommand{\SetWatermarkFontSize}[1]{}
\newcommand{\SetWatermarkScale}[1]{}
\newcommand{\SetWatermarkHorCenter}[1]{}
\newcommand{\SetWatermarkVertCenter}[1]{}
\newcommand{\SetWatermarkText}[1]{}
```

File 114 **lwarp-drftcite.sty**

## § 221 Package drftcite

(*Emulates or patches code by* Donald Arseneau.)

Pkg drftcite drftcite is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{drftcite}[1995/01/23]

\def\@lbibitem[#1]#2{\global\@HighCite\z@
  \item[
    \textsuperscript{\@nameuse{DCN@#2\@extra@b@citeb}}~%     lwarp
    \@biblabel{\@ifundefined{DCN@#2\@extra@b@citeb}{\@warning
    {Reference `#2' on page \thepage\space was never cited}}{}%
%    \DC@llap{$^{\@nameuse{DCN@#2\@extra@b@citeb}}$\ \ }%%o
   \@citeverb{#2}}\hfil]\if@filesw{\def\protect##1{\string ##1\space}%
   \immediate\write\@auxout{\string\bibcite{#2}{#1}}}\fi\ignorespaces}
```

---

File 115 **lwarp-easy-todo.sty**

## § 222 Package easy-todo

(*Emulates or patches code by* Juan Rada-Vilela.)

Pkg easy-todo easy-todo is patched for use by lwarp.

To remove the "P." heading for HTML:

```
\warpHTMLonly{\renewcommand{\todoindexpagetitle}{}}
```

**for HTML output:**

```
\LWR@ProvidesPackagePass{easy-todo}[2014/01/01]
```

\listoftodos Modified to correct buggy use of \flushright.

```
\let\LWR@easytodo@origlistoftodos\listoftodos

\renewcommand{\listoftodos}{%
\begingroup
\renewcommand{\flushright}{}
\LWR@easytodo@origlistoftodos
\endgroup
}
```

\todoii Modified to use \textcolor instead of \color.

```
\renewcommand{\todoii}[2]{%
\ifthenelse{\equal{\@todoobeyfinal}{true}}%
    {%
        \ifoptionfinal{\todoenable{false}}{\todoenable{true}}%
    }%
    {}%
\ifthenelse{\equal{\@todoenable}{true}}%
```

```
    {%
        \refstepcounter{todos}%
        \noindent{%
            \todocolor%
            \LWR@textcurrentcolor{%
                \normalfont\scriptsize{\bfseries{\thetodos.#1}}%
            }%
        }%
        \addcontentsline{lod}{todos}{\protect{\thetodos. }\LWR@isolate{#2}}%
    }%
    {}%
}
```

File 116 **lwarp-ebook.sty**

## § 223 Package ebook

(*Emulates or patches code by* Jørgen Steensgaard.)

Pkg ebook ebook is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{ebook}

\setcounter{secnumdepth}{0}
\setcounter{tocdepth}{2}

\providecommand{\pagefill}[1][0.001mm]{\noindent}

\providecommand{\ebook}{
\setcounter{secnumdepth}{0}
\setcounter{tocdepth}{2}
}
```

File 117 **lwarp-econometrics.sty**

## § 224 Package econometrics

(*Emulates or patches code by* Erik Kole.)

Pkg econometrics econometrics is used as-is for SVG math, and is emulated for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{econometrics}% no date specified in the original

\LWR@origRequirePackage{lwarp-common-mathjax-letters}

\begin{warpMathJax}
\LWR@infoprocessingmathjax{econometrics}

\CustomizeMathJax{\newcommand{\SC}{\mathbb{C}}}
\CustomizeMathJax{\newcommand{\SN}{\mathbb{N}}}
\CustomizeMathJax{\newcommand{\SQ}{\mathbb{Q}}}
```

```
\CustomizeMathJax{\newcommand{\SR}{\mathbb{R}}}
\CustomizeMathJax{\newcommand{\SZ}{\mathbb{Z}}}

\CustomizeMathJax{\newcommand{\calA}{\mathcal{A}}}
\CustomizeMathJax{\newcommand{\calB}{\mathcal{B}}}
\CustomizeMathJax{\newcommand{\calC}{\mathcal{C}}}
\CustomizeMathJax{\newcommand{\calD}{\mathcal{D}}}
\CustomizeMathJax{\newcommand{\calE}{\mathcal{E}}}
\CustomizeMathJax{\newcommand{\calF}{\mathcal{F}}}
\CustomizeMathJax{\newcommand{\calG}{\mathcal{G}}}
\CustomizeMathJax{\newcommand{\calH}{\mathcal{H}}}
\CustomizeMathJax{\newcommand{\calI}{\mathcal{I}}}
\CustomizeMathJax{\newcommand{\calJ}{\mathcal{J}}}
\CustomizeMathJax{\newcommand{\calK}{\mathcal{K}}}
\CustomizeMathJax{\newcommand{\calL}{\mathcal{L}}}
\CustomizeMathJax{\newcommand{\calM}{\mathcal{M}}}
\CustomizeMathJax{\newcommand{\calN}{\mathcal{N}}}
\CustomizeMathJax{\newcommand{\calO}{\mathcal{O}}}
\CustomizeMathJax{\newcommand{\calP}{\mathcal{P}}}
\CustomizeMathJax{\newcommand{\calQ}{\mathcal{Q}}}
\CustomizeMathJax{\newcommand{\calR}{\mathcal{R}}}
\CustomizeMathJax{\newcommand{\calS}{\mathcal{S}}}
\CustomizeMathJax{\newcommand{\calT}{\mathcal{T}}}
\CustomizeMathJax{\newcommand{\calU}{\mathcal{U}}}
\CustomizeMathJax{\newcommand{\calV}{\mathcal{V}}}
\CustomizeMathJax{\newcommand{\calW}{\mathcal{W}}}
\CustomizeMathJax{\newcommand{\calX}{\mathcal{X}}}
\CustomizeMathJax{\newcommand{\calY}{\mathcal{Y}}}
\CustomizeMathJax{\newcommand{\calZ}{\mathcal{Z}}}

\LWR@mathjax@addlatin@u@bfit{m}% uppercase Latin, bold italic
\LWR@mathjax@addlatin@l@bfit{v}% lowercase Latin, bold italic

\LWR@mathjax@addgreek@l@bfit{v}{}% lowercase Greek bold italic
\LWR@mathjax@addgreek@u@bfit*{m}{}% uppercase Greek bold italic, capitalized macro names

\CustomizeMathJax{\newcommand{\rb}{\mathrm{b}}}
\CustomizeMathJax{\newcommand{\rB}{\mathrm{B}}}
\CustomizeMathJax{\newcommand{\rC}{\mathrm{C}}}
\CustomizeMathJax{\newcommand{\rD}{\mathrm{D}}}
\CustomizeMathJax{\newcommand{\rf}{\mathrm{f}}}
\CustomizeMathJax{\newcommand{\rF}{\mathrm{F}}}
\CustomizeMathJax{\newcommand{\rH}{\mathrm{H}}}
\CustomizeMathJax{\newcommand{\rL}{\mathrm{L}}}
\CustomizeMathJax{\newcommand{\rN}{\mathrm{N}}}
\CustomizeMathJax{\newcommand{\rt}{\mathrm{t}}}
\CustomizeMathJax{\newcommand{\rU}{\mathrm{U}}}
\CustomizeMathJax{\newcommand{\rGam}{\mathrm{Gam}}}
\CustomizeMathJax{\newcommand{\rBeta}{\mathrm{Beta}}}

\CustomizeMathJax{\newcommand{\Bin}{\mathrm{Bin}}}
\CustomizeMathJax{\newcommand{\eu}{\mathrm{e}}}
\CustomizeMathJax{\newcommand{\iu}{\mathrm{i}}}
\CustomizeMathJax{\newcommand{\LN}{\mathrm{LN}}}
\CustomizeMathJax{\newcommand{\IN}{\mathrm{IN}}}
```

```
65
66 \CustomizeMathJax{\newcommand{\Poi}{\mathrm{Poi}}}
67
68 \CustomizeMathJax{\newcommand{\ped}[1]{_\mathrm{#1}}}
69 \CustomizeMathJax{\newcommand{\ap}[1]{^\mathrm{#1}}}
70 \CustomizeMathJax{\renewcommand{\Re}{\mathrm{Re}}{\nolimits}}
71 \CustomizeMathJax{\renewcommand{\Im}{\mathrm{Im}}{\nolimits}}
72
73 \CustomizeMathJax{\newcommand{\deriv}[3][]{%
74     \frac{\mathrm{d}^{#1}#2}{\mathrm{d}\,#3^{#1}}%
75 }}
76 \CustomizeMathJax{\newcommand{\pderiv}[3][]{%
77     \frac{\partial^{#1}#2}{\partial #3^{#1}}%
78 }}
79
80 \CustomizeMathJax{\newcommand{\bias}{\operatorname{bias}}}
81 \CustomizeMathJax{\newcommand{\col}{\operatorname{col}}}
82 \CustomizeMathJax{\newcommand{\corr}{\operatorname{corr}}}
83 \CustomizeMathJax{\newcommand{\cov}{\operatorname{cov}}}
84 \CustomizeMathJax{\newcommand{\dg}{\operatorname{dg}}}
85 \CustomizeMathJax{\newcommand{\diag}{\operatorname{diag}}}
86 \CustomizeMathJax{\newcommand{\E}{\operatorname{E}}}
87 \CustomizeMathJax{\newcommand{\etr}{\operatorname{etr}}}
88 \CustomizeMathJax{\newcommand{\ip}{\mathrm{int}}{\nolimits}}
89 \CustomizeMathJax{\newcommand{\kur}{\operatorname{kur}}}
90 \CustomizeMathJax{\newcommand{\MSE}{\operatorname{MSE}}}
91 \CustomizeMathJax{\newcommand{\MSFE}{\operatorname{MSFE}}}
92 \CustomizeMathJax{\newcommand{\OLS}{\operatorname{OLS}}}
93 \CustomizeMathJax{\newcommand{\plim}{\operatorname{plim}}}
94 \CustomizeMathJax{\newcommand{\resid}{\operatorname{resid}}}
95 \CustomizeMathJax{\newcommand{\rk}{\operatorname{rk}}}
96 \CustomizeMathJax{\newcommand{\SE}{\operatorname{SE}}}
97 \CustomizeMathJax{\newcommand{\sgn}{\operatorname{sgn}}}
98 \CustomizeMathJax{\newcommand{\tr}{\operatorname{tr}}}
99 \CustomizeMathJax{\newcommand{\var}{\operatorname{var}}}
100 \CustomizeMathJax{\renewcommand{\vec}{\operatorname{vec}}}
101 \CustomizeMathJax{\newcommand{\vech}{\operatorname{vech}}}
102
103 \CustomizeMathJax{\newcommand{\distr}{\sim}}
104 \CustomizeMathJax{\newcommand{\adistr}{\stackrel{a}{\distr}}}
105 \CustomizeMathJax{\newcommand{\diff}{\Delta}}
106 \CustomizeMathJax{\newcommand{\fdiff}{\diff_{\rf}}}
107 \CustomizeMathJax{\newcommand{\bdiff}{\diff_{\rb}}}
108
109 \CustomizeMathJax{\newcommand{\eps}{\epsilon}}
110 \CustomizeMathJax{\newcommand{\epsi}{\varepsilon}}
111
112 \CustomizeMathJax{\newcommand{\longto}{\longrightarrow}}
113 \CustomizeMathJax{\newcommand{\pto}{\stackrel{p}{\longrightarrow}}}
114 \CustomizeMathJax{\newcommand{\dto}{\stackrel{d}{\longrightarrow}}}
115 \CustomizeMathJax{\newcommand{\wto}{\stackrel{w}{\longrightarrow}}}
116
117 \CustomizeMathJax{\newcommand{\Infmat}{\bm\calI}}
118 \CustomizeMathJax{\newcommand{\Hesmat}{\bm\calH}}
119 \CustomizeMathJax{\newcommand{\bcdot}{\bullet}}
```

```
120
121 \CustomizeMathJax{\newcommand{\vones}{\bm\imath}}
122 \CustomizeMathJax{\newcommand{\vzeros}{\boldsymbol{0}}}
123 \CustomizeMathJax{\newcommand{\mZeros}{\mathbf{O}}}
124
125 \CustomizeMathJax{\newcommand{\e}{\eu}}
126 \CustomizeMathJax{\newcommand{\mply}{\cdot}}
127 \CustomizeMathJax{\newcommand{\rW}{\ensuremath{\mathrm{W}}}}
128 \end{warpMathJax}
```

File 118 **lwarp-ed.sty**

## § 225 Package ed

(*Emulates or patches code by* Michael Kohlhase.)

Pkg ed ed is patched for use by lwarp.

**for HTML output:**

```
1 \LWR@ProvidesPackagePass{ed}[2012/01/29]
```

Bugs:

1. todolist fails with the hide option, as does \edexplanation.
2. \edstubURI is actually \edstuURI.

```
2 \RequirePackage{xcolor}
3
4 \renewenvironment{edstub}[2][The following blue text]
5 {%
6     \def\@test{#1}%
7     \begin{center}%
8         \huge%
9         \textcolor{red}{%
10            #1 is only a provisional stub\\\Large
11            the Office document
12            \ifx\ed@stubURI\@empty{#2}\else\LWR@href{\ed@stubURI}{#2}\fi\
13            contains more text\\which will be merged for the final document%
14        }%
15    \end{center}%
16    \BlockClass[color:blue]{edstub}%
17 }
18 {\endBlockClass}
```

File 119 **lwarp-ellipsis.sty**

## § 226 Package ellipsis

(*Emulates or patches code by* Peter J. Heslin.)

Pkg ellipsis ellipsis is emulated.

```
\LWR@ProvidesPackageDrop{ellipsis}[2004/09/28]

\newcommand{\ellipsisgap}{0.1em}

\newcommand*{\midwordellipsis}{\,\textellipsis\,}
```

---

File 120 **lwarp-embrac.sty**

# § 227 Package embrac

(*Emulates or patches code by* Clemens Niederberger.)

Pkg embrac embrac is patched for HTML and used as-is for print.

**for HTML output:**

```
\LWR@ProvidesPackagePass{embrac}[2017/07/04]

\ExplSyntaxOn
\RenewDocumentCommand{\embrac_kern:n}{m}{}
\ExplSyntaxOff

\LetLtxMacro\LWR@orig@HTML@emph\LWR@HTML@emph
\RenewDocumentCommand{\LWR@HTML@emph}{s m}{\LWR@orig@HTML@emph{#2}}

\LetLtxMacro\LWR@orig@HTML@textit\LWR@HTML@textit
\RenewDocumentCommand{\LWR@HTML@textit}{s m}{\LWR@orig@HTML@textit{#2}}

\LetLtxMacro\LWR@orig@HTML@textsl\LWR@HTML@textsl
\RenewDocumentCommand{\LWR@HTML@textsl}{s m}{\LWR@orig@HTML@textsl{#2}}

\ifxetexorluatex
    \LetLtxMacro\LWR@orig@HTML@textsi\LWR@HTML@textsi
    \RenewDocumentCommand{\LWR@HTML@textsi}{s m}{%
    \LWR@orig@HTML@textsi{#2}}
\fi

\AtBeginDocument{
    \LWR@formatted{emph}
    \LWR@formatted{textit}
    \LWR@formatted{textsl}
    \ifxetexorluatex
        \LWR@formatted{textsi}
    \fi
}

\newcommand{\LWR@HTML@EmbracOff}{}
\LWR@formatted{EmbracOff}

\newcommand{\LWR@HTML@EmbracOn}{}
\LWR@formatted{EmbracOn}
```

File 121 **lwarp-emptypage.sty**

# § 228 Package emptypage

Pkg emptypage emptypage is ignored.

**for HTML output:** Discard all options for lwarp-emptypage:

```
\LWR@ProvidesPackageDrop{emptypage}[2010/05/30]
```

File 122 **lwarp-endfloat.sty**

# § 229 Package endfloat

Pkg endfloat endfloat is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{endfloat}[2019/04/15]

\newcommand\figureplace{}
\newcommand\tableplace{}
\newcommand\floatplace[1]{}
\newcounter{posttable}
\newcounter{postfigure}
\newcommand*{\theposttbl}{}
\newcommand*{\thepostfig}{}
\newcommand{\AtBeginFigures}[1]{}
\newcommand{\AtBeginTables}[1]{}
\newcommand{\AtBeginDelayedFloats}[1]{}
\newcommand*{\processdelayedfloats}{}
\newcommand*{\efloatseparator}{}
\def\efloattype{}
\providecommand\efloatheading[1]{}
\providecommand\efloatpreamble{}
\providecommand\efloatpostamble{}
\NewDocumentCommand{\addtodelayedfloat}{s m m}{}
\providecommand{\efloatbegin}{}
\providecommand{\efloatend}{}
\providecommand{\efloatbeginlist}{}
\providecommand{\efloatendlist}{}
```

File 123 **lwarp-endheads.sty**

# § 230 Package endheads

Pkg endheads endheads is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{endheads}[2017/04/06]
```

```
\newcommand{\changesinglepageabbrev}[1]{}
\newcommand{\changemultiplepageabbrev}[1]{}
\newcommand{\changenotesname}[1]{}
\newcommand{\changenotesheader}[1]{}
\newcommand{\changenotescontentsname}[1]{}
\newcommand{\changechapternotesline}[1]{}
\newcommand{\checknoteheaders}{}
\newif\ifnotesincontentson \notesincontentsonfalse
\newcommand{\notesincontents}{\notesincontentsontrue}
\newif\ifendnoteheaderson \endnoteheadersonfalse
\newcommand{\setupendnoteheaders}{%
    \endnoteheadersontrue%
}
\newif\iftitleinnotes \titleinnotestrue
\newcommand{\styleforchapternotebegin}{}
\newcommand{\styleforchapternoteend}{}
\newcommand{\setstyleforchapternotebegin}[1]{%
    \renewcommand{\styleforchapternotebegin}{#1}%
}
\newcommand{\setstyleforchapternoteend}[1]{%
    \renewcommand{\styleforchapternoteend}{#1}%
}
\newcommand{\resetendnotes}{}
\newif\ifnotesbychapteron \notesbychapteronfalse
\newcommand{\notesbychapter}{\notesbychapterontrue}
```

---

File 124 **lwarp-endnotes.sty**

§ 231 Package

# endnotes

(*Emulates or patches code by* John Lavagnino.)

Pkg endnotes Patched for HTML.

table of contents To place the endnotes in the TOC, use:

```
\usepackage{endnotes}
\appto\enoteheading{\addcontentsline{toc}{section}{\notesname}}
\renewcommand*{\notesname}{Endnotes} % optional
```

HTML page To additionally have the endnotes on their own HTML page, if `FileDepth` allows:

```
\ForceHTMLPage
\theendnotes
```

⚠ `\endnotemark` numbering If using MathJax, see section 8.5.4 regarding the use of `\endnotemark` and `\endnotetext`.

**for HTML output:**

```
\LWR@ProvidesPackagePass{endnotes}
```

```
\def\enoteformat{%
% \rightskip\z@ \leftskip\z@ \parindent=1.8em
\leavevmode
% \llap{
```

```
\CustomizeMathJax{\newcommand{\us}{\unit{\micro s}}}
\CustomizeMathJax{\newcommand{\ns}{\unit{ns}}}
\CustomizeMathJax{\newcommand{\ps}{\unit{ps}}}
%
\CustomizeMathJax{\newcommand{\um}{\unit{\micro m}}}
\CustomizeMathJax{\newcommand{\mm}{\unit{mm}}}
\CustomizeMathJax{\newcommand{\cm}{\unit{cm}}}
\CustomizeMathJax{\newcommand{\dm}{\unit{dm}}}
\CustomizeMathJax{\newcommand{\m}{\unit{m}}}
\CustomizeMathJax{\newcommand{\km}{\unit{km}}}
%
\CustomizeMathJax{\newcommand{\MA}{\unit{MA}}}
\CustomizeMathJax{\newcommand{\kA}{\unit{kA}}}
\CustomizeMathJax{\newcommand{\A}{\unit{A}}}
\CustomizeMathJax{\newcommand{\mA}{\unit{mA}}}
\CustomizeMathJax{\newcommand{\uA}{\unit{\micro A}}}
\CustomizeMathJax{\newcommand{\nA}{\unit{nA}}}
%
\CustomizeMathJax{\newcommand{\MV}{\unit{MV}}}
\CustomizeMathJax{\newcommand{\kV}{\unit{kV }}}
\CustomizeMathJax{\newcommand{\V}{\unit{V}}}
\CustomizeMathJax{\newcommand{\mV}{\unit{mV}}}
\CustomizeMathJax{\newcommand{\uV}{\unit{\micro V}}}
%
\CustomizeMathJax{\newcommand{\mohm}{\unit{m\Omega}}}
\CustomizeMathJax{\newcommand{\ohm}{\unit{\Omega}}}
\CustomizeMathJax{\newcommand{\kohm}{\unit{k\Omega}}}
\CustomizeMathJax{\newcommand{\Mohm}{\unit{M\Omega}}}
%
\CustomizeMathJax{\newcommand{\pSi}{\unit{pS}}}
\CustomizeMathJax{\newcommand{\nSi}{\unit{nS}}}
\CustomizeMathJax{\newcommand{\uSi}{\unit{\micro S}}}
\CustomizeMathJax{\newcommand{\mSi}{\unit{mS}}}
\CustomizeMathJax{\newcommand{\Si}{\unit{S}}}
\CustomizeMathJax{\newcommand{\kSi}{\unit{kS}}}
\CustomizeMathJax{\newcommand{\MSi}{\unit{MS}}}
%
\CustomizeMathJax{\newcommand{\fFa}{\unit{fF}}}
\CustomizeMathJax{\newcommand{\pFa}{\unit{pF}}}
\CustomizeMathJax{\newcommand{\nFa}{\unit{nF}}}
\CustomizeMathJax{\newcommand{\uFa}{\unit{\micro F}}}
\CustomizeMathJax{\newcommand{\mFa}{\unit{mF}}}
\CustomizeMathJax{\newcommand{\Fa}{\unit{F}}}
%
\CustomizeMathJax{\newcommand{\fHe}{\unit{fH}}}
\CustomizeMathJax{\newcommand{\pHe}{\unit{pH}}}
\CustomizeMathJax{\newcommand{\nHe}{\unit{nH}}}
\CustomizeMathJax{\newcommand{\uHe}{\unit{\micro H}}}
\CustomizeMathJax{\newcommand{\mHe}{\unit{mH}}}
\CustomizeMathJax{\newcommand{\He}{\unit{H}}}
%
\CustomizeMathJax{\newcommand{\dB}{\unit{dB}}}
\CustomizeMathJax{\newcommand{\dBm}{\unit{dBm}}}
%
\CustomizeMathJax{\newcommand{\uW}{\unit{\micro W}}}
```

```
\CustomizeMathJax{\newcommand{\mW}{\unit{mW}}}
\CustomizeMathJax{\newcommand{\W}{\unit{W}}}
\CustomizeMathJax{\newcommand{\kW}{\unit{kW}}}
\CustomizeMathJax{\newcommand{\MW}{\unit{MW}}}
%
\CustomizeMathJax{\newcommand{\Hz}{\unit{Hz}}}
\CustomizeMathJax{\newcommand{\kHz}{\unit{kHz}}}
\CustomizeMathJax{\newcommand{\MHz}{\unit{MHz}}}
\CustomizeMathJax{\newcommand{\GHz}{\unit{GHz}}}
\CustomizeMathJax{\newcommand{\THz}{\unit{THz}}}
%
\CustomizeMathJax{\newcommand{\bit}{\unit{bit}}}
\CustomizeMathJax{\newcommand{\kbit}{\unit{Kib}}}
\CustomizeMathJax{\newcommand{\Mbit}{\unit{Mib}}}
\CustomizeMathJax{\newcommand{\Byte}{\unit{B}}}
\CustomizeMathJax{\newcommand{\kByte}{\unit{KiB}}}
\CustomizeMathJax{\newcommand{\MByte}{\unit{Mib}}}
\CustomizeMathJax{\newcommand{\GByte}{\unit{GiB}}}
\CustomizeMathJax{\newcommand{\TByte}{\unit{TiB}}}
\CustomizeMathJax{\newcommand{\bits}{\unit{bit/s}}}
\CustomizeMathJax{\newcommand{\kbits}{\unit{Kib/s}}}
\CustomizeMathJax{\newcommand{\Mbits}{\unit{Mib/s}}}
\CustomizeMathJax{\newcommand{\Bytes}{\unit{B/s}}}
\CustomizeMathJax{\newcommand{\kBytes}{\unit{KiB/s}}}
\CustomizeMathJax{\newcommand{\MBytes}{\unit{MiB/s}}}
\CustomizeMathJax{\newcommand{\GBytes}{\unit{GiB/s}}}
\CustomizeMathJax{\newcommand{\TBytes}{\unit{TiB/s}}}
\CustomizeMathJax{\newcommand{\chips}{\unit{chip/s}}}
\CustomizeMathJax{\newcommand{\kchips}{\unit{Ki\mkern2mu chip/s}}}
\CustomizeMathJax{\newcommand{\Mchips}{\unit{Mi\mkern2mu chip/s}}}
\CustomizeMathJax{\newcommand{\chipsubit}{\unit{chip/bit}}}
%
\CustomizeMathJax{\newcommand{\frecciadex}[1][0.5]{%
    \hspace{.25cm}\Longrightarrow \hspace{.25cm}}%
}
\CustomizeMathJax{\newcommand{\varianzarumore}{\frac{N_0}{2}}}
%
\CustomizeMathJax{\newcommand{\etsymbolbracearg}[2]{%
    #1\mathopen{}\left\lbrace#2\right\rbrace\mathclose{}}%
}
\CustomizeMathJax{\newcommand{\fourier}[1]{\etsymbolbracearg{\mathcal{F}}{#1}}}
\CustomizeMathJax{\newcommand{\invfourier}[1]{\etsymbolbracearg{\mathcal{F}^{-1}}{#1}}}
\CustomizeMathJax{\newcommand{\partereale}[1]{\etsymbolbracearg{\textbf{Re}}{#1}}}
\CustomizeMathJax{\newcommand{\parteimm}[1]{\etsymbolbracearg{\textbf{Im}}{#1}}}
\CustomizeMathJax{\newcommand{\Info}[1]{I\left(#1\right)}}
\CustomizeMathJax{\newcommand{\versore}[1]{\hat{#1}}}
\CustomizeMathJax{\newcommand{\vettore}[1]{\overrightarrow{#1}}}
\CustomizeMathJax{\newcommand{\coseno}[1]{\cos\left(2\pi#1t\right)}}
\CustomizeMathJax{\newcommand{\seno}[1]{\sin\left(2\pi#1t\right)}}
\CustomizeMathJax{\newcommand{\energia}[1]{\mathcal{E}_{#1}}}
\CustomizeMathJax{\newcommand{\moduloexp}[2]{\left\vert#1\right\vert^{#2}}}
\CustomizeMathJax{\newcommand{\modulo}[1]{\left\vert#1\right\vert}}
\CustomizeMathJax{\newcommand{\indB}[1]{%
    \mathopen{}\left.#1\right\vert_{\mathrm{dB}}\mathclose{}}}%
\CustomizeMathJax{\newcommand{\for}[2]{\left. #1 \right\vert_{#2}}}
```

```
\CustomizeMathJax{\newcommand{\massimo}[1]{\etsymbolbracearg{\max}{#1}}}
\CustomizeMathJax{\newcommand{\minimo}[1]{\etsymbolbracearg{\min}{#1}}}
\CustomizeMathJax{\newcommand{\valc}{3\cdot 10^8}}
\CustomizeMathJax{\newcommand{\loga}[2]{\log_{#1}#2}}
\CustomizeMathJax{\newcommand{\analitic}[1]{\mathring{#1}}}
\CustomizeMathJax{\newcommand{\diff}{\mathop{}\mathopen{\mathrm{d}}}}
\CustomizeMathJax{\newcommand{\intinf}[1]{\int_{-\infty}^{+\infty}{#1}}}
\CustomizeMathJax{\newcommand{\deltain}[1]{\delta\left(#1\right)}}
\CustomizeMathJax{\newcommand{\iu}{\mathrm{j}}}
\CustomizeMathJax{\newcommand{\ex}[1]{\mathrm{e}^{#1}}}
%
\CustomizeMathJax{\newcommand{\gammatens}{{}^{\mathrm{V}}\Gamma}}
\CustomizeMathJax{\newcommand{\gammacorr}{{}^{\mathrm{I}}\Gamma}}
\CustomizeMathJax{\newcommand{\gammatensin}[1]{{}^{\mathrm{V}}\Gamma_{\mathrm{#1}}}}
\CustomizeMathJax{\newcommand{\gammacorrin}[1]{{}^{\mathrm{I}}\Gamma_{\mathrm{#1}}}}
\CustomizeMathJax{\newcommand{\gammain}[1]{\Gamma_{\mathrm{#1}}}}
\CustomizeMathJax{\newcommand{\gammak}{{}^{\mathrm{k}}\Gamma}}
%
\CustomizeMathJax{\newcommand{\lbvt}{\lambda_0}}
\CustomizeMathJax{\newcommand{\lbg}{\lambda_g}}
\CustomizeMathJax{\newcommand{\lbgvt}{\lambda_{g_0}}}
%
\CustomizeMathJax{\newcommand{\potin}[1]{P_{\mathrm{#1}}}}
\CustomizeMathJax{\newcommand{\potdisp}[1][]{P_{\mathrm{disp}}^{#1}}}
\CustomizeMathJax{\newcommand{\potDC}[1][]{P_{\mathrm{DC}}^{#1}}}
\CustomizeMathJax{\newcommand{\potCC}[1][]{P_{\mathrm{CC}}^{#1}}}
\CustomizeMathJax{\newcommand{\potirr}[1][]{P_{\mathrm{irr}}^{#1}}}
\CustomizeMathJax{\newcommand{\potdiss}[1][]{P_{\mathrm{diss}}^{#1}}}
\CustomizeMathJax{\newcommand{\potinc}[1][]{P_{\mathrm{inc}}^{#1}}}
%
\CustomizeMathJax{\newcommand{\z}[1]{Z_{\mathrm{#1}}}}
\CustomizeMathJax{\newcommand{\znorm}[1]{z_{\mathrm{#1}}}}
\CustomizeMathJax{\newcommand{\y}[1]{Y_{\mathrm{#1}}}}
\CustomizeMathJax{\newcommand{\ynorm}[1]{y_{\mathrm{#1}}}}
\CustomizeMathJax{\newcommand{\zinf}[1][]{Z_{\infty#1}}}
\CustomizeMathJax{\newcommand{\zinfn}[1]{\zinf[#1]}}
\CustomizeMathJax{\newcommand{\yinf}[1][]{Y_{\infty#1}}}
\CustomizeMathJax{\newcommand{\yinfn}[1]{\yinf[#1]}}
\CustomizeMathJax{\newcommand{\zvt}{Z_0}}
\CustomizeMathJax{\newcommand{\yvt}{Y_0}}
%
\CustomizeMathJax{\newcommand{\campoe}{\underline{\mathcal{E}}(\underline{r},t)}}
\CustomizeMathJax{\newcommand{\campoefas}{\underline{E}(\underline{r})}}
\CustomizeMathJax{\newcommand{\campoh}{\underline{\mathcal{H}}(\underline{r},t)}}
\CustomizeMathJax{\newcommand{\campohfas}{\underline{H}(\underline{r})}}
%
\CustomizeMathJax{\newcommand{\signt}[1]{{#1}(t)}}
\CustomizeMathJax{\newcommand{\signf}[1]{{#1}(f)}}
\CustomizeMathJax{\newcommand{\signn}[1]{{#1}(n)}}
\CustomizeMathJax{\newcommand{\signz}[1]{{#1}(z)}}
%
\CustomizeMathJax{\newcommand{\prob}[1]{\mathcal{P}\left(#1\right)}}
\CustomizeMathJax{\newcommand{\valatt}[1]{\mathbb{E}\left[#1\right]}}
\CustomizeMathJax{\newcommand{\var}[1]{\mathrm{Var}\left[#1\right]}}
\CustomizeMathJax{\newcommand{\comma}{\, , \,}}
```

```
\CustomizeMathJax{\newcommand{\dato}{\,|\,}}
%
\CustomizeMathJax{\let\bfRe\partereale}
\CustomizeMathJax{\let\bfIm\parteimm}
\CustomizeMathJax{\let\noisevar\varianzarumore}
% \CustomizeMathJax{\let\exerend\finees}
\CustomizeMathJax{\let\Spimplies\frecciadex}
\CustomizeMathJax{\let\Downimplies\frecciadown}
\CustomizeMathJax{\let\unitvec\versore}
\CustomizeMathJax{\let\vector\vettore}
\CustomizeMathJax{\let\cosine\coseno}
\CustomizeMathJax{\let\sine\seno}
\CustomizeMathJax{\let\energy\energia}
\CustomizeMathJax{\let\Abs\modulo}
\CustomizeMathJax{\let\AbsPow\moduloexp}
\CustomizeMathJax{\let\Max\massimo}
\CustomizeMathJax{\let\Min\minimo}
\CustomizeMathJax{\let\clight\valc}
\CustomizeMathJax{\let\Log\loga}
\CustomizeMathJax{\let\analytic\analitic}
\CustomizeMathJax{\let\infint\intinf}
\CustomizeMathJax{\let\deltaimp\deltain}
\CustomizeMathJax{\let\Vgamma\gammatens}
\CustomizeMathJax{\let\Cgamma\gammacorr}
\CustomizeMathJax{\let\Vgammain\gammatensin}
\CustomizeMathJax{\let\Cgammain\gammacorrin}
\CustomizeMathJax{\let\Kgamma\gammak}
\CustomizeMathJax{\let\powerin\potin}
\CustomizeMathJax{\let\availpow\potdisp}
\CustomizeMathJax{\let\irrpow\potirr}
\CustomizeMathJax{\let\disspow\potdiss}
\CustomizeMathJax{\let\incpow\potinc}
\CustomizeMathJax{\let\potalim\potCC}
\CustomizeMathJax{\let\potDC\potCC}
\CustomizeMathJax{\let\Efield\campoe}
\CustomizeMathJax{\let\Hfield\campoh}
\CustomizeMathJax{\let\phasorEfield\campoefas}
\CustomizeMathJax{\let\phasorHfiled\campohfas}
\CustomizeMathJax{\let\given\dato}
\CustomizeMathJax{\let\expval\valatt}
\CustomizeMathJax{\let\rmexp\ex}
\end{warpMathJax}
```

File 126 **lwarp-enumerate.sty**

§ 233 Package

# enumerate

Pkg enumerate enumerate is supported with no changes.

This package is only required because it was used in the past to drop and then emulate the package. It cannot be removed because an older version which dropped the package may still remain, for example in a local vs. distribution directory, but it is now supported directly by lwarp and thus must no longer be dropped.

**for HTML output:**
```
\LWR@ProvidesPackagePass{enumerate}[2015/07/23]
```

File 127 **lwarp-enumitem.sty**

## § 234 Package enumitem

(*Emulates or patches code by* Javier Bezos.)

Pkg enumitem enumitem is supported with minor adjustments.

**for HTML output:**
```
\LWR@ProvidesPackagePass{enumitem}[2018/11/30]
```

\newlist {⟨*name*⟩} {⟨*type*⟩} {⟨*maxdepth*⟩}
\renewlist {⟨*name*⟩} {⟨*type*⟩} {⟨*maxdepth*⟩}

For enumitem lists, new lists must have the start and end actions assigned to the new environment. Renewed lists already have their actions assigned, and thus need no changes.

```
\let\LWR@enumitem@orignewlist\newlist

\renewcommand*{\newlist}[3]{%
\LWR@enumitem@orignewlist{#1}{#2}{#3}%
\AtBeginEnvironment{#1}{\@nameuse{LWR@#2start}}%
\AtEndEnvironment{#1}{\@nameuse{LWR@#2end}}%
}

\def\DrawEnumitemLabel{}
```

File 128 **lwarp-epigraph.sty**

## § 235 Package epigraph

(*Emulates or patches code by* Peter Wilson.)

Pkg epigraph epigraph is emulated for HTML, and used as-is for print output.

Use CSS to format epigraphs.

**for HTML output:**
```
\LWR@ProvidesPackagePass{epigraph}[2020/01/02]
```

```
\DeclareDocumentCommand{\LWR@HTML@qitem}{m m}
{%
    \begin{BlockClass}{qitem}%
    #1%
    \LWR@stoppars%
    \ifbool{FormatWP}%
        {\begin{BlockClass}[border-top:1px solid gray]{epigraphsource}}%
        {\begin{BlockClass}{epigraphsource}}%
    #2%
    \end{BlockClass}%
```

```
    \end{BlockClass}%
}
\LWR@formatted{qitem}

\DeclareDocumentCommand{\LWR@HTML@epigraph}{m m}
{%
    \begin{LWR@BlockClassWP}{\LWR@print@mbox{text-align:right}}{}{epigraph}%
    \qitem{#1}{#2}%
    \end{LWR@BlockClassWP}%
}
\LWR@formatted{epigraph}

\DeclareDocumentEnvironment{LWR@HTML@epigraphs}{}
    {\LWR@BlockClassWP{\LWR@print@mbox{text-align:right}}{}{epigraph}}
    {\endLWR@BlockClassWP}
\LWR@formattedenv{epigraphs}
```

The following cannot be used in print mode while generating HTML:

```
\renewcommand{\epigraphhead}[2][0]{#2}
\renewcommand{\dropchapter}[1]{}
\renewcommand*{\undodrop}{}
```

---

File 129 **lwarp-epsf.sty**

§ 236 Package

# epsf

(*Emulates or patches code by* Tom Rokicki.)

Pkg epsf epsf is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{epsf}% not date given

\xpretocmd{\epsfsetgraph}
    {\begin{lateximage}}
    {}
    {\LWR@patcherror{lwarp-epsf}{epsfsetgraph-begin}}

\xapptocmd{\epsfsetgraph}
    {\end{lateximage}}
    {}
    {\LWR@patcherror{lwarp-epsf}{epsfsetgraph-end}}
```

---

File 130 **lwarp-epsfig.sty**

§ 237 Package

# epsfig

Pkg epsfig epsfig is emulated for use by lwarp.

⚠ Only the LaTeX2e syntax is emulated.

**for HTML output:**

```
\LWR@ProvidesPackagePass{epsfig}[2017/06/25]
```

A few additional keys to capture the filename:

```
\RequirePackage{graphics}

\define@key{igraph}{file}{%
    \xdef\LWR@epsfig@filename{#1}%
}

\define@key{igraph}{figure}{%
    \xdef\LWR@epsfig@filename{#1}%
}

\define@key{igraph}{prolog}{}

\define@key{igraph}{silent}[]{}
```

The captured filename is used as the argument to `\includegraphics`:

```
\newcommand{\LWR@HTML@epsfig}[1]{\includegraphics[#1]{\LWR@epsfig@filename}}
\LWR@formatted{epsfig}

\newcommand{\LWR@HTML@psfig}[1]{\includegraphics[#1]{\LWR@epsfig@filename}}
\LWR@formatted{psfig}
```

---

File 131 **lwarp-epstopdf.sty**

# § 238 Package epstopdf

Pkg epstopdf

Previous versions of lwarp had a nullfied version, but now epstopdf-base is supported. lwarp-epstopdf becomes a placeholder to overwrite previous versions.

See package epstopdf-base for details.

**for HTML output:**

```
\LWR@ProvidesPackagePass{epstopdf}[2020-01-24]
```

---

File 132 **lwarp-epstopdf-base.sty**

# § 239 Package epstopdf-base

Pkg epstopdf-base

⚠ convert to .svg

Images with an .eps extension will be converted to .pdf. The HTML output uses the .svg version, so use

Enter ⇒ **lwarpmk pdftosvg <listofPDFfiles>**

to generate .svg versions.

**for HTML output:**

```
\LWR@ProvidesPackagePass{epstopdf-base}[2020-01-24]
```

Redefine to remember the image filename, replacing `.pdf` with `.svg`. Use the epstopdf print version inside a `lateximage`.

```
\newcommand*{\LWR@HTML@ETE@OrgGin@setfile}[3]{%
    \edef\LWR@tempone{#3}%
    \StrSubstitute{\LWR@tempone}{.pdf}{.svg}[\LWR@tempone]%
    \StrSubstitute{\LWR@tempone}{.PDF}{.SVG}[\LWR@tempone]%
    \xdef\LWR@parsedfilename{\LWR@tempone}%
}

\LWR@formatted{ETE@OrgGin@setfile}
```

`\includegraphics` in HTML mode redefines `\Gin@setfile` to be `\LWR@HTML@Gin@setfile`, which is now redirected to epstopdf's version:

```
\renewcommand*{\LWR@HTML@Gin@setfile}[3]{%
    \ETE@Gin@setfile{#1}{#2}{#3}%
}
```

Allow `.eps` images to be found if a suffix is not provided:

```
\AtBeginDocument{
\DeclareGraphicsExtensions{%
    .eps,.EPS,.svg,.SVG,.gif,.GIF,.png,.PNG,.jpg,.JPG,.jpeg,.JPEG%
}
\DeclareGraphicsRule{.svg}{svg}{.svg}{}
\DeclareGraphicsRule{.SVG}{svg}{.SVG}{}
}
```

Likewise when inside a `lateximage`:

```
\appto\LWR@restoreorigformatting{%
\DeclareGraphicsExtensions{%
    .eps,.EPS,.pdf,.PDF,.gif,.GIF,.png,.PNG,.jpg,.JPG,.jpeg,.JPEG%
}%
}
```

---

File 133 **lwarp-eqlist.sty**

§ 240 Package

# eqlist

Pkg `eqlist`

eqlist is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{eqlist}[2002/08/15]

\newenvironment{eqlist}[1][]{\description}{\enddescription}
\newenvironment{eqlist*}[1][]{\description}{\enddescription}
\newenvironment{Eqlist}[2][]{\description}{\enddescription}
\newenvironment{Eqlist*}[2][]{\description}{\enddescription}
\newcommand*{\longitem}[1][]{\item[#1]}
\newcommand*{\eqlistinit}{}
\newcommand*{\eqliststarinit}{}
```

```
\newcommand*{\eqlistinitpar}{}
\def\eqlistlabel#1{#1}
\newcommand{\eqlistauto}[1]{}
\newcommand{\eqlistnoauto}{}
```

File 134 **lwarp-eqparbox.sty**

## § 241 Package eqparbox

(*Emulates or patches code by* Scott Pakin.)

Pkg eqparbox eqparbox is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{eqparbox}[2017/09/03]

\NewDocumentCommand{\LWR@HTML@eqparbox}{O{t} O{} O{t} m +m}{%
    {%
        \minipagefullwidth%
        \parbox[#1][#2][#3]{\linewidth}{#5}%
    }%
}
\LWR@formatted{eqparbox}

\NewDocumentCommand{\LWR@HTML@eqmakebox}{o o m}{%
    \makebox[#2]{#3}%
}
\LWR@formatted{eqmakebox}

\NewDocumentCommand{\LWR@HTML@eqframebox}{o o m}{%
    \framebox[#2]{#3}%
}
\LWR@formatted{eqframebox}

\NewDocumentEnvironment{LWR@HTML@eqminipage}{O{t} O{} O{t} m}
{%
    \begingroup%
    \minipagefullwidth%
    \minipage[#1][#2][#3]{\linewidth}%
}%
{%
    \endminipage%
    \endgroup%
}

\newcommand*{\LWR@HTML@eqboxwidth}[1]{.25\linewidth}
\LWR@formatted{eqboxwidth}

\newcommand*{\LWR@HTML@eqsetminwidth}[2]{}
\newcommand*{\LWR@HTML@eqsetmaxwidth}[2]{}

\newcommand*{\LWR@HTML@eqsetminwidthto}[2]{}
\newcommand*{\LWR@HTML@eqsetmaxwidthto}[2]{}
```

```
%     {\inlinemathother$_d^{\@thefnmark}$\inlinemathnormal}
    {\textsubscript{d}\textsuperscript{\@thefnmark}}
    {}
    {\LWR@patcherror{erratum}{eDelete}}

\xpatchcmd{\erratum}
    {$_r^{\@thefnmark}$}
%     {\inlinemathother$_r^{\@thefnmark}$\inlinemathnormal}
    {\textsubscript{r}\textsuperscript{\@thefnmark}}
    {}
    {\LWR@patcherror{erratum}{eReplace}}
```

Finish the current page's errata before closing and reloading the list:

```
\preto\PrintErrata{\LWR@maybe@orignewpage}
```

No longer defining math macros with the HTML $:

```
\StopDefiningMath
```

---

File 136 **lwarp-eso-pic.sty**

# § 243 Package eso-pic

(*Emulates or patches code by* Rolf Niepraschk.)

Pkg eso-pic eso-pic is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{eso-pic}[2018/04/12]

\newcommand*{\LenToUnit}{}
\newcommand{\AtPageUpperLeft}[1]{}
\newcommand{\AtPageLowerLeft}[1]{}
\newcommand{\AtPageCenter}[1]{}
\newcommand{\AtStockLowerLeft}[1]{}
\newcommand{\AtStockUpperLeft}[1]{}
\newcommand{\AtStockCenter}[1]{}
\newcommand{\AtTextUpperLeft}[1]{}
\newcommand{\AtTextLowerLeft}[1]{}
\newcommand{\AtTextCenter}[1]{}
\NewDocumentCommand{\AddToShipoutPictureBG}{s +m}{}

\newcommand{\AddToShipoutPicture}{\AddToShipoutPictureBG}
\NewDocumentCommand{\AddToShipoutPictureFG}{s +m}{}
\newcommand*{\ClearShipoutPictureBG}{}
\newcommand*{\ClearShipoutPicture}{}
\newcommand*{\ClearShipoutPictureFG}{}
\newcommand{\gridSetup}[6][]{}
```

---

File 137 **lwarp-esvect.sty**

## § 244 Package esvect

(*Emulates or patches code by* Eddie Saudrais.)

Pkg esvect esvect is used as-is for SVG math, and emulated for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{esvect}% no date given

\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\LWResvectvv}[1]{\overrightarrow{#1}}}
\CustomizeMathJax{\newcommand{\LWResvectvvstar}[2]{\overrightarrow{#1}\!_{#2}}}
\CustomizeMathJax{\newcommand{\vv}{\ifstar\LWResvectvvstar\LWResvectvv}}
\end{warpMathJax}
```

---

File 138 **lwarp-etoc.sty**

## § 245 Package etoc

Pkg etoc etoc is ignored. All commands are nullified.

⚠ `\tableofcontents` with `\ref`

The etoc package uses a non-standard syntax which looks ahead after a `\tableofcontents` for a following `\ref`. These `\ref`s appear in the HTML result unless they are removed. Where a `\tableofcontents` is followed by `\ref`, and perhaps also `\label` as well, enclose all of them inside `\warpprintonly`:

```
\warpprintonly{\tableofcontents \ref{toc:abc} \label{toc:def}}
```

or place all code related to a local `\tableofcontents` inside a `warpprint` environment.

⚠ home page

Be sure to keep the initial `\tableofcontents` on the home page, perhaps in its own `\warpHTMLonly` macro or `warpHTML` environment.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{etoc}[2019/11/17]

\def\etocsetlevel#1#2{}
\def\etocskipfirstprefix{}
\let\etocthename   \@empty
\let\etocthenumber \@empty
\let\etocthepage   \@empty
\let\etocthelinkedname   \@empty
\let\etocthelinkednumber \@empty
\let\etocthelinkedpage   \@empty
\let\etocthelink   \@firstofone % prior to 1.08j its was \let to \@empty
\DeclareRobustCommand*{\etocname}  {}
\DeclareRobustCommand*{\etocnumber}{}
\DeclareRobustCommand*{\etocpage}  {}
\DeclareRobustCommand*{\etoclink}  {\@firstofone}
\DeclareRobustCommand*{\etocifnumbered}{\@firstoftwo}
\DeclareRobustCommand*{\etociffirst}{\@firstoftwo}
\DeclareRobustCommand*\etocifwasempty{\@firstoftwo}
\let\etocaftertitlehook    \@empty
\let\etocaftercontentshook \@empty
```

```
\long\def\etocbkgcolorcmd{\relax}
\newcommand*\etocframedstyle[2][]{}
\def\etocmulticol{}
\def\etocruled{}
\def\etocframed{}
\def\etoclocalmulticol{}
\def\etoclocalruled{}
\def\etoclocalframed{}
\def\etocarticlestyle{}
\def\etocarticlestylenomarks{}
\def\etocbookstyle{}
\def\etocbookstylenomarks{}
\let\etocreportstyle\etocbookstyle
\let\etocreportstylenomarks\etocbookstylenomarks
\def\etocmemoirtoctotocfmt #1#2{}
\def\etocmemoirstyle{}
\def\etocscrartclstyle{}
\let\etocscrbookstyle\etocscrartclstyle
\let\etocscrreprtstyle\etocscrartclstyle
\def\etocstandarddisplaystyle{\etocarticlestyle}
\newcommand*\etocmarkboth[1]{}
\newcommand*\etocmarkbothnouc[1]{}
\newcommand\etoctocstyle[3][section]{}
\newcommand\etoctocstylewithmarks[4][section]{}
\newcommand\etoctocstylewithmarksnouc[4][section]{}
\def\etocignoretoctocdepth{}
\def\etocsettocdepth[1]{}
\def\etocdepthtag   #1#{\Etoc@depthtag }
\def\Etoc@depthtag  #1{}
\def\etocignoredepthtags {}
\def\etocobeydepthtags   {}
\def\etocsettagdepth #1#2{}
\def\invisibletableofcontents {}
\def\invisiblelocaltableofcontents{}
\def\etocsetnexttocdepth #1{}
\def\etocsetlocaltop #1#{\Etoc@set@localtop}
\def\Etoc@set@localtop #1{}
\def\etocstandardlines {}
\def\etoctoclines      {}
\let\etocaftertochook    \@empty
\let\etocbeforetitlehook \@empty
\appto\tableofcontents{\def\tableofcontents{}}
```

---

File 139 **lwarp-eurosym.sty**

# § 246 Package eurosym

(*Emulates or patches code by* Henrik Theiling.)

Pkg eurosym eurosym is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{eurosym}[1998/08/06]
```

```
\renewrobustcmd\officialeuro{\HTMLentity{euro}}
\let\geneuro\officialeuro
\let\geneuronarrow\officialeuro
\let\geneurowide\officialeuro
\let\euro\officialeuro
\renewrobustcmd\eurobars{}
\renewrobustcmd\eurobarsnarrow{}
\renewrobustcmd\eurobarswide{}
```

---

File 140 **lwarp-everypage.sty**

## § 247 Package everypage

(*Emulates or patches code by* Sergio Callegari.)

Pkg everypage everypage is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{everypage}[2007/06/20]

\newcommand*{\AddEverypageHook}[1]{}
\newcommand*{\AddThispageHook}[1]{}
```

---

File 141 **lwarp-everyshi.sty**

## § 248 Package everyshi

(*Emulates or patches code by* Martin Schröder.)

Pkg everyshi ignored.

**for HTML output:** Discard all options for lwarp-everyshi:

```
\LWR@ProvidesPackageDrop{everyshi}[2001/05/15]

\let\EveryShipout\relax
\newcommand*{\EveryShipout}[1]{}

\let\AtNextShipout\relax
\newcommand*{\AtNextShipout}[1]{}
```

---

File 142 **lwarp-extarrows.sty**

## § 249 Package extarrows

(*Emulates or patches code by* Huynh Ky Anh.)

Pkg extarrows extarrows is used as-is for SVG math, and emulted for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{extarrows}[2008/05/15]
```

```
\begin{warpMathJax}
\CustomizeMathJax{\Newextarrow\xLongleftarrow{10,10}{0x21D0}}
\CustomizeMathJax{\Newextarrow\xLongrightarrow{10,10}{0x21D2}}
\CustomizeMathJax{\Newextarrow\xLongleftrightarrow{10,10}{0x21D4}}
\CustomizeMathJax{\Newextarrow\xLeftrightarrow{10,10}{0x21D4}}
\CustomizeMathJax{\Newextarrow\xlongleftrightarrow{10,10}{0x2194}}
\CustomizeMathJax{\Newextarrow\xleftrightarrow{10,10}{0x2194}}
\CustomizeMathJax{\let\xlongleftarrow\xleftarrow}
\CustomizeMathJax{\let\xlongrightarrow\xrightarrow}
\end{warpMathJax}
```

File 143 **lwarp-extramarks.sty**

## § 250 Package extramarks

(*Emulates or patches code by* Piet van Oostrum.)

Pkg extramarks extramarks is ignored.

**for HTML output:** Discard all options for lwarp-extramarks:

```
\LWR@ProvidesPackageDrop{extramarks}[2019/01/31]

\newcommand*{\extramarks}[2]{}
\newcommand*{\firstleftxmark}{}
\newcommand*{\lastleftxmark}{}
\newcommand*{\firstrightxmark}{}
\newcommand*{\lastrightxmark}{}
\newcommand*{\firstxmark}{}
\newcommand*{\lastxmark}{}
\newcommand*{\topxmark}{}
\newcommand*{\topleftxmark}{}
\newcommand*{\toprightxmark}{}
\newcommand*{\firstleftmark}{}
\newcommand*{\lastrightmark}{}
\newcommand*{\firstrightmark}{}
\newcommand*{\lastleftmark}{}
```

-250(O5o31m9TJ/F798.9 4-25]0d0J398.9070Td[(File)-1 7(143)]TJ0g0G0g0G/F19 17.2

```
\newenvironmentFramedEqn
{
\lateximage% NEW
\setlength{\fboxsep}{15pt}
. . . }{. . .
\[\fbox{\TheSbox}\]
\endlateximage% NEW
}
```

framing alternatives

`\fbox` works with fancybox. Also see lwarp's `\fboxBlock` macro and `fminipage` environment for alternatives to `\fbox` for framing environments.

framed table example

The fancybox documentation's example of a framed table using an `\fbox` containing a `tabular` does not work with lwarp, but the `FramedTable` environment does work if `\fbox` is replaced by `\fboxBlock`. This method does lose some HTML formatting. A better method is to enclose the table's contents inside a `fminipage` environment. The caption may be placed either inside or outside the `fminipage`:

```
\begin{table}
\begin{fminipage}{\linewidth}
\begin{tabular}{lr}
. . .
\end{tabular}
\end{fminipage}
\end{table}
```

⚠ framed verbatim

lwarp does not support the `verbatim` environment inside a span, box, or fancybox's `\Sbox`, but a `verbatim` may be placed inside a `fminipage`. The fancybox documentation's example `FramedVerb` may be defined as:

```
\newenvironment{FramedVerb}[1] % width
{
  \VerbatimEnvironment
  \fminipage{#1}
  \beginVerbatim
}{
  \endVerbatim
  \endfminipage
}
```

framed `\VerbBox`

fancybox's `\VerbBox` may be used inside `\fbox`.

indented alignment

`LVerbatim`, `\LVerbatimInput`, and `\LUseVerbatim` indent with horizontal space which may not line up exactly with what *pdftotext* detects. Some lines may be off slightly in their left edge.

fancybox, fancyvrb
⚠ `\VerbatimFootnotes`
⚠ sectioning or displaymath

If using fancybox or fancyvrb with `\VerbatimFootnotes`, and using footnotes in a sectioning command or display math, use `\footnotemark` and `\footnotetext`:

```
\subsection[Subsection Name]
    {Subsection Name\protect\footnotemark}
\footnotetext{A footnote with \verb+verbtim+.}
```

and likewise for equations or display math.

At present there is a bug such that paragraph closing tags are not present in footnotes when \VerbatimFootnotes are selected. The browser usually compensates.

```
\LWR@ProvidesPackagePass{fancybox}[2010/05/15]
```

After the preamble is loaded, after any patches to Verbatim:

```
\AfterEndPreamble{
\LWR@traceinfo{Patching fancybox.}
```

\VerbatimFootnotes Patched to use the new version.

```
\def\VerbatimFootnotes{%
\let\@footnotetext\V@footnotetext%
\let\LWR@footnotetext\V@footnotetext% lwarp
}
```

\V@@footnotetext Patches in a subset of lwarp's \LWR@footnotetext to the fancyvrb version of \V@@footnotetext.

```
\def\V@@footnotetext{%
\LWR@traceinfo{V@footnotetext}%
\global\setbox\LWR@footnotebox=\vbox\bgroup%
```

Add to any current footnotes:

```
    \unvbox\LWR@footnotebox%
```

Remember the footnote number for \ref:

```
    \protected@edef\@currentlabel{%
        \csname p@footnote\endcsname\@thefnmark%
    }% @currentlabel
```

Use HTML superscripts in the footnote even inside a lateximage:

```
    \renewrobustcmd{\textsuperscript}[1]{\LWR@htmlspan{sup}{##1}}%
```

Use paragraph tags if in a tabular data cell or a lateximage:

```
    \ifthenelse{%
        \boolean{LWR@doingstartpars} \AND%
        \cnttest{\value{LWR@lateximagedepth}}{=}{0}%
    }%
        {}%
        {\LWR@htmltagc{\LWR@tagregularparagraph}\LWR@orignewline}%
```

Append the footnote to the list:

```
    \@makefntext{}%
```

The footnote text will follow after \V@@@footnotetext has completed.

```
  \bgroup%
  \aftergroup{\V@@@footnotetext}%
  \ignorespaces%
}%

}% AfterEndPreamble
```

```
\renewcommand*{\@shadowbox}[1]{%
\ifbool{FormatWP}%
{\InlineClass[border:1px solid black]{shadowbox}{#1}}%
{\InlineClass{shadowbox}{#1}}%
}

\renewcommand*{\@doublebox}[1]{%
\ifbool{FormatWP}%
{\InlineClass[border:1px double black]{doublebox}{#1}}%
{\InlineClass{doublebox}{#1}}%
}

\renewcommand*{\@ovalbox}[2]{%
\ifbool{FormatWP}%
{\InlineClass[border:1px solid black; border-radius:1ex]{ovalbox}{#2}}%
{%
    \ifthenelse{\isequivalentto{#1}{\thinlines}}%
        {\InlineClass{ovalbox}{#2}}%
        {\InlineClass{Ovalbox}{#2}}%
}%
}
```

Convert minipages, parboxes, and lists into linear text using the LWR@nestspan environment:

```
\let\LWR@origSbox\Sbox

\def\Sbox{\LWR@origSbox\LWR@nestspan}


\let\LWR@origendSbox\endSbox

\def\endSbox{\endLWR@nestspan\LWR@origendSbox}
```

Beqnarray is adapted for MathJax or enclosed inside a lateximage:

```
\RenewEnviron{Beqnarray}
{\LWR@eqnarrayfactor}

\csgpreto{Beqnarray*}{\boolfalse{LWR@numbereqnarray}}
```

\GenericCaption is enclosed in an HTML block:

```
\renewcommand{\GenericCaption}[1]{%
\LWR@figcaption%
\LWR@isolate{#1}%
\endLWR@figcaption%
}
```

Btrivlist is enclosed in an HTML block. This is a tabular, and does not use \item.

\trivlist {⟨*l/c/r*⟩} [⟨*t/c/b*⟩]

```
\RenewDocumentEnvironment{Btrivlist}{m o}
```

```
{%
    \LWR@stoppars%
    \begin{BlockClass}{Btrivlist}%
    \tabular{#1}%
}
{%
    \endtabular%
    \end{BlockClass}%
    \LWR@startpars%
}
```

`Btrivlist` is also neutralized when used inside a span:

```
\AtBeginEnvironment{LWR@nestspan}{%
\RenewDocumentEnvironment{Btrivlist}{m o}{}{}%
}
```

lwarp's handling of `\item` is patched to accept fancybox's optional arguments:

```
\let\LWRFB@origitemizeitem\LWR@itemizeitem
\let\LWRFB@origdescitem\LWR@descitem

\RenewDocumentCommand{\LWR@itemizeitem}{d()o}{%
    \IfValueTF{#2}{%
        \LWRFB@origitemizeitem[#2]%
    }{%
        \LWRFB@origitemizeitem%
    }%
}

\RenewDocumentCommand{\LWR@descitem}{d()o}{%
    \IfValueTF{#2}{%
        \LWRFB@origdescitem[#2]~%
    }{%
        \LWRFB@origdescitem%
    }%
}


\RenewDocumentCommand{\LWR@nestspanitem}{d()}{%
\if@newlist\else{\LWR@htmltagc{br /}}\fi%
\LWR@origitem%
}
```

The various boxed lists become regular lists:

```
\renewenvironment{Bitemize}[1][]{\begin{itemize}}{\end{itemize}}
\renewenvironment{Benumerate}[1][]{\begin{enumerate}}{\end{enumerate}}
\renewenvironment{Bdescription}[1][]{\begin{description}}{\end{description}}
```

`\boxput` simply prints one then the other argument, side-by-side instead of above and behind:

```
\RenewDocumentCommand{\boxput}{s d() m m}{%
```

```
\newcommand*{\fancyhead}[2][]{}
\newcommand*{\fancyfoot}[2][]{}
\newcommand*{\fancyhf}[2][]{}

\newcommand*{\lhead}[2][]{}
\newcommand*{\chead}[2][]{}
\newcommand*{\rhead}[2][]{}
\newcommand*{\lfoot}[2][]{}
\newcommand*{\cfoot}[2][]{}
\newcommand*{\rfoot}[2][]{}
\newcommand*{\headrulewidth}{}
\newcommand*{\footrulewidth}{}
\providecommand{\headruleskip}{0pt}
\providecommand{\footruleskip}{0pt}
\newcommand{\plainheadrulewidth}{0pt}
\newcommand{\plainfootrulewidth}{0pt}
\def\fancyplain#1#2{#1}
\newcommand*{\headrule}{}
\newcommand*{\footrule}{}
\newlength{\headwidth}
\newcommand*{\fancycenter}[1][1em]{}
\newcommand*{\fancyheadoffset}[2][]{}
\newcommand*{\fancyfootoffset}[2][]{}
\newcommand*{\fancyhfoffset}[2][]{}
\newcommand{\fancyheadinit}[1]{}
\newcommand{\fancyfootinit}[1]{}
\newcommand{\fancyhfinit}[1]{}
\newcommand*{\iffloatpage}[2]{#2}
\newcommand*{\ifftopfloat}[2]{#2}
\newcommand*{\iffbotfloat}[2]{#2}
\newcommand*{\iffootnote}[2]{#2}

\newcommand{\fancypagestyle}[1]{%
  \@ifnextchar[{\f@nch@pagestyle{#1}}{\f@nch@pagestyle{#1}[]}%
}
\long\def\f@nch@pagestyle#1[#2]#3{}
```

---

File 146 **lwarp-fancyref.sty**

§ 253 Package

# fancyref

(*Emulates or patches code by* Axel Reichert.)

Pkg fancyref fancyref is modifed for HTML output.

**for HTML output:**

```
\LWR@ProvidesPackagePass{fancyref}[1999/02/03]
```

To remove the margin option, if \fancyrefhook is anything other than the paren option, then force it to the default instead. (Comparing to the margin option was not possible since lwarp has revised the meaning of \mbox so the comparison failed.)

```
\newcommand*{\LWRfref@parenfancyrefhook}[1]{(#1)}

```

```
\ifdefstrequal{\fancyrefhook}{\LWRfref@parenfancyrefhook}
{}{
    \renewcommand*{\fancyrefhook}[1]{#1}%
}
```

File 147 **lwarp-fancytabs.sty**

## § 254 Package fancytabs

Pkg fancytabs fancytabs is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{fancytabs}[2016/03/29]

\newcommand{\fancytab}[3][RIGHT]{}
\newcommand{\fancytabsStyle}[1]{}
\newcommand{\fancytabsHeight}[1]{}
\newcommand{\fancytabsWidth}[1]{}
\newcommand{\fancytabsCount}[1]{}
\newcommand{\fancytabsLeftColor}[1]{}
\newcommand{\fancytabsRightColor}[1]{}
\newcommand{\fancytabsTop}[1]{}
\newcommand{\fancytabsTextVPos}[1]{}
\newcommand{\fancytabsTextHPos}[1]{}
\newcommand{\fancytabsGap}[1]{}
\newcommand{\fancytabsFloor}[1]{}
\newcommand{\fancytabsRotate}[1]{}
```

File 148 **lwarp-fancyvrb.sty**

## § 255 Package fancyvrb

(*Emulates or patches code by* Timothy Van Zandt.)

Pkg fancyvrb fancyvrb is supported with some patches.

HTML classes The fancy verbatim environment is placed inside a  of class fancyvrb. The label is placed inside a  of class fancyvrblabel. The verbatim text itself is placed inside a  of class verbatim.

fancybox, fancyvrb
⚠ \VerbatimFootnotes
⚠ sectioning or displaymath

If using fancybox or fancyvrb with \VerbatimFootnotes, and using footnotes in a sectioning command or display math, use \footnotemark and \footnotetext:

```
\subsection[Subsection Name]
    {Subsection Name\protect\footnotemark}
\footnotetext{A footnote with \verb+verbtim+.}
```

and likewise for equations or display math.

At present there is a bug such that paragraph closing tags are not present in footnotes when \VerbatimFootnotes are selected. The browser usually compensates.

```
\AtBeginDocument{\RequirePackage{xcolor}}% for \convertcolorspec

\LWR@ProvidesPackagePass{fancyvrb}[2008/02/07]
```

Initial default patch for fancyvrb:

```
\fvset{frame=none}%
```

After the preamble is loaded, after any patches to `Verbatim`:

```
\AfterEndPreamble{
\LWR@traceinfo{Patching fancyvrb.}
```

`\VerbatimFootnotes` Patched to use the new version.

```
\def\VerbatimFootnotes{%
\let\@footnotetext\V@footnotetext%
\let\footnote\V@footnote%
\let\LWR@footnotetext\V@footnotetext% lwarp
}
```

`\V@@footnotetext` Patches in a subset of lwarp's `\LWR@footnotetext` to the fancyvrb version of `\V@@footnotetext`.

```
\def\V@@footnotetext{%
\LWR@traceinfo{V@footnotetext}%
\global\setbox\LWR@footnotebox=\vbox\bgroup%
```

Add to any current footnotes:

```
    \unvbox\LWR@footnotebox%
```

Remember the footnote number for `\ref`:

```
    \protected@edef\@currentlabel{%
        \csname p@footnote\endcsname\@thefnmark%
    }% @currentlabel
```

Use HTML superscripts in the footnote even inside a `lateximage`:

```
    \renewrobustcmd{\textsuperscript}[1]{\LWR@htmlspan{sup}{##1}}%
```

Use paragraph tags if in a tabular data cell or a `lateximage`:

```
    \ifthenelse{%
        \boolean{LWR@doingstartpars} \AND%
        \cnttest{\value{LWR@lateximagedepth}}{=}{0}%
    }%
        {}%
        {\LWR@htmltagc{\LWR@tagregularparagraph}\LWR@orignewline}%
```

Append the footnote mark to the list:

```
    \@makefntext{}%
```

The footnote text will follow after `\V@@@footnotetext` has completed.

```
  \bgroup%
  \aftergroup{\V@@@footnotetext}%
  \ignorespaces%
}%
```

```
\preto\FVB@Verbatim{\LWR@forcenewpage}
\preto\FVB@LVerbatim{\LWR@forcenewpage}
% \preto\FVB@BVerbatim{\LWR@forcenewpage}% Fails, so done below.
```

Simplified to remove PDF formatting:

```
\def\FV@BeginListFrame@Single{%
  \FV@SingleFrameLine{\z@}%
}

\def\FV@EndListFrame@Single{%
  \FV@SingleFrameLine{\@ne}%
}

\def\FV@BeginListFrame@Lines{%
  \FV@SingleFrameLine{\z@}%
}

\def\FV@EndListFrame@Lines{%
    \FV@SingleFrameLine{\@ne}%
}

\renewcommand*{\FV@SingleFrameSep}{}
```

Adds HTML formatting:

```
\def\FV@BUseVerbatim#1{%
    \FV@BVerbatimBegin#1\FV@BVerbatimEnd%
}
```

`\LWR@FVstyle` Holds the style of the verbatim.

```
\newcommand*{\LWR@FVstyle}{}
```

The following patches to `Verbatim` are executed at the start and end of the environment, depending on the choice of `frame`. Original code is from the fancyvrb package.

```
\newcommand*{\LWR@fvstartnone}{%
\LWR@traceinfo{fvstartnone}%
% \hbox to\z@{
\BlockClass[\LWR@FVstyle]{fancyvrb}
\LWR@stoppars
\ifx\FV@LabelPositionTopLine\relax\else
    \ifx\FV@LabelBegin\relax\else
        \FancyVerbRuleColor{\LWR@FVfindbordercolor}
        \LWR@htmltagc{%
            div class=\textquotedbl{}fancyvrblabel\textquotedbl\ % space
           style=\textquotedbl{}color: \LWR@origpound\LWR@tempcolor\textquotedbl%
        }
        \LWR@print@textrm{\FV@LabelBegin}% \textrm preserves emdash
        \LWR@htmltagc{/div}\LWR@orignewline%
    \fi
\fi
\LWR@atbeginverbatim{verbatim}%
```

```
% }%
}

\newcommand*{\LWR@fvendnone}{%
\LWR@traceinfo{fvendnone}%
% \hbox to\z@{
\LWR@afterendverbatim%
\LWR@stoppars%
\ifx\FV@LabelPositionBottomLine\relax\else
    \ifx\FV@LabelEnd\relax\else
        \FancyVerbRuleColor{\LWR@FVfindbordercolor}
        \LWR@htmltagc{%
            div class=\textquotedbl{}fancyvrblabel\textquotedbl\ % space
           style=\textquotedbl{}color: \LWR@origpound\LWR@tempcolor\textquotedbl%
        }
        \LWR@print@textrm{\FV@LabelEnd}
        \LWR@htmltagc{/div}\LWR@orignewline%
    \fi
\fi
\endBlockClass
}

\newcommand*{\LWR@fvstartsingle}{%
\LWR@traceinfo{fvstartsingle}%
\LWR@fvstartnone%
\FV@BeginListFrame@Single%
}

\newcommand*{\LWR@fvendsingle}{%
\LWR@traceinfo{fvendsingle}%
\FV@EndListFrame@Single%
\LWR@fvendnone%
}

\newcommand*{\LWR@fvstartline}{%
\LWR@traceinfo{fvstartline}%
\LWR@fvstartnone%
% \setlength{\LWR@templengthone}{\baselineskip}%
\FV@BeginListFrame@Lines%
% \setlength{\baselineskip}{\LWR@templengthone}%
% \setlength{\baselineskip}{5pt}%
}

\newcommand*{\LWR@fvendline}{%
\LWR@traceinfo{fvendline}%
\FV@EndListFrame@Lines%
\LWR@fvendnone%
}
```

The following patches select the start/left/right/end behaviors depending on `frame`. Original code is from the fancyvrb package.

```
\newcommand*{\LWR@FVfindbordercolor}{%
\FancyVerbRuleColor%
\LWR@findcurrenttextcolor%
```

```
    \LWR@FVborderstyle{-bottom}%
}%
\let\FV@BeginListFrame\LWR@fvstartnone%
\let\FV@LeftListFrame\relax%
\let\FV@RightListFrame\relax%
\let\FV@EndListFrame\LWR@fvendline}
```

Seems to be required in some situations:

```
\def\FV@FrameFillLine{}%
```

```
\def\FV@Frame@leftline{%
\renewcommand*{\LWR@FVstyle}{%
    \LWR@currenttextcolorstyle\LWR@indentHTMLtwo%
    \LWR@FVborderstyle{-left}%
}%
% To define the \FV@FrameFillLine macro (from \FV@BeginListFrame)
\ifx\FancyVerbFillColor\relax%
\let\FV@FrameFillLine\relax%
\else%
\@tempdima\FV@FrameRule\relax%
\multiply\@tempdima-\tw@%
\edef\FV@FrameFillLine{%
{\noexpand\FancyVerbFillColor{\vrule\@width\number\@tempdima sp}%
\kern-\number\@tempdima sp}}%
\fi%
\let\FV@BeginListFrame\LWR@fvstartnone%
\let\FV@LeftListFrame\FV@LeftListFrame@Single%
\let\FV@RightListFrame\relax%
\let\FV@EndListFrame\LWR@fvendnone}
```

Adds the optional label to the top and bottom edges. Original code is from the fancyvrb package.

```
\def\FV@SingleFrameLine#1{%
%   \hbox to\z@{%
%     \kern\leftmargin
    \ifnum#1=\z@\relax
      \let\FV@Label\FV@LabelBegin
    \else
      \let\FV@Label\FV@LabelEnd
    \fi
    \ifx\FV@Label\relax
%       \FancyVerbRuleColor{\vrule \@width\linewidth \@height\FV@FrameRule}%
    \else
      \ifnum#1=\z@
%         \setbox\z@\hbox{\strut\enspace\FV@LabelBegin\enspace\strut}%
        \ifx\FV@LabelPositionTopLine\relax
        \else
        \fi
      \else
%         \setbox\z@\hbox{\strut\enspace\FV@LabelEnd\enspace\strut}%
        \ifx\FV@LabelPositionBottomLine\relax
        \else
        \fi
```

End of the modifications to make at the end of the preamble:

```
270 } % \AfterEndPreamble
```

---

File 149 **lwarp-fbox.sty**

§ 256 Package

# fbox

(*Emulates or patches code by* Herbert Voss.)

Pkg fbox fbox is patched for use by lwarp.

**for HTML output:**

```
1 \LWR@ProvidesPackagePass{fbox}[2020/06/22]
```

This will be \LWR@formatted when \AtBeginDocument:

```
2 \LetLtxMacro\LWR@HTML@fbox\fbox
```

Instead of using the original, the new version is used with all borders:

```
3 \renewcommand*{\orig@fbox}{\FBox@i[tblr]}
```

\WR@fboxpkg@border {⟨*1: top/bottom/left/right*⟩} {⟨*2: padding, or empty*⟩}

Accumulates HTML styles for border, and padding if given:

```
4 \newcommand*{\LWR@fboxpkg@border}[2]{%
5     \appto\LWR@tempone{%
6         border-#1: % space
7         \LWR@printlength{\LWR@atleastonept} % space
8         solid \LWR@origpound\LWR@tempcolor ;\LWR@indentHTML
9     }%
10    \ifblank{#2}{}{%
11        \appto\LWR@tempone{%
12            padding-#1: \LWR@printlength{#2} ;\LWR@indentHTML
13        }%
14    }%
15 }
```

A hack to reuse the same code for inline and blocks:

```
16 \newbool{LWR@fboxpkg@ispar}
17 \boolfalse{LWR@fboxpkg@ispar}
```

Acculumate HTML styles for left and right padding, depending on \if@fbox@space@left, \if@fbox@space@right:

```
18 \newcommand{\LWR@fboxpkg@lrpadding}[1]{%
19     \csuse{if@fbox@space@#1}%
20         \appto\LWR@tempone{%
21             padding-#1: \LWR@printlength{\fbox@@sep};\LWR@indentHTML
22         }
23     \else%
```

```
        \appto\LWR@tempone{%
            padding-#1: 0pt;\LWR@indentHTML
        }
    \fi%
}
```

The HTML version, modified to use HTML styles and either an `\InlineClass` or `BlockClass`:

```
\newcommand{\LWR@HTML@FBox@iii}[1]{%
```

Find and set the text color, rule width, margin:

```
    \LWR@forceminwidth{\fbox@@rule}%
    \LWR@findcurrenttextcolor%
    \def\LWR@tempone{%
        color: \LWR@origpound\LWR@tempcolor ; \LWR@indentHTML
        margin: 1ex ; \LWR@indentHTML
    }%
```

Add left/right padding:

```
    \LWR@fboxpkg@lrpadding{left}%
    \LWR@fboxpkg@lrpadding{right}%
```

Per the original to decode the borders, in a new way:

```
    \ifnum\the\@tempcntb>8\relax
        \advance\@tempcntb by -8
        \LWR@fboxpkg@border{top}{\fbox@@sep}%
    \fi
    \ifnum\@tempcntb>3
        \advance\@tempcntb by -4
        \LWR@fboxpkg@border{left}{}%
    \fi
    \ifnum\@tempcntb>1
        \LWR@fboxpkg@border{right}{}%
    \fi
    \ifodd\@tempcntb
        \LWR@fboxpkg@border{bottom}{\fbox@@sep}%
    \fi
```

Generate a `BlockClass` or `\InlineClass` with the contents:

```
    \color@begingroup
    \ifbool{LWR@fboxpkg@ispar}%
        {%
            \begin{BlockClass}[\LWR@tempone]{fboxpkg}%
                #1%
            \end{BlockClass}%
        }%
        {%
            \InlineClass[\LWR@tempone]{fboxpkg}{%
                #1%
            }%
        }%
```

```
    \color@endgroup
    \boolfalse{LWR@fboxpkg@ispar}% globally
}
\LWR@formatted{FBox@iii}
```

For \fparbox, set the use of BlockClass, then reuse the above:

```
\long\def\LWR@HTML@FParBox@i[#1]#2{%
    \booltrue{LWR@fboxpkg@ispar}%
    \FBox@i[#1]{#2}
}
\LWR@formatted{FParBox@i}

\long\def\LWR@HTML@FParBox@ii#1{%
    \booltrue{LWR@fboxpkg@ispar}%
    \FBox@i[tblr]{#1}%
}
\LWR@formatted{FParBox@ii}
```

For MathJax, absorb and ignore star and optional arguments:

```
\CustomizeMathJax{\let\LWRorigfbox\fbox}
\CustomizeMathJax{\newcommand{\LWRfboxpkgtwo}[2][]{\LWRorigfbox{#2}}}
\CustomizeMathJax{\renewcommand{\fbox}{\ifstar\LWRfboxpkgtwo\LWRfboxpkgtwo}}
\CustomizeMathJax{\newcommand{\fparbox}{\fbox}}
```

---

File 150 **lwarp-fewerfloatpages.sty**

## § 257 Package fewerfloatpages

Pkg fewerfloatpages fewerfloatpages is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{fewerfloatpages}[2020/02/14]

\newcommand\floatpagekeepfraction{\textfraction}
\newcounter{floatpagedeferlimit}
\newcounter{floatpagekeeplimit}
```

---

File 151 **lwarp-figcaps.sty**

## § 258 Package figcaps

(*Emulates or patches code by* Patrick W. Daly.)

Pkg figcaps figcaps is ignored.

**for HTML output:** Discard all options for lwarp-figcaps:

```
\LWR@ProvidesPackageDrop{figcaps}[1999/02/23]
```

```
\newcommand*{\figcapson}{}
\newcommand*{\figcapsoff}{}
\newcommand*{\printfigures}{}
\newcommand*{\figmarkon}{}
\newcommand*{\figmarkoff}{}
\def\figurecapname{Figure Captions}
\def\tablepagename{Tables}
\def\figurepagename{Figures}
```

File 152 **lwarp-figsize.sty**

## § 259 Package figsize

(*Emulates or patches code by* Anthony A. Tanbakuchi.)

Pkg figsize figsize is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{figsize}[2002/03/18]
```

Emulates a virtual 6×9 inch textsize.

```
\newlength{\figwidth}
\newlength{\figheight}

\newcommand{\SetFigLayout}[3][0]{%
\setlength{\figheight}{8in}%
\setlength{\figheight}{\figheight / #2}%
%
\setlength{\figwidth}{5.5in}%
\setlength{\figwidth}{\figwidth / #3}%
}
```

File 153 **lwarp-fitbox.sty**

## § 260 Package fitbox

Pkg fitbox fitbox is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{fitbox}[2019/02/20]

\NewDocumentCommand{\fitbox}{s o m}{%
    \begin{BlockClass}{fitbox}
    #3
    \end{BlockClass}
}

\newcommand*{\fitboxset}[1]{}

\newdimen\fitboxnatheight
\newdimen\fitboxnatwidth
```

**for HTML output:**

```
\LWR@ProvidesPackagePass{fixme}[2017/03/05]
```

Restore lwarp's version of `\@wrindex`, ignoring the fixme package's `target` option:

```
\let\@wrindex\LWR@wrindex
```

Float-related macros required by lwarp:

```
\newcommand{\ext@fixme}{lox}

\renewcommand{\l@fixme}[2]{%
    \hypertocfloat{1}{fixme}{lox}%
        {\LWR@nameref{\BaseJobname-autopage-\arabic{LWR@nextautopage}} --- #1}
        {#2}
}
```

Other modifications:

```
\def\FXFaceInlineHTMLStyle{font-weight:bold}

\renewcommand*\FXLayoutInline[3]{ %
\InlineClass[\FXFaceInlineHTMLStyle]{fixmeinline}%
    {\@fxtextstd{#1}{#2}{#3}}%
}

\def\FXFaceEnvHTMLStyle{font-weight:bold}

\renewcommand*\FXEnvLayoutPlainBegin[2]{%
\BlockClass[\FXFaceEnvHTMLStyle]{fixmebold}
\ignorespaces#2 \fxnotename{#1}: \ignorespaces}

\renewcommand*\FXEnvLayoutPlainEnd[2]{\endBlockClass}

\renewcommand*\FXEnvLayoutSignatureBegin[2]{%
\BlockClass[\FXFaceEnvHTMLStyle]{fixmebold}
\fxnotename{#1}: \ignorespaces}

\renewcommand*\FXEnvLayoutSignatureEnd[2]{\@fxsignature{#2}\endBlockClass}

\def\FXFaceSignatureHTMLStyle{font-style:italic}

\DeclareRobustCommand*\@fxsignature[1]{%
\ifthenelse{\equal{#1}{}}%
    {}%
    { -- {\InlineClass[\FXFaceSignatureHTMLStyle]{fixmesignature}{#1}}}%
}


\def\FXFaceTargetHTMLStyle{font-style:italic}

\renewcommand\FXTargetLayoutPlain[2]{%
    \InlineClass[\FXFaceTargetHTMLStyle]{fixmetarget}{#2}%
}
```

File 157 **lwarp-fixmetodonotes.sty**

## § 264 Package fixmetodonotes

(*Emulates or patches code by* Gioele Barabucci.)

Pkg fixmetodonotes fixmetodonotes is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{fixmetodonotes}[2013/04/28]

\renewcommand{\NOTES@addtolist}[2]{%
    \refstepcounter{NOTES@note}%
%   \phantomsection% REMOVED
    \addcontentsline{notes}{NOTES@note}{%
        \protect\numberline{\theNOTES@note}{{#1}: {#2}}%
    }%
}

\renewcommand{\NOTES@marker}[2]{\fbox{%
    \textcolor{#2}{% WAS \color
        \textbf{#1}}%
    }}

\renewcommand{\NOTES@colorline}[2]{%
  \bgroup%
    \ULon{\LWR@backgroundcolor{#1}{#2}}%
}
```

File 158 **lwarp-flafter.sty**

## § 265 Package flafter

Pkg flafter flafter is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{flafter}[2018/01/08]
\providecommand\fl@trace[1]{}
```

File 159 **lwarp-flippdf.sty**

## § 266 Package flippdf

Pkg flippdf flippdf is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{flippdf}[2006/06/30]

\newcommand\FlipPDF{}
\newcommand\UnFlipPDF{}
```

```
    \def\LWR@temptwo{\@nameuse{#1name}}%
    \ifdefequal{\LWR@tempone}{\LWR@temptwo}{}{%
        \SetupFloatingEnvironment{#1}{name=#2}%
    }%
}
```

\floatplacement {⟨*type*⟩} {⟨*placement*⟩}

Float placement is ignored.

```
\newcommand*{\floatplacement}[2]{%
    \SetupFloatingEnvironment{#1}{placement=#2}%
}
```

\floatstyle {⟨*style*⟩}

Remember the style for future floats:

```
\newcommand{\floatstyle}[1]{%
    \def\LWR@floatstyle{#1}%
}
```

\restylefloat * {⟨*type*⟩}

Remember the style for this float:

```
\NewDocumentCommand{\restylefloat}{s m}{%
    \csedef{LWR@floatstyle@#2}{\LWR@floatstyle}%
}
```

\listof See section 77.2 for the `\listof` command in the lwarp core.

---

File 161 **`lwarp-floatflt.sty`**

§ 268 Package

# floatflt

(*Emulates or patches code by* Mats Dahlgren.)

Pkg floatflt floatflt is emulated.

**for HTML output:** Discard all options for lwarp-floatflt:

```
\LWR@ProvidesPackageDrop{floatflt}[1997/07/16]
```

Env [⟨⟩] offset {⟨*type*⟩} {⟨*width*⟩} Borrowed from the lwarp version of keyfloat:

```
\NewDocumentEnvironment{KFLTfloatflt@marginfloat}{O{-1.2ex} m m}
{%
    \begin{LWR@setvirtualpage}*%
    \ifblank{#3}{%
        \LWR@BlockClassWP{%
            float:right; %
            width: 1.5in; % reasonable dummy width for word processor
            margin:10pt%
```

```
        }{}%
        {marginblock}%
    }{%
        \setlength{\LWR@templengthone}{#3}%
        \LWR@BlockClassWP{%
            float:right; %
            width:\LWR@printlength{\LWR@templengthone};  % extra space
            margin:10pt%
        }{%
            width:\LWR@printlength{\LWR@templengthone}%
        }%
        {marginblock}%
    }%
    \renewcommand*{\@captype}{#2}%
}
{%
    \endLWR@BlockClassWP%
    \end{LWR@setvirtualpage}%
}
```

Env floatingfigure [⟨*placement*⟩] {⟨*width*⟩}

```
\DeclareDocumentEnvironment{floatingfigure}{o m}
  {\begin{KFLTfloatflt@marginfloat}{figure}{#2}}
  {\end{KFLTfloatflt@marginfloat}}
```

Env floatingtable [⟨*placement*⟩]

```
\DeclareDocumentEnvironment{floatingtable}{o}
  {\begin{KFLTfloatflt@marginfloat}{table}{}}
  {\end{KFLTfloatflt@marginfloat}}
```

---

File 162 **lwarp-floatpag.sty**

§ 269 Package

# floatpag

(*Emulates or patches code by* Vytas Statulevičius and Sigitas Tolušis.)

Pkg floatpag floatpag is ignored.

**for HTML output:** Discard all options for lwarp-floatpag:

```
\LWR@ProvidesPackageDrop{floatpag}[2012/05/29]
```

```
\newcommand*{\floatpagestyle}[1]{}
\newcommand*{\rotfloatpagestyle}[1]{}
\newcommand*{\thisfloatpagestyle}[1]{}
```

---

File 163 **lwarp-floatrow.sty**

§ 270 Package

# floatrow

(*Emulates or patches code by* Olga Lapko.)

Pkg floatrow floatrow is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{floatrow}[2008/08/02]
```

⚠ Misplaced alignment tab character &

Use `\StartDefiningTabulars` and `\StopDefiningTabulars` before and after defining macros using `\ttabbox` with a tabular inside. See section 8.10.1.

⚠ subfig package

When combined with the subfig package, while inside a `subfloatrow` `\ffigbox` and `\ttabbox` must have the caption in the first of the two of the mandatory arguments.

⚠ `\FBwidth`, `\FBheight`

The emulation of floatrow does not support `\FBwidth` or `\FBheight`. These values are pre-set to `.3\linewidth` and `2in`. Possible solutions include:

- Use fixed lengths. lwarp will scale the HTML lengths appropriately.
- Use `warpprint` and `warpHTML` environments to select appropriate values for each case.
- Inside a `warpHTML` environment, manually change `\FBwidth` or `\FBheight` before the `\ffigbox` or `\ttabbox`. Use `\FBwidth` or `\FBheight` normally afterwards; it will be used as expected in print output, and will use your custom-selected value in HTML output. This custom value will be used repeatedly, until it is manually changed to a new value.

After everything has loaded, remember whether subcaption was loaded. If not, it is assumed that subfig is used instead:

```
\newbool{LWR@subcaptionloaded}

\AtBeginDocument{
\@ifpackageloaded{subcaption}
    {\booltrue{LWR@subcaptionloaded}}
    {\boolfalse{LWR@subcaptionloaded}}
}
```

`\floatbox` `[`⟨*1 preamble*⟩`]` `{`⟨*2 captype*⟩`}` `[`⟨*3 width*⟩`]` `[`⟨*4 height*⟩`]` `[`⟨*5 vert pos*⟩`]` `{`⟨*6 caption*⟩`}` `{`⟨*7 object*⟩`}`

Only parameters for captype, width, caption, and object are used.

`LWR@insubfloatrow` is true if inside a `subfloatrow` environment.

There are two actions, depending on the use of subcaption or subfig.

```
\NewDocumentCommand{\floatbox}{o m o o o +m +m}{%
\ifbool{LWR@subcaptionloaded}%
{% subcaption
```

For subcaption:

```
    \ifbool{LWR@insubfloatrow}%
    {% subcaption in a subfloatrow
```

subfigure and subtable environments take width as an argument.

```
        \IfValueTF{#3}%
        {\@nameuse{sub#2}{#3}}%
        {\@nameuse{sub#2}{\linewidth}}%
    }% subcaption in a subfloatrow
    {% subcaption not in subfloatrow
```

figure and table environments do not take a width argument.

```
        \@nameuse{#2}%
    }% subcaption not in subfloatrow
    #6

    #7
```

End the environments:

```
    \ifbool{LWR@insubfloatrow}%
    {\@nameuse{endsub#2}}%
    {\@nameuse{end#2}}%
}% subcaption
{% assume subfig
```

For subfig:

```
\ifbool{LWR@insubfloatrow}%
{% subfig in a subfloatrow
```

\subfloat is a macro, not an environment.

Package subfig's \subfloat command takes an optional argument which is the caption, but \floatbox argument #6 contains commands to create the caption and label, not the caption itself. Thus, \caption is temporarily disabled to return its own argument without braces.

```
    \begingroup
    \let\caption\@firstofone
    \subfloat[#6]{#7}
    \endgroup
}% subfig in a subfloatrow
{% subfig package, but not a subfig
```

figure and table are environments:

```
\@nameuse{#2}
#6

#7
\@nameuse{end#2}
}% subfig package, but not a subfig
}% assume subfig
}
```

Not used:

```
\newcommand*{\nocapbeside}{}
\newcommand*{\capbeside}{}
\newcommand*{\captop}{}
\newlength{\FBwidth}
\setlength{\FBwidth}{.3\linewidth}
```

```
\newlength{\FBheight}
\setlength{\FBheight}{2in}
\newcommand*{\useFCwidth}{}
\newcommand{\floatsetup}[2][]{}
\newcommand{\thisfloatsetup}[1]{}
\newcommand{\clearfloatsetup}[1]{}
\newcommand*{\killfloatstyle}{}
```

`\newfloatcommand` {⟨*1 command*⟩} {⟨*2 captype*⟩} [⟨*3 preamble*⟩] [⟨*4 default width*⟩]

Preamble and default width are ignored.

```
\NewDocumentCommand{\newfloatcommand}{m m o o}{%
\@namedef{#1}{
\floatbox{#2}
}
}
```

`\renewfloatcommand` {⟨*1 command*⟩} {⟨*2 captype*⟩} [⟨*3 preamble*⟩] [⟨*4 default width*⟩]

Preamble and default width are ignored.

```
\NewDocumentCommand{\renewfloatcommand}{m m o o}{%
\@namedef{#1}{%
\floatbox{#2}
}
}
```

`\ffigbox` [⟨*width*⟩] [⟨*height*⟩] [⟨*vposn*⟩] {⟨*caption commands*⟩} {⟨*contents*⟩}

```
\newfloatcommand{ffigbox}{figure}[\nocapbeside][]
```

`\ttabbox` [⟨*width*⟩] [⟨*height*⟩] [⟨*vposn*⟩] {⟨*caption commands*⟩} {⟨*contents*⟩}

```
\newfloatcommand{ttabbox}{table}[\captop][\FBwidth]
```

`\fcapside` [⟨*width*⟩] [⟨*height*⟩] [⟨*vposn*⟩] {⟨*caption commands*⟩} {⟨*contents*⟩}

```
\newfloatcommand{fcapside}{figure}[\capbeside][]
```

Env `floatrow` [⟨*numfloats*⟩]

The row of floats is placed into a `<div>` of class `floatrow`.

```
\newenvironment*{floatrow}[1][2]
{%
    \begin{LWR@setvirtualpage}*%
    \BlockClass{floatrow}%
}
{
    \endBlockClass%
    \end{LWR@setvirtualpage}%
}
```

Keys for `\DeclareNewFloatType`:

```
\newcommand*{\LWR@frowkeyplacement}{}
\newcommand*{\LWR@frowkeyname}{}
\newcommand*{\LWR@frowkeyfileext}{}
\newcommand*{\LWR@frowkeywithin}{}
\newcommand*{\LWR@frowkeycapstyle}{}

\define@key{frowkeys}{placement}{}%
\define@key{frowkeys}{name}{\renewcommand{\LWR@frowkeyname}{#1}}%
\define@key{frowkeys}{fileext}{\renewcommand{\LWR@frowkeyfileext}{#1}}%
\define@key{frowkeys}{within}{\renewcommand{\LWR@frowkeywithin}{#1}}%
\define@key{frowkeys}{relatedcapstyle}{}%
```

`\DeclareNewFloatType` {⟨*type*⟩} {⟨*options*⟩}

Use `\listof{type}{Title}` to print a list of the floats.

```
\newcommand*{\DeclareNewFloatType}[2]{%
```

Reset key values:

```
\renewcommand*{\LWR@frowkeyplacement}{}%
\renewcommand*{\LWR@frowkeyname}{}%
\renewcommand*{\LWR@frowkeyfileext}{}%
\renewcommand*{\LWR@frowkeywithin}{}%
\renewcommand*{\LWR@frowkeycapstyle}{}%
```

Read new key values:

```
\LWR@traceinfo{about to setkeys frowkeys}%
\setkeys{frowkeys}{#2}%
\LWR@traceinfo{finished setkeys frowkeys}%
```

Create a new float with optional [within]:

```
\ifthenelse{\equal{\LWR@frowkeywithin}{}}%
{%
    \DeclareFloatingEnvironment[
        placement=\LWR@frowkeyplacement,
        fileext=\LWR@frowkeyfileext
    ]{#1}%
}%
{%
    \DeclareFloatingEnvironment[
        placement=\LWR@frowkeyplacement,
        fileext=\LWR@frowkeyfileext,
        within=\LWR@frowkeywithin
    ]{#1}%
%     \LWR@traceinfo{finished newfloat #1}%
}%
```

Rename the float if a name was given:

```
\ifthenelse{\equal{\LWR@frowkeyname}{}}%
    {}%
    {%
        \SetupFloatingEnvironment{#1}{name={\LWR@frowkeyname}}%
    }%
}
```

Not used:

```
\newcommand{\buildFBBOX}[2]{}
\newcommand*{\CenterFloatBoxes}{}
\newcommand*{\TopFloatBoxes}{}
\newcommand*{\BottomFloatBoxes}{}
\newcommand*{\PlainFloatBoxes}{}

\newcommand{\capsubrowsettings}{}

\NewDocumentCommand{\RawFloats}{o o}{}
```

`\RawCaption` `{`⟨*text*⟩`}`

To be used inside a minipage or parbox.

```
\newcommand{\RawCaption}[1]{#1}
```

`\floatfoot` `{`⟨*text*⟩`}`

Places additional text inside a float, inside a css `<div>` of class `floatfoot`.

```
\NewDocumentCommand{\floatfoot}{s +m}{%
    \begin{BlockClass}{floatfoot}
    #2
    \end{BlockClass}
}
```

Used to compute `\linewidth`.

```
\newbool{LWR@insubfloatrow}
\boolfalse{LWR@insubfloatrow}
```

Env `subfloatrow` `[`⟨*num_floats*⟩`]`

```
\newenvironment*{subfloatrow}[1][2]
{
```

The row of floats is placed into a `<div>` of class `floatrow`:

```
    \LWR@forcenewpage
    \BlockClass{floatrow}
```

While inside the floatrow, `LWR@insubfloatrow` is set true, which tells `\floatbox` to use `\subfigure` or `\subtable`.

```
    \begingroup%
    \booltrue{LWR@insubfloatrow}%
}
{%
    \endgroup%
    \endBlockClass%
    \boolfalse{LWR@insubfloatrow}%
}
```

---

File 164 **lwarp-fltrace.sty**

§ 271 Package

# fltrace

Pkg fltrace fltrace is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{fltrace}[2018/01/08]

\def\tracefloats{}
\def\tracefloatsoff{}
\def\tracefloatvals{}
```

---

File 165 **lwarp-flushend.sty**

§ 272 Package

# flushend

(*Emulates or patches code by* Sigitas Tolušis.)

Pkg flushend flushend is ignored.

**for HTML output:** Discard all options for lwarp-flushend:

```
\LWR@ProvidesPackageDrop{flushend}[2017/03/27]

\newcommand*{\flushend}{}
\newcommand*{\raggedend}{}
\newcommand*{\flushcolsend}{}
\newcommand*{\raggedcolsend}{}
\newcommand*{\atColsBreak}[1]{}
\newcommand*{\atColsEnd}[1]{}
\newcommand*{\showcolsendrule}{}
```

---

File 166 **lwarp-fnbreak.sty**

§ 273 Package

# fnbreak

Pkg fnbreak fnbreak is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{fnbreak}[2012/01/01]

\newcommand*{\fnbreakverbose}{}
\newcommand*{\fnbreaknonverbose}{}
\newcommand*{\fnbreaklabel}{}
\newcommand*{\fnbreaknolabel}{}
```

---

File 167 **lwarp-fncychap.sty**

§ 274 Package

# fncychap

(*Emulates or patches code by* Ulf A. Lindgren.)

## § 277 Package fnpos

(*Emulates or patches code by* Hiroshi Nakashima.)

Pkg fnpos fnpos is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{fnpos}[1999/07/14]

\newcommand*{\makeFNbottom}{}
\newcommand*{\makeFNmid}{}
\newcommand*{\makeFNbelow}{}
\newcommand*{\makeFNabove}{}
```

---

File 171 **lwarp-fontawesome.sty**

## § 278 Package fontawesome

(*Emulates or patches code by* Xavier Danaux.)

Pkg fontawesome fontawesome is patched for use by lwarp.

Hashed inline images are used, as there may not be Unicode support for all icons.

⚠ *poppler* syntax warning If using pdfLaTeX, *poppler* may issue a syntax warning regarding parsing a ligature component. XeLaTeX or LuaLaTeX may be used to avoid this warning.

In the following, the general strategy is to intercept `\symbol` and embed it inside a `lateximage`. These changes are done inside a local group.

For pdfLaTeX, the `alt` tag includes the icon (symbol) number. For XeLaTeX and LuaLaTeX, the `alt` tag is generic.

**for HTML output:**

```
\LWR@ProvidesPackagePass{fontawesome}[2016/05/15]

\LetLtxMacro\LWR@orig@symbol\symbol

\ifxetexorluatex

\newfontfamily{\LWR@orig@FA}{FontAwesome}

\newcommand*{\LWR@fontawesome@xelatex@symbol}[1]{%
    \LWR@findcurrenttextcolor%
   \begin{lateximage}*[icon][fontawesomexetex#1SZ\LWR@font@size{}CL\LWR@tempcolor]%
    \csuse{\LWR@font@size}%
    \LWR@orig@FA%
    \LWR@orig@symbol{#1}%
    \end{lateximage}%
}

\RenewDocumentCommand{\FA}{}{%
    \LetLtxMacro\symbol\LWR@fontawesome@xelatex@symbol%
}

```

```
\else

\newcommand*{\LWR@fontawesome@symbolX}[2]{%
    \LWR@findcurrenttextcolor%
   \begin{lateximage}*[icon #1][fontawesome#2#1SZ\LWR@font@size{}CL\LWR@tempcolor]%
    \csuse{\LWR@font@size}%
    \fontencoding{U}\fontfamily{fontawesome#2}\selectfont%
    \LWR@orig@symbol{#1}%
    \end{lateximage}%
}

\newcommand*{\LWR@fontawesome@symbolone}[1]{%
    \LWR@fontawesome@symbolX{#1}{one}%
}

\newcommand*{\LWR@fontawesome@symboltwo}[1]{%
    \LWR@fontawesome@symbolX{#1}{two}%
}

\newcommand*{\LWR@fontawesome@symbolthree}[1]{%
    \LWR@fontawesome@symbolX{#1}{three}%
}

\renewrobustcmd\FAone{%
    \LetLtxMacro\symbol\LWR@fontawesome@symbolone%
}

\renewrobustcmd\FAtwo{%
    \LetLtxMacro\symbol\LWR@fontawesome@symboltwo%
}

\renewrobustcmd\FAthree{%
    \LetLtxMacro\symbol\LWR@fontawesome@symbolthree%
}
\fi
```

---

File 172 **lwarp-fontawesome5.sty**

# § 279 Package fontawesome5

(*Emulates or patches code by* Marcel Krüger.)

Pkg fontawesome5 fontawesome5 is patched for use by lwarp.

Hashed inline images are used, as there may not be Unicode support for all icons.

The `alt` tag has the name of the icon.

**for HTML output:**

```
\LWR@ProvidesPackagePass{fontawesome5}[2018/07/27]

\ExplSyntaxOn
\cs_set:Nn\fontawesome_use_icon:nn{
    \LWR@findcurrenttextcolor
```

```
\cs_if_exist:cTF{c__fontawesome_slot_#2_tl}{
  \begin{lateximage}*[#2][fontawesome5#1SZ\LWR@font@size{}CL\LWR@tempcolor]
  \csuse{\LWR@font@size}
  \exp_last_unbraced:Nv
    \__fontawesome_icon_at:nnnn
    {c__fontawesome_slot_#2_tl}
      {#1}{#2}
  \end{lateximage}
}{
  \msg_error:nnxx{fontawesome5}{icon-not-found}{#2}{#1}
}
}
\ExplSyntaxOff
```

File 173 **lwarp-fontaxes.sty**

## § 280 Package fontaxes

(*Emulates or patches code by* Andreas Bühmann, Michael Ummels.)

Pkg fontaxes fontaxes is emulated for HTML, and used as-is for print output.

Functionality for small caps is in the lwarp core. Swashes and figure styles are ignored for HTML.

**for HTML output:**

```
\LWR@ProvidesPackagePass{fontaxes}[2014/03/23]

\ifdef{\LWR@HTML@swshape}{}{% duplicated by nfssext-cfr
    \newcommand{\LWR@HTML@swshape}{}
    \LWR@formatted{swshape}

    \newrobustcmd{\LWR@HTML@textsw}[1]{#1}
    \LWR@formatted{textsw}

    \FilenameNullify{%
        \LetLtxMacro\swshape\@empty%
        \LetLtxMacro\textsw\firstofone%
    }
}
```

File 174 **lwarp-fontenc.sty**

## § 281 Package fontenc

Pkg fontenc If using pdfLaTeX, lwarp used to require fontenc be loaded before lwarp, but now lwarp itself loads \fontenc with T1 encoding, which lwarp requires. fontenc is now allowed to be loaded with another encoding after lwarp.

lwarp-fontenc is no longer necessary, but is still provided to overwrite older versions.

**for HTML output:**

```
\LWR@ProvidesPackagePass{fontenc}[2017/04/05]
```

File 175 **lwarp-footmisc.sty**

§ 282 Package

# footmisc

(*Emulates or patches code by* Robin Fairbairns.)

Pkg footmisc footmisc is emulated.

lwarp incidentally happens to emulate the `stable` option.

```
\LWR@ProvidesPackageDrop{footmisc}[2011/06/06]
```

Some nullified commands:

```
\newcommand{\footnotelayout}{}
\newcommand{\setfnsymbol}[1]{}
\NewDocumentCommand{\DefineFNsymbols}{s m o m}{}

\newdimen\footnotemargin
\footnotemargin1.8em\relax

\newcommand*\hangfootparskip{0.5\baselineskip}
\newcommand*\hangfootparindent{0em}%

\let\pagefootnoterule\footnoterule
\let\mpfootnoterule\footnoterule
\def\splitfootnoterule{\kern-3\p@ \hrule \kern2.6\p@}

\providecommand*{\multiplefootnotemarker}{3sp}
\providecommand*{\multfootsep}{,}
```

Using cleveref. `\labelcref` only prints the number of the object, not its type.

```
\providecommand*{\footref}[1]{\labelcref{#1}}
```

The following work as-is:

```
\newcommand\mpfootnotemark{%
  \@ifnextchar[%
    \@xmpfootnotemark%
    {%
      \stepcounter\@mpfn%
      \protected@xdef\@thefnmark{\thempfn}%
      \@footnotemark%
    }%
}
\def\@xmpfootnotemark[#1]{%
  \begingroup%
    \csname c@\@mpfn\endcsname #1\relax%
    \unrestored@protected@xdef\@thefnmark{\thempfn}%
  \endgroup%
```

```
  \@footnotemark%
}
```

File 176 **lwarp-footnote.sty**

§ 283 Package

# footnote

(*Emulates or patches code by* Mark Wooding.)

Pkg footnote footnote is used with minor patches.

**for HTML output:**

```
\LWR@ProvidesPackagePass{footnote}[1997/01/28]
```

Removed print-version formatting:

```
\def\fn@startnote{%
%   \@parboxrestore%
  \protected@edef\@currentlabel{\csname p@\@mpfn\endcsname\@thefnmark}%
%   \color@begingroup% *** conflicts with lwarp
}

% \let\fn@endnote\color@endgroup% *** conflicts with lwarp
\def\fn@endnote{%
\LWR@htmltagc{/\LWR@tagregularparagraph}%
\LWR@orignewline%
}
```

Removed print-version formatting:

```
\def\fn@startfntext{%
  \setbox\z@\vbox\bgroup%
    \fn@startnote%
    \ignorespaces%
}
```

Removed print-version formatting, added closing paragraph tag:

```
\def\fn@endfntext{%
    \LWR@htmltagc{/\LWR@tagregularparagraph}%
    \LWR@orignewline%
  \egroup%
  \begingroup%
    \let\@makefntext\@empty%
    \let\@finalstrut\@gobble%
    \LetLtxMacro\rule\@gobbletwo% *8* also the optional argument?
    \@footnotetext{\unvbox\z@}%
  \endgroup%
}
```

These have been redefined, so re-`\let` them again:

```
\let\endfootnote\fn@endfntext
\let\endfootnotetext\endfootnote
```

File 177 **lwarp-footnotebackref.sty**

§ 284 Package footnotebackref

Pkg footnotebackref footnotebackref is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{footnotebackref}[2012/07/01]
```

File 178 **lwarp-footnotehyper.sty**

§ 285 Package footnotehyper

Pkg footnotehyper footnotehyper is a hyperref-safe version of footnote. For lwarp, footnotehyper is emulated.

**for HTML output:** Discard all options for lwarp-footnotehyper:

```
\RequirePackage{footnote}
\LWR@ProvidesPackageDrop{footnotehyper}[2018/01/23]
```

File 179 **lwarp-footnoterange.sty**

§ 286 Package footnoterange

(*Emulates or patches code by* H.-Martin Münch.)

Pkg footnoterange footnoterange is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{footnoterange}[2012/02/17]

\csletcs{footnoterange}{footnoterange*}
\csletcs{endfootnoterange}{endfootnoterange*}
```

File 180 **lwarp-footnpag.sty**

§ 287 Package footnpag

Pkg footnpag footnpag is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{footnpag}
```

File 181 **lwarp-foreign.sty**

New in v1.1a:

```
\define@key{igraph}{quite}{}
\define@key{igraph}{page}{}
\define@key{igraph}{pagebox}{}
\define@key{igraph}{interpolate}[true]{}
```

New in v1.1b:

```
\define@key{igraph}{decodearray}{}
```

## § 308.3 Printing HTML styles

`\LWR@rotstyle` {⟨*prefix*⟩} {⟨*degrees*⟩}

Prints the rotate style with the given prefix.

`prefix` is `-ms-` or `-webkit-` or nothing, and is used to generate three versions of the `transform:rotate` style.

```
\newcommand*{\LWR@rotstyle}[2]{%
    \edef\LWR@tempone{#2}%
    \setcounter{LWR@tempcountone}{-1*\real{\LWR@tempone}} % space
    #1transform:rotate(\arabic{LWR@tempcountone}deg); % space
}
```

`\LWR@scalestyle` {⟨*prefix*⟩} {⟨*xscale*⟩} {⟨*yscale*⟩}

Prints the scale style with the given prefix.

`prefix` is `-ms-` or `-webkit-` or nothing, and is used to generate three versions of the `transform:scale` style.

```
\newcommand*{\LWR@scalestyle}[3]{%
    #1transform:scale(#2,#3);
}
```

## § 308.4 `\includegraphics`

`\LWR@opacity` For HTML, used only for `\includegraphics`.

`\LWR@opacity` may be set by the transparent package.

```
\def\LWR@opacity{1}
```

`\LWR@imagesizebox` Used to determine the actual image size if needed.

```
\newsavebox{\LWR@imagesizebox}
```

`\LWR@HTML@Gin@setfile` {⟨*w*⟩} {⟨*h*⟩} {⟨*filename*⟩} Sets the parsed filename for HTML output.

```
\newcommand*{\LWR@HTML@Gin@setfile}[3]{%
    \xdef\LWR@parsedfilename{#3}%
}
```

Key [Gin] `class` CSS class for the image.

Define the new class key for the print-mode version of `\includegraphics`, which is enabled inside a `lateximage`.

```
\AtBeginDocument{
\define@key{Gin}{class}{}
\define@key{Gin}{alt}{}
}
```

\LWR@replaceEPSSVG

Usually, references to EPS files become SVG files, but if the epstopdf package is being used, it automatically converts EPS to PDF, and the following must NOT be done.

```
\AtBeginDocument{
\@ifpackageloaded{epstopdf}
{
    \newcommand*{\LWR@replaceEPSSVG}{}
}{%
    \newcommand*{\LWR@replaceEPSSVG}{%
        \StrSubstitute{\LWR@tempone}{.eps}{.svg}[\LWR@tempone]%
        \StrSubstitute{\LWR@tempone}{.EPS}{.SVG}[\LWR@tempone]%
    }
}%
}
```

\LWR@ig@wpimagesizes * [⟨*2: options*⟩] [⟨*3: options*⟩] {⟨*4: filename*⟩}

If formatting for a word processor, find and set the actual image size, without rotation, using PDF instead of SVG to find the original bounding box:

```
\newcommand*{\LWR@ig@wpimagesizes}[4]{%
    \ifbool{FormatWP}{%
        \begingroup%
        \LWR@restoreorigformatting%
        \ifpdf%
        \appto\LWR@restoreorigformatting{%
            \DeclareGraphicsExtensions{%
                .pdf,.PDF,.gif,.GIF,.png,.PNG,.jpg,.JPG,.jpeg,.JPEG%
            }%
        }%
        \else% \ifpdf
                \ifXeTeX%
        \appto\LWR@restoreorigformatting{%
            \DeclareGraphicsExtensions{%
                .pdf,.PDF,.gif,.GIF,.png,.PNG,.jpg,.JPG,.jpeg,.JPEG%
            }%
        }%
                \else%
        \appto\LWR@restoreorigformatting{%
            \DeclareGraphicsExtensions{%
                .eps,.EPS,.gif,.GIF,.png,.PNG,.jpg,.JPG,.jpeg,.JPEG%
            }%
        }%
                \fi%
        \fi% \ifpdf
        \define@key{Gin}{angle}{}%
        \IfBooleanTF{#1}%
        {% starred
            \IfValueTF{#3}%
```

```
            {%
                \global\sbox{\LWR@imagesizebox}{%
                    \LWR@origincludegraphics*[#2][#3]{#4}%
                }%
            }%
            {%
                \IfValueTF{#2}%
                {%
                    \global\sbox{\LWR@imagesizebox}{%
                        \LWR@origincludegraphics*[#2]{#4}%
                    }%
                }{%
                    \global\sbox{\LWR@imagesizebox}{%
                        \LWR@origincludegraphics*{#4}%
                    }%
                }%
            }%
        }% starred
        {% not starred
            \IfValueTF{#3}%
            {%
                \global\sbox{\LWR@imagesizebox}{%
                    \LWR@origincludegraphics[#2][#3]{#4}%
                }%
            }%
            {%
                \IfValueTF{#2}%
                {%
                    \global\sbox{\LWR@imagesizebox}{%
                        \LWR@origincludegraphics[#2]{#4}%
                    }%
                }{%
                    \global\sbox{\LWR@imagesizebox}{%
                        \LWR@origincludegraphics{#4}%
                    }%
                }%
            }%
        }% not starred
        \endgroup%
        \settowidth{\LWR@igwidth}{\usebox{\LWR@imagesizebox}}%
        \global\renewcommand*{\LWR@igwidthstyle}{%
            width:\LWR@printlength{\LWR@igwidth}%
        }%
        \settoheight{\LWR@igheight}{\usebox{\LWR@imagesizebox}}%
        \global\renewcommand*{\LWR@igheightstyle}{%
            height:\LWR@printlength{\LWR@igheight}%
        }%
    }{}% FormatWP
}
```

\LWR@ig@htmltag For the HTML reference, add the graphicspath, filename, extension, alt tag, style, and class.

```
\newcommand*{\LWR@ig@htmltag}{%
    img\LWR@indentHTML%
```

```
    src=\textquotedbl%
    \detokenize\expandafter{\LWR@parsedfilename}%
    \textquotedbl\LWR@indentHTML%
```

Only include a style tag if a width, height, angle, or scale was given:

```
    \ifthenelse{
        \NOT\equal{\LWR@igwidthstyle}{} \OR
        \NOT\equal{\LWR@igheightstyle}{} \OR
        \NOT\equal{\LWR@igorigin}{} \OR
        \NOT\equal{\LWR@igangle}{} \OR
        \NOT\equal{\LWR@igxscale}{1} \OR
        \NOT\equal{\LWR@igyscale}{1}
    }%
    {%
        style=\textquotedbl\LWR@indentHTML
        \ifthenelse{\NOT\equal{\LWR@igwidthstyle}{}}%
            {\LWR@igwidthstyle;\LWR@indentHTML}{}%
        \ifthenelse{\NOT\equal{\LWR@igheightstyle}{}}%
            {\LWR@igheightstyle;\LWR@indentHTML}{}%
        \ifthenelse{\NOT\equal{\LWR@igorigin}{}}%
            {%
                transform-origin: \LWR@originnames{\LWR@igorigin};%
                \LWR@indentHTML%
            }{}%
        \ifthenelse{\NOT\equal{\LWR@igangle}{}}%
        {%
            \LWR@rotstyle{-ms-}{\LWR@igangle}\LWR@indentHTML
            \LWR@rotstyle{-webkit-}{\LWR@igangle}\LWR@indentHTML
            \LWR@rotstyle{}{\LWR@igangle }\LWR@indentHTML
        }{}%
        \ifthenelse{%
            \NOT\equal{\LWR@igxscale}{1}\OR%
            \NOT\equal{\LWR@igyscale}{1}%
        }%
        {%
            \LWR@scalestyle{-ms-}{\LWR@igxscale}{\LWR@igyscale}%
            \LWR@indentHTML
            \LWR@scalestyle{-webkit-}{\LWR@igxscale}{\LWR@igyscale}%
            \LWR@indentHTML
            \LWR@scalestyle{}{\LWR@igxscale}{\LWR@igyscale}%
            \LWR@indentHTML
        }{}%
        %
        \ifthenelse{\NOT\equal{\LWR@opacity}{1}}%
            {opacity:\LWR@opacity;\LWR@indentHTML}{}%
        %
        \textquotedbl\LWR@indentHTML%
    }{}%
```

Set the class and alt tag:

```
    class=\textquotedbl\LWR@igclass\textquotedbl\LWR@indentHTML%
   alt=\textquotedbl\AltTextOpen\LWR@igalt\AltTextClose\textquotedbl\ \LWR@orignewline%
}% end of image tags
```

\LWR@includegraphicsb * [⟨2: options⟩] [⟨3: options⟩] {⟨4: filename⟩}

graphics syntax is \includegraphics * [⟨llx,lly⟩] [⟨urx,ury⟩] {⟨file⟩}

graphicx syntax is \includegraphics [⟨key values⟩] {⟨file⟩}

If #3 is empty, only one optional argument was given, thus graphicx syntax.

If using \epsfig or \psfig from the epsfig package, #4 will be \LWR@epsfig@filename, which will have been set by the file or figure keys. Therefore, #4 must not be used until after the keys have been processed.

```
\NewDocumentCommand{\LWR@includegraphicsb}{s o o m}
{%
```

Start the image tag on a new line, allow PDF output word wrap:

```
    \LWR@origtilde \LWR@orignewline%
```

Temporarily compute \linewidth, \textwidth, \textheight arguments with a 6x9 inch size until the next \endgroup.

```
    \begin{LWR@setvirtualpage}%
```

For correct em sizing during the width and height conversions:

```
    \large%
```

Reset some defaults, possibly will be changed below if options were given:

```
    \setlength{\LWR@igwidth}{0pt}%
    \setlength{\LWR@igheight}{0pt}%
    \renewcommand*{\LWR@igwidthstyle}{}%
    \renewcommand*{\LWR@igheightstyle}{}%
    \renewcommand*{\LWR@igorigin}{}%
    \renewcommand*{\LWR@igangle}{}%
    \renewcommand*{\LWR@igxscale}{1}%
    \renewcommand*{\LWR@igyscale}{1}%
    \renewcommand*{\LWR@igclass}{inlineimage}%

    \ifdefvoid{\LWR@ThisAltText}{%
        \edef\LWR@igalt{\ImageAltText}%
    }{%
        \edef\LWR@igalt{\LWR@ThisAltText}%
    }%
```

If #3 is empty, only one optional argument was given, thus graphicx syntax:

```
    \IfValueF{#3}{%
        \IfValueTF{#2}%
            {\setkeys{igraph}{#2}}%
            {\setkeys{igraph}{}}%
    }%
```

Fully expand and detokenize the filename, changing the file extension to .svg if necessary.

```
    \begingroup%
    \LetLtxMacro\Gin@setfile\LWR@HTML@Gin@setfile%
    \edef\LWR@tempone{#4}%
    \StrSubstitute{\LWR@tempone}{.pdf}{.svg}[\LWR@tempone]%
    \StrSubstitute{\LWR@tempone}{.PDF}{.SVG}[\LWR@tempone]%
```

```
    \LWR@replaceEPSSVG%
    \xdef\LWR@parsedfilename{\LWR@tempone}%
    \Ginclude@graphics{\detokenize\expandafter{\LWR@tempone}}%
    \endgroup%
    \filename@parse{\LWR@parsedfilename}%
```

Remove doubled // in the directory path, from the 2020/10/01 LaTeX kernel change.

```
    \StrSubstitute{\LWR@parsedfilename}{//}{/}[\LWR@parsedfilename]%
    \LWR@traceinfo{LWR@parsedfilename is \LWR@parsedfilename}%
```

If formatting for a word processor, find and set the actual image size, without rotation, using PDF instead of SVG to find the original bounding box:

```
    \LWR@ig@wpimagesizes{#1}{#2}{#3}{#4}%
```

Create the HTML reference with the graphicspath, filename, extension, alt tag, style, and class:

```
    \LWR@traceinfo{LWR@includegraphicsb: about to create href}%
    \LWR@href{\LWR@parsedfilename}%
    {% start of href
        \LWR@traceinfo{LWR@includegraphicsb: about to LWR@htmltag}%
        \LWR@htmltag{\LWR@ig@htmltag}%
    }% end of href
```

Return to original page size and font size:

```
    \end{LWR@setvirtualpage}%
```

Clear the single-use `alt` text:

```
    \gdef\LWR@ThisAltText{}%
    \LWR@traceinfo{LWR@includegraphicsb done}%
}
```

`\includegraphics` `[`⟨*key=val*⟩`]` `{`⟨*filename*⟩`}`

Handles width and height, converted to fixed width and heights.

The user should always use no file suffix in the document source.

```
\AtBeginDocument{

\LWR@traceinfo{Patching includegraphics.}

\LetLtxMacro\LWR@origincludegraphics\includegraphics


\renewrobustcmd*{\includegraphics}
{%
```

This graphic should trigger an HTML paragraph even if alone, so ensure that are doing paragraph handling:

```
\LWR@traceinfo{includegraphics}%
\LWR@ensuredoingapar%
\LWR@includegraphicsb%
}% includegraphics
}% AtBeginDocument
```

Select `inline-block` so that HTML will transform this span:

```
\LWR@htmltagc{%
    span\LWR@indentHTML
    style=\textquotedbl\LWR@indentHTML
    display: inline-block;\LWR@indentHTML
```

If an origin was given, translate and print the origin information:

```
    \ifthenelse{\NOT\equal{\LWR@rotboxorigin}{}}%
      {transform-origin: \LWR@originnames{\LWR@rotboxorigin};\LWR@indentHTML}%
        {}%
```

Print the rotation information:

```
    \LWR@rotstyle{-ms-}{#2}\LWR@indentHTML
    \LWR@rotstyle{-webkit-}{#2}\LWR@indentHTML
    \LWR@rotstyle{}{#2}\textquotedbl\LWR@orignewline%
}\LWR@orignewline%
```

Print the text to be rotated:

```
\begin{LWR@nestspan}%
#3%
```

Close the span:

```
\LWR@htmltagc{/span}%
\end{LWR@nestspan}%
}
```

The high-level interface:

```
\LWR@formatted{rotatebox}

}% AtBeginDocument
```

`\scalebox` {⟨*h-scale*⟩} [⟨*v-scale*⟩] {⟨*text*⟩}

```
\AtBeginDocument{
```

The HTML version:

```
\NewDocumentCommand{\LWR@HTML@scalebox}{m o m}{%
```

Select `inline-block` so that HTML will transform this span:

```
\LWR@htmltagc{%
    span\LWR@indentHTML
    style=\textquotedbl\LWR@indentHTML
    display: inline-block;\LWR@indentHTML
```

Print the scaling information:

```
    \LWR@scalestyle{-ms-}{#1}{\IfNoValueTF{#2}{#1}{#2}}\LWR@indentHTML
    \LWR@scalestyle{-webkit-}{#1}{\IfNoValueTF{#2}{#1}{#2}}\LWR@indentHTML
    \LWR@scalestyle{}{#1}{\IfNoValueTF{#2}{#1}{#2}}
    \textquotedbl\LWR@orignewline
}\LWR@orignewline%
```

Print the text to be scaled:

```
\begin{LWR@nestspan}%
#3%
```

Close the span:

```
\LWR@htmltagc{/span}%
\end{LWR@nestspan}%
}
```

The high-level interface:

```
\LWR@formatted{scalebox}

}% AtBeginDocument
```

`\reflectbox` {⟨*text*⟩}

```
\AtBeginDocument{

\newcommand{\LWR@HTML@reflectbox}[1]{%
    \scalebox{-1}[1]{#1}%
}% \reflectbox

\LWR@formatted{reflectbox}

}% AtBeginDocument
```

`\resizebox` {⟨*h-length*⟩} {⟨*v-length*⟩} {⟨*text*⟩}

Simply prints its text argument.

```
\AtBeginDocument{

\NewDocumentCommand{\LWR@HTML@resizebox}{s m m m}{%
    #4%
}

\LWR@formatted{resizebox}

}% AtBeginDocument
```

---

File 202 **lwarp-graphicx.sty**

## § 309 Package graphicx

Pkg graphicx graphicx is emulated.

graphicx loads graphics, which also loads lwarp-graphics, which remembers the original graphics definitions for use inside a `latexmage`, and then patches them `\AtBeginDocument` for HTML output.

lwarp-graphics handles the syntax of either graphics or graphicx.

**for HTML output:**

```
1 \LWR@ProvidesPackagePass{graphicx}[2020/09/09]
```

---

File 203 **lwarp-grffile.sty**

## § 310 Package grffile

Pkg grffile grffile is supported as-is. File types known to the browser are displayed, and unknown file types are given a link. Each PDF image for print mode should be accompanied by an SVG, PNG, or JPG version for HTML.

⚠ matching PDF and SVG

lwarp-grffile now exists as a placeholder since grffile used to be emulated by lwarp, and thus older versions of lwarp-grffile may exist and should be overwritten by this newer version.

**for HTML output:**

```
1 \LWR@ProvidesPackagePass{grffile}[2017/06/30]
```

---

File 204 **lwarp-grid.sty**

## § 311 Package grid

Pkg grid grid is ignored.

**for HTML output:**

```
1 \LWR@ProvidesPackageDrop{grid}[2009/06/16]
2 \newenvironment*{gridenv}{}{}
```

---

File 205 **lwarp-grid-system.sty**

## § 312 Package grid-system

(*Emulates or patches code by* Marcus Bitzl.)

Pkg grid-system grid-system is patched for use by lwarp.

**for HTML output:**

```
1 \LWR@ProvidesPackagePass{grid-system}[2014/02/16]
```

(`\ifdef` is in case the older syntax is removed.)

```
\AtBeginEnvironment{Row}{\setlength{\linewidth}{6in}}

\ifdef{\endrow}{
    \AtBeginEnvironment{row}{\setlength{\linewidth}{6in}}
}{}

\renewcommand{\gridsystem@finishcell}{\hspace{\gridsystem@cellsep}}
```

---

File 206 **lwarp-gridset.sty**

# § 313 Package gridset

Pkg gridset gridset is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{gridset}[2020-02-12]

\newcommand*{\gridbase}{}
\newcommand*{\gridinterval}{}
\newcommand*{\SavePos}[1]{}
\ifLuaTeX
\else
\let\savepos\SavePos
\fi
\newcommand*{\vskipnextgrid}{}
\newcommand*{\thegridinfo}[1]{(thegridinfo)}
\newcommand*{\theposinfo}[1]{(theposinfo)}
\newcommand*{\theypos}[1]{(theypos)}
```

---

File 207 **lwarp-hang.sty**

# § 314 Package hang

(*Emulates or patches code by* Andreas Nolda.)

Pkg hang hang is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{hang}[2017/02/18]

\newlength{\hangingindent}
\setlength{\hangingindent}{1em}
\newlength{\hangingleftmargin}
\setlength{\hangingleftmargin}{0em}

\newcommand*{\LWR@findhangingleftmargin}{%
\setlength{\LWR@templengthone}{\hangingleftmargin}%
\addtolength{\LWR@templengthone}{\hangingindent}%
}

```

```
\newenvironment{hangingpar}
{
    \LWR@findhangingleftmargin%
    \BlockClass[%
        \LWR@print@mbox{margin-left:\LWR@printlength{\LWR@templengthone}} ; %
        \LWR@print@mbox{text-indent:-\LWR@printlength{\hangingindent}}%
    ]%
    {hangingpar}%
}
{\endBlockClass}

\newenvironment{hanginglist}
{%
    \renewcommand*{\LWR@printcloselist}{\LWR@printcloseitemize}%
    \renewcommand*{\LWR@printopenlist}{%
        \LWR@findhangingleftmargin%
        ul style=\textquotedbl%
            \LWR@print@mbox{list-style-type:none;} % extra space
            \LWR@print@mbox{%
                margin-left:\LWR@printlength{\LWR@templengthone}%
            } ; % extra space
            \LWR@print@mbox{%
                text-indent:-\LWR@printlength{\hangingindent}%
            }%
        \textquotedbl%
    }%
    \let\item\LWR@itemizeitem%
    \list{}{}%
}
{\endlist}

\newenvironment{compacthang}
{\hanginglist}
{\endhanginglist}

\newlength{\labeledleftmargin}
\setlength{\labeledleftmargin}{0em}

\newenvironment{labeledpar}[2]
{%
    \BlockClass[%
        \LWR@findhangingleftmargin%
        \LWR@print@mbox{margin-left:\LWR@printlength{\LWR@templengthone}} ; %
        \LWR@print@mbox{text-indent:-\LWR@printlength{\hangingindent}}%
    ]{labeledpar}#2%
}
{\endBlockClass}

\newenvironment{labeledlist}[1]
{\hanginglist}
{\endhanginglist}

\newenvironment{compactlabel}[1]
{\hanginglist}
{\endhanginglist}
```

File 208 **lwarp-hanging.sty**

§ 315 Package

# hanging

Pkg hanging hanging is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{hanging}[2009/09/02]

\@ifclassloaded{memoir}{
\let\hangpara\relax
\let\hangparas\relax
\let\endhangparas\relax
\let\hangpunct\relax
\let\endhangpunct\relax
}{}
```

\hangpara {⟨*indent*⟩} {⟨*afternum*⟩}

Use hangparas instead.

```
\newcommand*{\hangpara}[2]{}
```

Env hangparas {⟨*indent*⟩} {⟨*afternum*⟩}

```
\newenvironment*{hangparas}[2]
{%
    \BlockClass[%
        \LWR@print@mbox{margin-left:\LWR@printlength{#1}} ; %
        \LWR@print@mbox{text-indent:-\LWR@printlength{#1}}%
    ]%
    {hangingpar}%
}
{\endBlockClass}
```

Env hangpunct

```
\newenvironment*{hangpunct}
{\BlockClass{hangpunct}}
{\endBlockClass}

\newcommand{\nhpt}{.}
\newcommand{\nhlq}{‘}
\newcommand{\nhrq}{’}
```

File 209 **lwarp-hepunits.sty**

§ 316 Package

# hepunits

(*Emulates or patches code by* Andy Buckley.)

Pkg hepunits hepunits is used as-is, and emulated for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{hepunits}[2020/04/10]

\begin{warpMathJax}
\LWR@infoprocessingmathjax{hepunits}

\ifx\@HEPopt@sicmds\@yes
\CustomizeMathJax{\newcommand{\micron}{\micro\metre}}
\CustomizeMathJax{\newcommand{\mrad}{\milli\radian}}
\fi

\CustomizeMathJax{\newcommand{\gauss}{\mathrm{G}}}

\CustomizeMathJax{\newcommand{\invcmsq}{\centi\metre\tothe{-2}}}
\CustomizeMathJax{\newcommand{\invcmsqpersecond}{\invcmsq\second\tothe{-1}}}
\CustomizeMathJax{\newcommand{\invcmsqpersec}{\invcmsqpersecond}}

%% (Inverse) cross-sections
\CustomizeMathJax{\newcommand{\invbarn}{\barn\tothe{-1}}}

\ifx\@HEPopt@noprefixcmds\@empty
\CustomizeMathJax{\newcommand{\millibarn}{\milli\barn}}
\CustomizeMathJax{\newcommand{\microbarn}{\micro\barn}}
\CustomizeMathJax{\newcommand{\nanobarn}{\nano\barn}}
\CustomizeMathJax{\newcommand{\picobarn}{\pico\barn}}
\CustomizeMathJax{\newcommand{\femtobarn}{\femto\barn}}
\CustomizeMathJax{\newcommand{\attobarn}{\atto\barn}}
\CustomizeMathJax{\newcommand{\zeptobarn}{\zepto\barn}}
\CustomizeMathJax{\newcommand{\yoctobarn}{\yocto\barn}}
\CustomizeMathJax{\newcommand{\invnanobarn}{\nano\invbarn}}
\CustomizeMathJax{\newcommand{\invpicobarn}{\pico\invbarn}}
\CustomizeMathJax{\newcommand{\invfemtobarn}{\femto\invbarn}}
\CustomizeMathJax{\newcommand{\invattobarn}{\atto\invbarn}}
\CustomizeMathJax{\newcommand{\invzeptobarn}{\zepto\invbarn}}
\CustomizeMathJax{\newcommand{\invyoctobarn}{\yocto\invbarn}}
\CustomizeMathJax{\newcommand{\invnb}{\invnanobarn}}
\CustomizeMathJax{\newcommand{\invpb}{\invpicobarn}}
\CustomizeMathJax{\newcommand{\invfb}{\invfemtobarn}}
\CustomizeMathJax{\newcommand{\invab}{\invattobarn}}
\CustomizeMathJax{\newcommand{\invzb}{\invzeptobarn}}
\CustomizeMathJax{\newcommand{\invyb}{\invyoctobarn}}
\fi

\CustomizeMathJax{\newcommand{\electronvoltc}{\electronvolt\per\mathit{c}}}
\CustomizeMathJax{\newcommand{\electronvoltcsq}{\electronvolt\per\mathit{c}\squared}}
\CustomizeMathJax{\let\eVc\electronvoltc}
\CustomizeMathJax{\let\eVcsq\electronvoltcsq}

\ifx\@HEPopt@noprefixcmds\@empty
\CustomizeMathJax{\newcommand{\meV}{\milli\eV}}
\CustomizeMathJax{\newcommand{\keV}{\kilo\eV}}
\CustomizeMathJax{\newcommand{\MeV}{\mega\eV}}
\CustomizeMathJax{\newcommand{\GeV}{\giga\eV}}
\CustomizeMathJax{\newcommand{\TeV}{\tera\eV}}
\CustomizeMathJax{\newcommand{\meVc}{\milli\eVc}}
```

```
\CustomizeMathJax{\newcommand{\keVc}{\kilo\eVc}}
\CustomizeMathJax{\newcommand{\MeVc}{\mega\eVc}}
\CustomizeMathJax{\newcommand{\GeVc}{\giga\eVc}}
\CustomizeMathJax{\newcommand{\TeVc}{\tera\eVc}}
\CustomizeMathJax{\newcommand{\meVcsq}{\milli\eVcsq}}
\CustomizeMathJax{\newcommand{\keVcsq}{\kilo\eVcsq}}
\CustomizeMathJax{\newcommand{\MeVcsq}{\mega\eVcsq}}
\CustomizeMathJax{\newcommand{\GeVcsq}{\giga\eVcsq}}
\CustomizeMathJax{\newcommand{\TeVcsq}{\tera\eVcsq}}
\fi
\end{warpMathJax}
```

---

File 210 **lwarp-hhline.sty**

## § 317 Package hhline

(*Emulates or patches code by* David Carlisle.)

Pkg hhline hhline is patched for use by lwarp.

Only a rudimentary emulation is provided so far. If the argument contains any = characters, the result is a double \hline. If none, the result is a single \hline.

**for HTML output:**

```
\LWR@ProvidesPackagePass{hhline}[2014/10/28]

\newrobustcmd*{\LWR@HTML@hhline}[1]{%
    \edef\LWR@tempone{\detokenize\expandafter{#1}}%
    \IfSubStr[1]{\LWR@tempone}{=}{\hline\hline}{\hline}%
}
% ^^A or:
% ^^A \newrobustcmd*{\LWR@HTML@hhline}[1]{\LWR@getmynexttoken}

\AtBeginDocument{\LWR@expandableformatted{hhline}}
```

For MathJax. A simple \hline is used.

```
\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\hhline}[1]{\hline}}
\end{warpMathJax}
```

---

File 211 **lwarp-hhtensor.sty**

## § 318 Package hhtensor

(*Emulates or patches code by* Harald Harders.)

Pkg hhtensor hhtensor is used as-is, and emulated for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{hhtensor}[2011/12/29]
```

```
\begin{warpMathJax}
\iftensor@bold
  \CustomizeMathJax{\newcommand{\vec}[1]{\boldsymbol{#1}}}
  \CustomizeMathJax{\newcommand{\matr}[1]{\boldsymbol{#1}}}
  \CustomizeMathJax{\newcommand{\tens}[2]{\boldsymbol{#1}}}
\else
  \iftensor@uline
    \CustomizeMathJax{\newcommand{\vec}[1]{\ushort{#1}}}
    \CustomizeMathJax{\newcommand{\matr}[1]{\ushortd{#1}}}
    \CustomizeMathJax{\newcommand{\tens}[2]{
        \underset{
            \raise{.5ex}{\underset{#2}{\sim}}
        }{#1}
    }}
  \else
    \CustomizeMathJax{\newcommand{\matr}[1]{\vec{\vec{#1}}}}
    \CustomizeMathJax{\newcommand{\tens}[2]{
        \underset{
            \raise{.5ex}{\underset{#2}{\sim}}
        }{#1}
    }}
  \fi
\fi
\CustomizeMathJax{\newcommand{\dcdot}{\mathrel{\cdot\mkern 0.0mu \cdot}}}
\CustomizeMathJax{\newcommand{\trans}{{}^{\mathrm{T}}}}
\end{warpMathJax}
```

---

File 212 **lwarp-hypbmsec.sty**

# § 319 Package hypbmsec

Pkg hypbmsec hypbmsec is emulated by the lwarp core.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{hypbmsec}[2016/05/16]
```

---

File 213 **lwarp-hypcap.sty**

# § 320 Package hypcap

Pkg hypcap hypcap is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{hypcap}[2016/05/16]
```

```
\newcommand*{\capstart}{}
\newcommand*{\hypcapspace}{}
\newcommand*{\hypcapredef}[1]{}
\newcommand*{\capstartfalse}{}
\newcommand*{\capstarttrue}{}
```

File 214 **lwarp-hypdestopt.sty**

# § 321 Package hypdestopt

Pkg hypdestopt hypdestopt is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{hypdestopt}[2016/05/21]
```

File 215 **lwarp-hypernat.sty**

# § 322 Package hypernat

Pkg hypernat hypernat is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{hypernat}[2001/07/09]
```

File 216 **lwarp-hyperref.sty**

# § 323 Package hyperref

(*Emulates or patches code by* Sebastian Rahtz, Heiko Oberdiek, The LaTeX3 Project.)

Pkg hyperref hyperref is emulated.

**for HTML output:**

```
% \LWR@ProvidesPackageDrop{hyperref}% not allowed
% \ProvidesPackage{lwarp-#1-#2}% not allowed
\PackageInfo{lwarp}{%
Using the lwarp HTML version of package ‘hyperref’,\MessageBreak
and discarding options except backref, pagebackref.\MessageBreak
(Not using \protect\ProvidesPackage, so that other packages\MessageBreak
do not attempt to patch lwarp’s version of ‘hyperref’.)\MessageBreak}

\SetupKeyvalOptions{family=LWR@hyperref,prefix=LWR@hyperref@}

\newcommand{\hypersetup}[1]{\setkeys{LWR@hyperref}{#1}}

\define@key{LWR@hyperref}{a4paper}[]{}
\define@key{LWR@hyperref}{a5paper}[]{}
\define@key{LWR@hyperref}{b5paper}[]{}
\define@key{LWR@hyperref}{letterpaper}[]{}
\define@key{LWR@hyperref}{legalpaper}[]{}
\define@key{LWR@hyperref}{executivepaper}[]{}
\define@key{LWR@hyperref}{implicit}[]{}
\define@key{LWR@hyperref}{draft}[]{}
\define@key{LWR@hyperref}{final}[]{}
\define@key{LWR@hyperref}{setpagesize}[]{}
```

```
\define@key{LWR@hyperref}{debug}[]{}
\define@key{LWR@hyperref}{linktocpage}[]{}
\define@key{LWR@hyperref}{linktoc}[]{}
\define@key{LWR@hyperref}{extension}[]{}
\define@key{LWR@hyperref}{verbose}[]{}
\define@key{LWR@hyperref}{typexml}[]{}
\define@key{LWR@hyperref}{raiselinks}[]{}
\define@key{LWR@hyperref}{breaklinks}[]{}
\define@key{LWR@hyperref}{localanchorname}[]{}
\define@key{LWR@hyperref}{pageanchor}[]{}
\define@key{LWR@hyperref}{plainpages}[]{}
\define@key{LWR@hyperref}{naturalnames}[]{}
\define@key{LWR@hyperref}{hypertexnames}[]{}
\define@key{LWR@hyperref}{nesting}[]{}
\define@key{LWR@hyperref}{destlabel}[]{}
\define@key{LWR@hyperref}{unicode}[]{}
\define@key{LWR@hyperref}{pdfencoding}[]{}
\define@key{LWR@hyperref}{psdextra}[]{}
\define@key{LWR@hyperref}{pdfversion}[]{}
\define@key{LWR@hyperref}{dvipdfmx-outline-open}[]{}
\define@key{LWR@hyperref}{driverfallback}[]{}
\define@key{LWR@hyperref}{customdriver}[]{}
\define@key{LWR@hyperref}{hyperfigures}[]{}
\define@key{LWR@hyperref}{hyperfootnotes}[]{}
\define@key{LWR@hyperref}{hyperindex}[]{}
\define@key{LWR@hyperref}{encap}[]{}
\define@key{LWR@hyperref}{colorlinks}[]{}
\define@key{LWR@hyperref}{ocgcolorlinks}[]{}
\define@key{LWR@hyperref}{frenchlinks}[]{}
\define@key{LWR@hyperref}{bookmarks}[]{}
\define@key{LWR@hyperref}{bookmarksopen}[]{}
\define@key{LWR@hyperref}{bookmarksdepth}[]{}
\define@key{LWR@hyperref}{bookmarksopenlevel}[]{}
\define@key{LWR@hyperref}{bookmarkstype}[]{}
\define@key{LWR@hyperref}{bookmarksnumbered}[]{}
\define@key{LWR@hyperref}{CJKbookmarks}[]{}
\define@key{LWR@hyperref}{link}[]{}
\define@key{LWR@hyperref}{anchor}[]{}
\define@key{LWR@hyperref}{cite}[]{}
\define@key{LWR@hyperref}{file}[]{}
\define@key{LWR@hyperref}{url}[]{}
\define@key{LWR@hyperref}{menu}[]{}
\define@key{LWR@hyperref}{run}[]{}
\define@key{LWR@hyperref}{linkbordercolor}[]{}
\define@key{LWR@hyperref}{anchorbordercolor}[]{}
\define@key{LWR@hyperref}{citebordercolor}[]{}
\define@key{LWR@hyperref}{filebordercolor}[]{}
\define@key{LWR@hyperref}{urlbordercolor}[]{}
\define@key{LWR@hyperref}{menubordercolor}[]{}
\define@key{LWR@hyperref}{runbordercolor}[]{}
\define@key{LWR@hyperref}{pagecolor}[]{}
\define@key{LWR@hyperref}{baseurl}[]{}
\define@key{LWR@hyperref}{linkfileprefix}[]{}
\define@key{LWR@hyperref}{pdfpagetransition}[]{}
\define@key{LWR@hyperref}{pdfpageduration}[]{}
```

```
\define@key{LWR@hyperref}{pdfpagehidden}[]{}
\define@key{LWR@hyperref}{pagebordercolor}[]{}
\define@key{LWR@hyperref}{allbordercolors}[]{}
\define@key{LWR@hyperref}{pdfhighlight}[]{}
\define@key{LWR@hyperref}{pdfborder}[]{}
\define@key{LWR@hyperref}{pdfborderstyle}[]{}
\define@key{LWR@hyperref}{pdfprintpagerange}[]{}
\define@key{LWR@hyperref}{pdfusetitle}[]{}
\define@key{LWR@hyperref}{pdftitle}[]{}
\define@key{LWR@hyperref}{pdfauthor}[]{}
\define@key{LWR@hyperref}{pdfproducer}[]{}
\define@key{LWR@hyperref}{pdfcreator}[]{}
\define@key{LWR@hyperref}{addtopdfcreator}[]{}
\define@key{LWR@hyperref}{pdfcreationdate}[]{}
\define@key{LWR@hyperref}{pdfmoddate}[]{}
\define@key{LWR@hyperref}{pdfsubject}[]{}
\define@key{LWR@hyperref}{pdfkeywords}[]{}
\define@key{LWR@hyperref}{pdftrapped}[]{}
\define@key{LWR@hyperref}{pdfinfo}[]{}
\define@key{LWR@hyperref}{pdfview}[]{}
\define@key{LWR@hyperref}{pdflinkmargin}[]{}
\define@key{LWR@hyperref}{pdfstartpage}[]{}
\define@key{LWR@hyperref}{pdfstartview}[]{}
\define@key{LWR@hyperref}{pdfremotestartview}[]{}
\define@key{LWR@hyperref}{pdfpagescrop}[]{}
\define@key{LWR@hyperref}{pdftoolbar}[]{}
\define@key{LWR@hyperref}{pdfmenubar}[]{}
\define@key{LWR@hyperref}{pdfwindowui}[]{}
\define@key{LWR@hyperref}{pdffitwindow}[]{}
\define@key{LWR@hyperref}{pdfcenterwindow}[]{}
\define@key{LWR@hyperref}{pdfdisplaydoctitle}[]{}
\define@key{LWR@hyperref}{pdfa}[]{}
\define@key{LWR@hyperref}{pdfnewwindow}[]{}
\define@key{LWR@hyperref}{pdflang}[]{}
\define@key{LWR@hyperref}{pdfpagelabels}[]{}
\define@key{LWR@hyperref}{pdfescapeform}[]{}
\define@key{LWR@hyperref}{english}[]{}
\define@key{LWR@hyperref}{UKenglish}[]{}
\define@key{LWR@hyperref}{british}[]{}
\define@key{LWR@hyperref}{USenglish}[]{}
\define@key{LWR@hyperref}{american}[]{}
\define@key{LWR@hyperref}{german}[]{}
\define@key{LWR@hyperref}{austrian}[]{}
\define@key{LWR@hyperref}{ngerman}[]{}
\define@key{LWR@hyperref}{naustrian}[]{}
\define@key{LWR@hyperref}{russian}[]{}
\define@key{LWR@hyperref}{brazil}[]{}
\define@key{LWR@hyperref}{brazilian}[]{}
\define@key{LWR@hyperref}{portuguese}[]{}
\define@key{LWR@hyperref}{spanish}[]{}
\define@key{LWR@hyperref}{catalan}[]{}
\define@key{LWR@hyperref}{afrikaans}[]{}
\define@key{LWR@hyperref}{french}[]{}
\define@key{LWR@hyperref}{frenchb}[]{}
\define@key{LWR@hyperref}{francais}[]{}
```

```
\define@key{LWR@hyperref}{acadian}[]{}
\define@key{LWR@hyperref}{canadien}[]{}
\define@key{LWR@hyperref}{italian}[]{}
\define@key{LWR@hyperref}{magyar}[]{}
\define@key{LWR@hyperref}{hungarian}[]{}
\define@key{LWR@hyperref}{greek}[]{}
\define@key{LWR@hyperref}{dutch}[]{}
\define@key{LWR@hyperref}{tex4ht}[]{}
\define@key{LWR@hyperref}{pdftex}[]{}
\define@key{LWR@hyperref}{luatex}[]{}
\define@key{LWR@hyperref}{nativepdf}[]{}
\define@key{LWR@hyperref}{dvipdfm}[]{}
\define@key{LWR@hyperref}{dvipdfmx}[]{}
\define@key{LWR@hyperref}{xetex}[]{}
\define@key{LWR@hyperref}{pdfmark}[]{}
\define@key{LWR@hyperref}{dvips}[]{}
\define@key{LWR@hyperref}{hypertex}[]{}
\define@key{LWR@hyperref}{vtex}[]{}
\define@key{LWR@hyperref}{vtexpdfmark}[]{}
\define@key{LWR@hyperref}{dviwindo}[]{}
\define@key{LWR@hyperref}{dvipsone}[]{}
\define@key{LWR@hyperref}{textures}[]{}
\define@key{LWR@hyperref}{latex2html}[]{}
\define@key{LWR@hyperref}{ps2pdf}[]{}
\define@key{LWR@hyperref}{vietnamese}[]{}
\define@key{LWR@hyperref}{vietnam}[]{}
\define@key{LWR@hyperref}{arabic}[]{}
\define@key{LWR@hyperref}{hidelinks}[]{}
\define@key{LWR@hyperref}{draft}[]{}
\define@key{LWR@hyperref}{nolinks}[]{}
\define@key{LWR@hyperref}{final}[]{}
\define@key{LWR@hyperref}{pdfa}[]{}
\define@key{LWR@hyperref}{pdfversion}[]{}
\define@key{LWR@hyperref}{typexml}[]{}
\define@key{LWR@hyperref}{tex4ht}[]{}
\define@key{LWR@hyperref}{pdftex}[]{}
\define@key{LWR@hyperref}{nativepdf}[]{}
\define@key{LWR@hyperref}{dvipdfm}[]{}
\define@key{LWR@hyperref}{dvipdfmx}[]{}
\define@key{LWR@hyperref}{dvipdfmx-outline-open}[]{}
\define@key{LWR@hyperref}{pdfmark}[]{}
\define@key{LWR@hyperref}{dvips}[]{}
\define@key{LWR@hyperref}{hypertex}[]{}
\define@key{LWR@hyperref}{vtex}[]{}
\define@key{LWR@hyperref}{vtexpdfmark}[]{}
\define@key{LWR@hyperref}{dviwindo}[]{}
\define@key{LWR@hyperref}{dvipsone}[]{}
\define@key{LWR@hyperref}{textures}[]{}
\define@key{LWR@hyperref}{latex2html}[]{}
\define@key{LWR@hyperref}{ps2pdf}[]{}
\define@key{LWR@hyperref}{xetex}[]{}
\define@key{LWR@hyperref}{driverfallback}[]{}
\define@key{LWR@hyperref}{customdriver}[]{}
\define@key{LWR@hyperref}{pdfversion}[]{}
\define@key{LWR@hyperref}{bookmarks}[]{}
```

```
\define@key{LWR@hyperref}{ocgcolorlinks}[]{}
\define@key{LWR@hyperref}{colorlinks}[]{}
\define@key{LWR@hyperref}{frenchlinks}[]{}
\define@key{LWR@hyperref}{backref}[]{}
\define@key{LWR@hyperref}{pagebackref}[]{}
\define@key{LWR@hyperref}{destlabel}[]{}
\define@key{LWR@hyperref}{pdfpagescrop}[]{}
\define@key{LWR@hyperref}{pdfpagemode}[]{}
\define@key{LWR@hyperref}{pdfnonfullscreenpagemode}[]{}
\define@key{LWR@hyperref}{pdfdirection}[]{}
\define@key{LWR@hyperref}{pdfviewarea}[]{}
\define@key{LWR@hyperref}{pdfviewclip}[]{}
\define@key{LWR@hyperref}{pdfprintarea}[]{}
\define@key{LWR@hyperref}{pdfprintclip}[]{}
\define@key{LWR@hyperref}{pdfprintscaling}[]{}
\define@key{LWR@hyperref}{pdfduplex}[]{}
\define@key{LWR@hyperref}{pdfpicktraybypdfsize}[]{}
\define@key{LWR@hyperref}{pdfprintpagerange}[]{}
\define@key{LWR@hyperref}{pdfnumcopies}[]{}
\define@key{LWR@hyperref}{pdfstartview}[]{}
\define@key{LWR@hyperref}{pdfstartpage}[]{}
\define@key{LWR@hyperref}{pdftoolbar}[]{}
\define@key{LWR@hyperref}{pdfmenubar}[]{}
\define@key{LWR@hyperref}{pdfwindowui}[]{}
\define@key{LWR@hyperref}{pdffitwindow}[]{}
\define@key{LWR@hyperref}{pdfcenterwindow}[]{}
\define@key{LWR@hyperref}{pdfdisplaydoctitle}[]{}
\define@key{LWR@hyperref}{pdfpagelayout}[]{}
\define@key{LWR@hyperref}{pdflang}[]{}
\define@key{LWR@hyperref}{baseurl}[]{}
\define@key{LWR@hyperref}{pdfusetitle}[]{}
\define@key{LWR@hyperref}{pdfpagelabels}[]{}
\define@key{LWR@hyperref}{hyperfootnotes}[]{}
\define@key{LWR@hyperref}{hyperfigures}[]{}
\define@key{LWR@hyperref}{hyperindex}[]{}
\define@key{LWR@hyperref}{encap}[]{}
\define@key{LWR@hyperref}{linkcolor}[]{}
\define@key{LWR@hyperref}{anchorcolor}[]{}
\define@key{LWR@hyperref}{citecolor}[]{}
\define@key{LWR@hyperref}{filecolor}[]{}
\define@key{LWR@hyperref}{urlcolor}[]{}
\define@key{LWR@hyperref}{menucolor}[]{}
\define@key{LWR@hyperref}{runcolor}[]{}
\define@key{LWR@hyperref}{allcolors}[]{}

\DeclareStringOption[false]{backref}[section]

\DeclareBoolOption{pagebackref}

\DeclareDefaultOption{}

\ProcessKeyvalOptions*\relax
```

Maybe load backref:

```
\ifdefstring{\LWR@hyperref@backref}{section}
    {\RequirePackage{backref}}
    {}

\ifdefstring{\LWR@hyperref@backref}{slide}
    {\RequirePackage{backref}}
    {}

\ifdefstring{\LWR@hyperref@backref}{page}
    {\RequirePackage{backref}}
    {}

\ifLWR@hyperref@pagebackref
    \RequirePackage{backref}
\fi


\LetLtxMacro\href\LWR@href
\LetLtxMacro\nolinkurl\LWR@nolinkurl
\LetLtxMacro\url\LWR@url
\LetLtxMacro\phantomsection\LWR@phantomsection


\newcommand*{\hyperbaseurl}[1]{}
```

`\hyperimage` {⟨*URL*⟩} {⟨*alt text*⟩}

Insert an image with alt text:

```
\NewDocumentCommand{\LWR@hyperimageb}{m +m}{%
    \LWR@ensuredoingapar%
    \def\LWR@templink{#1}%
    \@onelevel@sanitize\LWR@templink%
    \LWR@htmltag{%
        img src=\textquotedbl\LWR@templink\textquotedbl\ %
        alt=\textquotedbl#2\textquotedbl\ %
        class=\textquotedbl{}hyperimage\textquotedbl%
    }%
    \LWR@ensuredoingapar%
    \endgroup%
}

\newrobustcmd*{\hyperimage}{%
    \begingroup%
    \LWR@linkcatcodes%
    \LWR@hyperimageb%
}

```

`\hyperdef` {⟨*1: category*⟩} {⟨*2: name*⟩} {⟨*3: text*⟩}

Creates an HTML anchor to `category.name` with the given text.

```
\NewDocumentCommand{\LWR@hyperdefb}{m m +m}{%
    \LWR@ensuredoingapar%
    \LWR@label@createtag{#1.#2}%
    #3%
```

```
    \endgroup%
}

\newcommand*{\hyperdef}{%
    \begingroup%
    \LWR@linkcatcodes%
    \LWR@hyperdefb%
}

```

\LWR@hyperrefb {⟨*1: URL*⟩} {⟨*2: category*⟩} {⟨*3: name*⟩} {⟨*4: text*⟩}

Creates an HTML link to URL#category.name with the given text.

To avoid nested links, \ref is temporarily redefined to the print version.

```
\newcommand{\LWR@hyperreffinish}[1]{%
    \begingroup%
    \RenewDocumentCommand{\ref}{s m}{\LWR@print@ref{##2}}%
   #1%
    \endgroup%
    \LWR@htmltag{/a}%
}

\newcommand*{\LWR@hyperrefbb}[3]{%
    \LWR@htmltag{%
        a href=\textquotedbl%
            \detokenize\expandafter{#1}\LWR@hashmark%
            \detokenize\expandafter{#2}.\detokenize\expandafter{#3}%
        \textquotedbl%
        \LWR@addlinktitle%
    }%
    \endgroup%
    \LWR@hyperreffinish%
}

\newrobustcmd*{\LWR@hyperrefb}{%
    \begingroup%
    \LWR@linkcatcodes%
    \LWR@hyperrefbb%
}

```

\LWR@hyperrefc [⟨*label*⟩] {⟨*text*⟩}

Creates text as an HTML link to the LaTeX label.

```

\NewDocumentCommand{\LWR@hyperrefcb}{O{label}}{%
    \LWR@startref{#1}%
    \endgroup%
    \LWR@hyperreffinish%
}

\newcommand*{\LWR@hyperrefc}{%
    \begingroup%
    \LWR@linkcatcodes%
    \LWR@hyperrefcb%
```

```
}
```

`\hyperref` {⟨*1: URL*⟩} {⟨*2: category*⟩} {⟨*3: name*⟩} {⟨*4: text*⟩} — or — [⟨*1: label*⟩] {⟨*2: text*⟩}

```
\DeclareRobustCommand*{\hyperref}{%
    \LWR@ensuredoingapar%
    \@ifnextchar[\LWR@hyperrefc\LWR@hyperrefb%
}
```

`\hypertarget` {⟨*name*⟩} {⟨*text*⟩}

Creates an anchor to name with the given text.

```
\NewDocumentCommand{\LWR@hypertargetb}{m +m}{%
    \label{LWR-ht-#1}%
    #2%
    \endgroup%
}

\newcommand*{\hypertarget}{%
    \begingroup%
    \LWR@linkcatcodes%
    \LWR@hypertargetb%
}
```

`\hyperlink` {⟨*name*⟩} {⟨*text*⟩}

Creates a link to the anchor created by hypertarget, with the given link text.

Declared because also defined by memoir.

```
\DeclareDocumentCommand{\LWR@hyperlinkb}{m}{%
    \LWR@hyperrefcb[LWR-ht-#1]%
}

\DeclareDocumentCommand{\hyperlink}{}{%
    \LWR@ensuredoingapar%
    \begingroup%
    \LWR@linkcatcodes%
    \LWR@hyperlinkb%
}
```

`\autoref` * {⟨*label*⟩}

For HTML, `\cleveref` is used instead.

```
\NewDocumentCommand{\autoref}{s m}{%
    \IfBooleanTF{#1}{\ref{#2}}{\cref{#2}}%
}
```

`\autopageref` {⟨*label*⟩}

For HTML, `\cleveref` is used instead.

```
\NewDocumentCommand{\autopageref}{s m}{%
    \IfBooleanTF{#1}{\cpageref{#2}}{\cref{#2}}%
```

```
}
```

\pdfstringdef {⟨*macroname*⟩} {⟨*TEXstring*⟩}

```
\newcommand{\pdfstringdef}[2]{}
```

\pdfbookmark [⟨*level*⟩] {⟨*text*⟩} {⟨*name*⟩}

```
\newcommand{\pdfbookmark}[3][]{}
```

\currentpdfbookmark {⟨*text*⟩} {⟨*name*⟩}

```
\newcommand{\currentpdfbookmark}[2]{}
```

\subpdfbookmark {⟨*text*⟩} {⟨*name*⟩}

```
\newcommand{\subpdfbookmark}[2]{}
```

\belowpdfbookmark {⟨*text*⟩} {⟨*name*⟩}

```
\newcommand{\belowpdfbookmark}[2]{}
```

\texorpdfstring {⟨*TEXstring*⟩} {⟨*PDFstring*⟩}

```
\let\texorpdfstring\relax
\newcommand{\texorpdfstring}[2]{#1}
```

{⟨*commands*⟩}

\pdfstringdefDisableCommands

```
\newcommand{\pdfstringdefDisableCommands}[1]{}
```

\hypercalcbp {⟨*dimen*⟩} From hyperref.

```
\def\hypercalcbp#1{%
    \strip@pt\dimexpr 0.99626401\dimexpr(#1)\relax\relax
}%
```

\Acrobatmenu {⟨*menuoption*⟩} {⟨*text*⟩}

```
\newcommand{\Acrobatmenu}[2]{}
```

\TextField [⟨*parameters*⟩] {⟨*label*⟩}

```
\DeclareRobustCommand{\TextField}[2][]{}
```

\CheckBox [⟨*parameters*⟩] {⟨*label*⟩}

```
\DeclareRobustCommand{\CheckBox}[2][]{}
```

\ChoiceMenu [⟨*parameters*⟩] {⟨*label*⟩} {⟨*choices*⟩}

```
\DeclareRobustCommand{\ChoiceMenu}[3][]{}
```

\PushButton [⟨*parameters*⟩] {⟨*label*⟩}

```
374 \DeclareRobustCommand{\PushButton}[2][]{}
```

\Submit [⟨*parameters*⟩] {⟨*label*⟩}

```
375 \DeclareRobustCommand{\Submit}[2][]{}
```

\Reset [⟨*parameters*⟩] {⟨*label*⟩}

```
376 \DeclareRobustCommand{\Reset}[2][]{}
```

\Gauge [⟨*parameters*⟩] {⟨*label*⟩}

```
377 \DeclareRobustCommand{\Gauge}[2][]{}
```

\LayoutTextField {⟨*label*⟩} {⟨*field*⟩}

```
378 \newcommand*{\LayoutTextField}[2]{}
```

\LayoutChoiceField {⟨*label*⟩} {⟨*field*⟩}

```
379 \newcommand*{\LayoutChoiceField}[2]{}
```

\LayoutCheckField {⟨*label*⟩} {⟨*field*⟩}

```
380 \newcommand*{\LayoutCheckField}[2]{}
```

\MakeRadioField {⟨*width*⟩} {⟨*height*⟩}

```
381 \newcommand*{\MakeRadioField}[2]{}
```

\MakeCheckField {⟨*width*⟩} {⟨*height*⟩}

```
382 \newcommand*{\MakeCheckField}[2]{}
```

\MakeTextField {⟨*width*⟩} {⟨*height*⟩}

```
383 \newcommand*{\MakeTextField}[2]{}
```

\MakeChoiceField {⟨*width*⟩} {⟨*height*⟩}

```
384 \newcommand*{\MakeChoiceField}[2]{}
```

\MakeFieldButton {⟨*text*⟩}

```
385 \newcommand{\MakeFieldButton}[1]{}
```

---

File 217 **lwarp-hyperxmp.sty**

## § 324 Package hyperxmp

Pkg hyperxmp hyperxmp is ignored.

**for HTML output:** Discard all options for lwarp-hyperxmp:

```
\LWR@ProvidesPackageDrop{hyperxmp}[2018/11/27]
```

---

File 218 **lwarp-hyphenat.sty**

## § 325 Package hyphenat

Pkg hyphenat hyphenat is emulated during HTML output, while the print-mode version is used inside a `latexmage`.

**for HTML output:**

```
\LWR@ProvidesPackagePass{hyphenat}[2009/09/02]

\LetLtxMacro\LWRHYNAT@origtextnhtt\textnhtt
\LetLtxMacro\LWRHYNAT@orignhttfamily\nhttfamily
\LetLtxMacro\LWRHYNAT@orignohyphens\nohyphens
\LetLtxMacro\LWRHYNAT@origbshyp\bshyp
\LetLtxMacro\LWRHYNAT@origfshyp\fshyp
\LetLtxMacro\LWRHYNAT@origdothyp\dothyp
\LetLtxMacro\LWRHYNAT@origcolonhyp\colonhyp
\LetLtxMacro\LWRHYNAT@orighyp\hyp

\LetLtxMacro\textnhtt\texttt
\LetLtxMacro\nhttfamily\ttfamily

\renewcommand{\nohyphens}[1]{#1}
\renewrobustcmd{\bshyp}{%
    \ifmmode\backslash\else\textbackslash\fi%
}
\renewrobustcmd{\fshyp}{/}
\renewrobustcmd{\dothyp}{.}
\renewrobustcmd{\colonhyp}{:}
\renewrobustcmd{\hyp}{-}

\appto\LWR@restoreorigformatting{%
\LetLtxMacro\textnhtt\LWRHYNAT@origtextnhtt%
\LetLtxMacro\nhttfamily\LWRHYNAT@orignhttfamily%
\LetLtxMacro\nohyphens\LWRHYNAT@orignohyphens%
\LetLtxMacro\bshyp\LWRHYNAT@origbshyp%
\LetLtxMacro\fshyp\LWRHYNAT@origfshyp%
\LetLtxMacro\dothyp\LWRHYNAT@origdothyp%
\LetLtxMacro\colonhyp\LWRHYNAT@origcolonhyp%
\LetLtxMacro\hyp\LWRHYNAT@orighyp%
}
```

---

File 219 **lwarp-idxlayout.sty**

## § 326 Package idxlayout

(*Emulates or patches code by* Thomas Titz.)

Pkg idxlayout idxlayout is emulated.

**for HTML output:** Discard all options for lwarp-idxlayout:

```
\LWR@ProvidesPackageDrop{idxlayout}[2012/03/30]

\newcommand{\LWR@indexprenote}{}
```

`\AtBeginDocument` to help with package load order.

```
\AtBeginDocument{
    \preto\printindex{

    \LWR@maybe@orignewpage
    \LWR@startpars

    \LWR@indexprenote

    }
}

\newcommand{\setindexprenote}[1]{\renewcommand{\LWR@indexprenote}{#1}}
\newcommand*{\noindexprenote}{\renewcommand{\LWR@indexprenote}{}}

\newcommand{\idxlayout}[1]{}
\newcommand*{\indexfont}{}
\newcommand*{\indexjustific}{}
\newcommand*{\indexsubsdelim}{}
\newcommand*{\indexstheadcase}{}
```

---

File 220 **lwarp-ifoddpage.sty**

## § 327 Package ifoddpage

(*Emulates or patches code by* Martin Scharrer.)

Pkg ifoddpage ifoddpage is emulated.

**for HTML output:** Discard all options for lwarp-ifoddpage:

```
\LWR@ProvidesPackageDrop{ifoddpage}[2016/04/23]

\newif\ifoddpage

\newif\ifoddpageoroneside

\DeclareRobustCommand{\checkoddpage}{\oddpagetrue\oddpageoronesidetrue}

```

```
}

\catcode`\_=8%
```

\@index The HTML version of \@index:

```
\catcode`\_=12%

\def\@index[#1]{%
    \ifstrequal{#1}{\imki@jobname}%
    {%
        \@ifundefined{#1@idxfile}%
        {%
            \PackageWarning{lwarp-imakeidx}{Undefined index file `#1'}%
            \begingroup
            \@sanitize
            \imki@nowrindex%
        }%
        {%
            \edef\@idxfile{#1}%
            \begingroup
            \@sanitize
            \@wrindex\@idxfile%
        }%
    }%
    {%
        \@ifundefined{#1_html@idxfile}%
        {%
            \PackageWarning{lwarp-imakeidx}{Undefined index file `#1_html'}%
            \begingroup
            \@sanitize
            \imki@nowrindex%
        }%
        {%
            \edef\@idxfile{#1_html}%
            \begingroup
            \@sanitize
            \@wrindex\@idxfile%
        }%
    }%
}

\catcode`\_=8%
```

\item
\subitem
\subsubitem HTML versions of \item, etc.:

```
\appto\theindex{%
    \let\item\LWR@indexitem%
    \let\subitem\LWR@indexsubitem%
    \let\subsubitem\LWR@indexsubsubitem%
}
```

\imki@wrindexentrysplit {⟨*file*⟩} {⟨*entry*⟩} {⟨*page*⟩}

\imki@wrindexentryunique {⟨*file*⟩} {⟨*entry*⟩} {⟨*page*⟩}

While writing index entries, adds an HTML label, and writes the label's index instead of the page number:

```
\renewcommand\imki@wrindexentrysplit[3]{%
\addtocounter{LWR@autoindex}{1}%
\label{LWRindex-\arabic{LWR@autoindex}}%
  \expandafter\protected@write\csname#1@idxfile\endcsname{}%
    {\string\indexentry{#2}{\arabic{LWR@autoindex}}}%
}

\renewcommand\imki@wrindexentryunique[3]{%
\addtocounter{LWR@autoindex}{1}%
\label{LWRindex-\arabic{LWR@autoindex}}%
  \protected@write\@indexfile{}%
    {\string\indexentry[#1]{#2}{\arabic{LWR@autoindex}}}%
}

\def\imki@wrindexsplit#1#2{%
\imki@wrindexentrysplit{#1}{#2}{\thepage}%
\endgroup\imki@showidxentry{#1}{#2}%
  \@esphack%
}

\def\imki@wrindexunique#1#2{%
\imki@wrindexentryunique{#1}{#2}{\thepage}%
\endgroup\imki@showidxentry{#1}{#2}%
  \@esphack%
  }

```

\LWR@imki@setxdydefopts

Sets the *xindy* HTML options, ignoring the user's settings.

```
\newcommand*{\LWR@imki@setxdydefopts}{%
    \edef\imki@options{ \space %
        -M \space \LWR@xindyStyle\space %
        -L \space \LWR@xindyLanguage\space %
        -C \space \LWR@xindyCodepage\space %
    }%
}
```

\LWR@imki@setdefopts {⟨*user options*⟩}

Sets the HTML options, added to the user's settings, depending on whether *makeindex* or *xindy* are used.

For *makeindex*, the user's choice is ignored, and only the lwarp version is used. (Only one style at a time is possible.)

For *xindy*, multiple modules may be specified, and the lwarp version is appended.

```
\newcommand*{\LWR@imki@setdefopts}[1]{%
\ifblank{#1}{%
    \edef\imki@options{\space -s \space \LWR@makeindexStyle \space}%
```



Pkg inputtrc inputtrc is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{inputttrc}[2012/10/10]
```

Patched to remove extraneous spaces, which sometimes showed up in logos inside a `lateximage`.

```
\renewcommand*{\IT@prim@input}[1]{%
  \typeout{\IT@indent\IT@currfile INPUTTING #1}%
%% ... TODO: option to write to '.log' only.
  \xdef\IT@filestack{{\IT@currfile}\IT@filestack}%
  \xdef\IT@currfile{#1}%
  \expandafter \gdef\expandafter \IT@indent\expandafter{%
    \IT@indent \IT@indent@unit}%                lwarp
  \@@input#1%                                   lwarp
  \expandafter\IT@pop@indent\IT@indent   \@nil% lwarp
  \expandafter\IT@pop@file  \IT@filestack\@nil% lwarp
  \IT@maybe@returnmessage%% v0.2                lwarp
}
```

---

File 225 **lwarp-intopdf.sty**

# § 332 Package intopdf

Pkg intopdf intopdf is emulated.

The filespec, MIME type, and description are ignored for now.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{intopdf}[2019/05/28]
```

```
\NewDocumentCommand{\attachandlink}{o m o m m}{%
    \LWR@href{#2}{#5}%
}
```

---

File 226 **lwarp-isomath.sty**

# § 333 Package isomath

(*Emulates or patches code by* Günter Milde.)

Pkg isomath isomath is used as-is for SVG math, and emulated for MathJax.

⚠ MathJax sans MathJax does not provide a sans math font, so sans is typeset as roman.

**for HTML output:**

```
\LWR@ProvidesPackagePass{isomath}[2012/09/04]
```

```
\begin{warpMathJax}
\CustomizeMathJax{\let\mathbfit\boldsymbol}
\CustomizeMathJax{\let\mathsfbfit\mathbfit}% not sans
\CustomizeMathJax{\let\mathsfit\mathit}% not sans
```

```
\CustomizeMathJax{\let\vectorsym\mathbfit}
\CustomizeMathJax{\let\matrixsym\mathbfit}
\CustomizeMathJax{\let\tensorsym\mathsfbfit}
\CustomizeMathJax{\let\mathboldsans\mathsfbfit}
\CustomizeMathJax{\let\mathbold\mathbfit}
\CustomizeMathJax{\let\mathsans\mathrm}% not sans
\end{warpMathJax}
```

File 227 **lwarp-isotope.sty**

§ 334 Package

# isotope

(*Emulates or patches code by* Heiko Bauke.)

Pkg isotope isotope is patched for use by lwarp with SVG math, and emulated for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{isotope}[2011/08/26]

\newcommand{\LWR@HTML@isotope@two}[2][]{%
    \renewcommand{\isotope@atomicnumber}{#1}%
    \edef\LWR@isotope@alttag{%
        \textbackslash(
        \textbackslash{}isotope
        [\isotope@nucleonnumber]%
        [\isotope@atomicnumber]%
        \{#2\}
        \textbackslash)%
    }%
  \ifbool{mathjax}%
    {\LWR@isotope@alttag}%
    {% SVG
        \m@th%
        \LWR@subsingledollar*%
        {% alt tag
            \LWR@isotope@alttag%
        }%
        {isotope}% add'l hashing
        {% contents
            \settowidth\@tempdimb{%
                \ensuremath{\scriptstyle\isotope@nucleonnumber}%
            }%
            \settowidth\@tempdimc{%
                \ensuremath{\scriptstyle\isotope@atomicnumber}%
            }%
            \ifdim\@tempdimb<\@tempdimc\@tempdimb=\@tempdimc\fi%
            \ensuremath{
                {}%
                ^{\makebox[\@tempdimb][r]{%
                    \ensuremath{%
                    \scriptstyle\isotope@nucleonnumber%
                    }% ensuremath
                }}%
                _{\makebox[\@tempdimb][r]{%
```

```
                    \ensuremath{%
                        \scriptstyle\isotope@atomicnumber%
                    }% ensuremath
                }}%
                \isotopestyle{#2}%
            }% ensuremath
        }% contents
    }% SVG
  \endgroup%
}%
\LWR@formatted{isotope@two}

\begin{warpMathJax}
\CustomizeMathJax{%
    \newcommand{\LWRisotopetwo}[2][]{%
        {%
            \vphantom{\mathrm{#2}}%
            {}^{\LWRisotopenucleonnumber}_{#1}%
            \mathrm{#2}%
        }%
    }%
}

\CustomizeMathJax{%
    \newcommand{\isotope}[1][]{%
        \def\LWRisotopenucleonnumber{#1}%
        \LWRisotopetwo%
    }%
}
\end{warpMathJax}
```

---

File 228 **lwarp-jurabib.sty**

# § 335 Package jurabib

(*Emulates or patches code by* Jens Berger.)

Pkg jurabib jurabib is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{jurabib}[2004/01/25]

\renewrobustcmd{\jblangle}{\textless}

\renewrobustcmd{\jbrangle}{\textgreater}

\renewcommand*{\jb@biblaw@item}{%
    \hspace{0.5em}%
%     $\triangleright$
    \HTMLunicode{25B7}%     lwarp
    \hspace{0.5em}%
}

\renewrobustcmd{\jbarchsig}[2]{%
```

```
     \ifjbweareinbib
        \settowidth{\jb@subarchitemwidth}{\jbsamesubarchindent+#1}%
       \setlength{\jb@subarchentrywidth}{\textwidth-\jb@subarchitemwidth-4em}%
%      \begin{tabular}{@{}p{\jb@subarchitemwidth}@{}j{\jb@subarchentrywidth}@{}}%
           #1\ifjb@dot\unskip\unskip\unskip.\fi
%             &
            \quad%      lwarp
            \ifthenelse{\equal{#2}{}}{}{\jbarchnameformat{#2}}%
%         \end{tabular}
     \fi
}%


\xpatchcmd{\jb@do@post@item}
    {\begin{tabular}{p{\jb@biblaw@item@width}j{\jb@biblaw@entry@width}}}
    {}
    {}
    {\LWR@patcherror{jurabib}{jb@do@post@item 1}}

\xpatchcmd{\jb@do@post@item}
    {\multicolumn{2}{p{\columnwidth}}{\jb@@name}}
    {\jb@@name}
    {}
    {\LWR@patcherror{jurabib}{jb@do@post@item 2}}

\xpatchcmd{\jb@do@post@item}
    {\jb@biblaw@item & \jb@@fulltitle}
    {\jb@biblaw@item \quad \jb@@fulltitle}
    {}
    {\LWR@patcherror{jurabib}{jb@do@post@item 3}}

\xpatchcmd{\jb@do@post@item}
    {\end{tabular}}
    {}
    {}
    {\LWR@patcherror{jurabib}{jb@do@post@item 4}}

\xpatchcmd{\jb@do@post@item}
    {\begin{minipage}[t]{\bibnumberwidth}}
    {}
    {}
    {\LWR@patcherror{jurabib}{jb@do@post@item 5}}

\xpatchcmd{\jb@do@post@item}
    {\end{minipage}}
    {\quad}
    {}
    {\LWR@patcherror{jurabib}{jb@do@post@item 6}}
```

File 229 **lwarp-karnaugh-map.sty**

# § 336 Package karnaugh-map

(*Emulates or patches code by* Mattias Jacobsson.)

Pkg karnaugh-map karnaugh-map is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{karnaugh-map}[2017/02/20]
```

This patch is needed only because lwarp changes the definition of \&, and the original uses \ifnum to compare 0 with \&. It is hard to patch this environment, so the entire thing is redefined here, with the lwarp modifications identified in comments.

```
\RenewDocumentEnvironment{karnaugh-map}{s O{4} O{4} O{1} O{$X_1X_0$} O{$X_3X_2$} O{$X_5X_4$}} {%
  \begingroup
    % store map size {[START]
      \renewcommand{\@karnaughmap@var@mapsizex@}{#2}%
      \renewcommand{\@karnaughmap@var@mapsizey@}{#3}%
      \renewcommand{\@karnaughmap@var@mapsizez@}{#4}%
    % [END]}
    % determinate if markings should be color or black and white
    \IfBooleanTF{#1}{%
      % should be black and white
      \renewcommand{\@karnaughmap@var@bw@}{1}%
    }{%
      % should be color
      \renewcommand{\@karnaughmap@var@bw@}{0}%
    }%
    %
    % find matching matrix template and alignment parameters {[START]
    \newcommand{\@karnaughmap@local@matrixtemplate@}{0}% '0' is considered as missing matrix template
      \newcommand{\@karnaughmap@local@maprealignmentx@}{0}%
      \newcommand{\@karnaughmap@local@maprealignmenty@}{0}%
    \ifnum\@karnaughmap@var@mapsizex@\@karnaughmap@var@mapsizey@\@karnaughmap@var@mapsizez@=221
        \renewcommand{\@karnaughmap@local@matrixtemplate@}{%
                  \&                  0 \&                   1 \& \phantom{0} \\
             0 \& |(000000)|  \phantom{0} \& |(000001)|  \phantom{0} \&         \\
             1 \& |(000010)|  \phantom{0} \& |(000011)|  \phantom{0} \&         \\
        \phantom{0}  \&                    \&                    \&          \\
        }%
      \fi
    \ifnum\@karnaughmap@var@mapsizex@\@karnaughmap@var@mapsizey@\@karnaughmap@var@mapsizez@=241
        \renewcommand{\@karnaughmap@local@matrixtemplate@}{%
                 \&                  0 \&                   1 \& \phantom{00} \\
            00 \& |(000000)|  \phantom{0} \& |(000001)|  \phantom{0} \&         \\
            01 \& |(000010)|  \phantom{0} \& |(000011)|  \phantom{0} \&         \\
            11 \& |(000110)|  \phantom{0} \& |(000111)|  \phantom{0} \&         \\
            10 \& |(000100)|  \phantom{0} \& |(000101)|  \phantom{0} \&         \\
        \phantom{00} \&                    \&                    \&          \\
        }%
      \fi
    \ifnum\@karnaughmap@var@mapsizex@\@karnaughmap@var@mapsizey@\@karnaughmap@var@mapsizez@=421
        \renewcommand{\@karnaughmap@local@matrixtemplate@}{%
               \&               00 \&               01 \&               11 \&               10 \& \phanto
            0  \& |(000000)|  \phantom{0} \& |(000001)|  \phantom{0} \& |(000011)|  \phantom{0} \& |(00001
            1  \& |(000100)|  \phantom{0} \& |(000101)|  \phantom{0} \& |(000111)|  \phantom{0} \& |(00011
```

```
      \phantom{00} \&                \&                \&                \&                \&
       }%
     \fi
   \ifnum\@karnaughmap@var@mapsizex@\@karnaughmap@var@mapsizey@\@karnaughmap@var@mapsizez@=441
      \renewcommand{\@karnaughmap@local@matrixtemplate@}{%
             \&              00 \&              01 \&              11 \&              10 \& \phanto
          00 \& |(000000)| \phantom{0} \& |(000001)| \phantom{0} \& |(000011)| \phantom{0} \& |(00001
          01 \& |(000100)| \phantom{0} \& |(000101)| \phantom{0} \& |(000111)| \phantom{0} \& |(00011
          11 \& |(001100)| \phantom{0} \& |(001101)| \phantom{0} \& |(001111)| \phantom{0} \& |(00111
          10 \& |(001000)| \phantom{0} \& |(001001)| \phantom{0} \& |(001011)| \phantom{0} \& |(00101
      \phantom{00} \&                \&                \&                \&                \&
       }%
     \fi
   \ifnum\@karnaughmap@var@mapsizex@\@karnaughmap@var@mapsizey@\@karnaughmap@var@mapsizez@=442
      \renewcommand{\@karnaughmap@local@matrixtemplate@}{%
             \&              00 \&              01 \&              11 \&              10 \& \phanto
          00 \& |(000000)| \phantom{0} \& |(000001)| \phantom{0} \& |(000011)| \phantom{0} \& |(00001
          01 \& |(000100)| \phantom{0} \& |(000101)| \phantom{0} \& |(000111)| \phantom{0} \& |(00011
          11 \& |(001100)| \phantom{0} \& |(001101)| \phantom{0} \& |(001111)| \phantom{0} \& |(00111
          10 \& |(001000)| \phantom{0} \& |(001001)| \phantom{0} \& |(001011)| \phantom{0} \& |(00101
      \phantom{00} \&                \&                \&                \&                \&
       }%
       \renewcommand{\@karnaughmap@local@maprealignmentx@}{2.5}%
     \fi
   \ifnum\@karnaughmap@var@mapsizex@\@karnaughmap@var@mapsizey@\@karnaughmap@var@mapsizez@=444
      \renewcommand{\@karnaughmap@local@matrixtemplate@}{%
             \&              00 \&              01 \&              11 \&              10 \& \phanto
          00 \& |(000000)| \phantom{0} \& |(000001)| \phantom{0} \& |(000011)| \phantom{0} \& |(00001
          01 \& |(000100)| \phantom{0} \& |(000101)| \phantom{0} \& |(000111)| \phantom{0} \& |(00011
          11 \& |(001100)| \phantom{0} \& |(001101)| \phantom{0} \& |(001111)| \phantom{0} \& |(00111
          10 \& |(001000)| \phantom{0} \& |(001001)| \phantom{0} \& |(001011)| \phantom{0} \& |(00101
      \phantom{00} \&                \&                \&                \&                \&
          00 \& |(100000)| \phantom{0} \& |(100001)| \phantom{0} \& |(100011)| \phantom{0} \& |(10001
          01 \& |(100100)| \phantom{0} \& |(100101)| \phantom{0} \& |(100111)| \phantom{0} \& |(10011
          11 \& |(101100)| \phantom{0} \& |(101101)| \phantom{0} \& |(101111)| \phantom{0} \& |(10111
          10 \& |(101000)| \phantom{0} \& |(101001)| \phantom{0} \& |(101011)| \phantom{0} \& |(10101
      \phantom{00} \&                \&                \&                \&                \&
       }%
       \renewcommand{\@karnaughmap@local@maprealignmentx@}{2.5}%
       \renewcommand{\@karnaughmap@local@maprealignmenty@}{-2.5}%
     \fi
   % [END]}
  % test if a matrix template is found or not(aka "\@karnaughmap@local@matrixtemplate@" equals to '0')
   \ifdefstring{\@karnaughmap@local@matrixtemplate@}{0}{%  lwarp
%    \ifnum0=\@karnaughmap@local@matrixtemplate@%  original
     % print error if no template could be found
     \PackageError{lwarp-karnaugh-map}{%
       Can not find a template fitting your specification
      (\@karnaughmap@var@mapsizex@\space x \@karnaughmap@var@mapsizey@\space x
       \@karnaughmap@var@mapsizez@)%
     }{%
       Existing templates have the following dimensions:
       2x2x1, 2x4x1, 4x2x1, 4x4x1, 4x4x2, and 4x4x4.
     }%
%    \fi   original
```

```
    }{\relax}%    lwarp
    \begin{tikzpicture}
      % grid
      % for all dimensions
    \draw[color=black, ultra thin] (0,0) grid (\@karnaughmap@var@mapsizex@,\@karnaughmap@var@mapsizey@);
      % when there are 2 sub maps
      \ifnum\@karnaughmap@var@mapsizez@=2
        \draw[color=black, ultra thin] (5,0) grid (9,4);
      \fi
      % when there are 4 sub maps
      \ifnum\@karnaughmap@var@mapsizez@=4
        \draw[color=black, ultra thin] (5,0) grid (9,4);
        \draw[color=black, ultra thin] (0,-5) grid (4,-1);
        \draw[color=black, ultra thin] (5,-5) grid (9,-1);
      \fi
      % labels
      % for all dimensions
    \node[above] at (\@karnaughmap@var@mapsizex@*0.5,\@karnaughmap@var@mapsizey@+0.9) {\small{#5}};
      \node[left] at (-0.9,\@karnaughmap@var@mapsizey@*0.5) {\small{#6}};
      % when there are 2 sub maps
      \ifnum\@karnaughmap@var@mapsizez@=2
        \node[above] at (7,4.9) {\small{#5}};
        % extra sub maps labels
        \node[below] at (2,-0.1) {\small{#7$=0$}};
        \node[below] at (7,-0.1) {\small{#7$=1$}};
      \fi
      % when there are 4 sub maps
      \ifnum\@karnaughmap@var@mapsizez@=4
        \node[above] at (7,4.9) {\small{#5}};
        \node[left] at (-0.9,-3) {\small{#6}};
        % extra sub maps labels
        \node[below] at (2,-0.1) {\small{#7$=00$}};
        \node[below] at (7,-0.1) {\small{#7$=01$}};
        \node[below] at (2,-5.1) {\small{#7$=10$}};
        \node[below] at (7,-5.1) {\small{#7$=11$}};
      \fi
      % data
      \matrix[
        matrix of nodes,
        ampersand replacement=\&,
        column sep={1cm,between origins},
        row sep={1cm,between origins},
    ] at (\@karnaughmap@var@mapsizex@*0.5+\@karnaughmap@local@maprealignmentx@,\@karnaughmap@var@mapsiz
        \@karnaughmap@local@matrixtemplate@%
      };
}{
    \end{tikzpicture}
  \endgroup
}
```

File 230 **lwarp-keyfloat.sty**

## § 337 Package keyfloat

(*Emulates or patches code by* Brian Dunn.)

Pkg keyfloat keyfloat is supported with a considerable amount of hacking. (It's a mashup of lwarp, keyfloat, and tocdata.)

⚠ keywrap If placing a `\keyfig[H]` inside a `keywrap`, use an absolute width for `\keyfig`, instead of `lw`-proportional widths. (The `[H]` option forces the use of a minipage, which internally adjusts for a virtual 6-inch wide minipage, which then corrupts the `lw` option.)

**for HTML output:**

```
\LWR@ProvidesPackagePass{keyfloat}[2019/09/23]

\@ifpackagelater{keyfloat}{2019/09/23}{\relax}{
    \PackageError{lwarp-keyfloat}
    {%
        The keyfloat package is out of date.\MessageBreak
        Update to keyfloat v2.01 2019/09/23 or later%
    }
    {%
        Please update the keyfloat package.  It's worth it!%
    }
}
```

After keyfloat has loaded:

```
\AtBeginDocument{


\providecommand*{\KFLT@LWR@hook@boxouter}{}
\renewcommand*{\KFLT@LWR@hook@boxouter}{%
    \ifbool{KFLT@keywrap}{%
    }{%
        \ifnumequal{\value{KFLT@keyfloatdepth}}{0}{%
            \setlength{\linewidth}{6in}%
            \setlength{\textwidth}{6in}%
            \setlength{\textheight}{9in}%
        }{}%
    }%
    \normalcolor%
}


\LetLtxMacro\KFLT@LWR@hook@keysubfloats\KFLT@LWR@hook@boxouter

\let\KFLT@LWR@hook@keyfloatsminipage\relax
\let\endKFLT@LWR@hook@keyfloatsminipage\relax
\newenvironment*{KFLT@LWR@hook@keyfloatsminipage}[1]{}{}


\LetLtxMacro\KFLT@LWR@hook@keyfloats\KFLT@LWR@hook@boxouter

\renewcommand*{\KFLT@maybeendfloatrow}{%
    \ifnumless{\value{KFLT@thiscol}}{\value{KFLT@numcols}}%
    {}% thiscol < numcols
    {% >=
```

```
        \defcounter{KFLT@thiscol}{0}%
    }%
}%

\renewcommand{\KFLT@trackrows}%
{%
```

If are nested inside a keyfloats or a subfloat:

```
    \ifboolexpr{%
        test {\ifnumgreater{\value{KFLT@keyfloatdepth}}{0}} or%
        bool{KFLT@inkeysubfloats}%
    }%
    {% nested
```

Tracks row start and end:

```
        \KFLT@maybestartfloatrow%
```

Possibly fill space between columns:

```
        \ifnumgreater{\value{KFLT@thiscol}}{1}%
            {%
%                   \hfill%
            }%
            {}%
    }% nested
    {}% not nested
}


\RenewDocumentCommand{\KFLT@onefigureimage}{m}
{%
\LWR@traceinfo{KFLT@onefigureimage}%
% \begin{lrbox}{\KFLT@envbox}%
\ifthenelse{\NOT\equal{\KFLT@lw}{}}%
    {%
        \KFLT@frame{\includegraphics%
        [scale=\KFLT@s,width=\KFLT@imagewidth]{#1}}%
    }%
    {% not linewidth
        \ifthenelse{\dimtest{\KFLT@w}{>}{0pt}}%
        {% width is given
            \ifthenelse{\dimtest{\KFLT@h}{>}{0pt}}%
            {% w and h
                \KFLT@frame{\includegraphics%
                [scale=\KFLT@s,%
                width=\KFLT@imagewidth,height=\KFLT@h]{#1}}%
            }% w and h
            {% only w
                \KFLT@frame{\includegraphics%
                [scale=\KFLT@s,width=\KFLT@imagewidth]{#1}}%
            }% only w
        }% width is given
        {% width is not given
            \ifthenelse{\dimtest{\KFLT@h}{>}{0pt}}%
```

```
            {%
                \KFLT@frame{\includegraphics%
                [scale=\KFLT@s,height=\KFLT@h]{#1}}%
            }%
            {%
                \KFLT@frame{\includegraphics%
                [scale=\KFLT@s]{#1}}%
            }%
        }% width is not given
    }% not linewidth
% \end{lrbox}%
% \unskip%
% \KFLT@findenvboxwidth%
% \begin{turn}{\KFLT@r}%
% \KFLT@frame{\usebox{\KFLT@envbox}}%
% \unskip%
% \end{turn}%
\LWR@traceinfo{KFLT@onefigureimage: done}%
}

\RenewDocumentEnvironment{KFLT@boxinner}{}
{%
    \LWR@traceinfo{KFLT@boxinner}%
    \LWR@stoppars%
    \minipagefullwidth%
    \ifboolexpr{bool{KFLT@ft} or bool{KFLT@f}}{%
        \fminipage{\KFLT@imagewidth}%
    }{%
        \minipage{\KFLT@imagewidth}%
    }%
}
{%
    \ifboolexpr{bool{KFLT@ft} or bool{KFLT@f}}{%
        \endfminipage%
    }{%
        \endminipage%
    }%
    \LWR@startpars%
    \LWR@traceinfo{KFLT@boxinner: done}%
}

\newcommand*{\LWR@KFLT@settextalign}[1]{%
    \def\LWR@KFLT@textalign{justify}%
    \ifcsstring{KFLT@#1textalign}{\centering}%
        {\def\LWR@KFLT@textalign{center}}%
        {}%
    \ifcsstring{KFLT@#1textalign}{\raggedleft}%
        {\def\LWR@KFLT@textalign{right}}%
        {}%
    \ifcsstring{KFLT@#1textalign}{\raggedright}%
        {\def\LWR@KFLT@textalign{left}}%
        {}%
}

\renewcommand{\KFLT@addtext}[1]
```

```
{%
```

Is there text to add?

```
    \ifcsempty{KFLT@#1t}%
    {}% no text
    {% text to add
        {% local
```

Add some space, then create a  to contain the text:

```
        \addvspace{\smallskipamount}%
        \LWR@KFLT@settextalign{#1}%
        \begin{BlockClass}[text-align:\LWR@KFLT@textalign]{floatnotes}%
```

Set the alignment and some text parameters:

```
%         \csuse{KFLT@#1textalign}%
%         \footnotesize%
        \setlength{\parskip}{1.5ex}%
        \setlength{\parindent}{0em}%
```

Typeset the actual text:

```
        \csuse{KFLT@#1t}%
```

Close it all out with a little more space:

```
        \end{BlockClass}%
%         \par\addvspace{2ex}%
        }% local
    }% text to add
}

\@ifpackageloaded{tocdata}
{}
{% tocdata not loaded

    \newcommand*{\LWR@KFLT@setnamealign}[1]{%
        \def\LWR@KFLT@textalign{justify}%
        \ifstrequal{#1}{\centering}%
            {\def\LWR@KFLT@textalign{center}}%
            {}%
        \ifstrequal{#1}{\raggedleft}%
            {\def\LWR@KFLT@textalign{right}}%
            {}%
        \ifstrequal{#1}{\raggedright}%
            {\def\LWR@KFLT@textalign{left}}%
            {}%
    }

    \renewcommand*{\KFLT@@addartisttext}[3]{%

```

Add space and create the name inside a :

```
%         \addvspace{\medskipamount}%
    %     \begin{minipage}{\linewidth}%
          \LWR@KFLT@setnamealign{#3}%
          \begin{BlockClass}[text-align:\LWR@KFLT@textalign]{floatnotes}%

```

Text alignment is #3, and depends on artist or author:

```
    %     #3%

```

#1 is empty or 'subgrp'
#2 is empty for artist, 'u' for author:

```
          \footnotesize\textsc{%
              \KFLT@optionalname{\csuse{KFLT@#1a#2p}}%
              \KFLT@optionalname{\csuse{KFLT@#1a#2f}}%
              \csuse{KFLT@#1a#2l}%
              \csuse{KFLT@#1a#2s}%
          }%
    %     \end{minipage}%
          \end{BlockClass}
%         \par\addvspace{2ex}%
    }

}% tocdata not loaded
```

Env KFLT@marginfloat [⟨*offset*⟩] {⟨*type*⟩}

```
\DeclareDocumentEnvironment{KFLT@marginfloat}{O{-1.2ex} m}
{%
    \uselengthunit{PT}%
    \LWR@BlockClassWP%
        {float:right; width:2in; margin:10pt}%
        {}%
        {marginblock}%
    \renewcommand*{\@captype}{#2}%
    \minipage{\LWR@usersmarginparwidth}%
    \setlength{\marginparwidth}{.95\LWR@usersmarginparwidth}%
}
{%
    \endminipage%
    \endLWR@BlockClassWP%
}

\DeclareDocumentEnvironment{marginfigure}{o}
    {\begin{KFLT@marginfloat}{figure}}
    {\end{KFLT@marginfloat}}

\DeclareDocumentEnvironment{margintable}{o}
    {\begin{KFLT@marginfloat}{table}}
    {\end{KFLT@marginfloat}}
```

Env keywrap {⟨*width*⟩} {⟨*keyfloat*⟩}

```
\DeclareDocumentEnvironment{keywrap}{m +m}
{%
    \begin{LWR@setvirtualpage}*
    \setlength{\LWR@templengthone}{#1}%
    \begin{LWR@BlockClassWP}%
        {%
         float:right; width:\LWR@printlength{\LWR@templengthone};  % extra space
            margin:10pt%
        }%
        {}%
        {marginblock}%
    \setlength{\linewidth}{.95\LWR@templengthone}%
    \booltrue{KFLT@keywrap}%
    #2%
    \end{LWR@BlockClassWP}%
    \end{LWR@setvirtualpage}%
}
{}

}% AtBeginDocument
```

File 231 **lwarp-keystroke.sty**

## § 338 Package keystroke

(*Emulates or patches code by* Werner Fink.)

Pkg keystroke keystroke is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{keystroke}[2010/04/23]

\newcommand*{\LWR@HTML@keystroke}[1]{
    \InlineClass{keystroke}{#1}
}
\LWR@formatted{keystroke}


\newcommand*{\LWR@HTML@Return}{\keystroke{\HTMLunicode{021A9}}}
\LWR@formatted{Return}

\newcommand*{\LWR@HTML@BSpace}{\keystroke{\HTMLunicode{027FB}}}
\LWR@formatted{BSpace}

\newcommand*{\LWR@HTML@Tab}{\keystroke{|\HTMLunicode{021C6}|}}
\LWR@formatted{Tab}

\newcommand*{\LWR@HTML@UArrow}{\keystroke{\HTMLunicode{02191}}}
\LWR@formatted{UArrow}

\newcommand*{\LWR@HTML@DArrow}{\keystroke{\HTMLunicode{02193}}}
```

```
\LWR@formatted{DArrow}

\newcommand*{\LWR@HTML@LArrow}{\keystroke{\HTMLunicode{02190}}}
\LWR@formatted{LArrow}

\newcommand*{\LWR@HTML@RArrow}{\keystroke{\HTMLunicode{02192}}}
\LWR@formatted{RArrow}

% Preserves the language options:
\LetLtxMacro\LWR@HTML@Shift\Shift
\xpatchcmd{\LWR@HTML@Shift}
    {$\Uparrow$}
    {\HTMLunicode{21D1}}
    {}
    {}
\LWR@formatted{Shift}

\LetLtxMacro\LWR@HTML@PgUp\PgUp
\xpatchcmd{\LWR@HTML@PgUp}
    {$\uparrow$}
    {\HTMLunicode{2191}}
    {}
    {}
\LWR@formatted{PgUp}

\LetLtxMacro\LWR@HTML@PgDown\PgDown
\xpatchcmd{\LWR@HTML@PgDown}
    {$\downarrow$}
    {\HTMLunicode{2193}}
    {}
    {}
\LWR@formatted{PgDown}
```

File 232 **lwarp-kpfonts.sty**

§ 339 Package

# kpfonts

(*Emulates or patches code by* Christophe Caignaert.)

Pkg kpfonts kpfonts is used as-is for SVG math, and is emulated for MathJax.

⚠ limitations The MathJax emulation honors the options uprightRoman for \D only, classicReIm, frenchstyle for Greek only, upright for Greek only, uprightgreeks, slantedGreeks, and mathcalasscript.

The dedicated macros for Greek work correctly.

SVG math should appear the same as the printed output.

**for HTML output:**

```
\LWR@ProvidesPackagePass{kpfonts}[2010/08/20]

\LWR@infoprocessingmathjax{kpfonts}

```

```
\LWR@origRequirePackage{lwarp-common-mathjax-newpxtxmath}

\LWR@origRequirePackage{lwarp-common-mathjax-letters}

\begin{warpMathJax}

\ifkp@calasscr
    \CustomizeMathJax{\let\LWRorigmathscr\mathscr}
    \CustomizeMathJax{\let\LWRorigmathcal\mathcal}
    \CustomizeMathJax{\let\mathscr\LWRorigmathcal}
    \CustomizeMathJax{\let\mathcal\LWRorigmathscr}
\fi

\ifkp@upgrk % lowercase
    \LWR@mathjax@addgreek@l@up{}{}
    \LWR@mathjax@addgreek@l@it{other}{}
\else
    \LWR@mathjax@addgreek@l@up{other}{}
\fi

\ifkp@slGrk
    \LWR@mathjax@addgreek@u@it*{}{}
    \LWR@mathjax@addgreek@u@up*{other}{}
    \LWR@mathjax@addgreek@u@up*{var}{}
\else
    \LWR@mathjax@addgreek@u@it*{other}{}
    \LWR@mathjax@addgreek@u@it*{var}{}
\fi

\LWR@mathjax@addgreek@u@up*{}{up}
\LWR@mathjax@addgreek@l@up{}{up}

\LWR@mathjax@addgreek@u@it*{}{sl}
\LWR@mathjax@addgreek@l@it{}{sl}

\CustomizeMathJax{\newcommand{\partialsl}{\mathord{\unicode{x1D715}}}}
\CustomizeMathJax{\let\partialup\uppartial}% not upright

\ifkp@oldReIm
\else
    \CustomizeMathJax{\renewcommand{\Re}{\mathfrak{Re}}}
    \CustomizeMathJax{\renewcommand{\Im}{\mathfrak{Im}}}
\fi

\ifkp@Dcommand
    \ifkp@upRm%
        \CustomizeMathJax{
            \def\D#1{\mathclose{\,\mathrm{d}}#1}
        }
    \else
        \CustomizeMathJax{
            \def\D#1{\mathclose{\,\mathit{d}}#1}
        }
    \fi
\fi
```

```
60
61 \CustomizeMathJax{\let\pounds\mathsterling}
62 \CustomizeMathJax{\let\kppounds\mathsterling}
63
64 \CustomizeMathJax{\newcommand{\mathup}[1]{\mathrm{#1}}}% never sans
65 \CustomizeMathJax{\let\mathupright\mathup}
66
67 \end{warpMathJax}
```

File 233 **lwarp-kpfonts-otf.sty**

§ 340 Package

# kpfonts-otf

(*Emulates or patches code by* Daniel Flipo.)

Pkg kpfonts-otf

kpfonts-otf is used as-is for SVG math, and is emulated for MathJax.

⚠ limitations

The MathJax emulation honors the options `fancyReIm`, `mathcal`, `frenchstyle` for Greek only, and `mathcalasscript`.

Also see the options for unicode-math, which is loaded by kpfonts-otf.

The unicode-math dedicated macros for Greek work correctly.

⚠ `\mathversion`

The MathJax emulation does not change with the use of `\mathversion`. Whatever emulation is established at the begin of the document will remain.

SVG math should appear the same as the printed output.

**for HTML output:**

```
1 \LWR@ProvidesPackagePass{kpfonts-otf}[2020/06/20]
2
3 \LWR@infoprocessingmathjax{kpfonts-otf}
4
5 \LWR@origRequirePackage{lwarp-common-mathjax-nonunicode}
6
7 \LWR@origRequirePackage{lwarp-common-mathjax-letters}
8
9 \begin{warpMathJax}
10
11 \ifkp@calasscr
12     \CustomizeMathJax{\let\mathscr\mathcal}
13 \else
14     \CustomizeMathJax{\let\mathcal\mathscr}
15 \fi
16
17 \ifkp@frenchstyle
18     \LWR@mathjax@addgreek@l@up{}{}
19     \LWR@mathjax@addgreek@u@up*{}{}
20 \fi
21
22 \ifkp@oldReIm
23     \CustomizeMathJax{\renewcommand{\Re}{\mathfrak{Re}}}
24     \CustomizeMathJax{\renewcommand{\Im}{\mathfrak{Im}}}
25 \else
```

```
\fi

\ifkp@Dcommand
    \CustomizeMathJax{
        \def\D#1{\mathclose{\,\mathrm{d}}#1}
    }
\fi

\CustomizeMathJax{\let\varint\int}
\CustomizeMathJax{\let\variint\iint}
\CustomizeMathJax{\let\variiint\iiint}
\CustomizeMathJax{\let\variiiint\iiiint}
\CustomizeMathJax{\let\varidotsint\idotsint}

\CustomizeMathJax{\newcommand{\varointctrclockwise}{\mathop{\unicode{x2939}\!\!\unicode{x0222E}}}}
\CustomizeMathJax{\newcommand{\oiintclockwise}{\mathop{\unicode{x0222F}\!\!\unicode{x2938}}}}
\CustomizeMathJax{\newcommand{\oiintctrclockwise}{\mathop{\unicode{x2939}\!\!\unicode{x0222F}}}}
\CustomizeMathJax{\newcommand{\varoiintclockwise}{\mathop{\unicode{x0222F}\!\!\unicode{x2938}}}}
\CustomizeMathJax{\newcommand{\varoiintctrclockwise}{\mathop{\unicode{x2939}\!\!\unicode{x0222F}}}}
\CustomizeMathJax{\newcommand{\oiiintclockwise}{\mathop{\unicode{x02230}\!\!\unicode{x2938}}}}
\CustomizeMathJax{\newcommand{\oiiintctrclockwise}{\mathop{\unicode{x2939}\!\!\unicode{x02230}}}}
\CustomizeMathJax{\newcommand{\varoiiintclockwise}{\mathop{\unicode{x02230}\!\!\unicode{x2938}}}}
\CustomizeMathJax{\newcommand{\varoiiintctrclockwise}{\mathop{\unicode{x2939}\!\!\unicode{x02230}}}}
\CustomizeMathJax{\newcommand{\sqiint}{\mathop{\unicode{x2A16}\!\!\unicode{x2A16}}}}
\CustomizeMathJax{\newcommand{\sqiiint}{\mathop{\unicode{x2A16}\!\!\unicode{x2A16}\!\!\unicode{x2A16}}}

\CustomizeMathJax{\let\widearc\overparen}
\CustomizeMathJax{\let\widearcarrow\overrightarrow}
\CustomizeMathJax{\let\overrightarc\overrightarrow}

\end{warpMathJax}
```

---

File 234 **lwarp-layaureo.sty**

# § 341 Package layaureo

Pkg layaureo layaureo is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{layaureo}[2004/09/16]
```

---

File 235 **lwarp-layout.sty**

# § 342 Package layout

Pkg layout layout is ignored.

**for HTML output:** Discard all options for lwarp-layout:

```
\LWR@ProvidesPackageDrop{layout}[2014/10/28]

\NewDocumentCommand{\layout}{s}{}
```

File 236 **lwarp-layouts.sty**

# § 343 Package layouts

Pkg layouts layouts is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{layouts}[2009/09/02]

\newif\ifoddpagelayout
  \oddpagelayouttrue
\newif\iftwocolumnlayout
  \twocolumnlayoutfalse
\newif\ifdrawmarginpars
  \drawmarginparstrue
\newif\ifdrawparameters
  \drawparameterstrue
\newif\iflistaspara
  \listasparatrue
\newif\ifruninhead
  \runinheadfalse
\newif\ifprintparameters
  \printparameterstrue
\newif\ifdrawdimensions
  \drawdimensionsfalse
\newif\ifprintheadings
  \printheadingstrue
\newcommand{\testdrawdimensions}{}
\newcommand{\testprintparameters}{}
\newcommand{\setlabelfont}[1]{}
\newcommand{\setparametertextfont}[1]{}
\newcommand{\setvaluestextsize}[1]{}
\newcommand{\setlayoutscale}[1]{}
\newcommand{\setuplayouts}{}
\newcommand{\printinunitsof}[1]{}
\newcommand{\prntlen}[1]{}
\newcommand{\trypaperwidth}[1]{}
\newcommand{\trypaperheight}[1]{}
\newcommand{\tryhoffset}[1]{}
\newcommand{\tryvoffset}[1]{}
\newcommand{\trytopmargin}[1]{}
\newcommand{\tryheadheight}[1]{}
\newcommand{\tryheadsep}[1]{}
\newcommand{\trytextheight}[1]{}
\newcommand{\tryfootskip}[1]{}
\newcommand{\tryoddsidemargin}[1]{}
\newcommand{\tryevensidemargin}[1]{}
\newcommand{\trytextwidth}[1]{}
\newcommand{\trymarginparsep}[1]{}
\newcommand{\trymarginparwidth}[1]{}
\newcommand{\trymarginparpush}[1]{}
\newcommand{\trycolumnsep}[1]{}
```

```
\newcommand{\trycolumnseprule}[1]{}
\newcommand{\setfootbox}[2]{}
\newcommand{\currentpage}{}
\newcommand{\drawpage}{(draw page)}
\newcommand{\pagediagram}{(page diagram)}
\newcommand{\pagedesign}{(page design)}
\newcommand{\pagevalues}{(page values)}
\newcommand{\trystockwidth}[1]{}
\newcommand{\trystockheight}[1]{}
\newcommand{\trytrimedge}[1]{}
\newcommand{\trytrimtop}[1]{}
\newcommand{\tryuppermargin}[1]{}
\newcommand{\tryspinemargin}[1]{}
\newcommand{\currentstock}{}
\newcommand{\drawstock}{(draw stock)}
\newcommand{\stockdiagram}{(stock diagram)}
\newcommand{\stockdesign}{(stock design)}
\newcommand{\stockvalues}{(stock values)}
\newcommand{\tryitemindent}[1]{}
\newcommand{\trylabelwidth}[1]{}
\newcommand{\trylabelsep}[1]{}
\newcommand{\tryleftmargin}[1]{}
\newcommand{\tryrightmargin}[1]{}
\newcommand{\trylistparindent}[1]{}
\newcommand{\trytopsep}[1]{}
\newcommand{\tryparskip}[1]{}
\newcommand{\trypartopsep}[1]{}
\newcommand{\tryparsep}[1]{}
\newcommand{\tryitemsep}[1]{}
\newcommand{\currentlist}{}
\newcommand{\drawlist}{(draw list)}
\newcommand{\listdiagram}{(list diagram)}
\newcommand{\listdesign}{(list design)}
\newcommand{\listvalues}{(list values)}
\newcommand{\tryfootins}[1]{}
\newcommand{\tryfootnotesep}[1]{}
\newcommand{\tryfootnotebaseline}[1]{}
\newcommand{\tryfootruleheight}[1]{}
\newcommand{\tryfootrulefrac}[1]{}
\newcommand{\currentfootnote}{}
\newcommand{\drawfootnote}{(draw footnote)}
\newcommand{\footnotediagram}{(footnote diagram)}
\newcommand{\footnotedesign}{(footnote design)}
\newcommand{\footnotevalues}{(footnote values)}
\newcommand{\tryparindent}[1]{}
\newcommand{\tryparlinewidth}[1]{}
\newcommand{\tryparbaselineskip}[1]{}
\newcommand{\currentparagraph}{}
\newcommand{\drawparagraph}{(draw paragraph)}
\newcommand{\paragraphdiagram}{(paragraph diagram)}
\newcommand{\paragraphdesign}{(paragraph design)}
\newcommand{\paragraphvalues}{(paragraph values)}
\newcommand{\trybeforeskip}[1]{}
\newcommand{\tryafterskip}[1]{}
\newcommand{\tryindent}[1]{}
```

```
\newcommand{\currentheading}{}
\newcommand{\drawheading}[1]{(draw heading)}
\newcommand{\headingdiagram}[1]{(heading diagram)}
\newcommand{\headingdesign}[1]{(heading design)}
\newcommand{\headingvalues}{(heading values)}
\newcommand{\trytextfloatsep}[1]{}
\newcommand{\tryfloatsep}[1]{}
\newcommand{\tryintextsep}[1]{}
\newcommand{\trytopfigrule}[1]{}
\newcommand{\trybotfigrule}[1]{}
\newcommand{\currentfloat}{}
\newcommand{\drawfloat}{(draw float)}
\newcommand{\floatdiagram}{(float diagram)}
\newcommand{\floatdesign}{(float design)}
\newcommand{\floatvalues}{(float values)}
\newcommand{\trytotalnumber}[1]{}
\newcommand{\trytopnumber}[1]{}
\newcommand{\trybottomnumber}[1]{}
\newcommand{\trytopfraction}[1]{}
\newcommand{\trytextfraction}[1]{}
\newcommand{\trybottomfraction}[1]{}
\newcommand{\currentfloatpage}{}
\newcommand{\drawfloatpage}{(draw floatpage)}
\newcommand{\floatpagediagram}{(floatpage diagram)}
\newcommand{\floatpagedesign}{(floatpage design)}
\newcommand{\floatpagevalues}{(floatpage values)}
\newcommand{\trytocindent}[1]{}
\newcommand{\trytocnumwidth}[1]{}
\newcommand{\trytoclinewidth}[1]{}
\newcommand{\trytocrmarg}[1]{}
\newcommand{\trytocpnumwidth}[1]{}
\newcommand{\trytocdotsep}[1]{}
\newcommand{\currenttoc}{}
\newcommand{\drawtoc}{(draw toc)}
\newcommand{\tocdiagram}{(toc diagram)}
\newcommand{\tocdesign}{(toc design)}
\newcommand{\tocvalues}{(toc values)}
\newcommand{\drawaspread}[8][0]{(a spread)}
\newcommand{\drawfontframe}[1]{(font frame)}
\newcommand{\drawfontframelabel}[1]{}
```

File 237 **lwarp-leading.sty**

# § 344 Package leading

Pkg `leading` leading is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{leading}[2008/12/11]
\newcommand\leading[1]{}
```

File 238 **lwarp-leftidx.sty**

## § 345 Package leftidx

(*Emulates or patches code by* Harald Harders.)

Pkg leftidx leftidx works as-is with SVG math, and is emulated for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{leftidx}[2003/09/24]

\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\leftidx}[3]{{\vphantom{#2}}#1#2#3}}
\CustomizeMathJax{\newcommand{\ltrans}[1]{\leftidx{^\mathrm{t}}{\!#1}{}}}
\end{warpMathJax}
```

---

File 239 **lwarp-letterspace.sty**

## § 346 Package letterspace

(*Emulates or patches code by* R Schlicht.)

Pkg letterspace letterspace is a subset of microtype, which is pre-loaded by lwarp. All user options and macros are ignored and disabled.

**for HTML output:** Discard all options for lwarp-letterspace:

```
\LWR@ProvidesPackageDrop{letterspace}[2018/01/14]

\newcommand*\lsstyle{}
\newcommand\textls[2][]{}
\def\textls#1#{}
\newcommand*\lslig[1]{#1}
```

---

File 240 **lwarp-lettrine.sty**

## § 347 Package lettrine

(*Emulates or patches code by* Daniel Flipo.)

Pkg lettrine lettrine is emulated.

**for HTML output:** Discard all options for lwarp-lettrine:

```
\LWR@ProvidesPackageDrop{lettrine}[2018-08-28]
```

The initial letter is in a  of class `lettrine`, and the following text is in a  of class `lettrinetext`. `\lettrine` [⟨*keys*⟩] {⟨*letter*⟩} {⟨*additional text*⟩}

```
\DeclareDocumentCommand{\lettrine}{o m m}{%
    \InlineClass{lettrine}{#2}\InlineClass{lettrinetext}{#3} % extra space
}

```

```
\newcounter{DefaultLines}
\setcounter{DefaultLines}{2}
\newcounter{DefaultDepth}
\newcommand*{\DefaultOptionsFile}{\relax}
\newcommand*{\DefaultLoversize}{0}
\newcommand*{\DefaultLraise}{0}
\newcommand*{\DefaultLhang}{0}
\newdimen\DefaultFindent
\setlength{\DefaultFindent}{\z@}
\newdimen\DefaultNindent
\setlength{\DefaultNindent}{0.5em}
\newdimen\DefaultSlope
\setlength{\DefaultSlope}{\z@}
\newdimen\DiscardVskip
\setlength{\DiscardVskip}{0.2\p@}
\newif\ifLettrineImage
\newif\ifLettrineOnGrid
\newif\ifLettrineRealHeight

\newcommand*{\LettrineTextFont}{\scshape}
\newcommand*{\LettrineFontHook}{}
\newcommand*{\LettrineFont}[1]{\InlineClass{lettrine}{#1}}
\newcommand*{\LettrineFontEPS}[1]{\includegraphics[height=1.5ex]{#1}}
```

---

File 241 **lwarp-libertinust1math.sty**

## § 348 Package libertinust1math

(*Emulates or patches code by* Michael Sharpe.)

Pkg libertinust1math libertinust1math is used as-is for SVG math, and is emulated for MathJax.

The MathJax emulation honors `frenchmath` for Greek but not Latin characters, and `slantedGreek`, `uprightGreek`, and `ISO` also adjust Greek characters. MathJax cannot yet honor options for adjusting Latin characters.

The dedicated macros for upright and italic Greek letters do work correctly.

Some of the symbol font macros such as `\mathsfbf` do not use a sans font because MathJax does not yet have sans Greek.

SVG math honors all font choices, and should appear the same as the printed output.

**for HTML output:**

```
\LWR@ProvidesPackagePass{libertinust1math}[2020/06/10]

\LWR@infoprocessingmathjax{libertinust1math}

\LWR@origRequirePackage{lwarp-common-mathjax-letters}

\begin{warpMathJax}

\iflibus@slantedG
    \LWR@mathjax@addgreek@u@it*{}{}
```

```
\else
    \LWR@mathjax@addgreek@u@up*{}{}
\fi

\LWR@mathjax@addgreek@u@it*{}{it}
\LWR@mathjax@addgreek@u@up*{up}{}
\LWR@mathjax@addgreek@u@up*{}{up}

\iflibus@frenchm
    \LWR@mathjax@addgreek@l@up{}{}
\else
    \LWR@mathjax@addgreek@l@it{}{}
\fi

\LWR@mathjax@addgreek@l@it{}{it}
\LWR@mathjax@addgreek@l@up{}{up}
\LWR@mathjax@addgreek@l@up{up}{}

\CustomizeMathJax{\let\uppartial\partial}% not upright


\CustomizeMathJax{\let\mathsfbf\mathbf}% not sans
% \CustomizeMathJax{\newcommand{\mathsfbf}[1]{%
%     \mmlToken{mi}[mathvariant="bold-sans-serif"]{#1}% not greek
% }}% not sans

% \CustomizeMathJax{\newcommand{\mathbfit}[1]{\boldsymbol{#1}}}
\CustomizeMathJax{\let\mathbfit\boldsymbol}


% \CustomizeMathJax{\newcommand{\mathsfbfit}[1]{\boldsymbol{#1}}}% not sans
\CustomizeMathJax{\let\mathsfbfit\mathbfit}% not sans
% \CustomizeMathJax{\newcommand{\mathsfbfit}[1]{%
%     \mmlToken{mi}[mathvariant="sans-serif-bold-italic"]{#1}% not greek
% }}%


\CustomizeMathJax{\let\mathsfit\mathit}% not sans
% \CustomizeMathJax{\newcommand{\mathsfit}[1]{%
%     \mmlToken{mi}[mathvariant="sans-serif-italic"]{#1}% not greek
% }}

\CustomizeMathJax{\let\vectorsym\mathbfit}
\CustomizeMathJax{\let\matrixsym\mathbfit}
\CustomizeMathJax{\let\tensorsym\mathsfbfit}
\CustomizeMathJax{\let\mathboldsans\mathsfbfit}
\CustomizeMathJax{\let\mathbold\mathbfit}
```

`lwarp_mathjax.txt` adds `\left`/`\right` support for delimiters.

```
\CustomizeMathJax{\let\dlb\lBrack}
\CustomizeMathJax{\let\drb\rBrack}

\CustomizeMathJax{\let\sqrtsign\sqrt}

\CustomizeMathJax{\let\smallintsl\smallint}
```

```
\CustomizeMathJax{\newcommand{\smalliintsl}{\mathop{\unicode{x222C}}\limits}}
\CustomizeMathJax{\newcommand{\smalliiintsl}{\mathop{\unicode{x222D}}\limits}}
\CustomizeMathJax{\newcommand{\smalliiiintsl}{\mathop{\unicode{x2A0C}}\limits}}
\CustomizeMathJax{\newcommand{\smallointsl}{\mathop{\unicode{x222E}}\limits}}
\CustomizeMathJax{\newcommand{\smalloiintsl}{\mathop{\unicode{x222F}}\limits}}

\CustomizeMathJax{\let\smallintup\smallint}
\CustomizeMathJax{\newcommand{\smalliintup}{\mathop{\unicode{x222C}}\limits}}
\CustomizeMathJax{\newcommand{\smalliiintup}{\mathop{\unicode{x222D}}\limits}}
\CustomizeMathJax{\newcommand{\smalliiiintup}{\mathop{\unicode{x2A0C}}\limits}}
\CustomizeMathJax{\newcommand{\smallointup}{\mathop{\unicode{x222E}}\limits}}
\CustomizeMathJax{\newcommand{\smalloiintup}{\mathop{\unicode{x222F}}\limits}}

\CustomizeMathJax{\let\intslop\int}
\CustomizeMathJax{\newcommand{\iintslop}{\mathop{\unicode{x222C}}\limits}}
\CustomizeMathJax{\newcommand{\iiintslop}{\mathop{\unicode{x222D}}\limits}}
\CustomizeMathJax{\newcommand{\iiiintslop}{\mathop{\unicode{x2A0C}}\limits}}
\CustomizeMathJax{\let\ointslop\oint}
\CustomizeMathJax{\newcommand{\oiintslop}{\mathop{\unicode{x222F}}\limits}}
\CustomizeMathJax{\newcommand{\oiiintslop}{\mathop{\unicode{x2230}}\limits}}

\CustomizeMathJax{\let\intupop\int}
\CustomizeMathJax{\newcommand{\iintupop}{\mathop{\unicode{x222C}}\limits}}
\CustomizeMathJax{\newcommand{\iiintupop}{\mathop{\unicode{x222D}}\limits}}
\CustomizeMathJax{\newcommand{\iiiintupop}{\mathop{\unicode{x2A0C}}\limits}}
\CustomizeMathJax{\let\ointupop\oint}
\CustomizeMathJax{\newcommand{\oiintupop}{\mathop{\unicode{x222F}}\limits}}
\CustomizeMathJax{\newcommand{\oiiintupop}{\mathop{\unicode{x2230}}\limits}}

\CustomizeMathJax{\newcommand{\smalliint}{\mathop{\unicode{x222C}}\limits}}
\CustomizeMathJax{\newcommand{\smalliiint}{\mathop{\unicode{x222D}}\limits}}
\CustomizeMathJax{\newcommand{\smalliiiint}{\mathop{\unicode{x2A0C}}\limits}}
\CustomizeMathJax{\newcommand{\smalloint}{\mathop{\unicode{x222E}}\limits}}
\CustomizeMathJax{\newcommand{\smalloiint}{\mathop{\unicode{x222F}}\limits}}

\CustomizeMathJax{\let\intop\int}
\CustomizeMathJax{\newcommand{\iintop}{\mathop{\unicode{x222C}}\limits}}
\CustomizeMathJax{\newcommand{\iiintop}{\mathop{\unicode{x222D}}\limits}}
\CustomizeMathJax{\newcommand{\iiiintop}{\mathop{\unicode{x2A0C}}\limits}}
\CustomizeMathJax{\let\ointop\oint}
\CustomizeMathJax{\newcommand{\oiintop}{\mathop{\unicode{x222F}}\limits}}
\CustomizeMathJax{\newcommand{\oiiintop}{\mathop{\unicode{x2230}}\limits}}

\CustomizeMathJax{\newcommand{\oiint}{\mathop{\unicode{x222F}}\limits}}

\CustomizeMathJax{\newcommand{\bigcupdot}{\mathop{\unicode{x2A03}}}}
\CustomizeMathJax{\newcommand{\bigsqcap}{\mathop{\unicode{x2A05}}}}
\CustomizeMathJax{\newcommand{\xsol}{\mathop{\unicode{x29F8}}}}
\CustomizeMathJax{\newcommand{\xbsol}{\mathop{\unicode{x29F9}}}}
\CustomizeMathJax{\let\prodop\prod}
\CustomizeMathJax{\let\coprodop\coprod}
\CustomizeMathJax{\let\sumop\sum}
\CustomizeMathJax{\let\bigwedgeop\bigwedge}
\CustomizeMathJax{\let\bigveeop\bigvee}
\CustomizeMathJax{\let\bigcapop\bigcap}
```

```
\CustomizeMathJax{\let\bigcupop\bigcup}
\CustomizeMathJax{\let\xsolop\xsol}
\CustomizeMathJax{\let\xbsolop\xbsol}
\CustomizeMathJax{\let\bigodotop\bigodot}
\CustomizeMathJax{\let\bigoplusop\bigoplus}
\CustomizeMathJax{\let\bigotimesop\bigotimes}
\CustomizeMathJax{\let\bigcupdotop\bigcupdot}
\CustomizeMathJax{\let\biguplusop\biguplus}
\CustomizeMathJax{\let\bigsqcapop\bigsqcap}
\CustomizeMathJax{\let\bigsqcupop\bigsqcup}

\CustomizeMathJax{\newcommand{\ovhook}[1]{\mathord{#1\unicode{x00309}}}}
\CustomizeMathJax{\newcommand{\candra}[1]{\mathord{#1\unicode{x00310}}}}
\CustomizeMathJax{\newcommand{\oturnedcomma}[1]{\mathord{#1\unicode{x00312}}}}
\CustomizeMathJax{\newcommand{\ocommatopright}[1]{\mathord{#1\unicode{x00315}}}}
\CustomizeMathJax{\newcommand{\droang}[1]{\mathord{#1\unicode{x0031A}}}}
\CustomizeMathJax{\newcommand{\leftharpoonaccent}[1]{\mathord{#1\unicode{x020D0}}}}
\CustomizeMathJax{\newcommand{\rightharpoonaccent}[1]{\mathord{#1\unicode{x020D1}}}}
\CustomizeMathJax{\newcommand{\leftarrowaccent}[1]{\mathord{#1\unicode{x020D0}}}}
\CustomizeMathJax{\let\rightarrowaccent\vec}

\CustomizeMathJax{\newcommand{\leftrightarrowaccent}[1]{\mathord{#1\unicode{x020E1}}}}
\CustomizeMathJax{\newcommand{\annuity}[1]{\mathord{#1\unicode{x020E7}}}}
\CustomizeMathJax{\newcommand{\widebridgeabove}[1]{\mathord{#1\unicode{x020E9}}}}
\CustomizeMathJax{\newcommand{\asteraccent}[1]{\mathord{#1\unicode{x020F0}}}}

% neutralized:
\CustomizeMathJax{\newcommand{\braceld}{}}
\CustomizeMathJax{\newcommand{\bracerd}{}}
\CustomizeMathJax{\newcommand{\bracelu}{}}
\CustomizeMathJax{\newcommand{\braceru}{}}
\CustomizeMathJax{\newcommand{\braceex}{}}
\CustomizeMathJax{\newcommand{\bracemu}{}}
\CustomizeMathJax{\newcommand{\bracemd}{}}
\CustomizeMathJax{\newcommand{\parenld}{}}
\CustomizeMathJax{\newcommand{\parenrd}{}}
\CustomizeMathJax{\newcommand{\parenlu}{}}
\CustomizeMathJax{\newcommand{\parenru}{}}
\CustomizeMathJax{\newcommand{\bracketld}{}}
\CustomizeMathJax{\newcommand{\bracketrd}{}}
\CustomizeMathJax{\newcommand{\bracketlu}{}}
\CustomizeMathJax{\newcommand{\bracketru}{}}
\CustomizeMathJax{\newcommand{\bracketex}{}}
\CustomizeMathJax{\newcommand{\parenex}{}}

\CustomizeMathJax{\newcommand{lhook}{~}}
\CustomizeMathJax{\newcommand{rhook}{~}}
\CustomizeMathJax{\newcommand{relbar}{-}}
\CustomizeMathJax{\newcommand{Relbar}{=}}

\CustomizeMathJax{\newcommand{\mapstochar}{\mathrel{\unicode{x21A6}}}}

\CustomizeMathJax{\newcommand{\Zbar}{\mathord{\unicode{x0001B5}}}}
\CustomizeMathJax{\newcommand{\notchar}{\mathrel{\unicode{x000AC}}}}
\CustomizeMathJax{\newcommand{\upbackepsilon}{\mathord{\unicode{x03F6}}}}
```

```
\CustomizeMathJax{\newcommand{\smblkcircle}{\mathbin{\unicode{x02022}}}}
\CustomizeMathJax{\newcommand{\enleadertwodots}{\mathord{\unicode{x02025}}}}
\CustomizeMathJax{\newcommand{\unicodeellipsis}{\mathord{\unicode{x02026}}}}
\CustomizeMathJax{\newcommand{\mathellipsis}{\mathinner{\unicode{x02026}}}}
\CustomizeMathJax{\newcommand{\dprime}{\mathord{\unicode{x02033}}}}
\CustomizeMathJax{\newcommand{\trprime}{\mathord{\unicode{x02034}}}}
\CustomizeMathJax{\newcommand{\backdprime}{\mathord{\unicode{x02036}}}}
\CustomizeMathJax{\newcommand{\backtrprime}{\mathord{\unicode{x02037}}}}
\CustomizeMathJax{\newcommand{\caretinsert}{\mathord{\unicode{x02038}}}}
\CustomizeMathJax{\newcommand{\Exclam}{\mathord{\unicode{x0203C}}}}

\CustomizeMathJax{\newcommand{\hyphenbullet}{\mathord{\unicode{x02043}}}}
\CustomizeMathJax{\newcommand{\fracslash}{\mathbin{\unicode{x02044}}}}
\CustomizeMathJax{\newcommand{\Question}{\mathord{\unicode{x02047}}}}
\CustomizeMathJax{\newcommand{\closure}{\mathrel{\unicode{x02050}}}}
\CustomizeMathJax{\newcommand{\qprime}{\mathord{\unicode{x02057}}}}
\CustomizeMathJax{\newcommand{\vertoverlay}{\mathrel{\unicode{x020D2}}}}
\CustomizeMathJax{\newcommand{\enclosecircle}{\mathord{\unicode{x020DD}}}}
\CustomizeMathJax{\newcommand{\enclosesquare}{\mathord{\unicode{x020DE}}}}
\CustomizeMathJax{\newcommand{\enclosetriangle}{\mathord{\unicode{x020E4}}}}
\CustomizeMathJax{\newcommand{\Eulerconst}{\mathord{\unicode{x02107}}}}
\CustomizeMathJax{\newcommand{\turnediota}{\mathord{\unicode{x02129}}}}
\CustomizeMathJax{\newcommand{\Angstrom}{\mathord{\unicode{x0212B}}}}

\CustomizeMathJax{\newcommand{\sansLturned}{\mathord{\unicode{x02142}}}}
\CustomizeMathJax{\newcommand{\sansLmirrored}{\mathord{\unicode{x02143}}}}
\CustomizeMathJax{\newcommand{\Yup}{\mathord{\unicode{x02144}}}}
\CustomizeMathJax{\newcommand{\upand}{\mathbin{\unicode{x0214B}}}}
\CustomizeMathJax{\newcommand{\increment}{\mathord{\unicode{x02206}}}}
\CustomizeMathJax{\newcommand{\smallin}{\mathrel{\unicode{x0220A}}}}
\CustomizeMathJax{\newcommand{\nni}{\mathrel{\unicode{x0220C}}}}

\CustomizeMathJax{\newcommand{\smallni}{\mathrel{\unicode{x0220D}}}}
\CustomizeMathJax{\newcommand{\QED}{\mathord{\unicode{x0220E}}}}
\CustomizeMathJax{\newcommand{\vysmwhtcircle}{\mathbin{\unicode{x02218}}}}
\CustomizeMathJax{\newcommand{\vysmblkcircle}{\mathbin{\unicode{x02219}}}}
\CustomizeMathJax{\newcommand{\rightangle}{\mathord{\unicode{x0221F}}}}

\CustomizeMathJax{\newcommand{\Colon}{\mathrel{\unicode{x02237}}}}
\CustomizeMathJax{\newcommand{\dotminus}{\mathbin{\unicode{x02238}}}}
\CustomizeMathJax{\newcommand{\dashcolon}{\mathrel{\unicode{x02239}}}}
\CustomizeMathJax{\newcommand{\dotsminusdots}{\mathrel{\unicode{x0223A}}}}
\CustomizeMathJax{\newcommand{\kernelcontraction}{\mathrel{\unicode{x0223B}}}}
\CustomizeMathJax{\newcommand{\invlazys}{\mathbin{\unicode{x0223E}}}}

\CustomizeMathJax{\newcommand{\sinewave}{\mathord{\unicode{x0223F}}}}
\CustomizeMathJax{\newcommand{\nsime}{\mathrel{\unicode{x02244}}}}
\CustomizeMathJax{\newcommand{\simneqq}{\mathrel{\unicode{x02246}}}}
\CustomizeMathJax{\newcommand{\napprox}{\mathrel{\unicode{x02249}}}}
\CustomizeMathJax{\newcommand{\approxident}{\mathrel{\unicode{x0224B}}}}
\CustomizeMathJax{\newcommand{\backcong}{\mathrel{\unicode{x0224C}}}}

\CustomizeMathJax{\newcommand{\nasymp}{\mathrel{\unicode{x0226D}}}}
\CustomizeMathJax{\newcommand{\nlesssim}{\mathrel{\unicode{x02274}}}}
\CustomizeMathJax{\newcommand{\ngtrsim}{\mathrel{\unicode{x02275}}}}
```

```
\CustomizeMathJax{\newcommand{\nlessgtr}{\mathrel{\unicode{x02278}}}}
\CustomizeMathJax{\newcommand{\ngtrless}{\mathrel{\unicode{x02279}}}}

\CustomizeMathJax{\newcommand{\nsubset}{\mathrel{\unicode{x02284}}}}
\CustomizeMathJax{\newcommand{\nsupset}{\mathrel{\unicode{x02285}}}}

\CustomizeMathJax{\newcommand{\cupleftarrow}{\mathbin{\unicode{x0228C}}}}
\CustomizeMathJax{\newcommand{\cupdot}{\mathbin{\unicode{x0228D}}}}
\CustomizeMathJax{\newcommand{\circledequal}{\mathbin{\unicode{x0229C}}}}

\CustomizeMathJax{\newcommand{\assert}{\mathrel{\unicode{x022A6}}}}
\CustomizeMathJax{\newcommand{\VDash}{\mathrel{\unicode{x022AB}}}}
\CustomizeMathJax{\newcommand{\prurel}{\mathrel{\unicode{x022B0}}}}

\CustomizeMathJax{\newcommand{\origof}{\mathrel{\unicode{x022B6}}}}
\CustomizeMathJax{\newcommand{\smallprod}{\mathop{\unicode{x0220F}}}}% not small
\CustomizeMathJax{\newcommand{\smallcoprod}{\mathop{\unicode{x02210}}}}% not small
\CustomizeMathJax{\newcommand{\smallsum}{\mathop{\unicode{x02211}}}}% not small
\CustomizeMathJax{\newcommand{\Hfraktur}{\mathord{\unicode{x1D525}}}}
\CustomizeMathJax{\newcommand{\dsol}{\mathbin{\unicode{x029F6}}}}
\CustomizeMathJax{\newcommand{\rsolbar}{\mathbin{\unicode{x029F7}}}}

\CustomizeMathJax{\newcommand{\eqless}{\mathrel{\unicode{x022DC}}}}
\CustomizeMathJax{\newcommand{\eqgtr}{\mathrel{\unicode{x022DD}}}}
\CustomizeMathJax{\newcommand{\npreccurlyeq}{\mathrel{\unicode{x022E0}}}}
\CustomizeMathJax{\newcommand{\nsucccurlyeq}{\mathrel{\unicode{x022E1}}}}
\CustomizeMathJax{\newcommand{\nsqsubseteq}{\mathrel{\unicode{x022E2}}}}
\CustomizeMathJax{\newcommand{\nsqsupseteq}{\mathrel{\unicode{x022E3}}}}
\CustomizeMathJax{\newcommand{\sqsubsetneq}{\mathrel{\unicode{x022E4}}}}
\CustomizeMathJax{\newcommand{\sqsupsetneq}{\mathrel{\unicode{x022E5}}}}
\CustomizeMathJax{\newcommand{\nvartriangleleft}{\mathrel{\unicode{x022EA}}}}
\CustomizeMathJax{\newcommand{\nvartriangleright}{\mathrel{\unicode{x022EB}}}}

\CustomizeMathJax{\newcommand{\vdotsmath}{\mathrel{\unicode{x022EE}}}}
\CustomizeMathJax{\newcommand{\unicodecdots}{\mathord{\unicode{x022EF}}}}
\CustomizeMathJax{\newcommand{\adots}{\mathrel{\unicode{x022F0}}}}
\CustomizeMathJax{\newcommand{\succneq}{\mathrel{\unicode{x02AB2}}}}
\CustomizeMathJax{\newcommand{\preceqq}{\mathrel{\unicode{x02AB3}}}}
\CustomizeMathJax{\newcommand{\succeqq}{\mathrel{\unicode{x02AB4}}}}
\CustomizeMathJax{\newcommand{\precneq}{\mathrel{\unicode{x02AB1}}}}

\CustomizeMathJax{\newcommand{\mapsfrom}{\mathrel{\unicode{x021A4}}}}

\CustomizeMathJax{\newcommand{\longmapsfrom}{\mathrel{\unicode{x027FB}}}}

\CustomizeMathJax{\newcommand{\diameter}{\mathord{\unicode{x02300}}}}
\CustomizeMathJax{\newcommand{\coloneq}{\mathrel{\unicode{x02254}}}}
\CustomizeMathJax{\newcommand{\eqcolon}{\mathrel{\unicode{x02255}}}}
\CustomizeMathJax{\newcommand{\arceq}{\mathrel{\unicode{x02258}}}}
\CustomizeMathJax{\newcommand{\wedgeq}{\mathrel{\unicode{x02259}}}}
\CustomizeMathJax{\newcommand{\veeeq}{\mathrel{\unicode{x0225A}}}}

\CustomizeMathJax{\newcommand{\stareq}{\mathrel{\unicode{x0225B}}}}
\CustomizeMathJax{\newcommand{\eqdef}{\mathrel{\unicode{x0225D}}}}
\CustomizeMathJax{\newcommand{\measeq}{\mathrel{\unicode{x0225E}}}}
```

```
\CustomizeMathJax{\newcommand{\questeq}{\mathrel{\unicode{x0225F}}}}
\CustomizeMathJax{\newcommand{\nequiv}{\mathrel{\unicode{x02262}}}}
\CustomizeMathJax{\newcommand{\Equiv}{\mathrel{\unicode{x02263}}}}

\CustomizeMathJax{\newcommand{\house}{\mathord{\unicode{x02302}}}}

\CustomizeMathJax{\newcommand{\musicalnote}{\mathord{\unicode{x0266A}}}}
\CustomizeMathJax{\newcommand{\degree}{\mathord{\unicode{x000B0}}}}
\CustomizeMathJax{\newcommand{\mathsection}{\mathord{\unicode{x000A7}}}}
\CustomizeMathJax{\newcommand{\mathparagraph}{\mathord{\unicode{x000B6}}}}
\CustomizeMathJax{\newcommand{\checkmarkmath}{\mathord{\unicode{x02713}}}}
\CustomizeMathJax{\newcommand{\invnot}{\mathord{\unicode{x02310}}}}

\CustomizeMathJax{\newcommand{\mathvisiblespace}{\mathord{\unicode{x02423}}}}
\CustomizeMathJax{\newcommand{\mdlgblksquare}{\mathord{\unicode{x025A0}}}}
\CustomizeMathJax{\newcommand{\mdlgwhtsquare}{\mathord{\unicode{x025A1}}}}

\CustomizeMathJax{\newcommand{\bigblacktriangleup}{\mathord{\unicode{x025B2}}}}
\CustomizeMathJax{\newcommand{\varbigtriangleup}{\mathord{\unicode{x025B3}}}}

\CustomizeMathJax{\newcommand{\bigblacktriangledown}{\mathord{\unicode{x025BC}}}}
\CustomizeMathJax{\newcommand{\varbigtriangledown}{\mathord{\unicode{x025BD}}}}
\CustomizeMathJax{\newcommand{\Longmapsfrom}{\mathrel{\unicode{x027FD}}}}

% bug in print font:
\CustomizeMathJax{\newcommand{\mdlgblkdiamond}{\mathord{\unicode{x025C6}}}}

\CustomizeMathJax{\newcommand{\mdlgwhtdiamond}{\mathord{\unicode{x025C7}}}}
\CustomizeMathJax{\newcommand{\Longmapsto}{\mathrel{\unicode{x027FE}}}}
\CustomizeMathJax{\newcommand{\fisheye}{\mathord{\unicode{x025C9}}}}
\CustomizeMathJax{\newcommand{\mdlgwhtlozenge}{\mathord{\unicode{x025CA}}}}
\CustomizeMathJax{\newcommand{\mdlgwhtcircle}{\mathbin{\unicode{x025CB}}}}
\CustomizeMathJax{\newcommand{\bullseye}{\mathord{\unicode{x025CE}}}}
\CustomizeMathJax{\newcommand{\mdlgblkcircle}{\mathord{\unicode{x025CF}}}}

\CustomizeMathJax{\newcommand{\Nwarrow}{\mathrel{\unicode{x021D6}}}}
\CustomizeMathJax{\newcommand{\Nearrow}{\mathrel{\unicode{x021D7}}}}
\CustomizeMathJax{\newcommand{\Searrow}{\mathrel{\unicode{x021D8}}}}
\CustomizeMathJax{\newcommand{\Swarrow}{\mathrel{\unicode{x021D9}}}}

\CustomizeMathJax{\newcommand{\Mapsfrom}{\mathord{\unicode{x02906}}}}
\CustomizeMathJax{\newcommand{\smwhtcircle}{\mathord{\unicode{x025E6}}}}
\CustomizeMathJax{\newcommand{\smwhtdiamond}{\mathbin{\unicode{x022C4}}}}
\CustomizeMathJax{\newcommand{\Mapsto}{\mathord{\unicode{x02907}}}}

\CustomizeMathJax{\let\ngets\nleftarrow}
\CustomizeMathJax{\let\nsimeq\nsime}
\CustomizeMathJax{\let\nle\nleq}
\CustomizeMathJax{\let\nge\ngeq}

\end{warpMathJax}
```

File 242 **lwarp-lineno.sty**

# § 349 Package lineno

(*Emulates or patches code by* Stephan I. Böttcher.)

Pkg lineno lineno is partly emulated, but mostly ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{lineno}[2005/11/02]

\newcommand*\resetlinenumber[1][\@ne]{}

\def\linenumbers{%
    \@ifnextchar[{\resetlinenumber}%]
                 {\@ifstar{\resetlinenumber}{}}%
    }

\newcommand*{\nolinenumbers}{}

\@namedef{linenumbers*}{\par\linenumbers*}
\@namedef{runninglinenumbers*}{\par\runninglinenumbers*}

\def\endlinenumbers{\par}
\let\endrunninglinenumbers\endlinenumbers
\let\endpagewiselinenumbers\endlinenumbers
\expandafter\let\csname endlinenumbers*\endcsname\endlinenumbers
\expandafter\let\csname endrunninglinenumbers*\endcsname\endlinenumbers
\let\endnolinenumbers\endlinenumbers

\def\pagewiselinenumbers{\linenumbers\setpagewiselinenumbers}

\def\runninglinenumbers{\setrunninglinenumbers\linenumbers}

\def\setpagewiselinenumbers{}

\def\setrunninglinenumbers{}

\def\linenomath{}%
\@namedef{linenomath*}{}%
\def\endlinenomath{}
\expandafter\let\csname endlinenomath*\endcsname\endlinenomath

\let\linelabel\label

\def\switchlinenumbers{\@ifstar{}{}}
\def\setmakelinenumbers#1{\@ifstar{}{}}

\def\leftlinenumbers{\@ifstar{}{}}
\def\rightlinenumbers{\@ifstar{}{}}

\newcounter{linenumber}
\newcount\c@pagewiselinenumber
\let\c@runninglinenumber\c@linenumber

\def\runningpagewiselinenumbers{}
\def\realpagewiselinenumbers{}

```

```
\NewDocumentCommand\modulolinenumbers{s o}{}

\chardef\c@linenumbermodulo=5
\modulolinenumbers[1]

\newcommand*\firstlinenumber[1]{}

\newcommand\internallinenumbers{}
\let\endinternallinenumbers\endlinenumbers
\@namedef{internallinenumbers*}{\internallinenumbers}
\expandafter\let\csname endinternallinenumbers*\endcsname\endlinenumbers

\newcommand*{\linenoplaceholder}[1]{% redefine per language
    (line number reference for \detokenize\expandafter{#1})
}

\newcommand*{\lineref}[2][]{\linenoplaceholder{#2}}
\newcommand*{\linerefp}[2][]{\linenoplaceholder{#2}}
\newcommand*{\linerefr}[2][]{\linenoplaceholder{#2}}

\newcommand\quotelinenumbers
   {\@ifstar\linenumbers{\@ifnextchar[\linenumbers{\linenumbers*}}}

\newdimen\linenumbersep
\newdimen\linenumberwidth
\newdimen\quotelinenumbersep

\quotelinenumbersep=\linenumbersep
\let\quotelinenumberfont\linenumberfont

\def\linenumberfont{\normalfont\tiny\sffamily}


\linenumberwidth=10pt
\linenumbersep=10pt

\def\thelinenumber{}

\def\LineNumber{}
\def\makeLineNumber{}
\def\makeLineNumberLeft{}
\def\makeLineNumberRight{}
\def\makeLineNumberOdd{}
\def\makeLineNumberEven{}
\def\makeLineNumberRunning{}


\newenvironment{numquote}     {\quote}{\endquote}
\newenvironment{numquotation} {\quotation}{\endquotation}
\newenvironment{numquote*}    {\quote}{\endquote}
\newenvironment{numquotation*}{\quotation}{\endquotation}

\newdimen\bframerule
\bframerule=\fboxrule
```

```
104
105 \newdimen\bframesep
106 \bframesep=\fboxsep
107
108 \newenvironment{bframe}
109 {%
110     \LWR@forceminwidth{\bframerule}%
111     \BlockClass[
112         border:\LWR@printlength{\LWR@atleastonept} solid black ; %
113         padding:\LWR@printlength{\bframesep}%
114     ]{bframe}
115 }
116 {\endBlockClass}
```

File 243 **lwarp-lips.sty**

## § 350 Package lips

(*Emulates or patches code by* Matt Swift.)

Pkg lips lips is emulated.

```
1 % \LWR@ProvidesPackageDrop{lips}
2 \PackageInfo{lwarp}{Using the lwarp version of package ‘lips’.}%
3 \ProvidesPackage{lwarp-lips}[2001/08/31]
4
5 \NewDocumentCommand{\Lips}{}{\textellipsis}
6
7 \NewDocumentCommand{\BracketedLips}{}{[\textellipsis]}
8
9 \let\lips\Lips
10 \let\olips\lips
11
12 \DeclareOption*{}
13 \DeclareOption{mla}{
14 \let\lips\BracketedLips
15 }
16 \ProcessOptions\relax
17
18 \newcommand \LPNobreakList {}
```

File 244 **lwarp-listings.sty**

## § 351 Package listings

(*Emulates or patches code by* Carsten Heinz, Brooks Moses, Jobst Hoffmann.)

Pkg listings listings is supported with some limitations. Text formatting is not yet supported.

```
1 \LWR@ProvidesPackagePass{listings}[2018/09/02]
```

Force flexible columns. Fixed columns inserts spaces in the PDF output.

```
\lst@column@flexible
```

Patches to embed listings inside `pre` tags:

```
\let\LWR@origlst@Init\lst@Init
\let\LWR@origlst@DeInit\lst@DeInit

\let\LWR@origlsthkEveryPar\lsthk@EveryPar

\renewcommand{\l@lstlisting}[2]{\hypertocfloat{1}{lstlisting}{lol}{#1}{#2}}
```

`\lstset` {⟨*options*⟩}

Use the listings `literate` option to replace HTML entities:

```
\def\lstset@#1{\endgroup%
%  \ifx\@empty#1%
%         \@empty%
%     \else%
        \setkeys{lst}{%
            #1%
            ,literate=%
            {<}{\HTMLentity{lt}}{4}%
            {>}{\HTMLentity{gt}}{4}%
            {'}{\HTMLentity{apos}}{6}%
            {‘}{\HTMLentity{grave}}{7}%
```

The ampersand is not treated here, as the result is inconsistent spacing. It is nevertheless converted to `&` elsewhere. Sanitizing the double quote interferes with listings' conversion of visible spaces inside strings.

```
        }%
%     \fi%
}
```

`\lst@Init` {⟨*backslash-processing*⟩} Done at the start of a listing.

```
\renewcommand{\lst@Init}[1]{%
```

Perform the listings initialization:

```
\LWR@traceinfo{lst@Init}%
```

`\LWR@forcenewpage` is moved to the start to avoid a spurrious bug with paragraph handling and conditionals.

```
\lst@ifdisplaystyle%
    \LWR@forcenewpage%
\fi%
\renewcommand*{\@captype}{lstlisting}%
\let\lst@aboveskip\z@\let\lst@belowskip\z@%
\gdef\lst@boxpos{t}%
\let\lst@frame\@empty
    \let\lst@frametshape\@empty
    \let\lst@framershape\@empty
```

```
    \let\lst@framebshape\@empty
    \let\lst@framelshape\@empty
\lstframe@\lst@frameround ffff\relax%
\lst@multicols\@empty%
\LWR@origlst@Init{#1}\relax%
```

Avoids extra horizontal space:

```
\def\lst@framelr{}%
```

```
\LWR@traceinfo{finished origlst@Init}%
\lst@ifdisplaystyle%
```

Creating a display.

Disable line numbers, produce the <pre>, then reenable line numbers.

```
    \LWR@traceinfo{About to create verbatim.}%
    \let\lsthk@EveryPar\relax%

    \LWR@atbeginverbatim{programlisting}%

    \let\lsthk@EveryPar\LWR@origlsthkEveryPar%
\else%
```

Inline, so open a :

```
    \ifbool{LWR@verbtags}{\LWR@htmltag{%
        span class=\textquotedbl{}inlineprogramlisting\textquotedbl%
    }}{}%
\fi%
\LWR@traceinfo{lst@Init done}%
}

```

`\lst@DeInit` Done at the end of a listing.

```
\renewcommand*{\lst@DeInit}{%
\lst@ifdisplaystyle%
```

Creating a display.

Disable line numbers, produce the </pre>, then reenable line numbers:

```
    \let\lsthk@EveryPar\relax%
    \LWR@afterendverbatim%
    \let\lsthk@EveryPar\LWR@origlsthkEveryPar%
\else%
```

Inline, so create the closing :

```
    \ifbool{LWR@verbtags}{\noindent\LWR@htmltag{/span}}{}%
\fi%
```

Final listings deinit:

```
\LWR@origlst@DeInit%
}
```

`\lst@MakeCaption` {⟨*t/b*⟩}

This is called BOTH at the top and at the bottom of each listing.

Patched for lwarp.

```
\def\lst@MakeCaption#1{%
\LWR@traceinfo{MAKING CAPTION at #1}%
  \lst@ifdisplaystyle
\LWR@traceinfo{making a listings display caption}%
    \ifx #1t%
         \ifx\lst@@caption\@empty\expandafter\lst@HRefStepCounter \else
                                  \expandafter\refstepcounter
         \fi {lstlisting}%
\LWR@traceinfo{About to assign label: !\lst@label!}%
%         \ifx\lst@label\@empty\else
% \label{\lst@label}\fi
\LWR@traceinfo{Finished assigning the label.}%
        \let\lst@arg\lst@intname \lst@ReplaceIn\lst@arg\lst@filenamerpl
        \global\let\lst@name\lst@arg \global\let\lstname\lst@name
        \lst@ifnolol\else
            \ifx\lst@@caption\@empty
                \ifx\lst@caption\@empty
                    \ifx\lst@intname\@empty
                    \else
                        \def\lst@temp{ }%
                        \ifx\lst@intname\lst@temp \else
```

This code places a contents entry for a non-float. This would have to be modified for lwarp:

```
\LWR@traceinfo{addcontents lst@name: -\lst@name-}%
%                            \addcontentsline{lol}{lstlisting}{\lst@name}
                        \fi
                    \fi
                \fi
            \else
```

This would have to be modified for lwarp:

```
\LWR@traceinfo{addcontents lst@@caption: -\lst@@caption-}%
                 \addcontentsline{lol}{lstlisting}%
{\protect\numberline{\thelstlisting}%
{\protect\ignorespaces \LWR@isolate{\lst@@caption} \protect\relax}}%
            \fi
        \fi
     \fi
    \ifx\lst@caption\@empty\else
\LWR@traceinfo{lst@caption not empty-}%
        \lst@IfSubstring #1\lst@captionpos
            {\begingroup
\LWR@traceinfo{at the selected position}%
```

These space and box commands are not needed for HTML output:

```
%              \let\@@vskip\vskip
%              \def\vskip{\afterassignment\lst@vskip \@tempskipa}%
%              \def\lst@vskip{\nobreak\@@vskip\@tempskipa\nobreak}%
%              \par\@parboxrestore\normalsize\normalfont % \noindent (AS)
%              \ifx #1t\allowbreak \fi
             \ifx\lst@title\@empty
```

New lwarp code to create a caption:

```
                    \LWR@stoppars%
                  \lst@makecaption\fnum@lstlisting{\ignorespaces \lst@caption}
            \else
```

New lwarp code to create a title:

```
%                 \lst@maketitle\lst@title % (AS)
\LWR@traceinfo{Making title: \lst@title}%
\begin{BlockClass}{lstlistingtitle}%    lwarp
\lst@maketitle\lst@title%               lwarp
\end{BlockClass}%                       lwarp
            \fi
\LWR@traceinfo{About to assign label: !\lst@label!}%
        \ifx\lst@label\@empty\else
\leavevmode% gets rid of bad space factor error
\GetTitleStringExpand{\lst@caption}%
\edef\LWR@lntemp{\GetTitleStringResult}%
\edef\@currentlabelname{\detokenize\expandafter{\LWR@lntemp}}%
\label{\lst@label}\fi
\LWR@traceinfo{Finished assigning the label.}%
```

Not needed for lwarp:

```
%             \ifx #1b\allowbreak \fi
            \endgroup}{}%
    \fi
\LWR@traceinfo{end of making a listings display caption}%
  \else
\LWR@traceinfo{INLINE}%
  \fi
\LWR@traceinfo{DONE WITH CAPTION at #1}%
}

\renewcommand{\lst@maketitle}[1]{%
    \LWR@isolate{#1}%
}%

```

line numbers

Patched to keep left line numbers outside of the left margin, and place right line numbers in a field `\VerbatimHTMLWidth` wide.

```
\lst@Key{numbers}{none}{%
    \let\lst@PlaceNumber\@empty
    \lstKV@SwitchCases{#1}%
    {none:\\%
     left:\def\lst@PlaceNumber{%
```

For now, lwarp places left line numbers inline. Ideally the entire line would be moved to the right, but conflicts with list indenting occurs.

```
%         \LWR@origllap{
            \LWR@orignormalfont%
            \lst@numberstyle{\thelstnumber}\kern\lst@numbersep%
%         }
    }\\%
     right:\def\lst@PlaceNumber{\LWR@origrlap{\LWR@orignormalfont
                \kern 6in \kern\lst@numbersep
```

Error for heads which should have been in \warpprintonly:

```
\newcommand*{\LWR@longtable@headerror}{%
    \PackageError{lwarp-longtable}
    {For longtable:\MessageBreak
    1: Keep either one of an \protect\endhead\space or
        \protect\endfirsthead\space\MessageBreak
        \space phrase as-is, to be used by both print and HTML.\MessageBreak
    2: Place any other \protect\end... phrases inside a\MessageBreak
        \space\protect\warpprintonly\space macro,
            to be ignored by HTML.\MessageBreak
    3: Add a final footer for HTML at the end of the table\MessageBreak
        \space inside a \protect\warpHTMLonly\space macro.
            This can be\MessageBreak
        \space a copy of an \protect\endfoot\space or
            \protect\endfirstfoot\space phrase,\MessageBreak
        \space but without the actual \protect\endfoot\space
            or \protect\endfirstfoot\MessageBreak
        \space macros.  If using threeparttablex, add\MessageBreak
        \space \protect\insertTableNotes\space here,
            optionally with\MessageBreak
        \space \protect\UseMinipageWidths\space in front.\MessageBreak
    See the Lwarp documentation regarding longtables\MessageBreak
    and threeparttablex}
    {See the Lwarp documentation regading longtables and threeparttablex.}
}
```

Error if more than one of \endhead or \endfirsthead is outside of warpprintonly.

```
\newcommand*{\LWR@longtable@maybeheaderror}{%
\ifbool{LWR@longtable@havehead}%
    {\LWR@longtable@headerror}%
    {%
        \booltrue{LWR@longtable@havehead}
        \LWR@tabularendofline% throws away options //[dim] and //*
    }%
}
```

Error if more than one of these is outside of warpprint.

```
\def\endhead{\LWR@longtable@maybeheaderror}
\def\endfirsthead{\LWR@longtable@maybeheaderror}
```

Error if ANY of these is outside of warpprint.

```
\def\endfoot{\LWR@longtable@headerror}
\def\endlastfoot{\LWR@longtable@headerror}
```

```
\providecommand*{\LWR@HTML@tabularnewline}{\LWR@tabularendofline}
\LWR@formatted{tabularnewline}
```

```
\newcommand{\setlongtables}{}% Obsolete command, does nothing.
\newlength{\LTleft}
\newlength{\LTright}
\newlength{\LTpre}
```

```
\newlength{\LTpost}
\newlength{\LTcapwidth}

\LetLtxMacro\LWR@origkill\kill
\renewcommand*{\kill}{\LWR@tabularendofline}
\appto\LWR@restoreorigformatting{%
\LetLtxMacro\kill\LWR@origkill%
}
```

File 248 **lwarp-lpic.sty**

## § 355 Package lpic

(*Emulates or patches code by* R. Matveyev.)

Pkg lpic lpic is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{lpic}[2010/12/23]

\BeforeBeginEnvironment{lpic}{%
    \begin{lateximage}[-lpic-~\PackageDiagramAltText]%
}

\AfterEndEnvironment{lpic}{\end{lateximage}}
```

File 249 **lwarp-lscape.sty**

## § 356 Package lscape

(*Emulates or patches code by* D. P. Carlisle.)

Pkg lscape lscape is ignored.

**for HTML output:** Discard all options for lwarp-lscape.

```
\LWR@ProvidesPackageDrop{lscape}[2000/10/22]

\newenvironment*{landscape}{}{}
```

File 250 **lwarp-ltablex.sty**

## § 357 Package ltablex

(*Emulates or patches code by* Anil K. Goel.)

Pkg ltablex ltablex is emulated by lwarp.

**for HTML output:**

Relies on tabularx.

```
\RequirePackage{longtable}
\RequirePackage{tabularx}

\LWR@ProvidesPackageDrop{ltablex}[2014/08/13]

\DeclareDocumentEnvironment{tabularx}{m o m}
{\longtable{#3}}
{\endlongtable}

\DeclareDocumentEnvironment{tabularx*}{m o m}
{\longtable{#3}}
{\endlongtable}

\newcommand*{\keepXColumns}{}
\newcommand*{\convertXColumns}{}
```

---

File 251 **lwarp-ltcaption.sty**

## § 358 Package ltcaption

(*Emulates or patches code by* Axel Sommerfeldt.)

Pkg ltcaption ltcaption is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{ltcaption}[2018/08/26]
```

\LTcaptype is already defined by lwarp.

longtable* is already defined by lwarp-longtable.

```
\newlength{\LTcapskip}
\newlength{\LTcapleft}
\newlength{\LTcapright}
\newcommand*{\LTcapmarginsfalse}{}
```

---

File 252 **lwarp-ltxgrid.sty**

## § 359 Package ltxgrid

Pkg ltxgrid ltxgrid is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{ltxgrid}[2010/07/25]

\newcommand*{\onecolumngrid}{}
\newcommand*{\twocolumngrid}{}
\newcommand*{\removestuff}{}
\newcommand*{\addstuff}[2]{}
\newcommand*{\replacestuff}[2]{}
```

File 253 **lwarp-ltxtable.sty**

§ 360 Package

# ltxtable

Pkg ltxtable ltxtable is emulated.

⚠ table numbering The print version does not seem to honor longtable* from the caption package, while lwarp does.

**for HTML output:**

```
\RequirePackage{tabularx,longtable}
\LWR@ProvidesPackageDrop{ltxtable}[1995/12/11]
```

\LTXtable {⟨*width*⟩} {⟨*file*⟩}

```
\newcommand*{\LTXtable}[2]{%
    \input{#2}%
}
```

File 254 **lwarp-lua-check-hyphen.sty**

§ 361 Package

# lua-check-hyphen

Pkg lua-check-hyphen lua-check-hyphen is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{lua-check-hyphen}[2018/04/19]
```

```
\newcommand*{\LuaCheckHyphen}[1]{}
```

File 255 **lwarp-lua-visual-debug.sty**

§ 362 Package

# lua-visual-debug

Pkg lua-visual-debug lua-visual-debug is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{lua-visual-debug}[2016/05/30]
```

File 256 **lwarp-luacolor.sty**

§ 363 Package

# luacolor

Pkg luacolor luacolor is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{luacolor}[2016/05/16]
```

```
\newcommand{\luacolorProcessBox}[1]{}
```

File 257 **lwarp-luamplib.sty**

## § 364 Package luamplib

(*Emulates or patches code by* Hans Hagen, Taco Hoekwater, Elie Roux, Philipp Gesang, Kim Dohyun.)

Pkg luamplib luamplib is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{luamplib}[2020/02/24]

\BeforeBeginEnvironment{mplibcode}{%
    \begin{lateximage}[-mplibcode-~\PackageDiagramAltText]%
}
\AfterEndEnvironment{mplibcode}{\end{lateximage}}
```

File 258 **lwarp-luatexko.sty**

## § 365 Package luatexko

(*Emulates or patches code by* Dohyun Kim, Soojin Nam.)

Pkg luatexko luatexko is patched for use by lwarp.

Modern HTML is used for \dotemph, \ruby, and offset and thickness control for \uline, etc.

**for HTML output:**

```
\LWR@ProvidesPackagePass{luatexko}[2020/03/20]

\newcommand{\LWR@HTML@dotemph}[1]{%
%     \uline{#1}%
    \InlineClass[text-emphasis-style: dot]{dotemph}{#1}%
}
\LWR@formatted{dotemph}

\newcommand{\LWR@HTML@ruby}[2]{%
    \LWR@htmltagc{ruby}%
    \LWR@htmltagc{rb}#1\LWR@htmltagc{/rb}%
    \LWR@htmltagc{rp}(\LWR@htmltagc{/rp}%
    \LWR@htmltagc{rt}#2\LWR@htmltagc{/rt}%
    \LWR@htmltagc{rp})\LWR@htmltagc{/rp}%
    \LWR@htmltagc{/ruby}%
}
\LWR@formatted{ruby}
```

The following is modified from lwarp-ulem:

```
\NewDocumentCommand{\LWR@HTML@uline}{+m}{%
    \InlineClass%
```

```
        (text-decoration:underline; text-decoration-skip: auto)%
        [%
            text-underline-offset: \ulinedown ;
            text-decoration-thickness: \ulinewidth%
        ]%
        {uline}{\LWR@isolate{#1}}%
}
\LWR@formatted{uline}

\NewDocumentCommand{\LWR@HTML@uuline}{+m}{%
    \InlineClass%
        (%
            text-decoration:underline; text-decoration-skip: auto;%
            text-decoration-style:double%
        )%
        [%
            text-underline-offset: \ulinedown ;
            text-decoration-thickness: \ulinewidth%
        ]%
        {uuline}{\LWR@isolate{#1}}%
}
\LWR@formatted{uuline}

\NewDocumentCommand{\LWR@HTML@uwave}{+m}{%
    \InlineClass%
        (%
            text-decoration:underline; text-decoration-skip: auto;%
            text-decoration-style:wavy%
        )%
        [%
            text-underline-offset: \ulinedown ;
            text-decoration-thickness: \ulinewidth%
        ]%
        {uwave}{\LWR@isolate{#1}}%
}
\LWR@formatted{uwave}

\NewDocumentCommand{\LWR@HTML@sout}{+m}{%
    \InlineClass%
        (text-decoration:line-through)%
        [text-decoration-thickness: \ulinewidth]%
        {sout}{\LWR@isolate{#1}}%
}
\LWR@formatted{sout}

\NewDocumentCommand{\LWR@HTML@xout}{+m}{%
    \InlineClass%
        (text-decoration:line-through)%
        [text-decoration-thickness: \ulinewidth]%
        {xout}{\LWR@isolate{#1}}%
}
\LWR@formatted{xout}

\NewDocumentCommand{\LWR@HTML@dashuline}{+m}{%
    \InlineClass%
```

```
\let\LWRTODONOTES@orig@todototoc\todototoc

\renewcommand*{\todototoc}{%
\LWR@phantomsection%
\LWRTODONOTES@orig@todototoc%
}


\renewcommand{\@todonotes@drawMarginNoteWithLine}{%
\fcolorbox
    {\@todonotes@currentbordercolor}
    {\@todonotes@currentbackgroundcolor}
    {\arabic{@todonotes@numberoftodonotes}}
\marginpar{\@todonotes@drawMarginNote}
}

\renewcommand{\@todonotes@drawInlineNote}{%
\fcolorboxBlock%
    {\@todonotes@currentbordercolor}%
    {\@todonotes@currentbackgroundcolor}%
    {%
        \if@todonotes@authorgiven%
        {\@todonotes@author:\,}%
        \fi%
        \@todonotes@text%
    }%
}

\newcommand{\@todonotes@drawMarginNote}{%
    \if@todonotes@authorgiven%
        \@todonotes@author\par%
    \fi%
    \arabic{@todonotes@numberoftodonotes}: %
    \fcolorbox%
    {\@todonotes@currentbordercolor}%
    {\@todonotes@currentbackgroundcolor}%
    {%
        \@todonotes@sizecommand%
        \@todonotes@text %
    }%
}%

\renewcommand{\missingfigure}[2][]{%
\setkeys{todonotes}{#1}%
\addcontentsline{tdo}{todo}{\@todonotes@MissingFigureText: #2}%
\fcolorboxBlock%
    {\@todonotes@currentbordercolor}%
    {\@todonotes@currentfigcolor}%
    {%
        \setlength{\fboxrule}{4pt}%
        \fcolorbox{red}{white}{Missing figure} \quad #2%
    }
}

\LetLtxMacro\LWRTODONOTES@orig@todocommon\@todocommon
```

```
64
65 \RenewDocumentCommand{\@todocommon}{m m}{%
66 \begingroup%
67 \renewcommand*{\phantomsection}{}%
68 \LWRTODONOTES@orig@todocommon{#1}{#2}%
69 \endgroup%
70 }
71
72 \renewcommand{\@todoarea}[3][]{%
73     \@todonotes@areaselectedtrue%
74     \@todocommon{#1}{#2}%
75     \todonotes@textmark@highlight{#3}%
76     \zref@label{@todonotes@\arabic{@todonotes@numberoftodonotes}@end}%
77 }%
78
79
80 \DeclareDocumentCommand{\todonotes@textmark@highlight}{m}{%
81 \InlineClass[background:\LWR@origpound{}B3FFB3]{highlight}{#1}%
82 }
83
84 \fi% \if@todonotes@disabled
```

---

File 260 **lwarp-luavlna.sty**

## § 367 Package luavlna

(*Emulates or patches code by* Michal Hoftich, Miro Hrončok.)

Pkg luavlna luavlna is patched for use by lwarp.

The package is disabled for HTML output, due to incompatibilities with lwarp's handling of math SVG images.

**for HTML output:**

```
1 \LWR@ProvidesPackagePass{luavlna}[2019/10/30]

2 \preventsingleoff
3 \LetLtxMacro\preventsingleon\preventsingleoff
```

---

File 261 **lwarp-lyluatex.sty**

## § 368 Package lyluatex

(*Emulates or patches code by* Fr. Jacques Peron, Urs Liska, Br. Samuel Springuel.)

Pkg lyluatex lyluatex is patched for use by lwarp.

For the first compile, to set *lwarpmk*'s configuration, use:

```
lualatex --shell-escape <filename>
```

⚠ images After compiling the document with **lwarpmk html**, use **lwarpmk limages** to convert the Lilypond images for HTML.

The option insert=systems results in an image per system. Each music image "system" css is placed inside a  of class lyluatex, which defaults to display: inline-block.

⚠ insert=fullpage The option insert=fullpage results in a single image per page of printed output. Each css music "fullpage" image is placed inside a  of class lyluatex. To match the number of measures per line with the printed version, use the geometry package to select the page geometry, or use the lyluatex options for page and staff sizes.

⚠ options To use \linewidth or \textwidth inside the package options for lyluatex, use the kvoptions-patch package first:

```
\usepackage{kvoptions-patch}
\usepackage[...,line-width-0.8\linewidth,...]{lyluatex}
```

⚠ raw-pdf If using raw-pdf, the resulting PDF images must be converted to SVG:

Enter ⇒ **lwarpmk pdftosvg tmp-ly/*.pdf**

**for HTML output:**

```
\LWR@origRequirePackage{luacode}

\LWR@ProvidesPackagePass{lyluatex}[2019/05/27]
```

User-redefinable ALT tag:

```
\newcommand*{\LyluatexImageAltText}{-lilypond-~\PackageDiagramAltText}
```

\ly@compilescore {⟨*Lilypond object*⟩}

```
\LetLtxMacro\LWR@orig@ly@compilescore\ly@compilescore

\renewcommand*{\ly@compilescore}[1]{%
```

A local group holds a number of changes:

```
    \begingroup%
```

The user's original geometry and font size are restored to match the print version. This allows for correct spacing in the musical score.

```
    \LWR@maybe@orignewpage%
    \LWR@origloadgeometry{LWR@usergeometry}%
    \LWR@print@normalsize%
```

A local group holds a redefined \includegraphics which is used by *lyluatex.lua* to insert the *Lilypond* score if insert=systems is used. This is now placed inside a lateximage, which itself is placed inside a  of class lyluatex.

\LWR@addbaselinemarker preserves the left margins.

```
    \renewcommand{\includegraphics}[2][]{%
        \InlineClass{lyluatex}{%
            \begin{lateximage}[\LyluatexImageAltText]%
            \LWR@addbaselinemarker%
            \LWR@origincludegraphics{##2}%
```

**for HTML output:**

```
\LWR@ProvidesPackageDrop{magaz}[2011/11/24]

\newcommand\FirstLine[1]{%
    \begingroup%
    \FirstLineFont{%
        \LWR@textcurrentcolor{%
            \LWR@textcurrentfont{%
                #1%
            }%
        }%
    }%
    \endgroup%
}

\providecommand\FirstLineFont{\scshape}
```

File 263 **lwarp-makeidx.sty**

## § 370 Package makeidx

(*Emulates or patches code by* LaTeX Project Team.)

Pkg makeidx makeidx is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{makeidx}[2014/09/29]
```

`\@wrindex` is redefined `\AtBeginDocument` by the lwarp core.

`\printindex`

```
\preto\printindex{%
    \LWR@maybe@orignewpage%
    \LWR@startpars%
}
```

File 264 **lwarp-manyfoot.sty**

## § 371 Package manyfoot

Pkg manyfoot manyfoot is emulated.

bigfoot, manyfoot

⚠ verbatim

Verbatim footnotes are not yet supported.

If using the bigfoot package, and possibly also manyfoot, problems may occur with counter allocation because lwarp uses many counters, and there is a difference in how counters numbered 256 and up are handled in pdfLaTeX. With bigfoot this has been known to show up as an error related to one footnote insert being forbidden inside another. Another problem showed up as a input stack error, and which of these problems occurred depended on how many counters were allocated.

As a possible solution, try creating several new counters before defining bigfoot or manyfoot footnotes, hoping to shift the problematic counter above the 256 threshold. It may instead be necessary to use XeLaTeX or LuaLaTeX instead of pdfLaTeX.

lwarp's emulation of bigfoot uses manyfoot, so some of the bigfoot enhancements are included here.

The bigfoot "default" footnote is ignored, using the lwarp version instead.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{manyfoot}[2005/09/11]

\RequirePackage{nccfoots}

\newcommand{\extrafootnoterule}{}

\let\defaultfootnoterule\footnoterule

\newcommand*{\SelectFootnoteRule}[2][0]{}

\newcommand{\footnoterulepriority}{1}

\newcommand{\SetFootnoteHook}[1]{}
\@onlypreamble\SetFootnoteHook

\newcommand{\SplitNote}{}

\newcommand*\ExtraParaSkip[1]{}

\newcommand*{\newfootnote}[2][plain]{%
    \ifstrequal{#2}{default}{}{% not "default"
        \expandafter\newbox\csname LWR@footnote#2box\endcsname%
        \appto{\LWR@printpendingfootnotes}{%
            \LWR@@printpendingfootnotes{footnote#2}%
        }
        \long\csdef{Footnotetext#2}##1##2{%
            \NCC@makefnmark{##1}%
            \LWR@@footnotetext{##2}{LWR@footnote#2box}%
        }%
        \long\csdef{Footnotetext#2+}##1##2{%
            \NCC@makefnmark{##1}%
            \LWR@@footnotetext{##2}{LWR@footnote#2box}%
        }%
    }% not "default"
}
\@onlypreamble\newfootnote

\newcommand*{\DeclareNewFootnote}[2][plain]{%
  \@ifnextchar[%
        {\LWR@manyfoot@declare{#1}{#2}}%
        {\LWR@manyfoot@declare{#1}{#2}[arabic]}%
}

\def\LWR@manyfoot@declare#1#2[#3]{%
\ifstrequal{#2}{default}{}{% not "default"
  \newfootnote[#1]{#2}%
```

```
\newcounter{footnote#2}%
  \newcounter{footnote#2Reset}%
  \setcounter{footnote#2Reset}{0}%
  \csdef{thefootnote#2}{%
    \expandafter\noexpand\csname @#3\endcsname%
    \expandafter\noexpand\csname c@footnote#2\endcsname%
  }%
```

For bigfoot, the footnote commands may be appended with one or two plusses or one or two minuses, which are ignored in HTML.

```
 \expandafter\NewDocumentCommand\csname footnote#2\endcsname{t{+}t{+}t{-}t{-}}{%
      \stepcounter{footnote#2}%
      \protected@xdef\@thefnmark{\csname thefootnote#2\endcsname}%
      \@footnotemark%
      \csuse{Footnotetext#2}{\@thefnmark}% absorbs the footnote contents
  }%
  \csdef{footnotemark#2}{%
      \stepcounter{footnote#2}%
      \protected@xdef\@thefnmark{\csname thefootnote#2\endcsname}%
      \@footnotemark%
  }%
 \expandafter\NewDocumentCommand\csname footnotetext#2\endcsname{t{+}t{+}t{-}t{-}}{%
      \protected@xdef\@thefnmark{\csname thefootnote#2\endcsname}%
      \csuse{Footnotetext#2}{\@thefnmark}% absorbs the footnote contents
  }%
  \csdef{Footnotemark#2}{%
    \Footnotemark%
  }%
  \csdef{Footnote#2}##1{%
    \Footnotemark{##1}%
    \csuse{Footnotetext#2}{##1}%
  }%
}% not "default"
}
\@onlypreamble\DeclareNewFootnote
```

---

File 265 **lwarp-marginal.sty**

## § 372 Package marginal

Pkg marginal

marginal is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{marginal}

\newcommand*{\showlostmarginals}{}
\newcommand*{\enlargefreelist}{}
\newcommand*{\onesidemarginals}{}
```

---

File 266 **lwarp-marginfit.sty**

## § 373 Package marginfit

Pkg marginfit marginfit is ignored.

**for HTML output:** Discard all options for lwarp-marginfit:

```
\LWR@ProvidesPackageDrop{marginfit}[2018/06/08]
```

---

File 267 **lwarp-marginfix.sty**

## § 374 Package marginfix

(*Emulates or patches code by* Stephen Hicks.)

Pkg marginfix marginfix is ignored.

**for HTML output:** Discard all options for lwarp-marginfix:

```
\LWR@ProvidesPackageDrop{marginfix}[2013/09/08]

\newcommand*{\marginskip}[1]{}
\newcommand*{\clearmargin}{}
\newcommand*{\softclearmargin}{}
\newcommand*{\extendmargin}[1]{}
\newcommand*{\mparshift}[1]{}
\newdimen\marginheightadjustment
\newdimen\marginposadjustment
\newcommand*{\blockmargin}[1][]{}
\newcommand*{\unblockmargin}[1][]{}
\newcommand*{\marginphantom}[2][]{}
```

---

File 268 **lwarp-marginnote.sty**

## § 375 Package marginnote

(*Emulates or patches code by* Markus Kohm.)

Pkg marginnote marginnote is emulated.

**for HTML output:** Discard all options for lwarp-marginnote:

```
\LWR@ProvidesPackageDrop{marginnote}[2018/08/09]

\NewDocumentCommand{\marginnote}{+o +m o}{\marginpar{#2}}

\newcommand*{\marginnoteleftadjust}{}
\newcommand*{\marginnoterightadjust}{}
\newcommand*{\marginnotetextwidth}{}
\let\marginnotetextwidth\textwidth
\newcommand*{\marginnotevadjust}{}
```

```
\LWR@ProvidesPackagePass{mathalpha}[2019/10/05]

\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\mathbbb}[1]{\boldsymbol{\mathbb{#1}}}}% not bold
\CustomizeMathJax{\newcommand{\mathbcal}[1]{\boldsymbol{\mathcal{#1}}}}
\CustomizeMathJax{\newcommand{\mathbfrak}[1]{\boldsymbol{\mathfrak{#1}}}}
\CustomizeMathJax{\newcommand{\mathbscr}[1]{\boldsymbol{\mathscr{#1}}}}% not bold
\end{warpMathJax}
```

File 271 **lwarp-mathastext.sty**

# § 378 Package mathastext

(*Emulates or patches code by* Jean-François Burnol.)

Pkg mathastext mathastext is used as-is for SVG math, and emulated for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{mathastext}[2019/11/16]

\LWR@origRequirePackage{lwarp-common-mathjax-letters}

\begin{warpMathJax}
\ifmst@itgreek
%     \LWR@mathjax@addgreek@l@it{}{}
\else
    \ifmst@upgreek
        \LWR@mathjax@addgreek@l@up{}{}
    \else
        \ifmst@frenchmath
            \LWR@mathjax@addgreek@l@up{}{}
        \else
            \ifmst@italic
%               \LWR@mathjax@addgreek@l@it{}{}
            \else
                \LWR@mathjax@addgreek@l@up{}{}
            \fi
        \fi
    \fi
\fi

\ifcase\mst@greek@select
    \or{\LWR@mathjax@addgreek@u@it*{}{}}
%     \or{\LWR@mathjax@addgreek@u@up*{}{}}
\fi

\CustomizeMathJax{\newcommand{\mathnormalbold}[1]{\boldsymbol{#1}}}
\CustomizeMathJax{\newcommand{\MathEulerBold}[1]{\boldsymbol{#1}}}
\CustomizeMathJax{\newcommand{\MathEuler}[1]{{#1}}}
\CustomizeMathJax{\newcommand{\MathPSymbol}[1]{{#1}}}
\CustomizeMathJax{\let\fouriervec\vec}
\CustomizeMathJax{\let\pmvec\vec}
\CustomizeMathJax{\let\inodot\imath}
\CustomizeMathJax{\let\jnodot\jmath}
```

```
\LWR@origRequirePackage{lwarp-common-mathjax-overlaysymbols}

\begin{warpMathJax}
\LWR@infoprocessingmathjax{mathdesign}
```

Default greek upright or italicized:

```
\if@MD@grupright
\LWR@mathjax@addgreek@l@up{}{}
\fi

\if@MD@GRupright
\else
\LWR@mathjax@addgreek@u@it*{}{}
\fi
```

Upright:

```
\LWR@mathjax@addgreek@l@up{}{up}
\LWR@mathjax@addgreek@u@up*{}{up}
```

Italicized:

```
\LWR@mathjax@addgreek@l@it{}{it}
\LWR@mathjax@addgreek@u@it*{}{it}
```

Adapt to mathdesign inconsistency:

```
\CustomizeMathJax{\let\digammaup\Digammaup}
\CustomizeMathJax{\renewcommand{\digammait}{\mathit{\digammaup}}}
```

Extra symbols:

```
\CustomizeMathJax{\newcommand{\smallin}{\mathrel{\unicode{x220A}}}}
\CustomizeMathJax{\newcommand{\smallowns}{\mathrel{\unicode{x220D}}}}
\CustomizeMathJax{\newcommand{\notsmallin}{\mathrel{\LWRoverlaysymbols{/}{\unicode{x220A}}}}}
\CustomizeMathJax{\newcommand{\notsmallowns}{\mathrel{\LWRoverlaysymbols{/}{\unicode{x220D}}}}}
\CustomizeMathJax{\newcommand{\rightangle}{\mathord{\unicode{x221F}}}}
```

Integrals:

```
\CustomizeMathJax{\newcommand{\intclockwise}{\mathop{\unicode{x2231}}\limits}}
\CustomizeMathJax{\newcommand{\ointclockwise}{\mathop{\unicode{x2232}}\limits}}
\CustomizeMathJax{\newcommand{\ointctrclockwise}{\mathop{\unicode{x2233}}\limits}}
\CustomizeMathJax{\newcommand{\oiint}{\mathop{\unicode{x222F}}\limits}}
\CustomizeMathJax{\newcommand{\oiiint}{\mathop{\unicode{x2230}}\limits}}
```

Math and text mode:

```
\CustomizeMathJax{\newcommand{\ddag}{\unicode{x2021}}}
\CustomizeMathJax{\newcommand{\P}{\unicode{x00B6}}}
\CustomizeMathJax{\newcommand{\copyright}{\unicode{x00A9}}}
\CustomizeMathJax{\newcommand{\dag}{\unicode{x2020}}}
\CustomizeMathJax{\newcommand{\pounds}{\unicode{x00A3}}}
```

Extra symbols:

```
\CustomizeMathJax{\newcommand{\iddots}{\mathinner{\unicode{x22F0}}}}
\CustomizeMathJax{\newcommand{\utimes}{\mathbin{\overline{\times}}}}
\CustomizeMathJax{\newcommand{\dtimes}{\mathbin{\underline{\times}}}}
\CustomizeMathJax{\newcommand{\udtimes}{\mathbin{\overline{\underline{\times}}}}}
\CustomizeMathJax{\newcommand{\leftwave}{\left\{}}
\CustomizeMathJax{\newcommand{\rightwave}{\right\}}}

\end{warpMathJax}
```

---

File 274 **lwarp-mathdots.sty**

## § 381 Package mathdots

(*Emulates or patches code by* Dan Luecking.)

Pkg mathdots mathdots is used as-is for SVG math, and emulated for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{mathdots}[2014/06/11]

\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\iddots}{\mathinner{\unicode{x22F0}}}}
\CustomizeMathJax{\let\fixedddots\ddots}
\CustomizeMathJax{\let\fixedvdots\vdots}
\CustomizeMathJax{\let\fixediddots\iddots}
\CustomizeMathJax{\let\originalddots\ddots}
\CustomizeMathJax{\let\originalvdots\vdots}
\CustomizeMathJax{\let\originaliddots\iddots}
\CustomizeMathJax{\let\originaldddot\dddot}
\CustomizeMathJax{\let\originalddddot\ddddot}
\end{warpMathJax}
```

---

File 275 **lwarp-mathfixs.sty**

## § 382 Package mathfixs

(*Emulates or patches code by* Niklas Beisert.)

Pkg mathfixs mathfixs is used as-is for SVG math, and is emulated for MathJax.

⚠ Greek letters are unchanged.

**for HTML output:**

```
\LWR@ProvidesPackagePass{mathfixs}[2018/12/30]

\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\rfrac}[2]{\tfrac{#1}{#2}}}
\CustomizeMathJax{\newcommand{\vfrac}[2]{\mathinner{{}^{#1}\!/{}_{#2}}}}
\CustomizeMathJax{\newcommand{\ProvideMathFix}[1]{}}
\CustomizeMathJax{\newcommand{\mathbold}[1]{\boldsymbol{#1}}}
\CustomizeMathJax{\newcommand{\.}{\,}}
\end{warpMathJax}
```

File 276 **lwarp-mathpazo.sty**

## § 383 Package mathpazo

(*Emulates or patches code by* Walter Schmidt.)

Pkg mathpazo mathpazo is used as-is for SVG math, and is emulated for MathJax.

⚠ limitations The MathJax emulation ignores all package options. The dedicated macros for upright greek letters do work correctly.

SVG math should appear the same as the printed output.

**for HTML output:**

```
\LWR@ProvidesPackagePass{mathpazo}[2020/03/25]
```

For MathJax:

```
\LWR@origRequirePackage{lwarp-common-mathjax-letters}

\begin{warpMathJax}
\LWR@infoprocessingmathjax{mathpazo}

\ifpazo@slGreek
\LWR@mathjax@addgreek@u@it*{}{}
\fi

\LWR@mathjax@addgreek@u@up*{up}{}

\CustomizeMathJax{\newcommand{\mathbold}[1]{\boldsymbol{#1}}}
\end{warpMathJax}
```

File 277 **lwarp-mathptmx.sty**

## § 384 Package mathptmx

(*Emulates or patches code by* Walter Schmidt.)

Pkg mathptmx mathptmx is used as-is for SVG math, and is emulated for MathJax.

⚠ limitations The MathJax emulation ignores all package options. The dedicated macros for upright greek letters do work correctly.

SVG math should appear the same as the printed output.

**for HTML output:**

```
\LWR@ProvidesPackagePass{mathptmx}[2020/03/25]
```

For MathJax:

```
\LWR@origRequirePackage{lwarp-common-mathjax-letters}
```

```
3
4 \begin{warpMathJax}
5 \LWR@infoprocessingmathjax{mathptmx}
6
7 \@ifpackagewith{mathptmx}{slantedGreek}
8     {\LWR@mathjax@addgreek@u@it*{}{}}
9     {}
10
11 \LWR@mathjax@addgreek@u@up*{up}{}
12 \end{warpMathJax}
```

---

File 278 **lwarp-mathspec.sty**

# § 385 Package mathspec

(*Emulates or patches code by* Andrew Gilbert Moschou.)

Pkg mathspec mathspec is used as-is with SVG math, and is emulated for MathJax.

⚠ quotes Double quotes (\" and the " character) are removed during MathJax emulation, but this also includes inside \text.

**for HTML output:**

```
1 \LWR@ProvidesPackagePass{mathspec}[2016/12/22]

2 \LWR@origRequirePackage{lwarp-common-mathjax-letters}
3
4 \begin{warpMathJax}
```

Neutralize double quotes (" and \"):

```
5 \booltrue{LWR@MathJax@silentquotes}
```

Sort options for out Greek emulation:

```
6 \AtBeginDocument{
7 \ifcase\eu@GreekUppercase@@value %% If Greek Uppercase Regular
8     \LWR@mathjax@addgreek@u@up*{}{}
9 \or %% If Greek Uppercase Italic
10    \LWR@mathjax@addgreek@u@it*{}{}
11 \or %% If Greek Uppercase Plain
12    \LWR@mathjax@addgreek@u@up*{}{}
13 \fi
14 \ifcase\eu@GreekLowercase@@value %% If Greek Lowercase Regular
15    \LWR@mathjax@addgreek@l@up{}{}
16 \or %% If Greek Lowercase Italic
17    \LWR@mathjax@addgreek@l@it{}{}
18 \or %% If Greek Lowercase Plain
19    \LWR@mathjax@addgreek@l@it{}{}
20 \fi
21 }
```

Swap definitions according the mathspec conditionals:

```
\newcommand*{\LWR@mathspec@varforms}{%
\eu@ifbooltrue{GreekLowercase}{
    \eu@ifbooltrue{exchangebetaforms}{
        \CustomizeMathJax{\let\LWRorigbeta\beta}
        \CustomizeMathJax{\let\beta\varbeta}
        \CustomizeMathJax{\let\varbeta\LWRorigbeta}
    }
    \eu@ifbooltrue{exchangeepsilonforms}{
        \CustomizeMathJax{\let\LWRorigepsilon\epsilon}
        \CustomizeMathJax{\let\epsilon\varepsilon}
        \CustomizeMathJax{\let\varepsilon\LWRorigepsilon}
    }
    \eu@ifbooltrue{exchangethetaforms}{
        \CustomizeMathJax{\let\LWRorigtheta\theta}
        \CustomizeMathJax{\let\theta\vartheta}
        \CustomizeMathJax{\let\vartheta\LWRorigtheta}
    }
    \eu@ifbooltrue{exchangekappaforms}{
        \CustomizeMathJax{\let\LWRorigkappa\kappa}
        \CustomizeMathJax{\let\kappa\varkappa}
        \CustomizeMathJax{\let\varkappa\LWRorigkappa}
    }
    \eu@ifbooltrue{exchangepiforms}{
        \CustomizeMathJax{\let\LWRorigpi\pi}
        \CustomizeMathJax{\let\pi\varpi}
        \CustomizeMathJax{\let\varpi\LWRorigpi}
    }
    \eu@ifbooltrue{exchangerhoforms}{
        \CustomizeMathJax{\let\LWRorigrho\rho}
        \CustomizeMathJax{\let\rho\varrho}
        \CustomizeMathJax{\let\varrho\LWRorigrho}
    }
    \eu@ifbooltrue{exchangephiforms}{
        \CustomizeMathJax{\let\LWRorigphi\phi}
        \CustomizeMathJax{\let\phi\varphi}
        \CustomizeMathJax{\let\varphi\LWRorigphi}
    }
}
\eu@ifbooltrue{GreekUppercase}{
    \eu@ifbooltrue{exhangeThetaforms}{
        \CustomizeMathJax{\let\LWRorigTheta\Theta}
        \CustomizeMathJax{\let\Theta\varTheta}
        \CustomizeMathJax{\let\varTheta\LWRorigTheta}
    }
}
}
```

Append new action to mathspec's `\AtBeginDocument` code:

```
\xapptocmd{\exchangeforms}
    {\AtBeginDocument{\LWR@mathspec@varforms}}
    {}
    {\LWR@patcherror{mathspec}{exchangeforms}}

\end{warpMathJax}
```

```
\CustomizeMathJax{\Newextarrow\xrightharpoonup{10,10}{0x21c0}}
\CustomizeMathJax{\Newextarrow\xleftharpoonup{10,10}{0x21bc}}
\CustomizeMathJax{\Newextarrow\xleftrightharpoons{10,10}{0x21cb}}

\CustomizeMathJax{\newcommand{\LWRdounderbracket}[3]{%
    \mathinner{\underset{#3}{\underline{\llcorner{#1}\lrcorner}}}%
}}
\CustomizeMathJax{\newcommand{\LWRunderbracket}[2][]{\LWRdounderbracket{#2}}}
\CustomizeMathJax{\newcommand{\underbracket}[1][]{\LWRunderbracket}}
\CustomizeMathJax{\newcommand{\LWRdooverbracket}[3]{%
    \mathinner{\overset{#3}{\overline{\ulcorner{#1}\urcorner}}}%
}}
\CustomizeMathJax{\newcommand{\LWRoverbracket}[2][]{\LWRdooverbracket{#2}}}
\CustomizeMathJax{\newcommand{\overbracket}[1][]{\LWRoverbracket}}

\CustomizeMathJax{\newcommand{\LaTeXunderbrace}[1]{\underbrace{#1}}}
\CustomizeMathJax{\newcommand{\LaTeXoverbrace}[1]{\overbrace{#1}}}

\CustomizeMathJax{\newenvironment{matrix*}[1][]{\begin{matrix}}{\end{matrix}}}
\CustomizeMathJax{\newenvironment{pmatrix*}[1][]{\begin{pmatrix}}{\end{pmatrix}}}
\CustomizeMathJax{\newenvironment{bmatrix*}[1][]{\begin{bmatrix}}{\end{bmatrix}}}
\CustomizeMathJax{\newenvironment{Bmatrix*}[1][]{\begin{Bmatrix}}{\end{Bmatrix}}}
\CustomizeMathJax{\newenvironment{vmatrix*}[1][]{\begin{vmatrix}}{\end{vmatrix}}}
\CustomizeMathJax{\newenvironment{Vmatrix*}[1][]{\begin{Vmatrix}}{\end{Vmatrix}}}
\CustomizeMathJax{\newenvironment{smallmatrix*}[1][]{\begin{matrix}}{\end{matrix}}}
\CustomizeMathJax{\newenvironment{psmallmatrix*}[1][]{\begin{pmatrix}}{\end{pmatrix}}}
\CustomizeMathJax{\newenvironment{bsmallmatrix*}[1][]{\begin{bmatrix}}{\end{bmatrix}}}
\CustomizeMathJax{\newenvironment{Bsmallmatrix*}[1][]{\begin{Bmatrix}}{\end{Bmatrix}}}
\CustomizeMathJax{\newenvironment{vsmallmatrix*}[1][]{\begin{vmatrix}}{\end{vmatrix}}}
\CustomizeMathJax{\newenvironment{Vsmallmatrix*}[1][]{\begin{Vmatrix}}{\end{Vmatrix}}}
\CustomizeMathJax{\newenvironment{psmallmatrix}[1][]{\begin{pmatrix}}{\end{pmatrix}}}
\CustomizeMathJax{\newenvironment{bsmallmatrix}[1][]{\begin{bmatrix}}{\end{bmatrix}}}
\CustomizeMathJax{\newenvironment{Bsmallmatrix}[1][]{\begin{Bmatrix}}{\end{Bmatrix}}}
\CustomizeMathJax{\newenvironment{vsmallmatrix}[1][]{\begin{vmatrix}}{\end{vmatrix}}}
\CustomizeMathJax{\newenvironment{Vsmallmatrix}[1][]{\begin{Vmatrix}}{\end{Vmatrix}}}


\CustomizeMathJax{\newcommand{\LWRmultlined}[1][]{\begin{multline*}}}
\CustomizeMathJax{\newenvironment{multlined}[1][]{\LWRmultlined}{\end{multline*}}}

\CustomizeMathJax{\let\LWRorigshoveleft\shoveleft}
\CustomizeMathJax{\renewcommand{\shoveleft}[1][]{\LWRorigshoveleft}}
\CustomizeMathJax{\let\LWRorigshoveright\shoveright}
\CustomizeMathJax{\renewcommand{\shoveright}[1][]{\LWRorigshoveright}}

\CustomizeMathJax{\newenvironment{dcases}{\begin{cases}}{\end{cases}}}
\CustomizeMathJax{\newenvironment{dcases*}{\begin{cases}}{\end{cases}}}
\CustomizeMathJax{\newenvironment{rcases}{\begin{cases}}{\end{cases}}}
\CustomizeMathJax{\newenvironment{rcases*}{\begin{cases}}{\end{cases}}}
\CustomizeMathJax{\newenvironment{drcases}{\begin{cases}}{\end{cases}}}
\CustomizeMathJax{\newenvironment{drcases*}{\begin{cases}}{\end{cases}}}
\CustomizeMathJax{\newenvironment{cases*}{\begin{cases}}{\end{cases}}}

\CustomizeMathJax{\newcommand{\MoveEqLeft}[1][]{}}

```

```
\CustomizeMathJax{% special parsing to handle '&' in argument
    \def\LWRAboxed#1&#2&#3!|!{\fbox{\(#1\)}&\fbox{\(#2\)}}
    \newcommand{\Aboxed}[1]{\LWRAboxed#1&&!|!}
}


\CustomizeMathJax{
   \newcommand{\LWRABLines}[1][\Updownarrow]{#1 \notag \\}% star/nostar the same
    \newcommand{\ArrowBetweenLines}{\ifstar\LWRABLines\LWRABLines}
}


\CustomizeMathJax{\newcommand{\shortintertext}[1]{\text{#1}\notag \\}}

\CustomizeMathJax{\newcommand{\vdotswithin}[1]{\hspace{.5em}\vdots}}


\CustomizeMathJax{\newcommand{\LWRshortvdotswithinstar}[1]{\vdots \hspace{.5em} & \\}}
\CustomizeMathJax{\newcommand{\LWRshortvdotswithinnostar}[1]{& \hspace{.5em}\vdots \\}}
\CustomizeMathJax{%
    \newcommand{\shortvdotswithin}%
        {\ifstar\LWRshortvdotswithinstar\LWRshortvdotswithinnostar}%
}

\CustomizeMathJax{\newcommand{\MTFlushSpaceAbove}{}}
\CustomizeMathJax{\newcommand{\MTFlushSpaceBelow}{\\}}

\LetLtxMacro\LWR@mathtools@orig@DeclarePairedDelimiter\DeclarePairedDelimiter
\renewcommand{\DeclarePairedDelimiter}[3]{
    \LWR@mathtools@orig@DeclarePairedDelimiter{#1}{#2}{#3}
% starred:
    \appto\LWR@customizedMathJax{\LWRbackslash(}
    \appto\LWR@customizedMathJax{%
       \LWRbackslash{}newcommand\{\LWRbackslash\macrotocsname{#1}LWRsubstar\}%
    }%
    \appto\LWR@customizedMathJax{[2][]}%
    \appto\LWR@customizedMathJax{\{\{}%
    \LWR@subcustomizedmathjax{##1\left#2##2##1\right#3}%
    \appto\LWR@customizedMathJax{\}\}}%
    \appto\LWR@customizedMathJax{\LWRbackslash)\par}%
% not starred:
    \appto\LWR@customizedMathJax{\LWRbackslash(}
    \appto\LWR@customizedMathJax{%
      \LWRbackslash{}newcommand\{\LWRbackslash\macrotocsname{#1}LWRsubnostar\}%
    }%
    \appto\LWR@customizedMathJax{[2][]}%
    \appto\LWR@customizedMathJax{\{\{}%
    \LWR@subcustomizedmathjax{##1#2##2##1#3}%
    \appto\LWR@customizedMathJax{\}\}}%
    \appto\LWR@customizedMathJax{\LWRbackslash)\par}%
% user macro:
    \appto\LWR@customizedMathJax{\LWRbackslash(}
    \appto\LWR@customizedMathJax{%
        \LWRbackslash{}newcommand\{\LWRbackslash{}\macrotocsname{#1}\}%
        \{\LWRbackslash{}ifstar%
            \LWRbackslash{}\macrotocsname{#1}LWRsubstar%
            \LWRbackslash{}\macrotocsname{#1}LWRsubnostar%
```

```
        \}%
    }%
    \appto\LWR@customizedMathJax{\LWRbackslash)\par}%
}
\@onlypreamble\DeclareParedDelimiter

% (DeclarePairedDelimiterX is already defined to use \DeclarePairedDelimiterXPP.)

\LetLtxMacro\LWR@mathtools@orig@DeclarePairedDelimiterXPP\DeclarePairedDelimiterXPP
\DeclareDocumentCommand{\DeclarePairedDelimiterXPP}{m O{1} m m m m m}{
    \LWR@mathtools@orig@DeclarePairedDelimiterXPP{#1}[#2]{#3}{#4}{#5}{#6}{#7}
% subsubstar, second opt arg
    \appto\LWR@customizedMathJax{\LWRbackslash(}%
    \appto\LWR@customizedMathJax{%
      \LWRbackslash{}newcommand\{\LWRbackslash\macrotocsname{#1}LWRsubsubstar\}%
    }%
    \appto\LWR@customizedMathJax{[#2]}%
    \appto\LWR@customizedMathJax{\{\{\LWRbackslash{}left}%
    \LWR@subcustomizedmathjax{#3#4#7}%
    \appto\LWR@customizedMathJax{\LWRbackslash{}right}%
    \LWR@subcustomizedmathjax{#5#6}%
    \appto\LWR@customizedMathJax{\}\}}%
    \appto\LWR@customizedMathJax{\LWRbackslash)\par}%
% substar, first opt arg
    \appto\LWR@customizedMathJax{\LWRbackslash(}%
    \appto\LWR@customizedMathJax{%
      \LWRbackslash{}newcommand\{\LWRbackslash\macrotocsname{#1}LWRsubstar\}[1][]%
    }%
    \appto\LWR@customizedMathJax{%
        \{
        \LWRbackslash{}def\LWRbackslash{}delimsize\{\#1\}
        \LWRbackslash\macrotocsname{#1}LWRsubsubstar
        \}%
    }%
    \appto\LWR@customizedMathJax{\LWRbackslash)\par}%
% subsubnostar, second opt arg
    \appto\LWR@customizedMathJax{\LWRbackslash(}%
    \appto\LWR@customizedMathJax{%
      \LWRbackslash{}newcommand\{\LWRbackslash\macrotocsname{#1}LWRsubsubnostar\}%
    }%
    \appto\LWR@customizedMathJax{[#2]}%
    \appto\LWR@customizedMathJax{\{\{\LWRbackslash{}delimsize}%
    \LWR@subcustomizedmathjax{#3#4#7}%
    \appto\LWR@customizedMathJax{\LWRbackslash{}delimsize}%
    \LWR@subcustomizedmathjax{#5#6}%
    \appto\LWR@customizedMathJax{\}\}}%
    \appto\LWR@customizedMathJax{\LWRbackslash)\par}%
% subnostar, first opt arg
    \appto\LWR@customizedMathJax{\LWRbackslash(}%
    \appto\LWR@customizedMathJax{%
      \LWRbackslash{}newcommand\{\LWRbackslash\macrotocsname{#1}LWRsubnostar\}[1][]%
    }%
    \appto\LWR@customizedMathJax{%
        \{
        \LWRbackslash{}def\LWRbackslash{}delimsize\{\#1\}
```

```
        \LWRbackslash\macrotocsname{#1}LWRsubsubnostar
        \}%
    }%
    \appto\LWR@customizedMathJax{\LWRbackslash)\par}%
% user macro:
    \appto\LWR@customizedMathJax{\LWRbackslash(}
    \appto\LWR@customizedMathJax{%
        \LWRbackslash{}newcommand\{%
            \LWRbackslash{}\macrotocsname{#1}%
        \}%
            \{\LWRbackslash{}ifstar%
                \LWRbackslash{}\macrotocsname{#1}LWRsubstar%
                \LWRbackslash{}\macrotocsname{#1}LWRsubnostar%
            \}%
    }%
    \appto\LWR@customizedMathJax{\LWRbackslash)\par}%
}
\@onlypreamble\DeclareParedDelimiterXPP
\@onlypreamble\DeclareParedDelimiterX

\CustomizeMathJax{\newcommand\lparen{(}}
\CustomizeMathJax{\newcommand\rparen{)}}
\CustomizeMathJax{\newcommand{\ordinarycolon}{:}}


\CustomizeMathJax{\newcommand{\vcentcolon}{\mathrel{\unicode{x2236}}}}

\CustomizeMathJax{\newcommand\dblcolon{\mathrel{\unicode{x2237}}}}
\CustomizeMathJax{\newcommand\coloneqq{\mathrel{\unicode{x2236}\!=}}}
\CustomizeMathJax{\newcommand\Coloneqq{\mathrel{\unicode{x2237}\!=}}}
\CustomizeMathJax{\newcommand\coloneq{\mathrel{\unicode{x2236}-}}}
\CustomizeMathJax{\newcommand\Coloneq{\mathrel{\unicode{x2237}-}}}

\CustomizeMathJax{\newcommand\eqqcolon{\mathrel{=\!\unicode{x2236}}}}
\CustomizeMathJax{\newcommand\Eqqcolon{\mathrel{=\!\unicode{x2237}}}}
\CustomizeMathJax{\newcommand\eqcolon{\mathrel{-\unicode{x2236}}}}
\CustomizeMathJax{\newcommand\Eqcolon{\mathrel{-\unicode{x2237}}}}

\CustomizeMathJax{\newcommand\colonapprox{\mathrel{\unicode{x2236}\!\approx}}}
\CustomizeMathJax{\newcommand\Colonapprox{\mathrel{\unicode{x2237}\!\approx}}}
\CustomizeMathJax{\newcommand\colonsim{\mathrel{\unicode{x2236}\!\sim}}}
\CustomizeMathJax{\newcommand\Colonsim{\mathrel{\unicode{x2237}\!\sim}}}


\CustomizeMathJax{\newcommand{\nuparrow}{\mathrel{\cancel{\uparrow}}}}
\CustomizeMathJax{\newcommand{\ndownarrow}{\mathrel{\cancel{\downarrow}}}}
\CustomizeMathJax{\newcommand{\bigtimes}{\mathop{\Large\times}\limits}}

\CustomizeMathJax{\newcommand{\prescript}[3]{{}^{#1}_{#2}#3}}


\CustomizeMathJax{\newenvironment{lgathered}{\begin{gathered}}{\end{gathered}}}
\CustomizeMathJax{\newenvironment{rgathered}{\begin{gathered}}{\end{gathered}}}

\LetLtxMacro\LWR@mathtools@orig@newgathered\newgathered
\renewcommand{\newgathered}[4]{%
```

```
    \LWR@mathtools@orig@newgathered{#1}{#2}{#3}{#4}%
    \appto\LWR@customizedMathJax{\LWRbackslash(}%
    \LWR@subcustomizedmathjax{%
        \newenvironment{#1}{\begin{gathered}}{\end{gathered}}%
    }%
    \appto\LWR@customizedMathJax{\LWRbackslash)}%
}
\@onlypreamble\newgathered

\CustomizeMathJax{\newcommand{\splitfrac}[2]{{}^{#1}_{#2}}}
\CustomizeMathJax{\let\splitdfrac\splitfrac}
\end{warpMathJax}
```

---

File 280 **lwarp-mattens.sty**

## § 387 Package mattens

(*Emulates or patches code by* Danie Els.)

Pkg mattens mattens is used as-is for SVG math, and is emulated for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{mattens}[2010/03/26]

\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\LWRmattensnull}{}}

\CustomizeMathJax{\newcommand{\LWRmattensnostar}[2][]{%
  {#1{\LWRmattensundercmd{\LWRmattensovercmd{\LWRmattenscross{\boldsymbol{#2}}}}}}%
}}

\CustomizeMathJax{\newcommand{\LWRmattensstar}[2][]{%
    {#1{\LWRmattensundercmd{\LWRmattensovercmd{\LWRmattenscross{#2}}}}}%
}}

\CustomizeMathJax{\newcommand{\LWRmattens}{
    \ifstar\LWRmattensstar\LWRmattensnostar%
}}

\CustomizeMathJax{\newcommand{\aS}{%
    \let\LWRmattenscross\LWRmattensnull%
    \let\LWRmattensovercmd\overrightarrow%
    \let\LWRmattensundercmd\LWRmattensnull%
    \LWRmattens%
}}

\CustomizeMathJax{\newcommand{\Sa}{%
    \let\LWRmattenscross\LWRmattensnull%
    \let\LWRmattensovercmd\underrightarrow%
    \let\LWRmattensundercmd\LWRmattensnull%
    \LWRmattens%
}}

\CustomizeMathJax{\newcommand{\bS}{%
```

```
    \let\LWRmattenscross\LWRmattensnull%
    \let\LWRmattensovercmd\overline%
    \let\LWRmattensundercmd\LWRmattensnull%
    \LWRmattens%
}}

\CustomizeMathJax{\newcommand{\Sb}{%
    \let\LWRmattenscross\LWRmattensnull%
    \let\LWRmattensovercmd\underline%
    \let\LWRmattensundercmd\LWRmattensnull%
    \LWRmattens%
}}

\CustomizeMathJax{\newcommand{\aSa}{%
    \let\LWRmattenscross\LWRmattensnull%
    \let\LWRmattensovercmd\overrightarrow%
    \let\LWRmattensundercmd\underrightarrow%
    \LWRmattens%
}}

\CustomizeMathJax{\newcommand{\aSb}{%
    \let\LWRmattenscross\LWRmattensnull%
    \let\LWRmattensovercmd\overrightarrow%
    \let\LWRmattensundercmd\underline%
    \LWRmattens%
}}

\CustomizeMathJax{\newcommand{\bSa}{%
    \let\LWRmattenscross\LWRmattensnull%
    \let\LWRmattensovercmd\overline%
    \let\LWRmattensundercmd\underrightarrow%
    \LWRmattens%
}}

\CustomizeMathJax{\newcommand{\bSb}{%
    \let\LWRmattenscross\LWRmattensnull%
    \let\LWRmattensovercmd\overline%
    \let\LWRmattensundercmd\underline%
    \LWRmattens%
}}

\CustomizeMathJax{\newcommand{\aCSa}{%
    \let\LWRmattenscross\tilde%
    \let\LWRmattensovercmd\overrightarrow%
    \let\LWRmattensundercmd\underrightarrow%
    \LWRmattens%
}}

\CustomizeMathJax{\newcommand{\bCSb}{%
    \let\LWRmattenscross\tilde%
    \let\LWRmattensovercmd\overline%
    \let\LWRmattensundercmd\underline%
    \LWRmattens%
}}
\end{warpMathJax}
```

File 281 **lwarp-maybemath.sty**

## § 388 Package maybemath

(*Emulates or patches code by* Andy Buckley.)

Pkg maybemath maybemath is used as-is for SVG math, and is emulated for MathJax.

⚠ no effect MathJax is not able to detect the surrounding text font, so all maybemath macros are ignored.

**for HTML output:**

```
\LWR@ProvidesPackagePass{maybemath}[2005/2/22]

\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\mayberm}[1]{{#1}}}
\CustomizeMathJax{\let\maybebm\mayberm}
\CustomizeMathJax{\let\maybeit\mayberm}
\CustomizeMathJax{\let\maybeitrm\mayberm}
\CustomizeMathJax{\let\maybeitsubscript\mayberm}
\CustomizeMathJax{\let\maybesf\mayberm}
\CustomizeMathJax{\let\maybebmsf\mayberm}
\end{warpMathJax}
```

File 282 **lwarp-mcaption.sty**

## § 389 Package mcaption

(*Emulates or patches code by* Stephan Hennig.)

Pkg mcaption mcaption is ignored.

**for HTML output:** Discard all options for lwarp-mcaption:

```
\LWR@ProvidesPackageDrop{mcaption}[2009/03/13]

\newenvironment{margincap}{}{}
\newcommand*{\margincapalign}{}
\newlength{\margincapsep}
```

File 283 **lwarp-mdframed.sty**

## § 390 Package mdframed

(*Emulates or patches code by* Marco Daniel, Elke Schubert.)

Pkg mdframed mdframed is loaded with options forced to `frame method=none`.

## § 390.1 Limitations

support Most basic functionality is supported, including frame background colors and single-border colors and thickness, title and subtitle background colors and borders and thickness, border radius, and shadow. CSS classes are created for mdframed environments and frame titles.

⚠ loading When used, lwarp loads mdframed in HTML with `framemethod=none`.

font For title font, use

```
frametitlefont=\textbf,
```

instead of

```
frametitlefont=\bfseries,
```

where `\textbf` must appear just before the comma and will receive the following text as its argument (since the text happens to be between braces in the mdframed source). Since lwarp does not support `\bfseries` and friends, only one font selection may be made at a time.

theoremtitlefont `theoremtitlefont` is not supported, since the following text is not in braces in the mdframed source.

ignored options `userdefinedwidth` and `align` are currently ignored.

css classes Environments created or encapsulated by mdframed are enclosed in a `<div>` of class `mdframed`, and also class `md<environmentname>` for new environments.

Frame titles are placed in a `<div>` of class |mdframedtitle|. Subtitles are in a `<div>` of class |mdframedsubtitle|, and likewise for subsubtitles.

Pre-existing hooks are used to patch extra functions before and after the frames.

## § 390.2 Package loading

**for HTML output:**

```
\RequirePackage{xcolor}% for \convertcolorspec

\LWR@ProvidesPackageDrop{mdframed}[2013/07/01]
```

Do not require Ti*k*z or pstricks:

```
\LWR@origRequirePackage[framemethod=none]{mdframed}
```

## § 390.3 Patches

Patch to remove PDF formatting and add HTML tags:

```
\AtBeginDocument{
\def\mdf@trivlist#1{%
  \edef\mdf@temp{%
%     \topsep=\the\topsep\relax%
%     \partopsep=\the\partopsep\relax%
%     \parsep=\the\parsep\relax%
  }%
%   \setlength{\topsep}{#1}%
```

```
%   \topskip\z@%
%   \partopsep\z@%
%   \parsep\z@%
%   \@nmbrlistfalse%
%   \@trivlist%
%   \labelwidth\z@%
%   \leftmargin\z@%
%   \itemindent\z@%
  \let\@itemlabel\@empty%
  \def\makelabel##1{##1}%
%   \item\relax\mdf@temp\relax%
}

\renewcommand*{\endmdf@trivlist}{%
\LWR@traceinfo{endmdf@trivlist}%
% \endtrivlist%
\LWR@listend%
}
}% AtBeginDocument
```

## § 390.4 Initial setup

To handle css and paragraphs, patch code at start and end of environment and contents. `\LWR@print@raggedright` helps avoid hyphenation.

```
\mdfsetup{
startcode={\LWR@mdframedstart\LWR@print@raggedright},
endcode={\LWR@mdframedend},
startinnercode={\LWR@startpars\LWR@print@raggedright},
endinnercode={\LWR@stoppars},
}
```

## § 390.5 Color and length HTML conversion

`\LWR@mdfprintcolor` {⟨*mdfcolorkey*⟩}

Given the mdframed key, print the color.

```
\newcommand*{\LWR@mdfprintcolor}[1]{%
\convertcolorspec{named}{\@nameuse{mdf@#1}}{HTML}\LWR@tempcolor%
\LWR@origpound\LWR@tempcolor
}
```

`\LWR@mdfprintlength` {⟨*mdflengthkey*⟩}

Given the mdframed key, print the length.

```
\newcommand*{\LWR@mdfprintlength}[1]{%
\LWR@forceminwidth{\@nameuse{mdf@#1@length}}%
\LWR@printlength{\LWR@atleastonept}%
}
```

## § 390.6 Environment encapsulation

\LWR@mdframedstart Actions before an mdframe starts.

Encapsulate a frame inside a  of the desired class.

```
\newcommand*{\LWR@mdframedstart}{%
\LWR@traceinfo{LWR@mdframedstart start}%
```

Warn if starting a frame inside a :

```
    \LWR@spanwarninvalid{mdframe}%
```

Turn off paragraph handling during the generation of the encapsulating tags:

```
\LWR@stoppars%
```

Open a  and with custom class and custom style. A BlockClass environment is not used because this  is created by the mdframed startcode and endcode settings, which do not properly nest the  inside the mdframed environment.

```
\LWR@htmltagc{div class=\textquotedbl%
mdframed%
\ifdefstring{\LWR@mdthisenv}{mdframed}{}{ \LWR@mdthisenv}%
\textquotedbl \LWR@orignewline
style=\textquotedbl\LWR@orignewline
```

Convert and print the background color:

```
background: \LWR@mdfprintcolor{backgroundcolor} ; \LWR@orignewline
```

Convert and print the border color and width:

```
border: \LWR@mdfprintlength{linewidth} solid
\LWR@mdfprintcolor{linecolor} ; \LWR@orignewline
```

Convert and print the border radius:

```
border-radius: \LWR@mdfprintlength{roundcorner} ; \LWR@orignewline
```

Convert and print the shadow:

```
\ifbool{mdf@shadow}{%
    box-shadow:
    \LWR@mdfprintlength{shadowsize}
    \LWR@mdfprintlength{shadowsize}
    \LWR@mdfprintlength{shadowsize}
    \LWR@mdfprintcolor{shadowcolor} ;
}
{box-shadow: none ;}
\LWR@orignewline

\textquotedbl}
% \LWR@htmldivclass{\LWR@mdthisenv}
```

mdframed environment may not work with the HTML versions of the following, so restore them to their originals while inside mdframed:

```
\LWR@select@print@hspace%
\renewcommand*{\rule}{\LWR@print@rule}
\LetLtxMacro\makebox\LWR@print@makebox%

\LWR@startpars%
\LWR@traceinfo{LWR@mdframedstart done}%
}
```

\LWR@mdframedend Actions after an mdframe ends.

After closing the , globally restore to the default environment type:

```
\newcommand*{\LWR@mdframedend}{
\LWR@traceinfo{LWR@mdframedend start}%
```

Close the custom :

```
\LWR@htmldivclassend{\LWR@mdthisenv}
```

Reset future custom class to the default:

```
\gdef\LWR@mdthisenv{mdframed}
```

Resume paragraph handling:

```
\LWR@startpars%
\LWR@traceinfo{LWR@mdframedend done}%
}
```

## § 390.7 Mdframed environment

```
\renewenvironment{mdframed}[1][]{%
 \color@begingroup%
   \mdfsetup{userdefinedwidth=\linewidth,#1}%
   \mdf@startcode%
   \mdf@preenvsetting%
   \ifdefempty{\mdf@firstframetitle}{}%
            {\let\mdf@frametitlesave\mdf@frametitle%
             \let\mdf@frametitle\mdf@firstframetitle%
            }%
   \ifvmode\nointerlineskip\fi%
        \ifdefempty{\mdf@frametitle}{}%
            {\mdfframedtitleenv{\mdf@frametitle}%
%             \mdf@@frametitle@use%
            }%
   \mdf@trivlist{\mdf@skipabove@length}%%
   \mdf@settings%
%    \mdf@lrbox{\mdf@splitbox@one}%
%    \mdf@startinnercode%
  }%
  {%
%    \mdf@@ignorelastdescenders%
   \par%
%     \unskip\ifvmode\nointerlineskip\hrule \@height\z@ \@width\hsize\fi%%
   \ifmdf@footnoteinside%
      \def\mdf@reserveda{%
        \mdf@footnoteoutput%
%         \mdf@endinnercode%
%         \endmdf@lrbox%
%         \ifdefempty{\mdf@frametitle}{}%
%             {\mdfframedtitleenv{\mdf@frametitle}\mdf@@frametitle@use}%
%         \detected@mdf@put@frame
      }%
   \else%
      \def\mdf@reserveda{%
%         \mdf@endinnercode%
```

```
%         \endmdf@lrbox%
%         \ifdefempty{\mdf@frametitle}{}%
%             {\mdfframedtitleenv{\mdf@frametitle}\mdf@@frametitle@use}%
%         \detected@mdf@put@frame%
        \mdf@footnoteoutput%
        }%
   \fi%
   \mdf@reserveda%
  \aftergroup\endmdf@trivlist%
 \color@endgroup%
 \mdf@endcode%
}
```

\mdf@footnoteoutput

```
\renewrobustcmd*\mdf@footnoteoutput{%
    \LWR@printpendingmpfootnotes%
}
```

## § 390.8 Titles and subtitles

\mdfframedtitleenv {⟨*title*⟩}

Place the title inside a  of class mdframedtitle:

```
\newlength{\LWR@titleroundcorner}

\renewrobustcmd\mdfframedtitleenv[1]{%
\LWR@traceinfo{LWR@mdframedtitleenv start}%
```

Open a  with a custom class and custom style:

```
\begin{BlockClass}[%
```

Convert and print the title background color:

```
background:
\LWR@mdfprintcolor{frametitlebackgroundcolor}
; \LWR@orignewline
```

Convert and print the title rule:

```
\ifbool{mdf@frametitlerule}{%
    border-bottom:
    \LWR@mdfprintlength{frametitlerulewidth}
    solid
    \LWR@mdfprintcolor{frametitlerulecolor}
    ; \LWR@orignewline
}{}%
```

Finish the custom style and the opening  tag:

```
]{mdframedtitle}%
```

Print the title inside the :

```
\mdf@frametitlefont{\LWR@textcurrentfont{#1}}%
```

Close the :

```
\end{BlockClass}%
\LWR@traceinfo{LWR@mdframedtitleenv end}%
```

```
}
```

`\LWR@mdfsubtitlecommon` {⟨*sub — or — subsub*⟩} [⟨*options*⟩] {⟨*title*⟩}

Common code for `\LWR@mdfsubtitle` and `\LWR@mdfsubsubtitle`.

Encapsulate the subtitle inside a `<div>` of class `mdframedsubtitle`:

```
\NewDocumentCommand{\LWR@mdfsubtitlecommon}{m o m}
{% the following empty line is required

\LWR@traceinfo{LWR@mdframedsubtitlecommon start}%
```

Open a `<div>` with a custom `class` and custom `style`:

```
\begin{BlockClass}[%
```

Convert and print the background color:

```
background:
\LWR@mdfprintcolor{#1titlebackgroundcolor}
; \LWR@orignewline
```

Convert and print the above line:

```
\ifbool{mdf@#1titleaboveline}{%
    border-top:
    \LWR@mdfprintlength{#1titleabovelinewidth}
    solid
    \LWR@mdfprintcolor{#1titleabovelinecolor}
    ; \LWR@orignewline
}{}%
```

Convert and print the below line:

```
\ifbool{mdf@#1titlebelowline}{%
    border-bottom:
    \LWR@mdfprintlength{#1titlebelowlinewidth}
    solid
    \LWR@mdfprintcolor{#1titlebelowlinecolor}
    ; \LWR@orignewline
}{}%
```

Finish the custom style and the opening `<div>` tag:

```
]{mdframed#1title}%
```

Perform the original subtitle action:

```
\IfNoValueTF{#2}
{\@nameuse{LWR@origmdf#1title}{\csuse{mdf@#1titlefont}{\LWR@textcurrentfont{#3}}}}%
{\@nameuse{LWR@origmdf#1title}[#2]{\csuse{mdf@#1titlefont}{\LWR@textcurrentfont{#3}}}}%
```

Close the `<div>`:

```
\end{BlockClass}%
\LWR@traceinfo{LWR@mdframedsubtitlecommon end}%
}
```

`\LWR@mdfsubtitle` [⟨*options*⟩] {⟨*title*⟩}

```
\newcommand*{\LWR@mdfsubtitle}{%
```

```
\LWR@mdfsubtitlecommon{sub}%
}
\let\mdfsubtitle\LWR@mdfsubtitle
```

`\LWR@mdfsubsubtitle` `[⟨options⟩] {⟨title⟩}`

```
\newcommand*{\LWR@mdfsubsubtitle}{%
\LWR@mdfsubtitlecommon{subsub}%
}
\let\mdfsubsubtitle\LWR@mdfsubsubtitle
```

## § 390.9 New environments

`\LWR@mdthisenv` Stores the environment of the frame about to be created:

```
\newcommand*{\LWR@mdthisenv}{mdframed}
```

`\newmdenv` `[⟨options⟩] {⟨env-name⟩}`

Modified from the original to remember the environment.

```
\renewrobustcmd*\newmdenv[2][]{%
\newenvironment{#2}%
{%
\mdfsetup{#1}%
\renewcommand*{\LWR@mdthisenv}{md#2}%
\begin{mdframed}%
}
{\end{mdframed}}%
}
```

`\surroundwithmdframed` `[⟨options⟩] {⟨environment⟩}`

Modified from the original to remember the environment.

```
\renewrobustcmd*{\surroundwithmdframed}[2][]{%
\BeforeBeginEnvironment{#2}{%
\renewcommand*{\LWR@mdthisenv}{md#2}%
\begin{mdframed}[#1]}%
\AfterEndEnvironment{#2}{\end{mdframed}}%
}
```

`\mdtheorem` `[⟨mdframed-options⟩] {⟨envname⟩} [⟨numberedlike⟩] {⟨caption⟩} [⟨within⟩]`

Modified from the original to remember the environment.

```
\DeclareDocumentCommand{\mdtheorem}{ O{} m o m o }%
 {\ifcsdef{#2}%
   {\mdf@PackageWarning{Environment #2 already exits\MessageBreak}}%
   {%
    \IfNoValueTF {#3}%
     {%#3 not given -- number relationship
      \IfNoValueTF {#5}%
        {%#3+#5 not given
        \@definecounter{#2}%
        \expandafter\xdef\csname the#2\endcsname{\@thmcounter{#2}}%
        \newenvironment{#2}[1][]{%
```

```
      \refstepcounter{#2}%
      \ifstrempty{##1}%
        {\let\@temptitle\relax}%
        {%
         \def\@temptitle{\mdf@theoremseparator%
                         \mdf@theoremspace%
                         \mdf@theoremtitlefont%
                         \LWR@textcurrentfont{##1}}% lwarp
         \mdf@thm@caption{#2}{{#4}{\csname the#2\endcsname}{##1}}%
         }%
      \begin{mdframed}[#1,frametitle={\strut#4\ \csname the#2\endcsname%
                                      \@temptitle}]}%
      {\end{mdframed}}%
    \newenvironment{#2*}[1][]{%
      \ifstrempty{##1}{\let\@temptitle\relax}{\def\@temptitle{:\ ##1}}%
      \begin{mdframed}[#1,frametitle={\strut#4\@temptitle}]}%
      {\end{mdframed}}%
    }%
    {%#5 given -- reset counter
    \@definecounter{#2}\@newctr{#2}[#5]%
    \expandafter\xdef\csname the#2\endcsname{\@thmcounter{#2}}%
    \expandafter\xdef\csname the#2\endcsname{%
           \expandafter\noexpand\csname the#5\endcsname \@thmcountersep%
              \@thmcounter{#2}}%
    \newenvironment{#2}[1][]{%
      \refstepcounter{#2}%
      \ifstrempty{##1}%
        {\let\@temptitle\relax}%
        {%
         \def\@temptitle{\mdf@theoremseparator%
                         \mdf@theoremspace%
                         \mdf@theoremtitlefont%
                         \LWR@textcurrentfont{##1}}% lwarp
         \mdf@thm@caption{#2}{{#4}{\csname the#2\endcsname}{##1}}%
         }
      \begin{mdframed}[#1,frametitle={\strut#4\ \csname the#2\endcsname%
                                      \@temptitle}]}%
      {\end{mdframed}}%
    \newenvironment{#2*}[1][]{%
      \ifstrempty{##1}%
        {\let\@temptitle\relax}%
        {%
         \def\@temptitle{\mdf@theoremseparator%
                         \mdf@theoremspace%
                         \mdf@theoremtitlefont%
                         \LWR@textcurrentfont{##1}}% lwarp
         \mdf@thm@caption{#2}{{#4}{\csname the#2\endcsname}{##1}}%
         }%
      \begin{mdframed}[#1,frametitle={\strut#4\@temptitle}]}%
      {\end{mdframed}}%
    }%
  }%
  {%#3 given -- number relationship
    \global\@namedef{the#2}{\@nameuse{the#3}}%
    \newenvironment{#2}[1][]{%
```

```
          \refstepcounter{#3}%
          \ifstrempty{##1}%
            {\let\@temptitle\relax}%
            {%
             \def\@temptitle{\mdf@theoremseparator%
                             \mdf@theoremspace%
                             \mdf@theoremtitlefont%
                             \LWR@textcurrentfont{##1}}% lwarp
             \mdf@thm@caption{#2}{{#4}{\csname the#2\endcsname}{##1}}%
             }
          \begin{mdframed}[#1,frametitle={\strut#4\ \csname the#2\endcsname%
                                          \@temptitle}]}%
          {\end{mdframed}}%
        \newenvironment{#2*}[1][]{%
          \ifstrempty{##1}{\let\@temptitle\relax}{\def\@temptitle{:\ ##1}}%
          \begin{mdframed}[#1,frametitle={\strut#4\@temptitle}]}%
          {\end{mdframed}}%
     }%
    \BeforeBeginEnvironment{#2}{\renewcommand*{\LWR@mdthisenv}{md#2}}% lwarp
    \BeforeBeginEnvironment{#2*}{\renewcommand*{\LWR@mdthisenv}{md#2}}% lwarp
   }%
}
```

`\newmdtheoremenv` `[`⟨*1: mdframed-options*⟩`]` `{`⟨*2: envname*⟩`}` `[`⟨*3: numberedlike*⟩`]` `{`⟨*4: caption*⟩`}` `[`⟨*5: within*⟩`]`

Modified from the original to remember the environment.

```
\DeclareDocumentCommand\newmdtheoremenv{O{} m o m o }{%
 \ifboolexpr{ test {\IfNoValueTF {#3}} and test {\IfNoValueTF {#5}} }%
    {\newtheorem{#2}{#4}}%
    {%
     \IfValueT{#3}{\newtheorem{#2}[#3]{#4}}%
     \IfValueT{#5}{\newtheorem{#2}{#4}[#5]}%
    }%
 \BeforeBeginEnvironment{#2}{%
 \renewcommand*{\LWR@mdthisenv}{md#2}%
 \begin{mdframed}[#1]}%
 \AfterEndEnvironment{#2}{%
 \end{mdframed}}%
}
```

---

File 284 **lwarp-mdwmath.sty**

# § 391 Package mdwmath

(*Emulates or patches code by* Mark Wooding.)

Pkg mdwmath mdwmath is used as-is for SVG math, and is emulated for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{mdwmath}[1996/04/11]

\begin{warpMathJax}
\CustomizeMathJax{\let\LWRmdwmathsqrt\sqrt}
\CustomizeMathJax{\renewcommand{\sqrt}{\ifstar\LWRmdwmathsqrt\LWRmdwmathsqrt}}
```

```
\CustomizeMathJax{\newcommand{\bitand}{\mathbin\&}}
\CustomizeMathJax{\def\bitor{\mathbin\mid}}
\CustomizeMathJax{\def\dblor{\mathbin{\mid\mid}}}
\CustomizeMathJax{\def\dbland{\mathbin{\mathrel\bitand\mathrel\bitand}}}
\end{warpMathJax}
```

File 285 **lwarp-media9.sty**

§ 392 Package

# media9

Pkg media9 media9 is emulated.

The packages multimedia, movie15, and media9 are supported.

HTML5 <audio> and <video> objects are created for .mp3 and .mp4 files.

HTML5 <embed> objects are created for http and ftp links.

\href links are created for other media types. (Unfortunately, there is not much overlap between the file types supported for print output and the file types supported by HTML5.)

For media9, a multimedia object is inserted for each addresource=, as well as each flashvars source= and src=. This may result in duplicate objects.

Undesired objects may be nullified by placing them inside \warpprintonly or the warpprint environment.

Each HTML multimedia object includes the poster text, except for <embed> objects. For movie15, the text option is supported to specify the poster text.

The width, height, and totalheight options are supported. The HTML object is scaled according to the display width, correctly compensating for either tall or wide viewports.

Other options are ignored.

media9 \addmediapath is supported. It is assumed that the same path structure will exist for the HTML document.

HTML5 media controls are always specified for each <audio> and <video> object.

media9 slideshows are not supported.

\hyperlinkmovie, \movieref, and \mediabutton are not supported.

3D objects are not supported.

If using a YouTube™ video, use an "embedded" URL with .../embed/... instead of .../v/...

⚠ & in a URL Many special characters are converted to regular catcode 12 characters for use inside a URL. & is used in the flash variables fields, which are split with xparse \SplitList, which does not seem to work with a catcode 12 divider token, so & is not converted to catcode 12, and will not work in a URL with media9. Using & in a URL in a flashvars field may also cause parsing problems with print output, as well.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{media9}[2019/02/21]

\LWR@origRequirePackage{lwarp-common-multimedia}

\RequirePackage{xkeyval}
```

\addmediapath {⟨*path*⟩}

Supported.

```
\newcommand*{\LWR@medianine@path}{}

\newcommand*{\addmediapath}[1]{\appto\LWR@medianine@path{{#1}}}
```

The options and poster text are reused in several places.

```
\newcommand*{\LWR@medianine@postertext}{}
\newcommand*{\LWR@medianine@options}{}
```

Each addresource can generate a multimedia object.

```
\define@key{LWR@medianine}{addresource}{%
    \expandafter\LWR@multimedia\expandafter[\LWR@medianine@options]
        {\LWR@medianine@postertext}
        {#1}
}
```

Each flashvars source can generate a multimedia object.

```
\newcommand*{\LWR@medianine@flashvarsb}[1]{%
    \IfBeginWith{#1}{source=}{%
        \StrGobbleLeft{#1}{7}[\LWR@tempone]%
        \expandafter\LWR@multimedia\expandafter[\LWR@medianine@options]%
            {\LWR@medianine@postertext}%
            {\LWR@tempone}%
    }{}%
    \IfBeginWith{#1}{src=}{%
        \StrGobbleLeft{#1}{4}[\LWR@tempone]%
        \expandafter\LWR@multimedia\expandafter[\LWR@medianine@options]%
            {\LWR@medianine@postertext}%
            {\LWR@tempone}%
    }{}%
}

\NewDocumentCommand{\LWR@medianine@flashvars}{ >{\SplitList{&}} m }{%
    \ProcessList {#1}{\LWR@medianine@flashvarsb}%
}

\define@key{LWR@medianine}{flashvars}{%
    \LWR@medianine@flashvars{#1}%
}
```

\includemedia [⟨*options*⟩] {⟨*poster text*⟩} {⟨*file or* URL⟩}

```
\newcommand*{\LWR@includemediab}[3][]{%
```

```
    \let\input@path\LWR@medianine@path%
    \renewcommand*{\LWR@medianine@options}{#1}%
    \renewcommand*{\LWR@medianine@postertext}{#2}%
    \setkeys*{LWR@medianine}{#1}%
    \IfBeginWith{#3}{http}{\LWR@multimedia[#1]{#2}{#3}}{%
    \IfBeginWith{#3}{HTTP}{\LWR@multimedia[#1]{#2}{#3}}{%
    \IfBeginWith{#3}{ftp}{\LWR@multimedia[#1]{#2}{#3}}{%
    \IfBeginWith{#3}{FTP}{\LWR@multimedia[#1]{#2}{#3}}{%
    }}}}%
    \endgroup%
}

\newrobustcmd*{\includemedia}{%
    \begingroup%
    \LWR@linkmediacatcodes%
    \LWR@includemediab%
}
```

`\mediabutton` `[`⟨*options*⟩`]` `{`⟨*text*⟩`}`

Ignored.

```
\newcommand*{\mediabutton}[2][]{}
```

---

File 286 **lwarp-memhfixc.sty**

# § 393 Package memhfixc

Pkg memhfixc memhfixc is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{memhfixc}[2013/05/30]
```

---

File 287 **lwarp-menukeys.sty**

# § 394 Package menukeys

(*Emulates or patches code by* Tobias Weh.)

Pkg menukeys menukeys is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{menukeys}[2020/12/19]
```

Patch to use a `lateximage` whose `alt` text is the contents of this use of the macro. A hash on these contents allows the reuse of the image for each instance of the same contents.

```
\xpatchcmd{\tw@define@menu@macro@}
    {\@nameuse{tw@style@#4@pre}}
    {%
        \begin{lateximage}*[\detokenize{##2}]%
        \@nameuse{tw@style@#4@pre}%
    }
```

```
    {}
    {\LWR@patcherror{menukeys}{tw@define@menu@macro@}}

\xpatchcmd{\tw@define@menu@macro@}
    {\@nameuse{tw@style@#4@post}}
    {%
        \@nameuse{tw@style@#4@post}%
        \end{lateximage}%
    }
    {}
    {\LWR@patcherror{menukeys}{tw@define@menu@macro@ B}}
```

Patch the existing macros:

```
\renewmenumacro{\menu}[>]{menus}
\renewmenumacro{\directory}[/]{paths}
\renewmenumacro{\keys}[+]{roundedkeys}
```

---

File 288 **lwarp-metalogo.sty**

## § 395 Package metalogo

(*Emulates or patches code by* Andrew Gilbert Moschou.)

Pkg metalogo metalogo is used in print mode, and emulated in HTML.

**for HTML output:**

```
\LWR@ProvidesPackagePass{metalogo}[2010/05/29]

\newcommand*{\LWR@HTML@setlogokern}[2]{}
\newcommand*{\LWR@HTML@setlogodrop}[2][XeTeX]{}
\newcommand*{\LWR@HTML@setLaTeXa}[1]{}
\newcommand*{\LWR@HTML@setLaTeXee}[1]{}
\newcommand*{\LWR@HTML@seteverylogo}[1]{}
\newcommand*{\LWR@HTML@everylogo}[1]{}

\LWR@formatted{setlogokern}
\LWR@formatted{setlogodrop}
\LWR@formatted{setLaTeXa}
\LWR@formatted{setLaTeXee}
\LWR@formatted{seteverylogo}
\LWR@formatted{everylogo}
```

---

File 289 **lwarp-metalogox.sty**

## § 396 Package metalogox

(*Emulates or patches code by* Brian Dunn.)

Pkg metalogox metalogox is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{metalogox}[2019/01/20]
```

## § 398 Package microtype

(*Emulates or patches code by* R Schlicht.)

Pkg microtype microtype is pre-loaded by lwarp. All user options and macros are ignored and disabled.

**for HTML output:** Discard all options for lwarp-microtype:

```
\LWR@ProvidesPackageDrop{microtype}[2018/01/14]

\DeclareDocumentCommand{\DeclareMicrotypeSet}{o m m}{}
\DeclareDocumentCommand{\UseMicrotypeSet}{o m}{}
\DeclareDocumentCommand{\DeclareMicrotypeSetDefault}{o m}{}
\DeclareDocumentCommand{\SetProtrusion}{o m m}{}
\DeclareDocumentCommand{\SetExpansion}{o m m}{}
\DeclareDocumentCommand{\SetTracking}{o m m}{}
\DeclareDocumentCommand{\SetExtraKerning}{o m m}{}
\DeclareDocumentCommand{\SetExtraSpacing}{o m m}{}
\DeclareDocumentCommand{\DisableLigatures}{o m}{}
\DeclareDocumentCommand{\DeclareCharacterInheritance}{o m m}{}
\DeclareDocumentCommand{\DeclareMicrotypeVariants}{m}{}
\DeclareDocumentCommand{\DeclareMicrotypeAlias}{m m}{}
\DeclareDocumentCommand{\LoadMicrotypeFile}{m}{}
\DeclareDocumentCommand{\DeclareMicrotypeBabelHook}{m m}{}
\DeclareDocumentCommand{\microtypesetup}{m}{}
\DeclareDocumentCommand{\microtypecontext}{m}{}
\DeclareDocumentCommand{\textmicrotypecontext}{m m}{#2}
\@ifpackageloaded{letterspace}{\let\MT@textls\relax}{%
\DeclareDocumentCommand{\lsstyle}{}{}
\DeclareDocumentCommand{\textls}{o +m}{}
\DeclareDocumentCommand{\lslig}{m}{#1}
}
\def\DeclareMicrotypeSet#1#{\@gobbletwo}
\def\DeclareMicrotypeVariants#1#{\@gobble}
\@onlypreamble\DeclareMicrotypeSet
\@onlypreamble\UseMicrotypeSet
\@onlypreamble\DeclareMicrotypeSetDefault
\@onlypreamble\DisableLigatures
\@onlypreamble\DeclareMicrotypeVariants
\@onlypreamble\DeclareMicrotypeBabelHook
```

---

File 292 **lwarp-midfloat.sty**

## § 399 Package midfloat

(*Emulates or patches code by* Sigitas Tolušis.)

Pkg midfloat midfloat is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{midfloat}[2012/05/29]

\newenvironment{strip}[1][]{}{}
\newskip\stripsep
```

```
        \end{tabular}
        \end{BlockClass}
    }
    \group_end:
    \LWR@startpars%
}
\ExplSyntaxOff

\LWR@formatted{minibox}
```

File 295 **lwarp-minitoc.sty**

# § 402 Package minitoc

Pkg minitoc minitoc is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{minitoc}[2018/07/12]
```

mtcoff disables minitoc.

```
\usepackage{mtcoff}
```

File 296 **lwarp-minted.sty**

# § 403 Package minted

(*Emulates or patches code by* Geoffrey M. Poore.)

Pkg minted minted is patched for use by lwarp.

⚠ limitations mathescape and highlightlines don't work. Line numbers on the right will not be aligned. Due to *pdftotext*, extra spaces may appear in broken lines if other formatting is included.

**for HTML output:**

```
\LWR@ProvidesPackagePass{minted}[2017/07/19]

\xpatchcmd{\minted}
    {\setkeys{minted@opt@cmd}{#1}}
    {%
        \setkeys{minted@opt@cmd}{%
            #1,%
            mathescape=false,breaklines,texcomments=false,highlightlines={}%
        }%
    }
    {}
    {\LWR@patcherror{minted}{minted}}

\xpatchcmd{\mintinline}
    {\setkeys{minted@opt@cmd}{#1}}
    {\setkeys{minted@opt@cmd}{%
```

```
            #1,%
            mathescape=false,breaklines,texcomments=false,highlightlines={}%
        }%
    }
    {}
    {\LWR@patcherror{minted}{mintinline}}

\xpatchcmd{\mint}
    {\setkeys{minted@opt@cmd}{#1}}
    {%
        \setkeys{minted@opt@cmd}{%
            #1,%
            mathescape=false,breaklines,texcomments=false,highlightlines={}%
        }%
    }
    {}
    {\LWR@patcherror{minted}{mint}}

\xpatchcmd{\inputminted}
    {\setkeys{minted@opt@cmd}{#1}}
    {\setkeys{minted@opt@cmd}{%
            #1,%
            mathescape=false,breaklines,texcomments=false,highlightlines={}%
        }%
    }
    {}
    {\LWR@patcherror{minted}{inputminted}}
```

File 297 **lwarp-mismath.sty**

# § 404 Package mismath

(*Emulates or patches code by* Antoine Missier.)

Pkg mismath mismath is patched for SVG math, and emulated for MathJax.

⚠ MathJax `\enumber`, `\inumber`, `\jnumber`, and `\pinumber` are ignored for MathJax, except that `\itpi` is made available as a clone of `\pi`.

For MathJax, `\boldvect` and `\arrowvect` are honored if in the preamble.

If `\boldvectcommand` is set to `\mathbf` in the preamble, it will be used for MathJax, otherwise it will default to `\mathit`. `\boldvectcommand` may also be set with `\CustomizeMathJax` in the preamble. See section 8.7.5. Note that as of this writing there is not a bold italic font across all MathJax fonts.

If `\probastyle` is set to `\mathbb` in the preamble, it will be used for MathJax, otherwise it will default to `\mathrm`. `\probastyle` may be set with `\CustomizeMathJax` in the preamble.

If `\mathset` is set to `\mathbb` in the preamble, it will be used for MathJax, otherwise it will default to `\mathbf`. `\mathset` may be set with `\CustomizeMathJax` in the preamble.

**for HTML output:**

```
\LWR@ProvidesPackagePass{mismath}[2019/12/27]
```

For MathJax, used in the HTML comment before the environment.

```
\ifbool{mathjax}{
    \RenewEnviron{mathcols}{%
        \preto\BODY{\begin{aligned}\displaystyle}
        \appto\BODY{\end{aligned}}
        \expandafter\(\BODY\)
    }
}% mathjax
```

For SVG math. The `lateximage` restores the original defintion of the `math` environment.

```
{% svg
    \renewenvironment{mathcols}{
        \begin{lateximage}
        \begin{math}
        \begin{aligned}\displaystyle
    }{
        \end{aligned}%
        \end{math}
        \end{lateximage}
    }
}% svg

\renewcommand{\changecol}{
    \end{aligned}   \qquad
    \begin{aligned}\displaystyle
}

\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\mathup}[1]{\mathrm{#1}}}
\CustomizeMathJax{\newcommand{\e}{\mathrm{e}}}
\CustomizeMathJax{\newcommand{\i}{\mathrm{i}}}
\CustomizeMathJax{\newcommand{\j}{\mathrm{j}}}

\CustomizeMathJax{\newcommand{\boldvect}{}}
\CustomizeMathJax{\newcommand{\arrowvect}{}}
\CustomizeMathJax{\newcommand{\pinumber}[1][]{}}
\CustomizeMathJax{\newcommand{\hvect}[1]{\vec{\vphantom{h}#1}}}
\CustomizeMathJax{\newcommand{\hvec}[1]{\vec{\vphantom{t}#1}}}
\CustomizeMathJax{%
    \newcommand{\norm}[1]{\left\vert\left\vert#1\right\vert\right\vert}
}
\CustomizeMathJax{\newcommand{\di}{\mathop{}\!\mathrm{d}}}

\CustomizeMathJax{\newcommand{\P}{\operatorname{\probastyle{P}}}}
\CustomizeMathJax{\newcommand{\E}{\operatorname{\probastyle{E}}}}
\CustomizeMathJax{\newcommand{\V}{\operatorname{\probastyle{V}}}}
\CustomizeMathJax{\newcommand{\Par}{\unicode{x00B6}}}

\CustomizeMathJax{\DeclareMathOperator{\adj}{adj}}
\CustomizeMathJax{\DeclareMathOperator{\Aut}{Aut}}
\CustomizeMathJax{\DeclareMathOperator{\Conv}{Conv}}
\CustomizeMathJax{\DeclareMathOperator{\cov}{cov}}
\CustomizeMathJax{\DeclareMathOperator{\Cov}{Cov}}
```

```
\CustomizeMathJax{\newcommand{\curl}{\operatorname{\vect{\mathrm{curl}}}}}
\CustomizeMathJax{\DeclareMathOperator{\divg}{div}}
\CustomizeMathJax{\DeclareMathOperator{\End}{End}}

\CustomizeMathJax{\DeclareMathOperator{\erf}{erf}}
\CustomizeMathJax{\newcommand{\grad}{\operatorname{\vect{\mathrm{grad}}}}}
\CustomizeMathJax{\DeclareMathOperator{\id}{id}}
\CustomizeMathJax{\DeclareMathOperator{\Id}{Id}}
\CustomizeMathJax{\DeclareMathOperator{\im}{im}}
\CustomizeMathJax{\let\oldIm\Im}
\CustomizeMathJax{\renewcommand{\Im}{\operatorname{Im}}}
\CustomizeMathJax{\DeclareMathOperator{\lb}{lb}}
\CustomizeMathJax{\DeclareMathOperator{\lcm}{lcm}}

\CustomizeMathJax{\DeclareMathOperator{\rank}{rank}}
\CustomizeMathJax{\let\oldRe\Re}
\CustomizeMathJax{\renewcommand{\Re}{\operatorname{Re}}}
\CustomizeMathJax{\newcommand{\rot}{\operatorname{\vect{\mathrm{rot}}}}}
\CustomizeMathJax{\DeclareMathOperator{\sgn}{sgn}}
\CustomizeMathJax{\DeclareMathOperator{\spa}{span}}
\CustomizeMathJax{\DeclareMathOperator{\tr}{tr}}
\CustomizeMathJax{\DeclareMathOperator{\Var}{Var}}
\CustomizeMathJax{\DeclareMathOperator{\Zu}{Z}}

\CustomizeMathJax{\DeclareMathOperator{\arccot}{arccot}}
\CustomizeMathJax{\DeclareMathOperator{\sech}{sech}}
\CustomizeMathJax{\DeclareMathOperator{\csch}{csch}}
\CustomizeMathJax{\DeclareMathOperator{\arsinh}{arsinh}}
\CustomizeMathJax{\DeclareMathOperator{\arcosh}{arcosh}}
\CustomizeMathJax{\DeclareMathOperator{\artanh}{artanh}}
\CustomizeMathJax{\DeclareMathOperator{\arcoth}{arcoth}}
\CustomizeMathJax{\DeclareMathOperator{\arsech}{arsech}}
\CustomizeMathJax{\DeclareMathOperator{\arcsch}{arcsch}}

\CustomizeMathJax{\DeclareMathOperator{\bigO}{\mathcal{O}}}
\CustomizeMathJax{\DeclareMathOperator{\bigo}{O}}
\CustomizeMathJax{\DeclareMathOperator{\lito}{o}}

\CustomizeMathJax{\newcommand{\R}{\mathset{R}}}
\CustomizeMathJax{\newcommand{\C}{\mathset{C}}}
\CustomizeMathJax{\newcommand{\N}{\mathset{N}}}
\CustomizeMathJax{\newcommand{\Z}{\mathset{Z}}}
\CustomizeMathJax{\newcommand{\Q}{\mathset{Q}}}
\CustomizeMathJax{\newcommand{\F}{\mathset{F}}}
\CustomizeMathJax{\newcommand{\K}{\mathset{K}}}

\CustomizeMathJax{\newcommand{\ds}{\displaystyle}}
\CustomizeMathJax{\newcommand{\dlim}{\lim\limits}}
\CustomizeMathJax{\newcommand{\dsum}{\sum\limits}}
\CustomizeMathJax{\newcommand{\dprod}{\prod\limits}}
\CustomizeMathJax{\newcommand{\dcup}{\bigcup\limits}}
\CustomizeMathJax{\newcommand{\dcap}{\bigcap\limits}}
\CustomizeMathJax{\newcommand{\lbar}{\overline}}
\CustomizeMathJax{\newcommand{\hlbar}[1]{\overline{\vphantom{h}#1}}}
\CustomizeMathJax{\newcommand{\eqdef}{\stackrel{\mathrm{def}}{=}}}
```

```
\CustomizeMathJax{\newcommand{\unbr}{\underbrace}}
\CustomizeMathJax{\newcommand{\iif}{if and only if }}

\CustomizeMathJax{\newcommand{\mul}{\mathord{\times}}}
\CustomizeMathJax{\newcommand{\then}{\ \Longrightarrow \ \mbox{} }}
\CustomizeMathJax{\newcommand{\txt}[1]{\quad\text{#1}\quad}}
\CustomizeMathJax{\newcommand{\paren}[1]{\mathopen{\left(#1\right)}}}
\CustomizeMathJax{\newcommand{\pow}[2]{\left( #1 \right)^{\!#2}}}
\CustomizeMathJax{\newcommand{\abs}[1]{\left\vert#1\right\vert}}
\CustomizeMathJax{\newcommand{\lfrac}[2]{\frac{\:#1\:}{\:#2\:}}}

\CustomizeMathJax{\newenvironment{system}[1][l]%
    {\left\{\begin{array}{@{.15em}#1@{}}}
    {\end{array}\right.}
}

\CustomizeMathJax{\newenvironment{spmatrix}
    {\left(\begin{smallmatrix}}
    {\end{smallmatrix}\right)}
}

\CustomizeMathJax{%
    \newenvironment{mathcols}
        {\begin{aligned}\displaystyle}
        {\end{aligned}}
}
\CustomizeMathJax{\newcommand{\changecol}{\end{aligned}\qquad\begin{aligned}}}
```

User-adjustable settings, detected if in the preamble.

```
\AtBeginDocument{
\ifdef{\itpi}{
    \CustomizeMathJax{\let\itpi\pi}
}{}
\ifdefstring{\boldvectcommand}{\mathbf}{
    \CustomizeMathJax{\newcommand{\boldvectcommand}[1]{\mathbf{#1}}}
}{
    \CustomizeMathJax{\newcommand{\boldvectcommand}[1]{\boldsymbol{#1}}}
}
\ifbool{arrowvect}{
    \CustomizeMathJax{\newcommand{\vect}[1]{\overrightarrow{#1}}}
}{
    \CustomizeMathJax{\newcommand{\vect}[1]{\boldvectcommand{#1}}}
}
\ifdefstring{\probastyle}{\mathbb}{
    \CustomizeMathJax{\newcommand{\probastyle}[1]{\mathbb{#1}}}
}{
    \CustomizeMathJax{\newcommand{\probastyle}[1]{\mathrm{#1}}}
}
\ifdefstring{\mathset}{\mathbb}{
    \CustomizeMathJax{\newcommand{\mathset}[1]{\mathbb{#1}}}
}{
    \CustomizeMathJax{\newcommand{\mathset}[1]{\mathbf{#1}}}
}
}
```

```
159 \end{warpMathJax}
```

---

File 298 **lwarp-mleftright.sty**

## § 405 Package mleftright

(*Emulates or patches code by* Heiko Oberdiek.)

Pkg mleftright mleftright is used as-is, and is emulated for MathJax.

**for HTML output:**

```
1 \LWR@ProvidesPackagePass{mleftright}[2019/12/03]

2 \begin{warpMathJax}
3 \CustomizeMathJax{\newcommand{\mleft}{\left}}
4 \CustomizeMathJax{\newcommand{\mright}{\right}}
5 \CustomizeMathJax{\newcommand{\mleftright}{}}
6 \CustomizeMathJax{\newcommand{\mleftrightrestore}{}}
7 \end{warpMathJax}
```

---

File 299 **lwarp-morefloats.sty**

## § 406 Package morefloats

Pkg morefloats morefloats is ignored.

**for HTML output:**

```
1 \LWR@ProvidesPackageDrop{morefloats}[2015/07/22]
```

---

File 300 **lwarp-moreverb.sty**

## § 407 Package moreverb

(*Emulates or patches code by* Robin Fairbairns.)

Pkg moreverb moreverb is supported with some patches.

```
1 \LWR@ProvidesPackagePass{moreverb}[2008/06/03]

2 \BeforeBeginEnvironment{verbatimtab}{%
3 \LWR@forcenewpage
4 \LWR@atbeginverbatim{Verbatim}%
5 }
6 \AfterEndEnvironment{verbatimtab}{%
7 \LWR@afterendverbatim%
8 }
9
10
11 \LetLtxMacro\LWRMV@orig@verbatimtabinput\@verbatimtabinput
```

```
12
13 \renewcommand{\@verbatimtabinput}[2][]{%
14 \LWR@forcenewpage
15 \LWR@atbeginverbatim{Verbatim}%
16 \LWRMV@orig@verbatimtabinput[#1]{#2}%
17 \LWR@afterendverbatim%
18 }
19
20 \BeforeBeginEnvironment{listing}{%
21 \LWR@forcenewpage
22 \LWR@atbeginverbatim{programlisting}%
23 }
24
25 \AfterEndEnvironment{listing}{%
26 \LWR@afterendverbatim%
27 }
28
29 \BeforeBeginEnvironment{listingcont}{%
30 \LWR@forcenewpage
31 \LWR@atbeginverbatim{programlisting}%
32 }
33
34 \AfterEndEnvironment{listingcont}{%
35 \LWR@afterendverbatim%
36 }

37 \LetLtxMacro\LWRMV@@listinginput\@listinginput
38
39 \renewcommand{\@listinginput}[3][]{
40 \LWR@forcenewpage
41 \LWR@atbeginverbatim{programlisting}%
42 \LWRMV@@listinginput[#1]{#2}{#3}%
43 \LWR@afterendverbatim%
44 }
45
46
47 \renewenvironment*{boxedverbatim}
48 {
49 \LWR@forcenewpage
50 \LWR@atbeginverbatim{boxedverbatim}%
51 \verbatim%
52 }
53 {
54 \endverbatim%
55 \LWR@afterendverbatim%
56 }
```

File 301 **lwarp-movie15.sty**

## § 408 Package movie15

Pkg movie15 movie15 is emualted.

The packages multimedia, movie15, and media9 are supported.

HTML5 <audio> and <video> objects are created for .mp3 and .mp4 files.

HTML5 <embed> objects are created for http and ftp links.

\href links are created for other media types. (Unfortunately, there is not much overlap between the file types supported for print output and the file types supported by HTML5.)

For media9, a multimedia object is inserted for each addresource=, as well as each flashvars source= and src=. This may result in duplicate objects.

Undesired objects may be nullified by placing them inside \warpprintonly or the warpprint environment.

Each HTML multimedia object includes the poster text, except for <embed> objects. For movie15, the text option is supported to specify the poster text.

The width, height, and totalheight options are supported. The HTML object is scaled according to the display width, correctly compensating for either tall or wide viewports.

Other options are ignored.

media9 \addmediapath is supported. It is assumed that the same path structure will exist for the HTML document.

HTML5 media controls are always specified for each <audio> and <video> object.

media9 slideshows are not supported.

\hyperlinkmovie, \movieref, and \mediabutton are not supported.

3D objects are not supported.

If using a YouTube™ video, use an "embedded" URL with .../embed/... instead of .../v/...

**for HTML output:**

```
\LWR@ProvidesPackageDrop{movie15}[2012/05/16]

\LWR@origRequirePackage{lwarp-common-multimedia}

\RequirePackage{xkeyval}

\newcommand*{\LWR@moviefifteen@text}{}

\define@key{LWR@moviefifteen}{text}{\renewcommand{\LWR@moviefifteen@text}{#1}}

\newcommand*{\LWR@includemovieb}[4][]{%
    \renewcommand{\LWR@moviefifteen@text}{(multimedia)}
    \setkeys*{LWR@moviefifteen}{#1}%
    \LWR@multimediab[#1,width=#2,height=#3]{\LWR@moviefifteen@text}{#4}%
}

\newrobustcmd*{\includemovie}{%
    \begingroup%
    \LWR@linkmediacatcodes%
    \LWR@includemovieb%
}
```

```
21
22
23 \newcommand*{\movieref}[3][]{}
24
25 \LetLtxMacro\movie\LWR@multimedia
26 % \LetLtxMacro\sound\LWR@multimedia% not in media15
27
28 \newcommand{\hyperlinkmovie}[3][]{}
```

File 302 **lwarp-mparhack.sty**

## § 409 Package mparhack

Pkg mparhack mparhack is ignored.

**for HTML output:** Discard all options for lwarp-mparhack:

```
1 \LWR@ProvidesPackageDrop{mparhack}[2005/04/17]
```

File 303 **lwarp-multibib.sty**

## § 410 Package multibib

(*Emulates or patches code by* Thorsten Hansen.)

Pkg multibib multibib is patched for use by lwarp.

**for HTML output:**

```
1 \LWR@ProvidesPackagePass{multibib}[2008/12/10]

2 \xpatchcmd{\newcites}
3     {{\@suffix}}
4     {{\@suffix_html}}
5     {}
6     {\LWR@patcherror{multibib}{newcites}}
```

File 304 **lwarp-multicap.sty**

## § 411 Package multicap

Pkg multicap multicap is emualted.

**for HTML output:**

```
1 \LWR@ProvidesPackageDrop{multicap}[2002/05/04]

2 \newcommand*{\mfcaption}{\captionof{figure}}
3 \newcommand*{\mtcaption}{\captionof{table}}
4 \newcounter{mcapsize}
5 \newcounter{mcapskip}
6 \newlength{\abvmcapskip}
7 \newlength{\blwmcapskip}
```

File 305 **lwarp-multicol.sty**

§ 412 Package

# multicol

(*Emulates or patches code by* Frank Mittelbach.)

Pkg multicol multicol is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{multicol}[2018/12/27]
```

Multicols are converted into a 1–3 column display, browser-supported.

The optional multicols heading is placed inside a  of class multicolsheading.

The content is placed inside a  of class multicols.

Env multicols * {⟨*numcols*⟩} [⟨*heading*⟩]

```
\NewDocumentEnvironment{multicols}{s m o}
```

HTML  class to contain everything:

```
{
    \LWR@forcenewpage
    \BlockClass{multicols}
```

Optional HTML  class for the heading:

```
    \IfValueT{#3}{\begin{BlockClass}{multicolsheading}#3\end{BlockClass}}%
```

Change \linewidth to compensate for expected size:

```
    \setlength{\linewidth}{\linewidth/#2}
```

Locally force any minipages to be fullwidth:

```
    \booltrue{LWR@forceminipagefullwidth}
}
```

When done with the environment, close the :

```
{\endBlockClass}
```

Emulated null functions which are not used in HTML:

```
\newcommand*{\columnbreak}{}
\newcommand*{\RLmulticolcolumns}{}
\newcommand*{\LRmulticolcolumns}{}

\newlength{\premulticols}
\newlength{\postmulticols}
\newlength{\multicolsep}
\newlength{\multicolbaselineskip}
\newlength{\multicoltolerance}
\newlength{\multicolpretolerance}
\newcommand*{\columnseprulecolor}{\normalcolor}
```

```
\CustomizeMathJax{\newcommand{\set}[1]{%
    \mathchoice%
        {{\displaystyle\mathcal{#1}}}%
        {{\textstyle\mathcal{#1}}}%
        {{\scriptstyle\mathcal{#1}}}%
        {{\scriptscriptstyle\mathcal{#1}}}%
}}
\CustomizeMathJax{\def\argmax{\mathop{{\mathrm{arg}}\,\max}}}
\CustomizeMathJax{\def\argmin{\mathop{{\mathrm{arg}}\,\min}
}}
\end{warpMathJax}
```

File 309 **lwarp-multirow.sty**

§ 416 Package

# multirow

(*Emulates or patches code by* Piet van Oostrum, Øystein Bache, Jerry Leichter.)

Pkg multirow multirow is emulated during HTML output, and used as-is while inside a `latexmage`.

vposn

- Note that recent versions of multirow include a new optional vposn argument.

multirow cells

- For multirow, insert `\mrowcell` into any empty multi-row cells. This will be a null function for the print output, and is a placeholder for parsing the table for HTML output. An error is generated if this is missed.

```
. . . &  \multirow{2}{.5in}{text}  & . . .
. . . &  \mrowcell                 & . . .
```

colored cells

- The multirow documentation regarding colored cells recommends using a negative number of rows. This will not work with lwarp, so `\warpprintonly` and `\warpHTMLonly` must be used to make versions for print and HTML.

with \multicolumn

- See section 416.2 for `\multicolumrow`.

⚠ \multicolumn & \multirow

lwarp does not support directly combining `\multicolumn` and `\multirow`. Use `\multicolumnrow` instead. To create a 2 column, 3 row cell:

```
\multicolumnrow{2}{c}[c]{3}[0]{1in}[0pt]{Text}
```

The two arguments for `\multicolumn` come first, followed by the five arguments for `\multirow`, many of which are optional, followed by the contents.

⚠ skipped cells

⚠ empty cells

As per `\multirow`, skipped cells to the right of the `\multicolumnrow` statement are not included in the source code on the same line. On the following lines, `\mcolrowcell` must be used for each cell of each column and each row to be skipped. An error is generated if this is missed.

```
. . . &  \multicolumnrow{2}{c}[c]{3}[0]{1in}[0pt]{Text}  & . . .
. . . &  \mcolrowcell          &          \mcolrowcell   & . . .
. . . &  \mcolrowcell          &          \mcolrowcell   & . . .
```

⚠ MathJax

- MathJax does not support multirow, so it is emulated to only print its text on the first row. `\multirow` works as expected in text `tabulars` or SVG math.

In a `lateximage`, the print versions are restored.

See section 74.25 for the print-mode versions.

**for HTML output:** Remove the placeholder macro which was used if multirow was not loaded:

```
\LetLtxMacro\multirow\relax
\LWR@ProvidesPackagePass{multirow}[2021/01/29]
```

`\LWR@multirowborder` Set to `left` or `right` to create a thick border for the cell, for use by bigdelim:

```
\newcommand{\LWR@multirowborder}{}
```

## § 416.1 Multirow

`\LWR@multirow@par` `\par` inside a `\multirow`.

```
\newcommand*{\LWR@multirow@par}{\LWR@htmltag{br /}\LWR@origpar}%
```

`\multirow` `[`⟨*vpos*⟩`]` `{`⟨*numrows*⟩`}` `[`⟨*bigstruts*⟩`]` `{`⟨*width*⟩`}` `[`⟨*fixup*⟩`]` `{`⟨*text*⟩`}`

```
\NewDocumentCommand{\LWR@HTML@multirow}{O{c} m o m o +m}%
{%
\LWR@traceinfo{*** LWR@HTML@multirow #1 #2 #4}%
\booltrue{LWR@usedmultirow}%
\LWR@maybenewtablerow%
\LWR@tabularleftedge%
```

Print the start of a new table data cell:

```
\LWR@htmltag{td rowspan=\textquotedbl#2\textquotedbl\ %
```

A class adds the column spec and the rule:

```
class=\textquotedbl{}td%
```

Append this column's spec:

```
\LWR@getexparray{LWR@tablecolspec}{\arabic{LWR@tableLaTeXcolindex}}%
```

If this column has a cmidrule, add "rule" to the end of the HTML class tag. Also add the vertical bar class.

```
\LWR@addcmidruletrim%
\LWR@addleftmostbartag%
\LWR@printbartag{\arabic{LWR@tableLaTeXcolindex}}%
\textquotedbl%
\LWR@tdstartstyles%
```

The vertical alignment, if given:

```
\ifstrequal{#1}{c}{\LWR@tdaddstyle\LWR@print@mbox{vertical-align:middle}}{}%
\ifstrequal{#1}{b}{\LWR@tdaddstyle\LWR@print@mbox{vertical-align:bottom}}{}%
\ifstrequal{#1}{t}{\LWR@tdaddstyle\LWR@print@mbox{vertical-align:top}}{}%
```

The left/right border, if given:

```
\ifdefvoid{\LWR@multirowborder}{}{%
    \LWR@tdaddstyle%
    \LWR@print@mbox{border-\LWR@multirowborder:} 2px dotted black ; %
    \LWR@print@mbox{padding-\LWR@multirowborder:} 2px%
}%
```

Additional style elements:

```
\LWR@addcmidrulewidth%
\LWR@addcdashline%
\LWR@addtabularrulecolors%
\LWR@tdendstyles%
}%
```

The column's < spec:

```
\LWR@getexparray{LWR@colbeforespec}{\arabic{LWR@tableLaTeXcolindex}}%
```

While printing the text, redefine \\ to generate a new line. If a nested `tabular` occurs, \\ is redefined to `\LWR@tabularendofline` at the start of the `tabular`, then `\LWR@endofline` before again printing any `\multirow` contents inside the nested `tabular`.

\par is redefined to insert an HTML break, and if `tabular` is nested, it is redefined at the start of `tabular`.

```
\begingroup%
    \LetLtxMacro{\\}{\LWR@endofline}%
    \let\par\LWR@multirow@par%
    #6%
\endgroup%
\LWR@stoppars%
\boolfalse{LWR@intabularmetadata}%
\renewcommand{\LWR@multirowborder}{}%
\LWR@traceinfo{*** LWR@HTML@multirow done}%
}%

\LWR@formatted{multirow}
```

## § 416.2 Combined multicolumn and multirow

\multicolumnrow {⟨*1:cols*⟩} {⟨*2:halign*⟩} [⟨*3:vpos*⟩] {⟨*4:numrows*⟩} [⟨*5:bigstruts*⟩] {⟨*6:width*⟩} [⟨*7:fixup*⟩] {⟨*8:text*⟩}

\@ifpackageloaded{multirow} determines if v2.0 or later of multirow was used, which included the \ProvidesPackage macro.

The HTML version follows.

\AtBeginDocument because the print version had to see if multirow was loaded before determining how to define \LWR@print@multicolumnrow.

```
\AtBeginDocument{

\NewExpandableDocumentCommand{\LWR@HTML@multicolumnrow}{m m O{} m O{} m O{} +m}{%

\booltrue{LWR@usedmultirow}%
```

Figure out how many extra HTML columns to add for @ and ! columns:

```
\LWR@tabularhtmlcolumns{\arabic{LWR@tableLaTeXcolindex}}{#1}
```

Create the multicolumn/multirow tag, temporarily redefining the end of line. (Using a group caused problems with a nested tabular.

```
\LetLtxMacro{\\}{\LWR@endofline}%
\LWR@domulticolumn[#3][#4]{#1}{\arabic{LWR@tabhtmlcoltotal}}{#2}{#8}%
\LetLtxMacro{\\}{\LWR@tabularendofline}%
```

Move to the next LaTeX column:

```
\defaddtocounter{LWR@tableLaTeXcolindex}{#1}%
\defaddtocounter{LWR@tableLaTeXcolindex}{-1}%
```

Skip any trailing @ or ! columns for this cell:

```
\booltrue{LWR@skipatbang}%
}

\LWR@expandableformatted{multicolumnrow}

}% \AtBeginDocument
```

For MathJax. Only the text is used. All other parameters are ignored.

```
\begin{warpMathJax}
% \multirow[vpos]{num}[bigstruts]{width}[vmove]{text}
\CustomizeMathJax{\newcommand{\LWRsubmultirow}[2][]{#2}}
\CustomizeMathJax{\newcommand{\LWRmultirow}[2][]{\LWRsubmultirow}}
\CustomizeMathJax{\newcommand{\multirow}[2][]{\LWRmultirow}}
%
\CustomizeMathJax{\newcommand{\mrowcell}{}}
\CustomizeMathJax{\newcommand{\mcolrowcell}{}}
```

```
\CustomizeMathJax{\newcommand{\STneed}[1]{}}
\end{warpMathJax}
```

---

File 310 **lwarp-multitoc.sty**

## § 417 Package multitoc

Pkg multitoc multitoc is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{multitoc}[1999/06/08]

\newcommand{\multicolumntoc}{2}
\newcommand{\multicolumnlot}{2}
\newcommand{\multicolumnlof}{2}
\newcommand*{\immediateaddtocontents}[2]{}
```

---

File 311 **lwarp-musicography.sty**

## § 418 Package musicography

(*Emulates or patches code by* Andrew A. Cashner.)

Pkg musicography musicography is patched for use by lwarp.

Images are used for the meter symbols and fingered bass, since the HTML fonts tend not to be the correct size and HTML cannot stack items. The HTML `alt` tag copies `C` and `3/2`, etc. Hashes are used for the meter images, which are then reused as necessary.

⚠ Note that browser support for musical symbols may be buggy. ALT text and copy/paste into a text editor work well.

**for HTML output:**

```
\LWR@ProvidesPackagePass{musicography}[2019/05/28]

\NewDocumentCommand{\LWR@HTML@musSymbol}{ O{\musFont} m m m m }{%
\begin{lateximage}%
{#1\kern#2\raisebox{#3}{#5}\kern#4}%
\end{lateximage}%
}

\LWR@formatted{musSymbol}

\NewDocumentCommand{\LWR@HTML@musStemmedNote}{ m }{%
\begin{lateximage}%
\musSymbol{0.05em}{0.5ex}{0.2em}{#1\musStem}%
\end{lateximage}%
}

\LWR@formatted{musStemmedNote}

\NewDocumentCommand{\LWR@HTML@musFlaggedNote}{ m m }{%
```

```
\begin{lateximage}%
\musSymbol{0.05em}{0.5ex}{0pt}{#1\musStem}%
\musSymbol{0pt}{0pt}{0.9em}{#2}%
\end{lateximage}%
}

\LWR@formatted{musFlaggedNote}

\NewDocumentCommand{\LWR@HTML@musDottedNote}{ m }{%
\begin{lateximage}%
#1\musDot%
\end{lateximage}%
}

\LWR@formatted{musDottedNote}

\NewDocumentCommand{\LWR@HTML@musMeter}{ m m }{%
\begin{lateximage}*[#1/#2][#1#2]*%
\musStack{#1 #2}\kern0.05em%
\end{lateximage}%
}

\LWR@formatted{musMeter}

\NewDocumentCommand{\LWR@HTML@meterCplus}{ m }{%
\begin{lateximage}*[C#1]*%
    \meterC{}\kern-0.7pt#1%
\end{lateximage}%
}

\LWR@formatted{meterCplus}

\NewDocumentCommand{\LWR@HTML@meterC}{}{%
\begin{lateximage}*[C]*%
\musSymbolMeter{\symbol{83}}%
\end{lateximage}%
}

\LWR@formatted{meterC}

\NewDocumentCommand{\LWR@HTML@meterCutC}{}{%
\begin{lateximage}*[C|]*%
\musSymbolMeter{\symbol{82}}%
\end{lateximage}%
}

\LWR@formatted{meterCutC}

\NewDocumentCommand{\LWR@HTML@meterCThreeTwo}{}{%
\begin{lateximage}*[C3/2]*%
\meterCplus{\musStack{3 2}}%
\end{lateximage}%
}

\LWR@formatted{meterCThreeTwo}
```

```
74
75 \NewDocumentCommand{\LWR@HTML@meterO}{}{\HTMLunicode{25EF}}
76
77 \LWR@formatted{meterO}
78
79 \newcommand{\LWR@null@noFig}[1][]{}%
80
81 \NewDocumentCommand{\LWR@HTML@musFig}{ m }{%
82 \begin{lateximage}*[%
83     {% ALT text for copy/paste
84         \LetLtxMacro\noFig\LWR@null@noFig%
85         \LetLtxMacro\musSharp\LWR@HTML@musSharp%
86         \LetLtxMacro\musDoubleSharp\LWR@HTML@musDoubleSharp%
87         \LetLtxMacro\musFlat\LWR@HTML@musFlat%
88         \LetLtxMacro\musDoubleFlat\LWR@HTML@musDoubleFlat%
89         \LetLtxMacro\musNatural\LWR@HTML@musNatural%
90         {#1}% braces here because \noFig uses []
91     }%
92 ]*%
93     \musStack[\musFigFont]{#1}%
94 \end{lateximage}%
95 }
96
97 \LWR@formatted{musFig}
98
99 \NewDocumentCommand{\LWR@HTML@musFlat}       {}{\HTMLunicode{266D}}
100 \NewDocumentCommand{\LWR@HTML@musDoubleFlat} {}{\HTMLunicode{1D12B}}
101 \NewDocumentCommand{\LWR@HTML@musSharp}      {}{\HTMLunicode{266F}}
102 \NewDocumentCommand{\LWR@HTML@musDoubleSharp}{}{\HTMLunicode{1D12A}}
103 \NewDocumentCommand{\LWR@HTML@musNatural}    {}{\HTMLunicode{266E}}
104
105 \LWR@formatted{musFlat}
106 \LWR@formatted{musDoubleFlat}
107 \LWR@formatted{musSharp}
108 \LWR@formatted{musDoubleSharp}
109 \LWR@formatted{musNatural}
110
111 \NewDocumentCommand{\LWR@HTML@musWhole}         {}{\HTMLunicode{1D15D}}
112 \NewDocumentCommand{\LWR@HTML@musHalf}          {}{\HTMLunicode{1D15E}}
113 \NewDocumentCommand{\LWR@HTML@musQuarter}       {}{\HTMLunicode{1D15F}}
114 \NewDocumentCommand{\LWR@HTML@musEighth}        {}{\HTMLunicode{1D160}}
115 \NewDocumentCommand{\LWR@HTML@musSixteenth}     {}{\HTMLunicode{1D161}}
116 \NewDocumentCommand{\LWR@HTML@musThirtySecond}  {}{\HTMLunicode{1D162}}
117 \NewDocumentCommand{\LWR@HTML@musSixtyFourth}   {}{\HTMLunicode{1D163}}
118
119 \LWR@formatted{musWhole}
120 \LWR@formatted{musHalf}
121 \LWR@formatted{musQuarter}
122 \LWR@formatted{musEighth}
123 \LWR@formatted{musSixteenth}
124 \LWR@formatted{musThirtySecond}
125 \LWR@formatted{musSixtyFourth}
126
127 \NewDocumentCommand{\LWR@HTML@musWholeDotted}{}
128     {\HTMLunicode{1D15D}\HTMLunicode{1D16D}}
```

```
\NewDocumentCommand{\LWR@HTML@musHalfDotted}{}
    {\HTMLunicode{1D15E}\HTMLunicode{1D16D}}
\NewDocumentCommand{\LWR@HTML@musQuarterDotted}{}
    {\HTMLunicode{1D15F}\HTMLunicode{1D16D}}
\NewDocumentCommand{\LWR@HTML@musEighthDotted}{}
    {\HTMLunicode{1D160}\HTMLunicode{1D16D}}
\NewDocumentCommand{\LWR@HTML@musSixteenthDotted}{}
    {\HTMLunicode{1D161}\HTMLunicode{1D16D}}
\NewDocumentCommand{\LWR@HTML@musThirtySecondDotted}{}
    {\HTMLunicode{1D162}\HTMLunicode{1D16D}}
\NewDocumentCommand{\LWR@HTML@musSixtyFourthDotted}{}
    {\HTMLunicode{1D163}\HTMLunicode{1D16D}}

\LWR@formatted{musWholeDotted}
\LWR@formatted{musHalfDotted}
\LWR@formatted{musQuarterDotted}
\LWR@formatted{musEighthDotted}
\LWR@formatted{musSixteenthDotted}
\LWR@formatted{musThirtySecondDotted}
\LWR@formatted{musSixtyFourthDotted}
```

File 312 **lwarp-nameauth.sty**

# § 419 Package nameauth

(*Emulates or patches code by* Charles P. Schaum.)

Pkg nameauth nameauth is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{nameauth}[2017/03/22]
```

lwarp formatting is inserted in the following.

```
\renewcommand*\@nameauth@Hook[1]
{%
  \if@nameauth@Lock
    \@nameauth@InHooktrue%
    \protected@edef\test{#1}%
    \expandafter\@nameauth@TestDot\expandafter{\test}%
    \if@nameauth@InAKA
      \if@nameauth@AlwaysFormat
        \@nameauth@FirstFormattrue%
      \else
        \unless\if@nameauth@AKAFormat
        \@nameauth@FirstFormatfalse\fi
      \fi
      \if@nameauth@MainFormat
        \if@nameauth@FirstFormat
          \bgroup\NamesFormat{%
            \LWR@textcurrentcolor{\LWR@textcurrentfont{#1}}%    lwarp
          }\egroup%
        \else
          \bgroup\MainNameHook{%
```

```
            \LWR@textcurrentcolor{\LWR@textcurrentfont{#1}}%    lwarp
          }\egroup%
        \fi
      \else
        \if@nameauth@FirstFormat
          \bgroup\FrontNamesFormat{%
            \LWR@textcurrentcolor{\LWR@textcurrentfont{#1}}%    lwarp
          }\egroup%
        \else
          \bgroup\FrontNameHook{%
            \LWR@textcurrentcolor{\LWR@textcurrentfont{#1}}%    lwarp
          }\egroup%
        \fi
      \fi
    \else
      \if@nameauth@AlwaysFormat
        \@nameauth@FirstFormattrue%
      \fi
      \if@nameauth@MainFormat
        \if@nameauth@FirstFormat
          \bgroup\NamesFormat{%
            \LWR@textcurrentcolor{\LWR@textcurrentfont{#1}}%    lwarp
          }\egroup%
        \else
          \bgroup\MainNameHook{%
            \LWR@textcurrentcolor{\LWR@textcurrentfont{#1}}%    lwarp
          }\egroup%
        \fi
      \else
        \if@nameauth@FirstFormat
          \bgroup\FrontNamesFormat{%
            \LWR@textcurrentcolor{\LWR@textcurrentfont{#1}}%    lwarp
          }\egroup%
        \else
          \bgroup\FrontNameHook{%
            \LWR@textcurrentcolor{\LWR@textcurrentfont{#1}}%    lwarp
          }\egroup%
        \fi
      \fi
    \fi
    \@nameauth@FirstFormatfalse%
    \@nameauth@InHookfalse%
  \fi
}
```

File 313 **lwarp-nameref.sty**

## § 420 Package nameref

Pkg nameref nameref is emulated by lwarp.

**for HTML output:** Discard all options for lwarp-nameref:

```
\PackageInfo{lwarp}{%
Using the lwarp HTML version of package ‘nameref’,\MessageBreak
and discarding options.\MessageBreak
(Not using \protect\ProvidesPackage, so that other packages\MessageBreak
do not attempt to patch lwarp’s version of ‘nameref’.)\MessageBreak
}
\DeclareOption*{}
\ProcessOptions\relax
```

File 314 **lwarp-natbib.sty**

§ 421 Package

# natbib

(*Emulates or patches code by* Patrick W. Daly.)

Pkg natbib natbib is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{natbib}[2010/09/13]
```

Replace math < and > with `\textless` and `\textgreater`:

A macro to compare:

```
\newcommand{\LWRNB@NAT@open}{$<$}
```

To patch `\NAT@open` and `\NAT@close`

```
\newcommand{\LWRNB@patchnatbibopenclose}{
\ifdefstrequal{\NAT@open}{\LWRNB@NAT@open}
{
    \renewcommand{\NAT@open}{\textless}
    \renewcommand{\NAT@close}{\textgreater}
}{}
}
```

Do it now in case `angle` was selected as an option:

```
\LWRNB@patchnatbibopenclose
```

Also patch `\setcitestyle` to patch after settings are made:

```
\let\LWRNB@origsetcitestyle\setcitestyle

\renewcommand{\setcitestyle}[1]{%
\LWRNB@origsetcitestyle{#1}%
\LWRNB@patchnatbibopenclose%
}
```

File 315 **lwarp-nccfancyhdr.sty**

## § 422 Package nccfancyhdr

(*Emulates or patches code by* Alexander I. Rozhenko.)

Pkg nccfancyhdr nccfancyhdr is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{nccfancyhdr}[2004/12/07]

\newcommand*{\headrulewidth}{}
\newcommand*{\footrulewidth}{}
\newcommand{\headstrutheight}{}
\newcommand{\footstrutheight}{}
\newcommand*{\headrule}{}
\newcommand*{\footrule}{}

\newdimen\headwidth
\newcommand*{\extendedheaders}{}
\newcommand*{\normalheaders}{}

\newcommand*{\fancyhead}[2][]{}
\newcommand*{\fancyfoot}[2][]{}
\newcommand*{\fancyhf}[2][]{}
\newcommand*{\fancypagestyle}[2]{}
\newcommand*{\lhead}[2][]{}
\newcommand*{\chead}[2][]{}
\newcommand*{\rhead}[2][]{}
\newcommand*{\lfoot}[2][]{}
\newcommand*{\cfoot}[2][]{}
\newcommand*{\rfoot}[2][]{}

\newcommand{\nouppercase}[1]{#1}

\NewDocumentCommand{\fancycenter}{o o m m m}{}

\NewDocumentCommand{\newpagestyle}{m o m}{}

\newcommand*{\iffloatpage}[2]{#2}
\newcommand*{\ifftopfloat}[2]{#2}
\newcommand*{\iffbotfloat}[2]{#2}
```

---

File 316 **lwarp-nccfoots.sty**

## § 423 Package nccfoots

(*Emulates or patches code by* Alexander I. Rozhenko.)

Pkg nccfoots nccfoots is used as-is, and emulated for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{nccfoots}[2005/02/03]
```

⚠ For MathJax. There is no way to test for an empty argument, so the mark is not automatically duplicated.

As of v0.86, MathJax v3 does not offer *, so the unstarred version is used here.

```
\CustomizeMathJax{\newcommand{\LWRnrnostar}[1][0.5ex]{\\[#1]}}
\CustomizeMathJax{\newcommand{\nr}{\ifstar\LWRnrnostar\LWRnrnostar}}

\CustomizeMathJax{\newcommand{\mrel}[1]{\begin{aligned}#1\end{aligned}}}
\CustomizeMathJax{\newcommand{\underrel}[2]{\underset{#2}{#1}}}
\CustomizeMathJax{\newcommand{\medmath}[1]{#1}}
\CustomizeMathJax{\newcommand{\medop}[1]{#1}}
\CustomizeMathJax{\newcommand{\medint}[1]{#1}}
\CustomizeMathJax{\newcommand{\medintcorr}[1]{#1}}
\CustomizeMathJax{\newcommand{\mfrac}[2]{\frac{#1}{#2}}}
\CustomizeMathJax{\newcommand{\mbinom}[2]{\binom{#1}{#2}}}
\CustomizeMathJax{\newenvironment{mmatrix}{\begin{matrix}}{\end{matrix}}}

\CustomizeMathJax{\newcommand{\displaybreak}[1][]{}}
```

\eq, \eqs, \eqalign are created by LaTeX, not MathJax.

```
\end{warpMathJax}
```

---

File 318 **lwarp-needspace.sty**

## § 425 Package needspace

(*Emulates or patches code by* Peter Wilson.)

Pkg needspace needspace is ignored.

**for HTML output:** Discard all options for lwarp-needspace:

```
\LWR@ProvidesPackageDrop{needspace}[2010/09/12]

\DeclareDocumentCommand{\needspace}{m}{}
\DeclareDocumentCommand{\Needspace}{s m}{}
```

---

File 319 **lwarp-newpxmath.sty**

## § 426 Package newpxmath

(*Emulates or patches code by* Michael Sharpe.)

Pkg newpxmath newpxmath is used as-is for SVG math, and is emulated for MathJax.

⚠ limitations The MathJax emulation ignores all package options, except slantedGreek is honored. The dedicated macros for upright and italic Greek do work correctly.

SVG math should appear the same as the printed output.

**for HTML output:** The MathJax code from newtxmath is used:

```
\LWR@ProvidesPackagePass{newpxmath}[2020/01/09]

\LWR@infoprocessingmathjax{newpxmath}

\LWR@origRequirePackage{lwarp-common-mathjax-newpxtxmath}

\LWR@origRequirePackage{lwarp-common-mathjax-letters}

\begin{warpMathJax}

%   * \marg{2: prefix} \marg{3: postfix} \marg{4: i/u: italic/upright}
\LWR@mathjax@addgreek@u@up*{}{up}
\LWR@mathjax@addgreek@u@up*{up}{}
\LWR@mathjax@addgreek@l@up{up}{}
\LWR@mathjax@addgreek@l@up{}{up}
\LWR@mathjax@addgreek@u@it*{}{it}
\LWR@mathjax@addgreek@l@it{}{it}
```

Optional slanted Greek:

```
\ifpx@slantedG
    \LWR@mathjax@addgreek@u@it*{}{}
\fi

\end{warpMathJax}
```

---

File 320 **lwarp-newtxmath.sty**

§ 427 Package

# newtxmath

(*Emulates or patches code by* Michael Sharpe.)

Pkg newtxmath newtxmath is used as-is for SVG math, and is emulated for MathJax.

⚠ limitations The MathJax emulation ignores all package options, except `slantedGreek` is honored, and except that bold italic Latin letters are not defined for MathJax if the option is not selected.

The dedicated macros for upright and italic Greek and bold italic Latin letters do work correctly.

SVG math should appear the same as the printed output.

**for HTML output:**

```
\LWR@ProvidesPackagePass{newtxmath}[2020/08/04]

\LWR@infoprocessingmathjax{newtxmath}

\LWR@origRequirePackage{lwarp-common-mathjax-newpxtxmath}

\LWR@origRequirePackage{lwarp-common-mathjax-letters}

\begin{warpMathJax}

```

```
%   * \marg{2: prefix} \marg{3: postfix} \marg{4: i/u: italic/upright}
\LWR@mathjax@addgreek@u@up*{}{up}
\LWR@mathjax@addgreek@u@up*{up}{}
\LWR@mathjax@addgreek@l@up{up}{}
\LWR@mathjax@addgreek@l@up{}{up}
\LWR@mathjax@addgreek@u@it*{}{it}
\LWR@mathjax@addgreek@l@it{}{it}

% only newtxmath, not newpxmath:
\LWR@mathjax@addgreek@u@it*{it}{}
\LWR@mathjax@addgreek@l@it{it}{}

% only newtxmath, not newpxmath:
\ifdef{\iftx@BI}{
    \iftx@BI
        \LWR@mathjax@addlatin@u@bfit{BI}
        \LWR@mathjax@addlatin@l@bfit{BI}
    \fi
}{}
```

Optional slanted Greek:

```
\iftx@slantedG
    \LWR@mathjax@addgreek@u@it*{}{}
\fi

\end{warpMathJax}
```

---

File 321 **lwarp-newtxsf.sty**

§ 428 Package

# newtxsf

(*Emulates or patches code by* Michael Sharpe.)

Pkg newtxsf newtxsf is used as-is for SVG math, and is emulated for MathJax.

⚠ limitations The MathJax emulation ignores all package options, except slantedGreek is honored. The dedicated macros for upright and italic Greek and bold italic Latin letters do work correctly.

SVG math should appear the same as the printed output.

**for HTML output:**

```
\LWR@ProvidesPackagePass{newtxsf}[2020/05/02]

\LWR@infoprocessingmathjax{newtxsf}

\LWR@origRequirePackage{lwarp-common-mathjax-newpxtxmath}

\LWR@origRequirePackage{lwarp-common-mathjax-letters}

\begin{warpMathJax}

%   * \marg{2: prefix} \marg{3: postfix} \marg{4: i/u: italic/upright}
```

```
\LWR@mathjax@addgreek@u@up*{}{up}
\LWR@mathjax@addgreek@u@up*{up}{}
\LWR@mathjax@addgreek@l@up{up}{}
\LWR@mathjax@addgreek@l@up{}{up}
\LWR@mathjax@addgreek@u@it*{}{it}
\LWR@mathjax@addgreek@l@it{}{it}

% only newtxmath, not newpxmath:
\LWR@mathjax@addgreek@u@it*{it}{}
\LWR@mathjax@addgreek@l@it{it}{}
%
% only newtxmath, not newpxmath:
\ifdef{\iftx@BI}{
    \iftx@BI
        \LWR@mathjax@addlatin@u@bfit{BI}
        \LWR@mathjax@addlatin@l@bfit{BI}
    \fi
}{}
```

Optional slanted Greek:

```
\iftx@slantedG
    \LWR@mathjax@addgreek@u@it*{}{}
\fi

\end{warpMathJax}
```

---

File 322 **lwarp-nextpage.sty**

## § 429 Package nextpage

(*Emulates or patches code by* Peter Wilson.)

Pkg nextpage nextpage is ignored.

**for HTML output:** Discard all options for lwarp-nextpage.

```
\LWR@ProvidesPackageDrop{nextpage}[2009/09/03]

\DeclareDocumentCommand{\cleartoevenpage}{o}{}
\DeclareDocumentCommand{\movetoevenpage}{o}{}
\DeclareDocumentCommand{\cleartooddpage}{o}{}
\DeclareDocumentCommand{\movetooddpage}{o}{}
```

---

File 323 **lwarp-nfssext-cfr.sty**

## § 430 Package nfssext-cfr

(*Emulates or patches code by* Clea F. Rees.)

Pkg nfssext-cfr nfssext-cfr is emulated in HTML, and used as-is in print output.

Results depend on the browser's font.

**for HTML output:**

```
\LWR@ProvidesPackagePass{nfssext-cfr}[2017/03/28]
```

Macros which are present in the lwarp core are commented out here.

```
\newrobustcmd{\LWR@HTML@lnstyle}{}
\newrobustcmd{\LWR@HTML@osstyle}{\LWR@HTML@scshape}
\newrobustcmd{\LWR@HTML@instyle}{}
\newrobustcmd{\LWR@HTML@sustyle}{}
\newrobustcmd{\LWR@HTML@swstyle}{}
\newrobustcmd{\LWR@HTML@pstyle}{}
\newrobustcmd{\LWR@HTML@tistyle}{}
\newrobustcmd{\LWR@HTML@ostyle}{\LWR@HTML@scshape}
\newrobustcmd{\LWR@HTML@postyle}{\LWR@HTML@scshape}
\newrobustcmd{\LWR@HTML@ltstyle}{}
\newrobustcmd{\LWR@HTML@ofstyle}{}
\newrobustcmd{\LWR@HTML@altstyle}{}
\newrobustcmd{\LWR@HTML@regstyle}{}
\newrobustcmd{\LWR@HTML@embossstyle}{}
\newrobustcmd{\LWR@HTML@ornamentalstyle}{}
\newrobustcmd{\LWR@HTML@qtstyle}{}
\newrobustcmd{\LWR@HTML@shstyle}{}
\newrobustcmd{\LWR@HTML@swashstyle}{}
\newrobustcmd{\LWR@HTML@tmstyle}{\renewcommand*{\LWR@f@family}{tt}}
\newrobustcmd{\LWR@HTML@tvstyle}{\renewcommand*{\LWR@f@family}{tt}}
\newrobustcmd{\LWR@HTML@tstyle}{}
\newrobustcmd{\LWR@HTML@lstyle}{}
\newrobustcmd{\LWR@HTML@tlstyle}{}
\newrobustcmd{\LWR@HTML@plstyle}{}
\newrobustcmd{\LWR@HTML@tostyle}{\LWR@HTML@scshape}
% \newrobustcmd{\LWR@HTML@sishape}{}
\newrobustcmd{\LWR@HTML@olshape}{}
\newrobustcmd{\LWR@HTML@scolshape}{}
\newrobustcmd{\LWR@HTML@ushape}{}
\newrobustcmd{\LWR@HTML@scushape}{}
\newrobustcmd{\LWR@HTML@uishape}{\LWR@HTML@itshape}
\newrobustcmd{\LWR@HTML@rishape}{}
\newrobustcmd{\LWR@HTML@regwidth}{}
\newrobustcmd{\LWR@HTML@nwwidth}{}
\newrobustcmd{\LWR@HTML@cdwidth}{}
\newrobustcmd{\LWR@HTML@ecwidth}{}
\newrobustcmd{\LWR@HTML@ucwidth}{}
\newrobustcmd{\LWR@HTML@etwidth}{}
\newrobustcmd{\LWR@HTML@epwidth}{}
\newrobustcmd{\LWR@HTML@exwidth}{}
\newrobustcmd{\LWR@HTML@uxwidth}{}
\newrobustcmd{\LWR@HTML@mbweight}{\renewcommand*{\LWR@f@series}{md}}
\newrobustcmd{\LWR@HTML@dbweight}{\renewcommand*{\LWR@f@series}{db}}
\newrobustcmd{\LWR@HTML@sbweight}{\renewcommand*{\LWR@f@series}{sb}}
% \newrobustcmd{\LWR@HTML@ebweight}{\renewcommand*{\LWR@f@series}{eb}}
\newrobustcmd{\LWR@HTML@ubweight}{\renewcommand*{\LWR@f@series}{ub}}
% \newrobustcmd{\LWR@HTML@lgweight}{\renewcommand*{\LWR@f@series}{lg}}
\newrobustcmd{\LWR@HTML@elweight}{\renewcommand*{\LWR@f@series}{el}}
\newrobustcmd{\LWR@HTML@ulweight}{\renewcommand*{\LWR@f@series}{ul}}
```

```
% \newrobustcmd{\LWR@HTML@itshape}{}
% \newrobustcmd{\LWR@HTML@scshape}{}
% \newrobustcmd{\LWR@HTML@upshape}{}
\newrobustcmd{\LWR@HTML@dfshape}{}

\ifdef{\LWR@HTML@swshape}{}{% duplicated by fontaxes
    \newrobustcmd{\LWR@HTML@swshape}{}
}

\newrobustcmd{\LWR@HTML@ornament}[1]{}

\LWR@formatted{lnstyle}
\LWR@formatted{osstyle}
\LWR@formatted{instyle}
\LWR@formatted{sustyle}
\LWR@formatted{swstyle}
\LWR@formatted{pstyle}
\LWR@formatted{tistyle}
\LWR@formatted{ostyle}
\LWR@formatted{postyle}
\LWR@formatted{ltstyle}
\LWR@formatted{ofstyle}
\LWR@formatted{altstyle}
\LWR@formatted{regstyle}
\LWR@formatted{embossstyle}
\LWR@formatted{ornamentalstyle}
\LWR@formatted{qtstyle}
\LWR@formatted{shstyle}
\LWR@formatted{swashstyle}
\LWR@formatted{tmstyle}
\LWR@formatted{tvstyle}
\LWR@formatted{tstyle}
\LWR@formatted{lstyle}
\LWR@formatted{tlstyle}
\LWR@formatted{plstyle}
\LWR@formatted{tostyle}
% \LWR@formatted{sishape}
\LWR@formatted{olshape}
\LWR@formatted{scolshape}
\LWR@formatted{ushape}
\LWR@formatted{scushape}
\LWR@formatted{uishape}
\LWR@formatted{rishape}
\LWR@formatted{regwidth}
\LWR@formatted{nwwidth}
\LWR@formatted{cdwidth}
\LWR@formatted{ecwidth}
\LWR@formatted{ucwidth}
\LWR@formatted{etwidth}
\LWR@formatted{epwidth}
\LWR@formatted{exwidth}
\LWR@formatted{uxwidth}
\LWR@formatted{mbweight}
\LWR@formatted{dbweight}
\LWR@formatted{sbweight}
```

```
% \LWR@formatted{ebweight}
\LWR@formatted{ubweight}
% \LWR@formatted{lgweight}
\LWR@formatted{elweight}
\LWR@formatted{ulweight}
\LWR@formatted{itshape}% adapt to the new print version
\LWR@formatted{scshape}% adapt to the new print version
\LWR@formatted{upshape}% adapt to the new print version
\LWR@formatted{dfshape}

\ifdef{\LWR@HTML@swshape}{}{% duplicated by fontaxes
    \LWR@formatted{swshape}
}

\LWR@formatted{ornament}


\FilenameNullify{%
    \LetLtxMacro\lnstyle\@empty%
    \LetLtxMacro\osstyle\@empty%
    \LetLtxMacro\instyle\@empty%
    \LetLtxMacro\sustyle\@empty%
    \LetLtxMacro\swstyle\@empty%
    \LetLtxMacro\pstyle\@empty%
    \LetLtxMacro\tistyle\@empty%
    \LetLtxMacro\ostyle\@empty%
    \LetLtxMacro\postyle\@empty%
    \LetLtxMacro\ltstyle\@empty%
    \LetLtxMacro\ofstyle\@empty%
    \LetLtxMacro\altstyle\@empty%
    \LetLtxMacro\regstyle\@empty%
    \LetLtxMacro\embossstyle\@empty%
    \LetLtxMacro\ornamentalstyle\@empty%
    \LetLtxMacro\qtstyle\@empty%
    \LetLtxMacro\shstyle\@empty%
    \LetLtxMacro\swashstyle\@empty%
    \LetLtxMacro\tmstyle\@empty%
    \LetLtxMacro\tvstyle\@empty%
    \LetLtxMacro\tstyle\@empty%
    \LetLtxMacro\lstyle\@empty%
    \LetLtxMacro\tlstyle\@empty%
    \LetLtxMacro\plstyle\@empty%
    \LetLtxMacro\tostyle\@empty%
%   \LetLtxMacro\sishape\@empty%
    \LetLtxMacro\olshape\@empty%
    \LetLtxMacro\scolshape\@empty%
    \LetLtxMacro\ushape\@empty%
    \LetLtxMacro\scushape\@empty%
    \LetLtxMacro\uishape\@empty%
    \LetLtxMacro\rishape\@empty%
    \LetLtxMacro\regwidth\@empty%
    \LetLtxMacro\nwwidth\@empty%
    \LetLtxMacro\cdwidth\@empty%
    \LetLtxMacro\ecwidth\@empty%
    \LetLtxMacro\ucwidth\@empty%
    \LetLtxMacro\etwidth\@empty%
```

```
    \LetLtxMacro\epwidth\@empty%
    \LetLtxMacro\exwidth\@empty%
    \LetLtxMacro\uxwidth\@empty%
    \LetLtxMacro\mbweight\@empty%
    \LetLtxMacro\dbweight\@empty%
    \LetLtxMacro\sbweight\@empty%
%   \LetLtxMacro\ebweight\@empty%
    \LetLtxMacro\ubweight\@empty%
%   \LetLtxMacro\lgweight\@empty%
    \LetLtxMacro\elweight\@empty%
    \LetLtxMacro\ulweight\@empty%
%   \LetLtxMacro\itshape\@empty%
%   \LetLtxMacro\scshape\@empty%
%   \LetLtxMacro\upshape\@empty%
    \LetLtxMacro\dfshape\@empty%
    \LetLtxMacro\swshape\@empty%
    \LetLtxMacro\ornament\@gobble%
}

\newrobustcmd{\LWR@HTML@textln}[1]{\InlineClass{textln}{#1}}
\newrobustcmd{\LWR@HTML@textos}[1]{\textsc{#1}}
\newrobustcmd{\LWR@HTML@textin}[1]{#1}
\newrobustcmd{\LWR@HTML@textsu}[1]{#1}
% \newrobustcmd{\LWR@HTML@textsi}[1]{#1}
\newrobustcmd{\LWR@HTML@textdf}[1]{#1}


\ifdef{\LWR@HTML@textsw}{}{% duplicated by fontaxes
    \newrobustcmd{\LWR@HTML@textsw}[1]{#1}
    \LWR@formatted{textsw}
}

\newrobustcmd{\LWR@HTML@textti}[1]{#1}
\newrobustcmd{\LWR@HTML@textlt}[1]{#1}
\newrobustcmd{\LWR@HTML@textof}[1]{#1}
\newrobustcmd{\LWR@HTML@textalt}[1]{#1}
\newrobustcmd{\LWR@HTML@textreg}[1]{#1}
\newrobustcmd{\LWR@HTML@emboss}[1]{#1}
\newrobustcmd{\LWR@HTML@textorn}[1]{#1}
\newrobustcmd{\LWR@HTML@textqt}[1]{#1}
\newrobustcmd{\LWR@HTML@textsh}[1]{#1}
\newrobustcmd{\LWR@HTML@texttm}[1]{\texttt{#1}}
\newrobustcmd{\LWR@HTML@texttv}[1]{\texttt{#1}}
\newrobustcmd{\LWR@HTML@textl}[1]{\InlineClass{textln}{#1}}
\newrobustcmd{\LWR@HTML@texto}[1]{\textsc{#1}}
\newrobustcmd{\LWR@HTML@textp}[1]{\InlineClass{textp}{#1}}
\newrobustcmd{\LWR@HTML@textt}[1]{\InlineClass{textt}{#1}}
\newrobustcmd{\LWR@HTML@textpl}[1]{#1}
\newrobustcmd{\LWR@HTML@textpo}[1]{\textsc{#1}}
\newrobustcmd{\LWR@HTML@texttl}[1]{\InlineClass{textln}{#1}}
\newrobustcmd{\LWR@HTML@textto}[1]{\textsc{#1}}
\newrobustcmd{\LWR@HTML@textol}[1]{#1}
\newrobustcmd{\LWR@HTML@textswash}[1]{#1}
\newrobustcmd{\LWR@HTML@textu}[1]{#1}
\newrobustcmd{\LWR@HTML@textscu}[1]{#1}
\newrobustcmd{\LWR@HTML@textui}[1]{\LWR@HTML@textit{#1}}
```

```
\newrobustcmd{\LWR@HTML@textri}[1]{#1}
\newrobustcmd{\LWR@HTML@textnw}[1]{#1}
\newrobustcmd{\LWR@HTML@textcd}[1]{#1}
\newrobustcmd{\LWR@HTML@textec}[1]{#1}
\newrobustcmd{\LWR@HTML@textuc}[1]{#1}
\newrobustcmd{\LWR@HTML@textet}[1]{#1}
\newrobustcmd{\LWR@HTML@textep}[1]{#1}
\newrobustcmd{\LWR@HTML@textex}[1]{#1}
\newrobustcmd{\LWR@HTML@textux}[1]{#1}
\newrobustcmd{\LWR@HTML@textrw}[1]{#1}
\newrobustcmd{\LWR@HTML@textmb}[1]{{\LWR@HTML@mbweight\InlineClass{textmb}{#1}}}
\newrobustcmd{\LWR@HTML@textdb}[1]{{\LWR@HTML@dbweight\InlineClass{textdb}{#1}}}
\newrobustcmd{\LWR@HTML@textsb}[1]{{\LWR@HTML@sbweight\InlineClass{textsb}{#1}}}
% \newrobustcmd{\LWR@HTML@texteb}[1]{#1}
\newrobustcmd{\LWR@HTML@textub}[1]{{\LWR@HTML@ubweight\InlineClass{textub}{#1}}}
% \newrobustcmd{\LWR@HTML@textlg}[1]{#1}
\newrobustcmd{\LWR@HTML@textel}[1]{{\LWR@HTML@elweight\InlineClass{textel}{#1}}}
\newrobustcmd{\LWR@HTML@textul}[1]{{\LWR@HTML@ulweight\InlineClass{textul}{#1}}}

\LWR@formatted{textln}
\LWR@formatted{textos}
\LWR@formatted{textin}
\LWR@formatted{textsu}
% \LWR@formatted{textsi}
\LWR@formatted{textdf}
\LWR@formatted{textti}
\LWR@formatted{textlt}
\LWR@formatted{textof}
\LWR@formatted{textalt}
\LWR@formatted{textreg}
\LWR@formatted{emboss}
\LWR@formatted{textorn}
\LWR@formatted{textqt}
\LWR@formatted{textsh}
\LWR@formatted{texttm}
\LWR@formatted{texttv}
\LWR@formatted{textl}
\LWR@formatted{texto}
\LWR@formatted{textp}
\LWR@formatted{textt}
\LWR@formatted{textpl}
\LWR@formatted{textpo}
\LWR@formatted{texttl}
\LWR@formatted{textto}
\LWR@formatted{textol}
\LWR@formatted{textswash}
\LWR@formatted{textu}
\LWR@formatted{textscu}
\LWR@formatted{textui}
\LWR@formatted{textri}
\LWR@formatted{textnw}
\LWR@formatted{textcd}
\LWR@formatted{textec}
\LWR@formatted{textuc}
\LWR@formatted{textet}
```

```
\LWR@formatted{textep}
\LWR@formatted{textex}
\LWR@formatted{textux}
\LWR@formatted{textrw}
\LWR@formatted{textmb}
\LWR@formatted{textdb}
\LWR@formatted{textsb}
% \LWR@formatted{texteb}
\LWR@formatted{textub}
% \LWR@formatted{textlg}
\LWR@formatted{textel}
\LWR@formatted{textul}


\FilenameNullify{%
    \LetLtxMacro\textln\@firstofone%
    \LetLtxMacro\textos\@firstofone%
    \LetLtxMacro\textin\@firstofone%
    \LetLtxMacro\textsu\@firstofone%
%   \LetLtxMacro\textsi\@firstofone%
    \LetLtxMacro\textdf\@firstofone%
    \LetLtxMacro\textsw\@firstofone%
    \LetLtxMacro\textti\@firstofone%
    \LetLtxMacro\textlt\@firstofone%
    \LetLtxMacro\textof\@firstofone%
    \LetLtxMacro\textalt\@firstofone%
    \LetLtxMacro\textreg\@firstofone%
    \LetLtxMacro\emboss\@firstofone%
    \LetLtxMacro\textorn\@firstofone%
    \LetLtxMacro\textqt\@firstofone%
    \LetLtxMacro\textsh\@firstofone%
    \LetLtxMacro\texttm\@firstofone%
    \LetLtxMacro\texttv\@firstofone%
    \LetLtxMacro\textl\@firstofone%
    \LetLtxMacro\texto\@firstofone%
    \LetLtxMacro\textp\@firstofone%
    \LetLtxMacro\textt\@firstofone%
    \LetLtxMacro\textpl\@firstofone%
    \LetLtxMacro\textpo\@firstofone%
    \LetLtxMacro\texttl\@firstofone%
    \LetLtxMacro\textto\@firstofone%
    \LetLtxMacro\textol\@firstofone%
    \LetLtxMacro\textswash\@firstofone%
    \LetLtxMacro\textu\@firstofone%
    \LetLtxMacro\textscu\@firstofone%
    \LetLtxMacro\textui\@firstofone%
    \LetLtxMacro\textri\@firstofone%
    \LetLtxMacro\textnw\@firstofone%
    \LetLtxMacro\textcd\@firstofone%
    \LetLtxMacro\textec\@firstofone%
    \LetLtxMacro\textuc\@firstofone%
    \LetLtxMacro\textet\@firstofone%
    \LetLtxMacro\textep\@firstofone%
    \LetLtxMacro\textex\@firstofone%
    \LetLtxMacro\textux\@firstofone%
```

File 325 **lwarp-niceframe.sty**

## § 432 Package niceframe

Pkg niceframe niceframe is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{niceframe}% the original date is in yyyy/dd/mm format

\newcommand{\LWR@niceframe}[3]{%
    \begin{LWR@setvirtualpage}*%
    \setlength{\LWR@templengthone}{#1}%
    \begin{BlockClass}[max-width:\LWR@printlength{\LWR@templengthone}]{#3}%
    #2
    \end{BlockClass}%
    \end{LWR@setvirtualpage}%
}

\newcommand{\niceframe}[2][\textwidth]{\LWR@niceframe{#1}{#2}{niceframe}}
\newcommand{\curlyframe}[2][\textwidth]{\LWR@niceframe{#1}{#2}{curlyframe}}
\newcommand{\artdecoframe}[2][\textwidth]{\LWR@niceframe{#1}{#2}{artdecoframe}}

\newcommand{\generalframe}[9]{\LWR@niceframe{\textwidth}{#9}{generalframe}}
```

File 326 **lwarp-nicematrix.sty**

## § 433 Package nicematrix

(*Emulates or patches code by* F. Pantigny.)

Pkg nicematrix nicematrix is used as-is for SVG math, and is emulated for MathJax.

⚠ MathJax Keys/values are ignored in MathJax. `\Cdots`, etc. do not span multiple cells. `AutoNiceMatrix`, etc. are not supported for MathJax. SVG math output preserves all nicematrix features. To force SVG output for one or more consecutive math expressions, for inline math use `\inlinemathother` and `\inlinemathnormal`, or for display math use `\displaymathother` and `\displaymathnormal`.

**for HTML output:**

```
\LWR@ProvidesPackagePass{nicematrix}[2020/11/23]
```

`NiceTabular` must be converted to SVG to support the various nicematrix options:

```
\begin{warpHTML}
\BeforeBeginEnvironment{NiceTabular}{%
    \begin{lateximage}[-nicematrix-~\PackageDiagramAltText]%
}
\AfterEndEnvironment{NiceTabular}{\end{lateximage}}
\BeforeBeginEnvironment{NiceTabular*}{%
    \begin{lateximage}[-nicematrix-~\PackageDiagramAltText]%
```

```
}
\AfterEndEnvironment{NiceTabular*}{\end{lateximage}}
\end{warpHTML}
```

Special handling for the optional arguments, and the lack of a delimiter:

```
\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\LWRnicearrayarray}[1]{\begin{array}{#1}}}
\CustomizeMathJax{\def\LWRnicearrayarrayopt#1[#2] {\begin{array}{#1}}}

\CustomizeMathJax{%
    \newenvironment{NiceArray}[2][]%
        {\ifnextchar[{\LWRnicearrayarrayopt{#2}}{\LWRnicearrayarray{#2}}}%
        {\end{array}}%
}

\CustomizeMathJax{%
    \newcommand{\LWRnicearraywithdelimtwo}[2][]{%
        \ifnextchar[{\LWRnicearrayarrayopt{#2}}{\LWRnicearrayarray{#2}}%
    }%
}
```

General case with left/right delimiters:

```
\CustomizeMathJax{%
    \newenvironment{NiceArrayWithDelims}[2]%
        {%
            \def\LWRnicearrayrightdelim{\right#2}%
            \left#1%
            \LWRnicearraywithdelimtwo%
        }%
        {\end{array}\LWRnicearrayrightdelim}%
}
```

Instances of specific delimiters:

```
\CustomizeMathJax{%
    \newenvironment{pNiceArray}
        {\begin{NiceArrayWithDelims}{(}{)}}
        {\end{NiceArrayWithDelims}}
}

\CustomizeMathJax{%
    \newenvironment{bNiceArray}
        {\begin{NiceArrayWithDelims}{[}{]}}
        {\end{NiceArrayWithDelims}}
}

\CustomizeMathJax{%
    \newenvironment{BNiceArray}
        {\begin{NiceArrayWithDelims}{\{}{\}}}
        {\end{NiceArrayWithDelims}}
}

\CustomizeMathJax{%
```

```
    \newenvironment{vNiceArray}
        {\begin{NiceArrayWithDelims}{\vert}{\vert}}
        {\end{NiceArrayWithDelims}}
}

\CustomizeMathJax{%
    \newenvironment{VNiceArray}
        {\begin{NiceArrayWithDelims}{\Vert}{\Vert}}
        {\end{NiceArrayWithDelims}}
}
```

Ignore optional arg and use standard environments:

```
\CustomizeMathJax{\newenvironment{NiceMatrix}[1][]{\begin{matrix}}{\end{matrix}}}
\CustomizeMathJax{\newenvironment{pNiceMatrix}[1][]{\begin{pmatrix}}{\end{pmatrix}}}
\CustomizeMathJax{\newenvironment{bNiceMatrix}[1][]{\begin{bmatrix}}{\end{bmatrix}}}
\CustomizeMathJax{\newenvironment{BNiceMatrix}[1][]{\begin{Bmatrix}}{\end{Bmatrix}}}
\CustomizeMathJax{\newenvironment{vNiceMatrix}[1][]{\begin{vmatrix}}{\end{vmatrix}}}
\CustomizeMathJax{\newenvironment{VNiceMatrix}[1][]{\begin{Vmatrix}}{\end{Vmatrix}}}
```

Ignore optional argument and size. Print contents.

```
\CustomizeMathJax{\newcommand{\LWRnicematrixBlock}[1]{#1}}
\CustomizeMathJax{\def\LWRnicematrixBlockopt<#1>#2{#2}}

\CustomizeMathJax{%
   \newcommand{\Block}[2][]{\ifnextchar<\LWRnicematrixBlockopt\LWRnicematrixBlock}%
}
```

Form an approximation:

```
\CustomizeMathJax{%
    \newcommand{\diagbox}[2]{%
        \begin{array}{l}\hfill\quad#2\\\hline#1\quad\hfill\end{array}%
    }%
}
```

More approximations:

```
\CustomizeMathJax{\let\hdottedline\hdashline}

\CustomizeMathJax{\newcommand{\ldots}[1][]{\dots}}
\CustomizeMathJax{\newcommand{\Cdots}[1][]{\cdots}}
\CustomizeMathJax{\newcommand{\Vdots}[1][]{\vdots}}
\CustomizeMathJax{\newcommand{\Ddots}[1][]{\ddots}}
\CustomizeMathJax{\newcommand{\Iddots}[1][]{\mathinner{\unicode{x22F0}}}}

\CustomizeMathJax{\newcommand{\Hdotsfor}[1]{\ldots}}
\CustomizeMathJax{\newcommand{\Vdotsfor}[1]{\vdots}}
```

There is no way to emulate `AutoNiceMatrix` in MathJax.

```
\CustomizeMathJax{\newcommand{\AutoNiceMatrix}[2]{\text{(AutoNiceMatrix #1)}}}
\CustomizeMathJax{\let\pAutoNiceMatrix\AutoNiceMatrix}
\CustomizeMathJax{\let\bAutoNiceMatrix\AutoNiceMatrix}
```

```
\CustomizeMathJax{\let\BAutoNiceMatrix\AutoNiceMatrix}
\CustomizeMathJax{\let\vAutoNiceMatrix\AutoNiceMatrix}
\CustomizeMathJax{\let\VAutoNiceMatrix\AutoNiceMatrix}
\end{warpMathJax}
```

---

File 327 **lwarp-noitcrul.sty**

## § 434 Package noitcrul

(*Emulates or patches code by* Paul Ebermann.)

Pkg noitcrul noitcrul is used as-is for SVG and emulated for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{noitcrul}[2006/04/11]
```

```
\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\noitUnderline}[1]{\underline{#1}\!}}
\end{warpMathJax}
```

---

File 328 **lwarp-nolbreaks.sty**

## § 435 Package nolbreaks

(*Emulates or patches code by* Donald Arseneau.)

Pkg nolbreaks nolbreaks is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{nolbreaks}[2012/05/31]
```

```
\NewDocumentCommand{\nolbreaks}{s m}{\InlineClass{nolbreaks}{#2}}
```

---

File 329 **lwarp-nomencl.sty**

## § 436 Package nomencl

(*Emulates or patches code by* Boris Veytsman, Bernd Schandl, Lee Netherton, CV Radhakrishnan.)

Pkg nomencl nomencl is patched for use by lwarp.

To process the HTML nomenclature:

```
makeindex <project>_html.nlo -s nomencl.ist -o <project>_html.nls
```

**for HTML output:**

```
\LWR@ProvidesPackagePass{nomencl}[2005/09/22]
```

\BaseJobname is added to the label in case xr or xr-hyper are used.

```
\def\@@@nomenclature[#1]#2#3{%
```

```
\def\@tempa{#2}\def\@tempb{#3}%
\protected@write\@nomenclaturefile{}%
 {\string\nomenclatureentry{#1\nom@verb\@tempa @[{\nom@verb\@tempa}]%
     \begingroup\nom@verb\@tempb\protect\nomeqref{\theequation}%
       |nompageref}{\theLWR@previousautopagelabel}}%   lwarp
\endgroup
\@esphack}

\renewcommand*{\pagedeclaration}[1]{, \nameref{\BaseJobname-autopage-#1}}%
```

File 330 **lwarp-nonfloat.sty**

## § 437 Package nonfloat

(*Emulates or patches code by* Kai Rascher.)

Pkg nonfloat nonfloat is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{nonfloat}[1999/07/05]

\LetLtxMacro\topcaption\caption
\newcommand{\figcaption}{\def\@captype{figure}\caption}
\newcommand{\tabcaption}{\def\@captype{table}\topcaption}
\newenvironment{narrow}[2]{}{}
```

File 331 **lwarp-nonumonpart.sty**

## § 438 Package nonumonpart

Pkg nonumonpart nonumonpart is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{nonumonpart}[2011/04/15]
```

File 332 **lwarp-nopageno.sty**

## § 439 Package nopageno

Pkg nopageno nopageno is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{nopageno}[1989/01/01]
```

File 333 **lwarp-notes.sty**

## § 440 Package notes

Pkg notes notes is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{notes}[2002/10/29]

\newcommand*{\LWR@notes@onenote}[2]{%
\newenvironment{#1}
    {
        \BlockClass{notes#1}
        \begin{BlockClass}{notesicon}\textcircled{~#2~}\end{BlockClass}
        \BlockClass{notescontents}
    }
    {\endBlockClass\endBlockClass}
}

\LWR@notes@onenote{importantnote}{!}

\LWR@notes@onenote{warningnote}{--}

\LWR@notes@onenote{informationnote}{i}
```

File 334 **lwarp-notespages.sty**

## § 441 Package notespages

Pkg notespages notespages is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{notespages}[2016/08/21]

\newcommand*{\npnotesname}{}
\newcommand*{\npnotestext}{}
\newcommand*{\remainingtextheight}{}
\newdimen\remainingtextheight
\newcommand*{\notestitletext}{}
\newcommand*{\notesareatext}{}
\newcommand*{\npnpinfo}[1]{}
\newcommand*{\tracingnpmarks}{}
\newcommand*{\notespage}[1][]{}
\newcommand*{\notespages}[1][]{}
\newcommand*{\notesfill}[1][]{}
\newcommand*{\setnotespages}[1]{}
\newcommand*{\definenotesoption}[2]{}
\newcommand{\definenotesstyle}[2]{}
\newcommand{\definetitlestyle}[2]{}
\newcommand{\nppatchchapter}[1]{}
\newcommand{\npunpatchchapter}{}
```

File 335 **lwarp-nowidow.sty**

## § 442 Package nowidow

(*Emulates or patches code by* Raphaël Pinson.)

Pkg nowidow nowidow is ignored.

for HTML output: Discarding options for lwarp-nowidow.sty[2011/09/20]

\nowidow [⟨lines⟩]

\setnowidow [⟨lines⟩]

```
\newcommand*{\nowidow}[1][]{}
\newcommand*{\setnowidow}[1][]{}
```

\noclub [⟨lines⟩]

\setnoclub [⟨lines⟩]

```
\newcommand*{\noclub}[1][]{}
\newcommand*{\setnoclub}[1][]{}
```

File 336 **lwarp-ntheorem.sty**

## § 443 Package ntheorem

(*Emulates or patches code by* Wolfgang May, Andreas Schedler.)

Pkg ntheorem ntheorem is patched for use by lwarp.

Table 18: Ntheorem package — css styling of theorems and proofs

**Theorem:**  of class theorembody<theoremstyle>

**Theorem Header:**  of class theoremheader<style>

where <theoremstyle> is plain, break, etc.

### § 443.1 Limitations

⚠ Font control This conversion is not total. Font control is via css, and the custom LaTeX font settings are ignored.

⚠ cref reference format undefined If the print version does not use cleveref, place all \theoremstyle and \newtheorem declarations in the preamble inside \AtBeginDocument.[19] For some theorems, it may also be required to add inside \AtBeginDocument something such as:

[19] lwarp uses cleveref for the HTML conversion, and loads cleveref \AtEndPreamble, just before \AtBeginDocument.

```
\AtBeginDocument{ % if not using cleveref package
  \theoremstyle{definition}
  \newtheorem{dtheorem}{Definition}
  . . .
  \usepackage{etoolbox} % for \ifdef
  \ifdef{\cref}{
    \crefname{Proof}{Proof}{Proofs}
  }{}
}
```

⚠ Equation numbering

ntheorem has a bug with equation numbering in $\mathcal{AMS}$ environments when the option `thref` is used. lwarp does not share this bug, so equations with `\split`, etc, are numbered correctly with lwarp's HTML output, but not with the print output. It is recommended to use cleveref instead of ntheorem's `thref` option.

§ 443.2

## Options

Options `amsthm` or `standard` choose which set of theorems and proofs to initialize.

⚠ Disabled options

The options `thmmarks` and `amsmath` are disabled, since they heavily modify the underlying math code. Theorem marks are emulated. The AMS-math modifications are not done.

Option `thref` is disabled because cleveref functions are used instead. `\thref` is emulated.

Option `hyperref` is disabled because lwarp emulated hyperref.

**for HTML output:**

Some disabled options:

```
\DeclareOption{thref}{
    \AtEndDocument{
        \PackageWarningNoLine{lwarp}{%
            Lwarp uses cleveref, which takes over ntheorem's\MessageBreak
            referencing, including
                \protect\label \space and \protect\thref.\MessageBreak
            Cleveref does not accept ntheorem's optional\MessageBreak
            argument for \protect\label, so it will appear\MessageBreak
            in the text.  It is recommended to remove the\MessageBreak
            thref option, \protect\usepackage{cleveref} instead,\MessageBreak
            and remove any trailing optional arguments for \protect\label%
        }%
    }
}


\newbool{LWR@ntheoremmarks}
\boolfalse{LWR@ntheoremmarks}

\DeclareOption{thmmarks}{
\booltrue{LWR@ntheoremmarks}
\newif\ifsetendmark\setendmarktrue
}


\newbool{LWR@ntheoremamsthm}
\boolfalse{LWR@ntheoremamsthm}

```

```
\DeclareOption{amsthm}{\booltrue{LWR@ntheoremamsthm}}


\DeclareOption{amsmath}{}
\DeclareOption{hyperref}{}

\LWR@ProvidesPackagePass{ntheorem}[2011/08/15]
```

## § 443.3 Remembering the theorem style

Storage for the style being used for new theorems.

```
\newcommand{\LWR@newtheoremstyle}{plain}

\AtBeginDocument{
\@ifpackageloaded{cleveref}{
\gdef\@thm#1#2#3{%
   \if@thmmarks
     \stepcounter{end\InTheoType ctr}%
   \fi
   \renewcommand{\InTheoType}{#1}%
   \if@thmmarks
     \stepcounter{curr#1ctr}%
     \setcounter{end#1ctr}{0}%
   \fi
   \refstepcounter[#1]{#2}%  <<< cleveref modification
   \theorem@prework
    \LWR@forcenewpage% lwarp
    \BlockClass{theorembody#1}%\LWR@thisthmstyle% lwarp
   \trivlist % latex's \trivlist, calling latex's \@trivlist unchanged
   \ifuse@newframeskips  % cf. latex.ltx for topsepadd: \@trivlist
     \ifthm@inframe
       \thm@topsep\theoreminframepreskipamount
       \thm@topsepadd\theoreminframepostskipamount
      \else
       \thm@topsep\theorempreskipamount
       \thm@topsepadd\theorempostskipamount
      \fi
    \else% oldframeskips
      \thm@topsep\theorempreskipamount
      \thm@topsepadd \theorempostskipamount
      \ifvmode\advance\thm@topsepadd\partopsep\fi
   \fi
   \@topsep\thm@topsep
   \@topsepadd\thm@topsepadd
   \advance\linewidth -\theorem@indent
   \advance\linewidth -\theorem@rightindent
   \advance\@totalleftmargin \theorem@indent
   \parshape \@ne \@totalleftmargin \linewidth
   \@ifnextchar[{\@ythm{#1}{#2}{#3}}{\@xthm{#1}{#2}{#3}}
}
}{% not @ifpackageloaded{cleveref}
\gdef\@thm#1#2#3{%
   \if@thmmarks
     \stepcounter{end\InTheoType ctr}%
```

```
   \fi
   \renewcommand{\InTheoType}{#1}%
   \if@thmmarks
     \stepcounter{curr#1ctr}%
     \setcounter{end#1ctr}{0}%
   \fi
   \refstepcounter{#2}%
   \theorem@prework
    \LWR@forcenewpage% lwarp
    \BlockClass{theorembody#1}%\LWR@thisthmstyle% lwarp
   \trivlist % latex's \trivlist, calling latex's \@trivlist unchanged
   \ifuse@newframeskips  % cf. latex.ltx for topsepadd: \@trivlist
     \ifthm@inframe
       \thm@topsep\theoreminframepreskipamount
       \thm@topsepadd\theoreminframepostskipamount
      \else
       \thm@topsep\theorempreskipamount
       \thm@topsepadd\theorempostskipamount
      \fi
    \else% oldframeskips
      \thm@topsep\theorempreskipamount
      \thm@topsepadd \theorempostskipamount
      \ifvmode\advance\thm@topsepadd\partopsep\fi
   \fi
   \@topsep\thm@topsep
   \@topsepadd\thm@topsepadd
   \advance\linewidth -\theorem@indent
   \advance\linewidth -\theorem@rightindent
   \advance\@totalleftmargin \theorem@indent
   \parshape \@ne \@totalleftmargin \linewidth
   \@ifnextchar[{\@ythm{#1}{#2}{#3}}{\@xthm{#1}{#2}{#3}}
}
}
}% AtBeginDocument
```

Patched to remember the style being used for new theorems:

```
\gdef\theoremstyle#1{%
   \@ifundefined{th@#1}{\@warning
          {Unknown theoremstyle `#1'. Using `plain'}%
          \theorem@style{plain}
            \renewcommand{\LWR@newtheoremstyle}{plain}% lwarp
            }%
     {
       \theorem@style{#1}
       \renewcommand{\LWR@newtheoremstyle}{#1}% lwarp
       }
}
```

Patched to remember the style for this theorem type, and set it later when the environment is started.

```

\gdef\@xnthm#1#2[#3]{%
  \ifthm@tempif
```

```
    \csedef{LWR@thmstyle#1}{\LWR@newtheoremstyle}% lwarp
    \expandafter\@ifundefined{c@#1}%
       {\@definecounter{#1}}{}%
    \@newctr{#1}[#3]%
    \expandafter\xdef\csname the#1\endcsname{%
      \expandafter\noexpand\csname the#3\endcsname \@thmcountersep
         {\noexpand\csname\the\theoremnumbering\endcsname{#1}}}%
    \expandafter\gdef\csname mkheader@#1\endcsname
      {\csname setparms@#1\endcsname
       \@thm{#1}{#1}{#2}
       }%
    \global\@namedef{end#1}{\@endtheorem}
   \AtBeginEnvironment{#1}{\edef\LWR@thisthmstyle{\@nameuse{LWR@thmstyle#1}}}% lwarp
  \fi
}

\gdef\@ynthm#1#2{%
  \ifthm@tempif
    \csedef{LWR@thmstyle#1}{\LWR@newtheoremstyle}% lwarp
    \expandafter\@ifundefined{c@#1}%
       {\@definecounter{#1}}{}%
    \expandafter\xdef\csname the#1\endcsname
       {\noexpand\csname\the\theoremnumbering\endcsname{#1}}%
    \expandafter\gdef\csname mkheader@#1\endcsname
      {\csname setparms@#1\endcsname
       \@thm{#1}{#1}{#2}
       }%
    \global\@namedef{end#1}{\@endtheorem}
   \AtBeginEnvironment{#1}{\edef\LWR@thisthmstyle{\@nameuse{LWR@thmstyle#1}}}% lwarp
  \fi
}

\gdef\@othm#1[#2]#3{%
  \@ifundefined{c@#2}{\@nocounterr{#2}}%
   {\ifthm@tempif
    \csedef{LWR@thmstyle#1}{\LWR@newtheoremstyle}% lwarp
    \global\@namedef{the#1}{\@nameuse{the#2}}%
    \expandafter\protected@xdef\csname num@addtheoremline#1\endcsname{%
             \noexpand\@num@addtheoremline{#1}{#3}}%
    \expandafter\protected@xdef\csname nonum@addtheoremline#1\endcsname{%
             \noexpand\@nonum@addtheoremline{#1}{#3}}%
   \theoremkeyword{#3}%
   \expandafter\protected@xdef\csname #1Keyword\endcsname
            {\the\theoremkeyword}%
    \expandafter\gdef\csname mkheader@#1\endcsname
      {\csname setparms@#1\endcsname
               \@thm{#1}{#2}{#3}
       }%
    \global\@namedef{end#1}{\@endtheorem}
   \AtBeginEnvironment{#1}{\edef\LWR@thisthmstyle{\@nameuse{LWR@thmstyle#1}}}% lwarp
  \fi}
}
```

## § 443.4 HTML cross-referencing

Mimics a float by incrementing the float counter and generating an HTML anchor. These are used for list-of-theorem cross-references.

```
\newcommand{\LWR@inctheorem}{%
\addtocounter{LWR@thisautoid}{1}%
\LWR@stoppars%
\LWR@htmltag{%
  a id=\textquotedbl\LWR@print@mbox{autoid-\arabic{LWR@thisautoid}}\textquotedbl%
}%
\LWR@htmltag{/a}%
\LWR@startpars%
}
```

## § 443.5 \newtheoremstyle

The following are patched for CSS.

These were in individual files `thp.sty` for plain, `thmb.sty` for margin break, etc. They are gathered together here.

Each theorem is encased in a `BlockClass` environment of class `theorembody<style>`.

Each header is encased in an `\InlineClass` of class `theoremheader<style>`.

```
\gdef\newtheoremstyle#1#2#3{%
  \expandafter\@ifundefined{th@#1}%
   {\expandafter\gdef\csname th@#1\endcsname{%
    \def\@begintheorem####1####2{%
    \LWR@inctheorem% lwarp
    #2}%
    \def\@opargbegintheorem####1####2####3{%
    \LWR@inctheorem% lwarp
    #3}%
}%
}%
{\PackageError{\basename}{Theorem style #1 already defined}\@eha}
}
```

## § 443.6 Standard styles

```
\renewtheoremstyle{plain}%
  {\item[
    \InlineClass{theoremheaderplain}{##1\ ##2\theorem@separator}]}%
  {\item[
    \InlineClass{theoremheaderplain}{##1\ ##2\ (##3)\theorem@separator}]}

\renewtheoremstyle{break}%
  {\item[
    \InlineClass{theoremheaderbreak}{##1\ ##2\theorem@separator}\newline
    ]}%
  {\item[
    \InlineClass{theoremheaderbreak}%
        {##1\ ##2\ (##3)\theorem@separator}\newline
    ]}
```

```
214
215 \renewtheoremstyle{change}%
216   {\item[
217     \InlineClass{theoremheaderchange}{##2\ ##1\theorem@separator}]}%
218   {\item[
219     \InlineClass{theoremheaderchange}{##2\ ##1\ (##3)\theorem@separator}]}
220
221 \renewtheoremstyle{changebreak}%
222   {\item[
223         \InlineClass{theoremheaderchangebreak}%
224             {##2\ ##1\theorem@separator}\newline
225     ]}%
226   {\item[
227         \InlineClass{theoremheaderchangebreak}%
228             {##2\ ##1\ (##3)\theorem@separator}\newline
229     ]}
230
231 \renewtheoremstyle{margin}%
232   {\item[
233         \InlineClass{theoremheadermargin}{##2 \qquad ##1\theorem@separator}
234     ]}%
235   {\item[
236       \InlineClass{theoremheadermargin}{##2 \qquad ##1\ (##3)\theorem@separator}
237     ]}
238
239 \renewtheoremstyle{marginbreak}%
240   {\item[
241     \InlineClass{theoremheadermarginbreak}%
242         {##2 \qquad ##1\theorem@separator}\newline
243     ]}%
244   {\item[
245     \InlineClass{theoremheadermarginbreak}%
246         {##2 \qquad ##1\ (##3)\theorem@separator}\newline
247     ]}
248
249 \renewtheoremstyle{nonumberplain}%
250   {\item[
251     \InlineClass{theoremheaderplain}{##1\theorem@separator}]}%
252   {\item[
253     \InlineClass{theoremheaderplain}{##1\ (##3)\theorem@separator}]}
254
255 \renewtheoremstyle{nonumberbreak}%
256   {\item[
257     \InlineClass{theoremheaderbreak}{##1\theorem@separator}\newline
258     ]}%
259   {\item[
260     \InlineClass{theoremheaderbreak}{##1\ (##3)\theorem@separator}\newline
261     ]}
262
263 \renewtheoremstyle{empty}%
264   {\item[]}%
265   {\item[
266     \InlineClass{theoremheaderplain}{##3}]}
267
268 \renewtheoremstyle{emptybreak}%
```

```
  {\item[]}%
  {\item[
    \InlineClass{theoremheaderplain}{##3}] \ \newline}
```

## § 443.7 Additional objects

The following manually adjust the CSS for the standard configuration objects which are not a purely plain style:

```
\ifbool{LWR@ntheoremamsthm}{}{%
```

Upright text via CSS:

```
    \newtheoremstyle{plainupright}%
    {\item[
        \InlineClass{theoremheaderplain}{##1\ ##2\theorem@separator}]}%
    {\item[
        \InlineClass{theoremheaderplain}{##1\ ##2\ (##3)\theorem@separator}]}
```

Upright text and small caps header via CSS:

```
    \newtheoremstyle{nonumberplainuprightsc}%
    {\item[
        \InlineClass{theoremheadersc}{##1\theorem@separator}]}%
    {\item[
        \InlineClass{theoremheadersc}{##1\ (##3)\theorem@separator}]}
}% not amsthm
```

## § 443.8 Renewed standard configuration

The following standard configuration is renewed using the new CSS:

```
\ifbool{LWR@ntheoremamsthm}{}{%
```

```
\ifx\thm@usestd\@undefined
\else
    \theoremnumbering{arabic}
    \theoremstyle{plain}
    \RequirePackage{latexsym}
    \theoremsymbol{\Box}
    \theorembodyfont{\itshape}
    \theoremheaderfont{\normalfont\bfseries}
    \theoremseparator{}
    \renewtheorem{Theorem}{Theorem}
    \renewtheorem{theorem}{Theorem}
    \renewtheorem{Satz}{Satz}
    \renewtheorem{satz}{Satz}
    \renewtheorem{Proposition}{Proposition}
    \renewtheorem{proposition}{Proposition}
    \renewtheorem{Lemma}{Lemma}
    \renewtheorem{lemma}{Lemma}
    \renewtheorem{Korollar}{Korollar}
    \renewtheorem{korollar}{Korollar}
    \renewtheorem{Corollary}{Corollary}
```

```
    \renewtheorem{corollary}{Corollary}

    \theoremstyle{plainupright}
    \theorembodyfont{\upshape}
    \theoremsymbol{\HTMLunicode{25A1}}% UTF-8 white box
    \renewtheorem{Example}{Example}
    \renewtheorem{example}{Example}
    \renewtheorem{Beispiel}{Beispiel}
    \renewtheorem{beispiel}{Beispiel}
    \renewtheorem{Bemerkung}{Bemerkung}
    \renewtheorem{bemerkung}{Bemerkung}
    \renewtheorem{Anmerkung}{Anmerkung}
    \renewtheorem{anmerkung}{Anmerkung}
    \renewtheorem{Remark}{Remark}
    \renewtheorem{remark}{Remark}
    \renewtheorem{Definition}{Definition}
    \renewtheorem{definition}{Definition}

    \theoremstyle{nonumberplainuprightsc}
    \theoremsymbol{\HTMLunicode{220E}}% UTF-8 end-of-proof
    \renewtheorem{Proof}{Proof}
    \renewtheorem{proof}{Proof}
    \renewtheorem{Beweis}{Beweis}
    \renewtheorem{beweis}{Beweis}
    \qedsymbol{\HTMLunicode{220E}}% UTF-8 end-of-proof

    \theoremsymbol{}
\fi
}% not amsthm
```

## § 443.9 amsthm **option**

Only if the amsthm option was given:

```
\ifbool{LWR@ntheoremamsthm}{

\gdef\th@plain{%
  \def\theorem@headerfont{\normalfont\bfseries}\itshape%
  \def\@begintheorem##1##2{%
        \LWR@inctheorem% lwarp
      \item[
  \InlineClass{theoremheaderplain}{##1\ ##2.}
        ]}%
  \def\@opargbegintheorem##1##2##3{%
        \LWR@inctheorem% lwarp
     \item[
  \InlineClass{theoremheaderplain}{##1\ ##2\ (##3).}
        ]}}

\gdef\th@nonumberplain{%
  \def\theorem@headerfont{\normalfont\bfseries}\itshape%
  \def\@begintheorem##1##2{%
        \LWR@inctheorem% lwarp
      \item[
  \InlineClass{theoremheaderplain}{##1.}
```

```
        ]}%
  \def\@opargbegintheorem##1##2##3{%
        \LWR@inctheorem% lwarp
     \item[
  \InlineClass{theoremheaderplain}{##1\ (##3).}
        ]}}

\gdef\th@definition{%
  \def\theorem@headerfont{\normalfont\bfseries}\normalfont%
  \def\@begintheorem##1##2{%
        \LWR@inctheorem% lwarp
      \item[
  \InlineClass{theoremheaderdefinition}{##1\ ##2.}
        ]}%
  \def\@opargbegintheorem##1##2##3{%
        \LWR@inctheorem% lwarp
     \item[
  \InlineClass{theoremheaderdefinition}{##1\ ##2\ (##3).}
        ]}}

\gdef\th@nonumberdefinition{%
  \def\theorem@headerfont{\normalfont\bfseries}\normalfont%
  \def\@begintheorem##1##2{%
        \LWR@inctheorem% lwarp
      \item[
  \InlineClass{theoremheaderdefinition}{##1.}
        ]}%
  \def\@opargbegintheorem##1##2##3{%
        \LWR@inctheorem% lwarp
     \item[
  \InlineClass{theoremheaderdefinition}{##1\ (##3).}
        ]}}

\gdef\th@remark{%
  \def\theorem@headerfont{\itshape}\normalfont%
  \def\@begintheorem##1##2{%
        \LWR@inctheorem% lwarp
      \item[
  \InlineClass{theoremheaderremark}{##1\ ##2.}
        ]}%
  \def\@opargbegintheorem##1##2##3{%
        \LWR@inctheorem% lwarp
     \item[
  \InlineClass{theoremheaderremark}{##1\ ##2\ (##3).}
        ]}}

\gdef\th@nonumberremark{%
  \def\theorem@headerfont{\itshape}\normalfont%
  \def\@begintheorem##1##2{%
        \LWR@inctheorem% lwarp
      \item[
  \InlineClass{theoremheaderremark}{##1.}
        ]}%
  \def\@opargbegintheorem##1##2##3{%
        \LWR@inctheorem% lwarp
```

```
    \item[
  \InlineClass{theoremheaderremark}{##1\ (##3).}
        ]}}

\gdef\th@proof{%
  \def\theorem@headerfont{\normalfont\bfseries}\itshape%
  \def\@begintheorem##1##2{%
        \LWR@inctheorem% lwarp
      \item[
  \InlineClass{theoremheaderproof}{##1.}
        ]}%
  \def\@opargbegintheorem##1##2##3{%
        \LWR@inctheorem% lwarp
     \item[
  \InlineClass{theoremheaderproof}{##1\ (##3).}
        ]}}



\newcounter{proof}%
\if@thmmarks
    \newcounter{currproofctr}%
    \newcounter{endproofctr}%
\fi

\gdef\proofSymbol{\openbox}

\newcommand{\proofname}{Proof}

\newenvironment{proof}[1][\proofname]{
    \th@proof
    \def\theorem@headerfont{\itshape}%
    \normalfont
    \theoremsymbol{\HTMLunicode{220E}}% UTF-8 end-of-proof
    \@thm{proof}{proof}{#1}
}%
{\@endtheorem}

}{}% amsthm option
```

## § 443.10 Ending a theorem

Patched for css:

```
\let\LWR@origendtheorem\@endtheorem
\renewcommand{\@endtheorem}{%
\ifbool{LWR@ntheoremmarks}{%
    \ifsetendmark%
    \InlineClass{theoremendmark}{\csname\InTheoType Symbol\endcsname}%
    \setendmarkfalse%
    \fi%
}{}%
\LWR@origendtheorem% also does \@endtrivlist
\ifbool{LWR@ntheoremmarks}{\global\setendmarktrue}{}%
\endBlockClass%
}
```

## § 443.11 \NoEndMark

```
\gdef\NoEndMark{\global\setendmarkfalse}
```

## § 443.12 List-of

Redefined to reuse the float mechanism to add list-of-theorem links:

`\thm@thmline` {⟨*1: printed type*⟩} {⟨*2: #*⟩} {⟨*3: optional*⟩} {⟨*4: page*⟩}

```
\renewcommand{\thm@@thmline@noname}[4]{%
\hypertocfloat{1}{theorem}{thm}{#2 #3}{}%
}

\renewcommand{\thm@@thmline@name}[4]{%
\hypertocfloat{1}{theorem}{thm}{#1 #2 #3}{}%
}
```

This was redefined by ntheorem when loaded, so it is now redefined for lwarp:

```
\def\thm@@thmline{\thm@@thmline@name}
```

Patch for css:

```
\def\listtheorems#1{
\LWR@htmlelementclass{nav}{lothm}%
\begingroup
\c@tocdepth=-2%
\def\thm@list{#1}\thm@processlist
\endgroup
\LWR@htmlelementclassend{nav}{lothm}%
}
```

## § 443.13 Symbols

Proof QED symbol:

```
\newcommand{\qed}{\qquad\the\qedsymbol}

\AtBeginDocument{
\@ifundefined{LWR@orig@openbox}{
\LetLtxMacro\LWR@orig@openbox\openbox
\LetLtxMacro\LWR@orig@blacksquare\blacksquare
\LetLtxMacro\LWR@orig@Box\Box

\def\openbox{\text{\HTMLunicode{25A1}}}% UTF-8 white box
\def\blacksquare{\text{\HTMLunicode{220E}}}% UTF-8 end-of-proof
\def\Box{\text{\HTMLunicode{25A1}}}% UTF-8 white box

\appto\LWR@restoreorigformatting{%
\LetLtxMacro\openbox\LWR@orig@openbox%
\LetLtxMacro\blacksquare\LWR@orig@blacksquare%
\LetLtxMacro\Box\LWR@orig@Box%
}% appto
}{}% @ifundefined
}% AtBeginDocument
```

## § 443.14 Cross-referencing

```
}
```

The original was hard to adapt to lwarp's handling of &.

```
\StartDefiningTabulars
\renewcommand{\octavetable}{%
\begin{tabular}{ll}
\octaveprimes \pitch{C}{0} & \octavenumbers \pitch{C}{0} \\
\octaveprimes \pitch{C}{1} & \octavenumbers \pitch{C}{1} \\
\octaveprimes \pitch{C}{2} & \octavenumbers \pitch{C}{2} \\
\octaveprimes \pitch{C}{3} & \octavenumbers \pitch{C}{3} \\
\octaveprimes \pitch{C}{4} & \octavenumbers \pitch{C}{4} \\
\octaveprimes \pitch{C}{5} & \octavenumbers \pitch{C}{5} \\
\octaveprimes \pitch{C}{6} & \octavenumbers \pitch{C}{6} \\
\octaveprimes \pitch{C}{7} & \octavenumbers \pitch{C}{7} \\
\end{tabular}
}
\StopDefiningTabulars
```

---

File 338 **lwarp-overpic.sty**

# § 445 Package overpic

(*Emulates or patches code by* Rolf Niepraschk.)

Pkg overpic overpic is patched for use by lwarp.

⚠ scaling The macros \overpicfontsize and \overpicfontskip are used during HTML generation. These are sent to \fontsize to adjust the font size for scaling differences between the print and HTML versions of the document. Renew these macros before using the overpic and Overpic environments.

See section 87.2 for the print-mode version of \overpicfontsize and \overpicfontskip.

**for HTML output:**

```
\LWR@ProvidesPackagePass{overpic}[2017/10/06]

\newcommand*{\overpicfontsize}{12}
\newcommand*{\overpicfontskip}{14}

\BeforeBeginEnvironment{overpic}{%
    \begin{lateximage}%
    \fontsize{\overpicfontsize}{\overpicfontskip}%
    \selectfont%
}

\AfterEndEnvironment{overpic}{\end{lateximage}}

\BeforeBeginEnvironment{Overpic}{%
    \begin{lateximage}%
    \fontsize{\overpicfontsize}{\overpicfontskip}%
    \selectfont%
}

```

```
\AfterEndEnvironment{Overpic}{\end{lateximage}}
```

File 339 **lwarp-pagegrid.sty**

§ 446 Package

# pagegrid

Pkg pagegrid pagegrid is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{pagegrid}[2016/05/16]
\newcommand*{\pagegridsetup}[1]{}
```

File 340 **lwarp-pagenote.sty**

§ 447 Package

# pagenote

Pkg pagenote pagenote works as-is, but the page option is disabled.

⚠ labels Note that labels in page notes do not appear as expected, even in the print version.

**for HTML output:**

```
\DeclareOption{page}{}
\LWR@ProvidesPackagePass{pagenote}[2009/09/03]
```

For MathJax:

```
\begin{warpMathJax}
\appto\LWR@syncnotenumbers{\LWR@synconenotenumber{LWRpagenote}{\thepagenote}}
\CustomizeMathJax{\def\LWRpagenote{1}}
\CustomizeMathJax{\newcommand{\pagenote}[2][\LWRpagenote]{{}^{\mathrm{#1}}}}
\end{warpMathJax}
```

There is no \pagenotemark, so the following are not required:

```
\providecommand{\pagenotename}{pagenote}
\appto\LWR@syncnotenames{\LWR@synconenotename{LWRpagenote}{\pagenotename}}
```

File 341 **lwarp-pagesel.sty**

§ 448 Package

# pagesel

Pkg pagesel pagesel is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{pagesel}[2016/05/16]
```

File 342 **lwarp-paralist.sty**

## § 449 Package paralist

(*Emulates or patches code by* Bernd Schandl.)

Pkg paralist paralist is supported with minor changes.

**for HTML output:**

```
\LWR@ProvidesPackagePass{paralist}[2017/01/22]
```

The compact environments are identical to the regular ones:

```
\LetLtxMacro\compactitem\itemize
\LetLtxMacro\compactenum\enumerate
\LetLtxMacro\compactdesc\description
\LetLtxMacro\endcompactitem\enditemize
\LetLtxMacro\endcompactenum\endenumerate
\LetLtxMacro\endcompactdesc\enddescription
```

For the inline environments, revert `\item` to its original print-mode version:

```
\AtBeginEnvironment{inparaitem}{\LetLtxMacro\item\LWR@origitem}
\AtBeginEnvironment{inparaenum}{\LetLtxMacro\item\LWR@origitem}
\AtBeginEnvironment{inparadesc}{\LetLtxMacro\item\LWR@origitem}
```

Manual formatting of the description labels:

```
\def\paradescriptionlabel#1{{\normalfont\textbf{#1}}}
```

---

File 343 **lwarp-parallel.sty**

## § 450 Package parallel

(*Emulates or patches code by* Matthias Eckermann.)

Pkg parallel parallel is emulated.

Package options are ignored. Footnotes are treated as normal lwarp footnotes.

Environment option `c` gives side-by-side `<div>`s of class `minipage`, each of whose width is a percent depending on the given left and right widths, proportional to `\linewidth`.

Inside each environment, `\linewidth` and `\textwidth` are set for the print-output sizes.

**for HTML output:** Discard all options for lwarp-parallel:

```
\LWR@ProvidesPackageDrop{parallel}[2003/04/13]

\newcounter{LWR@parallel@Lwidth}
\newcounter{LWR@parallel@Rwidth}
\newcommand*{\LWR@parallel@border}

\newenvironment*{Parallel}[3][]%
    {%
        \LWR@printpendingfootnotes%
```

```
        \setlength{\linewidth}{\LWR@userstextwidth}%
        \setlength{\textwidth}{\LWR@userstextwidth}%
        \renewcommand*{\LWR@parallel@border}{}%
        \ifstrequal{#1}{v}%
            {%
           \renewcommand*{\LWR@parallel@border}{ ; border-left: 2px solid black}%
            }%
            {}%
        \ifblank{#2}{%
            \ifblank{#3}{% {}{}
                \setcounter{LWR@parallel@Lwidth}{45}%
                \setcounter{LWR@parallel@Rwidth}{45}%
            }% {}{}
            {% {}{x}
                \setlength{\LWR@templengthone}{\linewidth-#3}%
                \setcounter{LWR@parallel@Lwidth}{%
                    90*\ratio{\LWR@templengthone}{\linewidth}%
                }%
                \setcounter{LWR@parallel@Rwidth}{%
                    90*\ratio{#3}{\linewidth}%
                }%
            }% {}{x}
        }% #2 blank
        {% #2 non-blank
            \ifblank{#3}{% {x}{}
                \setcounter{LWR@parallel@Lwidth}{%
                    90*\ratio{#2}{\linewidth}%
                }%
                \setlength{\LWR@templengthone}{\linewidth-#2}%
                \setcounter{LWR@parallel@Rwidth}{%
                    90*\ratio{\LWR@templengthone}{\linewidth}%
                }%
            }% {x}{}
            {% {x}{x}
                \setcounter{LWR@parallel@Lwidth}{%
                    90*\ratio{#2}{\linewidth}%
                }%
                \setcounter{LWR@parallel@Rwidth}{%
                    90*\ratio{#3}{\linewidth}%
                }%
            }% {x}{x}
        }% #2 non-blank
    }
    {%
        \ParallelAtEnd%
        \renewcommand*{\ParallelAtEnd}{}%
        \LWR@printpendingfootnotes%
    }

\newcommand*{\ParallelLText}[1]{%
    \begin{BlockClass}[%
        width:\arabic{LWR@parallel@Lwidth}\% ; % space
        padding: .5ex 1\% ; % space
    ]{minipage}%
    #1%
```

```
    \end{BlockClass}%
}

\newcommand*{\ParallelRText}[1]{%
    \begin{BlockClass}[%
        width:\arabic{LWR@parallel@Rwidth}\% ; % space
        padding: .5ex 1\% ; % space
        \LWR@parallel@border%
    ]{minipage}%
    #1%
    \end{BlockClass}%
}

\newcommand*{\ParallelPar}{\LWR@printpendingfootnotes}

\newcommand*{\ParallelAtEnd}{}
```

File 344 **lwarp-parcolumns.sty**

§ 451 Package

# parcolumns

(*Emulates or patches code by* Jonathan Sauer.)

Pkg parcolumns

parcolumns is emulated.

rulebetween is honored. The other keys are ignored, including colwidths.

Each column is placed inside a  of class minipage, each of whose width is fixed at 85% divided by the number of columns. In most cases, this results in side-by-side minipages adapting to the browser width. Inside each minipage, \linewidth, \textwidth, and \textheight are set for a virtual $6 \times 9$ inch page, with \linewidth divided by the number of columns.

**for HTML output:**

Discard all options for lwarp-parcolumns:

```
\RequirePackage{keyval}%

\LWR@ProvidesPackageDrop{parcolumns}[2004/11/25]

\newcounter{LWR@parcolumns@numcols}
\newcounter{LWR@parcolumns@thiscol}
\newcounter{LWR@parcolumns@width}
\newbool{LWR@parcolumns@started}
\newbool{LWR@parcolumns@rule}

\define@key{LWRparcols}{colwidths}{}
\define@key{LWRparcols}{distance}{}
\define@key{LWRparcols}{rulebetween}[true]{%
    \setbool{LWR@parcolumns@rule}{#1}%
}
\define@key{LWRparcols}{nofirstindent}{}
\define@key{LWRparcols}{sloppy}{}
\define@key{LWRparcols}{sloppyspaces}{}
```

```
18
19 \newenvironment*{parcolumns}[2][]
20     {%
21         \begin{LWR@setvirtualpage}*[#2]%
22         \setcounter{LWR@parcolumns@numcols}{#2}%
23         \setcounter{LWR@parcolumns@thiscol}{1}%
24         \boolfalse{LWR@parcolumns@started}%
25         \boolfalse{LWR@parcolumns@rule}%
26         \setcounter{LWR@parcolumns@width}{%
27             85/#2
28         }%
29         \setkeys{LWRparcols}{#1}%
30     }
31     {%


32         \colplacechunks%
33         \end{LWR@setvirtualpage}%
34     }
35
36 \newcommand{\LWR@parcolumns@onecol}[1]{%
37     \ifbool{LWR@parcolumns@started}%
38         {}%
39         {%
40             \LWR@htmldivclass{parcolumns}%
41             \booltrue{LWR@parcolumns@started}%
42         }%
43     \ifboolexpr{%
44         bool {LWR@parcolumns@rule} and
45         test {%
46             \ifnumgreater
47                 {\value{LWR@parcolumns@thiscol}}
48                 {1}
49         }%
50     }%
51         {\renewcommand{\LWR@tempone}{ ; border-left: 2px solid black}}%
52         {\renewcommand{\LWR@tempone}{}}%
53     \begin{BlockClass}[%
54         width:\arabic{LWR@parcolumns@width}\% ; % space
55         padding: .5ex 1\% ; % space
56         \LWR@tempone%
57     ]{minipage}%
58     #1%
59     \end{BlockClass}%
60     \addtocounter{LWR@parcolumns@thiscol}{1}%
61 }
62
63 \newcommand{\colchunk}[2][\value{LWR@parcolumns@thiscol}]{%
64     \whileboolexpr{%
65         test {%
66             \ifnumcomp%
67                 {\value{LWR@parcolumns@thiscol}}
68                 {<}
69                 {#1}%
70         }%
71     }{%
```

```
        \LWR@parcolumns@onecol{}%
    }%
    \LWR@parcolumns@onecol{#2}%
}

\newcommand*{\colplacechunks}{%
    \ifbool{LWR@parcolumns@started}%
        {%
            \LWR@htmldivclassend{div}%
            \boolfalse{LWR@parcolumns@started}%
        }%
        {}%
    \setcounter{LWR@parcolumns@thiscol}{1}%
}
```

File 345 **lwarp-parnotes.sty**

§ 452 Package

# parnotes

(*Emulates or patches code by* Chelsea Hughes.)

Pkg parnotes parnotes is supported with some patches.

**for HTML output:**

```
\LWR@ProvidesPackagePass{parnotes}[2016/08/15]

\long\def\PN@parnote@real#1#2{%
    \parnotemark{#1}%
    % Unless this is the first parnote in \PN@text, add a separator first
    \unless\ifx\PN@text\@empty\g@addto@macro\PN@text{\parnoteintercmd}\fi
    % Redefine \@currentlabel to the parnote label, so \label works
    \g@addto@macro\PN@text{%
%         \phantomsection%
        \def\@currentlabel{#1}%
        \def\cref@currentlabel{%        lwarp
            [parnotemark][\arabic{parnotemark}][]\theparnotemark%
        }%
    }%
    \g@addto@macro\PN@text{%
        \LWR@textcurrentfont{%          lwarp
            \parnotemark{#1}\nolinebreak\thinspace#2%
        }%
    }%
}

\def\PN@parnotes@real{%
    % We call \par later, so this avoids recursion with \PN@parnotes@auto
    \PN@inparnotestrue
    \unless\ifvmode\par\fi
    % Avoid page breaks between a paragraph and its parnotes
    \nopagebreak\addvspace{\parnotevskip}%
    \LWR@forcenewpage%                  lwarp
    \begin{BlockClass}{footnotes}%      lwarp
    {\parnotefmt{\PN@text}\par}%
```

```
    \end{BlockClass}%                   lwarp
    \global\def\PN@text{}%
    \addvspace{\parnotevskip}%
    %
    % These can be enabled or disabled by package options
    %
    \PN@disable@indent
    \PN@reset@optional
    \PN@inparnotesfalse
}

\AtBeginDocument{
    \crefname{parnotemark}{paragraph note}{paragraph notes}
    \Crefname{parnotemark}{Paragraph note}{Paragraph notes}
}
```

For MathJax:

```
\begin{warpMathJax}
\providecommand{\parnotename}{parnote}
\appto\LWR@syncnotenumbers{%
    \addtocounter{parnotemark}{-1}% specific to parnotes
    \LWR@synconenotenumber{LWRparnote}{\theparnotemark}%
    \addtocounter{parnotemark}{1}% specific to parnotes
}
\appto\LWR@syncnotenames{\LWR@synconenotename{LWRparnote}{\parnotename}}
\CustomizeMathJax{\def\LWRparnote{1}}
\CustomizeMathJax{\newcommand{\parnote}[2][\LWRparnote]{{}^{\mathrm{#1}}}}
\CustomizeMathJax{\newcommand{\parnotemark}[1][\LWRparnote]{{}^{\mathrm{#1}}}}
\end{warpMathJax}
```

---

File 346 **lwarp-parskip.sty**

# § 453 Package parskip

Pkg parskip parskip is ignored.

**for HTML output:** Discard all options for lwarp-parskip.

```
\LWR@ProvidesPackageDrop{parskip}[2001/04/09]
```

---

File 347 **lwarp-pbox.sty**

# § 454 Package pbox

(*Emulates or patches code by* Simon Law.)

Pkg pbox pbox is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{pbox}[2011/12/07]
```

```
\NewDocumentCommand{\pbox}{O{t} O{} O{t} m +m}{%
\global\booltrue{LWR@minipagefullwidth}%
\parbox[#1][#2][#3]{#4}{#5}%
}

\newcommand{\settominwidth}[3][\columnwidth]{%
\settowidth{#2}{#3}%
}

\newcommand{\widthofpbox}[1]{%
\widthof{#1}%
}
```

File 348 **lwarp-pdfcol.sty**

## § 455 Package pdfcol

Pkg pdfcol pdfcol is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{pdfcol}[2018/11/01]

\ltx@newif\ifpdfcolAvailable
\pdfcolAvailablefalse

\def\pdfcolErrorNoStacks{
    \PackageInfo{lwarp-pdfcol}{Ignoring pdfcol for HTML output.}
}

\def\pdfcolInitStack#1{}%

\long\def\pdfcolIfStackExists#1#2#3{#3}%

\def\pdfcolSwitchStack#1{}%

\def\pdfcolSetCurrentColor{}%

\def\pdfcolSetCurrent#1{}%
```

File 349 **lwarp-pdfcolfoot.sty**

## § 456 Package pdfcolfoot

Pkg pdfcolfoot pdfcolfoot is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{pdfcolfoot}[2016/05/16]

\newcommand*{\pdfcolfoot@switch}{}

\newcommand*{\pdfcolfoot@current}{}
```

File 350 **lwarp-pdfcolmk.sty**

§ 457 Package

# pdfcolmk

Pkg pdfcolmk pdfcolmk is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{pdfcolmk}[2016/05/16]
```

File 351 **lwarp-pdfcolparallel.sty**

§ 458 Package

# pdfcolparallel

Pkg pdfcolparallel pdfcolparallel is ignored.

**for HTML output:**

```
\RequirePackage{keyval}%

\LWR@ProvidesPackageDropA{pdfcolparallel}{2016/05/16}
```

Pass options to parallel:

```
\DeclareOption*{%
    \PassoptionsToPackage{\CurrentOption}{parallel}%
}
```

Process the options:

```
\LWR@ProvidesPackageDropB
```

Require parallel with the given options:

```
\RequirePackage{parallel}[2003/04/13]
```

Ignore the new key:

```
\define@key{parallel}{rulebetweencolor}{}
```

File 352 **lwarp-pdfcolparcolumns.sty**

§ 459 Package

# pdfcolparcolumns

Pkg pdfcolparcolumns pdfcolparcolumns is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDropA{pdfcolparcolumns}{2016/05/16}
```

Pass options to parcolumns:

```
\DeclareOption*{%
    \PassoptionsToPackage{\CurrentOption}{parcolumns}%
}
```

Process the options:

```
\LWR@ProvidesPackageDropB
```

Require parcolumns with the given options:

```
\RequirePackage{parcolumns}[2004/11/25]
```

Ignore the new key:

```
\define@key{LWRparcols}{rulebetweencolor}{}
```

---

File 353 **lwarp-pdfcomment.sty**

§ 460 Package

# pdfcomment

Pkg pdfcomment pdfcomment is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{pdfcomment}[2016/06/13]

\newenvironment{pdfsidelinecomment}[2][]{}{}
\newcommand{\pdfcomment}[2][]{}
\newcommand{\pdfmargincomment}[2][]{}
\newcommand{\pdfmarkupcomment}[3][]{#2}
\newcommand{\pdffreetextcomment}[2][]{}
\newcommand{\pdfsquarecomment}[2][]{}
\newcommand{\pdfcirclecomment}[2][]{}
\newcommand{\pdflinecomment}[2][]{}
\newcommand{\pdftooltip}[3][]{#2}
\newcommand{\pdfcommentsetup}[2][]{}
\newcommand{\listofpdfcomments}[1][]{}
\newcommand{\setliststyle}[1]{}
\newcommand{\defineliststyle}[2]{}
\newcommand{\defineavatar}[2]{}
\newcommand{\definestyle}[2]{}
```

For MathJax:

```
\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\pdfmarkupcomment}[3][]{#2}}
\CustomizeMathJax{\newcommand{\pdftooltip}[3][]{#2}}
\end{warpMathJax}
```

---

File 354 **lwarp-pdfcrypt.sty**

## § 461 Package pdfcrypt

Pkg pdfcrypt pdfcrypt is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{pdfcrypt}[2016/05/16]
\newcommand*{\pdfcryptsetup}[1]{}
```

File 355 **lwarp-pdflscape.sty**

## § 462 Package pdflscape

Pkg pdflscape pdflscape is ignored.

**for HTML output:** Discard all options for lwarp-pdflscape:

```
\LWR@ProvidesPackageDrop{pdflscape}[2016/05/14]
```

File 356 **lwarp-pdfmarginpar.sty**

## § 463 Package pdfmarginpar

Pkg pdfmarginpar pdfmarginpar is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{pdfmarginpar}[2011/08/05]
\newcommand{\pdfmarginpar}[2][]{}
\newcommand{\pdfmarginparset}[1]{}
```

File 357 **lwarp-pdfpages.sty**

## § 464 Package pdfpages

(*Emulates or patches code by* Andreas Matthias.)

Pkg pdfpages pdfpages is patched for use by lwarp.

Option `link` and `linkname` work:

```
\hyperlink{<filename>.pdf.<pagenubmer>}{some text}
\hyperlink{<linkname>.<pagenubmer>}{some text}
```

Options which make no sense in HTML are disabled.

**for HTML output:**

```
\LWR@ProvidesPackagePass{pdfpages}[2017-10-31]
```

Disable option which have no meaning for HTML output:

```
\define@key{pdfpages}{fitpaper}[false]{}
\define@key{pdfpages}{landscape}[false]{}
\define@key{pdfpages}{openright}[false]{}
\define@key{pdfpages}{signature}{}
\define@key{pdfpages}{signature*}{}
\define@key{pdfpages}{booklet}[false]{}
\define@key{pdfpages}{rotateoversize}[false]{}
\define@key{pdfpages}{doublepages}[false]{}
\define@key{pdfpages}{doublepagestwist}[false]{}
\define@key{pdfpages}{doublepagestwistodd}[false]{}
\define@key{pdfpages}{doublepagestwist*}[false]{}
\define@key{pdfpages}{doublepagestwistodd*}[false]{}
\define@key{pdfpages}{duplicatepages}[2]{}
\define@key{pdfpages}{thread}[false]{}
\define@key{pdfpages}{threadname}{}
\define@key{pdfpages}{linkfit}{}
\define@key{pdfpages}{linktodoc}[false]{}
\define@key{pdfpages}{linktodocfit}{}
\define@key{pdfpages}{linkfilename}{}
\define@key{pdfpages}{survey}[false]{}
\define@key{pdfpages}{survey-nolink}[false]{}
\define@key{pdfpages}{newwindow}[false]{}
```

Use print mode while measuring the page numbers:

```
\xpretocmd{\AM@getpagecount}{\LWR@restoreorigformatting}{}{}
```

Emulate a bit of eso-pic:

```
\newif\ifESO@texcoord

\newcommand{\ESO@HookIIBG}{}

\renewcommand{\AM@AddToShipoutPicture}{\g@addto@macro\ESO@HookIIBG}

\renewcommand{\ClearShipoutPicture}{}
```

`\LWR@esopic@newpage` At each `\newpage`.

```
\newcommand*{\LWR@esopic@newpage}{%
```

Is there something to draw?

```
\ifdefvoid{\ESO@HookIIBG}%
{}%
{%
```

If the `link` option was specified, add a hyper target:

```
    \ifAM@link%
        \hypertarget{\AM@linkname.\AM@page}{}%
    \fi%
```

Draw inside a picture environment of the size of a virtual page:

```
    \begingroup%
    \setlength{\unitlength}{1in}%
    \begin{picture}(8,10.5)%
    \ESO@HookIIBG%
    \end{picture}%
    \endgroup%
    \global\let\ESO@HookIIBG\@empty%
}
}
```

`\AM@output` Patched to use `\LWR@esopic@newpage`.

```
\xpatchcmd{\AM@output}
    {\newpage}
    {\LWR@esopic@newpage}
    {}
    {\LWR@patcherror{pdfpages}{AM@output-1}}

\xpatchcmd{\AM@output}
    {\newpage}
    {\LWR@esopic@newpage}
    {}
    {\LWR@patcherror{pdfpages}{AM@output-2}}

\xpatchcmd{\AM@output}
    {\newpage}
    {\LWR@esopic@newpage}
    {}
    {\LWR@patcherror{pdfpages}{AM@output-3}}
```

`\includepdf` Patched to set the user's paper size.

```
\xpretocmd{\includepdf}{%
    \begingroup%
    \setlength{\paperwidth}{\LWR@userspaperwidth}%
    \setlength{\paperheight}{\LWR@userspaperheight}%
}{}{}

\xapptocmd{\includepdf}{%
    \endgroup%
}{}{}
```

`\includepdfmerge` Patched to set the user's paper size.

```
\xpretocmd{\includepdfmerge}{%
    \begingroup%
    \setlength{\paperwidth}{\LWR@userspaperwidth}%
    \setlength{\paperheight}{\LWR@userspaperheight}%
}{}{}

\xapptocmd{\includepdfmerge}{%
    \endgroup%
}{}{}
```

\AM@hyper@begin@i Hyper links are created by \LWR@esopic@newpage, so don't create them here:

```
\renewcommand{\AM@hyper@begin@i}{}
```

File 358 **lwarp-pdfprivacy.sty**

§ 465 Package

# pdfprivacy

Pkg pdfprivacy pdfprivacy is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{pdfprivacy}[2017/12/03]
```

File 359 **lwarp-pdfrender.sty**

§ 466 Package

# pdfrender

Pkg pdfrender pdfrender is allowed during HTML, but it has no effect on HTML text output. pdfrender is enabled for use with xfakebold, and it is enabled during HTML so that it may be in use when an SVG math image is started. I.e. xfakebold's \setBold may be used outside of a math expression and still be detected when the math begins.

The lwarp-pdfrender package is present because it used to disable pdfrender, so this newer version is to overwrite older versions.

**for HTML output:**

```
\LWR@ProvidesPackagePass{pdfrender}[2019/12/29]
```

File 360 **lwarp-pdfsync.sty**

§ 467 Package

# pdfsync

(*Emulates or patches code by* J. Laurens.)

Pkg pdfsync pdfsync is ignored.

**for HTML output:** Discard all options for lwarp-pdfsync:

```
\LWR@ProvidesPackageDrop{pdfsync}[2008/01/26]

\newcommand*{\pdfsync}{}
\newcommand*{\pdfsyncstart}{}
\newcommand*{\pdfsyncstop}{}
```

File 361 **lwarp-pdftricks.sty**

§ 468 Package

# pdftricks

(*Emulates or patches code by* C. V. Radhakrishnan, C. V. Rajagopal, Antoine Chambert-Loir.)

Pkg pdftricks pdftricks is patched for use by lwarp.

⚠ convert image files The pdftricks image files <jobname>-fig*.pdf must be converted to .svg, or else a missing file error will occur. The image files must also be converted again whenever they change. To convert the images:

Enter ⇒ **lwarpmk pdftosvg <jobname>-fig*.pdf**

**for HTML output:**

```
1 \LWR@ProvidesPackagePass{pdftricks}[2003/08/10]
```

Reuse the print-mode images:

```
2 \def\PDFTfigname{\BaseJobname-fig\thepsfig}
```

If the .pdf images have not yet been converted to .svg then an error about a missing file will occur. Warn the user to convert the images.

```
3 \PackageWarning{lwarp-pdftricks}{
4 When the pdftricks images change,
5 remember to convert PDF images to SVG using 'lwarpmk pdftosvg *-fig.pdf',
6 }
7
8 \AfterEndDocument{\typeout{***}}
9 \AfterEndDocument{\typeout{*** Note: If pdftricks images are not found, new, or updated,}}
10 \AfterEndDocument{\typeout{*** \space use 'lwarpmk pdftosvg \BaseJobname-fig*.pdf'}}
11 \AfterEndDocument{\typeout{***}}
```

---

File 362 **lwarp-pdfx.sty**

## § 469 Package pdfx

Pkg pdfx pdfx is ignored.

**for HTML output:**

```
1 \LWR@ProvidesPackageDrop{pdfx}[2017/05/18]
```

---

File 363 **lwarp-perpage.sty**

## § 470 Package perpage

(*Emulates or patches code by* David Kastrup.)

Pkg perpage perpage is mostly ignored, but support is added for footnote counters.

There is no page number in HTML, so most counters are not reset. If the document redefines \the<countername> to include \theperpage, it is necessary to place that redefininition inside a warpprint environment to avoid modifying the HTML defintions.

\AddAbsoluteCounter must not be inside warpprint, as the counter must be added for HTML also, although it is not incremented.

footnote numbering

To have footnote numbers reset each time footnotes are printed:

```
\setcounter{footnoteReset}{1}
```

For bigfoot, manyfoot, or perpage:

```
\MakePerPage{footnoteX}
— or —
\MakeSortedPerPage{footnoteX}
```

The footnotes are reset when they are printed, according to section level as set by `FootnoteDepth`, which is not necessarily by HTML page. This is recommended for `\alph`, `\Alph`, or `\fnsymbol` footnotes, due to the limited number of symbols which are available.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{perpage}[2014/10/25]

\newcommand\AddAbsoluteCounter[1]
{
    \@ifundefined{c@abs#1}{%
        \expandafter\newcount\csname c@abs#1\endcsname
        \global\value{abs#1}\@ne
%         \global\expandafter\let\csname cl@abs#1\endcsname\@empty
        \expandafter\xdef\csname theabs#1\endcsname{%
%             \noexpand\number \csname c@abs#1\endcsname
        }%
%         \global\@namedef{c@pabs@#1}{\pp@cl@begin
%         \stepcounter{abs#1}%
%         \pp@cl@end}%
%         \@addtoreset{pabs@#1}{#1}
    }
    {}
}

\AddAbsoluteCounter{page}
\def\theabspage{1}

\newcommand*\MakePerPage[2][1]{%
    \ifltxcounter{#2Reset}{%
        \setcounter{#2Reset}{#1}%
    }{

}%
}

\newcommand*\MakeSorted[1]{}

\newcommand*\MakeSortedPerPage[2][1]{%
    \ifltxcounter{#2Reset}{%
        \setcounter{#2Reset}{#1}%
    }{
}%
}

\newcommand*{\theperpage}{1}
```

File 364 **lwarp-pfnote.sty**

## § 471 Package pfnote

Pkg pfnote pfnote is ignored.

pfnote ⚠ pfnote numbers While emulating pfnote, lwarp is not able to reset HTML footnote numbers per page number to match the printed version, as HTML has no concept of page numbers. lwarp therefore uses continuous footnote numbering even for pfnote.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{pfnote}[1999/07/14]
```

File 365 **lwarp-phfqit.sty**

## § 472 Package phfqit

(*Emulates or patches code by* Philippe Faist.)

Pkg phfqit phfqit is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{phfqit}[2017/08/16]

\LetLtxMacro\LWR@origbitstring\bitstring

\renewcommand\bitstring[1]{%
\InlineClass[%
    text-decoration: overline underline ;
]{bitstring}{#1}%
% \phfqit@bitstring{#1}%
}

\appto\LWR@restoreorigformatting{%
\LetLtxMacro\bitstring\LWR@origbitstring%
}
```

File 366 **lwarp-physics.sty**

## § 473 Package physics

(*Emulates or patches code by* Sergio C. de la Barrera.)

Pkg physics physics works as-is for HTML with SVG math.

For MathJax, the MathJax v3 physics extension is used.

**for HTML output:**

```
\LWR@ProvidesPackagePass{physics}% No date is provided by the package.
```

```
\begin{warpMathJax}
\PackageWarningNoLine{lwarp, physics}{The MathJax v3 extension will be used}
\CustomizeMathJax{\require{physics}}
\end{warpMathJax}
```

File 367 **lwarp-physunits.sty**

§ 474 Package

# physunits

(*Emulates or patches code by* Brian W. Mulligan.)

Pkg physunits physunits is supported as-is for SVG math, and is emulated for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{physunits}[2020/03/26]

\begin{warpMathJax}
\LWR@infoprocessingmathjax{physunits}

\CustomizeMathJax{\newcommand{\micro}{\mu}}
\CustomizeMathJax{\newcommand{\V}[1][ ]{\,\mathrm{#1V}}}
\CustomizeMathJax{\newcommand{\Volt}[1][ ]{\,\mathrm{#1V}}}
\CustomizeMathJax{\newcommand{\Coulomb}[1][ ]{\,\mathrm{#1C}}}
\CustomizeMathJax{\newcommand{\esu}{\,\mathrm{esu}}}
\CustomizeMathJax{\newcommand{\Ohm}[1][ ]{\,\mathrm{#1\Omega}}}
\CustomizeMathJax{\newcommand{\Amp}[1][ ]{\,\mathrm{#1A}}}
\CustomizeMathJax{\newcommand{\Farad}[1][ ]{\,\mathrm{#1F}}}
\CustomizeMathJax{\newcommand{\Tesla}[1][ ]{\,\mathrm{#1T}}}
\CustomizeMathJax{\newcommand{\Gauss}[1][ ]{\,\mathrm{#1G}}}
\CustomizeMathJax{\newcommand{\Henry}[1][ ]{\,\mathrm{#1H}}}
\CustomizeMathJax{\newcommand{\eV}[1][ ]{\,\mathrm{#1eV}}}
\CustomizeMathJax{\newcommand{\keV}{\,\mathrm{keV}}}
\CustomizeMathJax{\newcommand{\MeV}{\,\mathrm{MeV}}}
\CustomizeMathJax{\newcommand{\J}[1][ ]{\,\mathrm{#1J}}}
\CustomizeMathJax{\newcommand{\Joule}[1][ ]{\,\mathrm{#1J}}}
\CustomizeMathJax{\newcommand{\erg}{\,\mathrm{erg}}}
\CustomizeMathJax{\newcommand{\kcal}{\,\mathrm{kcal}}}
\CustomizeMathJax{\newcommand{\Cal}{\,\mathrm{Cal}}}
\CustomizeMathJax{\newcommand{\calorie}[1][ ]{\,\mathrm{#1cal}}}
\CustomizeMathJax{\newcommand{\BTU}{\,\mathrm{BTU}}}
\CustomizeMathJax{\newcommand{\tnt}{\,\mathrm{ton\, of\, TNT}}}
\CustomizeMathJax{\newcommand{\Watt}[1][ ]{\,\mathrm{#1W}}}
\CustomizeMathJax{\newcommand{\hpi}{\,\mathrm{hp(I)}}}
\CustomizeMathJax{\newcommand{\hpm}{\,\mathrm{hp(M)}}}
\CustomizeMathJax{\newcommand{\hp}{\,\mathrm{hp}}}
\CustomizeMathJax{\newcommand{\meter}[1][ ]{\,\mathrm{#1m}}}
\CustomizeMathJax{\newcommand{\m}[1][ ]{\,\mathrm{#1m}}}
\CustomizeMathJax{\newcommand{\km}{\,\mathrm{km}}}
\CustomizeMathJax{\newcommand{\au}{\,\mathrm{au}}}
\CustomizeMathJax{\newcommand{\pc}[1][ ]{\,\mathrm{#1pc}}}
\CustomizeMathJax{\newcommand{\ly}[1][ ]{\,\mathrm{#1ly}}}
\CustomizeMathJax{\newcommand{\cm}{\,\mathrm{cm}}}
\CustomizeMathJax{\newcommand{\nm}{\,\mathrm{nm}}}
\CustomizeMathJax{\newcommand{\ft}{\,\mathrm{ft}}}
```

```
\CustomizeMathJax{\newcommand{\inch}{\,\mathrm{in}}}
\CustomizeMathJax{\newcommand{\mi}{\,\mathrm{mi}}}
\CustomizeMathJax{\newcommand{\s}[1][ ]{\,\mathrm{#1s}}}
\CustomizeMathJax{\newcommand{\Sec}[1][ ]{\,\mathrm{#1s}}}
\CustomizeMathJax{\newcommand{\Min}{\,\mathrm{min}}}
\CustomizeMathJax{\newcommand{\h}{\,\mathrm{h}}}
\CustomizeMathJax{\newcommand{\y}[1][ ]{\,\mathrm{#1y}}}
\CustomizeMathJax{\newcommand{\Day}{\,\mathrm{d}}}

\CustomizeMathJax{\newcommand{\gm}[1][ ]{\,\mathrm{#1g}}}
\CustomizeMathJax{\newcommand{\kg}{\,\mathrm{kg}}}
\CustomizeMathJax{\newcommand{\lb}{\,\mathrm{lb}}}
\CustomizeMathJax{\newcommand{\amu}{\,\mathrm{amu}}}
\CustomizeMathJax{\newcommand{\N}[1][ ]{\,\mathrm{#1N}}}
\CustomizeMathJax{\newcommand{\Newton}[1][ ]{\,\mathrm{#1N}}}
\CustomizeMathJax{\newcommand{\dyne}[1][ ]{\,\mathrm{#1dyn}}}
\CustomizeMathJax{\newcommand{\lbf}{\,\mathrm{lbf}}}
\CustomizeMathJax{\newcommand{\kmps}{\,\mathrm{km}\,\mathrm{s}^{-1}}}
\CustomizeMathJax{\newcommand{\kmph}{\,\mathrm{km}\,\mathrm{h}^{-1}}}
\CustomizeMathJax{\newcommand{\mps}[1][ ]{\,\mathrm{#1m}\,\mathrm{s}^{-1}}}
\CustomizeMathJax{\newcommand{\miph}{\,\mathrm{mi}\,\mathrm{h}^{-1}}}
\CustomizeMathJax{\newcommand{\kts}{\,\mathrm{kts}}}

\CustomizeMathJax{\newcommand{\mpss}[1][ ]{\,\mathrm{#1m}\,\mathrm{s}^{-2}}}
\CustomizeMathJax{\newcommand{\gacc}{\,\mathrm{g}}}
\CustomizeMathJax{\newcommand{\ftpss}{\,\mathrm{ft}\,\mathrm{s}^{-2}}}
\CustomizeMathJax{\newcommand{\K}[1][ ]{\,\mathrm{#1K}}}
\CustomizeMathJax{\newcommand{\Kelvin}[1][ ]{\,\mathrm{#1K}}}
\CustomizeMathJax{\newcommand{\Celcius}{\,^\circ{\mathrm{C}}}}
\CustomizeMathJax{\newcommand{\Rankine}{\,^\circ{\mathrm{R}}}}
\CustomizeMathJax{\newcommand{\Fahrenheit}{\,^\circ{\mathrm{F}}}}

\CustomizeMathJax{\newcommand{\rpm}{\,\mathrm{rev}\,\Min^{-1}}}

\CustomizeMathJax{\newcommand{\Hz}[1][ ]{\,\mathrm{#1Hz}}}
\CustomizeMathJax{\newcommand{\barP}[1][ ]{\,\mathrm{#1bar}}}
\CustomizeMathJax{\newcommand{\atm}{\,\mathrm{atm}}}
\CustomizeMathJax{\newcommand{\Pa}[1][ ]{\,\mathrm{#1Pa}}}
\CustomizeMathJax{\newcommand{\mmHg}{\,\mathrm{mmHg}}}
\CustomizeMathJax{\newcommand{\inHg}{\,\mathrm{inHg}}}
\CustomizeMathJax{\newcommand{\lbsi}{\,\mathrm{psi}}}
\CustomizeMathJax{\newcommand{\lbsf}{\,\mathrm{psf}}}
\CustomizeMathJax{\newcommand{\Ba}[1][ ]{\,\mathrm{#1Ba}}}
\CustomizeMathJax{\newcommand{\Torr}[1][ ]{\,\mathrm{#1Torr}}}
\CustomizeMathJax{\newcommand{\mol}{\,\mathrm{mol}}}
\end{warpMathJax}
```

File 368 **lwarp-picinpar.sty**

## § 475 Package picinpar

(*Emulates or patches code by* Friedhelm Sowa.)

Pkg picinpar picinpar is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{picinpar}% No date is assigned.
```

The window is floated by a BlockClass style.

```
\long\def\LWR@HTML@window[#1,#2,#3,#4] {%
    \if #2r%
        \begin{BlockClass}[float:right]{marginblock}%
    \else%
        \begin{BlockClass}[float:left]{marginblock}%
    \fi%
    #3\par%
    #4%
    \end{BlockClass}%
}

\def\endLWR@HTML@window{}

\LWR@formattedenv{window}
```

The framepic and wframepic are placed inside a BlockClass of class framebox.

```
\def\LWR@HTML@framepic#1{%
    \begin{BlockClass}{framebox}
    \expandafter\box\csname #1box\endcsname%
    \end{BlockClass}
}
\LWR@formatted{framepic}

\def\LWR@HTML@wframepic#1{%
    \begin{BlockClass}{framebox}
    \expandafter\box\csname #1box\endcsname%
    \end{BlockClass}
}
\LWR@formatted{wframepic}
```

The caption is placed inside a BlockClass of class figurecaption.

```
\long\def\LWR@HTML@@makewincaption#1#2{%
\begin{BlockClass}{figurecaption}
#1: #2
\end{BlockClass}
}
\LWR@formatted{@makewincaption}
```

With HTML output, figwindow and tabwindow must not pre-decrement their counters.

```
\long\def\LWR@HTML@figwindow[#1,#2,#3,#4] {%
%      \advance\c@figure -1
     \window[#1,#2,{#3},{\def\@captype{figure}%
        \wincaption#4\par}] }

\def\endLWR@HTML@figwindow{\endwindow}

\LWR@formattedenv{figwindow}
```

For tabwindow, to change the catcode of &, \StartDefiningTabulars is used before absorbing the arguments, and \EndDefiningTabulars is used at the end of the environment.

```
\long\def\LWR@HTML@subtabwindow[#1,#2,#3,#4] {%
%       \advance\c@table -1
      \window[#1,#2,{#3},{\def\@captype{table}%
         \wincaption#4\par}] }

\newcommand*{\LWR@HTML@tabwindow}{%
    \StartDefiningTabulars%
    \LWR@HTML@subtabwindow%
}

\def\endLWR@HTML@tabwindow{%
    \endwindow%
    \StopDefiningTabulars%
}

\LWR@formattedenv{tabwindow}
```

File 369 **lwarp-pifont.sty**

## § 476 Package pifont

(*Emulates or patches code by* Walter Schmidt.)

Pkg pifont pifont is patched for use by lwarp.

Hashed inline images are used, as there may not be Unicode support for all icons.

**for HTML output:**

```
\LWR@ProvidesPackagePass{pifont}[2005/04/12]

\renewcommand{\Pisymbol}[2]{%
    \begin{lateximage}*[Pisymbol][pisymbol#1#2]%
    {\Pifont{#1}\char#2}%
    \end{lateximage}%
}

\newcommand{\LWR@HTML@Pifill}[2]{
    \Pisymbol{#1}{#2} \Pisymbol{#1}{#2} \Pisymbol{#1}{#2}
}
\LWR@formatted{Pifill}

\newcommand{\LWR@HTML@Piline}[2]{%
    \par\noindent\hspace*{0.5in}
    \Pifill{#1}{#2} \Pifill{#1}{#2} \Pifill{#1}{#2}
}
\LWR@formatted{Piline}
```

File 370 **lwarp-pinlabel.sty**

## § 477 Package pinlabel

(*Emulates or patches code by* Colin Rourke.)

Pkg pinlabel pinlabel is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{pinlabel}% no date given

\xpretocmd{\psfig}
    {\begin{lateximage}[-pinlabel-~\PackageDiagramAltText]}
    {}
    {\LWR@patcherror{pinlabel}{psfigA}}

\xapptocmd{\psfig}
    {\end{lateximage}}
    {}
    {\LWR@patcherror{pinlabel}{psfigB}}
```

---

File 371 **lwarp-placeins.sty**

## § 478 Package placeins

(*Emulates or patches code by* Donald Arseneau.)

Pkg placeins placeins is ignored.

Discard all options for lwarp-placeins:

**for HTML output:**

```
\LWR@ProvidesPackageDrop{placeins}[2005/04/18]

\newcommand*{\FloatBarrier}{}
```

---

File 372 **lwarp-plarydshln.sty**

## § 479 Package plarydshln

Pkg plarydshln plarydshln is emulated by lwarp-arydshln.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{plarydshln}[2018/10/20]

\LWR@origRequirePackage{lwarp-arydshln}
```

---

File 373 **lwarp-plext.sty**

## § 480 Package plext

Pkg plext plext is preloaded by jtarticle and related classes.

**for HTML output:**

```
\LWR@loadbefore{plext}

\LWR@ProvidesPackagePass{plext}[2017/07/21]

\let\tate\relax

\DeclareExpandableDocumentCommand{\rensuji}{s o m}{#3}

% \layoutfloat(width,height)[pos]#4
\DeclareDocumentCommand{\layoutfloat}{d() o m}{}

% \DeclareLayoutCaption{type} <dir>(width)[pos1pos2]
\DeclareDocumentCommand{\DeclareLayoutCaption}{m d<> d() o}{}

\LetLtxMacro\pcaption\caption

% \layoutcaption<dir>(width)[pos]
\DeclareDocumentCommand{\layoutcaption}{d<> d() o}{}

\let\captiondir\relax
```

Add the optional <t/y> direction:

```
\RenewDocumentEnvironment{LWR@HTML@minipage}{d<> O{t} O{} O{t} m}
    {\LWR@HTML@sub@minipage{#2}{#3}{#4}{#5}}
    {\endLWR@HTML@sub@minipage}

\RenewDocumentCommand{\LWR@HTML@parbox}{d<> O{t} O{} O{t} m +m}
{
\LWR@traceinfo{parbox of width #4}%
\begin{minipage}[#2][#3][#4]{#5}%
#6
\end{minipage}%
}

% \pbox <t/y> [width] [l/r] {contents}
\RenewDocumentCommand{\pbox}{d<> O{0pt} O{c} m}{%
\global\booltrue{LWR@minipagefullwidth}%
\parbox{#2}{#4}%
}
```

`picture`, as modified by pext, is encapsulated by the lwarp core.

---

File 374 **lwarp-plextarydshln.sty**

# § 481 Package plextarydshln

Pkg plextarydshln plextarydshln is emulated by lwarp-arydshln.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{plextarydshln}[2018/10/20]

\LWR@origRequirePackage{lwarp-arydshln}
```

File 375 **lwarp-plextcolortbl.sty**

## § 482 Package plextcolortbl

Pkg plextcolortbl plextcolortbl is emulated by lwarp-colortbl.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{plextcolortbl}[2018/09/19]
\LWR@origRequirePackage{lwarp-colortbl}
```

File 376 **lwarp-plimsoll.sty**

## § 483 Package plimsoll

(*Emulates or patches code by* Palle Jørgensen.)

Pkg plimsoll plimsoll is used as-is for SVG math, and emulated for MathJax.

The `circ` option is honored. For MathJax, `\plimsollsans` is the same as `\plimsollroman`.

**for HTML output:**

```
\LWR@ProvidesPackagePass{plimsoll}[2020/10/09]

\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\plimsollroman}{\unicode{x029B5}}}

\CustomizeMathJax{\let\plimsoll\plimsollroman}
\CustomizeMathJax{\let\plimsollsans\plimsoll}

\ifdefstring{\stst}{^{\circ}}
    {\CustomizeMathJax{\newcommand{\stst}{^{\circ}}}}
    {\CustomizeMathJax{\newcommand{\stst}{^{\plimsoll}}}}
\end{warpMathJax}
```

File 377 **lwarp-prelim2e.sty**

## § 484 Package prelim2e

(*Emulates or patches code by* Martin Schröder.)

Pkg prelim2e prelim2e is ignored.

**for HTML output:** Discard all options for lwarp-prelim2e:

```
\LWR@ProvidesPackageDrop{prelim2e}[2009/05/29]

\newcommand{\PrelimText}{}
\newcommand{\PrelimTextStyle}{}
\newcommand{\PrelimWords}{}
```

A lateximage captures the modified image from the document.

```
\BeforeBeginEnvironment{psfrags}{%
    \begin{lateximage}[-psfrags-~\PackageDiagramAltText]%
}

\AfterEndEnvironment{psfrags}{\end{lateximage}}
```

---

File 381 **lwarp-psfragx.sty**

## § 488 Package psfragx

(*Emulates or patches code by* Pascal Kockaert.)

Pkg psfragx psfragx is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{psfragx}[2012/05/02]
```

A lateximage captures the modified image from the document.

```
\def\pfx@includegraphicx#1#2{%
    \begin{lateximage}[-psfragx-~\PackageDiagramAltText]%
    \mbox{\pfx@overpix{#1}{#2}\endpfx@overpix}%
    \end{lateximage}%
}

\def\@@@overpix[#1]<#2>[#3]#4{%
    \begin{lateximage}[-psfragx-~\PackageDiagramAltText]%
    \pfx@overpix{#1,ovpfgd={#2},ovpbgd={#3}}{#4}%
}

\def\endoverpix{%
    \endpfx@overpix%
    \end{lateximage}%
}
```

---

File 382 **lwarp-pst-eps.sty**

## § 489 Package pst-eps

(*Emulates or patches code by* Herbert Voss.)

Pkg pst-eps pst-eps is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{pst-eps}[2005/05/20]

\renewenvironment{TeXtoEPS}{}{}
\renewcommand{\PSTtoEPS}[3][]{}
```

File 383 **lwarp-pstool.sty**

§ 490 Package

# pstool

(*Emulates or patches code by* Zebb Prime, Will Robertson.)

Pkg pstool pstool is patched for use by lwarp.

\graphicspath is ignored, and the file directory must be stated.

⚠ path and filename The filename must not have a file extension.

Use

Enter ⇒ **lwarpmk html**

followed by

Enter ⇒ **lwarpmk limages**

.

**for HTML output:**

```
\LWR@ProvidesPackagePass{pstool}[2018/01/20]
```

Each image is placed inside a lateximage to capture the results of psfrag.

```
\renewcommand\pstool@alwaysprocess[3][]{%
    \begin{lateximage}[-pstool-~\PackageDiagramAltText]%
    \includegraphics{#2.pdf}%
    \end{lateximage}%
}
\LetLtxMacro\pstool@neverprocess\pstool@alwaysprocess
\LetLtxMacro\pstool@maybeprocess\pstool@alwaysprocess

\renewcommand\pstool@@psfragfig[4]{%
    \begin{lateximage}[-pstool-~\PackageDiagramAltText]%
    \includegraphics{#2.pdf}%
    \end{lateximage}%
}
```

File 384 **lwarp-pstricks.sty**

§ 491 Package

# pstricks

(*Emulates or patches code by* Timothy Van Zandt.)

Pkg pstricks pstricks is patched for use by lwarp.

⚠ use pspicture All pstricks content should be contained inside a pspicture environment.

**for HTML output:**

```
\LWR@ProvidesPackagePass{pstricks}[2018/01/06]
```

File 388 **lwarp-pxftnright.sty**

# § 495 Package pxftnright

Pkg pxftnright pxftnright is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{pxftnright}[2017/02/28]
\LWR@origRequirePackage{lwarp-ftnright}
```

File 389 **lwarp-pxjahyper.sty**

# § 496 Package pxjahyper

Pkg pxjahyper pxjahyper is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{pxjahyper}[2018/07/15]
```

File 390 **lwarp-quotchap.sty**

# § 497 Package quotchap

(*Emulates or patches code by* Karsten Tinnefeld, Jan Klever.)

Pkg quotchap quotchap is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{quotchap}[2019/07/09]

\newcommand{\@quotchap}{}
\newlength{\LWR@quotchapwidth}

\let\@printcites\relax

\newcommand*{\@iprintcites}{%
```

Place the quotes inside a  of class quotchap, of the maximum selected width:

```
\begin{BlockClass}[max-width: \LWR@printlength{\LWR@quotchapwidth}]{quotchap}
%\begin{minipage}{\LWR@quotchapwidth}
\@quotchap
%\end{minipage}
\end{BlockClass}
```

Deactivate the quote printing:

```
\global\let\@printcites\relax
}

\NewEnviron{savequote}[1][\linewidth]{%
```

Remember the width, adjusted for HTML, and make the length assignment global, per:
https://tex.stackexchange.com/questions/300823/why-is-setlength-ineffective-inside-a-tabular-environment

```
\setlength{\LWR@quotchapwidth}{#1*2}%
\global\LWR@quotchapwidth=\LWR@quotchapwidth%
```

Remember the body, and activate the quote printing:

```
\global\let\@quotchap\BODY
\global\let\@printcites\@iprintcites%
}
```

The quotation author is placed inside a  of class qauthor:

```
\newcommand{\qauthor}[1]{%
    \LWR@stoppars%
    \begin{BlockClass}{qauthor}%
    {#1}%
    \end{BlockClass}%
    \LWR@startpars%
}
```

Fonts are ignored. Use css.

```
\newcommand{\qsetcnfont}[1]{}
\providecommand*{\quotefont}{}
\providecommand*{\qauthorfont}{}
```

---

File 391 **lwarp-quoting.sty**

§ 498 Package

# quoting

(*Emulates or patches code by* Thomas Titz.)

Pkg quoting quoting is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{quoting}[2014/01/28]

\xpatchcmd{\quoting}{\quo@begintext}
    {\begin{LWR@blocktextcurrentfont}\quo@begintext}
    {}
    {\LWR@patcherror{quoting}{quoting}}

\xpatchcmd{\endquoting}{\quo@endtext}
    {\quo@endtext\end{LWR@blocktextcurrentfont}\LWR@stoppars}
    {}
    {\LWR@patcherror{quoting}{endquoting}}
```

File 392 **lwarp-ragged2e.sty**

## § 499 Package ragged2e

(*Emulates or patches code by* Martin Schröder.)

Pkg ragged2e ragged2e is emulated.

Discard all options for lwarp-ragged2e:

**for HTML output:**

```
\LWR@ProvidesPackageDrop{ragged2e}[2009/05/21]

\LetLtxMacro\Centering\centering
\LetLtxMacro\RaggedLeft\raggedleft
\LetLtxMacro\RaggedRight\raggedright
\newcommand*{\justifying}{}
\newlength{\CenteringLeftskip}
\newlength{\RaggedLeftLeftskip}
\newlength{\RaggedRightLeftskip}
\newlength{\CenteringRightskip}
\newlength{\RaggedLeftRightskip}
\newlength{\RaggedRightRightskip}
\newlength{\CenteringParfillskip}
\newlength{\RaggedLeftParfillskip}
\newlength{\RaggedRightParfillskip}
\newlength{\JustifyingParfillskip}
\newlength{\CenteringParindent}
\newlength{\RaggedLeftParindent}
\newlength{\RaggedRightParindent}
\newlength{\JustifyingParindent}
\newenvironment*{Center}{\center}{\endcenter}
\newenvironment*{FlushLeft}{\flushleft}{\endflushleft}
\newenvironment*{FlushRight}{\flushright}{\endflushright}
\newenvironment*{justify}{\justifying}{\endjustifying}
```

File 393 **lwarp-realscripts.sty**

## § 500 Package realscripts

(*Emulates or patches code by* Will Robertson.)

Pkg realscripts realscripts is emulated. See `lwarp.css` for the  of class supsubscript.

**for HTML output:**

```
\LWR@ProvidesPackagePass{realscripts}[2016/02/13]
```

The following are copied verbatim from the original, but given new names, since xparse definitions should not be `\let`.

```
\ExplSyntaxOn
```

```
3
4 \DeclareDocumentCommand \LWR@print@realsubscript {m} {
5   \fontspec_if_fontspec_font:TF {
6     \fontspec_if_opentype:TF
7     { \fontspec_if_feature:nTF {+subs}
8         { {\addfontfeature{VerticalPosition=Inferior}#1} }
9         { \fontspec_if_feature:nTF {+sinf}
10            { {\addfontfeature{VerticalPosition=ScientificInferior}#1} }
11            { \fakesubscript{#1} }
12        }
13    }
14    { \fontspec_if_aat_feature:nnTF {10} {2}
15        { {\addfontfeature{VerticalPosition=Inferior}#1} }
16        { \fakesubscript{#1} }
17    }
18  }
19  { \fakesubscript{#1} }
20 }
21
22 \DeclareDocumentCommand \LWR@HTML@realsubscript {m} {
23    \LWR@HTML@textsubscript{#1}
24 }
25
26 \LWR@formatted{realsubscript}
27
28
29 \DeclareDocumentCommand \LWR@print@realsuperscript {m} {
30   \fontspec_if_fontspec_font:TF
31   {
32     \fontspec_if_opentype:TF
33     { \fontspec_if_feature:nTF {+sups}
34       { {\addfontfeature{VerticalPosition=Superior}#1} }
35       { \fakesuperscript{#1} }
36     }
37     { \fontspec_if_aat_feature:nnTF {10} {1}
38       { {\addfontfeature{VerticalPosition=Superior}#1} }
39       { \fakesuperscript{#1} }
40     }
41   }
42   { \fakesuperscript{#1} }
43 }
44
45 \DeclareDocumentCommand \LWR@HTML@realsuperscript {m} {
46    \LWR@HTML@textsuperscript{#1}
47 }
48
49 \LWR@formatted{realsuperscript}
50
51
52 \DeclareDocumentCommand \LWR@print@textsubsuperscript {s O{l} mm} {
53   \leavevmode
54   \group_begin:
55   \IfBooleanTF #1
56   {
57     \hbox_set:Nn \l_tmpa_box {\textsubscript*{#3}}
```

```
    \hbox_set:Nn \l_tmpb_box {\textsuperscript*{#4}}
  }
  {
    \hbox_set:Nn \l_tmpa_box {\textsubscript{#3}}
    \hbox_set:Nn \l_tmpb_box {\textsuperscript{#4}}
  }
  \hbox_set:Nn \l_tmpa_box
    { \box_move_down:nn \subsupersep {\box_use:N \l_tmpa_box} }
  \hbox_set:Nn \l_tmpb_box
    { \box_move_up:nn \subsupersep {\box_use:N \l_tmpb_box} }
  \str_case:nnF {#2}
  {
    {l}{\use_i:nnn}
    {c}{\use_ii:nnn}
    {r}{\use_iii:nnn}
  }
  {
    \PackageWarning{realscripts}{
      Unknown~alignment~option~`#2'. \MessageBreak
      One~ of~ `l',~ `c',~ `r',~ only
    }
    \use_i:nnn
  }
  {
    \hbox_overlap_right:n { \box_use:N \l_tmpa_box }
    \hbox_overlap_right:n { \box_use:N \l_tmpb_box }
    \skip_horizontal:n {
      \dim_max:nn {\box_wd:N \l_tmpa_box} {\box_wd:N \l_tmpb_box}
    }
  }
  {
    \dim_compare:nTF { \box_wd:N \l_tmpa_box > \box_wd:N \l_tmpb_box }
    {
      \skip_horizontal:n {
        0.5\box_wd:N \l_tmpa_box-0.5\box_wd:N \l_tmpb_box
      }
      \box_use:N \l_tmpb_box
      \skip_horizontal:n {
        -0.5\box_wd:N \l_tmpa_box-0.5\box_wd:N \l_tmpb_box
      }
      \box_use:N \l_tmpa_box
    }
    {
      \skip_horizontal:n {
        0.5\box_wd:N \l_tmpb_box-0.5\box_wd:N \l_tmpa_box
      }
      \box_use:N \l_tmpa_box
      \skip_horizontal:n {
        -0.5\box_wd:N \l_tmpb_box-0.5\box_wd:N \l_tmpa_box
      }
      \box_use:N \l_tmpb_box
    }
  }
  {
    \skip_horizontal:n {
```

```
\def\showrefnames{}
\def\norefnames{}
\def\showcitenames{}
\def\nocitenames{}
\def\setonmsgs{}
\def\setoffmsgs{}
\def\checkunlbld{}
\def\ignoreunlbld{}
\newcommand*{\refcheckxrdoc}[2][]{}
```

---

File 395 **lwarp-register.sty**

§ 502 Package

# register

(*Emulates or patches code by* Matthew Lovell.)

Pkg register register is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{register}[2019/01/01]

\xpatchcmd{\register}
    {\centering}
    {%
        \begin{center}%
        \begin{lateximage}[-register-~\PackageDiagramAltText]%
    }
    {}
    {\LWR@patcherror{register}{register}}

\xpatchcmd{\endregister}
    {\leftskip}
    {%
        \end{lateximage}\end{center}%
        \leftskip%
    }%
    {}
    {\LWR@patcherror{register}{endregister}}

\expandafter\xapptocmd\csname register*\endcsname
    {%
        \begin{center}%
        \begin{lateximage}[-register-~\PackageDiagramAltText]%
    }
    {}
    {\LWR@patcherror{register}{register*}}

\expandafter\xpatchcmd\csname endregister*\endcsname
    {\leftskip}
    {%
        \end{lateximage}\end{center}%
        \leftskip%
    }%
    {}
```

```
    {\LWR@patcherror{register}{endregister*}}

\setlength{\regWidth}{5in}
```

File 396 **lwarp-relsize.sty**

§ 503 Package

# relsize

(*Emulates or patches code by* Donald Arseneau, Bernie Cosell, Matt Swift.)

Pkg relsize relsize is patched for use by lwarp, and emulated for MathJax.

For HTML, only the inline macros are supported: \textlarger, \textsmaller, and \textscale. Each becomes an inline span of a modified font-size.

\relsize, \larger, \smaller, and \relscale are ignored.

While creating SVG math for HTML, the original definitions are temporarilty restored, and so should work as expected.

⚠ not small The HTML browser's setting for minumum font size may limit how small the output will be displayed.

**for HTML output:**

```
\LWR@ProvidesPackagePass{relsize}[2013/03/29]

\let\LWR@origrelsize\relsize
\LetLtxMacro\LWR@origlarger\larger
\LetLtxMacro\LWR@origsmaller\smaller
\let\LWR@relscale\relscale
\LetLtxMacro\LWR@origtextlarger\textlarger
\LetLtxMacro\LWR@origtextsmaller\textsmaller
\let\LWR@textscale\textscale

\appto\LWR@restoreorigformatting{%
\let\relsize\LWR@origrelsize%
\LetLtxMacro\larger\LWR@origlarger%
\LetLtxMacro\smaller\LWR@origsmaller%
\let\relscale\LWR@relscale%
\LetLtxMacro\textlarger\LWR@origtextlarger%
\LetLtxMacro\textsmaller\LWR@origtextsmaller%
\let\textscale\LWR@textscale%
}

\newcounter{LWR@relsizetemp}

\renewcommand*{\relsize}[1]{}
\renewcommand*{\larger}[1][]{}
\renewcommand*{\smaller}[1][]{}
\renewcommand*{\relscale}[1]{}

\renewcommand*{\textlarger}[2][1]{%
\setcounter{LWR@relsizetemp}{100+(#1*20)}%
\InlineClass[font-size:\arabic{LWR@relsizetemp}\%]{textlarger}{#2}%
```

```
}

\renewcommand*{\textsmaller}[2][1]{%
\setcounter{LWR@relsizetemp}{100-(#1*20)}%
\InlineClass[font-size:\arabic{LWR@relsizetemp}\%]{textsmaller}{#2}%
}

\renewcommand*{\textscale}[2]{%
\setcounter{LWR@relsizetemp}{100*\real{#1}}%
\InlineClass[font-size:\arabic{LWR@relsizetemp}\%]{textscale}{#2}%
}
```

For MathJax:

```
\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\mathlarger}[1]{#1}}
\CustomizeMathJax{\newcommand{\mathsmaller}[1]{#1}}
\end{warpMathJax}
```

---

File 397 **lwarp-repeatindex.sty**

§ 504 Package

# repeatindex

Pkg repeatindex repeatindex is emulated for lwarp.

⚠ style file lwarp must be used with a special style file:

```
\usepackage[makeindex,makeindexStyle={lwarp_repeatindex}]{lwarp}
```

where `lwarp_repeatindex.ist` may be copied from the following modified version of `lwarp.ist`:

```
preamble
"\\begin{theindex}
  \\providecommand*\\lettergroupDefault[1]{}
  \\providecommand*\\lettergroup[1]{%
      \\par\\textbf{#1}\\par
      \\nopagebreak
  }
"
headings_flag 1
heading_prefix "
  \\lettergroup{"
heading_suffix "}"
delim_0 "], \\hyperindexref{"
delim_1 ", \\hyperindexref{"
delim_2 ", \\hyperindexref{"
delim_n "}, \\hyperindexref{"
delim_r "} -- \\hyperindexref{"
delim_t "}"
```

```
item_0 "\n  \\item ["
```

(The modifications are the `delim_0` and `item_0` entries.)

**for HTML output:**

```
\LWR@ProvidesPackageDrop{repeatindex}[2001/10/13]
```

In the lwarp core, `\LWR@indexitem` is modified to accept the optional `\item` argument.

```
\RequirePackage{makeidx}
\def\entryprefix{\itshape}
\def\entrypostfix{\dots}
```

---

File 398 **lwarp-repltext.sty**

## § 505 Package repltext

Pkg repltext repltext is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{repltext}[2020/09/25]
```

```
\newcommand{\repltext}[2]{#2}
\newcommand*{\prevrepl}{}
```

For MathJax:

```
\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\repltext}[2]{#2}}
\end{warpMathJax}
```

---

File 399 **lwarp-resizegather.sty**

## § 506 Package resizegather

Pkg resizegather resizegather is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{resizegather}[2016/05/16]
```

```
\newcommand*{\resizegathersetup}[1]{}
```

---

File 400 **lwarp-returntogrid.sty**

## § 507 Package returntogrid

Pkg returntogrid returntogrid is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{returntogrid}[2018/08/21]
```

File 404 **lwarp-romanbar.sty**

§ 511 Package

# romanbar

(*Emulates or patches code by* H.-Martin Münch.)

Pkg romanbar romanbar is patched for use by lwarp.

An inline class with an overline and underline is used.

**for HTML output:**

```
\LWR@ProvidesPackagePass{romanbar}[2012/01/01]

\DeclareRobustCommand{\Roman@bar}[1]{% #1 is in Roman, i.e. MMXII
\InlineClass[%
    text-decoration: overline underline ;
]{romanbar}{#1}%
}
```

File 405 **lwarp-romanbarpagenumber.sty**

§ 512 Package

# romanbarpagenumber

Pkg romanbarpagenumber romanbarpagenumber is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{romanbarpagenumber}[2015/02/06]
```

File 406 **lwarp-rotating.sty**

§ 513 Package

# rotating

(*Emulates or patches code by* Robin Fairbairns, Sebastian Rahtz, Leonor Barroca.)

Pkg rotating rotating is emulated.

All rotations are ignored in HTML output.

**for HTML output:**

```
\LWR@ProvidesPackagePass{rotating}[2016/08/11]
\RequirePackage{graphicx}

\LetLtxMacro\LWR@HTML@sidewaystable\table
\let\endLWR@HTML@sidewaystable\endtable
\LWR@formattedenv{sidewaystable}

\LetLtxMacro\LWR@HTML@sidewaysfigure\figure
\let\endLWR@HTML@sidewaysfigure\endfigure
\LWR@formattedenv{sidewaysfigure}
```

```
10
11 \newenvironment*{LWR@HTML@sideways}{}{}
12 \LWR@formattedenv{sideways}
13
14 \newenvironment*{LWR@HTML@turn}[1]{}{}
15 \LWR@formattedenv{turn}
16
17 \newenvironment*{LWR@HTML@rotate}[1]{}{}
18 \LWR@formattedenv{rotate}
19
20 \NewDocumentCommand{\LWR@HTML@turnbox}{m +m}{#2}
21 \LWR@formatted{turnbox}
22
23 \let\LWR@HTML@rotcaption\caption
24 \LWR@formatted{rotcaption}
25
26 \let\LWR@HTML@@makerotcaption\@makecaption
27 \LWR@formatted{@makerotcaption}
```

---

File 407 **lwarp-rotfloat.sty**

§ 514 Package

# rotfloat

(*Emulates or patches code by* Axel Sommerfeldt.)

Pkg rotfloat rotfloat is emulated.

**for HTML output:**

```
1 \LWR@ProvidesPackageDrop{rotfloat}[2004/01/04]
2
3 \RequirePackage{float}
4 \RequirePackage{rotating}
```

\newfloat {⟨*1: type*⟩} {⟨*2: placement*⟩} {⟨*3: ext*⟩} [⟨*4: within*⟩]

Emulates the \newfloat command from the float package. Sideways floats are \let to the same as regular floats.

"placement" is ignored.

```
5 \RenewDocumentCommand{\newfloat}{m m m o}{%
6 \IfValueTF{#4}%
7 {%
8     \DeclareFloatingEnvironment[fileext=#3,within=#4]{#1}%
9 }%
10 {%
11     \DeclareFloatingEnvironment[fileext=#3]{#1}%
12 }%
13 \csletcs{sideways#1}{#1}%
14 \csletcs{endsideways#1}{end#1}%
```

Remember the float style:

```
\csedef{LWR@floatstyle@#1}{\LWR@floatstyle}%
\csedef{LWR@floatstyle@sideways#1}{\LWR@floatstyle}%
```

newfloat package automatically creates the `\listof` command for new floats, but float does not, so remove `\listof` here in case it is manually created later:

```
\cslet{listof#1s}\relax%
\cslet{listof#1es}\relax%
\cslet{listofsideways#1s}\relax%
\cslet{listofsideways#1es}\relax%
}
```

---

File 408 **lwarp-rviewport.sty**

## § 515 Package rviewport

Pkg rviewport rviewport is honored inside a `lateximage`, and otherwise ignored for HTML output.

If rviewport is important for an image, enclose the image inside a `lateximage` environment.

**for HTML output:**

```
\LWR@ProvidesPackagePass{rviewport}[2011/08/27]
```

```
\define@key{igraph}{rviewport}{}
```

---

File 409 **lwarp-savetrees.sty**

## § 516 Package savetrees

Pkg savetrees savetrees is ignored.

**for HTML output:** Discard all options for lwarp-savetrees:

```
\LWR@ProvidesPackageDrop{savetrees}[2016/04/13]
```

---

File 410 **lwarp-scalefnt.sty**

## § 517 Package scalefnt

(*Emulates or patches code by* D. Carlisle.)

Pkg scalefnt scalefnt is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{scalefnt}
```

```
\DeclareRobustCommand\scalefont[1]{}
```

File 411 **lwarp-scalerel.sty**

## § 518 Package scalerel

(*Emulates or patches code by* Steven B. Segletes.)

Pkg scalerel scalerel is used as-is for SVG math, and is emulated and ignored for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{scalerel}[2016/12/29]
```

For MathJax:

```
\begin{warpMathJax}
\LWR@infoprocessingmathjax{scalerel}

\CustomizeMathJax{\newcommand{\scalerel}{\ifstar{\scalerelplain}{\scalerelplus}}}
\CustomizeMathJax{\newcommand{\scalerelplain}[3][]{#2}}
\CustomizeMathJax{\newcommand{\scalerelplus}[3][]{#2#3}}
\CustomizeMathJax{\newcommand{\stretchrel}{\ifstar{\stretchrelplain}{\stretchrelplus}}}
\CustomizeMathJax{\newcommand{\stretchrelplain}[3][]{#2}}
\CustomizeMathJax{\newcommand{\stretchrelplus}[3][]{#2#3}}
\CustomizeMathJax{\newcommand{\scaleto}[3][]{#2}}
\CustomizeMathJax{\newcommand{\stretchto}[3][]{#2}}
\CustomizeMathJax{\newcommand{\scaleleftright}[4][]{#2#3#4}}
\CustomizeMathJax{\newcommand{\stretchleftright}[4][]{#2#3#4}}
\CustomizeMathJax{\newcommand{\hstretch}[2]{#2}}
\CustomizeMathJax{\newcommand{\vstretch}[2]{#2}}
\CustomizeMathJax{\newcommand{\scaleobj}[2]{#2}}
\CustomizeMathJax{\newcommand{\ThisStyle}[1]{#1}}
\CustomizeMathJax{\newcommand{\SavedStyle}{}}
\CustomizeMathJax{\def\scriptstyleScaleFactor{.7}}
\CustomizeMathJax{\def\scriptscriptstyleScaleFactor{.5}}
\CustomizeMathJax{\newcommand{\discernmathstyle}{}}
\CustomizeMathJax{\newcommand{\ignoremathstyle}[1][T]{}}
\CustomizeMathJax{\newcommand{\Isnextbyte}[3][v]{}}
\end{warpMathJax}
```

File 412 **lwarp-schemata.sty**

## § 519 Package schemata

(*Emulates or patches code by* Charles P. Schaum.)

Pkg schemata schemata is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{schemata}[2020/11/23]

\LetLtxMacro\LWR@schemata@origschema\schema
\LetLtxMacro\LWR@schemata@origSchema\Schema
```

```
4
5 \renewcommand{\schema}[3][open]{%
6     \begin{lateximage}[-schemata-~\PackageDiagramAltText]%
7     \LWR@print@normalsize%
8     \LWR@schemata@origschema[#1]{#2}{#3}%
9     \end{lateximage}%
10 }
11
12 \renewcommand{\Schema}[5][open]{%
13     \begin{lateximage}[-schemata-~\PackageDiagramAltText]%
14     \LWR@print@normalsize%
15     \LWR@schemata@origSchema[#1]{#2}{#3}{#4}{#5}%
16     \end{lateximage}%
17 }
```

File 413 **lwarp-scrextend.sty**

§ 520 Package

# scrextend

Pkg scrextend scrextend is emulated.

This package may be loaded standalone, but is also loaded automatically if koma-script classes are in use. \DeclareDocumentCommand is used to overwrite the koma-script definitions.

**for HTML output:**

```
1 \LWR@ProvidesPackageDrop{scrextend}[2020/01/24]

2 \DeclareDocumentCommand{\setkomafont}{m m}{}
3 \DeclareDocumentCommand{\addkomafont}{m m}{}
4 \DeclareDocumentCommand{\usekomafont}{m}{}
5
6 \DeclareDocumentCommand{\usefontofkomafont}{m}{}
7 \DeclareDocumentCommand{\useencodingofkomafont}{m}{}
8 \DeclareDocumentCommand{\usesizeofkomafont}{m}{}
9 \DeclareDocumentCommand{\usefamilyofkomafont}{m}{}
10 \DeclareDocumentCommand{\useseriesofkomafont}{m}{}
11 \DeclareDocumentCommand{\useshapeofkomafont}{m}{}
12
13 \providecommand*{\coverpagetopmargin}{}
14 \providecommand*{\coverpagebottommargin}{}
15 \providecommand*{\coverpageleftmargin}{}
16 \providecommand*{\coverpagerightmargin}{}
17
```

Title page:

```
18 \AtBeginDocument{
19     \let\LWR@koma@orig@maketitle\maketitle
20     \DeclareDocumentCommand{\maketitle}{o}{\LWR@koma@orig@maketitle}
21 }
22
23 \DeclareDocumentCommand{\@maketitle}{}{%
```

```
    \ifdefvoid{\@titlehead}{}{%
        \begin{BlockClass}{titlehead}%
        \@titlehead%
        \end{BlockClass}%
    }%
    \ifdefvoid{\@subject}{}{%
        \begin{BlockClass}{subject}%
        \@subject%
        \end{BlockClass}%
    }%
    \LWR@stoppars%
    \LWR@htmltag{\LWR@tagtitle}%
    \@title%
    \LWR@htmltag{\LWR@tagtitleend}%
    \ifdefvoid{\@subtitle}{}{%
        \begin{BlockClass}{subtitle}%
        \@subtitle%
        \end{BlockClass}%
    }%
    \LWR@startpars%
    \begin{BlockClass}{author}%

    \renewcommand*{\cr}{}%
    \renewcommand*{\crcr}{}%
    \renewcommand*{\noalign}{}%

        \renewcommand{\and}{%
            \end{BlockClass}%
            \begin{BlockClass}{oneauthor}%
        }%
        \begin{BlockClass}{oneauthor}%
            \@author%
        \end{BlockClass}%
    \end{BlockClass}%
    \begin{BlockClass}{titledate}%
    \@date%
    \end{BlockClass}%
    \ifdefvoid{\@published}{}{%
        \begin{BlockClass}{published}%
        \@published%
        \end{BlockClass}%
    }%
}

\AddSubtitlePublished

\DeclareDocumentCommand{\extratitle}{m}{}
\DeclareDocumentCommand{\frontispiece}{m}{}

\def\@titlehead{}%
\DeclareDocumentCommand{\titlehead}{m}{\gdef\@titlehead{#1}}%

\def\@subject{}%
\DeclareDocumentCommand{\subject}{m}{\gdef\@subject{#1}}%

```

```
% \subtitle and \published are defined by \AddSubtitlePublished

\DeclareDocumentCommand{\publishers}{m}{\published{#1}}

\DeclareDocumentCommand{\uppertitleback}{m}{}
\DeclareDocumentCommand{\lowertitleback}{m}{}
\DeclareDocumentCommand{\dedication}{m}{}

\DeclareDocumentCommand{\ifthispageodd}{m m}{#1}

\DeclareDocumentCommand{\cleardoublepageusingstyle}{m}{}
\DeclareDocumentCommand{\cleardoubleemptypage}{}{}
\DeclareDocumentCommand{\cleardoubleplainpage}{}{}
\DeclareDocumentCommand{\cleardoublestandardpage}{}{}
\DeclareDocumentCommand{\cleardoubleoddpage}{}{}
\DeclareDocumentCommand{\cleardoubleoddpageusingstyle}{m}{}
\DeclareDocumentCommand{\cleardoubleoddemptypage}{}{}
\DeclareDocumentCommand{\cleardoubleoddplainpage}{}{}
\DeclareDocumentCommand{\cleardoubleoddstandardpage}{}{}
\DeclareDocumentCommand{\cleardoubleevenpage}{}{}
\DeclareDocumentCommand{\cleardoubleevenpageusingstyle}{m}{}
\DeclareDocumentCommand{\cleardoubleevenemptypage}{}{}
\DeclareDocumentCommand{\cleardoubleevenplainpage}{}{}
\DeclareDocumentCommand{\cleardoubleevenstandardpage}{}{}

\DeclareDocumentCommand{\multiplefootnoteseparator}{}{%
  \begingroup\let\thefootnotemark\multfootsep\@makefnmark\endgroup
}

\DeclareDocumentCommand{\multfootsep}{}{,}

\DeclareDocumentCommand{\footref}{m}{%
  \begingroup
    \unrestored@protected@xdef\@thefnmark{\ref{#1}}%
  \endgroup
  \@footnotemark
}

\DeclareDocumentCommand{\deffootnote}{o m m m}{}
\DeclareDocumentCommand{\deffootnotemark}{m}{}
\DeclareDocumentCommand{\setfootnoterule}{o m}{}
\DeclareDocumentCommand{\raggedfootnote}{}{}


\DeclareDocumentCommand{\dictum}{o m}{
\begin{LWR@BlockClassWP}{\LWR@print@mbox{text-align:right}}{}{dictum}
    #2
    \IfValueT{#1}
    {
        \LWR@stoppars%
        \ifbool{FormatWP}
     {\begin{BlockClass}[\LWR@print@mbox{border-top:} 1px solid gray]{dictumauthor}}
        {\begin{BlockClass}{dictumauthor}}
        \dictumauthorformat{#1}
        \end{BlockClass}
    }
```

```
\end{LWR@BlockClassWP}
}

\DeclareDocumentCommand{\dictumwidth}{}{}
\DeclareDocumentCommand{\dictumauthorformat}{m}{(#1)}
\DeclareDocumentCommand{\dictumrule}{}{}
\DeclareDocumentCommand{\raggeddictum}{}{}
\DeclareDocumentCommand{\raggeddictumtext}{}{}
\DeclareDocumentCommand{\raggeddictumauthor}{}{}

\DeclareDocumentEnvironment{labeling}{o m}
{%
\def\sc@septext{#1}%
\list{}{}%
\let\makelabel\labelinglabel%
}
{
\endlist
}

\DeclareDocumentCommand{\labelinglabel}{m}{%
#1 \qquad \sc@septext%
}

\let\addmargin\relax
\let\endaddmargin\relax
\cslet{addmargin*}{\relax}
\cslet{endaddmargin*}{\relax}


\NewDocumentEnvironment{addmargin}{s O{} m}
{
\LWR@stoppars%
\setlength{\LWR@templengthtwo}{#3}
\ifblank{#2}
{
    \begin{BlockClass}[
        \LWR@print@mbox{margin-left:\LWR@printlength{\LWR@templengthtwo}} ;
        \LWR@print@mbox{margin-right:\LWR@printlength{\LWR@templengthtwo}}
    ]{addmargin}
}
{
    \setlength{\LWR@templengthone}{#2}
    \begin{BlockClass}[
        \LWR@print@mbox{margin-left:\LWR@printlength{\LWR@templengthone}} ;
        \LWR@print@mbox{margin-right:\LWR@printlength{\LWR@templengthtwo}}
    ]{addmargin}
}
}
{\end{BlockClass}\LWR@startpars}
```

Ref to create a starred environment:
https://tex.stackexchange.com/questions/45401/use-the-s-star-argument-with-newdocumentenvironment

```

```

```
\ExplSyntaxOn
\cs_new:cpn {addmargin*} {\addmargin*}
\cs_new_eq:cN {endaddmargin*} \endaddmargin
\ExplSyntaxOff

\DeclareDocumentCommand{\marginline}{m}{\marginpar{#1}}
```

---

File 414 **lwarp-scrhack.sty**

# § 521 Package scrhack

Pkg scrhack scrhack is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{scrhack}[2018/03/30]
```

---

File 415 **lwarp-scrlayer.sty**

# § 522 Package scrlayer

(*Emulates or patches code by* Markus Kohm.)

Pkg scrlayer scrlayer is emulated.

⚠ Not fully tested! Please send bug reports!

**for HTML output:**

```
\LWR@ProvidesPackageDrop{scrlayer}[2018/03/30]

\newcommand*{\DeclareSectionNumberDepth}[2]{}
\newcommand*{\DeclareLayer}[2][]{}
\newcommand*{\DeclareNewLayer}[2][]{}
\newcommand*{\ProvideLayer}[2][]{}
\newcommand*{\RedeclareLayer}[2][]{}
\newcommand*{\ModifyLayer}[2][]{}
\newcommand*{\layerhalign}{}
\newcommand*{\layervalign}{}
\newcommand*{\layerxoffset}{}
\newcommand*{\layeryoffset}{}
\newcommand*{\layerwidth}{}
\newcommand*{\layerheight}{}
\providecommand*{\LenToUnit}[1]{\strip@pt\dimexpr#1*\p@/\unitlength}
\newcommand*{\putUL}[1]{}
\newcommand*{\putUR}[1]{}
\newcommand*{\putLL}[1]{}
\newcommand*{\putLR}[1]{}
\newcommand*{\putC}[1]{}
\newcommand*{\GetLayerContents}[1]{}
\newcommand{\IfLayerExists}[3]{#3}
\newcommand*{\DestroyLayer}[1]{}
\newcommand*{\layercontentsmeasure}{}
\newcommand*{\currentpagestyle}{}
```

```
\newcommand*{\BeforeSelectAnyPageStyle}[1]{}
\newcommand*{\AfterSelectAnyPageStyle}[1]{}
\newcommand*{\DeclarePageStyleAlias}[2]{}
\newcommand*{\DeclareNewPageStyleAlias}[2]{}
\newcommand*{\ProvidePageStyleAlias}[2]{}
\newcommand*{\RedeclarePageStyleAlias}[2]{}
\newcommand*{\DestroyPageStyleAlias}[1]{}
\newcommand*{\GetRealPageStyle}[1]{}
\newcommand*{\DeclarePageStyleByLayers}[3][]{}
\newcommand*{\DeclareNewPageStyleByLayers}[3][]{}
\newcommand*{\ProvidePageStyleByLayers}[3][]{}
\newcommand*{\RedeclarePageStyleByLayers}[3][]{}
\NewDocumentCommand{\ForEachLayerOfPageStyle}{s m m}{}
\newcommand*{\AddLayersToPageStyle}[2]{}
\newcommand*{\AddLayersAtBeginOfPageStyle}[2]{}
\newcommand*{\AddLayersAtEndOfPageStyle}[2]{}
\newcommand*{\RemoveLayersFromPageStyle}[2]{}
\newcommand*{\AddLayersToPageStyleBeforeLayer}[3]{}
\newcommand*{\AddLayersToPageStyleAfterLayer}[3]{}
\newcommand*{\UnifyLayersAtPageStyle}[1]{}
\newcommand*{\ModifyLayerPageStyleOptions}[2]{}
\newcommand*{\AddToLayerPageStyleOptions}[2]{}
\newcommand{\IfLayerPageStyleExists}[3]{#3}
\newcommand{\IfRealLayerPageStyleExists}[3]{#3}
\newcommand{\IfLayerAtPageStyle}[4]{#4}
\newcommand{\IfSomeLayerAtPageStyle}[4]{#4}
\newcommand{\IfLayersAtPageStyle}[4]{#4}
\newcommand*{\DestroyRealLayerPageStyle}[1]{}
\@ifundefined{footheight}{\newlength\footheight}{}
\DeclareDocumentCommand{\automark}{s o m}{}
\DeclareDocumentCommand{\manualmark}{}{}
\DeclareDocumentCommand{\MakeMarkcase}{m}{#1}


\newcommand{\partmarkformat}{}
\if@chapter
\newcommand{\chaptermarkformat}{}
\fi
\newcommand{\sectionmarkformat}{}
\DeclareDocumentCommand{\GenericMarkFormat}{m}{}

\newcommand*{\@mkleft}[1]{}
\newcommand*{\@mkright}[1]{}
\newcommand*{\@mkdouble}[1]{}
\newcommand*{\@mkboth}[2]{}
\newcommand{\scrlayerInitInterface}[1][]{}
\newcommand{\scrlayerAddToInterface}[3][]{}
\newcommand{\scrlayerAddCsToInterface}[3][]{}
\newcommand{\scrlayerOnAutoRemoveInterface}[2][]{}
```

File 416 **lwarp-scrlayer-notecolumn.sty**

## § 523 Package scrlayer-notecolumn

(*Emulates or patches code by* Markus Kohm.)

Pkg scrlayer-notecolumn scrlayer-notecolumn is emulated.

⚠ Not fully tested! Please send bug reports!

**for HTML output:**

```
\LWR@ProvidesPackageDrop{scrlayer-notecolumn}[2018/02/02]

\newcommand*{\DeclareNoteColumn}[2][]{}
\newcommand*{\DeclareNewNoteColumn}[2][]{}
\newcommand*{\ProvideNoteColumn}[2][]{}
\newcommand*{\RedeclareNoteColumn}[2][]{}
\NewDocumentCommand{\makenote}{s o m}{\marginpar{#3}}
\newcommand*{\syncwithnotecolumn}[1][]{}
\newcommand*{\syncwithnotecolumns}[1][]{}
\newcommand*{\clearnotecolumn}[1][]{}
\newcommand*{\clearnotecolumns}[1][]{}
```

---

File 417 **lwarp-scrlayer-scrpage.sty**

## § 524 Package scrlayer-scrpage

(*Emulates or patches code by* Markus Kohm.)

Pkg scrlayer-scrpage scrlayer-scrpage is ignored.

⚠ Not fully tested! Please send bug reports!

**for HTML output:**

```
\LWR@ProvidesPackageDrop{scrlayer-scrpage}[2018/03/30]

\@ifundefined{footheight}{\newlength\footheight}{}
\NewDocumentCommand{\lehead}{s o m}{}
\NewDocumentCommand{\cehead}{s o m}{}
\NewDocumentCommand{\rehead}{s o m}{}
\NewDocumentCommand{\lohead}{s o m}{}
\NewDocumentCommand{\cohead}{s o m}{}
\NewDocumentCommand{\rohead}{s o m}{}
\NewDocumentCommand{\lefoot}{s o m}{}
\NewDocumentCommand{\cefoot}{s o m}{}
\NewDocumentCommand{\refoot}{s o m}{}
\NewDocumentCommand{\lofoot}{s o m}{}
\NewDocumentCommand{\cofoot}{s o m}{}
\NewDocumentCommand{\rofoot}{s o m}{}
\NewDocumentCommand{\ohead}{s o m}{}
\NewDocumentCommand{\chead}{s o m}{}
\NewDocumentCommand{\ihead}{s o m}{}
\NewDocumentCommand{\ofoot}{s o m}{}
\NewDocumentCommand{\cfoot}{s o m}{}
\NewDocumentCommand{\ifoot}{s o m}{}
\DeclareDocumentCommand{\MakeMarkcase}{m}{#1}
\newcommand*{\defpairofpagestyles}[3][]{}
```

```
\newcommand*{\newpairofpagestyles}[3][]{}
\newcommand*{\renewpairofpagestyles}[3][]{}
\newcommand*{\providepairofpagestyles}[3][]{}

\newcommand*{\clearmainofpairofpagestyles}{}
\newcommand*{\clearplainofpairofpagestyles}{}
\newcommand*{\clearpairofpagestyles}{}
\newcommand*{\clearscrheadings}{}
\newcommand*{\clearscrheadfoot}{}
\newcommand*{\clearscrplain}{}

\NewDocumentCommand{\deftriplepagestyle}{m o o m m m m m m}{}
\NewDocumentCommand{\newtriplepagestyle}{m o o m m m m m m}{}
\NewDocumentCommand{\renewtriplepagestyle}{m o o m m m m m m}{}
\NewDocumentCommand{\providetriplepagestyle}{m o o m m m m m m}{}
\newcommand*{\defpagestyle}[3]{}
\newcommand*{\newpagestyle}[3]{}
\newcommand*{\providepagestyle}[3]{}
\newcommand*{\renewpagestyle}[3]{}
```

---

File 418 **lwarp-scrpage2.sty**

§ 525 Package

# scrpage2

(*Emulates or patches code by* Markus Kohm.)

Pkg scrpage2 scrpage2 is ignored.

⚠ Not fully tested! Please send bug reports!

**for HTML output:**

```
\LWR@ProvidesPackageDrop{scrpage2}[2018/03/30]

\@ifundefined{footheight}{\newlength\footheight}{}
\NewDocumentCommand{\lehead}{o m}{}
\NewDocumentCommand{\cehead}{o m}{}
\NewDocumentCommand{\rehead}{o m}{}
\NewDocumentCommand{\lohead}{o m}{}
\NewDocumentCommand{\cohead}{o m}{}
\NewDocumentCommand{\rohead}{o m}{}
\NewDocumentCommand{\lefoot}{o m}{}
\NewDocumentCommand{\cefoot}{o m}{}
\NewDocumentCommand{\refoot}{o m}{}
\NewDocumentCommand{\lofoot}{o m}{}
\NewDocumentCommand{\cofoot}{o m}{}
\NewDocumentCommand{\rofoot}{o m}{}
\NewDocumentCommand{\ohead}{o m}{}
\NewDocumentCommand{\chead}{o m}{}
\NewDocumentCommand{\ihead}{o m}{}
\NewDocumentCommand{\ofoot}{o m}{}
\NewDocumentCommand{\cfoot}{o m}{}
\NewDocumentCommand{\ifoot}{o m}{}
\DeclareDocumentCommand{\automark}{o m}{}
```

```
\DeclareDocumentCommand{\manualmark}{}{}
\DeclareDocumentCommand{\MakeMarkcase}{m}{#1}
\NewDocumentCommand{\deftripstyle}{m o o m m m m m}{}
\NewDocumentCommand{\defpagestyle}{s m m m}{}
\NewDocumentCommand{\newpagestyle}{s m m m}{}
\NewDocumentCommand{\renewpagestyle}{s m m m}{}
\NewDocumentCommand{\providepagestyle}{s m m m}{}
\newcommand{\partmarkformat}{}
\if@chapter
\newcommand{\chaptermarkformat}{}
\fi
\newcommand{\sectionmarkformat}{}
\newcommand{\subsectionmarkformat}{}
\newcommand{\subsubsectionmarkformat}{}
\newcommand{\paragraphmarkformat}{}
\newcommand{\subparagraphmarkformat}{}

\newcommand*{\clearscrheadings}{}
\newcommand*{\clearscrheadfoot}{}
\newcommand*{\clearscrplain}{}
```

---

File 419 **lwarp-section.sty**

§ 526 Package

# section

Pkg section section is ignored.

(*Emulates or patches code by* Oliver Pretzel.)

**for HTML output:**

```
\LWR@ProvidesPackageDrop{section}

\ifx\chapter\undefined
 \def\chsize{\Large}\def\hdsize{\huge}\else
 \def\chsize{\huge}\def\hdsize{\Huge}
\fi
\let\ttsize\LARGE
\let\ausize\large
\let\dasize\large
\let\secsize\Large
\let\subsize\large
\let\hdpos\raggedright
\newcounter{hddepth}
\let\fpind\relax
\def\ttfnt{}
\def\hdfnt{}
\def\fefnt{}
\def\thfnt{}
\def\pgfnt{}
\def\hmkfnt{}
\let\mkcse\uppercase
\def\hddot{}
\def\cpdot{:}
\def\nmdot{}
```

```
\ifx\secindent\undefined
 \newdimen\secindent
 \newskip\secpreskp
 \newskip\secpstskp
 \newdimen\subindent
 \newskip\subpreskp
 \newskip\subpstskp
 \newskip\parpstskp
 \newcount\c@hddepth
\fi
```

File 420 **lwarp-sectionbreak.sty**

## § 527 Package sectionbreak

(*Emulates or patches code by* Michal Hoftich.)

Pkg sectionbreak sectionbreak is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{sectionbreak}[2018-01-03]

\renewcommand\asterism{\HTMLunicode{2042}}

\renewcommand\pre@sectionbreak{}
\renewcommand\post@sectionbreak{}

\renewcommand\print@sectionbreak[1]{%
\begin{center}
#1
\end{center}
}

```

File 421 **lwarp-sectsty.sty**

## § 528 Package sectsty

(*Emulates or patches code by* Rowland McDonnell.)

Pkg sectsty sectsty is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{sectsty}[2002/02/25]

\newcommand*{\partfont}          [1] {}
\newcommand*{\partnumberfont}    [1] {}
\newcommand*{\parttitlefont}     [1] {}
\newcommand*{\chapterfont}       [1] {}
\newcommand*{\chapternumberfont} [1] {}
\newcommand*{\chaptertitlefont}  [1] {}
\newcommand*{\sectionfont}       [1] {}
\newcommand*{\subsectionfont}    [1] {}
```

```
\newcommand*{\subsubsectionfont} [1] {}
\newcommand*{\paragraphfont}     [1] {}
\newcommand*{\subparagraphfont}  [1] {}
\newcommand*{\minisecfont}  [1] {}
\newcommand*{\allsectionsfont}[1] {}
\newcommand{\nohang}{}
```

`\sectionrule` is only to be used in `*font` commands, thus it is ignored.

```
\newcommand*{\sectionrule}[5]{}

\def\ulemheading#1#2{}
```

---

File 422 **lwarp-selectp.sty**

## § 529 Package selectp

Pkg selectp selectp is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{selectp}% no date given

\newcommand*{\outputonly}[1]{}
```

---

File 423 **lwarp-semantic-markup.sty**

## § 530 Package semantic-markup

(*Emulates or patches code by* Andrew A. Cashner.)

Pkg semantic-markup semantic-markup is patched for use by lwarp.

⚠ If using the endnotes option, add `\theendnotes` where desired.

**for HTML output:**

```
\LWR@ProvidesPackagePass{semantic-markup}[2018/05/21]
```

The endnotes must be printed by the user before the end of the document, since the end is after the HTML footer, etc.

```
\ifendnotes
\RenewDocumentCommand{\SetupEndnotes}{}{%
    \let\footnote=\endnote
%     \AtEndDocument{\DoBeforeEndnotes{\EndnoteFont\theendnotes}}%
}
\fi
```

HTML unicode characters from musicography are used.

```
\RequirePackage{musicography}

```

```
\let\fl\musFlat
\let\sh\musSharp
\let\na\musNatural
```

The `\musfig` is placed inside a hashed image, with a simple `alt` tag.

```
\RequirePackage{amsmath}

\RenewDocumentCommand{\musfig}{ m m }{%
    \LWR@subsingledollar*%
        {#1/#2}% alt tag
        {musfig}% addl' hashing
        {% contents
            \LWR@origensuredmath{%
                \genfrac{}{}{0pt}{1}{\text{#1}}{\text{#2}}%
            }%
        }%
}
```

The `\meter` is taken from musicography, and becomes a hashed image with a simple `alt` tag.

```
\RenewDocumentCommand{\meter}{ m m }{%
    \musMeter{#1}{#2}%
}
```

---

File 424 **lwarp-seqsplit.sty**

§ 531 Package

# seqsplit

(*Emulates or patches code by* Boris Veytsman.)

Pkg seqsplit seqsplit is patched for use by lwarp.

For HTML output, the results are similar to print mode, and respond to window size.

⚠ SVG math results For SVG math, the output differs from print mode in that the contents are formatted in a minipage, which is then inline with the surrounding math.

For MathJax, the contents are used as-is.

**for HTML output:**

```
\LWR@ProvidesPackagePass{seqsplit}[2006/08/07]
```

Special handling because lwarp uses a box for SVG math, which does not normally allow line breaks, so a print-mode `minipage` must be used to allow line breaks. The `minipage` will not be wrapped inline with any surrounding math.

```
\begin{warpHTML}
\LetLtxMacro\LWR@orig@seqsplit\seqsplit

\renewcommand*{\seqsplit}[1]{%
    \ifmmode%
        \begin{LWR@print@minipage}{6in}%
```

```
        \LWR@orig@seqsplit{#1}%
        \end{LWR@print@minipage}%
    \else%
        \InlineClass[word-wrap:break-word]{seqsplit}{\LWR@orig@seqsplit{#1}}%
    \fi
}
```

Between characters, an empty HTML comment is placed to allow a line wrap in the HTML source, without adding spaces in the output.

```
\AtBeginDocument{
    \newcommand*{\LWR@HTML@seqinsert}{%
        \LWR@htmlcomment{ }%
    }
    \LWR@formatted{seqinsert}
}
\end{warpHTML}

\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\seqsplit}[1]{#1}}
\end{warpMathJax}
```

---

File 425 **lwarp-setspace.sty**

## § 532 Package setspace

(*Emulates or patches code by* Robin Fairbairns.)

Pkg setspace setspace is emulated.

Discard all options for lwarp-setspace:

**for HTML output:**

```
\LWR@ProvidesPackageDrop{setspace}[2011/12/19]

\newcommand*{\setstretch}[1]{}
\newcommand*{\SetSinglespace}[1]{}
\newcommand*{\singlespacing}{}
\newcommand*{\onehalfspacing}{}
\newcommand*{\doublespacing}{}

\newenvironment*{singlespace}
{
\LWR@forcenewpage
\BlockClass{singlespace}
}
{\endBlockClass}

\newenvironment*{singlespace*}
{
\LWR@forcenewpage
\BlockClass{singlespace}
}
{\endBlockClass}
```

```
\newenvironment*{spacing}[1]{

}{

}

\newenvironment*{onehalfspace}
{
\LWR@forcenewpage
\BlockClass{onehalfspace}
}
{\endBlockClass}

\newenvironment*{doublespace}
{
\LWR@forcenewpage
\BlockClass{doublespace}
}
{\endBlockClass}
```

File 426 **lwarp-shadethm.sty**

## § 533 Package shadethm

(*Emulates or patches code by* Jim Hefferon.)

Pkg shadethm shadethm is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{shadethm}[1999/11/23]

\newenvironment{LWR@HTML@shadebox}
{%
    \convertcolorspec{named}{shadethmcolor}{HTML}\LWR@tempcolor%
    \convertcolorspec{named}{shaderulecolor}{HTML}\LWR@tempcolortwo%
    \begin{BlockClass}[%
        background: \LWR@origpound\LWR@tempcolor ;
        border: 1px solid \LWR@origpound\LWR@tempcolortwo ;
    ]{shadebox}
}%
{\end{BlockClass}}
\LWR@formattedenv{shadebox}
```

File 427 **lwarp-shadow.sty**

## § 534 Package shadow

(*Emulates or patches code by* Mauro Orlandini.)

Pkg shadow shadow is emulated.

**for HTML output:** Discard all options for lwarp-shadow:

```
\LWR@ProvidesPackageDrop{shadow}[2003/02/19]

\newdimen\sboxsep
\newdimen\sboxrule
\newdimen\sdim

\newcommand{\shabox}[1]{%
\InlineClass{shabox}{#1}%
}
```

---

File 428 **lwarp-shapepar.sty**

## § 535 Package shapepar

(*Emulates or patches code by* Donald Arseneau.)

Pkg shapepar shapepar is patched for use by lwarp. Shapes appear in print mode, as well as inside a `latexmage`, but are ignored for HTML.

**for HTML output:**

```
\LWR@ProvidesPackagePass{shapepar}[2013/03/26]

\newcommand*{\LWR@HTML@shapepar}[2][]{}
\LWR@formatted{shapepar}

\NewDocumentCommand{\LWR@HTML@cutout}{m d()}{}
\LWR@formatted{cutout}
```

---

File 429 **lwarp-showidx.sty**

## § 536 Package showidx

Pkg showidx showidx is ignored.

**for HTML output:** Discard all options for lwarp-showidx:

```
\LWR@ProvidesPackageDrop{showidx}[2014/09/29]
```

`\@wrindex` is redefined `\AtBeginDocument` by the lwarp core.

---

File 430 **lwarp-showkeys.sty**

## § 537 Package showkeys

(*Emulates or patches code by* David Carlisle, Morten Høgholm.)

Pkg showkeys showkeys is ignored.

**for HTML output:** Discard all options for lwarp-showkeys:

```
\LWR@ProvidesPackageDrop{showkeys}[2014/10/28]
\NewDocumentCommand{\showkeys}{s}{}
```

---

File 431 **lwarp-showtags.sty**

§ 538 Package

# showtags

Pkg showtags showtags is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{showtags}% no version is given
\newcommand{\thecitetag}[1]{}
```

---

File 432 **lwarp-shuffle.sty**

§ 539 Package

# shuffle

(*Emulates or patches code by* Julian Gilbey and Antoine Lejay.)

Pkg shuffle shuffle is emulated for SVG math, and also emulated for MathJax.

The font used for shuffle may not render correctly when converted to SVG math, so a `picture` environment drawing is used instead.

For MathJax, the Unicode character is used, and for `\cshuffle` a `\bar` is added.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{shuffle}[2008/10/27]
\LWR@origRequirePackage{lwarp-common-mathjax-overlaysymbols}

\newcommand*{\LWR@shuffle@start}{%
    \hspace*{.2em}
    \begin{picture}(.75,0.65)
    \setlength{\unitlength}{1em}
    \put(0,0){\line(1,0){.75}}
    \put(0,0){\line(0,1){.5}}
    \put(.375,0){\line(0,1){.5}}
    \put(.75,0){\line(0,1){.5}}
}

\newcommand*{\LWR@shuffle@finish}{%
    \end{picture}
    \hspace*{.75em}
    \hspace*{.2em}
}

\newcommand*{\shuffle}{%
    \LWR@shuffle@start%
```

```
    \LWR@shuffle@finish%
}

\newcommand*{\cshuffle}{%
    \LWR@shuffle@start%
    \put(.05,.65){\line(1,0){.65}}%
    \LWR@shuffle@finish%
}


\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\shuffle}{\mathbin{\unicode{0x29E2}}}}
\CustomizeMathJax{\newcommand{\cshuffle}{%
    \mathbin{\LWRoverlaysymbols{\raise{.6ex}{-}}{\unicode{0x29E2}}}%
}}
\end{warpMathJax}
```

File 433 **lwarp-sidecap.sty**

§ 540 Package

# sidecap

(*Emulates or patches code by* Rolf Niepraschk, Hubert Gässlein.)

Pkg sidecap sidecap is emulated.

**for HTML output:** Discard all options for lwarp-sidecap.

```
\LWR@ProvidesPackageDrop{sidecap}[2003/06/06]
```

See:
http://tex.stackexchange.com/questions/45401/use-the-s-star-argument-with-newdocumentenvironment
regarding the creation of starred environments with xparse.

```
\NewDocumentEnvironment{SCtable}{soo}
{\IfValueTF{#3}{\table[#3]}{\table}}
{\endtable}

\ExplSyntaxOn
\cs_new:cpn {SCtable*} {\SCtable*}
\cs_new_eq:cN {endSCtable*} \endSCtable
\ExplSyntaxOff


\NewDocumentEnvironment{SCfigure}{soo}
{\IfValueTF{#3}{\figure[#3]}{\figure}}
{\endfigure}

\ExplSyntaxOn
\cs_new:cpn {SCfigure*} {\SCfigure*}
\cs_new_eq:cN {endSCfigure*} \endSCfigure
\ExplSyntaxOff

```

```
\RenewDocumentEnvironment{marginfigure}{o}
  {\begin{KFLTsidenotes@marginfloat}{figure}}
  {\end{KFLTsidenotes@marginfloat}}

\RenewDocumentEnvironment{margintable}{o}
  {\begin{KFLTsidenotes@marginfloat}{table}}
  {\end{KFLTsidenotes@marginfloat}}
```

The following were changed by sidenotes, and now are reset back to their lwarp-supported originals:

Restoring the definition from the LaTeX $2_\varepsilon$ `article.cls` source:

```
\renewenvironment{figure*}
               {\@dblfloat{figure}}
               {\end@dblfloat}

\renewenvironment{table*}
               {\@dblfloat{table}}
               {\end@dblfloat}
```

For MathJax:

⚠ Note that sidenotes does not support `\sidenote` inside math in print mode. Use `\sidenotemark` and `\sidenotetext` instead.

```
\begin{warpMathJax}
\providecommand{\sidenotename}{sidenote}
\appto\LWR@syncnotenumbers{\LWR@synconenotenumber{LWRsidenote}{\thesidenote}}
\appto\LWR@syncnotenames{\LWR@synconenotename{LWRsidenote}{\sidenotename}}
\CustomizeMathJax{\def\LWRsidenote{1}}
\CustomizeMathJax{\newcommand{\sidenotemark}[1][\LWRsidenote]{{}^{\mathrm{#1}}}}
\end{warpMathJax}
```

The following is not defined since is not allowed inside math in print mode, and also would have to be modified to parse the optional offset argument:

```
\CustomizeMathJax{\newcommand{\sidenote}[2][\LWRsidenote]{{}^{\mathrm{#1}}}}
```

---

File 435 **`lwarp-simplebnf.sty`**

§ 542 Package

# simplebnf

(*Emulates or patches code by* Jay Lee.)

Pkg `simplebnf` simplebnf is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{simplebnf}[2020/09/01]
```

The entire object is placed inside a `lateximage` whose `alt` text is the LaTeX source BNF expression.

```
\ExplSyntaxOn

\RenewDocumentEnvironment { bnfgrammar } { +b }
 {
   %% \l__input_seq is a list of term definitions.
   \regex_split:nnN { ;; } { #1 } \l__input_seq
   \begin{center}
   \begin{lateximage}[#1]%     lwarp
     \tl_set:Nn \l__table_tl
       {
         \begin{tabular}{lcll}
       }
   \bool_set_true:N \l_tmp_first_term % Is this the first term in this grammar?
   \seq_map_inline:Nn \l__input_seq
     {
       %% \l__term_seq    - (term, rhses)...
       %% \l__term_tl     - term
       %% \l__keypairs_tl - rhses
       \regex_split:nnN { ::= } { ##1 } \l__term_seq
       \seq_pop_left:NN \l__term_seq \l__term_tl
       \seq_pop_left:NN \l__term_seq \l__keypairs_tl

       \regex_replace_once:nnN { ^\s+ } {} \l__term_tl

       \bool_if:NTF \l_tmp_first_term
         {
           \bool_set_false:N \l_tmp_first_term
         }
         {
           \tl_put_right:Nn \l__table_tl { \\ }
         }
       \tl_put_right:Nx \l__table_tl
         {
           \bnfexpr { \l__term_tl } & \g__simplebnf_defeq_tl &
         }
       %% \l__keypairs_seq - (rhs:annot | rhs)...
       \seq_set_split:NnV \l__keypairs_seq { | } \l__keypairs_tl

       \bool_set_true:N \l__first_rhs
       \seq_map_function:NN \l__keypairs_seq \simplebnf_typeset_rhs:n
     }

   \tl_put_right:Nn \l__table_tl { \end{tabular} }
   \tl_use:N \l__table_tl
   \end{lateximage}%       lwarp
   \end{center}
 }
 { }

\ExplSyntaxOff
```

File 436 **lwarp-SIunits.sty**

For MathJax:

```
\begin{warpMathJax}
\LWR@infoprocessingmathjax{SIunits}

\CustomizeMathJax{\newcommand{\one}{}}
\CustomizeMathJax{\newcommand{\meter}{\metre}}
\CustomizeMathJax{\newcommand{\deka}{\deca}}
\CustomizeMathJax{\newcommand{\dekad}{\decad}}
\CustomizeMathJax{\newcommand{\per}{/}}
\CustomizeMathJax{\newcommand{\usk}{\;}}
\CustomizeMathJax{\newcommand{\unit}[2]{#1\,{#2}}}
\CustomizeMathJax{\newcommand{\power}[2]{#1^{#2}}}

\AtBeginDocument{%
 \if@redefsquare
  \CustomizeMathJax{\renewcommand{\square}[1]{\power{#1}{2}}}
 \else
   \if@defsquaren
    \CustomizeMathJax{\newcommand{\squaren}[1]{\power{#1}{2}}}
   \else
     \CustomizeMathJax{\renewcommand{\square}[1]{\power{#1}{2}}}
   \fi %\if@defsquaren
 \fi   %\if@redefsquare
}     %\AtBeginDocument

\CustomizeMathJax{\newcommand{\squared}{^{2}}}
\CustomizeMathJax{\newcommand{\cubic}[1]{\power{#1}{3}}}
\CustomizeMathJax{\newcommand{\cubed}{^{3}}}
\CustomizeMathJax{\newcommand{\fourth}[1]{\power{#1}{4}}}
\CustomizeMathJax{\newcommand{\reciprocal}[1]{\power{#1}{-1}}}
\CustomizeMathJax{\newcommand{\rp}{\reciprocal}}
\CustomizeMathJax{\newcommand{\rpsquare}[1]{\power{#1}{-2}}}
\CustomizeMathJax{\newcommand{\rpsquared}{^{-2}}}
\CustomizeMathJax{\newcommand{\rpcubic}[1]{\power{#1}{-3}}}
\CustomizeMathJax{\newcommand{\rpcubed}{^{-3}}}
\CustomizeMathJax{\newcommand{\rpfourth}[1]{\power{#1}{-4}}}
\CustomizeMathJax{\newcommand{\yocto}{\mathrm{y}}}
\CustomizeMathJax{\newcommand{\zepto}{\mathrm{z}}}
\CustomizeMathJax{\newcommand{\atto}{\mathrm{a}}}
\CustomizeMathJax{\newcommand{\femto}{\mathrm{f}}}
\CustomizeMathJax{\newcommand{\pico}{\mathrm{p}}}
\CustomizeMathJax{\newcommand{\nano}{\mathrm{n}}}
\CustomizeMathJax{\newcommand{\micro}{\mathrm{\unicode{x00B5}}}}
\CustomizeMathJax{\newcommand{\milli}{\mathrm{m}}}
\CustomizeMathJax{\newcommand{\centi}{\mathrm{c}}}
\CustomizeMathJax{\newcommand{\deci}{\mathrm{d}}}
\CustomizeMathJax{\newcommand{\deca}{\mathrm{da}}}
\CustomizeMathJax{\newcommand{\hecto}{\mathrm{h}}}
\CustomizeMathJax{\newcommand{\kilo}{\mathrm{k}}}
\CustomizeMathJax{\newcommand{\mega}{\mathrm{M}}}
\CustomizeMathJax{\newcommand{\giga}{\mathrm{G}}}
\CustomizeMathJax{\newcommand{\tera}{\mathrm{T}}}
\CustomizeMathJax{\newcommand{\peta}{\mathrm{P}}}
\CustomizeMathJax{\newcommand{\exa}{\mathrm{E}}}
```

```
\CustomizeMathJax{\newcommand{\zetta}{\mathrm{Z}}}
\CustomizeMathJax{\newcommand{\yotta}{\mathrm{Y}}}
\CustomizeMathJax{\newcommand{\yoctod}{\power{10}{-24}}}
\CustomizeMathJax{\newcommand{\zeptod}{\power{10}{-21}}}
\CustomizeMathJax{\newcommand{\attod}{\power{10}{-18}}}
\CustomizeMathJax{\newcommand{\femtod}{\power{10}{-15}}}
\CustomizeMathJax{\newcommand{\picod}{\power{10}{-12}}}
\CustomizeMathJax{\newcommand{\nanod}{\power{10}{-9}}}
\CustomizeMathJax{\newcommand{\microd}{\power{10}{-6}}}
\CustomizeMathJax{\newcommand{\millid}{\power{10}{-3}}}
\CustomizeMathJax{\newcommand{\centid}{\power{10}{-2}}}
\CustomizeMathJax{\newcommand{\decid}{\power{10}{-1}}}
\CustomizeMathJax{\newcommand{\decad}{\power{10}{1}}}
\CustomizeMathJax{\newcommand{\hectod}{\power{10}{2}}}
\CustomizeMathJax{\newcommand{\kilod}{\power{10}{3}}}
\CustomizeMathJax{\newcommand{\megad}{\power{10}{6}}}
\CustomizeMathJax{\newcommand{\gigad}{\power{10}{9}}}
\CustomizeMathJax{\newcommand{\terad}{\power{10}{12}}}
\CustomizeMathJax{\newcommand{\petad}{\power{10}{15}}}
\CustomizeMathJax{\newcommand{\exad}{\power{10}{18}}}
\CustomizeMathJax{\newcommand{\zettad}{\power{10}{21}}}
\CustomizeMathJax{\newcommand{\yottad}{\power{10}{24}}}
\CustomizeMathJax{\newcommand{\gram}{\mathrm{g}}}
\CustomizeMathJax{\newcommand{\metre}{\mathrm{m}}}
\CustomizeMathJax{\newcommand{\kilogram}{\kilo\gram}}
\CustomizeMathJax{\newcommand{\second}{\mathrm{s}}}
\CustomizeMathJax{\newcommand{\ampere}{\mathrm{A}}}
\CustomizeMathJax{\newcommand{\kelvin}{\mathrm{K}}}
\CustomizeMathJax{\newcommand{\mole}{\mathrm{mol}}}
\CustomizeMathJax{\newcommand{\candela}{\mathrm{cd}}}
\CustomizeMathJax{\newcommand{\radian}{\mathrm{rad}}}
\CustomizeMathJax{\newcommand{\steradian}{\mathrm{sr}}}
\CustomizeMathJax{\newcommand{\hertz}{\mathrm{Hz}}}
\CustomizeMathJax{\newcommand{\newton}{\mathrm{N}}}
\CustomizeMathJax{\newcommand{\pascal}{\mathrm{Pa}}}
\CustomizeMathJax{\newcommand{\joule}{\mathrm{J}}}
\CustomizeMathJax{\newcommand{\watt}{\mathrm{W}}}
\CustomizeMathJax{\newcommand{\coulomb}{\mathrm{C}}}
\CustomizeMathJax{\newcommand{\volt}{\mathrm{V}}}
\CustomizeMathJax{\newcommand{\farad}{\mathrm{F}}}
\CustomizeMathJax{\newcommand{\ohm}{\mathrm{\Omega}}}
\CustomizeMathJax{\newcommand{\siemens}{\mathrm{S}}}
\CustomizeMathJax{\newcommand{\weber}{\mathrm{Wb}}}
\CustomizeMathJax{\newcommand{\tesla}{\mathrm{T}}}
\CustomizeMathJax{\newcommand{\henry}{\mathrm{H}}}
\CustomizeMathJax{\newcommand{\degreecelsius}{\mathrm{\unicode{x2103}}}}
\CustomizeMathJax{\newcommand{\celsius}{\degreecelsius}}
\CustomizeMathJax{\newcommand{\lumen}{\mathrm{lm}}}
\CustomizeMathJax{\newcommand{\lux}{\mathrm{lx}}}
\CustomizeMathJax{\newcommand{\becquerel}{\mathrm{Bq}}}
\CustomizeMathJax{\newcommand{\sievert}{\mathrm{Sv}}}
\CustomizeMathJax{\newcommand{\katal}{\mathrm{kat}}}

\ifdef{\radianbase}{
\CustomizeMathJax{\newcommand{\radianbase}%
```

```
        {\metre\usk\reciprocal\metre}}
\CustomizeMathJax{\newcommand{\steradianbase}%
        {\squaremetre\usk\rpsquare\metre}}
\CustomizeMathJax{\newcommand{\hertzbase}%
        {\reciprocal\second}}
\CustomizeMathJax{\newcommand{\newtonbase}%
        {\metre\usk\kilogram\usk\second\rpsquared}}
\CustomizeMathJax{\newcommand{\pascalbase}%
        {\reciprocal\metre\usk\kilogram\usk\second\rpsquared}}
\CustomizeMathJax{\newcommand{\joulebase}%
        {\squaremetre\usk\kilogram\usk\second\rpsquared}}
\CustomizeMathJax{\newcommand{\wattbase}%
        {\squaremetre\usk\kilogram\usk\rpcubic\second}}
\CustomizeMathJax{\newcommand{\coulombbase}%
        {\ampere\usk\second}}
\CustomizeMathJax{\newcommand{\voltbase}%
        {\squaremetre\usk\kilogram\usk\rpcubic\second\usk\reciprocal\ampere}}
\CustomizeMathJax{\newcommand{\faradbase}%
     {\rpsquare\metre\usk\reciprocal\kilogram\usk\fourth\second\usk\ampere\squared}}
\CustomizeMathJax{\newcommand{\ohmbase}%
        {\squaremetre\usk\kilogram\usk\rpcubic\second\usk\rpsquare\ampere}}
\CustomizeMathJax{\newcommand{\siemensbase}%
     {\rpsquare\metre\usk\reciprocal\kilogram\usk\cubic\second\usk\ampere\squared}}
\CustomizeMathJax{\newcommand{\weberbase}%
       {\squaremetre\usk\kilogram\usk\second\rpsquared\usk\reciprocal\ampere}}
\CustomizeMathJax{\newcommand{\teslabase}%
        {\kilogram\usk\second\rpsquared\usk\reciprocal\ampere}}
\CustomizeMathJax{\newcommand{\henrybase}%
        {\squaremetre\usk\kilogram\usk\second\rpsquared\usk\rpsquare\ampere}}
\CustomizeMathJax{\newcommand{\celsiusbase}%
        {\kelvin}}
\CustomizeMathJax{\newcommand{\lumenbase}%
        {\candela\usk\squaremetre\usk\rpsquare\metre}}
\CustomizeMathJax{\newcommand{\luxbase}%
        {\candela\usk\squaremetre\usk\rpfourth\metre}}
\CustomizeMathJax{\newcommand{\becquerelbase}%
        {\hertzbase}}
\CustomizeMathJax{\newcommand{\graybase}%
        {\squaremetre\usk\second\rpsquared}}
\CustomizeMathJax{\newcommand{\sievertbase}%
        {\graybase}}
\CustomizeMathJax{\newcommand{\katalbase}%
        {\rp\second\usk\mole }}
}{}

\ifdef{\derradian}{
\CustomizeMathJax{\newcommand{\derradian}%
        {\metre\usk\reciprocal\metre}}
\CustomizeMathJax{\newcommand{\dersteradian}%
        {\squaremetre\usk\rpsquare\metre}}
\CustomizeMathJax{\newcommand{\derhertz}%
        {\reciprocal\second}}
\CustomizeMathJax{\newcommand{\dernewton}%
        {\metre\usk\kilogram\usk\second\rpsquared}}
\CustomizeMathJax{\newcommand{\derpascal}%
```

```
        {\newton\usk\rpsquare\metre}}
\CustomizeMathJax{\newcommand{\derjoule}%
        {\newton\usk\metre}}
\CustomizeMathJax{\newcommand{\derwatt}%
        {\joule\usk\reciprocal\second}}
\CustomizeMathJax{\newcommand{\dercoulomb}%
        {\ampere\usk\second}}
\CustomizeMathJax{\newcommand{\dervolt}%
        {\watt\usk\reciprocal\ampere}}
\CustomizeMathJax{\newcommand{\derfarad}%
        {\coulomb\usk\reciprocal\volt}}
\CustomizeMathJax{\newcommand{\derohm}%
        {\volt\usk\reciprocal\ampere}}
\CustomizeMathJax{\newcommand{\dersiemens}%
        {\ampere\usk\reciprocal\volt}}
\CustomizeMathJax{\newcommand{\derweber}%
       {\squaremetre\usk\kilogram\usk\second\rpsquared\usk\reciprocal\ampere}}
\CustomizeMathJax{\newcommand{\dertesla}%
        {\weber\usk\rpsquare\metre}}
\CustomizeMathJax{\newcommand{\derhenry}%
        {\weber\usk\reciprocal\ampere}}
\CustomizeMathJax{\newcommand{\dercelsius}%
        {\kelvin}}
\CustomizeMathJax{\newcommand{\derlumen}%
        {\candela\usk\steradian}}
\CustomizeMathJax{\newcommand{\derlux}%
        {\lumen\usk\rpsquare\metre}}
\CustomizeMathJax{\newcommand{\derbecquerel}%
        {\derhertz}}
\CustomizeMathJax{\newcommand{\dergray}%
        {\joule\usk\reciprocal\kilogram}}
\CustomizeMathJax{\newcommand{\dersievert}%
        {\dergray}}
\CustomizeMathJax{\newcommand{\derkatal}%
        {\katalbase}}
}{}

\CustomizeMathJax{\newcommand{\minute}{\mathrm{min}}}
\CustomizeMathJax{\newcommand{\hour}{\mathrm{h}}}
\CustomizeMathJax{\newcommand{\dday}{\mathrm{d}}}
\CustomizeMathJax{\newcommand{\degree}{\mathrm{^\circ}}}
\CustomizeMathJax{\newcommand{\paminute}{^\prime}}
\CustomizeMathJax{\newcommand{\arcminute}{^\prime}}
\CustomizeMathJax{\newcommand{\pasecond}{^{\prime\prime}}}
\CustomizeMathJax{\newcommand{\arcsecond}{^{\prime\prime}}}
\CustomizeMathJax{\newcommand{\ton}{\mathrm{t}}}
\CustomizeMathJax{\newcommand{\tonne}{\mathrm{t}}}
\CustomizeMathJax{\newcommand{\liter}{\mathrm{L}}}
\CustomizeMathJax{\newcommand{\litre}{\mathrm{l}}}
\CustomizeMathJax{\newcommand{\neper}{\mathrm{Np}}}
\CustomizeMathJax{\newcommand{\bel}{\mathrm{B}}}
\CustomizeMathJax{\newcommand{\curie}{\mathrm{Ci}}}
\CustomizeMathJax{\newcommand{\rad}{\mathrm{rad}}}
\CustomizeMathJax{\newcommand{\arad}{\mathrm{rd}}}
\CustomizeMathJax{\newcommand{\rem}{\mathrm{rem}}}
```

```
\CustomizeMathJax{\newcommand{\roentgen}{\mathrm{R}}}
\CustomizeMathJax{\newcommand{\electronvolt}{\mathrm{\mathrm{eV}}}}
\CustomizeMathJax{\newcommand{\atomicmass}{\mathrm{u}}}
\CustomizeMathJax{\newcommand{\atomicmassunit}{\mathrm{u}}}
\CustomizeMathJax{\newcommand{\dalton}{\mathrm{Da}}}
\CustomizeMathJax{\newcommand{\are}{\mathrm{a}}}
\CustomizeMathJax{\newcommand{\hectare}{\mathrm{\hecto\are}}}
\CustomizeMathJax{\newcommand{\barn}{\mathrm{b}}}
\CustomizeMathJax{\newcommand{\bbar}{\mathrm{bar}}}
\CustomizeMathJax{\newcommand{\gal}{\mathrm{Gal}}}
\CustomizeMathJax{\newcommand{\angstrom}{\mathrm{\unicode{x212B}}}}
\CustomizeMathJax{\newcommand{\rperminute}{\mathrm{r}\per\minute}}
\CustomizeMathJax{\newcommand{\rpersecond}{\mathrm{r}\per\second}}
\CustomizeMathJax{\newcommand{\squaremetre}{\power{\metre}{2}}}
\CustomizeMathJax{\newcommand{\cubicmetre}{\cubic\metre}}
\CustomizeMathJax{\newcommand{\graypersecond}{\gray\per\second}}
\CustomizeMathJax{\newcommand{\graypersecondnp}{\gray\usk\reciprocal\second}}
\CustomizeMathJax{\newcommand{\metrepersquaresecond}{\metre\per\second\squared}}
\CustomizeMathJax{\newcommand{\metrepersquaresecondnp}{\metre\usk\second\rpsquared}}
\CustomizeMathJax{\newcommand{\joulepermole}{\joule\per\mole}}
\CustomizeMathJax{\newcommand{\joulepermolenp}{\joule\usk\reciprocal\mole}}
\CustomizeMathJax{\newcommand{\molepercubicmetre}{\mole\per\cubic\metre}}
\CustomizeMathJax{\newcommand{\molepercubicmetrenp}{\mole\usk\rpcubic\metre}}
\CustomizeMathJax{\newcommand{\radianpersquaresecond}{\radian\per\second\squared}}
\CustomizeMathJax{\newcommand{\radianpersquaresecondnp}{\radian\usk\second\rpsquared}}
\CustomizeMathJax{\newcommand{\kilogramsquaremetrepersecond}{%
    \kilogram\usk\squaremetre\per\second%
}}
\CustomizeMathJax{\newcommand{\kilogramsquaremetrepersecondnp}{%
    \kilogram\usk\squaremetre\usk\reciprocal\second%
}}
\CustomizeMathJax{\newcommand{\radianpersecond}{\radian\per\second}}
\CustomizeMathJax{\newcommand{\radianpersecondnp}{\radian\usk\reciprocal\second}}
\CustomizeMathJax{\newcommand{\squaremetrepercubicmetre}{\squaremetre\per\cubic\metre}}
\CustomizeMathJax{\newcommand{\squaremetrepercubicmetrenp}{%
    \squaremetre\usk\rpcubic\metre%
}}
\CustomizeMathJax{\newcommand{\katalpercubicmetre}{\katal\per\cubic\metre}}
\CustomizeMathJax{\newcommand{\katalpercubicmetrenp}{\katal\usk\rpcubic\metre}}
\CustomizeMathJax{\newcommand{\coulombpermol}{\coulomb\per\mole}}
\CustomizeMathJax{\newcommand{\coulombpermolnp}{\coulomb\usk\reciprocal\mole}}
\CustomizeMathJax{\newcommand{\amperepersquaremetre}{\ampere\per\squaremetre}}
\CustomizeMathJax{\newcommand{\amperepersquaremetrenp}{\ampere\usk\rpsquare\metre}}
\CustomizeMathJax{\newcommand{\kilogrampercubicmetre}{\kilogram\per\cubic\metre}}
\CustomizeMathJax{\newcommand{\kilogrampercubicmetrenp}{\kilogram\usk\rpcubic\metre}}
\CustomizeMathJax{\newcommand{\squaremetrepernewtonsecond}{%
    \squaremetre\per\newton\usk\second%
}}
\CustomizeMathJax{\newcommand{\squaremetrepernewtonsecondnp}{%
    \squaremetre\usk\reciprocal\newton\usk\reciprocal\second%
}}
\CustomizeMathJax{\newcommand{\pascalsecond}{\pascal\usk\second}}
\CustomizeMathJax{\newcommand{\coulombpercubicmetre}{\coulomb\per\cubic\metre}}
\CustomizeMathJax{\newcommand{\coulombpercubicmetrenp}{\coulomb\usk\rpcubic\metre}}
\CustomizeMathJax{\newcommand{\amperemetresecond}{\ampere\usk\metre\usk\second}}
```

```
\CustomizeMathJax{\newcommand{\voltpermetre}{\volt\per\metre}}
\CustomizeMathJax{\newcommand{\voltpermetrenp}{\volt\usk\reciprocal\metre}}
\CustomizeMathJax{\newcommand{\coulombpersquaremetre}{\coulomb\per\squaremetre}}
\CustomizeMathJax{\newcommand{\coulombpersquaremetrenp}{\coulomb\usk\rpsquare\metre}}
\CustomizeMathJax{\newcommand{\faradpermetre}{\farad\per\metre}}
\CustomizeMathJax{\newcommand{\faradpermetrenp}{\farad\usk\reciprocal\metre}}
\CustomizeMathJax{\newcommand{\ohmmetre}{\ohm\usk\metre}}
\CustomizeMathJax{\newcommand{\kilowatthour}{\kilo\watt\hour}}
\CustomizeMathJax{\newcommand{\wattpersquaremetre}{\watt\per\squaremetre}}
\CustomizeMathJax{\newcommand{\wattpersquaremetrenp}{\watt\usk\rpsquare\metre}}
\CustomizeMathJax{\newcommand{\joulepersquaremetre}{\joule\per\squaremetre}}
\CustomizeMathJax{\newcommand{\joulepersquaremetrenp}{\joule\usk\rpsquare\metre}}
\CustomizeMathJax{\newcommand{\newtonpercubicmetre}{\newton\per\cubic\metre}}
\CustomizeMathJax{\newcommand{\newtonpercubicmetrenp}{\newton\usk\rpcubic\metre}}
\CustomizeMathJax{\newcommand{\newtonperkilogram}{\newton\per\kilogram}}
\CustomizeMathJax{\newcommand{\newtonperkilogramnp}{\newton\usk\reciprocal\kilogram}}
\CustomizeMathJax{\newcommand{\jouleperkelvin}{\joule\per\kelvin}}
\CustomizeMathJax{\newcommand{\jouleperkelvinnp}{\joule\usk\reciprocal\kelvin}}
\CustomizeMathJax{\newcommand{\jouleperkilogram}{\joule\per\kilogram}}
\CustomizeMathJax{\newcommand{\jouleperkilogramnp}{\joule\usk\reciprocal\kilogram}}
\CustomizeMathJax{\newcommand{\coulombperkilogram}{\coulomb\per\kilogram}}
\CustomizeMathJax{\newcommand{\coulombperkilogramnp}{\coulomb\usk\reciprocal\kilogram}}
\CustomizeMathJax{\newcommand{\squaremetrepersecond}{\squaremetre\per\second}}
\CustomizeMathJax{\newcommand{\squaremetrepersecondnp}{%
    \squaremetre\usk\reciprocal\second%
}}
\CustomizeMathJax{\newcommand{\squaremetrepersquaresecond}{%
    \squaremetre\per\second\squared%
}}
\CustomizeMathJax{\newcommand{\squaremetrepersquaresecondnp}{%
    \squaremetre\usk\second\rpsquared%
}}
\CustomizeMathJax{\newcommand{\kilogrammetrepersecond}{%
    \kilogram\usk\metre\per\second%
}}
\CustomizeMathJax{\newcommand{\kilogrammetrepersecondnp}{%
    \kilogram\usk\metre\usk\reciprocal\second%
}}
\CustomizeMathJax{\newcommand{\candelapersquaremetre}{\candela\per\squaremetre}}
\CustomizeMathJax{\newcommand{\candelapersquaremetrenp}{\candela\usk\rpsquare\metre}}
\CustomizeMathJax{\newcommand{\amperepermetre}{\ampere\per\metre}}
\CustomizeMathJax{\newcommand{\amperepermetrenp}{\ampere\usk\reciprocal\metre}}
\CustomizeMathJax{\newcommand{\joulepertesla}{\joule\per\tesla}}
\CustomizeMathJax{\newcommand{\joulepertesla np}{\joule\usk\reciprocal\tesla}}
\CustomizeMathJax{\newcommand{\henrypermetre}{\henry\per\metre}}
\CustomizeMathJax{\newcommand{\henrypermetrenp}{\henry\usk\reciprocal\metre}}
\CustomizeMathJax{\newcommand{\kilogrampersecond}{\kilogram\per\second}}
\CustomizeMathJax{\newcommand{\kilogrampersecondnp}{\kilogram\usk\reciprocal\second}}
\CustomizeMathJax{\newcommand{\kilogrampersquaremetresecond}{%
    \kilogram\per\squaremetre\usk\second%
}}
\CustomizeMathJax{\newcommand{\kilogrampersquaremetresecondnp}{%
    \kilogram\usk\rpsquare\metre\usk\reciprocal\second%
}}
\CustomizeMathJax{\newcommand{\kilogrampersquaremetre}{\kilogram\per\squaremetre}}
```

```
\CustomizeMathJax{\newcommand{\kilogrampersquaremetrenp}{\kilogram\usk\rpsquare\metre}}
\CustomizeMathJax{\newcommand{\kilogrampermetre}{\kilogram\per\metre}}
\CustomizeMathJax{\newcommand{\kilogrampermetrenp}{\kilogram\usk\reciprocal\metre}}
\CustomizeMathJax{\newcommand{\joulepermolekelvin}{\joule\per\mole\usk\kelvin}}
\CustomizeMathJax{\newcommand{\joulepermolekelvinnp}{%
    \joule\usk\reciprocal\mole\usk\reciprocal\kelvin%
}}
\CustomizeMathJax{\newcommand{\kilogramperkilomole}{\kilogram\per\kilo\mole}}
\CustomizeMathJax{\newcommand{\kilogramperkilomolenp}{%
    \kilogram\usk\kilo\reciprocal\mole%
}}
\CustomizeMathJax{\newcommand{\kilogramsquaremetre}{\kilogram\usk\squaremetre}}
\CustomizeMathJax{\newcommand{\kilogramsquaremetrenp}{\kilogramsquaremetre}}
\CustomizeMathJax{\newcommand{\kilogrammetrepersquaresecond}{%
    \kilogram\usk\metre\per\second\squared%
}}
\CustomizeMathJax{\newcommand{\kilogrammetrepersquaresecondnp}{%
    \kilogram\usk\metre\usk\second\rpsquared%
}}
\CustomizeMathJax{\newcommand{\newtonpersquaremetre}{\newton\per\squaremetre}}
\CustomizeMathJax{\newcommand{\newtonpersquaremetrenp}{\newton\usk\rpsquare\metre}}
\CustomizeMathJax{\newcommand{\persquaremetresecond}{1\per\squaremetre\usk\second}}
\CustomizeMathJax{\newcommand{\persquaremetresecondnp}{%
    \rpsquare\metre\usk\reciprocal\second%
}}
\CustomizeMathJax{\newcommand{\wattperkilogram}{\watt\per\kilogram}}
\CustomizeMathJax{\newcommand{\wattperkilogramnp}{\watt\usk\reciprocal\kilogram}}
\CustomizeMathJax{\newcommand{\wattpercubicmetre}{\watt\per\cubic\metre}}
\CustomizeMathJax{\newcommand{\wattpercubicmetrenp}{\watt\usk\rpcubic\metre}}
\CustomizeMathJax{\newcommand{\wattpersquaremetresteradian}{%
    \watt\per\squaremetre\usk\steradian%
}}
\CustomizeMathJax{\newcommand{\wattpersquaremetresteradiannp}{%
    \watt\usk\rpsquare\metre\usk\rp\steradian%
}}
\CustomizeMathJax{\newcommand{\jouleperkilogramkelvin}{\joule\per\kilogram\usk\kelvin}}
\CustomizeMathJax{\newcommand{\jouleperkilogramkelvinnp}{%
    \joule\usk\reciprocal\kilogram\usk\reciprocal\kelvin%
}}
\CustomizeMathJax{\newcommand{\squaremetreperkilogram}{\squaremetre\per\kilogram}}
\CustomizeMathJax{\newcommand{\rpsquaremetreperkilogram}{%
    \squaremetre\usk\reciprocal\kilogram%
}}
\CustomizeMathJax{\newcommand{\cubicmetreperkilogram}{\cubic\metre\per\kilogram}}
\CustomizeMathJax{\newcommand{\rpcubicmetreperkilogram}{%
    \cubic\metre\usk\reciprocal\kilogram%
}}
\CustomizeMathJax{\newcommand{\newtonpermetre}{\newton\per\metre}}
\CustomizeMathJax{\newcommand{\newtonpermetrenp}{\newton\usk\reciprocal\metre}}
\CustomizeMathJax{\newcommand{\Celsius}{\unicode{x2103}}}
\CustomizeMathJax{\newcommand{\wattpermetrekelvin}{\watt\per\metre\usk\kelvin}}
\CustomizeMathJax{\newcommand{\wattpermetrekelvinnp}{%
    \watt\usk\reciprocal\metre\usk\reciprocal\kelvin%
}}
\CustomizeMathJax{\newcommand{\newtonmetre}{\newton\usk\metre}
```

```
\CustomizeMathJax{\newcommand{\newtonmetrenp}{\newtonmetre}}}
\CustomizeMathJax{\newcommand{\squaremetrepercubicsecond}{%
    \squaremetre\per\cubic\second%
}}
\CustomizeMathJax{\newcommand{\squaremetrepercubicsecondnp}{%
    \squaremetre\usk\rpcubic\second%
}}
\CustomizeMathJax{\newcommand{\metrepersecond}{\metre\per\second}}
\CustomizeMathJax{\newcommand{\metrepersecondnp}{\metre\usk\reciprocal\second}}
\CustomizeMathJax{\newcommand{\joulepercubicmetre}{\joule\per\cubicmetre}}
\CustomizeMathJax{\newcommand{\joulepercubicmetrenp}{\joule\usk\rpcubic\metre}}
\CustomizeMathJax{\newcommand{\kilogrampercubicmetrecoulomb}{%
    \kilogram\per\cubic\metre\usk\coulomb%
}}
\CustomizeMathJax{\newcommand{\kilogrampercubicmetrecoulombnp}{%
    \kilogram\usk\rpcubic\metre\usk\reciprocal\coulomb%
}}
\CustomizeMathJax{\newcommand{\cubicmetrepersecond}{\cubicmetre\per\second}}
\CustomizeMathJax{\newcommand{\rpcubicmetrepersecond}{\cubicmetre\usk\reciprocal\second}}
\CustomizeMathJax{\newcommand{\kilogrampersecondcubicmetre}{%
    \kilogram\per\second\usk\cubicmetre%
}}
\CustomizeMathJax{\newcommand{\kilogrampersecondcubicmetrenp}{%
    \kilogram\usk\reciprocal\second\usk\rpcubic\metre%
}}
\end{warpMathJax}
```

---

File 437 **lwarp-siunitx.sty**

§ 544 Package

# siunitx

(*Emulates or patches code by* Joseph Wright.)

Pkg siunitx

siunitx is patched for use by lwarp, and is emulated for MathJax.

fractions

Due to *pdftotext* limitations, fraction output is replaced by symbol output for `per-mode` and `quotient-mode`.

⚠ math mode required

Some units will require that the expression be placed inside math mode.

⚠ tabular

Tabular `S` columns are rendered as simple `c` columns, and tabular `s` columns are not supported. These may be replaced by `c` columns with each cell contained in `\num` or `\si`.

⚠ MathJax

For math mode with SVG display, the original siunitx code is used while generating the SVG image. For text mode, lwarp uses an emulation which provides a very effective HTML interpretation of siunitx. For math expressions while using MathJax, a limited emulation is used. Most functions work reasonably well, but many options cannot be emulated. Complicated parsing such as for `\ang` is not supported. The result usually looks fine, and otherwise is enough to get the meaning across.

Document modifications required for MathJax:

custom units

- Custom units may be added with `\CustomizeMathJax`. See the lwarp-siunitx code

for examples.

⚠ unit spacing

- Units work better using ~ between units instead of using periods.

⚠ \square, \cubic

- To square or cube compound units, enclose the following compound units in braces:

  ```
  \cubic{\centi\meter}
  ```

  Single units do not require braces.

Also see MathJax option, section 8.7.4.

**for HTML output:**

```
\RequirePackage{xcolor}% for \convertcolorspec

\LWR@ProvidesPackagePass{siunitx}[2018/05/17]


\AtBeginDocument{% in case textcomp was not loaded
\DeclareSIUnit\bohr{\textit{a}\textsubscript{0}}
\DeclareSIUnit\clight{\textit{c}\textsubscript{0}}
\DeclareSIUnit\elementarycharge{\textit{e}}
\DeclareSIUnit\electronmass{\textit{m}\textsubscript{e}}
\DeclareSIUnit\hartree{\textit{E}\textsubscript{h}}
\DeclareSIUnit\planckbar{\LWR@siunitx@textplanckbar}
}% AtBeginDocument
```

\@ensuredmath is not supported inside an \hbox, so it must temporarily be restored to its original. Similar for \mbox. SVG math is created explicitly when necessary, using \LWR@subsingledollar.

```

\ExplSyntaxOn
%
```

Modified to set set HTML \textcolor if not black:

```
\cs_undefine:N \__siunitx_print_aux:
\cs_new_protected:Npn \__siunitx_print_aux:
  {
    \text
      {
        \__siunitx_ensure_ltr:n
          {
            \color@begingroup
            \__siunitx_print_color:
            \__siunitx_font_shape:
            \__siunitx_font_weight:
            \use:c
              {
                @@_ \l__siunitx_print_type_tl _
                text \l__siunitx_font_family_tl :
              }
            \bool_if:NTF \l__siunitx_font_math_mode_bool
              { \__siunitx_print_math: }
              {
                \LWR@findcurrenttextcolor% lwarp
```

```
                \ifdefstring{\LWR@tempcolor}{000000}% lwarp
                {\__siunitx_print_text:}% lwarp
                {% lwarp
                    \LWR@textcurrentcolor{% lwarp
                        \__siunitx_print_text:
                    }% lwarp
                }% lwarp
              }
            \color@endgroup
          }
      }
  }


\cs_undefine:N \__siunitx_set_math_fam:n
\cs_new_protected:Npn \__siunitx_set_math_fam:n #1 {
  \int_new:c { c__siunitx_math #1 _int }
  \group_begin:% lwarp
    \LetLtxMacro\@ensuredmath\LWR@origensuredmath% lwarp
    \LetLtxMacro\mbox\LWR@print@mbox% lwarp
    \hbox_set:Nn \l__siunitx_tmp_box
      {
        \ensuremath
          {
            \use:c { math #1 }
              {
                \int_gset:cn { c__siunitx_math #1 _int } { \fam }
              }
          }
      }
  \group_end:% lwarp
}

\cs_undefine:N \__siunitx_combined_output:n
\cs_new_protected:Npn \__siunitx_combined_output:n #1 {
    \group_begin:% lwarp
    \LetLtxMacro\@ensuredmath\LWR@origensuredmath% lwarp
    \LetLtxMacro\mbox\LWR@print@mbox% lwarp
  \bool_if:NTF \l__siunitx_number_parse_bool
    {
      \tl_clear:N \l__siunitx_number_out_tl
      \bool_set_false:N \l__siunitx_number_compound_bool
      \__siunitx_number_output_parse:n {#1}
    }
    {
```

For parse-numbers=false:

```
        \__siunitx_unit_output_pre_print:
        \begingroup%    lwarp
            \boolfalse{mathjax}%    lwarp
%       \__siunitx_print:nn { number } { \ensuremath {#1} }
            \LWR@subsingledollar{% lwarp
                \textbackslash( \LWR@HTMLsanitize{#1} \textbackslash)% lwarp
            }{siunitx}{%
```

```
                \__siunitx_print:nn { number } {%
                    \LWR@origensuredmath{#1}%
                }%
            }% lwarp
        \endgroup%    lwarp
        \__siunitx_unit_output_print:
    }
    \group_end:% lwarp
}
```

For `parse-numbers=false`:

```
\cs_set_protected:Npn \__siunitx_range_numbers_aux:n #1
  {
    \bool_if:NTF \l__siunitx_number_parse_bool
      {
        \tl_clear:N \l__siunitx_number_out_tl
        \tl_clear:N \l__siunitx_number_out_saved_tl
        \bool_set_false:N \l__siunitx_number_compound_bool
        \__siunitx_number_output_parse:n {#1}
        \bool_if:NT \l__siunitx_number_compound_bool
          { \msg_error:nnx { siunitx } { multi-part-range } {#1} }
      }
      {
        \__siunitx_unit_output_pre_print:
        \begingroup%    lwarp
            \boolfalse{mathjax}%    lwarp
%           \__siunitx_print:nn { number } {#1}
                \LWR@subsingledollar{% lwarp
                  \textbackslash( \LWR@HTMLsanitize{#1} \textbackslash)% lwarp
                }{siunitx}{%
                    \__siunitx_print:nn { number } {
                        \LWR@origensuredmath{#1}%
                    } % lwarp
                }% lwarp
        \endgroup%    lwarp
        \__siunitx_unit_output_print:
      }
  }
```

For `parse-numbers=false`:

```
\cs_set_protected:Npn \__siunitx_angle_print_direct_aux:nn #1#2 {
  \tl_if_empty:nF {#1}
    {
      \tl_set:Nn \l__siunitx_unit_tl {#2}
        \begingroup%    lwarp
            \boolfalse{mathjax}%    lwarp
%           \__siunitx_print:nn { number } {#1}
                \LWR@subsingledollar{% lwarp
                  \textbackslash( \LWR@HTMLsanitize{#1} \textbackslash)% lwarp
                }{siunitx}{%
                    \__siunitx_print:nn { number } {
                        \LWR@origensuredmath{#1}%
                    } % lwarp
```

```
                }% lwarp
        \endgroup%    lwarp
      \__siunitx_unit_output_print:
    }
}
%
```

For quotients, the fraction code is replaced by the symbol code:

```
\cs_undefine:N \__siunitx_number_output_quotient_fraction:
\cs_new_protected:Npn \__siunitx_number_output_quotient_fraction: {
  \bool_set_true:N \l__siunitx_number_compound_bool
  \__siunitx_number_output_quotient_aux_i:
  \tl_set_eq:NN \l__siunitx_number_out_tl
    \l__siunitx_number_numerator_tl
  \tl_put_right:NV \l__siunitx_number_out_tl \l__siunitx_output_quotient_tl
  \tl_put_right:NV \l__siunitx_number_out_tl
    \l__siunitx_number_denominator_tl
  \__siunitx_number_output_single_aux:
}
```

For units, the fraction code is replaced by the symbol code:

```
\cs_undefine:N \__siunitx_unit_format_fraction_fraction:
\cs_new_protected:Npn \__siunitx_unit_format_fraction_fraction: {
  \__siunitx_unit_format_fraction_symbol_aux:
  \int_compare:nNnT { \l__siunitx_unit_denominator_int } > { 1 }
    {
      \bool_if:NT \l__siunitx_unit_denominator_bracket_bool
        {
       \tl_put_left:NV \l__siunitx_unit_denominator_tl \l__siunitx_bracket_open_tl
       \tl_put_right:NV \l__siunitx_unit_denominator_tl \l__siunitx_bracket_close_tl
        }
    }
  \tl_set_eq:NN \l__siunitx_unit_tl \l__siunitx_unit_numerator_tl
  \tl_put_right:NV \l__siunitx_unit_tl \l__siunitx_per_symbol_tl
  \tl_put_right:NV \l__siunitx_unit_tl \l__siunitx_unit_denominator_tl
}
```

```
\cs_undefine:N \__siunitx_angle_print_astronomy_aux:
\cs_new_protected:Npn \__siunitx_angle_print_astronomy_aux: {
  \prop_get:NnNT \l__siunitx_number_out_prop { mantissa-integer }
    \l__siunitx_tmpa_tl
    { \__siunitx_print:nV { number } \l__siunitx_tmpa_tl }
 \ifnumcomp{\value{LWR@lateximagedepth}}{>}{0}% lwarp
 {% lateximage
  \hbox_set:Nn \l__siunitx_angle_marker_box
    {
      \__siunitx_print:nn { number } { { \l__siunitx_output_decimal_tl } }
    }
  \hbox_set:Nn \l__siunitx_angle_unit_box
    {
      \__siunitx_print:nV { unit } \l__siunitx_unit_tl
      \skip_horizontal:n { -\scriptspace }
    }
```

```
  \__siunitx_angle_print_astronomy_aux:n { marker }
  \__siunitx_angle_print_astronomy_aux:n { unit }
  \hbox_set:Nn \l__siunitx_angle_marker_box
    {
      \box_use:N \l__siunitx_angle_marker_box
      \box_use:N \l__siunitx_angle_unit_box
    }
  \dim_compare:nNnTF
    { \l__siunitx_angle_marker_dim } > { \l__siunitx_angle_unit_dim }
    { \__siunitx_angle_print_astronomy_marker: }
    { \__siunitx_angle_print_astronomy_unit: }
 }% lateximage
 {% not a lateximage
      \__siunitx_print:nV { unit } \l__siunitx_unit_tl
      \__siunitx_print:nn { number } { { \l__siunitx_output_decimal_tl } }
 }% not a lateximage
  \prop_get:NnNT \l__siunitx_number_out_prop { mantissa-decimal }
    \l__siunitx_tmpa_tl
    { \__siunitx_print:nV { number } \l__siunitx_tmpa_tl }
}


\cs_undefine:N \__siunitx_textsuperscript:n
\cs_new_protected:Npn \__siunitx_textsuperscript:n #1 {\textsuperscript{#1}}
```

\num [⟨*options*⟩] {⟨*value*⟩}

```
\RenewDocumentCommand \num { o m } {
  \leavevmode
  \group_begin:% lwarp
    \LetLtxMacro\@ensuredmath\LWR@origensuredmath% lwarp
    \LetLtxMacro\mbox\LWR@print@mbox% lwarp
    \bool_set_false:N \l__siunitx_font_set_bool
    \IfNoValueF {#1}
      { \keys_set:nn { siunitx } {#1} }
    \__siunitx_number_output:n {#2}
  \group_end:% lwarp
}
```

\numrange [⟨*options*⟩] {⟨*value1*⟩} {⟨*value2*⟩}

```
\RenewDocumentCommand \numrange { o m m } {
  \leavevmode
  \group_begin:% lwarp
    \LetLtxMacro\@ensuredmath\LWR@origensuredmath% lwarp
    \LetLtxMacro\mbox\LWR@print@mbox% lwarp
    \bool_set_false:N \l__siunitx_font_set_bool
    \IfNoValueF {#1}
      { \keys_set:nn { siunitx } {#1} }
    \__siunitx_range_numbers:nn {#2} {#3}
  \group_end:% lwarp
}
```

\ang {⟨*options*⟩} {⟨*angle*⟩}

```
\RenewDocumentCommand \ang { o > { \SplitArgument { 2 } { ; } } m } {
  \group_begin:% lwarp
    \LetLtxMacro\@ensuredmath\LWR@origensuredmath% lwarp
    \LetLtxMacro\mbox\LWR@print@mbox% lwarp
    \IfNoValueF {#1}
      { \keys_set:nn { siunitx } {#1} }
    \__siunitx_angle_output:nnn #2
  \group_end:% lwarp
}
```

`\si` {⟨*options*⟩} {⟨*unit*⟩}

```
\RenewDocumentCommand \si { o m } {
  \leavevmode
  \group_begin:% lwarp
    \LetLtxMacro\@ensuredmath\LWR@origensuredmath% lwarp
    \LetLtxMacro\mbox\LWR@print@mbox% lwarp
    \bool_set_false:N \l__siunitx_font_set_bool
    \IfNoValueTF {#1}
      { \__siunitx_unit_output:nn {#2} { } }
      {
        \keys_set:nn { siunitx } {#1}
        \__siunitx_unit_output:nn {#2} {#1}
      }
  \group_end:% lwarp
}
```

`\SIrange` [⟨*options*⟩] {⟨*value1*⟩} {⟨*value2*⟩} {⟨*unit*⟩}

```
\RenewDocumentCommand{\SIrange}{o m m m}
{%
  \leavevmode
  \group_begin:% lwarp
    \LetLtxMacro\@ensuredmath\LWR@origensuredmath% lwarp
    \LetLtxMacro\mbox\LWR@print@mbox% lwarp
    \bool_set_false:N \l__siunitx_font_set_bool
    \IfNoValueTF {#1}
      { \__siunitx_range_unit:nnnn {#4} { } {#2} {#3} }
      {
        \keys_set:nn { siunitx } {#1}
        \__siunitx_range_unit:nnnn {#4} {#1} {#2} {#3}
      }
  \group_end:% lwarp
}

\ExplSyntaxOff
```

For MathJax. (The following runs much faster as separate `\CusomizeMathJax` calls instead of one single call.)

```
\begin{warpMathJax}
\LWR@infoprocessingmathjax{siunitx}

\CustomizeMathJax{\newcommand{\tothe}[1]{^{#1}}}
```

```
\CustomizeMathJax{\newcommand{\raiseto}[2]{{#2}^{#1}}}
```

Used as an end marker when parsing values:

```
\CustomizeMathJax{\newcommand{\LWRsiunitxEND}{}}
```

\ang `[`⟨*options*⟩`]` `{`⟨*value*⟩`}`

```
\CustomizeMathJax{\def\LWRsiunitxang#1;#2;#3;#4\LWRsiunitxEND{%
    \ifblank{#1}{}{\num{#1}\degree}%
    \ifblank{#2}{}{\num{#2}^{\unicode{x2032}}}% \prime
    \ifblank{#3}{}{\num{#3}^{\unicode{x2033}}}% \dblprime
}}
\CustomizeMathJax{\newcommand{\ang}[2][]{\LWRsiunitxang#2;;;\LWRsiunitxEND}}
```

Processes scientific notation. Special handling for a mantissa which is either empty or only a minus sign.

```
\CustomizeMathJax{\newcommand{\LWRsiunitxnumscientific}[2]{%
    \ifblank{#1}%
        {}%
        {%
            \ifstrequal{#1}{-}%
                {-}%
                {\LWRsiunitxprintdecimal{#1}\times}%
        }%
    10^{\LWRsiunitxprintdecimal{#2}}
}}
```

\num handles optional powers (e, E, d, D), multiples (x), plus and minus, and period or comma decimal output.

To split the string, \def is used with parameter delimiters. When each of the following macro is used, extra delimiters are padded to the end of the arguments of each macro when used, and the final argument of each collects any extra unused delimiters.

```
\ExplSyntaxOn
\AtBeginDocument{
\ifdefstring{\l__siunitx_output_decimal_tl}{{,}}
    {% Use decimal comma
      \CustomizeMathJax{\def\LWRsiunitxprintdecimalsub#1.#2.#3\LWRsiunitxEND{%
            \mathrm{#1}%
            \ifblank{#2}
                {}%
                {,\mathrm{#2}}
        }}

        \CustomizeMathJax{\newcommand{\LWRsiunitxprintdecimal}[1]{%
            \LWRsiunitxprintdecimalsub#1...\LWRsiunitxEND%
        }}
    }
    {% Use decimal point
      \CustomizeMathJax{\def\LWRsiunitxprintdecimalsub#1,#2,#3\LWRsiunitxEND{%
            \mathrm{#1}%
```

```
            \ifblank{#2}
                {}%
                {.\mathrm{#2}}
        }}

        \CustomizeMathJax{\newcommand{\LWRsiunitxprintdecimal}[1]{%
            \LWRsiunitxprintdecimalsub#1,,,\LWRsiunitxEND%
        }}
    }
}
\ExplSyntaxOff
```

\num [⟨*options*⟩] {⟨*value*⟩}

```
\CustomizeMathJax{\def\LWRsiunitxnumplus#1+#2+#3\LWRsiunitxEND{%
    \ifblank{#2}
        {\LWRsiunitxprintdecimal{#1}}% no plus
        {%
            \ifblank{#1}%
                {\LWRsiunitxprintdecimal{#2}}% leading plus, ignore
                {% a+b
                    \LWRsiunitxprintdecimal{#1}%
                    \unicode{x02B}% plus sign
                    \LWRsiunitxprintdecimal{#2}%
                }%
        }%
}}

\CustomizeMathJax{\def\LWRsiunitxnumminus#1-#2-#3\LWRsiunitxEND{%
    \ifblank{#2}
        {\LWRsiunitxnumplus#1+++\LWRsiunitxEND}%
        {%
            \LWRsiunitxprintdecimal{#1}%
            \unicode{x02212}% mathematical minus sign
            \LWRsiunitxprintdecimal{#2}%
        }%
}}

\CustomizeMathJax{\def\LWRsiunitxnumpm#1+-#2+-#3\LWRsiunitxEND{%
    \ifblank{#2}%
        {\LWRsiunitxnumminus#1---\LWRsiunitxEND}%
        {%
            \LWRsiunitxprintdecimal{#1}%
            \unicode{x0B1}% \pm
            \LWRsiunitxprintdecimal{#2}%
        }%
}}

\CustomizeMathJax{\def\LWRsiunitxnumx#1x#2x#3x#4\LWRsiunitxEND{%
    \ifblank{#2}%
        {\LWRsiunitxnumpm#1+-+-\LWRsiunitxEND}%
        {%
            \ifblank{#3}%
                {%
                    \LWRsiunitxprintdecimal{#1}%
```

```
                    \times%
                    \LWRsiunitxprintdecimal{#2}%
                }%
                {%
                    \LWRsiunitxprintdecimal{#1}%
                    \times%
                    \LWRsiunitxprintdecimal{#2}%
                    \times%
                    \LWRsiunitxprintdecimal{#3}%
                }%
        }%
}}

\CustomizeMathJax{\def\LWRsiunitxnumD#1D#2D#3\LWRsiunitxEND{%
    \ifblank{#2}%
        {\LWRsiunitxnumx#1xxxxx\LWRsiunitxEND}%
        {\mathrm{\LWRsiunitxnumscientific{#1}{#2}}}%
}}

\CustomizeMathJax{\def\LWRsiunitxnumd#1d#2d#3\LWRsiunitxEND{%
    \ifblank{#2}%
        {\LWRsiunitxnumD#1DDD\LWRsiunitxEND}%
        {\mathrm{\LWRsiunitxnumscientific{#1}{#2}}}%
}}

\CustomizeMathJax{\def\LWRsiunitxnumE#1E#2E#3\LWRsiunitxEND{%
    \ifblank{#2}%
        {\LWRsiunitxnumd#1ddd\LWRsiunitxEND}%
        {\mathrm{\LWRsiunitxnumscientific{#1}{#2}}}%
}}

\CustomizeMathJax{\def\LWRsiunitxnume#1e#2e#3\LWRsiunitxEND{%
    \ifblank{#2}%
        {\LWRsiunitxnumE#1EEE\LWRsiunitxEND}%
        {\mathrm{\LWRsiunitxnumscientific{#1}{#2}}}%
}}

\CustomizeMathJax{\def\LWRsiunitxnumcomma#1,#2,#3\LWRsiunitxEND{%
    \ifblank{#2}
        {\LWRsiunitxnume#1eee\LWRsiunitxEND}
        {\LWRsiunitxnume#1.#2eee\LWRsiunitxEND}
}}

\CustomizeMathJax{\newcommand{\num}[2][]{\LWRsiunitxnumcomma#2,,,\LWRsiunitxEND}}
```

`\si` `[`⟨*options*⟩`]` `{`⟨*unit*⟩`}`

```
\CustomizeMathJax{\newcommand{\si}[2][]{\mathrm{#2}}}
```

`\SI` `[`⟨*options*⟩`]` `{`⟨*value*⟩`}` `[`⟨*prefix*⟩`]` `{`⟨*unit*⟩`}`

`\SI` has a second optional arg, which is parsed using `\ifnextchar`.

```
\CustomizeMathJax{\def\LWRsiunitxSIopt#1[#2]#3{%
    {#2}\num{#1}{#3}%
}}
```

```
\CustomizeMathJax{\newcommand{\LWRsiunitxSI}[2]{%
    \num{#1}\,{#2}%
}}

\CustomizeMathJax{\newcommand{\SI}[2][]{%
    \ifnextchar[%
        {\LWRsiunitxSIopt{#2}}%
        {\LWRsiunitxSI{#2}}%
}}
```

\numlist [⟨*options*⟩] {⟨*list*⟩}

\numlist should only be used in text mode. If used in MathJax, it is merely printed as input.

```
\CustomizeMathJax{\newcommand{\numlist}[2][]{\mathrm{#2}}}
```

\numrange [⟨*options*⟩] {⟨*value1*⟩} {⟨*value2*⟩}

\numrange should only be used in text mode. If used in MathJax math, an en-dash is used instead of the range-phase.

```
\CustomizeMathJax{\newcommand{\numrange}[3][]{\num{#2}\,\unicode{x2013}\,\num{#3}}}
```

\SIlist [⟨*options*⟩] {⟨*list*⟩}

\SIlist and \SIrange should only be used in text mode. If used in MathJax, a simple emulation is provided.

```
\CustomizeMathJax{\newcommand{\SIlist}[3][]{\mathrm{#2\,#3}}}
```

\SIrange [⟨*options*⟩] {⟨*value1*⟩} {⟨*value2*⟩} {⟨*unit*⟩}

```
\CustomizeMathJax{\newcommand{\SIrange}[4][]{\num{#2}\,#4\,\unicode{x2013}\,\num{#3}\,#4}}
```

\tablenum [⟨*options*⟩] {⟨*value*⟩}

```
\CustomizeMathJax{\newcommand{\tablenum}[2][]{\mathrm{#2}}}

\CustomizeMathJax{\newcommand{\ampere}{\mathrm{A}}}
\CustomizeMathJax{\newcommand{\candela}{\mathrm{cd}}}
\CustomizeMathJax{\newcommand{\kelvin}{\mathrm{K}}}
\CustomizeMathJax{\newcommand{\kilogram}{\mathrm{kg}}}
\CustomizeMathJax{\newcommand{\metre}{\mathrm{m}}}
\CustomizeMathJax{\newcommand{\mole}{\mathrm{mol}}}
\CustomizeMathJax{\newcommand{\second}{\mathrm{s}}}
%
\CustomizeMathJax{\newcommand{\becquerel}{\mathrm{Bq}}}
\CustomizeMathJax{\newcommand{\degreeCelsius}{\unicode{x2103}}}
\CustomizeMathJax{\newcommand{\coulomb}{\mathrm{C}}}
\CustomizeMathJax{\newcommand{\farad}{\mathrm{F}}}
\CustomizeMathJax{\newcommand{\gray}{\mathrm{Gy}}}
\CustomizeMathJax{\newcommand{\hertz}{\mathrm{Hz}}}
\CustomizeMathJax{\newcommand{\henry}{\mathrm{H}}}
\CustomizeMathJax{\newcommand{\joule}{\mathrm{J}}}
```

```
\CustomizeMathJax{\newcommand{\katal}{\mathrm{kat}}}
\CustomizeMathJax{\newcommand{\lumen}{\mathrm{lm}}}
\CustomizeMathJax{\newcommand{\lux}{\mathrm{lx}}}
\CustomizeMathJax{\newcommand{\newton}{\mathrm{N}}}
\CustomizeMathJax{\newcommand{\ohm}{\mathrm{\Omega}}}
\CustomizeMathJax{\newcommand{\pascal}{\mathrm{Pa}}}
\CustomizeMathJax{\newcommand{\radian}{\mathrm{rad}}}
\CustomizeMathJax{\newcommand{\siemens}{\mathrm{S}}}
\CustomizeMathJax{\newcommand{\sievert}{\mathrm{Sv}}}
\CustomizeMathJax{\newcommand{\steradian}{\mathrm{sr}}}
\CustomizeMathJax{\newcommand{\tesla}{\mathrm{T}}}
\CustomizeMathJax{\newcommand{\volt}{\mathrm{V}}}
\CustomizeMathJax{\newcommand{\watt}{\mathrm{W}}}
\CustomizeMathJax{\newcommand{\weber}{\mathrm{Wb}}}
\CustomizeMathJax{\newcommand{\day}{\mathrm{d}}}
\CustomizeMathJax{\newcommand{\degree}{\mathrm{^\circ}}}
\CustomizeMathJax{\newcommand{\hectare}{\mathrm{ha}}}
\CustomizeMathJax{\newcommand{\hour}{\mathrm{h}}}
\CustomizeMathJax{\newcommand{\litre}{\mathrm{l}}}
\CustomizeMathJax{\newcommand{\liter}{\mathrm{L}}}
\CustomizeMathJax{\newcommand{\arcminute}{^\prime}}
\CustomizeMathJax{\newcommand{\minute}{\mathrm{min}}}
\CustomizeMathJax{\newcommand{\arcsecond}{^{\prime\prime}}}
\CustomizeMathJax{\newcommand{\tonne}{\mathrm{t}}}
\CustomizeMathJax{\newcommand{\astronomicalunit}{au}}
\CustomizeMathJax{\newcommand{\atomicmassunit}{u}}
\CustomizeMathJax{\newcommand{\bohr}{\mathit{a}_0}}
\CustomizeMathJax{\newcommand{\clight}{\mathit{c}_0}}
\CustomizeMathJax{\newcommand{\dalton}{\mathrm{D}_\mathrm{a}}}
\CustomizeMathJax{\newcommand{\electronmass}{\mathit{m}_{\mathrm{e}}}}
\CustomizeMathJax{\newcommand{\electronvolt}{\mathrm{eV}}}
\CustomizeMathJax{\newcommand{\elementarycharge}{\mathit{e}}}
\CustomizeMathJax{\newcommand{\hartree}{\mathit{E}_{\mathrm{h}}}}
\CustomizeMathJax{\newcommand{\planckbar}{\mathit{\unicode{x210F}}}}
\CustomizeMathJax{\newcommand{\angstrom}{\mathrm{\unicode{x212B}}}}
\CustomizeMathJax{\let\LWRorigbar\bar}
\CustomizeMathJax{\newcommand{\bar}{\mathrm{bar}}}
\CustomizeMathJax{\newcommand{\barn}{\mathrm{b}}}
\CustomizeMathJax{\newcommand{\bel}{\mathrm{B}}}
\CustomizeMathJax{\newcommand{\decibel}{\mathrm{dB}}}
\CustomizeMathJax{\newcommand{\knot}{\mathrm{kn}}}
\CustomizeMathJax{\newcommand{\mmHg}{\mathrm{mmHg}}}
\CustomizeMathJax{\newcommand{\nauticalmile}{\mathrm{M}}}
\CustomizeMathJax{\newcommand{\neper}{\mathrm{Np}}}
%
\CustomizeMathJax{\newcommand{\yocto}{\mathrm{y}}}
\CustomizeMathJax{\newcommand{\zepto}{\mathrm{z}}}
\CustomizeMathJax{\newcommand{\atto}{\mathrm{a}}}
\CustomizeMathJax{\newcommand{\femto}{\mathrm{f}}}
\CustomizeMathJax{\newcommand{\pico}{\mathrm{p}}}
\CustomizeMathJax{\newcommand{\nano}{\mathrm{n}}}
\CustomizeMathJax{\newcommand{\micro}{\mathrm{\unicode{x00B5}}}}
\CustomizeMathJax{\newcommand{\milli}{\mathrm{m}}}
\CustomizeMathJax{\newcommand{\centi}{\mathrm{c}}}
\CustomizeMathJax{\newcommand{\deci}{\mathrm{d}}}
```

```
\CustomizeMathJax{\newcommand{\deca}{\mathrm{da}}}
\CustomizeMathJax{\newcommand{\hecto}{\mathrm{h}}}
\CustomizeMathJax{\newcommand{\kilo}{\mathrm{k}}}
\CustomizeMathJax{\newcommand{\mega}{\mathrm{M}}}
\CustomizeMathJax{\newcommand{\giga}{\mathrm{G}}}
\CustomizeMathJax{\newcommand{\tera}{\mathrm{T}}}
\CustomizeMathJax{\newcommand{\peta}{\mathrm{P}}}
\CustomizeMathJax{\newcommand{\exa}{\mathrm{E}}}
\CustomizeMathJax{\newcommand{\zetta}{\mathrm{Z}}}
\CustomizeMathJax{\newcommand{\yotta}{\mathrm{Y}}}
%
\CustomizeMathJax{\newcommand{\percent}{\mathrm{\%}}}
%
\CustomizeMathJax{\newcommand{\meter}{\mathrm{m}}}
\CustomizeMathJax{\newcommand{\metre}{\mathrm{m}}}
%
\CustomizeMathJax{\newcommand{\gram}{\mathrm{g}}}
\CustomizeMathJax{\newcommand{\kg}{\kilo\gram}}
\CustomizeMathJax{\newcommand{\of}[1]{_{\mathrm{#1}}}}
\CustomizeMathJax{\newcommand{\squared}{^2}}
\CustomizeMathJax{\newcommand{\square}[1]{\mathrm{#1}^2}}
\CustomizeMathJax{\newcommand{\cubed}{^3}}
\CustomizeMathJax{\newcommand{\cubic}[1]{\mathrm{#1}^3}}
\CustomizeMathJax{\newcommand{\per}{/}}
\CustomizeMathJax{\newcommand{\celsius}{\unicode{x2103}}}
%
\CustomizeMathJax{\newcommand{\fg}{\femto\gram}}
\CustomizeMathJax{\newcommand{\pg}{\pico\gram}}
\CustomizeMathJax{\newcommand{\ng}{\nano\gram}}
\CustomizeMathJax{\newcommand{\ug}{\micro\gram}}
\CustomizeMathJax{\newcommand{\mg}{\milli\gram}}
\CustomizeMathJax{\newcommand{\g}{\gram}}
\CustomizeMathJax{\newcommand{\kg}{\kilo\gram}}
%
\CustomizeMathJax{\newcommand{\amu}{\mathrm{u}}}
%
\CustomizeMathJax{\newcommand{\pm}{\pico\metre}}
\CustomizeMathJax{\newcommand{\nm}{\nano\metre}}
\CustomizeMathJax{\newcommand{\um}{\micro\metre}}
\CustomizeMathJax{\newcommand{\mm}{\milli\metre}}
\CustomizeMathJax{\newcommand{\cm}{\centi\metre}}
\CustomizeMathJax{\newcommand{\dm}{\deci\metre}}
\CustomizeMathJax{\newcommand{\m}{\metre}}
\CustomizeMathJax{\newcommand{\km}{\kilo\metre}}
%
\CustomizeMathJax{\newcommand{\as}{\atto\second}}
\CustomizeMathJax{\newcommand{\fs}{\femto\second}}
\CustomizeMathJax{\newcommand{\ps}{\pico\second}}
\CustomizeMathJax{\newcommand{\ns}{\nano\second}}
\CustomizeMathJax{\newcommand{\us}{\micro\second}}
\CustomizeMathJax{\newcommand{\ms}{\milli\second}}
\CustomizeMathJax{\newcommand{\s}{\second}}
%
\CustomizeMathJax{\newcommand{\fmol}{\femto\mol}}
\CustomizeMathJax{\newcommand{\pmol}{\pico\mol}}
```

```
\CustomizeMathJax{\newcommand{\nmol}{\nano\mol}}
\CustomizeMathJax{\newcommand{\umol}{\micro\mol}}
\CustomizeMathJax{\newcommand{\mmol}{\milli\mol}}
\CustomizeMathJax{\newcommand{\mol}{\mol}}
\CustomizeMathJax{\newcommand{\kmol}{\kilo\mol}}
%
\CustomizeMathJax{\newcommand{\pA}{\pico\ampere}}
\CustomizeMathJax{\newcommand{\nA}{\nano\ampere}}
\CustomizeMathJax{\newcommand{\uA}{\micro\ampere}}
\CustomizeMathJax{\newcommand{\mA}{\milli\ampere}}
\CustomizeMathJax{\newcommand{\A}{\ampere}}
\CustomizeMathJax{\newcommand{\kA}{\kilo\ampere}}
%
\CustomizeMathJax{\newcommand{\ul}{\micro\litre}}
\CustomizeMathJax{\newcommand{\ml}{\milli\litre}}
\CustomizeMathJax{\newcommand{\l}{\litre}}
\CustomizeMathJax{\newcommand{\hl}{\hecto\litre}}
\CustomizeMathJax{\newcommand{\uL}{\micro\liter}}
\CustomizeMathJax{\newcommand{\mL}{\milli\liter}}
\CustomizeMathJax{\newcommand{\L}{\liter}}
\CustomizeMathJax{\newcommand{\hL}{\hecto\liter}}
%
\CustomizeMathJax{\newcommand{\mHz}{\milli\hertz}}
\CustomizeMathJax{\newcommand{\Hz}{\hertz}}
\CustomizeMathJax{\newcommand{\kHz}{\kilo\hertz}}
\CustomizeMathJax{\newcommand{\MHz}{\mega\hertz}}
\CustomizeMathJax{\newcommand{\GHz}{\giga\hertz}}
\CustomizeMathJax{\newcommand{\THz}{\tera\hertz}}
%
\CustomizeMathJax{\newcommand{\mN}{\milli\newton}}
\CustomizeMathJax{\newcommand{\N}{\newton}}
\CustomizeMathJax{\newcommand{\kN}{\kilo\newton}}
\CustomizeMathJax{\newcommand{\MN}{\mega\newton}}
%
\CustomizeMathJax{\newcommand{\Pa}{\pascal}}
\CustomizeMathJax{\newcommand{\kPa}{\kilo\pascal}}
\CustomizeMathJax{\newcommand{\MPa}{\mega\pascal}}
\CustomizeMathJax{\newcommand{\GPa}{\giga\pascal}}
%
\CustomizeMathJax{\newcommand{\mohm}{\milli\ohm}}
\CustomizeMathJax{\newcommand{\kohm}{\kilo\ohm}}
\CustomizeMathJax{\newcommand{\Mohm}{\mega\ohm}}
%
\CustomizeMathJax{\newcommand{\pV}{\pico\volt}}
\CustomizeMathJax{\newcommand{\nV}{\nano\volt}}
\CustomizeMathJax{\newcommand{\uV}{\micro\volt}}
\CustomizeMathJax{\newcommand{\mV}{\milli\volt}}
\CustomizeMathJax{\newcommand{\V}{\volt}}
\CustomizeMathJax{\newcommand{\kV}{\kilo\volt}}
%
\CustomizeMathJax{\newcommand{\W}{\watt}}
\CustomizeMathJax{\newcommand{\uW}{\micro\watt}}
\CustomizeMathJax{\newcommand{\mW}{\milli\watt}}
\CustomizeMathJax{\newcommand{\kW}{\kilo\watt}}
\CustomizeMathJax{\newcommand{\MW}{\mega\watt}}
```

```
\CustomizeMathJax{\newcommand{\GW}{\giga\watt}}
%
\CustomizeMathJax{\newcommand{\J}{\joule}}
\CustomizeMathJax{\newcommand{\uJ}{\micro\joule}}
\CustomizeMathJax{\newcommand{\mJ}{\milli\joule}}
\CustomizeMathJax{\newcommand{\kJ}{\kilo\joule}}
%
\CustomizeMathJax{\newcommand{\eV}{\electronvolt}}
\CustomizeMathJax{\newcommand{\meV}{\milli\electronvolt}}
\CustomizeMathJax{\newcommand{\keV}{\kilo\electronvolt}}
\CustomizeMathJax{\newcommand{\MeV}{\mega\electronvolt}}
\CustomizeMathJax{\newcommand{\GeV}{\giga\electronvolt}}
\CustomizeMathJax{\newcommand{\TeV}{\tera\electronvolt}}
%
\CustomizeMathJax{\newcommand{\kWh}{\kilo\watt\hour}}
%
\CustomizeMathJax{\newcommand{\F}{\farad}}
\CustomizeMathJax{\newcommand{\fF}{\femto\farad}}
\CustomizeMathJax{\newcommand{\pF}{\pico\farad}}
%
\CustomizeMathJax{\newcommand{\K}{\mathrm{K}}}
%
\CustomizeMathJax{\newcommand{\dB}{\mathrm{dB}}}
%
\CustomizeMathJax{\newcommand{\kibi}{\mathrm{Ki}}}
\CustomizeMathJax{\newcommand{\mebi}{\mathrm{Mi}}}
\CustomizeMathJax{\newcommand{\gibi}{\mathrm{Gi}}}
\CustomizeMathJax{\newcommand{\tebi}{\mathrm{Ti}}}
\CustomizeMathJax{\newcommand{\pebi}{\mathrm{Pi}}}
\CustomizeMathJax{\newcommand{\exbi}{\mathrm{Ei}}}
\CustomizeMathJax{\newcommand{\zebi}{\mathrm{Zi}}}
\CustomizeMathJax{\newcommand{\yobi}{\mathrm{Yi}}}
\end{warpMathJax}
```

---

File 438 **lwarp-skmath.sty**

# § 545 Package skmath

(*Emulates or patches code by* Simon Sigurdhsson.)

Pkg skmath skmath is used as-is for SVG math, and is emulated for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{skmath}[2019/10/15]
```

Only defined if package option requested:

```
\begin{warpMathJax}
\ExplSyntaxOn
\bool_if:NT\g__skmath_define_common_sets_bool{
\CustomizeMathJax{\newcommand{\N}{\mathbb{N}}}
\CustomizeMathJax{\newcommand{\Z}{\mathbb{Z}}}
\CustomizeMathJax{\newcommand{\Q}{\mathbb{Q}}}
\CustomizeMathJax{\newcommand{\R}{\mathbb{R}}}
```

```
\CustomizeMathJax{\newcommand{\C}{\mathbb{C}}}
}
```

skmath is using l3keys, which does not seem to have an equivalent to `\@ifpackagewith`. To detect package options, comparisons with the following are made to see if various macros have been defined as follows:

```
\cs_gset_nopar:Npn\LWR__skmath_imaginary_unit:n#1{{#1}}
\cs_gset_nopar:Npn\LWR__skmath_natural_log_e:{{e}}
\cs_gset_nopar:Npn\LWR__skmath_integral_d:{{d}}
\cs_gset_nopar:Npn\LWR__skmath_total_derivative_d:{{d}}
```

If `notation=iso`, use upright, else italic:

```
\cs_if_eq:NNTF \__skmath_imaginary_unit:n \LWR__skmath_imaginary_unit:n
    {
        \CustomizeMathJax{\newcommand{ii}{\mathit{i}}}
        \CustomizeMathJax{\newcommand{jj}{\mathit{j}}}
    }
    {
        \CustomizeMathJax{\newcommand{ii}{\mathrm{i}}}
        \CustomizeMathJax{\newcommand{jj}{\mathrm{j}}}
    }
```

If `notation=iso`, use upright, else italic:

```
\cs_if_eq:NNTF \__skmath_natural_log_e: \LWR__skmath_natural_log_e:
    { \CustomizeMathJax{\newcommand{\ee}{\mathit{e}}} }
    { \CustomizeMathJax{\newcommand{\ee}{\mathrm{e}}} }
```

skmath uses `\DeclarePairedDelimiter` from mathtools for `\abs` and `\norm`, and lwarp uses this to automatically define MathJax definitions for each.

If `notation=english`, use slanted, else upright:

```
\cs_if_eq:NNTF \__skmath_integral_d: \LWR__skmath_integral_d:
    { \CustomizeMathJax{\newcommand{\d}{\mathit{d}}} }
    { \CustomizeMathJax{\newcommand{\d}{\mathrm{d}}} }
```

Used to parse comma and caret arguments for `\pd` and `\td`:

```
\CustomizeMathJax{\def\LWRskmathEND{}}
```

Parse the arguments with up to four commas. Argument 6 contains any leftover commas.

```
\CustomizeMathJax{\def\LWRskmathpdstarsub#1#2,#3,#4,#5,#6\LWRskmathEND{
    #1_{#2#3#4#5}%
}}

\CustomizeMathJax{\newcommand{\LWRskmathpdstar}[2]{%
    \LWRskmathpdstarsub{#1}#2,,,,\LWRskmathEND%
}}
```

Parse the arguments with up to two carets. Argument 3 contains any leftover carets. `\LWRskmathpdplus` is used to only place a plus sign starting after the first term.

```
    \LWRskmathtrigtwo%
}}

\CustomizeMathJax{\renewcommand{\sin}{\LWRskmathtrig{sin}}}
\CustomizeMathJax{\renewcommand{\arcsin}{\LWRskmathtrig{arcsin}}}

\CustomizeMathJax{\renewcommand{\cos}{\LWRskmathtrig{cos}}}
\CustomizeMathJax{\renewcommand{\arccos}{\LWRskmathtrig{arccos}}}

\CustomizeMathJax{\renewcommand{\tan}{\LWRskmathtrig{tan}}}
\CustomizeMathJax{\renewcommand{\arctan}{\LWRskmathtrig{arctan}}}

\CustomizeMathJax{\renewcommand{\cot}{\LWRskmathtrig{cot}}}

\CustomizeMathJax{\renewcommand{\sinh}{\LWRskmathtrig{sinh}}}
\CustomizeMathJax{\renewcommand{\cosh}{\LWRskmathtrig{cosh}}}
\CustomizeMathJax{\renewcommand{\tanh}{\LWRskmathtrig{tanh}}}
```

Common code for `\ln` and `\log`:

```
\CustomizeMathJax{\newcommand{\LWRskmathlogtwo}[2][]{%
    \ifblank{#1}{}{_{#1}}%
    \ifblank{#2}{}{\left(#2\right)}%
}}

\CustomizeMathJax{\newcommand{\LWRskmathlog}[1]{%
    \operatorname{#1}%
    \LWRskmathlogtwo%
}}

\CustomizeMathJax{\renewcommand{\ln}{\LWRskmathlog{ln}}}
\CustomizeMathJax{\renewcommand{\log}{\LWRskmathlog{log}}}

\CustomizeMathJax{\newcommand{\LWRskmathexpparens}[1]{%
    \operatorname{exp}%
    \ifblank{#1}{}{\left(#1\right)}%
}}
```

See the skmath source for the original of the following:

```
\CustomizeMathJax{\newcommand{\LWRskmathexpnostar}[1]{%
    \mathchoice
        {\ee^{#1}}
        {\LWRskmathexpparens{#1}}
        {\LWRskmathexpparens{#1}}
        {\LWRskmathexpparens{#1}}
}}

\CustomizeMathJax{\renewcommand{\exp}{\ifstar\LWRskmathexpparens\LWRskmathexpnostar}}
```

Common code for `\min` etc:

```
\CustomizeMathJax{\newcommand{\LWRskmathminstar}[2][]{%
    \operatorname{\LWRskmathminname}%
```

```
    \ifblank{#1}{}{%
        _{\mathchoice{\mathclap{#1}}{#1}{#1}{#1}}
    }%
    \ifblank{#2}{}{#2}%
}}

\CustomizeMathJax{\newcommand{\LWRskmathminnostar}[2][]{%
    \ifblank{#1}%
        {\operatorname{\LWRskmathminname}}%
        {%
            \underset%
                {\mathchoice{\mathclap{#1}}{#1}{#1}{#1}}%
                {\operatorname{\LWRskmathminname}}%
        }%
    \ifblank{#2}{}{\left\{#2\right\}}%
}}
```

\LWRskmathminname seems to be recursion-safe since it is used immediately.

```
\CustomizeMathJax{\newcommand{\LWRskmathmin}[1]{%
    \def\LWRskmathminname{#1}%
    \ifstar\LWRskmathminstar\LWRskmathminnostar%
}}

\CustomizeMathJax{\renewcommand{\min}{\LWRskmathmin{min}}}
\CustomizeMathJax{\renewcommand{\argmin}{\arg\LWRskmathmin{min}}}

\CustomizeMathJax{\renewcommand{\max}{\LWRskmathmin{max}}}
\CustomizeMathJax{\renewcommand{\argmax}{\arg\LWRskmathmin{max}}}
\CustomizeMathJax{\renewcommand{\sup}{\LWRskmathmin{sup}}}
\CustomizeMathJax{\renewcommand{\inf}{\LWRskmathmin{inf}}}

\CustomizeMathJax{\let\bar\overline}

\CustomizeMathJax{\let\vec\boldsymbol}
```

Remember the original definitions:

```
\CustomizeMathJax{\let\LWRskmathRe\Re}
\CustomizeMathJax{\let\LWRskmathIm\Im}
```

Redefine depending on notation=iso:

```
\bool_if:NTF\g__skmath_iso_complex_parts_bool{
    \CustomizeMathJax{\renewcommand{\Re}[1]{%
        \LWRskmathRe%
        \ifblank{#1}{}{\left(#1\right)}%
    }}
    \CustomizeMathJax{\renewcommand{\Im}[1]{%
        \LWRskmathIm%
        \ifblank{#1}{}{\left(#1\right)}%
    }}
}{
    \CustomizeMathJax{\renewcommand{\Re}[1]{%
```

```
        \operatorname{Re}%
        \ifblank{#1}{}{#1}%
    }}
    \CustomizeMathJax{\renewcommand{\Im}[1]{%
        \operatorname{Im}%
        \ifblank{#1}{}{#1}%
    }}
}

\ExplSyntaxOff
\end{warpMathJax}
```

File 439 **lwarp-slantsc.sty**

# § 546 Package slantsc

(*Emulates or patches code by* Harald Harders.)

Pkg slantsc slantsc is emulated for HTML, and used as-is for print output.

**for HTML output:**

```
\LWR@ProvidesPackagePass{slantsc}[2012/01/01]

\newcommand*{\LWR@HTML@noscshape}{}
\LWR@formatted{noscshape}

\FilenameNullify{%
    \LetLtxMacro\noscshape\@empty%
}
```

File 440 **lwarp-slashed.sty**

# § 547 Package slashed

(*Emulates or patches code by* David Carlisle.)

Pkg slashed slashed works as-s for HTML SVG math. For MathJax, emulation is provided.

**for HTML output:**

```
\LWR@ProvidesPackagePass{slashed}[1997/01/16]

\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\slashed}[1]{\cancel{#1}}}
\end{warpMathJax}
```

File 441 **lwarp-soul.sty**

# § 548 Package soul

(*Emulates or patches code by* Melchior FRANZ.)

Pkg soul soul is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{soul}[2003/11/17]
\RequirePackage{xcolor}% for \convertcolorspec
```

Storage for the colors to use:

```
\newcommand*{\LWR@soululcolor}{}

\newcommand*{\LWR@soulstcolor}{}

% \definecolor{LWR@soulhlcolordefault}{HTML}{F8E800}
% \newcommand*{\LWR@soulhlcolor}{LWR@soulhlcolordefault}
\newcommand*{\LWR@soulhlcolor}{}
```

\so {⟨*text*⟩}

Basic markup with CSS:

```
\newcommand{\so}[1]{%
\InlineClass(letter-spacing:.2ex){letterspacing}{#1}%
}
```

\caps {⟨*text*⟩}

```
\newcommand{\caps}[1]{%
    \InlineClass%
        (font-variant:small-caps;letter-spacing:.1ex)%
        {capsspacing}{#1}%
}
```

\LWR@soulcolor {⟨*text*⟩} {⟨*color*⟩} {⟨*class*⟩} {⟨*colorstyle*⟩} {⟨*FormatWPstyle*⟩}

Add colors if not empty:

```
\newcommand{\LWR@soulcolor}[5]{%
\ifcsempty{#2}%
{%
    \InlineClass(#5){#3}{#1}%
}%
{%
    \convertcolorspec{named}{\@nameuse{#2}}{HTML}\LWR@tempcolor%
    \LWR@htmlspanclass[#5;#4:\LWR@origpound\LWR@tempcolor]{#3}{#1}%
}%
}

\newcommand{\ul}[1]{%
\LWR@soulcolor{#1}{LWR@soululcolor}{uline}{text-decoration-color}%
    {text-decoration:underline; text-decoration-skip: auto;}%
}

\newcommand{\st}[1]{
\LWR@soulcolor{#1}{LWR@soulstcolor}{sout}{text-decoration-color}%
    {text-decoration:line-through}%
}
```

```
\newcommand{\hl}[1]{
\LWR@soulcolor{#1}{LWR@soulhlcolor}{highlight}{background-color}%
    {background:\LWR@origpound{}F8E800}
}
```

Nullified:

```
\newcommand*{\soulaccent}[1]{}
\newcommand*{\soulregister}[2]{}
\newcommand{\sloppyword}[1]{#1}
\newcommand*{\sodef}[5]{\DeclareRobustCommand*#1[1]{\so{##1}}}
\newcommand*{\resetso}{}
\newcommand*{\capsdef}[5]{}
\newcommand*{\capsreset}{}
\newcommand*{\capssave}[1]{}
\newcommand*{\capsselect}[1]{}
\newcommand*{\setul}[2]{}
\newcommand*{\resetul}{}
\newcommand*{\setuldepth}[1]{}
\newcommand*{\setuloverlap}[1]{}
\newcommand*{\<}{}
```

Set colors:

```
\newcommand*{\setulcolor}[1]{\renewcommand{\LWR@soululcolor}{#1}}
\newcommand*{\setstcolor}[1]{\renewcommand{\LWR@soulstcolor}{#1}}
\newcommand*{\sethlcolor}[1]{\renewcommand{\LWR@soulhlcolor}{#1}}
```

Long versions of the user-level macros:

```
\let\textso\so
\let\textul\ul
\let\texthl\hl
\let\textcaps\caps
```

---

File 442 **lwarp-soulpos.sty**

§ 549 Package

# soulpos

(*Emulates or patches code by* Javier Bezos.)

Pkg soulpos soulpos is emulated.

**for HTML output:**

```
\RequirePackage{soul}
\RequirePackage{soulutf8}
\LWR@ProvidesPackageDrop{soulpos}[2012/02/25]

\NewDocumentCommand{\ulposdef}{m o m}{}

\newdimen\ulwidth

```

```
\newcommand\ifulstarttype[1]{%
\expandafter\@secondoftwo%
}

\newcommand\ifulendtype[1]{%
\expandafter\@secondoftwo%
}

\newcommand{\ulstarttype}{0}
\newcommand{\ulendtype}{0}
\newcommand\ulpostolerance{0}%
```

---

File 443 **lwarp-soulutf8.sty**

## § 550 Package soulutf8

Pkg soulutf8 soulutf8 is emulated.

lwarp's HTML output naturally supports UTF-8 encoding.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{soulutf8}[2016/05/16]
\RequirePackage{soul}
```

---

File 444 **lwarp-splitbib.sty**

## § 551 Package splitbib

(*Emulates or patches code by* Nicolas Markey.)

Pkg splitbib splitbib is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{splitbib}[2005/12/22]

\def\NMSB@stylebox#1#2{%
\begin{BlockClass}[text-align:center ; border: 1px solid black]{splitbibbox}
    \csname SB\NMSB@level font\endcsname{\LWR@textcurrentfont{#1#2}}
\end{BlockClass}
}

\def\NMSB@stylebar#1#2{%
\begin{BlockClass}[%
    text-align:center ;
    border-top: 1px solid black ;
    border-bottom: 1px solid black ;
]{splitbibbar}
    \csname SB\NMSB@level font\endcsname{\LWR@textcurrentfont{#1#2}}
\end{BlockClass}
}

\def\NMSB@styledash#1#2{%
```

```
\begin{BlockClass}[%
    text-align:center ;
]{splitbibdash}
    \csname SB\NMSB@level font\endcsname{\LWR@textcurrentfont{---~#1#2~---}}
\end{BlockClass}
}

\def\NMSB@stylenone#1#2{%
    \par
}

\def\NMSB@stylesimple#1#2{%
\par
 \csname SB\NMSB@level font\endcsname{\LWR@textcurrentfont{#1#2}}
\par
}
```

File 445 **lwarp-splitidx.sty**

§ 552 Package

# splitidx

(*Emulates or patches code by* Markus Kohm.)

Pkg splitidx splitidx is patched for use by lwarp.

If the latexmk option is selected for lwarp, *latexmk* will compile the document but will *not* compile the indexes. **lwarpmk printindex** and **lwarpmk htmlindex** will still be required.

⚠ \thepage When using \AtWriteToIndex or \AtNextWriteToIndex, the user must not refer to \thepage during HTML output, as the concept of a page number is meaningless. Instead, do

```
\addtocounter{LWR@autoindex}{1}
\LWR@new@label{LWRindex-\arabic{LWR@autoindex}}
```

where the \index-like action occurs, and then refer to \arabic{LWR@autoindex} instead of \thepage where the reference should occur.

See section 671.17 in the lwarp-patch-memoir package for the \@@wrspindexhyp macro as an example.

**for HTML output:**

```
\LWR@ProvidesPackagePass{splitidx}[2016/02/18]

\catcode`\_=12%
\xpatchcmd{\newindex}
    {\jobname-#2.idx}
    {\jobname-#2_html.idx}
    {}
    {\LWR@patcherror{splitidx}{@newindex}}
\catcode`\_=8%
```

Patched to use lwarp's automatic indexing counter instead of \thepage:

```
\renewcommand*{\@wrsindex}[2][]{%
  \ifx\relax#1\relax
    \if@splitidx
      \@wrsindex[idx]{#2}%
    \else
      \def\@tempa{#2}%
      \if@verbindex\@onelevel@sanitize\@tempa\fi
      \@wrindex{\@tempa}%
    \fi
  \else
    \def\@tempa{#2}%
    \csname index@#1@hook\endcsname
%     \expandafter\ifx\csname @@wrsindex\endcsname\relax
    \addtocounter{LWR@autoindex}{1}%                    lwarp
    \label{LWRindex-\arabic{LWR@autoindex}}%    lwarp
%       \@@@wrsindex{#1}{{\@tempa}{\thepage}}%
      \@@@wrsindex{#1}{{\@tempa}{\arabic{LWR@autoindex}}}%
%     \else
%       \def\@tempb{\@@wrsindex{#1}}%
%       \expandafter\@tempb\@tempa||\\%
%     \fi
    \endgroup
    \@esphack
  \fi
}
```

lwarp defines sectioning commands with xparse, so the below patches are done as temporary redefinitions instead of being `\let`.

```
\xpatchcmd{\printsubindex}
    {\let\section\subsection}
    {\renewcommand*{\section}{\subsection}}
    {}
    {\LWR@patcherror{splitidx}{printsubindex-section}}

\xpatchcmd{\printsubindex}
    {\let\chapter\section}
    {\renewcommand*{\chapter}{\section}}
    {}
    {\LWR@patcherror{splitidx}{printsubindex-chapter}}

\xpatchcmd{\printsubindex}
    {\let\@makechapterhead\section}
    {\def\@makechapterhead{\section}}
    {}
    {\LWR@patcherror{splitidx}{printsubindex-chapter}}
```

---

File 446 **lwarp-srcltx.sty**

§ 553 Package # srcltx

Pkg srcltx srcltx is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{srcltx}[2006/11/12]

\newif\ifSRCOK \SRCOKfalse
\newcommand*\srcIncludeHook[1]{}
\newcommand*\srcInputHook[1]{}
\newcommand*\MainFile{}
\def\MainFile{\jobname.tex}
\newcommand*\CurrentInput{}
\gdef\CurrentInput{\MainFile}
\newcommand\Input{}
\let\Input\input
```

---

File 447 **lwarp-srctex.sty**

## § 554 Package srctex

Pkg srctex srctex is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{srctex}[2006/11/12]
\LWR@origRequirePackage{lwarp-srcltx}
```

---

File 448 **lwarp-stabular.sty**

## § 555 Package stabular

(*Emulates or patches code by* Sigitas Tolušis.)

Pkg stabular stabular is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{stabular}[2014/03/20]
```

Env stabular [⟨*vpos*⟩] {⟨*colspec*⟩}

```
\newenvironment{stabular}[2][c]
{
\begin{tabular}[#1]{#2}
\renewcommand{\noalign}[1]{}
}
{\end{tabular}}
```

Env stabular {⟨*width*⟩} [⟨*vpos*⟩] {⟨*colspec*⟩}

```
\NewDocumentEnvironment{stabular*}{m o m}
{
\begin{tabular}[#2]{#3}
\renewcommand{\noalign}[1]{}
}
{\end{tabular}}
```

File 449 **lwarp-stackengine.sty**

## § 556 Package stackengine

```
\xpatchcmd{\stackanchor}{\stackengine}{\LWR@orig@stackengine}
    {}
    {\LWR@patcherror{stackengine}{stackanchor patch 2}}

\xpretocmd{\stackanchor}
    {\begin{lateximage}[\ImageAltText][][vertical-align:middle]}
    {}
    {\LWR@patcherror{stackengine}{stackanchor pre}}

\xapptocmd{\stackanchor}{\end{lateximage}}
    {}
    {\LWR@patcherror{stackengine}{stackanchor app}}
```

`\Centerstack` is simply placed inside a `lateximage` with a vertical alignment:

```
\xpretocmd{\Centerstack}
    {\begin{lateximage}[\ImageAltText][][vertical-align:middle]}
    {}
    {\LWR@patcherror{stackengine}{Centerstack pre}}

\xapptocmd{\Centerstack}{\end{lateximage}}
    {}
    {\LWR@patcherror{stackengine}{Centerstack app}}
```

`\savestack` reverts to print mode while saving the box, then places it inside a `lateximage` when used:

```
\renewcommand*\savestack[2]{%
  \xdef\sv@name{\stack@macro@name{#1}}%
  \@ifundefined{\sv@name content}{%
    \expandafter\newsavebox\expandafter{\csname\sv@name content\endcsname}%
   }{}%
    \begingroup%    lwarp
    \LWR@restoreorigformatting%     lwarp
    \RenewDocumentEnvironment{lateximage}{s o s o o}{}{}% lwarp: inside group
  \expandafter\LWR@gsavebox\csname\sv@name content\endcsname{#2}%
  \expandafter\gdef\expandafter#1\expandafter{%
        \expandafter\begin\expandafter{lateximage\expandafter}%     lwarp
        \expandafter\usebox\expandafter%
        {\csname\sv@name content\endcsname}%
        \expandafter\end\expandafter{lateximage\expandafter}%       lwarp
    }%
    \endgroup%      lwarp
}
```

---

File 450 **lwarp-stackrel.sty**

## § 557 Package stackrel

(*Emulates or patches code by* Heiko Oberdiek.)

Pkg stackrel stackrel is used as-is for SVG math, and is emulated for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{stackrel}[2016/05/16]

\begin{warpMathJax}
\CustomizeMathJax{\renewcommand{\stackrel}[3][]{%
    \mathrel{\mathop{#3}\limits_{#1}^{#2}}%
}}

\CustomizeMathJax{\newcommand{\stackbin}[3][]{%
    \mathbin{\mathop{#3}\limits_{#1}^{#2}}%
}}
\end{warpMathJax}
```

---

File 451 **lwarp-statex2.sty**

# § 558 Package statex2

(*Emulates or patches code by* Rodney A Sparapani.)

Pkg statex2 statex2 is patched for use by lwarp, and emulated for MathJax.

⚠ As of this version, option autobold does not appear to work for PDF output.

⚠ For MathJax, the tilde character ~ does not create \sim. Use \sim directly.

⚠ Because MathJax has limited conditional processing:

- \wrap only creates square braces, no matter what its optional arguments.
- \P, \pCau, \pN, and \pU do not handle special cases.

⚠ \and To have \and work if using \maketitle, place the following after the start of the document:

```
\newcommand*{\and}{%
    \relax\ifmmode%
        \expandafter\;\mb{\mathrm{and}}\;%
    \else%
        \expandafter\STATEXand%
    \fi%
}
```

**for HTML output:**

```
\LWR@ProvidesPackagePass{statex2}[2011/09/14]

\newcommand*{\LWR@HTML@Alpha}[1][]{%
    \fcolorbox{black}{ForestGreen}{\textcolor{white}{\textsf{ALPHA}}}%
    \textbf{\textcolor{ForestGreen}{\textsf{#1}}}%
}
\LWR@formatted{Alpha}

\newcommand*{\LWR@HTML@List}[1]{%
    \textbf{\textcolor{Dandelion}{\textsf{L}\textsubscript{\textit{#1}}}}%
```

```
}
\LWR@formatted{List}

\newcommand*{\LWR@HTML@Snd}[1][]{%
    \fcolorbox{black}{Dandelion}{\textcolor{white}{\textsf{2nd}}}%
    \textbf{\textcolor{Dandelion}{\textsf{#1}}}%
}
\LWR@formatted{Snd}

\begin{warpMathJax}
\LWR@infoprocessingmathjax{statex2}

\CustomizeMathJax{\newcommand{\cpi}{\boldsymbol{\pi}}}
\CustomizeMathJax{\newcommand{\c}[1]{\boldsymbol{\mathrm{#1}}}}
\CustomizeMathJax{\newcommand{\sfsl}[1]{\mathsf#1}}%     not slanted

\if@manualbold
\CustomizeMathJax{\newcommand{\mb}[1]{#1}}
\else
\CustomizeMathJax{\newcommand{\mb}[1]{\boldsymbol{#1}}}
\fi

\CustomizeMathJax{\newcommand{\diag}{\mb{\mathrm{diag}}}}
\CustomizeMathJax{\newcommand{\blockdiag}{\mb{\mathrm{blockdiag}}}}
\CustomizeMathJax{\newcommand{\erf}{\mb{\mathrm{erf}}}}
\CustomizeMathJax{\newcommand{\logit}{\mb{\mathrm{logit}}}}
\CustomizeMathJax{\newcommand{\trace}{\mb{\mathrm{trace}}}}

\CustomizeMathJax{\newcommand{\chisq}{{\mb{\chi^2}}}}
\CustomizeMathJax{\newcommand{\deriv}[2]{\mb{\frac{\d{}}{\d{#1}}}\wrap{\mb{#2}}}}
\CustomizeMathJax{\newcommand{\derivf}[2]{\mb{\frac{\d{}}{\d{#2}}}\wrap{\mb{#1}}}}
\CustomizeMathJax{\newcommand{\e}[1]{\mb{\mathrm{e}^{#1}}}}
\CustomizeMathJax{\newcommand{\E}[2][]{\mb{\mathrm{E}}_{\mb{#1}} \wrap{\mb{#2}}}}
\CustomizeMathJax{\newcommand{\ha}{{\mb{\frac{\alpha}{2}}}}}
\CustomizeMathJax{\newcommand{\I}[2][]{%
    \mb{\mathrm{I}}_{\mb{#1}} \LWRwrapparen{\mb{#2}}%
}}
\CustomizeMathJax{\newcommand{\IBeta}[2]{%
    \mb{\frac{\Gamma[#1+#2]}{\Gamma[#1]\Gamma[#2]}}%
}}
\CustomizeMathJax{\newcommand{\If}{\;\mb{\mathrm{if}}\;}}
\CustomizeMathJax{\newcommand{\im}{\mb{\mathrm{i}}}}
\CustomizeMathJax{\newcommand{\ol}{\overline}}
\CustomizeMathJax{\newcommand{\ow}{\;\mb{\mathrm{otherwise}}\;}}
\CustomizeMathJax{\newcommand{\pderiv}[2]{%
    \mb{\frac{\partial}{\partial #1}}\wrap{\mb{#2}}%
}}
\CustomizeMathJax{\newcommand{\pderivf}[2]{%
    \mb{\frac{\partial}{\partial #2}}\wrap{\mb{#1}}%
}}
\CustomizeMathJax{\newcommand{\sd}{\mb{\sigma}}}
\CustomizeMathJax{\newcommand{\ul}{\underline}}
\CustomizeMathJax{\newcommand{\V}[2][]{\mb{\mathrm{V}}_{\mb{#1}} \wrap{\mb{#2}}}}
\CustomizeMathJax{\newcommand{\vs}{\;\mb{\mathrm{vs.}}\;}}
\CustomizeMathJax{\newcommand{\where}{\;\mb{\mathrm{where}}\;}}
```

```
\CustomizeMathJax{\newcommand{\wrap}[2][]{\left[ #2 \right]}}%         only []
\CustomizeMathJax{\newcommand{\LWRwrapparen}[1]{\left( #1 \right)}}%    lwarp

% \CustomizeMathJax{\renewcommand{~}{\mb{\sim}}}% doesn't work,
% replace <space>~<space> with <space>\sim<space>

\CustomizeMathJax{\newcommand{\iid}{\;\stackrel{\mb{\mathrm{iid}}}{\sim}\;}}
\CustomizeMathJax{\newcommand{\ind}{\;\stackrel{\mb{\mathrm{ind}}}{\sim}\;}}
\CustomizeMathJax{\newcommand{\indpr}{%
    \;\stackrel{\mb{\mathrm{ind}}}{\stackrel{\mb{\mathrm{prior}}}{\sim}}\;%
}}
\CustomizeMathJax{\newcommand{\post}{\;\stackrel{\mb{\mathrm{post}}}{\sim}\;}}
\CustomizeMathJax{\newcommand{\prior}{\;\stackrel{\mb{\mathrm{prior}}}{\sim}\;}}

\CustomizeMathJax{\let\STATEXGamma=\Gamma}
\CustomizeMathJax{\renewcommand{\Gamma}[1][]{\mb{\STATEXGamma}\LWRwrapparen{\mb{#1}}}}
%
\CustomizeMathJax{\renewcommand{\and}{\;\mb{\mathrm{and}}\;}}
%
\CustomizeMathJax{\newcommand{\H}{\mb{\mathrm{H}}}}
%
\CustomizeMathJax{\newcommand{\P}[2][]{\mb{\mathrm{P}}_{\mb{#1}}\wrap{\mb{#2}}}}
%
\CustomizeMathJax{\newcommand{\|}{\mb{\mid}}}

\CustomizeMathJax{\newcommand{\B}[1]{\mb{\mathrm{B}}\LWRwrapparen{\mb{#1}}}}
\CustomizeMathJax{\newcommand{\BB}[1]{\mb{\mathrm{BetaBin}}\LWRwrapparen{\mb{#1}}}}
\CustomizeMathJax{\newcommand{\Bin}[2]{\mb{\mathrm{Bin}}\LWRwrapparen{\mb{#1,\ #2}}}}
\CustomizeMathJax{\newcommand{\Dir}[1]{\mb{\mathrm{Dirichlet}}\LWRwrapparen{\mb{#1}}}}
\CustomizeMathJax{\newcommand{\HG}[3]{%
    \mb{\mathrm{Hypergeometric}}\LWRwrapparen{\mb{#1,\ #2,\ #3}}%
}}
\CustomizeMathJax{\newcommand{\M}[2]{%
    \mb{\mathrm{Multinomial}}\LWRwrapparen{\mb{#1,\ #2}}%
}}
\CustomizeMathJax{\newcommand{\NB}[2]{\mb{\mathrm{NegBin}}\LWRwrapparen{\mb{#1,\ #2}}}}
\CustomizeMathJax{\newcommand{\Poi}[1]{\mb{\mathrm{Poisson}}\LWRwrapparen{\mb{#1}}}}
\CustomizeMathJax{\let\Poisson=\Poi}

\CustomizeMathJax{\newcommand{\pBB}[4][x]{%
    \mb{\frac{\Gamma[#2+1]\Gamma[#3+#1]\Gamma[#2+#4-#1]\Gamma[#3+#4]}%
    {\Gamma[#1+1]\Gamma[#2-#1+1]\Gamma[#2+#3+#4]\Gamma[#3]\Gamma[#4]}%
    \I[#1]{\{0, 1,\., #2\}}, \where #3>0,\; #4>0 \and n=1, 2,\.}%
}}
\CustomizeMathJax{\newcommand{\pBin}[3][x]{%
    \mb{\binom{#2}{#1}#3^{#1}} \LWRwrapparen{\mb{{1-#3}^{#2-#1}}}%
    \mb{\I[#1]{\{0,1,\.,#2\}}, \where p \in (0, 1) \and n=1, 2,\.}%
}}
\CustomizeMathJax{\newcommand{\pPoi}[2][x]{%
    \mb{\frac{1}{#1!}#2^{#1}\e{-#2}\I[#1]{\{0, 1,\.\}}, \where #2>0}%
}}

\CustomizeMathJax{\newcommand{\Cau}[2]{\mb{\mathrm{Cauchy}}\LWRwrapparen{\mb{#1,\ #2}}}}
\CustomizeMathJax{\let\Cauchy=\Cau}
\CustomizeMathJax{\newcommand{\Chi}[2][]{%
```

```
    \chisq_{\mb{#1}}\LWRwrapparen{\mb{#2}}%
}}
\CustomizeMathJax{\let\Chisq=\Chi}
\CustomizeMathJax{\newcommand{\Bet}[2]{\mb{\mathrm{Beta}}\LWRwrapparen{\mb{#1,\ #2}}}}
\CustomizeMathJax{\let\Beta=\Bet}
\CustomizeMathJax{\newcommand{\Exp}[1]{\mb{\mathrm{Exp}}\LWRwrapparen{\mb{#1}}}}
\CustomizeMathJax{\newcommand{\F}[2]{\mb{\mathrm{F}}\LWRwrapparen{\mb{#1,\ #2}}}}
\CustomizeMathJax{\newcommand{\Gam}[2]{\mb{\mathrm{Gamma}}\LWRwrapparen{\mb{#1,\ #2}}}}
\CustomizeMathJax{\newcommand{\IC}[1]{\mb{\mathrm{\chi^{-2}}}\LWRwrapparen{\mb{#1}}}}
\CustomizeMathJax{\newcommand{\IG}[2]{%
    \mb{\mathrm{Gamma^{-1}}}\LWRwrapparen{\mb{#1,\ #2}}%
}}
\CustomizeMathJax{\newcommand{\IW}[2]{%
    \mb{\mathrm{Wishart^{-1}}}\LWRwrapparen{\mb{#1,\ #2}}%
}}
\CustomizeMathJax{\newcommand{\Log}[2]{%
\mb{\mathrm{Logistic}}\LWRwrapparen{\mb{#1,\ #2}}%
}}
\CustomizeMathJax{\newcommand{\LogN}[2]{%
    \mb{\mathrm{Log\!-\!N}}\LWRwrapparen{\mb{#1,\ #2}}%
}}
\CustomizeMathJax{\newcommand{\N}[3][]{%
    \mb{\mathrm{N}}_{\mb{#1}}\LWRwrapparen{\mb{#2,\ #3}}%
}}
\CustomizeMathJax{\newcommand{\Par}[2]{\mb{\mathrm{Pareto}}\LWRwrapparen{\mb{#1,\ #2}}}}
\CustomizeMathJax{\let\Pareto=\Par}
\CustomizeMathJax{\newcommand{\Tsq}[2]{\mb{\mathrm{T^2}}\LWRwrapparen{\mb{#1,\ #2}}}}
\CustomizeMathJax{\newcommand{\U}[1]{\mb{\mathrm{U}}\LWRwrapparen{\mb{#1}}}}
\CustomizeMathJax{\newcommand{\W}[2]{\mb{\mathrm{Wishart}}\LWRwrapparen{\mb{#1,\ #2}}}}

\CustomizeMathJax{\renewcommand{\t}[1]{\mb{\mathrm{t}}\LWRwrapparen{\mb{#1}}}}

\CustomizeMathJax{\newcommand{\pBet}[3][x]{%
    \IBeta{#2}{#3}%
    #1^{#2-1}\LWRwrapparen{1-#1}^{#3-1}\I[#1]{0,\ 1}, \where #2>0 \and #3>0%
}}
\CustomizeMathJax{\newcommand{\pCau}[3][x]{%
%     \ifthenelse{\equal{#2, #3}{0, 1}}{\frac{1}{\cpi\LWRwrapparen{1+#1}^2}}%
  {\frac{1}{#3\cpi\left\{1+\wrap{\LWRwrapparen{x-#2}/#3}^2\right\}}, \where #3>0}%
}}% no special case for 0,1
\CustomizeMathJax{\newcommand{\pChi}[2][x]{%
    \frac{2^{-#2/2}}{\Gamma[#2/2]}#1^{#2/2-1}\e{-#1/2}%
    \I[#1]{0,\infty}, \where #2>0%
}}
\CustomizeMathJax{\newcommand{\pExp}[2][x]{%
    \frac{1}{#2}\e{-#1/#2}\I[#1]{0,\infty},%
    \where #2>0%
}}
\CustomizeMathJax{\newcommand{\pGam}[3][x]{%
    \frac{#3^{#2}}{\Gamma[#2]}#1^{#2-1}\e{-#3#1}%
    \I[#1]{0,\infty}, \where #2>0 \and #3>0%
}}
\CustomizeMathJax{\newcommand{\pN}[3][x]{%
%     \ifthenelse{\equal{#2, #3}{0, 1}}%
%     {\frac{1}{\sqrt{2\cpi}}\e{-#1^2/2}}%
```

```
    {\frac{1}{\sqrt{2\cpi \cdot #3}}\e{-\LWRwrapparen{#1-#2}^2/2 \cdot #3}}%
}}% no test for 0,1, must add \cdot
\CustomizeMathJax{\newcommand{\pPar}[3][x]{%
    \frac{#3}{#2\LWRwrapparen{1+#1/#2}^{#3+1}}\I[#1]{0,\infty},%
    \where #2>0 \and #3>0%
}}
\CustomizeMathJax{\newcommand{\pU}[3][x]{%
%     \ifthenelse{\equal{#2, #3}{0, 1}}{\I[#1]{0,\ 1}}%
    {\frac{1}{#3-#2}\I[#1]{#2,\ #3}, \where #2<#3}%
}}% no special case for 0,1

\CustomizeMathJax{\newcommand{\=}[1]{\bar{#1}}}
\CustomizeMathJax{\let\^\widehat}
\CustomizeMathJax{\let\~\widetilde}
\CustomizeMathJax{\newcommand{\'}[1]{\LWRwrapparen{\mb{#1}}}}
\CustomizeMathJax{\newcommand{\b}[1]{\bar{#1}}}
\CustomizeMathJax{\newcommand{\c}[1]{\mb{\mathrm{#1}}}}
\CustomizeMathJax{\newcommand{\d}[1]{\,\mb{\mathrm{d}{#1}}}}
\CustomizeMathJax{\newcommand{\.}{\mb{\ldots}}}
\end{warpMathJax}
```

---

File 452 **lwarp-statistics.sty**

§ 559 Package

# statistics

(*Emulates or patches code by* Julien Rivaud.)

Pkg statistics statistics is patched for use by lwarp.

⚠ \color The statistics documentation examples include the use of the \color macro. Use \textcolor instead.

⚠ math The statistics package uses math arrays, but the HTML version uses text tabulars to allow text copy/paste. If math is required, use \ensuremath or \( and \) as needed.

Pre/postline is ignored, and \hline is used instead. Each table will have an \hline above and below as a frame.

**for HTML output:**

```
\LWR@ProvidesPackagePass{statistics}[2019/09/29]

\ExplSyntaxOn
```

To use text tabular instead of math array. This allows text copy/paste of the results.

In the following, all changes for the Lwarp package are labelled "lwarp".

Redefined using the lwarp version of &:

```
\StartDefiningTabulars%     lwarp
\cs_set_protected_nopar:Nn \__statistics_table_make:nn {
    \int_compare:nT
            { 0 < \l__statistics_table_maxcols_int
                = \l__statistics_nbvals_int } {
```

```
        \__statistics_table_end:
        \tl_use:N \l__statistics_table_sep_tl
        \__statistics_table_start:
    }
    \int_incr:N \l__statistics_nbvals_int
    \int_incr:N \l__statistics_currange_int
    \fp_add:Nn \l__statistics_curtotal_fp { #2 }
    \__statistics_set_if_shown:N \l_tmpa_bool
    \tl_set:Nx \l_tmpa_tl {
        \exp_not:n { & \tl_set:Nn \currentcolumn } {
            \int_use:N \l__statistics_currange_int
        }
    }
    \bool_if:NTF \l_tmpa_bool {
        \tl_put_right:Nn \l_tmpa_tl
            {\__statistics_table_shown_format:n}
    }{
        \tl_put_right:Nn \l_tmpa_tl
            {\__statistics_table_hidden_format:n}
    }
    \seq_put_right:Nn \l__statistics_store_values_seq { #1 }
    \bool_if:NT \l__statistics_table_values_bool {
        \tl_put_right:Nx \l__statistics_table_values_tl {
            \exp_not:V \l_tmpa_tl {
                \exp_not:n {
                    \__statistics_table_values_format:n { #1 }
                }
            }
        }
    }
    \seq_put_right:Nx \l__statistics_store_counts_seq { \fp_eval:n {#2} }
    \bool_if:NT \l__statistics_table_counts_bool {
        \tl_put_right:Nx \l__statistics_table_counts_tl {
            \exp_not:V \l_tmpa_tl {
                \exp_not:n {
                    \__statistics_table_counts_format:n {
                        { \__statistics_table_allcounts_format:n { #2 } }
                    }
                }
            }
        }
    }
    \bool_if:NT \l__statistics_table_icc_bool {
        \tl_put_right:Nx \l__statistics_table_icc_tl {
            \exp_not:V \l_tmpa_tl {
                \exp_not:n { \__statistics_table_icc_format:n }
                {
                    \exp_not:n{ \__statistics_table_allcounts_format:n }
                        { \fp_use:N \l__statistics_curtotal_fp }
                }
            }
        }
    }
    \bool_if:NT \l__statistics_table_dcc_bool {
        \tl_put_right:Nx \l__statistics_table_dcc_tl {
```

```
            \exp_not:V \l_tmpa_tl {
                \exp_not:n { \__statistics_table_dcc_format:n }
                {
                    \exp_not:n{ \__statistics_table_allcounts_format:n }
                    {
                        \fp_eval:n {
                            \l__statistics_total_fp
                                - \l__statistics_curtotal_fp
                                + #2
                        }
                    }
                }
            }
        }
    }
    \fp_set:Nn \l__statistics_table_curICF_fp {
        round(\l__statistics_curtotal_fp
                / \l__statistics_total_fp,
            \l__statistics_table_round_int)
    }
    \bool_if:NT \l__statistics_table_frequencies_bool {
        \tl_put_right:Nx \l__statistics_table_frequencies_tl {
            \exp_not:V \l_tmpa_tl {
                \exp_not:n { \__statistics_table_frequencies_format:n }
                {
                    \exp_not:n{ \__statistics_table_allfreqs_format:n }
                    {
                        \fp_eval:n {
                            \l__statistics_table_curICF_fp
                                - \l__statistics_table_prevICF_fp
                        }
                    }
                }
            }
        }
    }
    \bool_if:NT \l__statistics_table_icf_bool {
        \tl_put_right:Nx \l__statistics_table_icf_tl {
            \exp_not:V \l_tmpa_tl {
                \exp_not:n { \__statistics_table_icf_format:n }
                {
                    \exp_not:n{ \__statistics_table_allfreqs_format:n }
                        { \fp_to_decimal:N \l__statistics_table_curICF_fp }
                }
            }
        }
    }
    \bool_if:NT \l__statistics_table_dcf_bool {
        \tl_put_right:Nx \l__statistics_table_dcf_tl {
            \exp_not:V \l_tmpa_tl {
                \exp_not:n { \__statistics_table_dcf_format:n }
                {
                    \exp_not:n{ \__statistics_table_allfreqs_format:n }
                    {
                        \fp_eval:n {
```

## § 578 Package tascmac

Pkg tascmac tascmac is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{tascmac}[2018/03/09]

\newenvironment*{boxnote}
    {
        \BlockClass[
            padding: .5ex ;
            border: 1px solid black ;
            border-top: 1px dashed black ;
        ]{boxnote}
    }
    {\endBlockClass}

\newenvironment*{screen}[1][]
    {
        \BlockClass[
            padding: .5ex ;
            border: 1px solid gray ;
            border-radius: 8pt
        ]{boxnote}
    }
    {\endBlockClass}

\newenvironment*{itembox}[2][]
    {
        \BlockClass[
            padding: .5ex ;
            border: 1px solid gray ;
            border-radius: 8pt
        ]{boxnote}
        \InlineClass{itemboxtitle}{#2}\par
    }
    {\endBlockClass}

\newenvironment*{shadebox}
    {
        \BlockClass[
            padding: .5ex ;
            border: 1px solid black ;
            box-shadow: 3px 3px 3px \#808080 ;
        ]{boxnote}
    }
    {\endBlockClass}

\newcommand*{\mask}[2]{%
    \InlineClass[background: lightgray]{mask}{#1}%
}

\newcommand*{\maskbox}[5]{%
    \InlineClass[background: lightgray]{mask}{#5}%
}

```

```
\newcommand*{\Maskbox}[6]{%
    \InlineClass[
        background: lightgray ;
        border: #5 solid black
    ]{mask}{#6}%
}

\newcommand*{\keytop}[2][]{%
    \InlineClass[%
        padding: .2ex ;
        border: 1px solid black ;
        border-radius: .7ex ;
    ]{keytop}{#2}%
}

\def\yen{\HTMLunicode{00A5}}

\def\return{\HTMLunicode{23CE}}

\def\Return{\HTMLunicode{23CE}}

\def\ascii{ASCII Corporation}

\def\Ascii{ASCII Corporation}

\def\ASCII{ASCII Corporation}
```

---

File 472 **lwarp-tcolorbox.sty**

§ 579 Package

# tcolorbox

(*Emulates or patches code by* Thomas F. Sturm.)

Pkg tcolorbox tcolorbox is patched for use by lwarp.

See section 8.3.8 for limitations.

**for HTML output:**

```
\LWR@ProvidesPackagePass{tcolorbox}[2020/04/28]

\newbool{LWR@havetcblower}
\boolfalse{LWR@havetcblower}
```

Colors are supported via HTML styles:

```
\newcommand{\LWR@tcolorbox@findcolors}{%
    \convertcolorspec{named}{tcbcolback}{HTML}\LWR@tcbcolback
    \convertcolorspec{named}{tcbcolframe}{HTML}\LWR@tcbcolframe
    \iftcb@titlefilled%
        \convertcolorspec{named}{tcbcolbacktitle}{HTML}\LWR@tcbcolbacktitle
    \else
        \convertcolorspec{named}{tcbcolframe}{HTML}\LWR@tcbcolbacktitle
    \fi
    \convertcolorspec{named}{tcbcoltitle}{HTML}\LWR@tcbcoltitle
```

```
        \boolfalse{LWR@havetcblower}
        \LWR@tcolorboxstart{tcolorbox}
        \tcb@insert@before@upper%
    }
    {
        \ifbool{LWR@havetcblower}{%
            \tcb@insert@after@lower%
        }{%
            \tcb@insert@after@upper%
        }%
        \end{BlockClass}
        \LWR@printpendingfootnotes
        \tcb@layer@dec
        \end{BlockClass}
        \LWR@tcolorbox@doendfloat%
    }
```

For the lower part, the upper part is finished then the lower is started. `\tcblower` is only temporarily defined where appropriate, so the HTML version is defined globally via `\newcommand` instead of `\renewcommand`.

```
\newcommand{\tcblower}{
    \tcb@insert@after@upper%
    \end{BlockClass}
    \begin{BlockClass}[%
        border-top: 1px dashed \LWR@origpound\LWR@tcbcolframe ;
        color: \LWR@origpound\LWR@tcbcollower ;
    ]{tcolorboxlower}
    \tcb@insert@before@lower%
}
```

Starred and unstarred `\tcbline` are simple `\hrule`s.

```
\AtBeginDocument{
\ifdef{\tcbline}{
    \newcommand*{\LWR@sub@tcbline}{%
        \begin{BlockClass}{hrule}
        \end{BlockClass}
    }
    \newcommand{\LWR@HTML@tcbline}{\@ifstar\LWR@sub@tcbline\LWR@sub@tcbline}
    \LWR@formatted{tcbline}
}{}
}

\newcommand{\LWR@HTML@tcbox}[2][]{
    \LWR@printpendingfootnotes
    \LWR@tcolorbox@dostartfloat%
    \begingroup
    \tcb@layer@inc
    \tcb@apply@box@options{#1}
%     \tcbset{title=,#1}
    \boolfalse{LWR@havetcblower}
    \LWR@tcolorboxstart{tcolorbox inlineminipage}
    \tcb@insert@before@upper%
    #2
```

```
    \ifbool{LWR@havetcblower}{%
        \tcb@insert@after@lower%
    }{%
        \tcb@insert@after@upper%
    }%
    \end{BlockClass}
    \LWR@printpendingfootnotes
    \end{BlockClass}
    \tcb@layer@dec%
    \endgroup%
    \LWR@tcolorbox@dostartfloat%
    \global\booltrue{LWR@minipagethispar}%
}
\LWR@formatted{tcbox}

\appto\LWR@restoreMathJaxformatting{%
    \renewcommand{\tcbox}[2][]{#2}%
}
```

Patches for the subtitle, which is placed inside a  of class tcolorboxsubtitle.

```
\xpatchcmd{\tcbsubtitle}
    {\begingroup}
    {\begingroup\let\kvtcb@title\relax\begin{BlockClass}{tcolorboxsubtitle}}
    {}
    {\LWR@patcherror{tcolorbox}{tcbsubtitle}}

\xpatchcmd{\tcbsubtitle}
    {\endgroup}
    {\end{BlockClass}\endgroup}
    {}
    {\LWR@patcherror{tcolorbox}{tcbsubtitleB}}
```

\tcboxfit is the same as \tcbox.

```
\AtBeginDocument{
    \ifdef{\tcboxfit}{%
        \let\LWR@HTML@tcboxfit\tcbox%
        \LWR@formatted{tcboxfit}
    }{}
}
```

\tcbtitle is patched to support the text font.

```
\LetLtxMacro\LWR@HTML@tcbtitle\tcbtitle
\xpatchcmd{\LWR@HTML@tcbtitle}
    {\kvtcb@before@title\tcbtitletext}
   {\kvtcb@before@title\LWR@textcurrentfont{\LWR@textcurrentcolor{\tcbtitletext}}}
    {}
    {\LWR@patcherror{tcolorbox}{LWR@HTML@tcbtitle}}
\LWR@formatted{tcbtitle}
```

List-of:

```
\renewcommand*\l@tcolorbox[2]{\hypertocfloat{1}{tcolorbox}{lof}{#1}{#2}}
```

Theorem limitations. An error is printed if the document uses `math`, `ams equation`, etc. `\tcboxmath` and `\tcbhighmath` are ignored for HTML.

```
\AtBeginDocument{
\pgfkeysifdefined{/tcb/libload/theorems}{

    \def\LWR@HTML@tcb@hack@amsmath{%
        \PackageError{lwarp}
            {%
                tcolorbox ``math'', ``ams equation'', and related\MessageBreak
                are not supported.\MessageBreak
                \protect\tcboxmath\space and
                \protect\tcbhighmath\space are emulated.\MessageBreak
                Enter 'H' for possible solutions%
            }
            {%
               Remove tcolorbox math-related options, and instead\MessageBreak
                use the usual math environments inside each tcolorbox.%
            }
    }
    \LWR@formatted{tcb@hack@amsmath}

    % Cause an error if using math:
    \tcbset{%
        math upper/.style={before upper*=\tcb@hack@amsmath,after upper*=$},%
        math lower/.style={before lower*=\tcb@hack@amsmath,after lower*=$},%
    }

    \appto\LWR@restoreorigformatting{%
    \tcbset{%
        math upper/.style={before upper*=$\displaystyle,after upper*=$},%
        math lower/.style={before lower*=$\displaystyle,after lower*=$},%
    }%
    }

    \newcommand{\LWR@HTML@tcboxmath}[2][]{#2}
    \LWR@formatted{tcboxmath}
    \newcommand{\LWR@HTML@tcbhighmath}[2][]{#2}
    \LWR@formatted{tcbhighmath}
    \appto\LWR@restoreMathJaxformatting{%
        \renewcommand{\tcboxmath}[2][]{#2}%
        \renewcommand{\tcbhighmath}[2][]{#2}%
    }
}{}% theorems loaded
}% AtBeginDocument
```

For MathJax:

```
\CustomizeMathJax{\newcommand{\tcbset}[1]{}}
\CustomizeMathJax{\newcommand{\tcbsetforeverylayer}[1]{}}
\CustomizeMathJax{\newcommand{\tcbox}[2][]{\boxed{\text{#2}}}}
\CustomizeMathJax{\newcommand{\tcboxfit}[2][]{\boxed{#2}}}
\CustomizeMathJax{\newcommand{\tcblower}{}}
\CustomizeMathJax{\newcommand{\tcbline}{}}
\CustomizeMathJax{\newcommand{\tcbtitle}{}}
```

```
\CustomizeMathJax{\newcommand{\tcbsubtitle[2][]{\mathrm{#2}}}}
\CustomizeMathJax{\newcommand{\tcboxmath}[2][]{\boxed{#2}}}
\CustomizeMathJax{\newcommand{\tcbhighmath}[2][]{\boxed{#2}}}
```

File 473 **lwarp-tensor.sty**

§ 580 Package

# tensor

(*Emulates or patches code by* Philip G. Ratcliffe.)

Pkg tensor tensor is used as-is for SVG math, and is emulated for MathJax.

⚠ spacing Compressed spacing and left justification are not possible with MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{tensor}[2004/12/20]
```

For MathJax. Special handling is required to parse the superscript and subscript arguments.

When a superscript or subscript is seen, it is processed and then the remainder is processesed recursively.

```
\begin{warpMathJax}
\CustomizeMathJax{\def\LWRtensorindicesthreesub#1#2{{_{#2}}\LWRtensorindicesthree}}
\CustomizeMathJax{\def\LWRtensorindicesthreesup#1#2{{^{#2}}\LWRtensorindicesthree}}
```

If not a superscript nor a subscript, processing stops.

```
\CustomizeMathJax{\newcommand{\LWRtensorindicesthreenotsup}{}}
```

Check ahead for a superscript or a subscript.

```
\CustomizeMathJax{\newcommand{\LWRtensorindicesthreenotsub}{
    \ifnextchar ^ \LWRtensorindicesthreesup \LWRtensorindicesthreenotsup
}}

\CustomizeMathJax{\newcommand{\LWRtensorindicesthree}{
    \ifnextchar _ \LWRtensorindicesthreesub \LWRtensorindicesthreenotsub
}}
```

Ignore star.

```
\CustomizeMathJax{\newcommand{\LWRtensorindicestwo}{
    \ifstar\LWRtensorindicesthree\LWRtensorindicesthree
}}
```

Remove the outer brace of the argument.

```
\CustomizeMathJax{\newcommand{\indices}[1]{\LWRtensorindicestwo#1}}
```

Attempting to use \vphantom here does not work:

```
\CustomizeMathJax{\newcommand{\LWRtensortwo}[3][]{{}\indices{#1}{#2}\indices{#3}}}
```

Ignore star.

```
\CustomizeMathJax{\newcommand{\tensor}{\ifstar\LWRtensortwo\LWRtensortwo}}
```

In text mode, \nuclide is converted to an SVG image.

```
\CustomizeMathJax{%
    \newcommand{\LWRnuclidetwo}[2][]{%
        {%
            \vphantom{\mathrm{#2}}%
            {}^{\LWRtensornucleonnumber}_{#1}%
            \mathrm{#2}%
        }%
    }%
}

\CustomizeMathJax{%
    \newcommand{\nuclide}[1][]{%
        \def\LWRtensornucleonnumber{#1}%
        \LWRnuclidetwo%
    }%
}
\end{warpMathJax}
```

---

File 474 **lwarp-termcal.sty**

§ 581 Package

# termcal

(*Emulates or patches code by* Bill Mitchell.)

Pkg termcal termcal is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{termcal}% questionable date in the .sty file
```

Nullify the @ because everything is being done in a token list.

```
\xpatchcmd{\endcalendar}
    {@{}}
    {}
    {}
    {\LWR@patcherror{termcal}{endcalendar}}
```

Remove the hbox:

```
\xpatchcmd{\ca@doaday}
    {\hbox to \hsize{\calprintdate\hfill\ifclassday\calprintclass\fi}}
    {%
        \calprintdate\hfill\ifclassday\calprintclass\fi%
    }
    {}
    {\LWR@patcherror{termcal}{ca@doaday}}
```

Change each of two ampersands to call the lwarp tabular version:

```
\xpatchcmd{\calday}
    {&}
    {\LWR@tabularampersand}
    {}
    {\LWR@patcherror{termcal}{calday}}

\xpatchcmd{\calday}
    {&}
    {\LWR@tabularampersand}
    {}
    {\LWR@patcherror{termcal}{calday B}}
```

---

File 475 **lwarp-textarea.sty**

# § 582 Package textarea

(*Emulates or patches code by* Alexander I. Rozhenko.)

Pkg textarea textarea is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{textarea}[2005/12/26]

\newcommand\StartFromTextArea{}
\newcommand\StartFromHeaderArea{}
\newcommand*\RestoreTextArea{}
\newcommand*\ExpandTextArea[1][*]{}
\let\NCC@restoretextarea\@empty
```

---

File 476 **lwarp-textcomp.sty**

# § 583 Package textcomp

(*Emulates or patches code by* Frank Mittelbach, Robin Fairbairns, Werner Lemberg.)

Pkg textcomp textcomp is patched for use by lwarp.

## § 583.1 Limitations

Some textcomp symbols do not have Unicode equivalents, and thus are not supported.

⚠ missing symbols Many textcomp symbols are not supported by many system/browser fonts. In the css try referencing fonts which are more complete, but expect to see gaps in coverage.

## § 583.2 Package loading

**for HTML output:**

```
\LWR@ProvidesPackagePass{textcomp}[2017/04/05]
```

## § 583.3 HTML symbols

For HTML, use HTML entities or direct Unicode, depending on the engine.

`\AtBeginDocument` improves support for LuaLaTeX and XeLaTeX.

### § 583.3.1 pdfLaTeX symbols

```
\AtBeginDocument{
\ifPDFTeX% pdflatex or dvi latex
\newcommand*{\LWR@HTML@textdegree}{\HTMLentity{deg}}
\newcommand*{\LWR@HTML@textcelsius}{\HTMLunicode{2103}}
\newcommand*{\LWR@HTML@textohm}{\HTMLunicode{2126}}
\newcommand*{\LWR@HTML@textmu}{\HTMLunicode{00B5}}
\newcommand*{\LWR@HTML@textlquill}{\HTMLunicode{2045}}
\newcommand*{\LWR@HTML@textrquill}{\HTMLunicode{2046}}
\newcommand*{\LWR@HTML@textcircledP}{\HTMLunicode{2117}}
\newcommand*{\LWR@HTML@texttwelveudash}{\HTMLunicode{2014}}% emdash
\newcommand*{\LWR@HTML@textthreequartersemdash}{\HTMLunicode{2014}}% emdash
\newcommand*{\LWR@HTML@textmho}{\HTMLunicode{2127}}
\newcommand*{\LWR@HTML@textnaira}{\HTMLunicode{20A6}}
\newcommand*{\LWR@HTML@textpeso}{\HTMLunicode{20B1}}
\newcommand*{\LWR@HTML@textrecipe}{\HTMLunicode{211E}}
\newcommand*{\LWR@HTML@textinterrobang}{\HTMLunicode{203D}}
\newcommand*{\LWR@HTML@textinterrobangdown}{\HTMLunicode{2E18}}
\newcommand*{\LWR@HTML@textperthousand}{\HTMLunicode{2030}}
\newcommand*{\LWR@HTML@textpertenthousand}{\HTMLunicode{2031}}
\newcommand*{\LWR@HTML@textbaht}{\HTMLunicode{0E3F}}
\newcommand*{\LWR@HTML@textdiscount}{\%}
\newcommand*{\LWR@HTML@textservicemark}{\HTMLunicode{2120}}
\else
```

### § 583.3.2 XeLaTeX and LuaLaTeX symbols

NOTE: Some of the following do not print well in the listing. Consult the .dtx or .sty file for the actual characters.

```
\newcommand*{\LWR@HTML@textdegree}{°}
\newcommand*{\LWR@HTML@textcelsius}{℃}
\newcommand*{\LWR@HTML@textohm}{Ω}
\newcommand*{\LWR@HTML@textmu}{µ}
\newcommand*{\LWR@HTML@textlquill}{⁅}
\newcommand*{\LWR@HTML@textrquill}{⁆}
\newcommand*{\LWR@HTML@textcircledP}{℗}
\newcommand*{\LWR@HTML@texttwelveudash}{–}% emdash
\newcommand*{\LWR@HTML@textthreequartersemdash}{–}% emdash
\newcommand*{\LWR@HTML@textmho}{℧}
\newcommand*{\LWR@HTML@textnaira}{₦}
\newcommand*{\LWR@HTML@textpeso}{₱}
```

```
\newcommand*{\LWR@HTML@textrecipe}{℞}
\newcommand*{\LWR@HTML@textinterrobang}{‽}
\newcommand*{\LWR@HTML@textinterrobangdown}{⸘}
\newcommand*{\LWR@HTML@textperthousand}{‰}
\newcommand*{\LWR@HTML@textpertenthousand}{‱}
\newcommand*{\LWR@HTML@textbaht}{฿}
\newcommand*{\LWR@HTML@textdiscount}{\%}
\newcommand*{\LWR@HTML@textservicemark}{℠}
\fi

\LWR@formatted{textdegree}
\LWR@formatted{textcelsius}
\LWR@formatted{textohm}
\LWR@formatted{textmu}
\LWR@formatted{textlquill}
\LWR@formatted{textrquill}
\LWR@formatted{textcircledP}
\LWR@formatted{texttwelveudash}
\LWR@formatted{textthreequartersemdash}
\LWR@formatted{textmho}
\LWR@formatted{textnaira}
\LWR@formatted{textpeso}
\LWR@formatted{textrecipe}
\LWR@formatted{textinterrobang}
\LWR@formatted{textinterrobangdown}
\LWR@formatted{textperthousand}
\LWR@formatted{textpertenthousand}
\LWR@formatted{textbaht}
\LWR@formatted{textdiscount}
\LWR@formatted{textservicemark}
```

## § 583.4 HTML diacritics

For HTML, Unicode diacritical marks are used:

```
\newcommand*{\LWR@HTML@capitalcedilla}[1]{#1\HTMLunicode{0327}}
\newcommand*{\LWR@HTML@capitalogonek}[1]{#1\HTMLunicode{0328}}
\newcommand*{\LWR@HTML@capitalgrave}[1]{#1\HTMLunicode{0300}}
\newcommand*{\LWR@HTML@capitalacute}[1]{#1\HTMLunicode{0301}}
\newcommand*{\LWR@HTML@capitalcircumflex}[1]{#1\HTMLunicode{0302}}
\newcommand*{\LWR@HTML@capitaltilde}[1]{#1\HTMLunicode{0303}}
\newcommand*{\LWR@HTML@capitaldieresis}[1]{#1\HTMLunicode{0308}}
\newcommand*{\LWR@HTML@capitalhungarumlaut}[1]{#1\HTMLunicode{30B}}
\newcommand*{\LWR@HTML@capitalring}[1]{#1\HTMLunicode{30A}}
\newcommand*{\LWR@HTML@capitalcaron}[1]{#1\HTMLunicode{30C}}
\newcommand*{\LWR@HTML@capitalbreve}[1]{#1\HTMLunicode{306}}
\newcommand*{\LWR@HTML@capitalmacron}[1]{#1\HTMLunicode{304}}
\newcommand*{\LWR@HTML@capitaldotaccent}[1]{#1\HTMLunicode{307}}
```

`\textcircled` becomes a span with a rounded border. `\providecommand` is used to avoid conflict with xunicode.

```
\providecommand*{\LWR@HTML@textcircled}[1]{%
    \InlineClass[border: 1px solid \LWR@currenttextcolor]{textcircled}{#1}%
}
```

```
\LWR@formatted{capitalcedilla}
\LWR@formatted{capitalogonek}
\LWR@formatted{capitalgrave}
\LWR@formatted{capitalacute}
\LWR@formatted{capitalcircumflex}
\LWR@formatted{capitaltilde}
\LWR@formatted{capitaldieresis}
\LWR@formatted{capitalhungarumlaut}
\LWR@formatted{capitalring}
\LWR@formatted{capitalcaron}
\LWR@formatted{capitalbreve}
\LWR@formatted{capitalmacron}
\LWR@formatted{capitaldotaccent}

\LWR@formatted{textcircled}
```

Nullify textcomp macros when generating filenames:

```
\FilenameNullify{%
    \renewcommand*{\textdegree}{}%
    \renewcommand*{\textcelsius}{}%
    \renewcommand*{\textohm}{}%
    \renewcommand*{\textmu}{}%
    \renewcommand*{\textlquill}{}%
    \renewcommand*{\textrquill}{}%
    \renewcommand*{\textcircledP}{}%
    \renewcommand*{\texttwelveudash}{}%
    \renewcommand*{\textthreequartersemdash}{}%
    \renewcommand*{\textmho}{}%
    \renewcommand*{\textnaira}{}%
    \renewcommand*{\textpeso}{}%
    \renewcommand*{\textrecipe}{}%
    \renewcommand*{\textinterrobang}{}%
    \renewcommand*{\textinterrobangdown}{}%
    \renewcommand*{\textperthousand}{}%
    \renewcommand*{\textpertenthousand}{}%
    \renewcommand*{\textbaht}{}%
    \renewcommand*{\textdiscount}{}%
    \renewcommand*{\textservicemark}{}%
    \renewcommand*{\textcircled}[1]{#1}%
    \renewcommand*{\capitalcedilla}[1]{#1}%
    \renewcommand*{\capitalogonek}[1]{#1}%
    \renewcommand*{\capitalgrave}[1]{#1}%
    \renewcommand*{\capitalacute}[1]{#1}%
    \renewcommand*{\capitalcircumflex}[1]{#1}%
    \renewcommand*{\capitaltilde}[1]{#1}%
    \renewcommand*{\capitaldieresis}[1]{#1}%
    \renewcommand*{\capitalhungarumlaut}[1]{#1}%
    \renewcommand*{\capitalring}[1]{#1}%
    \renewcommand*{\capitalcaron}[1]{#1}%
    \renewcommand*{\capitalbreve}[1]{#1}%
    \renewcommand*{\capitalmacron}[1]{#1}%
    \renewcommand*{\capitaldotaccent}[1]{#1}%
}% FilenameNullify
```

```
135
136 }% AtBeginDocument
```

File 477 **lwarp-textfit.sty**

## § 584 Package textfit

Pkg textfit textfit is emulated.

Text is placed into a  of class `textfit`. Sizes are approximated, and also limited by browser min/max font-size settings.

**for HTML output:**

```
1 \LWR@ProvidesPackageDrop{textfit}[1994/04/15]

2 \newsavebox{\LWR@textfitbox}
3
4 \newcommand*{\LWR@textfitscale}[2]{%
5 \setlength{\LWR@templengthone}{#1}%
6 \setlength{\LWR@templengthone}{%
7     1em*\ratio{\LWR@templengthone}{\LWR@templengthtwo}%
8 }%
9 \InlineClass[font-size:\LWR@printlength{\LWR@templengthone}]{textfit}{#2}%
10 }
11
12 \newcommand*{\scaletowidth}[2]{%
13 \sbox{\LWR@textfitbox}{#2}%
14 \settowidth{\LWR@templengthtwo}{\usebox{\LWR@textfitbox}}%
15 \LWR@textfitscale{#1}{#2}%
16 }
17
18 \newcommand*{\scaletoheight}[2]{%
19 \sbox{\LWR@textfitbox}{#2}%
20 \settoheight{\LWR@templengthtwo}{\usebox{\LWR@textfitbox}}%
21 \LWR@textfitscale{#1}{#2}%
22 }
```

File 478 **lwarp-textpos.sty**

## § 585 Package textpos

(*Emulates or patches code by* Norman Gray.)

Pkg textpos textpos is emulated.

**for HTML output:**

```
1 \LWR@ProvidesPackageDrop{textpos}[2020/09/26]

2 \NewDocumentEnvironment{textblock}{m o r()}{}{}
3 \NewDocumentEnvironment{textblock*}{m o r()}{}{}
4 \newcommand*{\TPGrid}[3][]{}
5 \def\TPShowGrid{\@ifstar{\@TPShowGrid}{\@TPShowGrid}}
```

```
          \renewcommand{\LWR@newtheoremstyle}{#1}% lwarp
      }%
      \begingroup
        \csname th@\the\theorem@style \endcsname
      \endgroup}
```

Patched to remember the style for this theorem type, and set it later when the environment is started.

```
\gdef\@xnthm#1#2[#3]{%
   \expandafter\@ifdefinable\csname #1\endcsname
   {%
    \csedef{LWR@thmstyle#1}{\LWR@newtheoremstyle}% lwarp
    \@definecounter{#1}\@newctr{#1}[#3]%
    \expandafter\xdef\csname the#1\endcsname
      {\expandafter \noexpand \csname the#3\endcsname
       \@thmcountersep \@thmcounter{#1}}%
    \def\@tempa{\global\@namedef{#1}}%
    \expandafter \@tempa \expandafter{%
      \csname th@\the \theorem@style
            \expandafter \endcsname \the \theorem@bodyfont
     \@thm{#1}{#2}}%
    \global \expandafter \let \csname end#1\endcsname \@endtheorem
   \AtBeginEnvironment{#1}{\edef\LWR@thisthmstyle{\@nameuse{LWR@thmstyle#1}}}% lwarp
   }}

\gdef\@ynthm#1#2{%
    \expandafter\@ifdefinable\csname #1\endcsname
   {
    \csedef{LWR@thmstyle#1}{\LWR@newtheoremstyle}% lwarp
    \@definecounter{#1}%
    \expandafter\xdef\csname the#1\endcsname{\@thmcounter{#1}}%
    \def\@tempa{\global\@namedef{#1}}\expandafter \@tempa
     \expandafter{\csname th@\the \theorem@style \expandafter
     \endcsname \the\theorem@bodyfont \@thm{#1}{#2}}%
    \global \expandafter \let \csname end#1\endcsname \@endtheorem
   \AtBeginEnvironment{#1}{\edef\LWR@thisthmstyle{\@nameuse{LWR@thmstyle#1}}}% lwarp
   }}

\gdef\@othm#1[#2]#3{%
  \expandafter\ifx\csname c@#2\endcsname\relax
   \@nocounterr{#2}%
  \else
   \expandafter\@ifdefinable\csname #1\endcsname
   {
    \csedef{LWR@thmstyle#1}{\LWR@newtheoremstyle}% lwarp
    \expandafter \xdef \csname the#1\endcsname
     {\expandafter \noexpand \csname the#2\endcsname}%
    \def\@tempa{\global\@namedef{#1}}\expandafter \@tempa
     \expandafter{\csname th@\the \theorem@style \expandafter
     \endcsname \the\theorem@bodyfont \@thm{#2}{#3}}%
    \global \expandafter \let \csname end#1\endcsname \@endtheorem
   \AtBeginEnvironment{#1}{\edef\LWR@thisthmstyle{\@nameuse{LWR@thmstyle#1}}}% lwarp
    }%
  \fi}
```

## § 586.2 css patches

The following are patched for css.

These were in individual files `thp.sty` for plain, `thmb.sty` for margin break, etc. They are gathered together here.

Each theorem is encased in a `BlockClass` environment of class `theorembody<style>`.

Each header is encased in an `\InlineClass` of class `theoremheader`.

```
\gdef\th@plain{%
  \def\@begintheorem##1##2{%
        \item[
            \InlineClass{theoremheader}{##1\ ##2}
        ]
    }%
\def\@opargbegintheorem##1##2##3{%
   \item[
        \InlineClass{theoremheader}{##1\ ##2\ (##3)}
    ]
    }
}

\gdef\th@break{%
  \def\@begintheorem##1##2{%
    \item[
        \InlineClass{theoremheader}{##1\ ##2}\newline%
    ]
    }%
\def\@opargbegintheorem##1##2##3{%
  \item[
        \InlineClass{theoremheader}{##1\ ##2\ (##3)}\newline
    ]
    }
}

\gdef\th@marginbreak{%
  \def\@begintheorem##1##2{
    \item[
        \InlineClass{theoremheader}{##2 \qquad ##1}\newline
    ]
    }%
\def\@opargbegintheorem##1##2##3{%
    \item[
        \InlineClass{theoremheader}{##2 \qquad ##1\ %
        (##3)}\newline
    ]
    }
}

\gdef\th@changebreak{%
  \def\@begintheorem##1##2{
    \item[
        \InlineClass{theoremheader}{##2\ ##1}\newline
    ]
```

```
    }%
\def\@opargbegintheorem##1##2##3{%
    \item[
        \InlineClass{theoremheader}{ ##2\ ##1\ %
        (##3)}\newline
    ]
    }
}

\gdef\th@change{%
  \def\@begintheorem##1##2{
    \item[
        \InlineClass{theoremheader}{##2\ ##1}
    ]
    }%
\def\@opargbegintheorem##1##2##3{%
    \item[
        \InlineClass{theoremheader}{##2\ ##1\ (##3)}
    ]
    }
}

\gdef\th@margin{%
  \def\@begintheorem##1##2{
    \item[
        \InlineClass{theoremheader}{##2 \qquad ##1}
    ]
    }%
\def\@opargbegintheorem##1##2##3{%
    \item[
            \InlineClass{theoremheader}{##2 \qquad ##1\ (##3)}
    ]
    }
}
```

Patched for css:

```
\gdef\@thm#1#2{\refstepcounter{#1}%
\LWR@forcenewpage% lwarp
    \BlockClass{theorembody\LWR@thisthmstyle}% lwarp
   \trivlist
   \@topsep \theorempreskipamount               % used by first \item
   \@topsepadd \theorempostskipamount           % used by \@endparenv
   \@ifnextchar [%
   {\@ythm{#1}{#2}}%
   {\@begintheorem{#2}{\csname the#1\endcsname}\ignorespaces}}

\gdef\@endtheorem{%
\endtrivlist
\endBlockClass
}
```

File 480 **lwarp-thinsp.sty**

## § 587 Package thinsp

Pkg thinsp thinsp is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{thinsp}[2016/10/02]

\AtBeginDocument{
\let\thinthinspace\relax% defined by some packages
\newcommand*{\thinthinspace}{\thinspace}
}

\newcommand*{\stretchthinspace}{\thinspace}
\newcommand*{\stretchthinthinspace}{\thinthinspace}
\newcommand*{\stretchnegthinspace}{\negthinspace}
```

---

File 481 **lwarp-thm-listof.sty**

## § 588 Package thm-listof

(*Emulates or patches code by* Ulrich M. Schwarz, Yukai Chou.)

Pkg thm-listof thm-listof is part of thmtools, and is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{thm-listof}[2019/12/22]
```

For font control, see the generated HTML and use CSS per amsthm or ntheorem.

Other thm-* package may be loaded by thm-listof.

```
\@ifpackagelater{thm-listof}{2020/08/01}{% v0.72
  \def\thmtlo@newentry{%
    \csdef{l@\thmt@envname}##1##2{\hypertocfloat{1}{figure}{lof}{##1}{##2}}%
  }
}{% earlier than v0.72
    \xpatchcmd{\listoftheorems}
        {%
            \@xa\protected@edef\csname l@\thmt@envname\endcsname{%
                \@nx\@dottedtocline{1}{1.5em}{\@nx\thmt@listnumwidth}%
            }%
        }
        {%
        \csdef{l@\thmt@envname}##1##2{\hypertocfloat{1}{figure}{lof}{##1}{##2}}%
        }
        {}
        {\LWR@patcherror{thm-listof}{listoftheorems}}

    \xpatchcmd{\thmt@mklistcmd}
        {%
            \@xa\protected@edef\csname l@\thmt@envname\endcsname{%
                \@nx\@dottedtocline{1}{1.5em}{\@nx\thmt@listnumwidth}%
            }%
        }
```

```
        {%
        \csdef{l@\thmt@envname}##1##2{\hypertocfloat{1}{figure}{lof}{##1}{##2}}%
        }
        {}
        {\LWR@patcherror{thm-listof}{thmt@mklistcmd}}
}
```

---

File 482 **lwarp-thm-restate.sty**

## § 589 Package thm-restate

(*Emulates or patches code by* Ulrich M. Schwarz.)

Pkg thm-restate thm-restate is part of thmtools, and is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{thm-restate}[2020/08/01]

\xpatchcmd{\thmt@restatable}
    {\@ifstar}
    {\edef\LWR@thisthmstyle{#2}\@ifstar}
    {}
    {\LWR@patcherror{thm-restate}{thmt@restatable}}
```

---

File 483 **lwarp-thmbox.sty**

## § 590 Package thmbox

(*Emulates or patches code by* Emmanuel Beffara.)

Pkg thmbox thmbox is emulated for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{thmbox}[2005/04/24]

\renewenvironment{thmbox}[2][]%
    {%
        \begin{BlockClass}{thmbox}
        \begin{BlockClass}{thmboxtitle}
        #2
        \end{BlockClass}
    }
    {\end{BlockClass}}

\renewenvironment{proof}[1][]
    {%
        \begin{BlockClass}{thmboxproof}%
        \InlineClass{thmboxproofname}{\proofname\ #1\unskip\,:}
    }
    {%
        \qquad\HTMLunicode{220E}% end of proof symbol
        \end{BlockClass}
```

```
    }

\renewenvironment{example}[1][\examplename]%
    {%
        \begin{BlockClass}{thmboxexample}%
        \InlineClass{thmboxexamplename}{#1\,:}
    }
    {\end{BlockClass}}

\renewenvironment{leftbar}[1][]%
    {\begin{BlockClass}{thmboxleftbar}}
    {\end{BlockClass}}
```

File 484 **lwarp-thmtools.sty**

# § 591 Package thmtools

(*Emulates or patches code by* Ulrich M. Schwarz.)

Pkg thmtools thmtools is patched for use by lwarp.

Also see thm-listof and thm-restate.

**for HTML output:**

```
\LWR@ProvidesPackagePass{thmtools}[2020/08/01]
```

The following patches either thm-amsthm or thm-ntheorem.

```
\def\thmt@headstyle@margin{%
    \InlineClass{amsthmnnumbertheorem}{\NUMBER}
    \
    \InlineClass{amsthmnametheorem}{\NAME}
    \InlineClass{amsthmnotetheorem}{\NOTE}
}

\let\thmt@headstyle@swapnumber\thmt@headstyle@margin
```

File 485 **lwarp-threadcol.sty**

# § 592 Package threadcol

Pkg threadcol threadcol is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{threadcol}[2013/01/06]

\newcommand{\setthreadname}[1]{}
```

File 486 **lwarp-threeparttable.sty**

## § 593 Package threeparttable

(*Emulates or patches code by* Donald Arseneau.)

Pkg threeparttable threeparttable is emulated.

Table note are contained inside a CSS  of class tnotes. If enumitem is used, the note item labels are also individually highlighted with an additional CSS  of class tnoteitemheader, otherwise they are plain text.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{threeparttable}[2003/06/13]
```

Env threeparttable [⟨*alignment*⟩]

```
\newenvironment*{threeparttable}[1][b]
    {\def\@captype{table}}
    {}
```

Env tablenotes [⟨*options*⟩]

```
\newenvironment*{tablenotes}[1][]
{%
\LWR@forcenewpage
\BlockClass{tnotes}%
\description%
}
{%
\enddescription%
\endBlockClass%
}
```

\tnote {⟨*text*⟩}

```
\newcommand{\tnote}[1]{\LWR@htmlspan{sup}{#1}}
```

Env measuredfigure [⟨*alignment*⟩]

```
\newenvironment*{measuredfigure}[1][t]
    {\def\@captype{figure}}
    {}
```

---

File 487 **lwarp-threeparttablex.sty**

## § 594 Package threeparttablex

Pkg threeparttablex threeparttablex is patched for use by lwarp.

threeparttablex is used with longtable and booktabs as follows:

```
\newcommand*{\Overviewpage}{}
\newlength{\thumbheight}
\newlength{\thumbwidth}
```

File 489 **lwarp-thumbs.sty**

§ 596 Package

# thumbs

Pkg thumbs thumbs is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{thumbs}[2014/03/09]
```

```
\newcommand{\addthumb}[4]{}
\newcommand{\addtitlethumb}[5]{}
\newcommand{\stopthumb}{}
\newcommand{\continuethumb}{}
\newcommand{\thumbsoverview}[1]{}
\newcommand{\thumbsoverviewback}[1]{}
\newcommand{\thumbsoverviewverso}[1]{}
\newcommand{\thumbsoverviewdouble}[1]{}
\newcommand{\thumbnewcolumn}{}
\newcommand{\addthumbsoverviewtocontents}[2]{}
\newcommand{\thumbsnophantom}{}
```

File 490 **lwarp-tikz.sty**

§ 597 Package

# tikz

(*Emulates or patches code by* Till Tantau.)

Pkg tikz tikz is supported.

⚠ displaymath and matrices If using display math with `tikzpicture` or `\tikz`, along with matrices with the & character, the document must be modified as follows:

```
\usepackage{tikz}
\tikzset{every picture/.style={ampersand replacement=\&}}
```

and each instance of & in the tikz expression must be replaced with `\&`.

Accept all options for lwarp-tikz:

```
\LWR@ProvidesPackagePass{tikz}[2015/08/07]
```

catcodes lwarp changes the catcode of $ for its own use. The Ti*k*z babel library temporarily changes catcodes back to normal for Ti*k*z's use. tikz v3.0.0 introduced the babel library which handles catcode changes. For older versions, lwarp must change $'s catcode itself.

Also see:
https://tex.stackexchange.com/questions/16199/
test-if-a-package-or-package-option-is-loaded

```
\newbool{LWR@tikzbabel}

\@ifpackagelater{tikz}{2013/12/20}% Test for Tikz version v3.0.0
{\usetikzlibrary{babel}\booltrue{LWR@tikzbabel}}
{\boolfalse{LWR@tikzbabel}}
```

Env pgfpicture The \pgfpicture environment is enclosed inside a \lateximage. Enclose the low-level \pgfpicture in a lateximage. This is also used by the higher-level \tikz and tikzpicture.

```
\preto\pgfpicture{%
    \begin{lateximage}[-tikz-~\PackageDiagramAltText]%
    \ifbool{LWR@tikzbabel}% Test for Tikz version v3.0.0
    {}%
    {\catcode`\$=3}% dollar sign is math shift
}

\appto\endpgfpicture{\end{lateximage}}
```

Ti*k*z is placed inside an SVG image, so use the original meanings of the following:

```
\LetLtxMacro\pgfutil@minipage\LWR@print@minipage
\let\pgfutil@endminipage\endLWR@print@minipage

\let\pgfutil@raggedleft\LWR@print@raggedleft
\let\pgfutil@raggedright\LWR@print@raggedright


\def\pgfutil@font@tiny{\LWR@print@tiny}
\def\pgfutil@font@scriptsize{\LWR@print@scriptsize}
\def\pgfutil@font@footnotesize{\LWR@print@footnotesize}
\def\pgfutil@font@small{\LWR@print@small}
\def\pgfutil@font@normalsize{\LWR@print@normalsize}
\def\pgfutil@font@large{\LWR@print@large}
\def\pgfutil@font@Large{\LWR@print@Large}
\def\pgfutil@font@huge{\LWR@print@huge}
\def\pgfutil@font@Huge{\LWR@print@Huge}

\def\pgfutil@font@itshape{\LWR@print@itshape}
\def\pgfutil@font@bfseries{\LWR@print@bfseries}

\def\pgfutil@font@normalfont{\LWR@print@normalfont}
```

---

File 491 **lwarp-tikz-imagelabels.sty**

§ 598 Package # tikz-imagelabels

(*Emulates or patches code by* Tobias Plüss.)

Pkg tikz-imagelabels tikz-imagelabels is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{tikz-imagelabels}[2019/06/27]

\BeforeBeginEnvironment{annotationimage}{%
    \begin{lateximage}[-tikz-imagelabels-~\PackageDiagramAltText]%
}

\AfterEndEnvironment{annotationimage}{\end{lateximage}}
```

---

File 492 **lwarp-titleps.sty**

§ 599 Package

# titleps

(*Emulates or patches code by* Javier Bezos.)

Pkg titleps titleps is loaded and used by lwarp during HTML output. All user options and macros are ignored and disabled.

Discard all options for lwarp-titleps:

**for HTML output:**

```
\LWR@ProvidesPackageDrop{titleps}[2016/03/15]
```

\pagestyle and \thispagestyle are already disabled in the lwarp code.

\newpagestyle {⟨*name*⟩} [⟨*style*⟩] {⟨*commands*⟩}

```
\NewDocumentCommand{\newpagestyle}{m o m}{}
```

\renewpagestyle {⟨*name*⟩} [⟨*style*⟩] {⟨*commands*⟩}

```
\NewDocumentCommand{\renewpagestyle}{m o m}{}
```

\sethead [⟨*el*⟩] [⟨*ec*⟩] [⟨*er*⟩] {⟨*ol*⟩} {⟨*oc*⟩} {⟨*or*⟩}

```
\NewDocumentCommand{\sethead}{o o o m m m}{}
```

\setfoot [⟨*el*⟩] [⟨*ec*⟩] [⟨*er*⟩] {⟨*ol*⟩} {⟨*oc*⟩} {⟨*or*⟩}

```
\NewDocumentCommand{\setfoot}{o o o m m m}{}
```

\settitlemarks * {⟨*names*⟩}

```
\NewDocumentCommand{\settitlemarks}{s m}{}
```

\headrule

```
\newcommand*{\headrule}{}
```

\footrule

```
\newcommand*{\footrule}{}
```

\setheadrule {⟨*length*⟩}

```
\newcommand*{\setheadrule}[1]{}
```

\setfootrule {⟨*length*⟩}

```
\newcommand*{\setfootrule}[1]{}
```

\makeheadrule

```
\newcommand*{\makeheadrule}{}
```

\makefootrule

```
\newcommand*{\makefootrule}{}
```

\setmarkboth {⟨*code*⟩}

```
\newcommand{\setmarkboth}[1]{}
```

\widenhead

```
\NewDocumentCommand{\widenhead}{s o o m m}{}
```

\bottitlemarks

```
\newcommand*{\bottitlemarks}{}
```

\toptitlemarks

```
\newcommand*{\toptitlemarks}{}
```

\firsttitlemarks

```
\newcommand*{\firsttitlemarks}{}
```

\nexttitlemarks

```
\newcommand*{\nexttoptitlemarks}{}
```

\outertitlemarks

```
\newcommand*{\outertitlemarks}{}
```

\innertitlemarks

```
\newcommand*{\innertitlemarks}{}
```

\newtitlemark * {⟨*name*⟩}

```
\NewDocumentCommand{\newtitlemark}{s m}{}
```

\pretitlemark * {⟨*section*⟩} {⟨*text*⟩}

```
\NewDocumentCommand{\pretitlemark}{s m m}{}
```

\ifsamemark {⟨*group*⟩} {⟨*command*⟩} {⟨*true*⟩} {⟨*false*⟩}

```
\newcommand{\ifsamemark}[4]{}
```

\setfloathead * [⟨.⟩] [⟨.⟩] [⟨.⟩] {⟨.⟩} {⟨.⟩} {⟨.⟩} {⟨*extra*⟩} [⟨*which*⟩]

```
\NewDocumentCommand{\setfloathead}{s o o o m m m m m}{}
```

\setfloatfoot * [⟨.⟩] [⟨.⟩] [⟨.⟩] {⟨.⟩} {⟨.⟩} {⟨.⟩} {⟨*extra*⟩} [⟨*which*⟩]

```
\NewDocumentCommand{\setfloatfoot}{s o o o m m m m m}{}
```

\nextfloathead * [⟨.⟩] [⟨.⟩] [⟨.⟩] {⟨.⟩} {⟨.⟩} {⟨.⟩} {⟨*extra*⟩} [⟨*which*⟩]

```
\NewDocumentCommand{\nextfloathead}{s o o o m m m m m}{}
```

\nextfloatfoot * [⟨.⟩] [⟨.⟩] [⟨.⟩] {⟨.⟩} {⟨.⟩} {⟨.⟩} {⟨*extra*⟩} [⟨*which*⟩]

```
\NewDocumentCommand{\nextfloatfoot}{s o o o m m m m m}{}
```

\newmarkset {⟨*markset*⟩}

```
\newcommand{\newmarkset}[1]{}
```

\newextramark * {⟨*markset*⟩} {⟨*macro-name*⟩}

```
\NewDocumentCommand{\newextramarkset}{s m m}{}
```

\botextramarks {⟨*markset*⟩}

```
\newcommand{\botextramarks}[1]{}
```

\topextramarks {⟨*markset*⟩}

```
\newcommand{\topextramarks}[1]{}
```

\firstextramarks {⟨*markset*⟩}

```
\newcommand{\firstextramarks}[1]{}
```

\nextextramarks {⟨*markset*⟩}

```
\newcommand{\nexttopextramarks}[1]{}
```

\outerextramarks {⟨*markset*⟩}

```
\newcommand{\outerextramarks}[1]{}
```

\innerextramarks {⟨*markset*⟩}

```
\newcommand{\innerextramarks}[1]{}
```

File 493 **lwarp-titleref.sty**

§ 600 Package titleref

Pkg titleref titleref is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{titleref}[2001/04/05]

\LetLtxMacro\titleref\nameref

\providecounter{LWR@currenttitle}

\newcommand*{\currenttitle}{%
    \addtocounter{LWR@currenttitle}{1}%
    \label{currenttitle\arabic{LWR@currenttitle}}%
    \nameref{currenttitle\arabic{LWR@currenttitle}}%
}

\newcommand*{\theTitleReference}[2]{}
```

File 494 **lwarp-titlesec.sty**

§ 601 Package titlesec

(*Emulates or patches code by* Javier Bezos.)

Pkg titlesec titlesec is emulated. All user options and macros are ignored and disabled.

Discard all options for lwarp-titlesec:

**for HTML output:**

```
\PackageInfo{lwarp}{Using the lwarp version of package 'titlesec'.}%
\ProvidesPackage{lwarp-titlesec}[2016/03/21]

\newbool{LWR@loadtitleps}
\boolfalse{LWR@loadtitleps}

\DeclareOption{pagestyles}{
    \booltrue{LWR@loadtitleps}
}

\DeclareOption*{}

\ProcessOptions\relax

\ifbool{LWR@loadtitleps}{
    \RequirePackage{lwarp-titleps}
}{}
```

\titlelabel {⟨*label-format*⟩}

```
\newcommand*{\titlelabel}[1]{}
```

\titleformat* {⟨*command*⟩} {⟨*format*⟩}

\titleformat {⟨*command*⟩} [⟨*shape*⟩] {⟨*format*⟩} {⟨*label*⟩} {⟨*sep*⟩} {⟨*begfore*⟩} [⟨*after*⟩]

```
\newcommand\titleformat{%
  \@ifstar{\ttl@format@s}%
          {\ttl@format@i}}
\newcommand{\ttl@format@s}[1]{}
\NewDocumentCommand{\ttl@format@i}{m o m m m m o}{}
```

\chaptertitlename

```
\@ifundefined{@chapapp}{\let\@chapapp\chaptername}{}
\newcommand\chaptertitlename{\@chapapp}
```

\titlespacing * {⟨*command*⟩} {⟨*left*⟩} {⟨*before*⟩} {⟨*after*⟩} [⟨*right*⟩]

```
\NewDocumentCommand{\titlespacing}{s m m m m o}{}
```

\filright

```
\newcommand*{\filright}{}
```

\filcenter

```
\newcommand*{\filcenter}{}
```

\filleft

```
\newcommand*{\filleft}{}
```

\fillast

```
\newcommand*{\fillast}{}
```

\filinner

```
\newcommand*{\filinner}{}
```

\filouter

```
\newcommand*{\filouter}{}
```

\wordsep

```
\newcommand\wordsep{\fontdimen\tw@\font \@plus
  \fontdimen\thr@@\font \@minus \fontdimen4\font}
```

\titleline * [⟨*align*⟩] {⟨*material*⟩}

```
\NewDocumentCommand{\titleline}{s o m}{}
```

\titlerule [⟨*height*⟩]

```
\providecommand*\titlerule{\@ifstar{\ttl@row}{\ttl@rule}}
\newcommand*{\ttl@rule}[1][]{}
\newcommand*{\ttl@row}[2][]{}
```

\iftitlemeasuring {⟨*true*⟩} {⟨*false*⟩}

```
\newcommand{\iftitlemeasuring}[2]{#2}
```

\assignpagestyle {⟨*command*⟩} {⟨*pagestyle*⟩}

```
\newcommand{\assignpagestyle}[2]{#2}
```

\titleclass {⟨*name*⟩} [⟨*startlevel*⟩] {⟨*class*⟩} [⟨*cmd*⟩]

```
\NewDocumentCommand{\titleclass}{m o m o}{}
```

---

File 495 **lwarp-titletoc.sty**

§ 602 Package

# titletoc

(*Emulates or patches code by* Javier Bezos.)

Pkg titletoc titletoc is emulated. All user options and macros are ignored and disabled.

Discard all options for lwarp-titletoc:

**for HTML output:**

```
\LWR@ProvidesPackageDrop{titletoc}[2011/12/15]
```

\dottedcontents {⟨*section*⟩} [⟨*left*⟩] {⟨*above*⟩} {⟨*label*⟩} {⟨*leader*⟩}

```
\NewDocumentCommand{\dottedcontents}{m o m m m}{}
```

\titlecontents * {⟨*section*⟩} [⟨*left*⟩] {⟨*above*⟩} {⟨*numbered*⟩} {⟨*numberless*⟩} {⟨*filler*⟩} [⟨*below or begin*⟩] [⟨*separator*⟩] [⟨*end*⟩]

```
\newcommand{\titlecontents}{\@ifstar{\ttl@tcstar}{\ttl@tcnostar}}
\NewDocumentCommand{\ttl@tcstar}{m o m m m m o o o}{}
\NewDocumentCommand{\ttl@tcnostar}{m o m m m m o}{}
```

\contentsmargin [⟨*correction*⟩] {⟨*right*⟩}

```
\newcommand{\contentsmargin}[2][]{}
```

\thecontentslabel

```
\newcommand*{\thecontentslabel}{thecontentslabel}
```

\thecontentspage

```
\newcommand*{\thecontentspage}{thecontentspage}
```

\contentslabel [⟨*format*⟩] {⟨*space*⟩}

```
\newcommand{\contentslabel}[2][]{\thecontentslabel}
```

\contentspage [⟨*format*⟩]

```
\newcommand{\contentspage}[1][]{\thecontentspage}
```

\contentspush {⟨*text*⟩}

```
\newcommand{\contentspush}[1]{}
```

\contentsuse {⟨*name*⟩} {⟨*text*⟩}

```
\newcommand{\contentsuse}[2]{}
```

\startcontents [⟨*name*⟩]

```
\newcommand*{\startcontents}[1][]{}
```

\stopcontents [⟨*name*⟩]

```
\newcommand*{\stopcontents}[1][]{}
```

\resumecontents [⟨*name*⟩]

```
\newcommand*{\resumecontents}[1][]{}
```

\printcontents [⟨*name*⟩] {⟨*prefix*⟩} {⟨*start*⟩} {⟨*code*⟩}

```
\newcommand{\printcontents}[4][]{}
```

\startlist [⟨*name*⟩] {⟨*list*⟩}

```
\newcommand{\startlist}[2][]{}
```

\stoplist [⟨*name*⟩] {⟨*list*⟩}

```
\newcommand{\stoplist}[2][]{}
```

\resumelist [⟨*name*⟩] {⟨*list*⟩}

```
\newcommand{\resumelist}[2][]{}
```

\printlist [⟨*name*⟩] {⟨*list*⟩} {⟨*prefix*⟩} {⟨*code*⟩}

```
\newcommand{\printlist}[4][]{}
```

```
        \LWR@htmltag{\LWR@tagtitleend}\LWR@startpars%
    }
    \maketitlehookb
    {
        \begin{BlockClass}{author}
        \renewcommand{\and}{%
            \end{BlockClass}%
            \begin{BlockClass}{oneauthor}%
        }
        \begin{BlockClass}{oneauthor}%
        \@bspreauthor \@author  \@bspostauthor%
        \end{BlockClass}%
        \end{BlockClass}%
    }
    \maketitlehookc
    {
        \begin{BlockClass}{titledate}%
        \@bspredate \@date \@bspostdate%
        \end{BlockClass}%
    }
    \maketitlehookd
}
```

\LWR@titlingmaketitle `\maketitle` for use inside an HTML `titlingpage` environment.

```
\renewcommand*{\LWR@titlingmaketitle}{%
```

Keep pending footnotes out of the title block:

```
\LWR@stoppars\@thanks\LWR@startpars
```

Select which kind of footnote marks to use:

```
\@bsmarkseries
```

Set up special patches:

```
\LWR@maketitlesetup
```

Typeset the title, etc:

```
\@maketitle
```

Immediately generate any `\thanks` footnotes:

```
\LWR@stoppars\@thanks\LWR@startpars
```

Reset the footnote counter:

```
\@bscontmark
}
```

\thanksmarkseries {⟨*series*⟩}

Sets the type of footnote marks used by \thanks, where type is ‘arabic’, ‘roman’, ‘fnsymbol’, etc.

```
\renewcommand{\thanksmarkseries}[1]{%
\def\@bsmarkseries{\renewcommand{\thefootnote}{\@nameuse{#1}{footnote}}}%
}
```

Set default titlepage thanks footnote marks. See section 68.7.

```
\@ifclassloaded{memoir}{
   \thanksmarkseries{arabic}
}{% not memoir
\if@titlepage
   \thanksmarkseries{arabic}
\else
   \thanksmarkseries{fnsymbol}
\fi
}% not memoir
```

---

File 497 **lwarp-tocbasic.sty**

§ 604 Package

# tocbasic

(*Emulates or patches code by* Markus Kohm.)

Pkg tocbasic tocbasic is nullified for lwarp.

This package may be loaded standalone, but is also loaded automatically if koma-script classes are in use. \DeclareDocumentCommand is used to overwrite the koma-script definitions.

**for HTML output:**

```
\LWR@ProvidesPackagePass{tocbasic}[2018/12/30]
```

```
\DeclareDocumentCommand{\usetocbasicnumberline}{o}{}
\DeclareDocumentCommand{\DeclareTOCStyleEntry}{o m m}{}
\DeclareDocumentCommand{\DeclareTOCStyleEntries}{o m m}{}
\DeclareDocumentCommand{\DeclareTOCEntryStyle}{m o m}{}
\DeclareDocumentCommand{\DefineTOCEntryOption}{m o m}{}
\DeclareDocumentCommand{\DefineTOCEntryBooleanOption}{m o m m m}{}
\DeclareDocumentCommand{\DefineTOCEntryCommandOption}{m o m m m}{}
\DeclareDocumentCommand{\DefineTOCEntryIfOption}{m o m m m}{}
\DeclareDocumentCommand{\DefineTOCEntryLengthOption}{m o m m m}{}
\DeclareDocumentCommand{\DefineTOCEntryNumberOption}{m o m m m}{}
\DeclareDocumentCommand{\CloneTOCEntryStyle}{m m}{}
\DeclareDocumentCommand{\TOCEntryStyleInitCode}{m m}{}
\DeclareDocumentCommand{\TOCEntryStyleStartInitCode}{m m}{}
```

---

File 498 **lwarp-tocbibind.sty**

# § 605 Package tocbibind

(*Emulates or patches code by* Peter Wilson.)

Pkg tocbibind tocbibind is patched for use by lwarp.

placement and TOC options An index may be placed inline with other HTML text, or on its own HTML page:

Pkg makeidx **Inline, with a manual TOC entry:**

A commonly-used method to introduce an index in a LaTeX document:

```
\cleardoublepage
\phantomsection
\addcontentsline{toc}{section}{\indexname}% or chapter
\printindex
```

Pkg makeidx **On its own HTML page, with a manual TOC entry:**

```
\begin{warpprint}
\cleardoublepage
\phantomsection
\addcontentsline{toc}{section}{\indexname}% or chapter
\end{warpprint}
\ForceHTMLPage
\ForceHTMLTOC
\printindex
```

Pkg tocbibind **Inline, with an automatic TOC entry:**

The tocbibind package may be used to automatically place an entry in the TOC.

```
\usepackage[nottoc]{tocbibind}
. . .
\cleardoublepage
\phantomsection % to fix print-version index link
\printindex
```

Pkg tocbibind **On its own HTML page, with an automatic TOC entry:**

```
\usepackage[nottoc]{tocbibind}
. . .
\cleardoublepage
\phantomsection % to fix print-version index link
\ForceHTMLPage
\printindex
```

Opt [tocbibind] numindex Use the tocbibind numindex option to generate a numbered index. Without this option, the index heading has no number.

numbered index section

Other packages, such as imakeidx, may also have options for including the index in the Table of Contents.

**for HTML output:**

```
\let\simplechapterdelim\relax

\LWR@ProvidesPackagePass{tocbibind}[2010/10/13]
```

```
\renewenvironment{theindex}%
{%
     \if@bibchapter
        \if@donumindex
            \chapter{\indexname}
        \else
          \if@dotocind
            \chapter*{\indexname}
            \addcontentsline{toc}{chapter}{\LWR@isolate{\indexname}}
          \else
            \chapter*{\indexname}
          \fi
        \fi
     \else
        \if@donumindex
            \section{\indexname}
        \else
          \if@dotocind
            \section*{\indexname}
            \addcontentsline{toc}{\@tocextra}{\LWR@isolate{\indexname}}
          \else
            \section*{\indexname}
          \fi
        \fi
     \fi
\let\item\LWR@indexitem%
\let\subitem\LWR@indexsubitem%
\let\subsubitem\LWR@indexsubsubitem%
}{}
```

The following code is shared by anonchap.

```
\DeclareDocumentCommand{\simplechapter}{O{\@empty}}{%
    \def\@chapcntformat##1{%
        #1~\csname the##1\endcsname\simplechapterdelim\quad%
    }%
}

\DeclareDocumentCommand{\restorechapter}{}{%
\let\@chapcntformat\@seccntformat%
}
```

---

File 499 **lwarp-tocdata.sty**

§ 606 Package

# tocdata

(*Emulates or patches code by* Brian Dunn.)

Pkg tocdata tocdata is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{tocdata}[2019/07/06]
```

```
\renewcommand*{\LWR@maybetocdata}{%
    \ifdefempty{\TD@thistocdata}{}{%
        \qquad \InlineClass{authorartist}{\tocdataformat{\TD@thistocdata}}%
        \def\TD@thistocdata{}
    }
}

\renewrobustcmd{\tocdatapartprint}[4]
{%
    \InlineClass{authorartist}{%
        \qquad --- %
        \TDoptionalnameprint{#1}\TDoptionalnameprint{#2}#3#4%
    }%
}

\@ifundefined{chapter}{}{
    \let\tocdatachapterprint\tocdatapartprint
}
\let\tocdatasectionprint\tocdatapartprint
\let\tocdatasubsectionprint\tocdatapartprint

\newcommand*{\LWR@TD@settextalign}[1]{%
    \def\LWR@TD@textalign{justify}%
    \ifcsstring{TD@#1align}{\centering}%
        {\def\LWR@TD@textalign{center}}%
        {}%
    \ifcsstring{TD@#1align}{\raggedleft}%
        {\def\LWR@TD@textalign{right}}%
        {}%
    \ifcsstring{TD@#1align}{\raggedright}%
        {\def\LWR@TD@textalign{left}}%
        {}%
}

\renewcommand{\TDartistauthorprint}[5]{%
    \LWR@TD@settextalign{#1}%
    \begin{BlockClass}[text-align:\LWR@TD@textalign]{floatnotes}%
   \InlineClass{authorartist}{\TDoptionalnameprint{#2}\TDoptionalnameprint{#3}#4#5}%
    \end{BlockClass}%
}

\newcommand*{\LWR@TD@setnamealign}[1]{%
    \def\LWR@TD@textalign{justify}%
    \ifcsstring{TD@#1textalign}{\centering}%
        {\def\LWR@TD@textalign{center}}%
        {}%
    \ifcsstring{TD@#1textalign}{\raggedleft}%
        {\def\LWR@TD@textalign{right}}%
        {}%
    \ifcsstring{TD@#1textalign}{\raggedright}%
        {\def\LWR@TD@textalign{left}}%
        {}%
}

\renewcommand{\TDartistauthortextprint}[2]{%
```

```
    \LWR@TD@setnamealign{#1}%
    \begin{BlockClass}[text-align:\LWR@TD@textalign]{floatnotes}%
    #2%
    \end{BlockClass}%
}
```

---

File 500 **lwarp-tocenter.sty**

§ 607 Package

# tocenter

Pkg tocenter tocenter is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{tocenter}[2004/12/09]

\NewDocumentCommand{\ToCenter}{s o m m}{}
\NewDocumentCommand{\FromMargins}{s o m m m m}{}
```

---

File 501 **lwarp-tocloft.sty**

§ 608 Package

# tocloft

(*Emulates or patches code by* Peter Wilson.)

Pkg tocloft tocloft is emulated. Most user options and macros are ignored and disabled. `\newlistof` and `\cftchapterprecis` are supported.

Pkg tocloft ⚠ tocloft & other packages

If using tocloft with tocbibind, anonchap, fncychap, or other packages which change chapter title formatting, load tocloft with its `titles` option, which tells tocloft to use standard LaTeX commands to create the titles, allowing other packages to work with it.

Discard all options for lwarp-tocloft:

**for HTML output:**

```
\LWR@ProvidesPackageDrop{tocloft}[2017/08/31]
```

`\tocloftpagestyle` {⟨*style*⟩}

```
\newcommand{\tocloftpagestyle}[1]{}
```

`\cftmarktoc`

```
\newcommand*{\cftmarktoc}{}
```

`\cfttoctitlefont`

```
\newcommand*{\cfttoctitlefont}{}
```

`\cftaftertoctitle`

```
\newcommand*{\cftaftertoctitle}{}
```

```
\newlength{\cftbeforetoctitleskip}
\newlength{\cftaftertoctitleskip}
```

`\cftmarklof`

```
\newcommand*{\cftmarklof}{}
```

`\cftloftitlefont`

```
\newcommand*{\cftloftitlefont}{}
```

`\cftafterloftitle`

```
\newcommand*{\cftafterloftitle}{}

\newlength{\cftbeforeloftitleskip}
\newlength{\cftafterloftitleskip}
```

`\cftmarklot`

```
\newcommand*{\cftmarklot}{}
```

`\cftlottitlefont`

```
\newcommand*{\cftlottitlefont}{}
```

`\cftafterlottitle`

```
\newcommand*{\cftafterlottitle}{}

\newlength{\cftbeforelottitleskip}
\newlength{\cftafterlottitleskip}
```

`\cftdot`

```
\providecommand*{\cftdot}{.}
```

`\cftdotsep`

```
\providecommand*{\cftdotsep}{1}
```

`\cftnodots`

```
\providecommand*{\cftnodots}{5000}
```

`\cftdotfill` {⟨*sep*⟩}

```
\providecommand{\cftdotfill}[1]{}
```

`\cftsetpnumwidth` {⟨*length*⟩}

```
\DeclareDocumentCommand{\cftsetpnumwidth}{m}{}
```

\cftsetrmarg {⟨*length*⟩}

```
\DeclareDocumentCommand{\cftsetrmarg}{m}{}
```

\cftpnumalign {⟨*alignment*⟩}

```
\DeclareDocumentCommand{\cftpnumalign}{m}{}

\LWR@providelength{\cftparskip}
```

The part-related items are also provided by memoir:

```
\LWR@providelength{\cftbeforepartskip}
\LWR@providelength{\cftpartindent}
\LWR@providelength{\cftpartnumwidth}
\providecommand*{\cftpartfont}{}
\providecommand*{\cftpartpresnum}{}
\providecommand*{\cftpartaftersnum}{}
\providecommand*{\cftpartaftersnumb}{}
\providecommand*{\cftpartleader}{}
\providecommand*{\cftpartdotsep}{1}
\providecommand*{\cftpartpagefont}{}
\providecommand*{\cftpartafterpnum}{}
```

memoir uses the full name “chapter” instead of “chap”:

```
\LWR@providelength{\cftbeforechapskip}
\LWR@providelength{\cftchapindent}
\LWR@providelength{\cftchapnumwidth}
\newcommand*{\cftchapfont}{}
\newcommand*{\cftchappresnum}{}
\newcommand*{\cftchapaftersnum}{}
\newcommand*{\cftchapaftersnumb}{}
\newcommand*{\cftchapleader}{}
\newcommand*{\cftchapdotsep}{1}
\newcommand*{\cftchappagefont}{}
\newcommand*{\cftchapafterpnum}{}
```

The following do not appear in memoir:

```
\LWR@providelength{\cftbeforesecskip}
\LWR@providelength{\cftsecindent}
\LWR@providelength{\cftsecnumwidth}
\newcommand*{\cftsecfont}{}
\newcommand*{\cftsecpresnum}{}
\newcommand*{\cftsecaftersnum}{}
\newcommand*{\cftsecaftersnumb}{}
\newcommand*{\cftsecleader}{}
\newcommand*{\cftsecdotsep}{1}
\newcommand*{\cftsecpagefont}{}
\newcommand*{\cftsecafterpnum}{}

\LWR@providelength{\cftbeforesubsecskip}
```

```
\LWR@providelength{\cftsubsecindent}
\LWR@providelength{\cftsubsecnumwidth}
\newcommand*{\cftsubsecfont}{}
\newcommand*{\cftsubsecpresnum}{}
\newcommand*{\cftsubsecaftersnum}{}
\newcommand*{\cftsubsecaftersnumb}{}
\newcommand*{\cftsubsecleader}{}
\newcommand*{\cftsubsecdotsep}{1}
\newcommand*{\cftsubsecpagefont}{}
\newcommand*{\cftsubsecafterpnum}{}

\LWR@providelength{\cftbeforesubsubsecskip}
\LWR@providelength{\cftsubsubsecindent}
\LWR@providelength{\cftsubsubsecnumwidth}
\newcommand*{\cftsubsubsecfont}{}
\newcommand*{\cftsubsubsecpresnum}{}
\newcommand*{\cftsubsubsecaftersnum}{}
\newcommand*{\cftsubsubsecaftersnumb}{}
\newcommand*{\cftsubsubsecleader}{}
\newcommand*{\cftsubsubsecdotsep}{1}
\newcommand*{\cftsubsubsecpagefont}{}
\newcommand*{\cftsubsubsecafterpnum}{}

\LWR@providelength{\cftbeforeparaskip}
\LWR@providelength{\cftparaindent}
\LWR@providelength{\cftparanumwidth}
\newcommand*{\cftparafont}{}
\newcommand*{\cftparapresnum}{}
\newcommand*{\cftparaaftersnum}{}
\newcommand*{\cftparaaftersnumb}{}
\newcommand*{\cftparaleader}{}
\newcommand*{\cftparadotsep}{1}
\newcommand*{\cftparapagefont}{}
\newcommand*{\cftparaafterpnum}{}

\LWR@providelength{\cftbeforesubparaskip}
\LWR@providelength{\cftsubparaindent}
\LWR@providelength{\cftsubparanumwidth}
\newcommand*{\cftsubparafont}{}
\newcommand*{\cftsubparapresnum}{}
\newcommand*{\cftsubparaaftersnum}{}
\newcommand*{\cftsubparaaftersnumb}{}
\newcommand*{\cftsubparaleader}{}
\newcommand*{\cftsubparadotsep}{1}
\newcommand*{\cftsubparapagefont}{}
\newcommand*{\cftsubparaafterpnum}{}

\LWR@providelength{\cftbeforefigskip}
\LWR@providelength{\cftfigindent}
\LWR@providelength{\cftfignumwidth}
\newcommand*{\cftfigfont}{}
\newcommand*{\cftfigpresnum}{}
\newcommand*{\cftfigaftersnum}{}
\newcommand*{\cftfigaftersnumb}{}
\newcommand*{\cftfigleader}{}
```

```
\newcommand*{\cftfigdotsep}{1}
\newcommand*{\cftfigpagefont}{}
\newcommand*{\cftfigafterpnum}{}

\LWR@providelength{\cftbeforesubfigskip}
\LWR@providelength{\cftsubfigindent}
\LWR@providelength{\cftsubfignumwidth}
\newcommand*{\cftsubfigfont}{}
\newcommand*{\cftsubfigpresnum}{}
\newcommand*{\cftsubfigaftersnum}{}
\newcommand*{\cftsubfigaftersnumb}{}
\newcommand*{\cftsubfigleader}{}
\newcommand*{\cftsubfigdotsep}{1}
\newcommand*{\cftsubfigpagefont}{}
\newcommand*{\cftsubfigafterpnum}{}

\LWR@providelength{\cftbeforetabskip}
\LWR@providelength{\cfttabindent}
\LWR@providelength{\cfttabnumwidth}
\newcommand*{\cfttabfont}{}
\newcommand*{\cfttabpresnum}{}
\newcommand*{\cfttabaftersnum}{}
\newcommand*{\cfttabaftersnumb}{}
\newcommand*{\cfttableader}{}
\newcommand*{\cfttabdotsep}{1}
\newcommand*{\cfttabpagefont}{}
\newcommand*{\cfttabafterpnum}{}

\LWR@providelength{\cftbeforesubtabskip}
\LWR@providelength{\cftsubtabindent}
\LWR@providelength{\cftsubtabnumwidth}
\newcommand*{\cftsubtabfont}{}
\newcommand*{\cftsubtabpresnum}{}
\newcommand*{\cftsubtabaftersnum}{}
\newcommand*{\cftsubtabaftersnumb}{}
\newcommand*{\cftsubtableader}{}
\newcommand*{\cftsubtabdotsep}{1}
\newcommand*{\cftsubtabpagefont}{}
\newcommand*{\cftsubtabafterpnum}{}

\DeclareDocumentCommand{\cftsetindents}{m m m}{}

\newcommand{\pagenumbersoff}[1]{}
\newcommand{\pagenumberson}[1]{}
```

\newlistentry [⟨*within*⟩] {⟨*counter*⟩} {⟨*ext*⟩} {⟨*level-1*⟩}

```
\DeclareDocumentCommand{\newlistentry}{o m m m}
{%
\LWR@traceinfo{newlistentry #2 #3 #4}%
\IfValueTF{#1}%
{%
    \@ifundefined{c@#2}{%
        \newcounter{#2}[#1]%
```

```
        \expandafter\edef\csname the#2\endcsname{%
            \expandafter\noexpand\csname the#1\endcsname.\noexpand\arabic{#2}%
        }%
    }{}%
}%
{%
    \@ifundefined{c@#2}{%
        \newcounter{#2}%
    }{}%
}%
\@namedef{l@#2}##1##2{%
    \hypertocfloat{1}{#2}{#3}{##1}{##2}%
    \def\cftwhatismyname{#2}% from memoir
}%
\expandafter\newlength\csname cftbefore#2skip\endcsname%
\expandafter\newlength\csname cft#2indent\endcsname%
\expandafter\newlength\csname cft#2numwidth\endcsname%
\@namedef{cft#2font}{}%
\@namedef{cft#2presnum}{}%
\@namedef{cft#2aftersnum}{}%
\@namedef{cft#2aftersnumb}{}%
\@namedef{cft#2leader}{}%
\@namedef{cft#2dotsep}{1}%
\@namedef{cft#2pagefont}{}%
\@namedef{cft#2afterpnum}{}%
\@namedef{toclevel@#2}{#4}%
\@namedef{cft#2fillnum}##1{}%
\LWR@traceinfo{newlistentry done}%
}
```

`\newlistof` `[`⟨*within*⟩`]` `{`⟨*type*⟩`}` `{`⟨*ext*⟩`}` `{`⟨*listofname*⟩`}`

Emulated through the `\newfloat` mechanism.

```
\DeclareDocumentCommand{\newlistof}{o m m m}
{%
    \IfValueTF{#1}%
        {\newlistentry[#1]{#2}{#3}{0}}%
        {\newlistentry{#2}{#3}{0}}%
    \@namedef{ext@#2}{#3}%
    \@ifundefined{c@#3depth}{\newcounter{#3depth}}{}%
    \setcounter{#3depth}{1}%
    \@namedef{cftmark#3}{}%
    \@namedef{listof#2}{\listof{#2}{#4}}%
    \@namedef{@cftmake#3title}{}%
    \expandafter\newlength\csname cftbefore#3titleskip\endcsname%
    \expandafter\newlength\csname cftafter#3titleskip\endcsname%
    \@namedef{cft#3titlefont}{}%
    \@namedef{cftafter#3title}{}%
    \@namedef{cft#3prehook}{}%
    \@namedef{cft#3posthook}{}%
}
```

`\cftchapterprecis` `{`⟨*text*⟩`}`

```
\newcommand{\cftchapterprecis}[1]{%
```

```
  \cftchapterprecishere{#1}
  \cftchapterprecistoc{#1}}
\newcommand{\cftchapterprecishere}[1]{%
  \begin{quote}\textit{#1}\end{quote}}
\newcommand{\cftchapterprecistoc}[1]{
  \addtocontents{toc}{%
  {
     \protect\begin{quote}#1\protect\end{quote}}
  }
}
```

File 502 **lwarp-tocstyle.sty**

§ 609 Package

# tocstyle

Pkg tocstyle tocstyle is ignored.

⚠ Not fully tested! Please send bug reports!

**for HTML output:**

```
\LWR@ProvidesPackageDrop{tocstyle}[2017/02/23]

\newcommand*{\usetocstyle}[2][]{}
\newcommand*{\deactivatetocstyle}[1][]{}
\newcommand*{\reactivatetocstyle}[1][]{}
\NewDocumentCommand{\settocfeature}{o o m m}{}
\NewDocumentCommand{\settocstylefeature}{o m m}{}
\NewDocumentCommand{\newtocstyle}{o o m m}{}
\newcommand*{\aliastoc}[2]{}
\newcommand*{\showtoc}[2][]{}
\newcommand{\iftochasdepth}[4]{}
```

File 503 **lwarp-todo.sty**

§ 610 Package

# todo

(*Emulates or patches code by* Federico Garcia.)

Pkg todo todo is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{todo}[2010/03/31]

\renewcommand\todoitem[2]{%
    \refstepcounter{todo}%
    \item[%
        \HTMLunicode{2610} \quad
        \ref{todopage:\thetodo}
     ] : {\todoformat\ifx#1\todomark\else\textbf{#1} \fi}#2%
    \label{todolbl:\thetodo}%
}%

\renewcommand\doneitem[2]{%
```

```
    \stepcounter{todo}%
    \item[%
        \HTMLunicode{2611} \quad
        \ref{todopage:\thetodo}
    ] \@nameuse{@done\the\c@todo}:
        {\todoformat\ifx#1\todomark\else\textbf{#1} \fi}#2%
}

\xpatchcmd{\@displaytodo}
    {\todoformat #1}{\todoformat \textbf{#1}}{}
    {\PackageWarning{lwarp-todo}{Unable to patch @displaytodo.}}

\xpatchcmd{\@displayfulltodo}
    {\todoformat #1}{\todoformat \textbf{#1}}{}
    {\PackageWarning{lwarp-todo}{Unable to patch @displayfulltodo.}}

\patchcmd{\todoenv}{\itshape see text.}{\textit{see text.}}{}
    {\PackageWarning{lwarp-todo}{Unable to patch todoenv.}}

\patchcmd{\astodos}{\todoformat #1}{\todoformat \textbf{#1}}{}
    {\PackageWarning{lwarp-todo}{Unable to patch astodos.}}

\AtBeginDocument{
    \crefname{todo}{todo}{todos}
    \Crefname{todo}{Todo}{Todos}
}
```

---

File 504 **lwarp-todonotes.sty**

# § 611 Package todonotes

(*Emulates or patches code by* Henrik Skov Midtiby.)

Pkg todonotes todonotes is emulated.

The documentation for todonotes and luatodonotes have an example with a todo inside a caption. If this example does not work it will be necessary to move the todo outside of the caption.

**for HTML output:**

```
\LWR@ProvidesPackagePass{todonotes}[2012/07/25]

\if@todonotes@disabled
\else

\newcommand{\ext@todo}{tdo}

\renewcommand{\l@todo}[2]{\hypertocfloat{1}{todo}{ldo}{#1}{#2}}

\let\LWRTODONOTES@orig@todototoc\todototoc

\renewcommand*{\todototoc}{%
\LWR@phantomsection%
```

```
\LWRTODONOTES@orig@todototoc%
}

\renewcommand{\@todonotes@drawMarginNoteWithLine}{
\fcolorbox
    {\@todonotes@currentbordercolor}
    {\@todonotes@currentbackgroundcolor}
    {\arabic{@todonotes@numberoftodonotes}}
\marginpar{\@todonotes@drawMarginNote}
}

\renewcommand{\@todonotes@drawInlineNote}{%
\fcolorboxBlock%
    {\@todonotes@currentbordercolor}%
    {\@todonotes@currentbackgroundcolor}%
    {%
        \if@todonotes@authorgiven%
        {\@todonotes@author:\,}%
        \fi%
        \@todonotes@text%
    }%
}

\renewcommand{\@todonotes@drawMarginNote}{%
    \if@todonotes@authorgiven%
        \@todonotes@author\par%
    \fi%
    \arabic{@todonotes@numberoftodonotes}: %
    \fcolorbox%
    {\@todonotes@currentbordercolor}%
    {\@todonotes@currentbackgroundcolor}%
    {%
        \@todonotes@sizecommand%
        \@todonotes@text %
    }%
}%

\renewcommand{\@todonotes@drawLineToRightMargin}{}

\renewcommand{\@todonotes@drawLineToLeftMargin}{}

\renewcommand{\missingfigure}[2][]{%
\setkeys{todonotes}{#1}%
\addcontentsline{tdo}{todo}{\@todonotes@MissingFigureText: #2}%
\fcolorboxBlock%
    {\@todonotes@currentbordercolor}%
    {\@todonotes@currentfigcolor}%
    {%
        \setlength{\fboxrule}{4pt}%
        \fcolorbox{red}{white}{Missing figure} \quad #2%
    }
}

\LetLtxMacro\LWRTODONOTES@orig@todo\@todo

```

```
\RenewDocumentCommand{\@todo}{o m}{%
\begingroup%
\renewcommand*{\phantomsection}{}%
\IfValueTF{#1}{%
    \LWRTODONOTES@orig@todo[#1]{#2}%
}{%
    \LWRTODONOTES@orig@todo{#2}%
}
\endgroup%
}

\fi% \if@todonotes@disabled
```

File 505 **lwarp-topcapt.sty**

## § 612 Package topcapt

Pkg topcapt topcapt is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{topcapt}[2004/12/11]

\LetLtxMacro\topcaption\caption
```

File 506 **lwarp-tram.sty**

## § 613 Package tram

Pkg tram tram is emulated.

⚠ block only The HTML emulation uses a , which must not appear inside an HTML  or an HTML paragraph. For this reason, the tram environment should only be used to contain paragraphs inside a \parbox or minipage. tram should not be used to mark up inline text.

To disable tram, allowing source compatibility with inline uses:

```
\begin{warpHTML}
\renewenvironment{tram}[1][]{}{}
\end{warpHTML}
```

**for HTML output:**

```
\LWR@ProvidesPackageDrop{tram}[2013/04/04]

\newenvironment{tram}[1][]%
    {\BlockClass[background:lightgray]{tram}}
    {\endBlockClass}
```

File 507 **lwarp-transparent.sty**

## § 614 Package transparent

(*Emulates or patches code by* Heiko Oberdiek.)

Pkg transparent transparent is emulated. `\texttransparent` works for inline objects. `\transparent` only works for `\includegraphics`.

⚠ Not XeLaTeX! Note that transparent does not work with XeLaTeX.

**for HTML output:**

```
\LWR@ProvidesPackagePass{transparent}[2019/11/29]

\newcommand*{\LWR@HTML@transparent}[1]{\edef\LWR@opacity{#1}}

\LWR@formatted{transparent}


\newcommand*{\LWR@HTML@texttransparent}[2]{%
\begingroup%
\transparent{#1}%
\InlineClass[opacity: #1]{transparent}{#2}%
\endgroup%
}

\LWR@formatted{texttransparent}
```

---

File 508 **lwarp-trimclip.sty**

## § 615 Package trimclip

Pkg trimclip trimclip is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{trimclip}[2018/04/08]
```

The third argument, the text, is not touched. This allows `\bgroup` / `\egroup`, and verbatim content.

```
\csdef{trimbox}{\@ifstar\@gobble\@gobble}
\csletcs{trimbox*}{trimbox}
\def\endtrimbox{}
\csletcs{endtrimbox*}{endtrimbox}

\csletcs{clipbox}{trimbox}
\csletcs{clipbox*}{trimbox}
\csletcs{endclipbox}{endtrimbox}
\csletcs{endclipbox*}{endtrimbox}

\csletcs{marginbox}{trimbox}
\csletcs{marginbox*}{trimbox}
\csletcs{endmarginbox}{endtrimbox}
\csletcs{endmarginbox*}{endtrimbox}
```

## § 617 Package truncate

Pkg truncate truncate is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{truncate}[2001/08/20]

\providecommand{\TruncateMarker}{}
\newcommand{\truncate}[3][\TruncateMarker]{#3}
```

---

File 511 **lwarp-turnthepage.sty**

## § 618 Package turnthepage

Pkg turnthepage turnthepage is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{turnthepage}[2011/03/24]

\newcommand{\turnthepage}{}
```

---

File 512 **lwarp-twoup.sty**

## § 619 Package twoup

Pkg twoup twoup is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{twoup}[2007/02/26]

\newcommand{\cleartolastpage}{}
```

---

File 513 **lwarp-txfonts.sty**

## § 620 Package txfonts

(*Emulates or patches code by* Young Ryu.)

Pkg txfonts txfonts is used as-is for SVG math, and is emulated for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{txfonts}[2008/01/22]
```

For MathJax:

```

\LWR@origRequirePackage{lwarp-common-mathjax-letters}

\begin{warpMathJax}
\LWR@infoprocessingmathjax{txfonts}

\LWR@mathjax@addgreek@l@up{}{up}
\end{warpMathJax}
```

File 514 **lwarp-txgreeks.sty**

## § 621 Package txgreeks

(*Emulates or patches code by* Jean-François Burnol.)

Pkg txgreeks txgreeks is used as-is for SVG math, and is emulated for MathJax.

The MathJax emulation honors all package options.

**for HTML output:**

```
\LWR@ProvidesPackagePass{txgreeks}[2011/03/16]

\LWR@infoprocessingmathjax{txgreeks}

\LWR@origRequirePackage{lwarp-common-mathjax-letters}

\begin{warpMathJax}
\iftgs@uplower% upright lowercase Greek
    \LWR@mathjax@addgreek@l@up{}{}
    \LWR@mathjax@addgreek@l@it{other}{}
\else% italic lowercase Greek
    \LWR@mathjax@addgreek@l@it{}{}
    \LWR@mathjax@addgreek@l@up{other}{}
\fi

\iftgs@itupper % italic uppercase Greek
    \LWR@mathjax@addgreek@u@it*{}{}
    \LWR@mathjax@addgreek@u@up*{other}{}
    \LWR@mathjax@addgreek@u@up*{var}{}
\else% upright uppercase Greek
    \LWR@mathjax@addgreek@u@up*{}{}
    \LWR@mathjax@addgreek@u@it*{other}{}
    \LWR@mathjax@addgreek@u@it*{var}{}
\fi
\end{warpMathJax}
```

File 515 **lwarp-typearea.sty**

## § 622 Package typearea

(*Emulates or patches code by* Markus Kohm.)

Pkg typearea typearea is emulated.

This package may be loaded standalone, but is also loaded automatically if koma-script classes are in use. `\DeclareDocumentCommand` is used to overwrite the koma-script definitions.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{typearea}[2018/03/30]
```

```
\DeclareDocumentCommand{\typearea}{o m}{}
\DeclareDocumentCommand{\recalctypearea}{}{}
\@ifundefined{footheight}{\newlength\footheight}{}
\DeclareDocumentCommand{\areaset}{o m m}{}
\DeclareDocumentCommand{\activateareas}{}{}
\DeclareDocumentCommand{\storeareas}{m}{}
\DeclareDocumentCommand{\BeforeRestoreareas}{s m}{}
\DeclareDocumentCommand{\AfterRestoreareas}{s m}{}
\DeclareDocumentCommand{\AfterCalculatingTypearea}{s m}{}
\DeclareDocumentCommand{\AfterSettingArea}{s m}{}
```

File 516 **lwarp-typicons.sty**

§ 623 Package

# typicons

(*Emulates or patches code by* Arthur Vigil, Xavier Danaux.)

Pkg typicons typicons is patched for use by lwarp.

If `\ticon` is used, the name of the icon is used in the `alt` tag. Otherwise, for each of the individual icon macros, a generic `alt` tag is used.

**for HTML output:**

```
\LWR@ProvidesPackagePass{typicons}[2015/05/20]

\LetLtxMacro\LWR@orig@symbol\symbol

\let\LWR@orig@typicon@TI\TI

\newcommand*{\LWR@typicon@symbol}[1]{%
    \begin{lateximage}*[typicon][typicon#1]%
    \begingroup%
    \LWR@orig@typicon@TI%
    \LWR@orig@symbol{#1}%
    \endgroup%
    \end{lateximage}%
}

\renewcommand*{\TI}{%
    \LetLtxMacro\symbol\LWR@typicon@symbol%
}

\renewcommand*{\ticon}[1]
{%
    \begin{lateximage}*[#1 icon][typicon#1]%
    \TI\csname ticon@#1\endcsname%
    \end{lateximage}%
}
```

File 517 **lwarp-ulem.sty**

## § 624 Package ulem

(*Emulates or patches code by* Donald Arseneau.)

Pkg ulem Patched for use by lwarp.

**for HTML output:** Use the original package:

```
\LWR@ProvidesPackagePass{ulem}[2012/05/18]
```

Basic markup commands, using CSS:

```
\NewDocumentCommand{\LWR@HTML@uline}{+m}{%
    \InlineClass%
        (text-decoration:underline; text-decoration-skip: auto)%
        {uline}{\LWR@isolate{#1}}%
}
\LWR@formatted{uline}

\NewDocumentCommand{\LWR@HTML@uuline}{+m}{%
    \InlineClass%
        (%
            text-decoration:underline; text-decoration-skip: auto;%
            text-decoration-style:double%
        )%
        {uuline}{\LWR@isolate{#1}}%
}
\LWR@formatted{uuline}

\NewDocumentCommand{\LWR@HTML@uwave}{+m}{%
    \InlineClass%
        (%
            text-decoration:underline; text-decoration-skip: auto;%
            text-decoration-style:wavy%
        )%
        {uwave}{\LWR@isolate{#1}}%
}
\LWR@formatted{uwave}

\NewDocumentCommand{\LWR@HTML@sout}{+m}{%
    \InlineClass%
        (text-decoration:line-through)%
        {sout}{\LWR@isolate{#1}}%
}
\LWR@formatted{sout}

\NewDocumentCommand{\LWR@HTML@xout}{+m}{%
    \InlineClass%
        (text-decoration:line-through)%
        {xout}{\LWR@isolate{#1}}%
}
\LWR@formatted{xout}

\NewDocumentCommand{\LWR@HTML@dashuline}{+m}{%
    \InlineClass%
```

```
        (%
            text-decoration:underline;%
            text-decoration-skip: auto;%
            text-decoration-style:dashed%
        )%
        {dashuline}{\LWR@isolate{#1}}%
}
\LWR@formatted{dashuline}

\NewDocumentCommand{\LWR@HTML@dotuline}{+m}{%
    \InlineClass%
        (%
            text-decoration:underline;%
            text-decoration-skip: auto;%
            text-decoration-style: dotted%
        )%
        {dotuline}{\LWR@isolate{#1}}%
}
\LWR@formatted{dotuline}
```

Nullified/emulated macros:

```
\NewDocumentCommand{\LWR@HTML@markoverwith}{m}{}
\LWR@formatted{markoverwith}

\NewDocumentCommand{\LWR@HTML@ULon}{+m}{\uline{#1}\egroup}
\LWR@formatted{ULon}
```

---

File 518 **lwarp-umoline.sty**

## § 625 Package umoline

(*Emulates or patches code by* Hiroshi Nakashima.)

Pkg umoline umoline is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{umoline}[2000/07/11]

\newcommand*{\LWR@HTML@Underline}[1]{%
    \InlineClass{uline}{#1}%
}
\LWR@formatted{Underline}

\newcommand*{\LWR@HTML@Midline}[1]{%
    \InlineClass{sout}{#1}%
}
\LWR@formatted{Midline}

\newcommand*{\LWR@HTML@Overline}[1]{%
    \InlineClass{oline}{#1}%
}
\LWR@formatted{Overline}

```

may be added as needed. Place the following in the document preamble after loading unicode-math, including a definition for each macro which is used in the document but undefined in MathJax:

```
\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\uplus}{\mathbin{\unicode{x0228E}}}}
...
\end{warpMathJax}
```

Use \mathrel, \mathbin, etc. depending on the category of each macro. For a list of macro names and symbols, see **texdoc unimath-symbols**.

**for HTML output:**

```
\LWR@ProvidesPackagePass{unicode-math}[2019/09/26]

\LWR@origRequirePackage{lwarp-common-mathjax-letters}

\begin{warpMathJax}
\LWR@infoprocessingmathjax{unicode-math}

% Not all are possible in MathJax.
\CustomizeMathJax{\let\symnormal\mathit}
\CustomizeMathJax{\let\symliteral\mathrm}
\CustomizeMathJax{\let\symbb\mathbb}
\CustomizeMathJax{\let\symbbit\mathbb}% not italic
\CustomizeMathJax{\let\symcal\mathcal}
\CustomizeMathJax{\let\symscr\mathscr}
\CustomizeMathJax{\let\symfrak\mathfrak}

\CustomizeMathJax{\let\symsfup\mathsf}

\CustomizeMathJax{\let\symsfit\mathit}% not sans
% \CustomizeMathJax{\newcommand{\symsfit}[1]{%
%     \mmlToken{mi}[mathvariant="sans-serif-italic"]{#1}}% not greek
% }

\CustomizeMathJax{\let\symbfsf\mathbf}% not sans
% \CustomizeMathJax{\newcommand{\symbfsf}[1]{%
%     \mmlToken{mi}[mathvariant="bold-sans-serif"]{#1}}% not greek
% }

\CustomizeMathJax{\let\symbfup\mathbf}
\CustomizeMathJax{\newcommand{\symbfit}[1]{\boldsymbol{#1}}}
\CustomizeMathJax{\let\symbfcal\mathcal}% not bold

\CustomizeMathJax{\let\symbfscr\mathscr}% not bold
% \CustomizeMathJax{\newcommand{\symbfscr}[1]{
%     \mmlToken{mi}[mathvariant="math-bold-script"]{#1}}% not greek
% }

\CustomizeMathJax{\let\symbffrak\mathfrak}% not bold
% \CustomizeMathJax{\newcommand{\symbffrak}[1]{%
%     \mmlToken{mi}[mathvariant="math-bold-fraktur"]{#1}}% not greek
% }

```

```
\CustomizeMathJax{\let\symbfsfup\mathbf}% not sans
% \CustomizeMathJax{\newcommand{\symbfsfup}[1]{%
%     \mmlToken{mi}[mathvariant="bold-sans-serif"]{#1}}% not greek
% }

\CustomizeMathJax{\newcommand{\symbfsfit}[1]{\boldsymbol{#1}}}% not sans
% \CustomizeMathJax{\newcommand{\symbfsfit}[1]{%
%     \mmlToken{mi}[mathvariant="sans-serif-bold-italic"]{#1}}% not greek
% }

% Duplicates below are commented out.
\CustomizeMathJax{\let\symup\mathrm}
\CustomizeMathJax{\let\symbf\mathbf}% \symbfup defined above
\CustomizeMathJax{\let\symit\mathit}
% \CustomizeMathJax{\let\symbfit\mathit}% not bold


\ExplSyntaxOn
\AtBeginDocument{
\bool_if:NTF \g__um_sfliteral_bool
    {\CustomizeMathJax{\let\symsf\symsfup}}
    {
        \bool_if:NTF \g__um_upsans_bool
            {\CustomizeMathJax{\let\symsf\symsfup}}
            {\CustomizeMathJax{\let\symsf\symsfit}}
    }
}
\ExplSyntaxOff

% \CustomizeMathJax{\let\symbfsfup\mathbf}% not sans
% \CustomizeMathJax{\let\symsfit\mathit}% not sans
% \CustomizeMathJax{\let\symbfsfit\mathit}% not bold nor sans
\CustomizeMathJax{\let\symtt\mathtt}
% \CustomizeMathJax{\let\symbb\mathbb}
% \CustomizeMathJax{\let\symbbit\mathbb}% not italic
% \CustomizeMathJax{\let\symscr\mathscr}
% \CustomizeMathJax{\let\symbfscr\mathscr}% not bold
% \CustomizeMathJax{\let\symfrak\mathfrak}
\CustomizeMathJax{\let\symbffrac\mathbffrac}
```

Some symbol categories defined by unicode-math, in case they are used inside custom macros:

```
\CustomizeMathJax{\newcommand{\mathfence}[1]{\mathord{#1}}}
\CustomizeMathJax{\newcommand{\mathover}[1]{#1}}
\CustomizeMathJax{\newcommand{\mathunder}[1]{#1}}
\CustomizeMathJax{\newcommand{\mathaccent}[1]{#1}}
\CustomizeMathJax{\newcommand{\mathbotaccent}[1]{#1}}
\CustomizeMathJax{\newcommand{\mathalpha}[1]{\mathord{#1}}}
```

`math-style` is one of: `ISO`, `TeX`, `french`, `upright`, or `literal`, which set `\g__um_upGreek_bool` and `\g__um_upgreek_bool`.

```
\ExplSyntaxOn

```

```
\AtBeginDocument{
\bool_if:NTF \g__um_upGreek_bool
    {\LWR@mathjax@addgreek@u@up*{}{}}
    {\LWR@mathjax@addgreek@u@it*{}{}}

\bool_if:NTF \g__um_upgreek_bool
    {\LWR@mathjax@addgreek@l@up{}{}}
    {\LWR@mathjax@addgreek@l@it{}{}}
}

\LWR@mathjax@addgreek@u@up*{up}{}
\LWR@mathjax@addgreek@u@it*{it}{}
\LWR@mathjax@addgreek@l@up{up}{}
\LWR@mathjax@addgreek@l@it{it}{}

\ExplSyntaxOff

\CustomizeMathJax{\let\lparen(}
\CustomizeMathJax{\let\rparen)}
\CustomizeMathJax{\newcommand{\cuberoot}[1]{\,{}^3\!\!\sqrt{#1}}\,}
\CustomizeMathJax{\newcommand{\fourthroot}[1]{\,{}^4\!\!\sqrt{#1}}\,}
```

Many `\mathopen`/`\mathclose` delimiters are defined in `lwarp_mathjax.txt`, where `\left`/`\right` support is added.

```
\CustomizeMathJax{\newcommand{\longdivision}[1]{\mathord{\unicode{x027CC}#1}}}

\CustomizeMathJax{\newcommand{\mathcomma}{,}}
\CustomizeMathJax{\newcommand{\mathcolon}{:}}
\CustomizeMathJax{\newcommand{\mathsemicolon}{;}}

\CustomizeMathJax{\newcommand{\overbracket}[1]{\mathinner{\overline{\ulcorner{#1}\urcorner}}}}
\CustomizeMathJax{\newcommand{\underbracket}[1]{\mathinner{\underline{\llcorner{#1}\lrcorner}}}}

\CustomizeMathJax{\newcommand{\overbar}[1]{\mathord{#1\unicode{x00305}}}}
\CustomizeMathJax{\newcommand{\ovhook}[1]{\mathord{#1\unicode{x00309}}}}
\CustomizeMathJax{\newcommand{\ocirc}[1]{\mathord{#1\unicode{x0030A}}}}
\CustomizeMathJax{\newcommand{\candra}[1]{\mathord{#1\unicode{x00310}}}}
\CustomizeMathJax{\newcommand{\oturnedcomma}[1]{\mathord{#1\unicode{x00312}}}}
\CustomizeMathJax{\newcommand{\ocommatopright}[1]{\mathord{#1\unicode{x00315}}}}
\CustomizeMathJax{\newcommand{\droang}[1]{\mathord{#1\unicode{x0031A}}}}
\CustomizeMathJax{\newcommand{\leftharpoonaccent}[1]{\mathord{#1\unicode{x020D0}}}}
\CustomizeMathJax{\newcommand{\rightharpoonaccent}[1]{\mathord{#1\unicode{x020D1}}}}
\CustomizeMathJax{\newcommand{\vertoverlay}[1]{\mathord{#1\unicode{x020D2}}}}
\CustomizeMathJax{\newcommand{\leftarrowaccent}[1]{\mathord{#1\unicode{x020D0}}}}
\CustomizeMathJax{\newcommand{\annuity}[1]{\mathord{#1\unicode{x020E7}}}}
\CustomizeMathJax{\newcommand{\widebridgeabove}[1]{\mathord{#1\unicode{x020E9}}}}
\CustomizeMathJax{\newcommand{\asteraccent}[1]{\mathord{#1\unicode{x020F0}}}}
\CustomizeMathJax{\newcommand{\threeunderdot}[1]{\mathord{#1\unicode{x020E8}}}}

\CustomizeMathJax{\newcommand{\Bbbsum}{\mathop{\unicode{x2140}}\limits}}
\CustomizeMathJax{\newcommand{\oiint}{\mathop{\unicode{x222F}}\limits}}
\CustomizeMathJax{\newcommand{\oiiint}{\mathop{\unicode{x2230}}\limits}}
\CustomizeMathJax{\newcommand{\intclockwise}{\mathop{\unicode{x2231}}\limits}}
\CustomizeMathJax{\newcommand{\ointclockwise}{\mathop{\unicode{x2232}}\limits}}
```

```
\CustomizeMathJax{\newcommand{\ointctrclockwise}{\mathop{\unicode{x2233}}\limits}}
\CustomizeMathJax{\newcommand{\varointclockwise}{\mathop{\unicode{x2232}}\limits}}
\CustomizeMathJax{\newcommand{\leftouterjoin}{\mathop{\unicode{x27D5}}\limits}}
\CustomizeMathJax{\newcommand{\rightouterjoin}{\mathop{\unicode{x27D6}}\limits}}
\CustomizeMathJax{\newcommand{\fullouterjoin}{\mathop{\unicode{x27D7}}\limits}}
\CustomizeMathJax{\newcommand{\bigbot}{\mathop{\unicode{x27D8}}\limits}}
\CustomizeMathJax{\newcommand{\bigtop}{\mathop{\unicode{x27D9}}\limits}}
\CustomizeMathJax{\newcommand{\xsol}{\mathop{\unicode{x29F8}}\limits}}
\CustomizeMathJax{\newcommand{\xbsol}{\mathop{\unicode{x29F9}}\limits}}
\CustomizeMathJax{\newcommand{\bigcupdot}{\mathop{\unicode{x2A03}}\limits}}
\CustomizeMathJax{\newcommand{\bigsqcap}{\mathop{\unicode{x2A05}}\limits}}
\CustomizeMathJax{\newcommand{\conjquant}{\mathop{\unicode{x2A07}}\limits}}
\CustomizeMathJax{\newcommand{\disjquant}{\mathop{\unicode{x2A08}}\limits}}
\CustomizeMathJax{\newcommand{\bigtimes}{\mathop{\unicode{x2A09}}\limits}}
\CustomizeMathJax{\newcommand{\modtwosum}{\mathop{\unicode{x2A0A}}\limits}}
\CustomizeMathJax{\newcommand{\sumint}{\mathop{\unicode{x2A0B}}\limits}}
\CustomizeMathJax{\newcommand{\intbar}{\mathop{\unicode{x2A0D}}\limits}}
\CustomizeMathJax{\newcommand{\intBar}{\mathop{\unicode{x2A0E}}\limits}}
\CustomizeMathJax{\newcommand{\fint}{\mathop{\unicode{x2A0F}}\limits}}
\CustomizeMathJax{\newcommand{\cirfnint}{\mathop{\unicode{x2A10}}\limits}}
\CustomizeMathJax{\newcommand{\awint}{\mathop{\unicode{x2A11}}\limits}}
\CustomizeMathJax{\newcommand{\rppolint}{\mathop{\unicode{x2A12}}\limits}}
\CustomizeMathJax{\newcommand{\scpolint}{\mathop{\unicode{x2A13}}\limits}}
\CustomizeMathJax{\newcommand{\npolint}{\mathop{\unicode{x2A14}}\limits}}
\CustomizeMathJax{\newcommand{\pointint}{\mathop{\unicode{x2A15}}\limits}}
\CustomizeMathJax{\newcommand{\sqint}{\mathop{\unicode{x2A16}}\limits}}
\CustomizeMathJax{\newcommand{\intlarhk}{\mathop{\unicode{x2A17}}\limits}}
\CustomizeMathJax{\newcommand{\intx}{\mathop{\unicode{x2A18}}\limits}}
\CustomizeMathJax{\newcommand{\intcap}{\mathop{\unicode{x2A19}}\limits}}
\CustomizeMathJax{\newcommand{\intcup}{\mathop{\unicode{x2A1A}}\limits}}
\CustomizeMathJax{\newcommand{\upint}{\mathop{\unicode{x2A1B}}\limits}}
\CustomizeMathJax{\newcommand{\lowint}{\mathop{\unicode{x2A1C}}\limits}}
\CustomizeMathJax{\newcommand{\bigtriangleleft}{\mathop{\unicode{x2A1E}}\limits}}
\CustomizeMathJax{\newcommand{\zcmp}{\mathop{\unicode{x2A1F}}\limits}}
\CustomizeMathJax{\newcommand{\zpipe}{\mathop{\unicode{x2A20}}\limits}}
\CustomizeMathJax{\newcommand{\zproject}{\mathop{\unicode{x2A21}}\limits}}
\CustomizeMathJax{\newcommand{\biginterleave}{\mathop{\unicode{x2AFC}}\limits}}
\CustomizeMathJax{\newcommand{\bigtalloblong}{\mathop{\unicode{x2AFF}}\limits}}
\CustomizeMathJax{\newcommand{\arabicmaj}{\mathop{\unicode{x1EEF0}}\limits}}
\CustomizeMathJax{\newcommand{\arabichad}{\mathop{\unicode{x1EEF1}}\limits}}

\end{warpMathJax}
```

---

File 521 **lwarp-units.sty**

§ 628 Package

# units

(*Emulates or patches code by* Axel Reichert.)

Pkg units units is patched for use by lwarp.

Values are not styled by CSS, and take the style of the surrounding HTML text.

```
\renewunit{\arcmin}{%
    \ifnumcomp{\value{LWR@lateximagedepth}}{>}{0}%
        {\ensuremath{{}^\prime}}%
        {\HTMLunicode{2032}}% prime
}

\renewunit{\arcsec}{%
    \ifnumcomp{\value{LWR@lateximagedepth}}{>}{0}%
        {\ensuremath{{}^{\prime\prime}}}%
        {\HTMLunicode{2033}}% dbl prime
}

\renewrobustcmd{\SI}[2]{%
  \begingroup%
    \let\unit@@xspace\relax%
    \unitSIdef\selectfont%
      \LWR@textcurrentfont{#1#2}% lwarp
  \endgroup%
}
```

---

File 523 **lwarp-upgreek.sty**

## § 630 Package upgreek

(*Emulates or patches code by* Walter Schmidt.)

Pkg upgreek upgreek is used as-is for SVG math, and is emulated for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{upgreek}[2003/02/12]
```

For MathJax:

```
\LWR@origRequirePackage{lwarp-common-mathjax-letters}

\begin{warpMathJax}
\LWR@infoprocessingmathjax{upgreek}

\LWR@mathjax@addgreek@l@up{up}{}
\LWR@mathjax@addgreek@u@up{Up}{}

\end{warpMathJax}
```

---

File 524 **lwarp-upref.sty**

## § 631 Package upref

Pkg upref upref is ignored.

**for HTML output:** Discard all options for lwarp-upref:

```
\LWR@ProvidesPackageDrop{upref}[2007/03/14]
```

File 525 **lwarp-url.sty**

## § 632 Package url

(*Emulates or patches code by* Donald Arseneau.)

Pkg url url is patched for use by lwarp.

**for HTML output:**

```
\LetLtxMacro\LWR@url@orig@url\LWR@url

\LWR@ProvidesPackagePass{url}[2013/09/16]

\newcommand*{\LWR@HTML@Url@FormatString}{%
    \expandafter\LWR@url@orig@url\expandafter{\Url@String}%
}
\LWR@formatted{Url@FormatString}
```

File 526 **lwarp-ushort.sty**

## § 633 Package ushort

(*Emulates or patches code by* Martin Väth.)

Pkg ushort ushort is used as-is, and emulated for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{ushort}[2001/06/13]

\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\ushortdline}[1]{%
    \kern{.1em}\underline{\underline{{#1}}}\kern{.1em}%
}}
\CustomizeMathJax{\newcommand{\ushort}[1]{\kern{.1em}\underline{#1}\kern{.1em}}}
\CustomizeMathJax{\newcommand{\ushortd}[1]{\ushortdline{#1}}}
\CustomizeMathJax{\newcommand{\ushortw}[1]{\kern{.1em}\underline{#1}\kern{.1em}}}
\CustomizeMathJax{\newcommand{\ushortdw}[1]{\ushortdline{#1}}}
\end{warpMathJax}
```

File 527 **lwarp-uspace.sty**

## § 634 Package uspace

Pkg uspace uspace is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{uspace}[2016/11/06]
```

```
\LWR@traceinfo{Finished patching verse.}
}% AfterEndPreamble
```

---

File 530 **lwarp-versonotes.sty**

## § 637 Package versonotes

(*Emulates or patches code by* Norman Gray.)

Pkg versonotes versonotes is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{versonotes}[2019/07/06]

\newcommand{\versonote}[1]{\marginpar{#1}}
\newdimen\versotextwidth
\newdimen\versoleftmargin
\newcommand*{\versolayout}{}
```

In case the user changed the page number before loading versonotes:

```
\setcounter{page}{1}
```

---

File 531 **lwarp-vertbars.sty**

## § 638 Package vertbars

(*Emulates or patches code by* Peter Wilson.)

Pkg vertbars vertbars is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{vertbars}[2010/11/27]

\newlength{\barwidth}
\setlength{\barwidth}{0.4pt}
\newlength{\barspace}
\setlength{\barspace}{1em}

\newenvironment{vertbar}{
    \LWR@forcenewpage
    \LWR@forceminwidth{\barwidth}
    \begin{BlockClass}[%
        border-left: \LWR@printlength{\LWR@atleastonept} solid black ; %
        padding-left: \LWR@printlength{\barspace}%
    ]{vertbar}
}{
    \end{BlockClass}
}
```

---

File 532 **lwarp-vmargin.sty**

## § 639 Package vmargin

Pkg vmargin vmargin is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{vmargin}[2004/07/15]

\newcommand*{\LWRVM@customsize}[2]{}
\newcommand*{\setpapersize}[2][]{\ifstrequal{#2}{custom}{\LWRVM@customsize}{}}
\newcommand*{\setmargins}[8]{}
\newcommand*{\setmarginsrb}[8]{}
\newcommand*{\setmargnohf}[4]{}
\newcommand*{\setmargnohfrb}[4]{}
\newcommand*{\setmarg}[4]{}
\newcommand*{\setmargrb}[4]{}
\newlength{\PaperWidth}
\setlength{\PaperWidth}{8.5in}
\newlength{\PaperHeight}
\setlength{\PaperHeight}{11in}
\newif\ifLandscape
```

---

File 533 **lwarp-vowel.sty**

## § 640 Package vowel

(*Emulates or patches code by* FUKUI Rei.)

Pkg vowel vowel is patched for use by lwarp.

This package has been tested with *pdflatex* and the Type 1 TIPA fonts using the following package load sequence:

```
\usepackage[T3,T1]{fontenc}
\usepackage[utf8]{inputenc}
\usepackage[noenc]{tipa}
\usepackage{vowel}
```

**for HTML output:**

```
\LWR@ProvidesPackagePass{vowel}[2002/08/08]

\renewenvironment{vowel}[1][]
    {%
        \begin{lateximage}[-vowel-~\PackageDiagramAltText]%
        \@vowel[#1]%
    }
    {%
        \@@vowel%
        \end{lateximage}%
    }
```

---

File 534 **lwarp-vpe.sty**

## § 641 Package vpe

Pkg vpe vpe is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{vpe}[2012/04/18]
```

---

File 535 **lwarp-vwcol.sty**

## § 642 Package vwcol

(*Emulates or patches code by* Will Robertson.)

Pkg vwcol vwcol is patched for use with lwarp.

The `width` option is ignored. All `vwcol` environments adjust to 1–3 equal-width columns, depening on the width of the browser window.

The remaining options are supported, except for `lines` and `maxrecursion`.

**for HTML output:**

```
\LWR@ProvidesPackagePass{vwcol}[2015/02/10]
```

Factored from `\vwcol`. Each is given a style tag to append to the final style.

`\LWR@vwcol@addrule` {⟨*style tag*⟩}

```
\newcommand*{\LWR@vwcol@addrule}[1]{%
    \appto{\LWR@vwcolstyle}{%
        #1: %
     \LWR@printlength{\vwcol@rule} solid \LWR@origpound\LWR@vwcol@rulecolor ; %
    }%
}
```

`\LWR@vwcol@addrule` {⟨*style tag*⟩}

```
\newcommand*{\LWR@vwcol@addgap}[1]{%
    \appto{\LWR@vwcolstyle}{%
        #1: %
        \LWR@printlength{\vwcol@sep} ; %
    }%
}
```

Env vwcol {⟨*key/values*⟩}

Redefine the environment to add a HTML style. The style is built depending on the required options.

```
\renewenvironment*{vwcol}[1][]{%
```

New paragraph, and process the options:

```
\LWR@stoppars%
\vwcolsetup{#1}%
```

Begin with no style:

```
\newcommand*{\LWR@vwcolstyle}{}
```

presep and postsep are created with HTML margins:

```
\if@vwcol@presep
    \appto{\LWR@vwcolstyle}{margin-left: 1em ; padding-left: .5em ; }
\fi
\if@vwcol@postsep
    \appto{\LWR@vwcolstyle}{margin-right: 1em ; padding-right: .5em ; }
\fi
```

sep becomes column-gap:

```
\ifdimgreater{\vwcol@sep}{1sp}{
    \LWR@vwcol@addgap{column-gap}
    \LWR@vwcol@addgap{-moz-column-gap}
    \LWR@vwcol@addgap{-webkit-column-gap}
}{}
```

rule become column-rule, while prerule and postrule become HTML borders:

```
\convertcolorspec{named}{\vwcol@rulecol}{HTML}\LWR@vwcol@rulecolor%
\ifdimgreater{\vwcol@rule}{0pt}{
    \ifdimless{\vwcol@rule}{1pt}{
        \setlength{\vwcol@rule}{1pt}
    }{}
    \LWR@vwcol@addrule{column-rule}
    \LWR@vwcol@addrule{-moz-column-rule}
    \LWR@vwcol@addrule{-webkit-column-rule}
    \if@vwcol@prerule\LWR@vwcol@addrule{border-left}\fi
    \if@vwcol@postrule\LWR@vwcol@addrule{border-right}\fi
}{}
```

Each of the justify options becomes a text-align. Indentation is added where appropriate.

```
\ifdefequal{\vwcol@justify}{\RaggedRight}{
    \appto{\LWR@vwcolstyle}{text-align: left ; }
    \ifdimgreater{\vwcol@parindent}{0pt}{
        \appto{\LWR@vwcolstyle}{%
            text-indent: \LWR@printlength{\vwcol@parindent} ; %
        }
    }{}
}{}

\ifdefequal{\vwcol@justify}{\RaggedLeft}{
    \appto{\LWR@vwcolstyle}{text-align: right ; }
}{}

\ifdefequal{\vwcol@justify}{\Centering}{
    \appto{\LWR@vwcolstyle}{text-align: center ; }
}{}

\ifdefequal{\vwcol@justify}{\justifying}{
    \appto{\LWR@vwcolstyle}{text-align: justify ; }
    \ifdimgreater{\vwcol@parindent}{0pt}{
        \appto{\LWR@vwcolstyle}{%
            text-indent: \LWR@printlength{\vwcol@parindent} ; %
        }
```

```
    }{}
}{}
```

Create the  with the assembled style:

```
\BlockClass[\LWR@vwcolstyle]{multicols}
}
```

When the environment ends:

```
{
\endBlockClass
\LWR@startpars
}
```

---

File 536 **lwarp-wallpaper.sty**

## § 643 Package wallpaper

(*Emulates or patches code by* Michael H.F. Wilkinson.)

Pkg wallpaper wallpaper is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{wallpaper}[2005/01/18]
```

```
\newcommand*{\CenterWallPaper}[2]{}
\newcommand*{\ThisCenterWallPaper}[2]{}
\newcommand*{\TileWallPaper}[3]{}
\newcommand*{\ThisTileWallPaper}[3]{}
\newcommand*{\TileSquareWallPaper}[2]{}
\newcommand*{\ThisTileSquareWallPaper}[2]{}
\newcommand*{\ULCornerWallPaper}[2]{}
\newcommand*{\ThisULCornerWallPaper}[2]{}
\newcommand*{\LLCornerWallPaper}[2]{}
\newcommand*{\ThisLLCornerWallPaper}[2]{}
\newcommand*{\URCornerWallPaper}[2]{}
\newcommand*{\ThisURCornerWallPaper}[2]{}
\newcommand*{\LRCornerWallPaper}[2]{}
\newcommand*{\ThisLRCornerWallPaper}[2]{}
\newcommand*{\ClearWallPaper}{}
\newlength{\wpXoffset}
\newlength{\wpYoffset}
```

---

File 537 **lwarp-watermark.sty**

## § 644 Package watermark

(*Emulates or patches code by* Alexander I. Rozhenko.)

Pkg watermark watermark is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{watermark}[2004/12/09]
```

```
\newcommand{\watermark}[1]{}
\newcommand{\leftwatermark}[1]{}
\newcommand{\rightwatermark}[1]{}
\newcommand{\thiswatermark}[1]{}
\newcommand{\thispageheading}[1]{}
```

File 538 **lwarp-widetable.sty**

## § 645 Package widetable

(*Emulates or patches code by* Claudio Beccari.)

Pkg widetable widetable is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{widetable}[2019-06-25]
```

```
\newenvironment{widetable}{\begin{tabular*}}{\end{tabular*}}
```

File 539 **lwarp-widows-and-orphans.sty**

## § 646 Package widows-and-orphans

Pkg widows-and-orphans widows-and-orphans is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{widows-and-orphans}[2018/09/01]
```

```
\NewDocumentCommand\WaOsetup{m}{}
\NewDocumentCommand\WaOparameters{}{}
\NewDocumentCommand\WaOignorenext{}{}
```

File 540 **lwarp-witharrows.sty**

## § 647 Package witharrows

(*Emulates or patches code by* F. Pantigny.)

Pkg witharrows witharrows is patched for use by lwarp. Emulation is provided for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{witharrows}[2019/12/27]
```

```
\ifbool{mathjax}{
    % For the hidden print version in the HTML:
    \newcommand{\Arrow}[2][]{}
    \newcommand{\unicode}[1]{}
    \NewDocumentEnvironment { DispWithArrows } { ! d < > ! O { } +b}
        {
            \IfValueTF{#1}{
```

```
                \begin{displaymath}
                #1 \left\lbrace
                \begin{align}
                #3
                \end{align}
                \right .
                \end{displaymath}
            }{
                \begin{displaymath}
                \begin{align}
                #3
                \end{align}
                \end{displaymath}
            }
        }
        {}
    \NewDocumentEnvironment { DispWithArrows* } { ! d < > ! O { } +b}
        {
            \IfValueTF{#1}{
                \begin{displaymath}
                #1 \left\lbrace
                \begin{align*}
                #3
                \end{align*}
                \right .
                \end{displaymath}
            }{
                \begin{displaymath}
                \begin{align*}
                #3
                \end{align*}
                \end{displaymath}
            }
        }
        {}
}{
    % If not MathJax, use SVG images.
    \BeforeBeginEnvironment{WithArrows}{\global\booltrue{LWR@unknownmathsize}}
    \BeforeBeginEnvironment{DispWithArrows}{%
        \begin{BlockClass}{displaymathnumbered}%
        \begin{lateximage}%
    }
    \AfterEndEnvironment{DispWithArrows}{\end{lateximage}\end{BlockClass}}
    \BeforeBeginEnvironment{DispWithArrows*}{%
        \begin{BlockClass}{displaymath}%
        \begin{lateximage}%
    }
    \AfterEndEnvironment{DispWithArrows*}{\end{lateximage}\end{BlockClass}}
}

\begin{warpMathJax}
\CustomizeMathJax{\newenvironment{WithArrows}[1][]{\begin{aligned}}{\end{aligned}}}
% Unable to make a sized box.
\CustomizeMathJax{\newcommand{\Arrow}[2][]{&{\Large\unicode{x2938}}~\textit{#2}}}
\end{warpMathJax}
```

File 541 **lwarp-wrapfig.sty**

# § 648 Package wrapfig

(*Emulates or patches code by* Donald Arseneau.)

Pkg wrapfig wrapfig is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{wrapfig}[2003/01/31]

\newcommand*{\LWR@wrapposition}{}

\newcommand*{\LWR@subwrapfigure}[2]{%
\renewcommand*{\LWR@wrapposition}{}%
\ifthenelse{%
    \equal{#1}{r}\OR\equal{#1}{R}\OR%
    \equal{#1}{o}\OR\equal{#1}{O}%
}%
    {\renewcommand*{\LWR@wrapposition}{float:right}}%
    {\renewcommand*{\LWR@wrapposition}{float:left}}%
\setlength{\LWR@templengthone}{#2}%
\LWR@BlockClassWP{%
    width:\LWR@printlength{\LWR@templengthone}; \LWR@wrapposition; %
    margin:10pt%
}%
{%
    width:\LWR@printlength{\LWR@templengthone}; \LWR@wrapposition; %
}%
{marginblock}%

\setlength{\linewidth}{\LWR@templengthone}%
}


\NewDocumentEnvironment{wrapfigure}{o m o m}
{%
    \begin{LWR@setvirtualpage}*%
    \LWR@subwrapfigure{#2}{#4}%
    \renewcommand*{\@captype}{figure}%
}
{%
    \endLWR@BlockClassWP%
    \end{LWR@setvirtualpage}%
}


\NewDocumentEnvironment{wraptable}{o m o m}
{%
    \begin{LWR@setvirtualpage}*%
    \LWR@subwrapfigure{#2}{#4}%
    \renewcommand*{\@captype}{table}%
```

```
}
{%
    \endLWR@BlockClassWP%
    \end{LWR@setvirtualpage}%
}


\NewDocumentEnvironment{wrapfloat}{m o m o m}
{%
    \begin{LWR@setvirtualpage}*%
    \LWR@subwrapfigure{#3}{#5}%
    \renewcommand*{\@captype}{#1}%
}
{%
    \endLWR@BlockClassWP%
    \end{LWR@setvirtualpage}%
}

\newlength{\wrapoverhang}
```

File 542 **lwarp-xbmks.sty**

## § 649 Package xbmks

Pkg xbmks xbmks is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{xbmks}[2018/07/04]

\newcommand{\xbmksetup}[1]{}
\NewDocumentCommand{\pdfbookmarkx}{o m o m}{}
\NewDocumentCommand{\currentpdfbookmarkx}{m o m}{}
\NewDocumentCommand{\subpdfbookmarkx}{m o m}{}
\NewDocumentCommand{\belowpdfbookmarkx}{m o m}{}
```

File 543 **lwarp-xcolor.sty**

## § 650 Package xcolor

(*Emulates or patches code by* Dr. Uwe Kern.)

Pkg xcolor xcolor is supported by lwarp.

## § 650.1 Limitations

\colorboxBlock and \fcolorboxBlock

\colorboxBlock and \fcolorboxBlock are provided for increased HTML compatibility, and they are identical to \colorbox and \fcolorbox in print mode. In HTML mode they place their contents into a  instead of a . These s are set to display: inline-block so adjacent \colorboxBlocks appear side-by-side in HTML, although text is placed before or after each.

Print-mode definitions for \colorboxBlock and \fcolorboxBlock are created by lwarp's core if xcolor is loaded.

background: none

\fcolorbox and \fcolorboxBlock allow a background color of none, in which case only the frame is drawn, which can be useful for HTML.

color support

Color definitions, models, and mixing are fully supported without any changes required.

colored tables

\rowcolors is supported, except that the optional argument is ignored so far.

colored text and boxes

\textcolor, \colorbox, and \fcolorbox are supported.

\color and \pagecolor

\color and \pagecolor are ignored. Use CSS or \textcolor where possible.

## § 650.2 xcolor definitions: location and timing

The lwarp core and its lwarp-xcolor package are tightly integrated to allow comparable results for print, HTML, and print inside an HTML lateximage. This requires a number of definitions and redefintions depending on whether each of xcolor and lateximage is being used, and whether print or HTML is being generated. Some of these actions are one-time when xcolor is loaded, and others are temporary as lateximage is used.

**When xcolor is loaded in print mode:** No special actions are taken at the time that xcolor is loaded in print mode, but see \AtBeginDocument below.

**When lwarp-xcolor is loaded in HTML mode:** xcolor's original definitions are saved for later restoration. \LWR@restoreorigformatting is appended to restore these definitions for use inside a lateximage. New HTML-mode definitions are created for \textcolor, \pagecolor, \nopagecolor, \colorbox, \colorboxBlock, \fcolorbox, \fcolorboxBlock, and fcolorminipage.

**\AtBeginDocument in print or HTML mode:** See Section 88. If xcolor has been loaded, the print-mode \fcolorbox is modified to accept a background color of none, and additional definitions are created for lwarp's new macros print-mode macros \colorboxBlock, \fcolorboxBlock, and fcolorminipage. The HTML versions of these macros will already have been created by lwarp-xcolor if it has been loaded.

For use inside an HTML lateximage, \LWR@restoreorigformatting is appended to temporarily set these functions to their print-mode versions.

**In a lateximage in HTML mode:** \LWR@restoreorigformatting temporarily restores the print-mode definitions of xcolor's functions. See \LWR@restoreorigformatting on page 535.

**\color:**

**Print:** Used as-is.

**HTML:** Ignored by *pdftotext*, and will not appear.

**HTML lateximage:** Colors will appear in a `lateximage`.

**`\textcolor`:**

**Print:** Used as-is.

**HTML:** Redefined by lwarp-xcolor, page 1214.

**HTML lateximage:** Remembers and reuses the print version.

**`\pagecolor`:**

**Print:** Used as-is.

**HTML:** Ignored.

**HTML lateximage:** Colors will be picked up in a `lateximage`.

**`\nopagecolor`:**

**Print:** Used as-is.

**HTML:** Ignored.

**HTML lateximage:** Colors will be picked up in a `lateximage`.

**`\colorbox`:**

**Print:** Used as-is.

**HTML:** Redefined by lwarp-xcolor, page 1215.

**HTML lateximage:** Remembers and reuses the print version.

**`\colorboxBlock`:**

**Print:** Becomes `\colorbox`.

**HTML:** Newly defined by lwarp-xcolor to use a `<div>`, page 1215.

**HTML lateximage:** Remembers and reuses the print version `\colorbox`.

**`\fcolorbox`:**

**Print:** Modified to allow a background of none.
`\LWR@print@fcolorbox` at section 88

**HTML:** Redefined by lwarp-xcolor, page 1215.

**HTML lateximage:** Remembers and reuses the print version.

**`\fcolorboxBlock`:**

**Print:** Becomes `\fcolorbox`. Section 88

**HTML:** Newly defined by lwarp-xcolor to use a `<div>`, page 1216.

**HTML lateximage:** Remembers and reuses the print version `\fcolorbox`.

**`fcolorminipage`:**

**Print:** Newly defined in the lwarp core.
`LWR@print@fcolorminipage` at section 88

**HTML:** Newly defined by lwarp-xcolor, page 1217.

**HTML `lateximage`:** Uses the print version.

**`\boxframe`:**

**Print:** Used as-is.

**HTML:** Redefined by lwarp-xcolor, page 1218.

**HTML `lateximage`:** Remembers and reuses the print version.

## § 650.3 Package loading

**for HTML output:**

```
\LWR@ProvidesPackagePass{xcolor}[2016/05/11]
```

## § 650.4 Remembering and restoring original definitions

Remember the following print-mode actions to be restored when inside a `lateximage` environment:

```
\LetLtxMacro\LWR@print@pagecolor\pagecolor
\LetLtxMacro\LWR@print@nopagecolor\nopagecolor
```

\LWR@restoreorigformatting

Inside a `lateximage` the following gets restored to their print-mode actions:

```
\appto\LWR@restoreorigformatting{%
\LetLtxMacro\pagecolor\LWR@print@pagecolor%
\LetLtxMacro\nopagecolor\LWR@print@nopagecolor%
}
```

## § 650.5 `\normalcolor`

\normalcolor

```
\DeclareRobustCommand{\LWR@HTML@normalcolor}{\color{black}}%

\LWR@formatted{normalcolor}
```

## § 650.6 HTML color style

\LWR@findcurrenttextcolor

Sets `\LWR@tempcolor` to the current color.

```
\renewcommand*{\LWR@findcurrenttextcolor}{%
\protect\colorlet{LWR@current@color}{.}%
\protect\convertcolorspec{named}{LWR@current@color}{HTML}\LWR@tempcolor%
}
```

\LWR@currenttextcolorstyle

Prints a color style for the current color.

```
\newcommand*{\LWR@currenttextcolorstyle}{%
\LWR@findcurrenttextcolor%
\ifdefstring{\LWR@tempcolor}{000000}%
{}%
{color: \LWR@origpound\LWR@tempcolor ; }%
}
```

\LWR@textcurrentcolor {⟨*text*⟩} Like \textcolor but uses the current \color instead.

```
\DeclareDocumentCommand{\LWR@textcurrentcolor}{m}{%
\begingroup%
\LWR@hook@processingtags%
\LWR@findcurrenttextcolor%
\InlineClass[color:\LWR@origpound\LWR@tempcolor]{textcolor}{%
    \renewcommand*{\LWR@currenttextcolor}{\LWR@origpound\LWR@tempcolor}%
    #1%
}%
\endgroup%
}
```

\LWR@colorstyle {⟨*1: model*⟩} {⟨*2: color*⟩}

For a color style, prints the color converted to HTML colors.

```
\NewDocumentCommand{\LWR@colorstyle}{m m}{%
\begingroup%
\LWR@hook@processingtags%
```

Use the xcolor package to convert to an HTML color space:

```
\convertcolorspec{#1}{#2}{HTML}\LWR@tempcolor%
```

Print the converted color:

```
\LWR@origpound\LWR@tempcolor%
\endgroup%
}
```

\LWR@backgroundcolor [⟨*model*⟩] {⟨*color*⟩} {⟨*text*⟩}

Similar to \textcolor, but prints black text against a color background.

Converted into an HTML hex color span.

```
\NewDocumentCommand{\LWR@backgroundcolor}{O{named} m m}{%
\begingroup%
\LWR@hook@processingtags%
\InlineClass[background:\LWR@colorstyle{#1}{#2}]{backgroundcolor}{%
#3%
}%
\endgroup%
}
```

## § 650.7 HTML border

\LWR@borderpadding {⟨*colorstyle*⟩} {⟨*color*⟩} Prints the HTML attributes for a black border and padding. \LWR@forceminwidth must be used first in order to set the border width.

```
\newcommand*{\LWR@borderpadding}[2]{%
border:\LWR@printlength{\LWR@atleastonept} solid \LWR@colorstyle{#1}{#2} ; %
padding:\LWR@printlength{\fboxsep}%
}
```

## § 650.8 High-level macros

\color [⟨*model*⟩] {⟨*color*⟩}

⚠ The current \color is used by HTML rules and frames, but does not affect the current HTML text output, due to the lack of HTML states and scoping limitations. Use \textcolor if possible.

```
\NewDocumentCommand{\LWR@HTML@color}{o m}{%
\IfValueTF{#1}{%
    \LWR@print@color[#1]{#2}%
    \convertcolorspec{#1}{#2}{HTML}\LWR@tempcolor%
}{%
    \LWR@print@color{#2}%
    \convertcolorspec{named}{#2}{HTML}\LWR@tempcolor%
}%
\edef\LWR@currenttextcolor{\LWR@origpound\LWR@tempcolor}%
}

\LWR@formatted{color}
```

\textcolor [⟨*model*⟩] {⟨*color*⟩} {⟨*text*⟩}

Converted into an HTML hex color span.

```
\NewDocumentCommand{\LWR@HTML@textcolor}{o m m}{%
\begingroup%
\LWR@hook@processingtags%
\IfValueTF{#1}{%
    \color[#1]{#2}%
}{%
    \color{#2}%
}%
\InlineClass[color:\LWR@currenttextcolor]{textcolor}{#3}%
\endgroup%
}%

\LWR@formatted{textcolor}
```

\pagecolor [⟨*model*⟩] {⟨*color*⟩}

Ignored. Use CSS instead.

```
\renewcommand*{\pagecolor}[2][named]{}
```

\nopagecolor Ignored.

```
\renewcommand*{\nopagecolor}{}
```

\colorbox [⟨*model*⟩] {⟨*color*⟩} {⟨*text*⟩}

Converted into an HTML hex background color .

```
\NewDocumentCommand{\LWR@HTML@colorbox}{O{named} m +m}{%
\begingroup%
\LWR@hook@processingtags%
\InlineClass[%
background:\LWR@colorstyle{#1}{#2} ; %
padding:\LWR@printlength{\fboxsep}%
]{colorbox}{#3}%
\endgroup%
}

\AtBeginDocument{
    \LWR@formatted{colorbox}
}
```

\colorboxBlock [⟨*model*⟩] {⟨*color*⟩} {⟨*text*⟩}

Converted into an HTML hex background color .

```
\NewDocumentCommand{\LWR@HTML@colorboxBlock}{O{named} m +m}{%
\begingroup%
\LWR@hook@processingtags%


\LWR@stoppars%

\begin{BlockClass}[%
background:\LWR@colorstyle{#1}{#2} ; %
padding:\LWR@printlength{\fboxsep}%
]{colorboxBlock}
#3
\end{BlockClass}%
\endgroup%
```

Prevent paragraph tags around horizontal white space until the start of the next paragraph:

```
\global\booltrue{LWR@minipagethispar}%
}

\AtBeginDocument{
    \LWR@formatted{colorboxBlock}
}
```

\fcolorbox [⟨*frame model*⟩] {⟨*frame color*⟩} [⟨*box model*⟩] {⟨*box color*⟩} {⟨*text*⟩}

Converted into a framed HTML hex background color span.

A background color of none creates a colored frame without a background color.

```
\NewDocumentCommand{\LWR@HTML@fcolorbox}{O{named} m O{#1} m +m}{%
\LWR@traceinfo{HTML fcolorbox #2 #4}%
\begingroup%
\LWR@hook@processingtags%
\LWR@forceminwidth{\fboxrule}%
\ifthenelse{\equal{#4}{none}}%
    {% no background color
        \InlineClass[%
        \LWR@borderpadding{#1}{#2}%
        ]{fcolorbox}{#5}%
    }%
    {% yes background color
        \InlineClass[%
        \LWR@borderpadding{#1}{#2} ; %
        background:\LWR@colorstyle{#3}{#4}%
        ]{fcolorbox}{#5}%
    }%
\endgroup%
}

\AtBeginDocument{
    \LWR@formatted{fcolorbox}
}
```

\fcolorboxBlock [⟨*frame model*⟩] {⟨*frame color*⟩} [⟨*box model*⟩] {⟨*box color*⟩} {⟨*text*⟩}

Converted into a framed HTML hex background color span.

A background color of none creates a colored frame without a background color.

```
\NewDocumentCommand{\LWR@HTML@fcolorboxBlock}{O{named} m O{#1} m +m}{%
\LWR@traceinfo{HTML fcolorboxBlock #2 #4}%
\begingroup%
\LWR@hook@processingtags%
\LWR@forceminwidth{\fboxrule}%

\LWR@stoppars%

\ifthenelse{\equal{#4}{none}}%
    {% no background color
        \begin{BlockClass}[%
            \LWR@borderpadding{#1}{#2}%
        ]{fcolorboxBlock}
        #5
        \end{BlockClass}%
    }%
    {% yes background color
        \convertcolorspec{#3}{#4}{HTML}\LWR@tempcolortwo%
```

```
        \begin{BlockClass}[%
            background:\LWR@origpound\LWR@tempcolortwo\ ; %
            \LWR@borderpadding{#1}{#2}%
        ]{fcolorboxBlock}
        #5
        \end{BlockClass}%
    }%
\endgroup%
```

Prevent paragraph tags around horizontal white space until the start of the next paragraph:

```
\global\booltrue{LWR@minipagethispar}%
\LWR@traceinfo{HTML fcolorboxBlock done}%
}

\AtBeginDocument{
    \LWR@formatted{fcolorboxBlock}
}
```

Creates a framed HTML  around its contents.

A print-output version is defined in the lwarp core: section 88

\LWR@subfcolorminipage {⟨*framemodel*⟩} {⟨*framecolor*⟩} {⟨*background tag*⟩} {⟨*height*⟩}

```
\NewDocumentCommand{\LWR@subfcolorminipage}{m m m m}{%

\LWR@stoppars%

\begin{BlockClass}[%
#3%
\LWR@borderpadding{#1}{#2} ; %
\IfValueT{#4}{height:\LWR@printlength{\LWR@tempheight} ; }%
width:\LWR@printlength{\LWR@tempwidth}%
]{fcolorminipage}%
}
```

Env fcolorminipage [⟨*1:framemodel*⟩] {⟨*2:framecolor*⟩} [⟨*3:boxmodel*⟩] {⟨*4:boxcolor*⟩} [⟨*5:align*⟩] [⟨*6:height*⟩] [⟨*7:inner-align*⟩] {⟨*8:width*⟩}

```
\NewDocumentEnvironment{LWR@HTML@fcolorminipage}{O{named} m O{#1} m O{c} o o m}
{%
\LWR@hook@processingtags%
\setlength{\LWR@tempwidth}{#8}%
\IfValueT{#6}{\setlength{\LWR@tempheight}{#6}}%
\LWR@forceminwidth{\fboxrule}%
\convertcolorspec{#1}{#2}{HTML}\LWR@tempcolor%
\ifthenelse{\equal{#4}{none}}%
    {\LWR@subfcolorminipage{#1}{#2}{}{#6}}%
    {%
        \convertcolorspec{#3}{#4}{HTML}\LWR@tempcolortwo%
        \LWR@subfcolorminipage{#1}{#2}%
            {background:\LWR@origpound\LWR@tempcolortwo\ ; }%
```

```
            {#6}%
    }%
}%
{%
    \end{BlockClass}%
```

Prevent paragraph tags around horizontal white space until the start of the next paragraph:

```
    \global\booltrue{LWR@minipagethispar}%
}

\AtBeginDocument{
\LWR@formattedenv{fcolorminipage}
}
```

\boxframe {⟨*width*⟩} {⟨*height*⟩} {⟨*depth*⟩}

The depth is added to the height, but the box is not decended below by the depth. `\textcolor` is honored.

```
\newcommand*{\LWR@HTML@boxframe}[3]{%
{%
\setlength{\LWR@tempwidth}{#1}%
\setlength{\LWR@tempheight}{#2}%
\addtolength{\LWR@tempheight}{#3}%
\LWR@forceminwidth{\fboxrule}%
\LWR@findcurrenttextcolor%
\InlineClass[%
display:inline-block ; %
border:\LWR@printlength{\LWR@atleastonept} solid \LWR@currenttextcolor{} ; %
width:\LWR@printlength{\LWR@tempwidth} ; %
height:\LWR@printlength{\LWR@tempheight}%
]{boxframe}{}%
}%
}

\LWR@formatted{boxframe}
```

## § 650.9 Row colors

\rowc@l@rs [⟨*cmds*⟩] {⟨*startrow*⟩} {⟨*odd color*⟩} {⟨*even color*⟩}

```
\newcommand*{\LWR@xcolortempcolor}{}

\def\rowc@l@rs[#1]#2#3#4%
{
\rownum=1%
   \@rowcolorstrue%
   \@ifxempty{#3}%
     {\def\@oddrowcolor{\@norowcolor}}%
     {%
        \convertcolorspec{named}{#3}{HTML}\LWR@xcolortempcolor%
        \edef\@oddrowcolor{%
```

```
            \csdef{LWR@xcolorrowHTMLcolor}{\LWR@xcolortempcolor}%
        }%
    }%
  \@ifxempty{#4}%
    {\def\@evenrowcolor{\@norowcolor}}%
    {%
        \convertcolorspec{named}{#4}{HTML}\LWR@xcolortempcolor%
        \edef\@evenrowcolor{%
            \csdef{LWR@xcolorrowHTMLcolor}{\LWR@xcolortempcolor}%
        }%
    }%
  \if@rowcmd
    \def\@rowcolors
    {%
%         #1%
        \if@rowcolors
%         \noalign{%
            \relax\ifnum\rownum<#2\@norowcolor\else
            \ifodd\rownum\@oddrowcolor\else\@evenrowcolor\fi\fi%
%          }%
        \fi%
    }%
  \else
    \def\@rowcolors
    {%
        \if@rowcolors
            \ifnum\rownum<#2%
%            \noalign{%
                \@norowcolor
%             }
            \else
%            #1%
%            \noalign{%
                \ifodd\rownum\@oddrowcolor\else\@evenrowcolor\fi%
%             }%
            \fi
        \fi%
    }%
  \fi
  \ignorespaces%
}
```

\@norowcolor Turns off color for this row.

```
\def\@norowcolor{%
\renewcommand{\LWR@xcolorrowHTMLcolor}{}%
}
```

\@rowc@lors Executed at the end of each row.

```
\def\@rowc@lors{%
%   \noalign{%
        \advance\rownum\@ne%
%   }%
    \@rowcolors%
```

```
271 }
```

File 544 **lwarp-xechangebar.sty**

## § 651 Package xechangebar

Pkg xechangebar xechangebar is ignored

**for HTML output:**

```
1 \LWR@ProvidesPackageDrop{xechangebar}[2017/08/03]
2 \LWR@origRequirePackage{lwarp-changebar}
```

File 545 **lwarp-xellipsis.sty**

## § 652 Package xellipsis

(*Emulates or patches code by* Donald P. Goodman III.)

Pkg xellipsis xellipsis is patched for use by lwarp.

When non-zero, each of the spaces is converted to an HTML thin unbreakable space.

**for HTML output:**

```
1 \LWR@ProvidesPackagePass{xellipsis}[2015/11/01]

2 \newcommand*{\LWR@xellipsespace}[1]{%
3 \ifdim#1=0pt\else%
4     \ifdim#1<\fontdimen2\font%
5         \,%
6     \else%
7         ~%
8     \fi%
9 \fi%
10 }
11
12 \def\xelip{%
13 \mbox{%
14     \LWR@xellipsespace{\xelipprebef}%
15     \xelipprechar%
16     \LWR@xellipsespace{\xelippreaft}%
17     \LWR@xellipsespace{\xelipbef}%
18     \xelipchar%
19     \xel@loopi = 1%
20     \loop\ifnum\xelipnum>\xel@loopi%
21         \advance\xel@loopi by1%
22         \LWR@xellipsespace{\xelipgap}%
23         \xelipchar%
24     \repeat%
25     \LWR@xellipsespace{\xelipaft}%
26     \LWR@xellipsespace{\xelippostbef}%
27     \xelippostchar%
28     \LWR@xellipsespace{\xelippostaft}%
29 }%
```

```
}%
```

File 546 **lwarp-xetexko-vertical.sty**

## § 653 Package xetexko-vertical

(*Emulates or patches code by* Dohyun Kim.)

Pkg xetexko-vertical xetexko-vertical is patched for use by lwarp.

**for HTML output:**

```
\LWR@loadbefore{xetexko-vertical}

\LWR@ProvidesPackagePass{xetexko-vertical}[2018/04/06]

\renewcommand{\verticaltypesetting}{}
\renewenvironment{vertical}[1]{\BlockClass{verticalrl}}{\endBlockClass}
\renewenvironment{horizontal}[1]{\BlockClass{horizontaltb}}{\endBlockClass}
\renewcommand{\vertlatin}[1]{#1}
```

File 547 **lwarp-xevlna.sty**

## § 654 Package xevlna

(*Emulates or patches code by* Zdeněk Wagner.)

Pkg xevlna xevlna is patched for use by lwarp.

Non-breakable spaces are inserted into HTML.

**for HTML output:**

```
\LWR@ProvidesPackagePass{xevlna}[2016/09/05]

\def\ProcessCSpreposition{\ifx\next\xevlnaXeTeXspace\HTMLentity{nbsp}\fi}

\appto{\LWR@hook@processingtags}{\xevlnaDisable}%
```

File 548 **lwarp-xfakebold.sty**

## § 655 Package xfakebold

(*Emulates or patches code by* Herbert Voss.)

Pkg xfakebold xfakebold is patched for use by lwarp, and additional underlying support is found in the lwarp core.

⚠ text mode xfakebold is only used in SVG math and `lateximages`. Text mode is not set bold, but `\setBold` in text will be applied to any following SVG math.

**for HTML output:**

```
\LWR@ProvidesPackagePass{xfakebold}[2020/06/24]
```

```
\newcommand*{\LWR@HTML@setBold}{\booltrue{LWR@xfakebold}}
\LWR@formatted{setBold}

\newcommand*{\LWR@HTML@unsetBold}{\boolfalse{LWR@xfakebold}}
\LWR@formatted{unsetBold}

\renewcommand*{\LWR@applyxfakebold}{%
    \ifbool{LWR@xfakebold}{\LWR@print@setBold}{\LWR@print@unsetBold}%
}
```

For MathJax, xfakebold is ignored.

```
\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\setBold}[1][]{}}
\CustomizeMathJax{\newcommand{\unsetBold}{}}
\end{warpMathJax}
```

---

File 549 **lwarp-xfrac.sty**

§ 656 Package

# xfrac

(*Emulates or patches code by* The LaTeX3 Project.)

Pkg xfrac Supported by adding xfrac instances, and emulated for MathJax.

**for HTML output:**

```
\LWR@ProvidesPackagePass{xfrac}[2018-08-23]
```

⚠ font size In the user's document preamble, lwarp should be loaded after font-related setup. During HTML conversion, this font is used by lwarp to generate its initial PDF output containing HTML tags, later to be converted by *pdftotext* to a plain text file. While the text may be in any font which *pdftotext* can read, the math is directly converted into SVG images using this same user-selected font. `xfrac` below is set for the Latin Modern (lmr) font. If another font is used, it may be desirable to redefine `\xfracHTMLfontsize` with a different em size.

`\sfrac` `[`⟨*instance*⟩`]` `{`⟨*num*⟩`}` `[`⟨*sep*⟩`]` `{`⟨*denom*⟩`}`

A text-mode instance for the default font is provided below. The numerator and denominator formats are adjusted to encase everything in HTML tags. `\scalebox` is made null inside the numerator and denominator, since the HTML tags should not be scaled, and we do not want to introduce additional HTML tags for scaling.

In math mode, which will appear inside a `latexmage`, no adjustments are necessary.

`\xfracHTMLfontsize` User-redefinable macro which controls the font size of the fraction.

```
\newcommand*{\xfracHTMLfontsize}{.6em}
```

instances Instances of xfrac for various font choices:

Produce CSS for a small raised numerator and a small denominator.

Scaling is turned off so that *pdftotext* correctly reads the result.

```
\DeclareInstance{xfrac}{default}{text}{
    numerator-format = {%
        \begingroup%
        \RenewDocumentCommand{\scalebox}{m o m}{##3}%
        \InlineClass{numerator}{#1}\,%
        \endgroup%
    },
    denominator-format = {%
        \begingroup%
        \RenewDocumentCommand{\scalebox}{m o m}{##3}%
        \InlineClass{denominator}{#1}%
        \endgroup%
    },
```

For *pdftotext*, do not scale the text:

```
    scaling = false
}

\DeclareInstance{xfrac}{lmr}{text}{
    numerator-format = {%
        \begingroup%
        \RenewDocumentCommand{\scalebox}{m o m}{##3}%
        \InlineClass{numerator}{#1}\,%
        \endgroup%
    },
    denominator-format = {%
        \begingroup%
        \RenewDocumentCommand{\scalebox}{m o m}{##3}%
        \InlineClass{denominator}{#1}%
        \endgroup%
    },
```

For *pdftotext*, do not scale the text:

```
    scaling = false
}

\DeclareInstance{xfrac}{lmss}{text}{
    numerator-format = {%
        \begingroup%
        \RenewDocumentCommand{\scalebox}{m o m}{##3}%
        \InlineClass{numerator}{#1}\,%
        \endgroup%
    },
    denominator-format = {%
        \begingroup%
        \RenewDocumentCommand{\scalebox}{m o m}{##3}%
        \InlineClass{denominator}{#1}%
        \endgroup%
    },
```

For *pdftotext*, do not scale the text:

```
    scaling = false
}

\DeclareInstance{xfrac}{lmtt}{text}{
    numerator-format = {%
        \begingroup%
        \RenewDocumentCommand{\scalebox}{m o m}{##3}%
        \InlineClass{numerator}{#1}\,%
        \endgroup%
    },
    denominator-format = {%
        \begingroup%
        \RenewDocumentCommand{\scalebox}{m o m}{##3}%
        \InlineClass{denominator}{#1}%
        \endgroup%
    },
```

For *pdftotext*, do not scale the text:

```
    scaling = false
}
```

For MathJax:

```
\begin{warpMathJax}
\CustomizeMathJax{\newcommand{\LWRsfrac}[2][/]{{}^\LWRsfracnumerator\!#1{}_{#2}}}
\CustomizeMathJax{\newcommand{\sfrac}[2][]{\def\LWRsfracnumerator{#2}\LWRsfrac}}
\end{warpMathJax}
```

---

File 550 **lwarp-xltabular.sty**

§ 657 Package

# xltabular

(*Emulates or patches code by* Rolf Niepraschk, Herbert Voss.)

Pkg xltabular xltabular is emulated by lwarp.

**for HTML output:** Relies on tabularx.

⚠ table numbering At present, an `xltabular` without a caption or with only a `\caption*` may be misnumbered in HTML, so it may be necessary to place at the end of the table:

```
\warpHTMLonly{\addtocounter{table}{-1}}
```

```
\RequirePackage{tabularx}
\RequirePackage{ltablex}

\LWR@ProvidesPackageDrop{xltabular}[2018/05/23]

\DeclareDocumentEnvironment{xltabular}{o m m}
{\longtable{#3}}
{\endlongtable}
```

File 551 **lwarp-xltxtra.sty**

## § 658 Package xltxtra

(*Emulates or patches code by* Will Robertson, Jonathan Kew.)

Pkg xltxtra xltxtra is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{xltxtra}[2016/01/21]

\RequirePackage{realscripts}
\RequirePackage{metalogo}
\newcommand*\TeX@logo@spacing[6]{}

\newcommand*{\vfrac}[2]{%
\textsuperscript{#1}/\textsubscript{#2}%
}

\newcommand\namedglyph[1]{%
  \@tempcnta=\XeTeXglyphindex "#1"\relax
  \ifnum\@tempcnta>0
    \XeTeXglyph\@tempcnta
  \else
    \xxt@namedglyph@fallback{#1}%
  \fi}

\newcommand\xxt@namedglyph@fallback[1]{[#1]}

\DeclareDocumentCommand{\showhyphens}{m}{}
```

File 552 **lwarp-xmpincl.sty**

## § 659 Package xmpincl

(*Emulates or patches code by* Maarten Sneep.)

Pkg xmpincl xmpincl is ignored.

**for HTML output:** Discard all options for lwarp-xmpincl:

```
\LWR@ProvidesPackageDrop{xmpincl}[2008/05/10]

\newcommand*{\includexmp}[1]{}
```

File 553 **lwarp-xpiano.sty**

```
    \clist_if_exist:cTF { c__xpinyin_multiple_ #1 _clist }
        { \l__xpinyin_multiple_tl \l__xpinyin_format_tl }
        { \l__xpinyin_format_tl }
    \ifdefempty{\l__xpinyin_format_tl}
        {#3}
        {\LWR@textcurrentcolor{#3}}
    \color_group_end:
}
\LWR@formatted{__xpinyin_make_pinyin_box:nnn}

\cs_new_protected_nopar:Npn \LWR@HTML@__xpinyin_CJKsymbol:nn #1#2
  {
    \__xpinyin_leavevmode:
    \LWR@htmltagc{ruby}
    \LWR@htmltagc{rb}
    \__xpinyin_save_CJKsymbol:n {#2}\null% \null removes extra space
    \LWR@htmltagc{/rb\space}
    \LWR@htmltagc{rp}(\LWR@htmltagc{/rp\space}
    \LWR@htmltagc{rt}
    \__xpinyin_make_pinyin_box:nnn {#1} {#2} { \use:c { c__xpinyin_ #1 _tl } }
    \LWR@htmltagc{/rt\space}
    \LWR@htmltagc{rp})\LWR@htmltagc{/rp\space}
    \LWR@htmltagc{/ruby\space}\null
  }
\LWR@formatted{__xpinyin_CJKsymbol:nn}

\cs_new_protected_nopar:Npn \LWR@HTML@__xpinyin_single_CJKsymbol:nn #1#2
  {
    \__xpinyin_leavevmode:
    \LWR@htmltagc{ruby}
    \LWR@htmltagc{rb}
    \__xpinyin_save_CJKsymbol:n {#1}\null% \null removes extra space
    \LWR@htmltagc{/rb\space}
    \LWR@htmltagc{rp}(\LWR@htmltagc{/rp\space}
    \LWR@htmltagc{rt}
    \__xpinyin_make_pinyin_box:xnn
      { \__xpinyin_to_unicode:n {#1} } {#1} { \__xpinyin_pinyin:n {#2} }
    \LWR@htmltagc{/rt\space}
    \LWR@htmltagc{rp})\LWR@htmltagc{/rp\space}
    \LWR@htmltagc{/ruby\space}\null
  }
\LWR@formatted{__xpinyin_single_CJKsymbol:nn}

\ExplSyntaxOff
```

The lwarp core uses the following to disable CJK xpinyin for filenames, sideTOC, and footnotes.

```
\renewcommand*{\LWR@disablepinyin}{\disablepinyin}

\FilenameNullify{\LWR@disablepinyin}
```

File 555 **lwarp-xr.sty**

## § 662 Package xr

(*Emulates or patches code by* Jean-Pierre Drucbert, David Carlisle.)

Pkg xr

xr is patched for use by lwarp. The `*_html.aux` file is used. `\externaldocument` is modified to also accept the optional arguments for xr-hyper, which currently uses xr for HTML output.

See section 5.17.

**for HTML output:**

```
\LWR@ProvidesPackagePass{xr}[2019/07/22]%

\LetLtxMacro\LWR@orig@externaldocument\externaldocument

\RenewDocumentCommand{\externaldocument}{O{} O{} m O{}}{%
    \ifblank{#1}{%
        \LWR@orig@externaldocument{#3_html}%
    }{%
        \LWR@orig@externaldocument[#1]{#3_html}%
    }%
}
```

---

File 556 **lwarp-xr-hyper.sty**

## § 663 Package xr-hyper

(*Emulates or patches code by* David Carlisle.)

Pkg xr-hyper

xr-hyper is replaced by xr, which is modified to accept the optional arguments for `\externaldocument`. So far, no hyperlinks are provided for citations.

See section 5.17.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{xr-hyper}[2019/10/03]%

\LWR@origRequirePackage{lwarp-xr}
```

---

File 557 **lwarp-xtab.sty**

## § 664 Package xtab

(*Emulates or patches code by* Peter Wilson.)

Pkg xtab

xtab is emulated.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{xtab}[2011/07/31]
```

⚠ Misplaced alignment tab character &

For `\tablefirsthead`, etc., enclose them as follows:

```
\StartDefiningTabulars
\tablefirsthead
. . .
\StopDefiningTabulars
```

See section 8.10.1.

⚠ lateximage supertabular and xtab are not supported inside a `lateximage`.

```
\newcommand{\LWRXT@firsthead}{}

\newcommand{\tablefirsthead}[1]{%
    \long\gdef\LWRXT@firsthead{#1}%
}

\newcommand{\tablehead}[1]{}

\newcommand{\tablelasthead}[1]{}

\newcommand{\notablelasthead}{}

\newcommand{\tabletail}[1]{}

\newcommand{\LWRXT@lasttail}{}

\newcommand{\tablelasttail}[1]{%
    \long\gdef\LWRXT@lasttail{#1}%
}


\newcommand{\tablecaption}[2][]{%
    \long\gdef\LWRXT@caption{%
        \ifblank{#1}%
            {\caption{#2}}%
            {\caption[#1]{#2}}%
    }%
}

\let\topcaption\tablecaption
\let\bottomcaption\tablecaption


\newcommand*{\LWRXT@caption}{}

\newcommand*{\shrinkheight}[1]{}

\newcommand*{\xentrystretch}[1]{}

\NewDocumentEnvironment{xtabular}{s o m}
{%
\LWR@traceinfo{xtabular}%
\table%
\LWRXT@caption%
\begin{tabular}{#3}%
\TabularMacro\ifdefvoid{\LWRXT@firsthead}%
{\LWR@getmynexttoken}%
{\expandafter\LWR@getmynexttoken\LWRXT@firsthead}%
```

```
}%
{%
\ifdefvoid{\LWRXT@lasttail}%
{}%
{%
\TabularMacro\ResumeTabular%
\LWRXT@lasttail%
}%
\end{tabular}%
\endtable%

\gdef\LWRXT@caption{}%

\LWR@traceinfo{xtabular done}%
}

\NewDocumentEnvironment{mpxtabular}{s o m}
{\minipage{\linewidth}\xtabular{#3}}
{\endxtabular\endminipage}
```

File 558 **lwarp-xunicode.sty**

§ 665 Package

# xunicode

Pkg xunicode

Error if xunicode is loaded after lwarp.

Patch lwarp-xunicode, but also verify that is was loaded before lwarp:

**for HTML output:**

```
\LWR@loadbefore{xunicode}%

\LWR@ProvidesPackagePass{xunicode}[2011/09/09]
```

\textcircled becomes a span with a rounded border. \providecommand is used to avoid conflict with textcomp.

```
\providecommand*{\LWR@HTML@textcircled}[1]{%
    \InlineClass[border: 1px solid \LWR@currenttextcolor]{textcircled}{#1}%
}

\LWR@formatted{textcircled}
```

Nullify xunicode macros when generating filenames:

```
\FilenameNullify{%
    \renewcommand*{\textdegree}{}%
    \renewcommand*{\textcelsius}{}%
    \renewcommand*{\textohm}{}%
    \renewcommand*{\textmu}{}%
    \renewcommand*{\textlquill}{}%
    \renewcommand*{\textrquill}{}%
    \renewcommand*{\textcircledP}{}%
    \renewcommand*{\texttwelveudash}{}%
```

```
    \renewcommand*{\textthreequartersemdash}{}%
    \renewcommand*{\textmho}{}%
    \renewcommand*{\textnaira}{}%
    \renewcommand*{\textpeso}{}%
    \renewcommand*{\textrecipe}{}%
    \renewcommand*{\textinterrobang}{}%
    \renewcommand*{\textinterrobangdown}{}%
    \renewcommand*{\textperthousand}{}%
    \renewcommand*{\textpertenthousand}{}%
    \renewcommand*{\textbaht}{}%
    \renewcommand*{\textdiscount}{}%
    \renewcommand*{\textservicemark}{}%
    \renewcommand*{\textcircled}[1]{#1}%
    \renewcommand*{\capitalcedilla}[1]{#1}%
    \renewcommand*{\capitalogonek}[1]{#1}%
    \renewcommand*{\capitalgrave}[1]{#1}%
    \renewcommand*{\capitalacute}[1]{#1}%
    \renewcommand*{\capitalcircumflex}[1]{#1}%
    \renewcommand*{\capitaltilde}[1]{#1}%
    \renewcommand*{\capitaldieresis}[1]{#1}%
    \renewcommand*{\capitalhungarumlaut}[1]{#1}%
    \renewcommand*{\capitalring}[1]{#1}%
    \renewcommand*{\capitalcaron}[1]{#1}%
    \renewcommand*{\capitalbreve}[1]{#1}%
    \renewcommand*{\capitalmacron}[1]{#1}%
    \renewcommand*{\capitaldotaccent}[1]{#1}%
}% FilenameNullify
```

File 559 **lwarp-xurl.sty**

## § 666 Package xurl

Pkg xurl xurl is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{xurl}[2020/01/14]

\def\useOriginalUrlSetting{}
```

File 560 **lwarp-xy.sty**

## § 667 Package xy

(*Emulates or patches code by* Kristoffer H. Rose, Ross Moore.)

Pkg xy xy is patched for use by lwarp.

**for HTML output:**

```
\LWR@ProvidesPackagePass{xy}[2013/10/06]
```

After xy modules have been loaded:

```
\AtBeginDocument{
```

The original definitions without a lateximage:

```
\LetLtxMacro\LWR@orig@xy\xy
\LetLtxMacro\LWR@orig@endxy\endxy
```

The outer-most xy environment is placed in a lateximage, but not more than one level deep, which would conflict with xy:

```
\renewcommand*{\xy}{%
    \ifnumcomp{\value{LWR@lateximagedepth}}{>}{0}%
        {\addtocounter{LWR@lateximagedepth}{1}}%
        {\begin{lateximage}[-xy-~\PackageDiagramAltText]}%
    \LWR@orig@xy%
}

\renewcommand*{\endxy}{%
    \LWR@orig@endxy%
    \ifnumcomp{\value{LWR@lateximagedepth}}{>}{1}%
        {\addtocounter{LWR@lateximagedepth}{-1}}%
        {\end{lateximage}}%
}
```

The \xybox must use the original definitions of \xy, \endxy:

```
\def\xybox#1{%
    \LWR@orig@xy#1\LWR@orig@endxy%
    \Edge@c={\rectangleEdge}\computeLeftUpness@%
}
```

If \xygraph is used, it is placed inside a lateximage:

```
\@ifundefined{xygraph}{}{

\LetLtxMacro\LWR@origxygraph\xygraph

\renewcommand{\xygraph}[1]{%
    \begin{lateximage}[-xy- xygraph \PackageDiagramAltText]
    \LWR@origxygraph{#1}
    \end{lateximage}
}

}% xygraph defined

}% AtBeginDocument
```

---

File 561 **lwarp-zhlineskip.sty**

§ 668 Package

# zhlineskip

Pkg zhlineskip zhlineskip is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{zhlineskip}[2019/05/15]
```

```
\newcommand*\SetTextEnvironmentSinglespace[1]{}
\newcommand*\RestoreTextEnvironmentLeading[1]{}
\newcommand*\SetMathEnvironmentSinglespace[1]{}
\newcommand*\RestoreMathEnvironmentLeading[1]{}
```

File 562 **lwarp-zwpagelayout.sty**

§ 669 Package

# zwpagelayout

(*Emulates or patches code by* Zdeněk Wagner.)

Pkg zwpagelayout zwpagelayout is ignored.

**for HTML output:**

```
\LWR@ProvidesPackageDrop{zwpagelayout}[2013/01/13]

\def\noBboxes{}
\@onlypreamble\noBboxes

\expandafter\ifx\csname definecolor\endcsname\relax \else
  \definecolor{cmykblack}{cmyk}{0,0,0,1}
  \definecolor{grblack}{gray}{0}
%   \ifzwpl@redefineblack
%     \definecolor{black}{cmyk}{0,0,0,1}\color{black}
%   \fi
  \definecolor{cmykred}{cmyk}{0,1,1,0}
  \definecolor{cmykgreen}{cmyk}{1,0,1,0}
  \definecolor{cmykblue}{cmyk}{1,1,0,0}
  \definecolor{rgbred}{rgb}{1,0,0}
  \definecolor{rgbgreen}{rgb}{0,1,0}
  \definecolor{rgbblue}{rgb}{0,0,1}
%   \ifzwpl@redefinetocmyk
%     \definecolor{red}{cmyk}{0,1,1,0}
%     \definecolor{green}{cmyk}{1,0,1,0}
%     \definecolor{blue}{cmyk}{1,1,0,0}
%   \fi
\fi

\let\OverprintXeTeXExtGState\relax

\DeclareRobustCommand\SetOverprint{\ignorespaces}
\DeclareRobustCommand\SetKnockout{\ignorespaces}
\DeclareRobustCommand\textoverprint[1]{{\SetOverprint#1}}
\DeclareRobustCommand\textknockout[1]{{\SetKnockout#1}}

\def\SetPDFminorversion#1{}
\@onlypreamble\SetPDFminorversion

\newcommand*\Vcorr{}

\DeclareRobustCommand\vb[1][]{}
\NewDocumentCommand{\NewOddPage}{* o}{}
\NewDocumentCommand{\NewEvenPage}{* o}{}
\def\SetOddPageMessage#{\gdef\ZW@oddwarning}
```

```
\def\SetEvenPageMessage#{\gdef\Z@@evenwarning}
\def\ZW@oddwarning{Empty page inserted}\let\ZW@evenwarning\ZW@oddwarning

\def\clap#1{#1}

\def\CropFlap{2in}
\def\CropSpine{1in}
\def\CropXSpine{1in}
\def\CropXtrim{.25in}
\def\CropYtrim{.25in}
\def\UserWidth{5in}
\def\UserLeftMargin{1in}
\def\UserRightMargin{1in}
\def\UserTopMargin{1in}
\def\UserBotMargin{1in}
\def\thePageNumber{\LWR@origpound\,\arabic{page}}
\ifXeTeX
\def\ifcaseZWdriver{\ifcase2}
\else
\def\ifcaseZWdriver{\ifcase1}
\fi
\DeclareRobustCommand\ZWifdriver[2]{}
```

File 563 **lwarp-patch-komascript.sty**

§ 670 Package

# patch-komascript

Pkg lwarp-patch-komascript

Patches for komascript classes.

lwarp loads this package when scrbook, scrartcl, or scrreprt classes are detected.

Many features are ignored during the HTML conversion. The goal is source-level compatibility.

\captionformat, \figureformat, and \tableformat are not yet emulated.

⚠ Not fully tested! Please send bug reports!

Some features have not yet been tested. Please contact the author with any bug reports.

**for HTML output:**

```
\ProvidesPackage{lwarp-patch-komascript}
```

typearea is emulated.

```
\RequirePackage{lwarp-typearea}
```

tocbasic is emulated.

```
\RequirePackage{lwarp-tocbasic}
```

scrextend patches most of the new macros.

```
\RequirePackage{lwarp-scrextend}
```

Indexing macros, simplified for lwarp:

```
\AtBeginDocument{

\renewcommand*{\idx@heading}{%
  \idx@@heading{\indexname}%
}

\renewenvironment{theindex}{%
  \idx@heading%
  \index@preamble\par\nobreak
    \let\item\LWR@indexitem%
    \let\subitem\LWR@indexsubitem%
    \let\subsubitem\LWR@indexsubsubitem%
}
{}

\renewcommand*\indexspace{}

}% AtBeginDocument
```

The \minisec is placed inside a  of class minisec.

```
\renewcommand*{\minisec}[1]{
    \begin{BlockClass}{minisec}
    #1
    \end{BlockClass}
}
```

The part and chapter preambles are placed as plain text just after each heading.

```
\@ifundefined{setpartpreamble}{}{
\RenewDocumentCommand{\setpartpreamble}{o o +m}{%
    \renewcommand{\part@preamble}{#3}%
}
}

\@ifundefined{setchapterpreamble}{}{
\RenewDocumentCommand{\setchapterpreamble}{o o +m}{%
    \renewcommand{\chapter@preamble}{#3}%
}
}
```

Do not use \chaptername:

```
\renewcommand*{\LWR@printchaptername}{}
```

Simple captions are used in all cases.

```
\AtBeginDocument{
\AtBeginDocument{
    \LetLtxMacro\captionbelow\caption
    \LetLtxMacro\captionabove\caption

    \LetLtxMacro\captionofbelow\captionof
```

```
    \LetLtxMacro\captionofabove\captionof
}
}

\RenewDocumentEnvironment{captionbeside}{o m o o o s}
{}
{%
    \IfValueTF{#1}%
        {\caption[#1]{#2}}%
        {\caption{#2}}%
}

\RenewDocumentEnvironment{captionofbeside}{m o m o o o s}
{}
{%
    \IfValueTF{#2}%
        {\captionof{#1}[#2]{#3}}%
        {\captionof{#1}{#3}}%
}

\RenewDocumentCommand{\setcapindent}{s m}{}
\renewcommand*{\setcaphanging}{}
\renewcommand*{\setcapwidth}[2][]{}
\renewcommand*{\setcapdynwidth}[2][]{}
\RenewDocumentCommand{\setcapmargin}{s o m}{}
```

File 564 **lwarp-patch-memoir.sty**

§ 671 Package

# patch-memoir

(*Emulates or patches code by* Peter Wilson.)

Pkg lwarp-patch-memoir Patches for memoir class.

⚠ Not fully tested! Please send bug reports!

lwarp loads this package when the memoir class is detected.

⚠ captions lwarp uses caption, which causes a warning from memoir. This is normal. Adjust captions via caption, instead of memoir.

⚠ options clash While emulating memoir, lwarp pre-loads a number of packages (section 671.1). This can cause an options clash when the user's document later loads the same packages with options. To fix this problem, specify the options before loading lwarp:

```
\documentclass{memoir}
. . .
\PassOptionsToPackage{options_list}{package_name}
. . .
\usepackage{lwarp}
. . .
\usepackage{package_name}
```

⚠ version numbers memoir emulates a number of packages, and declares a version date for each which

often does not match the date of the corresponding freestanding package. This can cause warnings about incorrect version numbers. Since lwarp is intended to support the freestanding packages, which are often newer than the date declared by memoir, it is hoped that memoir will update and change its emulated version numbers to match.

`\label(bookmark){tag}` `\label` accepts an optional `(bookmark)` argument, but this is ignored in HTML.

⚠ `comment` The `comment` environment is from the comment package, and thus requires that the `\begin` and `\end` each be on its own line:

```
\begin{comment}
This is a comment.
\end{comment}
```

`\newcomment` Comments defined with `\newcomment` use memoir's defintions, and behave as expected, where the `\begin` and `\end` do have to each be on its own line.

⚠ verbatim footnotes `\verbfootnote` is not supported.

⚠ `\newfootnoteseries` `\newfootnoteseries`, etc. are not supported.

⚠ page notes lwarp loads pagenote to perform memoir's pagenote functions, but there are minor differences in `\pagenotesubhead` and related macros.

page notes with cleveref To add support for pagenotes with cleveref, add:

```
\crefname{pagenote}{page note}{page notes}
\Crefname{pagenote}{Page note}{Page notes}
```

page note `\nameref` Note that for print mode, `\nameref` print the section name where the page notes are declared in the text, but for HTML it prints the name where the page notes are printed.

⚠ poems Poem numbering is not supported.

⚠ `verbatim` The `verbatim` environment does not yet support the memoir enhancements. It is currently recommended to load and use fancyvrb instead.

⚠ glossaries The memoir glossary system is not yet supported by *lwarpmk*. The glossaries package may be used instead, but does require the glossary entries be changed from the memoir syntax to the glossaries syntax.

**for HTML output:**

```
\ProvidesPackage{lwarp-patch-memoir}
```

## § 671.1 Packages

These are pre-loaded to provide emulation for many of memoir's functions. memoir pretends that abstract, etc. are already loaded, via its "emulated" package mechanism, but lwarp is directly loading the "`lwarp-`" version of each, which happens to avoid memoir's emulation system.

```
\RequirePackage{lwarp-abstract}% req'd
% \RequirePackage{lwarp-array}% no longer req'd
\RequirePackage{lwarp-booktabs}% req'd
% \RequirePackage{lwarp-ccaption}% emulated below
\RequirePackage{lwarp-changepage}% req'd
\RequirePackage{lwarp-crop}
% \RequirePackage{lwarp-dcolumn}% no longer req'd
```

```
\RequirePackage{lwarp-enumerate}% req'd
\RequirePackage{lwarp-epigraph}% req'd
\RequirePackage{lwarp-fancyvrb}% req'd
\RequirePackage{lwarp-footmisc}% req'd

\let\framed\relax \let\endframed\relax
\let\shaded\relax \let\endshaded\relax
\let\leftbar\relax \let\endleftbar\relax
\let\snugshade\relax \let\endsnugshade\relax
\RequirePackage{lwarp-framed}% req'd

\RequirePackage{lwarp-hanging}% req'd
\RequirePackage{lwarp-makeidx}% req'd
\DisemulatePackage{moreverb}
\RequirePackage{lwarp-moreverb}
\RequirePackage{lwarp-mparhack}
\RequirePackage{lwarp-needspace}% req'd
\RequirePackage{lwarp-nextpage}% req'd
\RequirePackage{lwarp-pagenote}% req'd
\RequirePackage{lwarp-parskip}
\RequirePackage{lwarp-setspace}% req'd
\RequirePackage{lwarp-showidx}

\makeindex

% \RequirePackage{lwarp-tabularx}% no longer req'd
\RequirePackage{lwarp-titling}% req'd
% \RequirePackage{lwarp-tocbibind}% not emulated by memoir
\RequirePackage{lwarp-tocloft}% req'd
\RequirePackage{lwarp-verse}% req'd
```

## § 671.2 Label handling

Insert the lwarp label mechanism into the memoir package mechanism:

- `\@mem@old@label` is the LaTeX definition of `\label`.
- `\LWR@orig@label` adds the memoir definition.
- lwarp's `\LWR@new@label` uses `\LWR@orig@label`.
- Want memoir's `\label` to use lwarp's `\label`, which then would use LaTeX's `\label`.
- So:
  - `\@mem@old@label` becomes `\LWR@new@label`.
  - `\LWR@orig@label` becomes `\@mem@old@label`.
- cleveref then encapsulates all the above.
- For a subcaption, cleveref modifies memoir's `\sf@memsub@label`.

```
\let\LWR@orig@label\@mem@old@label
\let\@mem@old@label\LWR@new@label
```

Patches for subfloats to support additional lwarp labels:

```
\AtBeginDocument{
    \renewcommand*{\sf@@memsub@label}[1]{%
        \@bsphack
        \sf@@memsub@label@hook{#1}%
        \@memoldlabel{#1}%
        \LWR@label@createtag{sub@#1}%
        \protected@write\@auxout{}{%
            \string\newlabel{sub@#1}%
            {{\@nameuse{@@thesub\@captype}}%
            {\thepage}}}%
        \LWR@write@lwarplabel{sub@#1}%
        \@esphack
    }
}
```

## § 671.3 Page layout

memoir already set the page size to a default, so it must be forced large for lwarp's use, to avoid tag overflows off the page.

```
\setstocksize{190in}{20in}
\setlrmarginsandblock{2in}{2in}{*}
\setulmarginsandblock{1in}{1in}{*}


\renewcommand*{\stockavi}{}
\renewcommand*{\stockav}{}
\renewcommand*{\stockaiv}{}
\renewcommand*{\stockaiii}{}
\renewcommand*{\stockavii}{}
\renewcommand*{\stockbvi}{}
\renewcommand*{\stockbv}{}
\renewcommand*{\stockbiv}{}
\renewcommand*{\stockbiii}{}
\renewcommand*{\stockbvii}{}
% \renewcommand*{\stockmetriccrownvo}{}% in docs but not in the package
\renewcommand*{\stockmlargecrownvo}{}
\renewcommand*{\stockmdemyvo}{}
\renewcommand*{\stockmsmallroyalvo}{}
\renewcommand*{\pageavi}{}
\renewcommand*{\pageavii}{}
\renewcommand*{\pageav}{}
\renewcommand*{\pageaiv}{}
\renewcommand*{\pageaiii}{}
\renewcommand*{\pagebvi}{}
\renewcommand*{\pagebvii}{}
\renewcommand*{\pagebv}{}
\renewcommand*{\pagebiv}{}
\renewcommand*{\pagebiii}{}
% \renewcommand*{\pagemetriccrownvo}{}% in docs but not in the package
\renewcommand*{\pagemlargecrownvo}{}
\renewcommand*{\pagemdemyvo}{}
\renewcommand*{\pagemsmallroyalvo}{}

```

```
\renewcommand*{\stockdbill}{}
\renewcommand*{\stockstatement}{}
\renewcommand*{\stockexecutive}{}
\renewcommand*{\stockletter}{}
\renewcommand*{\stockold}{}
\renewcommand*{\stocklegal}{}
\renewcommand*{\stockledger}{}
\renewcommand*{\stockbroadsheet}{}
\renewcommand*{\pagedbill}{}
\renewcommand*{\pagestatement}{}
\renewcommand*{\pageexecutive}{}
\renewcommand*{\pageletter}{}
\renewcommand*{\pageold}{}
\renewcommand*{\pagelegal}{}
\renewcommand*{\pageledger}{}
\renewcommand*{\pagebroadsheet}{}

\renewcommand*{\stockpottvo}{}
\renewcommand*{\stockfoolscapvo}{}
\renewcommand*{\stockcrownvo}{}
\renewcommand*{\stockpostvo}{}
\renewcommand*{\stocklargecrownvo}{}
\renewcommand*{\stocklargepostvo}{}
\renewcommand*{\stocksmalldemyvo}{}
\renewcommand*{\stockdemyvo}{}
\renewcommand*{\stockmediumvo}{}
\renewcommand*{\stocksmallroyalvo}{}
\renewcommand*{\stockroyalvo}{}
\renewcommand*{\stocksuperroyalvo}{}
\renewcommand*{\stockimperialvo}{}
\renewcommand*{\pagepottvo}{}
\renewcommand*{\pagefoolscapvo}{}
\renewcommand*{\pagecrownvo}{}
\renewcommand*{\pagepostvo}{}
\renewcommand*{\pagelargecrownvo}{}
\renewcommand*{\pagelargepostvo}{}
\renewcommand*{\pagesmalldemyvo}{}
\renewcommand*{\pagedemyvo}{}
\renewcommand*{\pagemediumvo}{}
\renewcommand*{\pagesmallroyalvo}{}
\renewcommand*{\pageroyalvo}{}
\renewcommand*{\pagesuperroyalvo}{}
\renewcommand*{\pageimperialvo}{}

\renewcommand*{\memfontfamily}{}
\renewcommand*{\memfontenc}{}
\renewcommand*{\memfontpack}{}

\renewcommand*{\anyptfilebase}{}
\renewcommand*{\anyptsize}{10}

\renewcommand*{\setstocksize}[2]{}
\renewcommand*{\settrimmedsize}[3]{}
\renewcommand*{\settrims}[2]{}

```

```
% \newlength{\lxvchars}
% \setlength{\lxvchars}{305pt}
% \newlength{\xlvchars}
% \setlength{\xlvchars}{190pt}
\renewcommand*{\setxlvchars}[1]{}
\renewcommand*{\setlxvchars}[1]{}

\renewcommand*{\settypeblocksize}[3]{}
\renewcommand*{\setlrmargins}[3]{}
\renewcommand*{\setlrmarginsandblock}[3]{}
\renewcommand*{\setbinding}[1]{}
\renewcommand*{\setulmargins}[3]{}
\renewcommand*{\setulmarginsandblock}[3]{}
\renewcommand*{\setcolsepandrule}[2]{}

\renewcommand*{\setheadfoot}[2]{}
\renewcommand*{\setheaderspaces}[3]{}
\renewcommand*{\setmarginnotes}[3]{}
\renewcommand*{\setfootins}[2]{}
\renewcommand*{\checkandfixthelayout}[1][]{}
\renewcommand*{\checkthelayout}[1]{}
\renewcommand*{\fixthelayout}{}
%
% \newlength{\stockheight}
% \newlength{\trimtop}
% \newlength{\trimedge}
% \newlength{\stockwidth}
% \newlength{\spinemargin}
% \newlength{\foremargin}
% \newlength{\uppermargin}
% \newlength{\headmargin}
%
\renewcommand*{\typeoutlayout}{}
\renewcommand*{\typeoutstandardlayout}{}
\renewcommand*{\settypeoutlayoutunit}[1]{}
\renewcommand*{\fixpdflayout}{}
\renewcommand*{\fixdvipslayout}{}

\renewcommand*{\medievalpage}[1][]{}
\renewcommand*{\isopage}[1][]{}
\renewcommand*{\semiisopage}[1][]{}

\renewcommand{\setpagebl}[3]{}
\renewcommand{\setpageml}[3]{}
\renewcommand{\setpagetl}[3]{}
\renewcommand{\setpagetm}[3]{}
\renewcommand{\setpagetr}[3]{}
\renewcommand{\setpagemr}[3]{}
\renewcommand{\setpagebr}[3]{}
\renewcommand{\setpagebm}[3]{}
\renewcommand{\setpagecc}[3]{}
```

## § 671.4 Text and fonts

```
\let\miniscule\tiny
\let\HUGE\Huge

\renewcommand*{\abnormalparskip}[1]{}
\renewcommand*{\nonzeroparskip}{}
\renewcommand*{\traditionalparskip}{}

\let\onelineskip\baselineskip

\let\OnehalfSpacing\onehalfspacing
\let\DoubleSpacing\doublespacing
\renewcommand*{\setPagenoteSpacing}[1]{}
\renewcommand*{\setFloatSpacing}[1]{}

\renewcommand{\SingleSpacing}{\@ifstar\singlespacing\singlespacing}

\let\setSingleSpace\SetSinglespace
\let\SingleSpace\singlespace
\let\endSingleSpace\endsinglespace
\let\Spacing\spacing
\let\endSpacing\endspacing
\let\OnehalfSpace\onehalfspace
\let\endOnehalfSpace\endonehalfspace
\csletcs{OnehalfSpace*}{onehalfspace}
\csletcs{endOnehalfSpace*}{endonehalfspace}
\let\DoubleSpace\doublespace
\let\endDoubleSpace\enddoublespace
\csletcs{DoubleSpace*}{doublespace}
\csletcs{endDoubleSpace*}{enddoublespace}
\renewcommand*{\setDisplayskipStretch}[1]{}
\renewcommand*{\memdskipstretch}{}
\renewcommand*{\noDisplayskipStretch}{}
\renewcommand*{\memdskips}{}

\renewcommand*{\midsloppy}{}
\renewenvironment*{midsloppypar}{}{}

\renewcommand*{\sloppybottom}{}
```

## § 671.5 Titles

```
\csletcs{titlingpage*}{titlingpage}
\csletcs{endtitlingpage*}{endtitlingpage}
\let\titlingpageend\relax
\newcommand{\titlingpageend}[2]{}
\let\andnext\and
\renewcommand*{\thanksmarkstyle}[1]{}

\renewcommand{\thanksfootmark}{%
    \thanksscript{\tamark}%
}

% \newlength{\thanksmarksep}% already provided by memoir
```

```
\renewcommand\titlingpageend[2]{}
```

## § 671.6 Abstracts

```
% \newlength{\absindent}
% \newlength{\absparsep}
\renewcommand*{\abstractcol}{}
\renewcommand*{\abstractintoc}{}
\renewcommand*{\abstractnum}{}
\renewcommand*{\abstractrunin}{}
```

## § 671.7 Docment divisions

\book * (⟨*2:PDF name*⟩) [⟨*3:TOC name*⟩] [⟨*4:PDF name*⟩] (⟨*5:PDF name*⟩) {⟨*6:name*⟩}

```
\DeclareDocumentCommand{\book}{s d() o o d() m}{%
    \LWR@section{#1}{#3}{#6}{book}%
}

\def\@apppage{%
    \part*{\appendixpagename}
}
\renewcommand\mempreaddapppagetotochook{}
\renewcommand\mempostaddapppagetotochook{}

\def\@sapppage{%
    \part*{\appendixpagename}
}

\DeclareDocumentCommand{\mainmatter}{s}{%
    \booltrue{LWR@mainmatter}%
}

\DeclareDocumentCommand{\frontmatter}{s}{%
    \boolfalse{LWR@mainmatter}%
}

\renewcommand*{\raggedbottomsection}{}
\renewcommand*{\normalbottomsection}{}
\renewcommand*{\bottomsectionskip}{}
\renewcommand*{\bottomsectionpenalty}{}
\csletcs{appendixpage*}{appendixpage}
\renewcommand*{\namedsubappendices}{}
\renewcommand*{\unnamedsubappendices}{}
\renewcommand*{\beforebookskip}{}
\renewcommand*{\afterbookskip}{}
\renewcommand*{\beforepartskip}{}
\renewcommand*{\afterpartskip}{}
\renewcommand*{\midbookskip}{}
\renewcommand*{\midpartskip}{}
\renewcommand*{\printbookname}{}
\renewcommand*{\booknamefont}{}
\renewcommand*{\booknamenum}{}
\renewcommand*{\printbooknum}{}
```

```
\renewcommand*{\booknumfont}{}
\renewcommand*{\printpartname}{}
\renewcommand*{\partnamefont}{}
\renewcommand*{\partnamenum}{}
\renewcommand*{\printpartnum}{}
\renewcommand*{\partnumfont}{}
\renewcommand*{\printbooktitle}[1]{}
\renewcommand*{\booktitlefont}{}
\renewcommand{\printparttitle}[1]{}
\renewcommand*{\parttitlefont}{}
\renewcommand*{\bookpageend}{}
\renewcommand*{\bookblankpage}{}
\renewcommand*{\nobookblankpage}{}
\renewcommand*{\partpageend}{}
\renewcommand*{\partblankpage}{}
\renewcommand*{\nopartblankpage}{}
\RenewDocumentCommand{\newleadpage}{s o m m}{}% todo
\RenewDocumentCommand{\renewleadpage}{s o m m}{}% todo
\renewcommand*{\leadpagetoclevel}{chapter}

\renewcommand*{\openright}{}
\renewcommand*{\openleft}{}
\renewcommand*{\openany}{}
\renewcommand*{\clearforchapter}{}
\renewcommand*{\memendofchapterhook}{}
\renewcommand*{\chapterheadstart}{}
% \newlength{\beforechapskip}
\renewcommand*{\afterchapternum}{}
% \newlength{\midchapskip}
\renewcommand*{\afterchaptertitle}{}
% \newlength{\afterchapskip}
\renewcommand*{\printchaptername}{}
\renewcommand*{\chapnamefont}{}
\renewcommand*{\chapternamenum}{}
\renewcommand*{\printchapternum}{}
\renewcommand*{\chapnumfont}{}
\renewcommand{\printchaptertitle}[1]{}
\renewcommand*{\chaptitlefont}{}
\renewcommand*{\printchapternonum}{}
\renewcommand*{\indentafterchapter}{}
\renewcommand*{\noindentafterchapter}{}
\renewcommand*{\insertchapterspace}{}

\renewcommand*{\chapterstyle}[1]{}
\renewcommand{\makechapterstyle}[2]{}
\renewcommand*{\chapindent}{}
\let\chapterprecis\cftchapterprecis
\let\chapterprecishere\cftchapterprecishere
\let\chapterprecistoc\cftchapterprecistoc
\renewcommand*{\precisfont}{}
\renewcommand*{\prechapterprecis}{}
\renewcommand*{\postchapterprecis}{}
\renewcommand{\precistoctext}[1]{}
\renewcommand*{\precistocfont}{}
\renewcommand*{\precistocformat}{}
```

```
% \newlength{\prechapterprecisshift}

\renewcommand*{\setbeforesecskip}[1]{}
\renewcommand*{\setaftersecskip}[1]{}
\renewcommand*{\setsecindent}[1]{}
\renewcommand*{\setsecheadstyle}[1]{}
\renewcommand*{\setbeforesubsecskip}[1]{}
\renewcommand*{\setaftersubsecskip}[1]{}
\renewcommand*{\setsubsecindent}[1]{}
\renewcommand*{\setsubsecheadstyle}[1]{}
\renewcommand*{\setbeforesubsubsecskip}[1]{}
\renewcommand*{\setaftersubsubsecskip}[1]{}
\renewcommand*{\setsubsubsecindent}[1]{}
\renewcommand*{\setsubsubsecheadstyle}[1]{}
\renewcommand*{\setbeforeparaskip}[1]{}
\renewcommand*{\setafterparaskip}[1]{}
\renewcommand*{\setparaindent}[1]{}
\renewcommand*{\setparaheadstyle}[1]{}
\renewcommand*{\setbeforesubparaskip}[1]{}
\renewcommand*{\setaftersubparaskip}[1]{}
\renewcommand*{\setsubparaindent}[1]{}
\renewcommand*{\setsubparaheadstyle}[1]{}
\renewcommand{\@hangfrom}[1]{#1}
\renewcommand{\sethangfrom}[1]{}
\renewcommand{\setsecnumformat}[1]{}

\renewcommand*{\hangsecnum}{}
\renewcommand*{\defaultsecnum}{}

\renewcommand*{\sechook}{}
\renewcommand{\setsechook}[1]{}
\renewcommand*{\subsechook}{}
\renewcommand{\setsubsechook}[1]{}
\renewcommand*{\subsubsechook}{}
\renewcommand{\setsubsubsechook}[1]{}
\renewcommand*{\parahook}{}
\renewcommand{\setparahook}[1]{}
\renewcommand*{\subparahook}{}
\renewcommand{\setsubparahook}[1]{}

\RenewDocumentCommand{\plainbreak}{s m}{\begin{center}~\end{center}}

\RenewDocumentCommand{\fancybreak}{s +m}{%
    \begin{center}#2\end{center}%
}

\RenewDocumentCommand{\plainfancybreak}{s m m +m}{%
    \begin{center}#4\end{center}%
}

\RenewDocumentCommand{\pfbreak}{s}{%
    \begin{center}
    \pfbreakdisplay
    \end{center}
}
```

```
391
392 % \newlength{\pfbreakskip}
393 \renewcommand{\pfbreakdisplay}{*\quad*\quad*}
394
395 \renewcommand{\makeheadstyles}[2]{}
396 \renewcommand*{\headstyles}[1]{}
```

## § 671.8 Pagination and headers

```
397 \renewcommand*{\savepagenumber}{}
398 \renewcommand*{\restorepagenumber}{}
399 \renewcommand*{\uppercaseheads}{}
400 \renewcommand*{\nouppercaseheads}{}
401
402 \renewcommand*{\bookpagemark}[1]{}
403 \renewcommand*{\partmark}[1]{}
404 \renewcommand*{\bibmark}{}
405 \renewcommand*{\indexmark}{}
406 \renewcommand*{\glossarymark}{}
407
408 \LWR@origpagestyle{empty}
409 \renewcommand*{\ps@empty}{}
410 \renewcommand*{\make
```

```
\renewcommand*{\clearplainmark}[1]{}
\renewcommand*{\clearmark}[1]{}
\renewcommand{\addtopsmarks}[3]{}
\renewcommand{\ifonlyfloats}[2]{#2}
\renewcommand*{\mergepagefloatstyle}[3]{}

\renewcommand*{\framepichead}{}
\renewcommand*{\framepictextfoot}{}
\renewcommand*{\framepichook}{}
\renewcommand*{\showheadfootlocoff}{}
\renewcommand*{\showtextblocklocoff}{}
```

## § 671.9 Paragraphs and lists

```
\renewcommand{\hangfrom}[1]{#1}
\let\centerfloat\centering
\renewcommand*{\raggedyright}[1][]{}
% \newlength{\ragrparindent}
\renewcommand{\sourceatright}[2][]{\attribution{#2}}
\let\memorigdbs\LWR@endofline
\let\memorigpar\par
\let\atcentercr\LWR@endofline

\renewcommand*{\linenottooshort}[1][]{}
\renewcommand*{\russianpar}{}
\renewcommand*{\lastlinerulefill}{}
\renewcommand*{\lastlineparrule}{}
\renewcommand*{\justlastraggedleft}{}
\renewcommand*{\raggedrightthenleft}{}
\renewcommand*{\leftcenterright}{}

\renewcommand{\leftspringright}[4]{%
    \begin{minipage}{#1\linewidth}#3\end{minipage}\qquad%
   \begin{minipage}{#2\linewidth}\begin{flushright}#4\end{flushright}\end{minipage}%
}

\renewenvironment*{blockdescription}
{\LWR@descriptionstart\LWR@origdescription}
{\enddescription}

\renewcommand*{\blockdescriptionlabel}[1]{\textbf{#1}}
\renewenvironment*{labelled}[1]{\begin{description}}{\end{description}}
\renewenvironment*{flexlabelled}[6]{\begin{description}}{\end{description}}
\renewcommand*{\tightlists}{}
\renewcommand*{\defaultlists}{}
\RenewDocumentCommand{\firmlists}{s}{}
\renewcommand*{\firmlist}{}
\renewcommand*{\tightlist}{}
\renewcommand*{\zerotrivseps}{}
\renewcommand*{\savetrivseps}{}
\renewcommand*{\restoretrivseps}{}
```

## § 671.10 Contents lists

```
\csletcs{tableofcontents*}{tableofcontents}
```

```
\csletcs{listoffigures*}{listoffigures}
\csletcs{listoftables*}{listoftables}
\renewenvironment{KeepFromToc}{}{}
\renewcommand*{\onecoltocetc}{}
\renewcommand*{\twocoltocetc}{}
\renewcommand*{\ensureonecol}{}
\renewcommand*{\restorefromonecol}{}
\renewcommand*{\doccoltocetc}{}

\renewcommand{\tocheadstart}{}
\renewcommand{\printtoctitle}[1]{}
\renewcommand{\tocmark}{}
\renewcommand{\aftertoctitle}{}
\renewcommand{\lofheadstart}{}
\renewcommand{\printloftitle}[1]{}
\renewcommand{\lofmark}{}
\renewcommand{\afterloftitle}{}
\renewcommand{\lotheadstart}{}
\renewcommand{\printlottitle}[1]{}
\renewcommand{\lotmark}{}
\renewcommand{\afterlottitle}{}

\renewcommand*{\setpnumwidth}[1]{}
\renewcommand*{\setrmarg}[1]{}
\renewcommand*{\cftbookbreak}{}
\renewcommand*{\cftpartbreak}{}
\renewcommand*{\cftchapterbreak}{}

% \newlength{\cftbeforebookskip}
% \newlength{\cftbookindent}
% \newlength{\cftbooknumwidth}
\renewcommand*{\cftbookfont}{}
\renewcommand*{\cftbookname}{}
\renewcommand*{\cftbookpresnum}{}
\renewcommand*{\cftbookaftersnum}{}
\renewcommand*{\cftbookaftersnumb}{}
\renewcommand*{\cftbookleader}{}
\renewcommand*{\cftbookdotsep}{1}
\renewcommand*{\cftbookpagefont}{}
\renewcommand*{\cftbookafterpnum}{}
\renewcommand*{\cftbookformatpnum}[1]{}
\renewcommand*{\cftbookformatpnumhook}[1]{}
```

Part is already defined by tocloft.

```
% \newlength{\cftbeforechapterskip}
% \newlength{\cftchapterindent}
% \newlength{\cftchapternumwidth}
\renewcommand*{\cftchapterfont}{}
\renewcommand*{\cftchaptername}{}
\renewcommand*{\cftchapterpresnum}{}
\renewcommand*{\cftchapteraftersnum}{}
\renewcommand*{\cftchapteraftersnumb}{}
\renewcommand*{\cftchapterleader}{}
\renewcommand*{\cftchapterdotsep}{1}
\renewcommand*{\cftchapterpagefont}{}
```

```
\renewcommand*{\cftchapterafterpnum}{}
\renewcommand*{\cftchapterformatpnum}[1]{}
\renewcommand*{\cftchapterformatpnumhook}[1]{}

% \newlength{\cftbeforesectionskip}
% \newlength{\cftsectionindent}
% \newlength{\cftsectionnumwidth}
\renewcommand*{\cftsectionfont}{}
\renewcommand*{\cftsectionname}{}
\renewcommand*{\cftsectionpresnum}{}
\renewcommand*{\cftsectionaftersnum}{}
\renewcommand*{\cftsectionaftersnumb}{}
\renewcommand*{\cftsectionleader}{}
\renewcommand*{\cftsectiondotsep}{1}
\renewcommand*{\cftsectionpagefont}{}
\renewcommand*{\cftsectionafterpnum}{}
\renewcommand*{\cftsectionformatpnum}[1]{}
\renewcommand*{\cftsectionformatpnumhook}[1]{}

% \newlength{\cftbeforesubsectionskip}
% \newlength{\cftsubsectionindent}
% \newlength{\cftsubsectionnumwidth}
\renewcommand*{\cftsubsectionfont}{}
\renewcommand*{\cftsubsectionname}{}
\renewcommand*{\cftsubsectionpresnum}{}
\renewcommand*{\cftsubsectionaftersnum}{}
\renewcommand*{\cftsubsectionaftersnumb}{}
\renewcommand*{\cftsubsectionleader}{}
\renewcommand*{\cftsubsectiondotsep}{1}
\renewcommand*{\cftsubsectionpagefont}{}
\renewcommand*{\cftsubsectionafterpnum}{}
\renewcommand*{\cftsubsectionformatpnum}[1]{}
\renewcommand*{\cftsubsectionformatpnumhook}[1]{}

% \newlength{\cftbeforesubsubsectionskip}
% \newlength{\cftsubsubsectionindent}
% \newlength{\cftsubsubsectionnumwidth}
\renewcommand*{\cftsubsubsectionfont}{}
\renewcommand*{\cftsubsubsectionname}{}
\renewcommand*{\cftsubsubsectionpresnum}{}
\renewcommand*{\cftsubsubsectionaftersnum}{}
\renewcommand*{\cftsubsubsectionaftersnumb}{}
\renewcommand*{\cftsubsubsectionleader}{}
\renewcommand*{\cftsubsubsectiondotsep}{1}
\renewcommand*{\cftsubsubsectionpagefont}{}
\renewcommand*{\cftsubsubsectionafterpnum}{}
\renewcommand*{\cftsubsubsectionformatpnum}[1]{}
\renewcommand*{\cftsubsubsectionformatpnumhook}[1]{}

% \newlength{\cftbeforeparagraphskip}
% \newlength{\cftparagraphindent}
% \newlength{\cftparagraphnumwidth}
\renewcommand*{\cftparagraphfont}{}
\renewcommand*{\cftparagraphname}{}
\renewcommand*{\cftparagraphpresnum}{}
\renewcommand*{\cftparagraphaftersnum}{}
```

```
\renewcommand*{\cftparagraphaftersnumb}{}
\renewcommand*{\cftparagraphleader}{}
\renewcommand*{\cftparagraphdotsep}{1}
\renewcommand*{\cftparagraphpagefont}{}
\renewcommand*{\cftparagraphafterpnum}{}
\renewcommand*{\cftparagraphformatpnum}[1]{}
\renewcommand*{\cftparagraphformatpnumhook}[1]{}

% \newlength{\cftbeforesubparagraphskip}
% \newlength{\cftsubparagraphindent}
% \newlength{\cftsubparagraphnumwidth}
\renewcommand*{\cftsubparagraphfont}{}
\renewcommand*{\cftsubparagraphname}{}
\renewcommand*{\cftsubparagraphpresnum}{}
\renewcommand*{\cftsubparagraphaftersnum}{}
\renewcommand*{\cftsubparagraphaftersnumb}{}
\renewcommand*{\cftsubparagraphleader}{}
\renewcommand*{\cftsubparagraphdotsep}{1}
\renewcommand*{\cftsubparagraphpagefont}{}
\renewcommand*{\cftsubparagraphafterpnum}{}
\renewcommand*{\cftsubparagraphformatpnum}[1]{}
\renewcommand*{\cftsubparagraphformatpnumhook}[1]{}

% \newlength{\cftbeforefigureskip}
% \newlength{\cftfigureindent}
% \newlength{\cftfigurenumwidth}
\renewcommand*{\cftfigurefont}{}
\renewcommand*{\cftfigurename}{}
\renewcommand*{\cftfigurepresnum}{}
\renewcommand*{\cftfigureaftersnum}{}
\renewcommand*{\cftfigureaftersnumb}{}
\renewcommand*{\cftfigureleader}{}
\renewcommand*{\cftfiguredotsep}{1}
\renewcommand*{\cftfigurepagefont}{}
\renewcommand*{\cftfigureafterpnum}{}
\renewcommand*{\cftfigureformatpnum}[1]{}
\renewcommand*{\cftfigureformatpnumhook}[1]{}

% \newlength{\cftbeforesubfigureskip}
% \newlength{\cftsubfigureindent}
% \newlength{\cftsubfigurenumwidth}
\newcommand*{\cftsubfigurefont}{}
\newcommand*{\cftsubfigurename}{}
\newcommand*{\cftsubfigurepresnum}{}
\newcommand*{\cftsubfigureaftersnum}{}
\newcommand*{\cftsubfigureaftersnumb}{}
\newcommand*{\cftsubfigureleader}{}
\newcommand*{\cftsubfiguredotsep}{1}
\newcommand*{\cftsubfigurepagefont}{}
\newcommand*{\cftsubfigureafterpnum}{}
\newcommand*{\cftsubfigureformatpnum}[1]{}
\newcommand*{\cftsubfigureformatpnumhook}[1]{}

% \newlength{\cftbeforetableskip}
% \newlength{\cfttableindent}
% \newlength{\cfttablenumwidth}
```

```
\renewcommand*{\cfttablefont}{}
\renewcommand*{\cfttablename}{}
\renewcommand*{\cfttablepresnum}{}
\renewcommand*{\cfttableaftersnum}{}
\renewcommand*{\cfttableaftersnumb}{}
\renewcommand*{\cfttableleader}{}
\renewcommand*{\cfttabledotsep}{1}
\renewcommand*{\cfttablepagefont}{}
\renewcommand*{\cfttableafterpnum}{}
\renewcommand*{\cfttableformatpnum}[1]{}
\renewcommand*{\cfttableformatpnumhook}[1]{}

% \newlength{\cftbeforesubtableskip}
% \newlength{\cftsubtableindent}
% \newlength{\cftsubtablenumwidth}
\newcommand*{\cftsubtablefont}{}
\newcommand*{\cftsubtablename}{}
\newcommand*{\cftsubtablepresnum}{}
\newcommand*{\cftsubtableaftersnum}{}
\newcommand*{\cftsubtableaftersnumb}{}
\newcommand*{\cftsubtableleader}{}
\newcommand*{\cftsubtabledotsep}{1}
\newcommand*{\cftsubtablepagefont}{}
\newcommand*{\cftsubtableafterpnum}{}
\newcommand*{\cftsubtableformatpnum}[1]{}
\newcommand*{\cftsubtableformatpnumhook}[1]{}

\renewcommand*{\booknumberline}[1]{}
\renewcommand*{\partnumberline}[1]{}
\renewcommand*{\chapternumberline}[1]{}
\renewcommand*{\numberlinehook}[1]{}
% \renewcommand*{\cftwhatismyname}{}%
\renewcommand*{\booknumberlinehook}[1]{}
\renewcommand*{\partnumberlinehook}[1]{}
\renewcommand*{\chapternumberlinehook}[1]{}
\renewcommand{\numberlinebox}[2]{}
\renewcommand{\booknumberlinebox}[2]{}
\renewcommand{\partnumberlinebox}[2]{}
\renewcommand{\chapternumberlinebox}[2]{}
%
% \newlength{\cftparfillskip}
\renewcommand*{\cftpagenumbersoff}[1]{}
\renewcommand*{\cftpagenumberson}[1]{}
\renewcommand*{\cftlocalchange}[3]{}
\renewcommand*{\cftaddtitleline}[4]{}
\renewcommand*{\cftaddnumtitleline}[4]{}
\renewcommand{\cftinsertcode}[2]{}
\renewcommand{\cftinserthook}[2]{}
\renewcommand{\settocpreprocessor}[2]{}
\DeclareRobustCommand{\cftpagenumbersoff}[1]{}
\DeclareRobustCommand{\cftpagenumberson}[1]{}
```

## § 671.11 Floats and captions

`\@xfloat`

`\@xdblfloat`

Reestablish lwarp's takeover the float handing, which memoir tried to grab:

```
\AtBeginDocument{
\def\@xfloat #1[#2]{%
    \LWR@floatbegin{#1}[#2]
    \normalsize
    \@nameuse{#1adjustment}%
    \LWR@futurenonspacelet\LWR@mynexttoken\LWR@floatalignment%
}
\def\@xdblfloat #1[#2]{%
    \LWR@floatbegin{#1}[#2]
    \normalsize
    \@nameuse{#1adjustment}%
    \LWR@futurenonspacelet\LWR@mynexttoken\LWR@floatalignment%
}
}
```

\newfloat [⟨*1: within*⟩] {⟨*2: type*⟩} {⟨*3: ext*⟩} {⟨*4: capname*⟩}

```
\RenewDocumentCommand{\newfloat}{o m m m}{%
    \def\LWR@tempone{#4}%
    \def\LWR@temptwo{\@nameuse{#2name}}%
    \ifdefequal{\LWR@tempone}{\LWR@temptwo}{% recursive name, already defined
        \IfValueTF{#1}%
            {\DeclareFloatingEnvironment[fileext=#3,within=#1]{#2}}%
            {\DeclareFloatingEnvironment[fileext=#3]{#2}}%
    }{% not recursive name
        \IfValueTF{#1}%
            {\DeclareFloatingEnvironment[fileext=#3,within=#1,name={#4}]{#2}}%
            {\DeclareFloatingEnvironment[fileext=#3,name={#4}]{#2}}%
    }%
```

newfloat package automatically creates the `\listof` command for new floats, but float does not, so remove `\listof` here in case it is manually created later.

```
    \cslet{listof#2s}\relax%
    \cslet{listof#2es}\relax%
}
```

\newlistof [⟨*within*⟩] {⟨*type*⟩} {⟨*ext*⟩} {⟨*listofname*⟩}

Emulated through the `\newfloat` mechanism. Note that memoir uses a different syntax than tocloft for the name.

```
\RenewDocumentCommand{\newlistof}{o m m m}
{%
    \IfValueTF{#1}%
        {\newlistentry[#1]{#2}{#3}{0}}%
        {\newlistentry{#2}{#3}{0}}%
    \@namedef{ext@#2}{#3}%
    \@ifundefined{c@#3depth}{\newcounter{#3depth}}{}%
    \setcounter{#3depth}{1}%
    \@namedef{#3mark}{}%
    \@namedef{#2}{\listof{#2}{#4}}%
    \@namedef{@cftmake#3title}{}%
    \@ifundefined{cftbefore#3titleskip}{%
        \expandafter\newlength\csname cftbefore#3titleskip\endcsname%
        \expandafter\newlength\csname cftafter#3titleskip\endcsname%
    }{}%
```

```
    \@namedef{cft#3titlefont}{}%
    \@namedef{cftafter#3title}{}%
    \@namedef{cft#3prehook}{}%
    \@namedef{cft#3posthook}{}%
}

\renewcommand{\setfloatadjustment}[2]{}
```

Borrowed from the lwarp version of keyfloat:

```
\NewDocumentEnvironment{KFLTmemoir@marginfloat}{O{-1.2ex} m}
{% start
    \LWR@BlockClassWP{float:right; width:2in; margin:10pt}{}{marginblock}%
    \renewcommand*{\@captype}{#2}%
}
{%
    \endLWR@BlockClassWP%
}

\DeclareDocumentEnvironment{marginfigure}{o}
  {\begin{KFLTmemoir@marginfloat}{figure}}
  {\end{KFLTmemoir@marginfloat}}

\DeclareDocumentEnvironment{margintable}{o}
  {\begin{KFLTmemoir@marginfloat}{table}}
  {\end{KFLTmemoir@marginfloat}}

\renewcommand{\setmarginfloatcaptionadjustment}[2]{}
\renewcommand{\setmpjustification}[2]{}
\renewcommand*{\mpjustification}{}
\renewcommand*{\setfloatlocations}[2]{}
\DeclareDocumentCommand{\suppressfloats}{o}{}
\renewcommand*{\FloatBlock}{}
\renewcommand*{\FloatBlockAllowAbove}{}
\renewcommand*{\FloatBlockAllowBelow}{}
\renewcommand*{\setFloatBlockFor}{}

\renewcommand{\captiontitlefinal}[1]{}
```

`\flegtable`, `\flegfigure`, `\flegtoctable`, `\flegtocfigure` are defined by memoir using `\newfloat`. These are defined with an `@` in ccaption.

```
\renewcommand{\flegtable}{\tablename}
\renewcommand{\flegfigure}{\figurename}
\renewcommand{\flegtoctable}{}
\renewcommand{\flegtocfigure}{}


\renewcommand{\@makesubfloatcaption}[2]{%
    \minipagefullwidth
    \begin{minipage}{\linewidth}%
    #1 \ignorespaces #2 \unskip%
    \end{minipage}
}

```

```
\renewcommand*{\tightsubcaptions}{}
\renewcommand*{\loosesubcaptions}{}

\renewcommand*{\subcaptionsize}[1]{}
\renewcommand*{\subcaptionlabelfont}[1]{}
\renewcommand*{\subcaptionfont}[1]{}
\renewcommand*{\subcaptionstyle}[1]{}

\renewcommand*{\hangsubcaption}{}
\renewcommand*{\shortsubcaption}{}
\renewcommand*{\normalsubcaption}{}

\RenewDocumentEnvironment{sidecaption}{o m o}
{}
{%
    \IfValueTF{#1}{\caption[#1]{#2}}{\caption{#2}}%
    \IfValueT{#3}{\label{#3}}%
}

% \newlength{\sidecapwidth}
% \newlength{\sidecapsep}
\renewcommand*{\setsidecaps}[2]{}
\renewcommand*{\sidecapmargin}[1]{}
% \newif\ifscapmargleft
\scapmargleftfalse
\renewcommand*{\setsidecappos}[1]{}
```

Env sidecontcaption

```
\RenewDocumentEnvironment{sidecontcaption}{m o}
{}
{%
    \ifdef{\ContinuedFloat}%
        {\ContinuedFloat}%
        {\addtocounter{\@captype}{-1}}%
    \caption{#1}%
```

Without \@captype, the section is referred to instead.

```
    \IfValueT{#2}{\label[\@captype]{#2}}%
}
```

\sidenamedlegend does not appear to use the TOC argument.

```
\renewenvironment{sidenamedlegend}[2][]{
    \begin{center}
    \@nameuse{\@captype name}\CaptionSeparator#2
    \end{center}
}
{}

\renewenvironment{sidelegend}[1]
{\begin{center}
    #1

}
```

```
{\end{center}}

\renewcommand*{\sidecapstyle}{}
\renewcommand*{\overridescapmargin}[1]{}
% \newlength{\sidecapraise}
\renewcommand*{\sidecapfloatwidth}{\linewidth}

\LetLtxMacro\ctabular\tabular
\LetLtxMacro\endctabular\endtabular

\renewcommand{\autorows}[5][]{%
    #5%
}

\renewcommand{\autocols}[5][]{%
    #5%
}
```

## § 671.12 Footnotes and page notes

```
\renewcommand*{\feetabovefloat}{}
\renewcommand*{\feetbelowfloat}{}
\renewcommand*{\feetatbottom}{}

\renewcommand*{\verbfootnote}[2][]{%
    \PackageError{lwarp,memoir}%
    {Verbatim footnotes are not yet supported by lwarp}%
    {This may be improved some day.}%
}

\renewcommand*{\plainfootnotes}{}
\renewcommand*{\twocolumnfootnotes}{}
\renewcommand*{\threecolumnfootnotes}{}
\renewcommand*{\paragraphfootnotes}{}
\renewcommand*{\footfudgefiddle}{}

\renewcommand*{\newfootnoteseries}[1]{%
    \PackageError{lwarp,memoir}%
    {Memoir footnote series are not yet supported by lwarp}%
    {This may be improved some day.}%
}

\renewcommand*{\plainfootstyle}[1]{}
\renewcommand*{\twocolumnfootstyle}[1]{}
\renewcommand*{\threecolumnfootstyle}[1]{}
\renewcommand*{\paragraphfootstyle}[1]{}

\renewcommand*{\footfootmark}{}
\renewcommand*{\footmarkstyle}[1]{}

% \newlength{\footmarkwidth}
% \newlength{\footmarksep}
% \newlength{\footparindent}

\renewcommand*{\foottextfont}{}

```

```
\renewcommand*{\marginparmargin}[1]{}
\renewcommand*{\sideparmargin}[1]{}

\LetLtxMacro\sidepar\marginpar
\renewcommand*{\sideparfont}{}
\renewcommand*{\sideparform}{}
\LWR@providelength{\sideparvshift}

\renewcommand*{\parnopar}{}

\renewcommand{\sidebar}[1]{\begin{quote}#1\end{quote}}
\renewcommand*{\sidebarmargin}[1]{}
\renewcommand*{\sidebarfont}{}
\renewcommand*{\sidebarform}{}
% \newlength{\sidebarhsep}
% \newlength{\sidebarvsep}
% \newlength{\sidebarwidth}
% \newlength{\sidebartopsep}
\renewcommand{\setsidebarheight}[1]{}
\renewcommand*{\setsidebars}[6]{}
\renewcommand*{\footnotesatfoot}{}
\renewcommand*{\footnotesinmargin}{}

\LetLtxMacro\sidefootnote\footnote
\LetLtxMacro\sidefootnotemark\footnotemark
\LetLtxMacro\sidefootnotetext\footnotetext

\renewcommand*{\sidefootmargin}[1]{}
% \newlength{\sidefoothsep}
% \newlength{\sidefootvsep}
% \newlength{\sidefootwidth}
% \newlength{\sidefootadjust}
% \newlength{\sidefootheight}
\renewcommand*{\setsidefootheight}[1]{}
% \renewcommand*{\sidefootfont}{}% in docs but not in the package
\renewcommand*{\setsidefeet}[6]{}
\renewcommand*{\sidefootmarkstyle}[1]{}
\renewcommand*{\sidefoottextfont}{}
\renewcommand*{\sidefootform}{}

\renewcommand*{\continuousnotenums}{\pncontopttrue}% from pagenote
\renewcommand*{\notepageref}{}
\renewcommand*{\prenotetext}{}
\renewcommand*{\postnotetext}{}
\LetLtxMacro\printpageinnoteshyperref\printpageinnotes
\renewcommand*{\foottopagenote}{}
\renewcommand*{\pagetofootnote}{}
```

`\m@m@wrpnote`

`\startnoteentrystart`

To have cleveref work with page note labels, the following patch writes `\thepagenote` and also adds `\arabic{pagenote}` to the first argument written to the `.ent` file:

```
\startnoteentry{{\thepagenote}{\arabic{pagenote}}} . . .
```

The arabic value is required for cleveref. \thepagenote becomes \@firstoftwo#1 and the arabic value becomes \@secondoftwo#1.

⚠ \nameref Note that for print mode,\nameref print the section name where the page notes are declared in the text, but for HTML it prints the name where the page notes are printed.

```
\xpatchcmd{\m@m@wrpnote}
    {\string\startnoteentry{\thepagenote}}
    {\string\startnoteentry{{\thepagenote}{\arabic{pagenote}}}}
    {}
    {\LWR@patcherror{memoir}{m@m@wrpnote}}

\renewcommand\startnoteentrystart[4]{%
  \prenoteinnotes%
  \noteidinnotes{\@firstoftwo#1}{#2}%
  \@ifmtarg{#2}{%
%         \phantomsection\def\@currentlabel{#1}%            original
        \def\@currentlabel{\@firstoftwo#1}%                 lwarp
        \def\cref@currentlabel{%                            lwarp
            [pagenote][\@secondoftwo#1][]\@firstoftwo#1%    lwarp
        }%                                                  lwarp
  }{}%
  \pagenoteanchor{#4}%
  \pageinnotes{#3}%
  \prenotetext%
}
```

## § 671.13 Decorative text

```
\renewcommand*{\epigraphposition}[1]{}
\renewcommand*{\epigraphtextposition}[1]{}
\renewcommand*{\epigraphsourceposition}[1]{}
\renewcommand*{\epigraphfontsize}[1]{}
\renewcommand*{\epigraphforheader}[2][]{}
\renewcommand*{\epigraphpicture}{}
```

## § 671.14 Poetry

```
\renewcommand*{\vinphantom}{}
\renewcommand*{\vleftofline}[1]{#1}
% \let\linenumberfrequency\poemlines
% \renewcommand*{\linenumberfont}[1]{}

\DeclareDocumentCommand{\PoemTitle}{s o o m}{%
    \IfValueTF{#2}%
        {\poemtitle[#2]{#4}}%
        {\poemtitle{#4}}%
}

\renewcommand*{\NumberPoemTitle}{}
\renewcommand*{\PlainPoemTitle}{}
\renewcommand*{\poemtitlepstyle}{}
\renewcommand*{\poemtitlestarmark}[1]{}
\renewcommand*{\poemtitlestarpstyle}{}
\renewcommand*{\PoemTitleheadstart}{}
\renewcommand*{\printPoemTitlenonum}{}
\renewcommand*{\printPoemTitlenum}{}
```

```
\renewcommand*{\afterPoemTitlenum}{}
\renewcommand*{\printPoemTitletitle}[1]{}
\renewcommand*{\afterPoemTitle}{}
\newlength{\midpoemtitleskip}
\renewcommand*{\PoemTitlenumfont}{}
\renewcommand*{\PoemTitlefont}{}
```

## § 671.15 Boxes, verbatims and files

```
\renewenvironment{qframe}{\framed}{\endframed}
\renewenvironment{qshade}{\shaded}{\endshaded}
```

```
\renewcommand*{\setverbatimfont}[1]{}
\renewcommand*{\tabson}[1]{}
\renewcommand*{\tabsoff}{}
\renewcommand*{\wrappingon}{}
\renewcommand*{\wrappingoff}{}
\renewcommand*{\verbatimindent}{}
\renewcommand*{\verbatimbreakchar}[1]{}
```

```
\DefineVerbatimEnvironment{fboxverbatim}{Verbatim}{frame=single}
```

`boxedverbatim` is already defined by moreverb. `boxedverbatim*` does not appear to work at all, even in a minimal print memoir document.

```
\renewcommand*{\bvbox}{}
\renewcommand*{\bvtopandtail}{}
\renewcommand*{\bvsides}{}
\renewcommand*{\nobvbox}{}
% \newlength\bvboxsep
\renewcommand*{\bvtoprulehook}{}
\renewcommand*{\bvtopmidhook}{}
\renewcommand*{\bvendrulehook}{}
\renewcommand*{\bvleftsidehook}{}
\renewcommand*{\bvrightsidehook}{}
\renewcommand*{\bvperpagetrue}{}
\renewcommand*{\bvperpagefalse}{}
\renewcommand{\bvtopofpage}[1]{}
\renewcommand{\bvendofpage}[1]{}
\renewcommand*{\linenumberfrequency}[1]{}
\renewcommand*{\resetbvlinenumber}{}
\renewcommand*{\setbvlinenums}[2]{}
\renewcommand*{\linenumberfont}[1]{}
\renewcommand*{\bvnumbersinside}{}
\renewcommand*{\bvnumbersoutside}{}
```

## § 671.16 Cross referencing

```
\renewcommand*{\fref}[1]{\cref{#1}}
\renewcommand*{\tref}[1]{\cref{#1}}
\renewcommand*{\pref}[1]{\cpageref{#1}}
\renewcommand*{\Aref}[1]{\cref{#1}}
\renewcommand*{\Bref}[1]{\cref{#1}}
\renewcommand*{\Pref}[1]{\cref{#1}}
\renewcommand*{\Sref}[1]{\cref{#1}}
```

```
\renewcommand*{\figurerefname}{Figure}
\renewcommand*{\tablerefname}{Table}
\renewcommand*{\pagerefname}{page}
\renewcommand*{\bookrefname}{Book~}
\renewcommand*{\partrefname}{Part~}
\renewcommand*{\chapterrefname}{Chapter~}
\renewcommand*{\sectionrefname}{\S}
\renewcommand*{\appendixrefname}{Appendix~}
\LetLtxMacro\titleref\nameref
\renewcommand*{\headnameref}{}
\renewcommand*{\tocnameref}{}

\providecounter{LWR@currenttitle}

\renewcommand*{\currenttitle}{%
    \addtocounter{LWR@currenttitle}{1}%
    \label{currenttitle\arabic{LWR@currenttitle}}%
    \nameref{currenttitle\arabic{LWR@currenttitle}}%
}

\renewcommand*{\theTitleReference}[2]{}
\renewcommand*{\namerefon}{}
\renewcommand*{\namerefoff}{}
```

## § 671.17 Back matter

\@@wrindexhyp

Redefined to write the LWR@autoindex counter instead of page. Note that memoir has two versions, depending on the use of hyperref.

```
\AtBeginDocument{

\def\@@wrindexhyp#1||\\{%
    \addtocounter{LWR@autoindex}{1}%
    \label{LWRindex-\arabic{LWR@autoindex}}%
%     \ifshowindexmark\@showidx{#1}\fi
    \protected@write\@auxout{}%
%         {\string\@@wrindexm@m{\@idxfile}{#1}{\thepage}}%
        {\string\@@wrindexm@m{\@idxfile}{#1}{\arabic{LWR@autoindex}}}%
    \endgroup
    \@esphack}%
```

\@@wrspindexhyp

\specialindex behaves like a regular \index, pointing to where \specialindex is used. If \specialindex is used inside a figure or table after the \caption, then the hyperlink will be given the name of that particular figure or table.

```
\def\@@wrspindexhyp#1||\\{%
    \addtocounter{LWR@autoindex}{1}%
    \label{LWRindex-\arabic{LWR@autoindex}}%
%     \ifshowindexmark\@showidx{#1}\fi
    \protected@write\@auxout{}%
%         {\string\@@wrindexm@m{\@idxfile}{#1}{\@nameuse{the\@sptheidx}}}%
        {\string\@@wrindexm@m{\@idxfile}{#1}{\arabic{LWR@autoindex}}}%
    \endgroup
    \@esphack}%

}% \AtBeginDocument
```

\@spindex Patched to append _html to the file:

```
\renewcommand{\@spindex}[2]{%
  \@ifundefined{#1@idxfile}%
  {\ifreportnoidxfile
     \@memwarn{Undefined index file #1}%
    \fi
    \begingroup
    \@sanitize
    \@nowrindex}%
  {\def\@idxfile{#1_html}%
   \def\@sptheidx{#2}%
   \begingroup
   \@sanitize
   \@wrspindex}}
```

\makeindex Patched to use _html filename and \BaseJobname:

```
\catcode`\_=12%
\renewcommand*{\makeindex}[1][\BaseJobname]{%
  \if@filesw
    \def\gindex{\@bsphack%
      \@ifnextchar [{\@index}{\@index[\BaseJobname]}}
    \def\specialindex{\@bsphack\@spindex}%
    \makememindexhook
    \expandafter\newwrite\csname #1@idxfile\endcsname
   \expandafter\immediate\openout \csname #1@idxfile\endcsname #1_html.idx\relax
    \typeout{Writing index file #1_html.idx }%
  \fi}
\catcode`\_=8%
```

\printindex Patched to use _html filename and \BaseJobname. This will later be patched by the lwarp core.

```
\catcode`\_=12%
\renewcommand{\printindex}[1][\BaseJobname]{\@input@{#1_html.ind}}
\catcode`\_=8%

\DeclareDocumentCommand{\newblock}{}{}
%
\renewcommand*{\showindexmarks}{}
\renewcommand*{\hideindexmarks}{}

\renewcommand*{\xindyindex}{}
```

## § 671.18 Miscellaneous

```
\renewcommand*{\changemarks}{}
\renewcommand*{\nochangemarks}{}
\renewcommand*{\added}[1]{}
\renewcommand*{\deleted}[1]{}
\renewcommand*{\changed}[1]{}

\renewcommand*{\showtrimsoff}{}
\renewcommand*{\showtrimson}{}
\renewcommand*{\trimXmarks}{}
\renewcommand*{\trimLmarks}{}
\renewcommand*{\trimFrame}{}
\renewcommand*{\trimNone}{}
\renewcommand*\trimmarkscolor{}
\renewcommand*{\trimmarks}{}
\renewcommand*{\tmarktl}{}
\renewcommand*{\tmarktr}{}
\renewcommand*{\tmarkbr}{}
\renewcommand*{\tmarkbl}{}
\renewcommand*{\tmarktm}{}
\renewcommand*{\tmarkmr}{}
\renewcommand*{\tmarkbm}{}
\renewcommand*{\tmarkml}{}
\renewcommand*{\trimmark}{}
\renewcommand*{\quarkmarks}{}
\renewcommand*{\registrationColour}[1]{}

\renewcommand*{\leavespergathering}[1]{}

\renewcommand*{\noprelistbreak}{}

\renewcommand*{\cleartorecto}{}
\renewcommand*{\cleartoverso}{}

\renewenvironment{vplace}[1][]{}{}
```

## § 671.19 ccaption emulation

```
\renewcommand*{\captiondelim}[1]{\renewcommand*{\CaptionSeparator}{#1}}
\renewcommand*{\captionnamefont}[1]{}
\renewcommand*{\captiontitlefont}[1]{}
\renewcommand*{\flushleftright}{}
\renewcommand*{\centerlastline}{}
\renewcommand*{\captionstyle}[2][]{}
\DeclareDocumentCommand{\captionwidth}{m}{}
\renewcommand*{\changecaptionwidth}{}
\renewcommand*{\normalcaptionwidth}{}
\renewcommand*{\hangcaption}{}
\renewcommand*{\indentcaption}[1]{}
\renewcommand*{\normalcaption}{}
\renewcommand{\precaption}[1]{}
\renewcommand{\postcaption}[1]{}
\renewcommand{\midbicaption}[1]{}
\renewcommand{\contcaption}[1]{%
%   \ContinuedFloat%
```

```
%   \caption{#1}%
    \begin{LWR@figcaption}% later becomes \caption*
    \LWR@isolate{\@nameuse{\@captype name}}~%
    \thechapter.\the\value{\@captype}\CaptionSeparator\LWR@isolate{#1}%
    \end{LWR@figcaption}%
}

\newlength{\abovelegendskip}
\setlength{\abovelegendskip}{0.5\baselineskip}
\newlength{\belowlegendskip}
\setlength{\belowlegendskip}{\abovelegendskip}
```

The extra \\ here forces a <br> in HTML when \legend is used in a \marginpar.

```
\renewcommand{\legend}[1]{\begin{center}#1\\\end{center}}

\renewcommand{\namedlegend}[2][]{%
    \begin{center}
    \@nameuse{fleg\@captype}\CaptionSeparator#2\\
    \end{center}
    \@nameuse{flegtoc\@captype}{#1}
}
```

\flegtable, \flegfigure, \flegtoctable, \flegtocfigure are defined by memoir using \newfloat. These are defined with an @ in ccaption.

```
\renewcommand{\newfixedcaption}[3][\caption]{%
  \renewcommand{#2}{\def\@captype{#3}#1}}
\renewcommand{\renewfixedcaption}[3][\caption]{%
  \renewcommand{#2}{\def\@captype{#3}#1}}
\renewcommand{\providefixedcaption}[3][\caption]{%
  \providecommand{#2}{\def\@captype{#3}#1}}

\renewcommand{\bitwonumcaption}[6][]{%
    \ifblank{#2}{\caption{#3}}{\caption[#2]{#3}}%
    \addtocounter{\@captype}{-1}%
    \begingroup%
    \csdef{\@captype name}{#4}%
    \ifblank{#5}{\caption{#6}}{\caption[#5]{#6}}%
    \endgroup%
    \ifblank{#1}{}{\label{#1}}%
}

\LetLtxMacro\bionenumcaption\bitwonumcaption% todo

\renewcommand{\bicaption}[5][]{%
    \ifblank{#2}{\caption{#3}}{\caption[#2]{#3}}%
    \begin{LWR@figcaption}% later becomes \caption*
    \LWR@isolate{#4} % space
    \thechapter.\the\value{\@captype}\CaptionSeparator\LWR@isolate{#5}%
    \end{LWR@figcaption}%
    \ifblank{#1}{}{\label{#1}}%
}

\renewcommand{\bicontcaption}[3]{%
    \contcaption{#1}%
```

```
    \begingroup%
    \csdef{\@captype name}{#2}%
    \contcaption{#3}%
    \endgroup%
}
```

Only in ccaption, not in memoir:

```
% \LetLtxMacro\longbitwonumcaption\bitwonumcaption%
% \LetLtxMacro\longbionenumcaption\bitwonumcaption%
% \LetLtxMacro\longbicaption\bicaption%
```

Patches for subfloats to support additional lwarp labels:

```
\renewcommand{\@memsubbody}{%
  \bgroup
  \let\label=\memsub@label
  \ifdonemaincaption\else
    \advance\csname c@\@captype\endcsname\@ne
  \fi
  % \refstepcounter{sub\@captype}\@contkeep%
%   \leavevmode%            lwarp
  \@ifnextchar [%
    {\@memsubfig}%
    {\@memsubfig[\@empty]}}

\renewcommand{\@memcontsubbody}{%
  \bgroup
  \let\label=\memsub@label
  \@contset
  % \refstepcounter{sub\@captype}\@contkeep%
%   \leavevmode%            lwarp
  \@ifnextchar [%
    {\@memsubfig}%
    {\@memsubfig[\@empty]}}


\long\def\@memsubfloat#1[#2][#3]#4{%
%   \@tempcnta=\@ne
%   \if@tightsubcap
%     \if@minipage
%       \@tempcnta=\z@
%     \else
%       \ifdim\lastskip=\z@
%         \@tempcnta=\@ne
%       \else
%         \@tempcnta=\tw@
%       \fi
%     \fi
%   \fi
%   \if@contbotsub
%     \def\subfig@top{\subfloattopskip}%
%     \def\subfig@bottom{\subfloatbottomskip}%
%   \else
%     \def\subfig@top{\subfloatbottomskip}%
%     \def\subfig@bottom{\subfloattopskip}%
```

```
%   \fi
%   \setbox\@tempboxa \hbox{#4}%
%   \@tempdima=\wd\@tempboxa
%   \vbox
  \bgroup%
    \mem@step@subcounter%
%     \vbox
    \LWR@stoppars%
    \minipagefullwidth%                 lwarp
    \begin{minipage}{\linewidth}%       lwarp
    \bgroup
%     \ifcase\@tempcnta
%       \@minipagefalse
%     \or
%       \vspace{\subfig@top}
%     \or
%       \ifdim \lastskip=\z@ \else
%         \@tempskipb\subfig@top\@xaddvskip
%       \fi
%     \fi
    \if@contbotsub
      #4% \box\@tempboxa
      \egroup
      \ifx \@empty#3\relax \else
%         \vskip\subfloatcapskip
        \@memsubcaption{#1}{#2}{#3}%
      \fi
    \else
      \ifx \@empty#3\relax \else
        \@memsubcaption{#1}{#2}{#3}%
%         \vskip\subfloatcapskip
%         \vskip\subfloatcaptopadj
      \fi\egroup
      #4% \box\@tempboxa
    \fi
%     \vspace{\subfig@bottom}
    \end{minipage}%                     lwarp
    \LWR@startpars%                     lwarp
  \egroup
\egroup
}
```

## § 671.20 Final patchwork

```
\newlistof{tableofcontents}{toc}{\contentsname}
\newlistof{listoffigures}{lof}{\listfigurename}
\newlistof{listoftables}{lot}{\listtablename}
```

---

File 565 **lwarp-common-multimedia.sty**

# § 672 Package common-multimedia

Pkg `lwarp-common-multimedia` Common code for multimedia, movie15, and media9.

```
            {\maxof{\LWR@multimedia@width}{\LWR@multimedia@height}}%
    }%
    \setlength{\LWR@multimedia@maxdimension}{1.1\LWR@multimedia@maxdimension}%
    \ifdimgreater{\LWR@multimedia@width}{0pt}{%
        width:%
            \LWR@printpercentlength%
                {\LWR@multimedia@width}%
                {\LWR@multimedia@maxdimension}vmin ; % space
    }{}%
    \ifdimgreater{\LWR@multimedia@height}{0pt}{%
        height:%
            \LWR@printpercentlength%
                {\LWR@multimedia@height}%
                {\LWR@multimedia@maxdimension}vmin ; % space
    }{}%
}
```

`\LWR@multimedia@fileAV` {⟨*poster text*⟩} {⟨*filename*⟩} {⟨*audio/video*⟩} {⟨*mimetype*⟩}

Creates a video or audio from a file. The 2019/10 update of the LaTeX kernel may cause extra quotes to be added in the filenames. They are removed here.

```
\newcommand*{\LWR@multimedia@fileAV}[4]{%
\IfFileExists{#2}{% also sets \@filef@und
\StrSubstitute[100]{\@filef@und}{"}{}[\LWR@parsedfilename]%
```

The container  is sized as desired.

```
    \ifstrequal{#3}{audio}{%
        \begin{BlockClass}{AVviewport}
    }{%
        \begin{BlockClass}[\LWR@multimedia@printsize\ margin:auto]{AVviewport}
    }
```

Paragraph tags are unnecessary for the A/V tags.

```
    \LWR@stoppars
```

The A/V element is 100% of the container.

```
    \LWR@htmltag{%
        #3\ % space
        \ifstrequal{#3}{audio}{}{%
            width=\textquotedbl{}100\%\textquotedbl\ % space
            height=\textquotedbl{}100\%\textquotedbl\ % space
        }%
        controls%
    }\LWR@orignewline
```

The file source and type:

```
    \LWR@htmltag{%
        source % space
        src=\textquotedbl%
        \LWR@parsedfilename\unskip\textquotedbl\ % space
        type=\textquotedbl{}#4\textquotedbl}
```

The poster text inside paragraph tags, along with a reference to the file.

```
    \LWR@startpars
```

```
    \LWR@href{\LWR@parsedfilename}{#1}
    \LWR@stoppars
```

Finish.

```
    \LWR@htmltag{/#3}\LWR@orignewline
    \end{BlockClass}
}{%
    \PackageError{lwarp-common-multimedia}
        {File '#2' not found}
        {Perhaps an incorrect path?}
}%
}
```

`\LWR@multimedia@httpAV` {⟨*poster text*⟩} {⟨*filename*⟩} {⟨*audio/video*⟩} {⟨*mimetype*⟩}

Creates a video or audio from a URL link.

```
\newcommand*{\LWR@multimedia@httpAV}[4]{%
```

The container  is sized as desired.

```
    \ifstrequal{#3}{audio}{%
        \begin{BlockClass}{AVviewport}
    }{%
        \begin{BlockClass}[\LWR@multimedia@printsize\ margin:auto]{AVviewport}
    }
```

Paragraph tags are unnecessary for the A/V tags.

```
    \LWR@stoppars
```

The A/V element is 100% of the container.

```
    \LWR@htmltag{%
        #3\ % space
        \ifstrequal{#3}{audio}{}{%
            width=\textquotedbl{}100\%\textquotedbl\ % space
            height=\textquotedbl{}100\%\textquotedbl\ controls%
        }%
    }\LWR@orignewline
```

The file source and type:

```
    \LWR@htmltag{%
        source % space
        src=\textquotedbl#2\textquotedbl\ % space
        type=\textquotedbl#4\textquotedbl}
```

The poster text inside paragraph tags, along with a reference to the URL.

```
    \LWR@startpars
    \LWR@href{#2}{#1}
    \LWR@stoppars
```

Finish.

```
    \LWR@htmltag{/#3}\LWR@orignewline
    \end{BlockClass}
}
```

Star to italicize the result, used when the unicode character does not exist.

```
\begin{warpMathJax}

\NewDocumentCommand{\LWR@mathjax@addletter}{s m m m m m}{
    \IfBooleanTF{#2}%
        {\edef\LWR@tempone{\LWRtexttitlecase{#5}}}%
        {\edef\LWR@tempone{#5}}%
    \xdef\LWR@customizedMathJax{%
        \LWR@customizedMathJax%
        \LWRbackslash(%
        \LWRbackslash def\LWRbackslash%
        #3% prefix
        \LWR@tempone%name
        #4% postfix
        \LWRleftbrace%
    }%
    \IfBooleanTF{#1}{%
        \xdef\LWR@customizedMathJax{%
            \LWR@customizedMathJax%
            \LWRbackslash mathit\LWRleftbrace%
            \LWRbackslash unicode\LWRleftbrace x#6\LWRrightbrace%
            \LWRrightbrace%
        }%
    }{%
        \xdef\LWR@customizedMathJax{%
            \LWR@customizedMathJax%
            \LWRbackslash unicode\LWRleftbrace x#6\LWRrightbrace%
        }%
    }%
    \xdef\LWR@customizedMathJax{%
        \LWR@customizedMathJax%
        \LWRrightbrace\LWRbackslash)\par%
    }%
}
```

* {⟨*2: prefix*⟩} {⟨*3: postfix*⟩}

\LWR@mathjax@addgreek@l@up

Star to capitalize the macro names.

Adds \CustomizeMathjax expressions to define a set of macros for Greek letters, lowercase upright.

```
\NewDocumentCommand{\LWR@mathjax@addgreek@l@up}{s m m}{
    \LWR@mathjax@addletter{#1}{#2}{#3}{alpha}{03B1}
    \LWR@mathjax@addletter{#1}{#2}{#3}{beta}{03B2}
    \LWR@mathjax@addletter{#1}{#2}{#3}{varbeta}{03D0}
    \LWR@mathjax@addletter{#1}{#2}{#3}{gamma}{03B3}
    \LWR@mathjax@addletter{#1}{#2}{#3}{digamma}{03DD}
    \LWR@mathjax@addletter{#1}{#2}{#3}{delta}{03B4}
    \LWR@mathjax@addletter{#1}{#2}{#3}{epsilon}{03F5}
    \LWR@mathjax@addletter{#1}{#2}{#3}{varepsilon}{03B5}
    \LWR@mathjax@addletter{#1}{#2}{#3}{zeta}{03B6}
    \LWR@mathjax@addletter{#1}{#2}{#3}{eta}{03B7}
    \LWR@mathjax@addletter{#1}{#2}{#3}{theta}{03B8}
    \LWR@mathjax@addletter{#1}{#2}{#3}{vartheta}{03D1}
    \LWR@mathjax@addletter{#1}{#2}{#3}{iota}{03B9}
```

```
    \LWR@mathjax@addletter{#1}{#2}{#3}{kappa}{03BA}
    \LWR@mathjax@addletter{#1}{#2}{#3}{varkappa}{03F0}
    \LWR@mathjax@addletter{#1}{#2}{#3}{lambda}{03BB}
    \LWR@mathjax@addletter{#1}{#2}{#3}{mu}{03BC}
    \LWR@mathjax@addletter{#1}{#2}{#3}{nu}{03BD}
    \LWR@mathjax@addletter{#1}{#2}{#3}{xi}{03BE}
    \LWR@mathjax@addletter{#1}{#2}{#3}{omicron}{03BF}
    \LWR@mathjax@addletter{#1}{#2}{#3}{pi}{03C0}
    \LWR@mathjax@addletter{#1}{#2}{#3}{varpi}{03D6}
    \LWR@mathjax@addletter{#1}{#2}{#3}{rho}{03C1}
    \LWR@mathjax@addletter{#1}{#2}{#3}{varrho}{03F1}
    \LWR@mathjax@addletter{#1}{#2}{#3}{sigma}{03C3}
    \LWR@mathjax@addletter{#1}{#2}{#3}{varsigma}{03C2}
    \LWR@mathjax@addletter{#1}{#2}{#3}{tau}{03C4}
    \LWR@mathjax@addletter{#1}{#2}{#3}{upsilon}{03C5}
    \LWR@mathjax@addletter{#1}{#2}{#3}{phi}{03D5}
    \LWR@mathjax@addletter{#1}{#2}{#3}{varphi}{03C6}
    \LWR@mathjax@addletter{#1}{#2}{#3}{chi}{03C7}
    \LWR@mathjax@addletter{#1}{#2}{#3}{psi}{03C8}
    \LWR@mathjax@addletter{#1}{#2}{#3}{omega}{03C9}
}
```

* {⟨*2: prefix*⟩} {⟨*3: postfix*⟩}

\LWR@mathjax@addgreek@u@up

Star to capitalize the macro names.

Adds \CustomizeMathjax expressions to define a set of macros for Greek letters, uppercase upright.

```
\NewDocumentCommand{\LWR@mathjax@addgreek@u@up}{s m m}{
    \LWR@mathjax@addletter{#1}{#2}{#3}{alpha}{0391}
    \LWR@mathjax@addletter{#1}{#2}{#3}{beta}{0392}
    \LWR@mathjax@addletter{#1}{#2}{#3}{gamma}{0393}
    \LWR@mathjax@addletter{#1}{#2}{#3}{digamma}{03DC}
    \LWR@mathjax@addletter{#1}{#2}{#3}{delta}{0394}
    \LWR@mathjax@addletter{#1}{#2}{#3}{epsilon}{0395}
    \LWR@mathjax@addletter{#1}{#2}{#3}{zeta}{0396}
    \LWR@mathjax@addletter{#1}{#2}{#3}{eta}{0397}
    \LWR@mathjax@addletter{#1}{#2}{#3}{theta}{0398}
    \LWR@mathjax@addletter{#1}{#2}{#3}{vartheta}{03F4}
    \LWR@mathjax@addletter{#1}{#2}{#3}{iota}{0399}
    \LWR@mathjax@addletter{#1}{#2}{#3}{kappa}{039A}
    \LWR@mathjax@addletter{#1}{#2}{#3}{lambda}{039B}
    \LWR@mathjax@addletter{#1}{#2}{#3}{mu}{039C}
    \LWR@mathjax@addletter{#1}{#2}{#3}{nu}{039D}
    \LWR@mathjax@addletter{#1}{#2}{#3}{xi}{039E}
    \LWR@mathjax@addletter{#1}{#2}{#3}{omicron}{039F}
    \LWR@mathjax@addletter{#1}{#2}{#3}{pi}{03A0}
    \LWR@mathjax@addletter{#1}{#2}{#3}{varpi}{03D6}
    \LWR@mathjax@addletter{#1}{#2}{#3}{rho}{03A1}
    \LWR@mathjax@addletter{#1}{#2}{#3}{sigma}{03A3}
    \LWR@mathjax@addletter{#1}{#2}{#3}{tau}{03A4}
    \LWR@mathjax@addletter{#1}{#2}{#3}{upsilon}{03A5}
    \LWR@mathjax@addletter{#1}{#2}{#3}{phi}{03A6}
    \LWR@mathjax@addletter{#1}{#2}{#3}{chi}{03A7}
    \LWR@mathjax@addletter{#1}{#2}{#3}{psi}{03A8}
```

```
    \LWR@mathjax@addletter{#1}{#2}{#3}{omega}{03A9}
}
```

* {⟨*2: prefix*⟩} {⟨*3: postfix*⟩}

\LWR@mathjax@addgreek@l@it

Star to capitalize the macro names.

Adds \CustomizeMathjax expressions to define a set of macros for Greek letters, lowercase italic.

```
\NewDocumentCommand{\LWR@mathjax@addgreek@l@it}{s m m}{
    \LWR@mathjax@addletter{#1}{#2}{#3}{alpha}{1D6FC}
    \LWR@mathjax@addletter{#1}{#2}{#3}{beta}{1D6FD}
    \LWR@mathjax@addletter{#1}{#2}{#3}{varbeta}{03D0}
    \LWR@mathjax@addletter{#1}{#2}{#3}{gamma}{1D6FE}
    \LWR@mathjax@addletter*{#1}{#2}{#3}{digamma}{03DD}
    \LWR@mathjax@addletter{#1}{#2}{#3}{delta}{1D6FF}
    \LWR@mathjax@addletter{#1}{#2}{#3}{epsilon}{1D716}
    \LWR@mathjax@addletter{#1}{#2}{#3}{varepsilon}{1D700}
    \LWR@mathjax@addletter{#1}{#2}{#3}{zeta}{1D701}
    \LWR@mathjax@addletter{#1}{#2}{#3}{eta}{1D702}
    \LWR@mathjax@addletter{#1}{#2}{#3}{theta}{1D703}
    \LWR@mathjax@addletter{#1}{#2}{#3}{vartheta}{1D717}
    \LWR@mathjax@addletter{#1}{#2}{#3}{iota}{1D704}
    \LWR@mathjax@addletter{#1}{#2}{#3}{kappa}{1D705}
    \LWR@mathjax@addletter{#1}{#2}{#3}{varkappa}{1D718}
    \LWR@mathjax@addletter{#1}{#2}{#3}{lambda}{1D706}
    \LWR@mathjax@addletter{#1}{#2}{#3}{mu}{1D707}
    \LWR@mathjax@addletter{#1}{#2}{#3}{nu}{1D708}
    \LWR@mathjax@addletter{#1}{#2}{#3}{xi}{1D709}
    \LWR@mathjax@addletter{#1}{#2}{#3}{omicron}{1D70A}
    \LWR@mathjax@addletter{#1}{#2}{#3}{pi}{1D70B}
    \LWR@mathjax@addletter{#1}{#2}{#3}{varpi}{1D71B}
    \LWR@mathjax@addletter{#1}{#2}{#3}{rho}{1D70C}
    \LWR@mathjax@addletter{#1}{#2}{#3}{varrho}{1D71A}
    \LWR@mathjax@addletter{#1}{#2}{#3}{sigma}{1D70E}
    \LWR@mathjax@addletter{#1}{#2}{#3}{varsigma}{1D70D}
    \LWR@mathjax@addletter{#1}{#2}{#3}{tau}{1D70F}
    \LWR@mathjax@addletter{#1}{#2}{#3}{upsilon}{1D710}
    \LWR@mathjax@addletter{#1}{#2}{#3}{phi}{1D719}
    \LWR@mathjax@addletter{#1}{#2}{#3}{varphi}{1D711}
    \LWR@mathjax@addletter{#1}{#2}{#3}{chi}{1D712}
    \LWR@mathjax@addletter{#1}{#2}{#3}{psi}{1D713}
    \LWR@mathjax@addletter{#1}{#2}{#3}{omega}{1D714}
}
```

* {⟨*2: prefix*⟩} {⟨*3: postfix*⟩}

\LWR@mathjax@addgreek@u@it

Star to capitalize the macro names.

Adds \CustomizeMathjax expressions to define a set of macros for Greek letters, uppercase italic.

```
\NewDocumentCommand{\LWR@mathjax@addgreek@u@it}{s m m}{
    \LWR@mathjax@addletter{#1}{#2}{#3}{alpha}{1D6E2}
    \LWR@mathjax@addletter{#1}{#2}{#3}{beta}{1D6E3}
    \LWR@mathjax@addletter{#1}{#2}{#3}{gamma}{1D6E4}
```

```
    \LWR@mathjax@addletter*{#1}{#2}{#3}{digamma}{03DC}
    \LWR@mathjax@addletter{#1}{#2}{#3}{delta}{1D6E5}
    \LWR@mathjax@addletter{#1}{#2}{#3}{epsilon}{1D6E6}
    \LWR@mathjax@addletter{#1}{#2}{#3}{zeta}{1D6E7}
    \LWR@mathjax@addletter{#1}{#2}{#3}{eta}{1D6E8}
    \LWR@mathjax@addletter{#1}{#2}{#3}{theta}{1D6E9}
    \LWR@mathjax@addletter{#1}{#2}{#3}{vartheta}{1D6F3}
    \LWR@mathjax@addletter{#1}{#2}{#3}{iota}{1D6EA}
    \LWR@mathjax@addletter{#1}{#2}{#3}{kappa}{1D6EB}
    \LWR@mathjax@addletter{#1}{#2}{#3}{lambda}{1D6EC}
    \LWR@mathjax@addletter{#1}{#2}{#3}{mu}{1D6ED}
    \LWR@mathjax@addletter{#1}{#2}{#3}{nu}{1D6EE}
    \LWR@mathjax@addletter{#1}{#2}{#3}{xi}{1D6EF}
    \LWR@mathjax@addletter{#1}{#2}{#3}{omicron}{1D6F0}
    \LWR@mathjax@addletter{#1}{#2}{#3}{pi}{1D6F1}
    \LWR@mathjax@addletter{#1}{#2}{#3}{rho}{1D6F2}
    \LWR@mathjax@addletter{#1}{#2}{#3}{sigma}{1D6F4}
    \LWR@mathjax@addletter{#1}{#2}{#3}{tau}{1D6F5}
    \LWR@mathjax@addletter{#1}{#2}{#3}{upsilon}{1D6F6}
    \LWR@mathjax@addletter{#1}{#2}{#3}{phi}{1D6F7}
    \LWR@mathjax@addletter{#1}{#2}{#3}{chi}{1D6F8}
    \LWR@mathjax@addletter{#1}{#2}{#3}{psi}{1D6F9}
    \LWR@mathjax@addletter{#1}{#2}{#3}{omega}{1D6FA}
}
```

* {⟨*2: prefix*⟩} {⟨*3: postfix*⟩}

\LWR@mathjax@addgreek@l@bfit

Star to capitalize the macro names.

Adds \CustomizeMathjax expressions to define a set of macros for Greek letters, lowercase boldface italic.

```
\NewDocumentCommand{\LWR@mathjax@addgreek@l@bfit}{s m m}{
    \LWR@mathjax@addletter{#1}{#2}{#3}{alpha}{1D736}
    \LWR@mathjax@addletter{#1}{#2}{#3}{beta}{1D737}
    \LWR@mathjax@addletter{#1}{#2}{#3}{varbeta}{03D0}
    \LWR@mathjax@addletter{#1}{#2}{#3}{gamma}{1D738}
    \LWR@mathjax@addletter*{#1}{#2}{#3}{digamma}{03DD}
    \LWR@mathjax@addletter{#1}{#2}{#3}{delta}{1D739}
    \LWR@mathjax@addletter{#1}{#2}{#3}{epsilon}{1D750}
    \LWR@mathjax@addletter{#1}{#2}{#3}{varepsilon}{1D73A}
    \LWR@mathjax@addletter{#1}{#2}{#3}{zeta}{1D73B}
    \LWR@mathjax@addletter{#1}{#2}{#3}{eta}{1D73C}
    \LWR@mathjax@addletter{#1}{#2}{#3}{theta}{1D73D}
    \LWR@mathjax@addletter{#1}{#2}{#3}{vartheta}{1D751}
    \LWR@mathjax@addletter{#1}{#2}{#3}{iota}{1D73E}
    \LWR@mathjax@addletter{#1}{#2}{#3}{kappa}{1D73F}
    \LWR@mathjax@addletter{#1}{#2}{#3}{varkappa}{1D752}
    \LWR@mathjax@addletter{#1}{#2}{#3}{lambda}{1D740}
    \LWR@mathjax@addletter{#1}{#2}{#3}{mu}{1D741}
    \LWR@mathjax@addletter{#1}{#2}{#3}{nu}{1D742}
    \LWR@mathjax@addletter{#1}{#2}{#3}{xi}{1D743}
    \LWR@mathjax@addletter{#1}{#2}{#3}{omicron}{1D744}
    \LWR@mathjax@addletter{#1}{#2}{#3}{pi}{1D745}
    \LWR@mathjax@addletter{#1}{#2}{#3}{varpi}{1D755}
    \LWR@mathjax@addletter{#1}{#2}{#3}{rho}{1D746}
```

```
    \LWR@mathjax@addletter{#1}{#2}{#3}{varrho}{1D754}
    \LWR@mathjax@addletter{#1}{#2}{#3}{sigma}{1D748}
    \LWR@mathjax@addletter{#1}{#2}{#3}{varsigma}{1D747}
    \LWR@mathjax@addletter{#1}{#2}{#3}{tau}{1D749}
    \LWR@mathjax@addletter{#1}{#2}{#3}{upsilon}{1D74A}
    \LWR@mathjax@addletter{#1}{#2}{#3}{phi}{1D753}
    \LWR@mathjax@addletter{#1}{#2}{#3}{varphi}{1D74B}
    \LWR@mathjax@addletter{#1}{#2}{#3}{chi}{1D74C}
    \LWR@mathjax@addletter{#1}{#2}{#3}{psi}{1D74D}
    \LWR@mathjax@addletter{#1}{#2}{#3}{omega}{1D74E}
}
```

* {⟨*2: prefix*⟩} {⟨*3: postfix*⟩}

\LWR@mathjax@addgreek@u@bfit

Star to capitalize the macro names.

Adds \CustomizeMathjax expressions to define a set of macros for Greek letters, uppercase boldface italic.

```
\NewDocumentCommand{\LWR@mathjax@addgreek@u@bfit}{s m m}{
    \LWR@mathjax@addletter{#1}{#2}{#3}{alpha}{1D71C}
    \LWR@mathjax@addletter{#1}{#2}{#3}{beta}{1D71D}
    \LWR@mathjax@addletter{#1}{#2}{#3}{gamma}{1D71E}
    \LWR@mathjax@addletter*{#1}{#2}{#3}{digamma}{03DC}
    \LWR@mathjax@addletter{#1}{#2}{#3}{delta}{1D71F}
    \LWR@mathjax@addletter{#1}{#2}{#3}{epsilon}{1D720}
    \LWR@mathjax@addletter{#1}{#2}{#3}{zeta}{1D721}
    \LWR@mathjax@addletter{#1}{#2}{#3}{eta}{1D722}
    \LWR@mathjax@addletter{#1}{#2}{#3}{theta}{1D723}
    \LWR@mathjax@addletter{#1}{#2}{#3}{vartheta}{1D72D}
    \LWR@mathjax@addletter{#1}{#2}{#3}{iota}{1D724}
    \LWR@mathjax@addletter{#1}{#2}{#3}{kappa}{1D725}
    \LWR@mathjax@addletter{#1}{#2}{#3}{lambda}{1D726}
    \LWR@mathjax@addletter{#1}{#2}{#3}{mu}{1D727}
    \LWR@mathjax@addletter{#1}{#2}{#3}{nu}{1D728}
    \LWR@mathjax@addletter{#1}{#2}{#3}{xi}{1D729}
    \LWR@mathjax@addletter{#1}{#2}{#3}{omicron}{1D72A}
    \LWR@mathjax@addletter{#1}{#2}{#3}{pi}{1D72B}
    \LWR@mathjax@addletter{#1}{#2}{#3}{rho}{1D72C}
    \LWR@mathjax@addletter{#1}{#2}{#3}{sigma}{1D72E}
    \LWR@mathjax@addletter{#1}{#2}{#3}{tau}{1D72F}
    \LWR@mathjax@addletter{#1}{#2}{#3}{upsilon}{1D730}
    \LWR@mathjax@addletter{#1}{#2}{#3}{phi}{1D731}
    \LWR@mathjax@addletter{#1}{#2}{#3}{chi}{1D732}
    \LWR@mathjax@addletter{#1}{#2}{#3}{psi}{1D733}
    \LWR@mathjax@addletter{#1}{#2}{#3}{omega}{1D734}
}
```

\LWR@mathjax@addgreek@u@bfup is not needed.

* {⟨*2: prefix*⟩} {⟨*3: postfix*⟩}

\LWR@mathjax@addgreek@u@bfup

Star to capitalize the macro names.

Adds \CustomizeMathjax expressions to define a set of macros for Greek letters, uppercase boldface upright.

```
\NewDocumentCommand{\LWR@mathjax@addgreek@u@bfup}{s m m}{
```

```
    \LWR@mathjax@addletter{#1}{#2}{#3}{alpha}{1D6A8}
    \LWR@mathjax@addletter{#1}{#2}{#3}{beta}{1D6A9}
    \LWR@mathjax@addletter{#1}{#2}{#3}{gamma}{1D6AA}
    \LWR@mathjax@addletter*{#1}{#2}{#3}{digamma}{03DC}
    \LWR@mathjax@addletter{#1}{#2}{#3}{delta}{1D6AB}
    \LWR@mathjax@addletter{#1}{#2}{#3}{epsilon}{1D6AC}
    \LWR@mathjax@addletter{#1}{#2}{#3}{zeta}{1D6AD}
    \LWR@mathjax@addletter{#1}{#2}{#3}{eta}{1D6AE}
    \LWR@mathjax@addletter{#1}{#2}{#3}{theta}{1D6AF}
    \LWR@mathjax@addletter{#1}{#2}{#3}{vartheta}{1D6B9}
    \LWR@mathjax@addletter{#1}{#2}{#3}{iota}{1D6B0}
    \LWR@mathjax@addletter{#1}{#2}{#3}{kappa}{1D6B1}
    \LWR@mathjax@addletter{#1}{#2}{#3}{lambda}{1D6B2}
    \LWR@mathjax@addletter{#1}{#2}{#3}{mu}{1D6B3}
    \LWR@mathjax@addletter{#1}{#2}{#3}{nu}{1D6B4}
    \LWR@mathjax@addletter{#1}{#2}{#3}{xi}{1D6B5}
    \LWR@mathjax@addletter{#1}{#2}{#3}{omicron}{1D6B6}
    \LWR@mathjax@addletter{#1}{#2}{#3}{pi}{1D6B7}
    \LWR@mathjax@addletter{#1}{#2}{#3}{rho}{1D6B8}
    \LWR@mathjax@addletter{#1}{#2}{#3}{sigma}{1D6BA}
    \LWR@mathjax@addletter{#1}{#2}{#3}{tau}{1D6BB}
    \LWR@mathjax@addletter{#1}{#2}{#3}{upsilon}{1D6BC}
    \LWR@mathjax@addletter{#1}{#2}{#3}{phi}{1D6BD}
    \LWR@mathjax@addletter{#1}{#2}{#3}{chi}{1D6BE}
    \LWR@mathjax@addletter{#1}{#2}{#3}{psi}{1D6BF}
    \LWR@mathjax@addletter{#1}{#2}{#3}{omega}{1D6C0}
}
```

{⟨*prefix*⟩}

`\LWR@mathjax@addlatin@u@bfit`

Adds `\CustomizeMathjax` expressions to define a set of macros for bold-face italic Latin letters, uppercase and lowercase.

```
\NewDocumentCommand{\LWR@mathjax@addlatin@u@bfit}{m}{
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{A}{1D468}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{B}{1D469}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{C}{1D46A}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{D}{1D46B}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{E}{1D46C}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{F}{1D46D}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{G}{1D46E}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{H}{1D46F}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{I}{1D470}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{J}{1D471}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{K}{1D472}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{L}{1D473}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{M}{1D474}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{N}{1D475}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{O}{1D476}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{P}{1D477}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{Q}{1D478}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{R}{1D479}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{S}{1D47A}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{T}{1D47B}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{U}{1D47C}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{V}{1D47D}
```

```
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{W}{1D47E}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{X}{1D47F}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{Y}{1D480}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{Z}{1D481}
}
```

{⟨*prefix*⟩}

\LWR@mathjax@addlatin@l@bfit

Adds \CustomizeMathjax expressions to define a set of macros for bold-face italic Latin letters, uppercase and lowercase.

```
\NewDocumentCommand{\LWR@mathjax@addlatin@l@bfit}{m}{
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{a}{1D482}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{b}{1D483}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{c}{1D484}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{d}{1D485}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{e}{1D486}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{f}{1D487}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{g}{1D488}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{h}{1D489}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{i}{1D48A}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{j}{1D48B}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{k}{1D48C}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{l}{1D48D}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{m}{1D48E}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{n}{1D48F}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{o}{1D490}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{p}{1D491}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{q}{1D492}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{r}{1D493}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{s}{1D494}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{t}{1D495}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{u}{1D496}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{v}{1D497}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{w}{1D498}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{x}{1D499}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{y}{1D49A}
    \LWR@mathjax@addletter{\BooleanFalse}{#1}{}{z}{1D49B}
}

\end{warpMathJax}
```

---

File 567 **lwarp-common-mathjax-newpxtxmath.sty**

# § 674 Package common-mathjax-newpxtxmath

(*Emulates or patches code by* Michael Sharpe.)

Pkg lwarp-common-mathjax-newpxtxmath

Common code used by newpxmath, newtxmath, and newtxsf for MathJax.

**for HTML output:**

```
\ProvidesPackage{lwarp-common-mathjax-newpxtxmath}[2020/09/20]
```

For MathJax:

```
\CustomizeMathJax{\let\smallintup\smallint}
\CustomizeMathJax{\newcommand{\smalliintup}{\mathop{\unicode{x222C}}\limits}}
\CustomizeMathJax{\newcommand{\smalliiintup}{\mathop{\unicode{x222D}}\limits}}
\CustomizeMathJax{\newcommand{\smalliiiintup}{\mathop{\unicode{x2A0C}}\limits}}
\CustomizeMathJax{\newcommand{\smallointup}{\mathop{\unicode{x222E}}\limits}}
\CustomizeMathJax{\newcommand{\smalloiintup}{\mathop{\unicode{x222F}}\limits}}
\CustomizeMathJax{\newcommand{\smalloiiintup}{\mathop{\unicode{x2230}}\limits}}
\CustomizeMathJax{\newcommand{\smallvarointclockwiseup}{\mathop{\unicode{x2232}}\limits}}
\CustomizeMathJax{\newcommand{\smallointctrclockwiseup}{\mathop{\unicode{x2233}}\limits}}
\CustomizeMathJax{\newcommand{\smallsumintup}{\mathop{\unicode{x2A0B}}\limits}}
\CustomizeMathJax{\newcommand{\smallfintup}{\mathop{\unicode{x2A0F}}\limits}}
\CustomizeMathJax{\newcommand{\smallsqintup}{\mathop{\unicode{x2A16}}\limits}}
%
\CustomizeMathJax{\newcommand{\iint}{\mathop{\unicode{x222C}}\limits}}
\CustomizeMathJax{\newcommand{\iiint}{\mathop{\unicode{x222D}}\limits}}
\CustomizeMathJax{\newcommand{\iiiint}{\mathop{\unicode{x2A0C}}\limits}}
\CustomizeMathJax{\newcommand{\oiint}{\mathop{\unicode{x222F}}\limits}}
\CustomizeMathJax{\newcommand{\oiiint}{\mathop{\unicode{x2230}}\limits}}
\CustomizeMathJax{\newcommand{\varointclockwise}{\mathop{\unicode{x2232}}\limits}}
\CustomizeMathJax{\newcommand{\ointctrclockwise}{\mathop{\unicode{x2233}}\limits}}
\CustomizeMathJax{\newcommand{\sumint}{\mathop{\unicode{x2A0B}}\limits}}
\CustomizeMathJax{\newcommand{\fint}{\mathop{\unicode{x2A0F}}\limits}}
\CustomizeMathJax{\newcommand{\sqint}{\mathop{\unicode{x2A16}}\limits}}
%
\CustomizeMathJax{\let\intsl\int}
\CustomizeMathJax{\newcommand{\iintsl}{\mathop{\unicode{x222C}}\limits}}
\CustomizeMathJax{\newcommand{\iiintsl}{\mathop{\unicode{x222D}}\limits}}
\CustomizeMathJax{\newcommand{\iiiintsl}{\mathop{\unicode{x2A0C}}\limits}}
\CustomizeMathJax{\let\ointsl\oint}
\CustomizeMathJax{\newcommand{\oiintsl}{\mathop{\unicode{x222F}}\limits}}
\CustomizeMathJax{\newcommand{\oiiintsl}{\mathop{\unicode{x2230}}\limits}}
\CustomizeMathJax{\newcommand{\varointclockwisesl}{\mathop{\unicode{x2232}}\limits}}
\CustomizeMathJax{\newcommand{\ointctrclockwisesl}{\mathop{\unicode{x2233}}\limits}}
\CustomizeMathJax{\newcommand{\sumintsl}{\mathop{\unicode{x2A0B}}\limits}}
\CustomizeMathJax{\newcommand{\fintsl}{\mathop{\unicode{x2A0F}}\limits}}
\CustomizeMathJax{\newcommand{\sqintsl}{\mathop{\unicode{x2A16}}\limits}}
%
\CustomizeMathJax{\let\intup\int}
\CustomizeMathJax{\newcommand{\iintup}{\mathop{\unicode{x222C}}\limits}}
\CustomizeMathJax{\newcommand{\iiintup}{\mathop{\unicode{x222D}}\limits}}
\CustomizeMathJax{\newcommand{\iiiintup}{\mathop{\unicode{x2A0C}}\limits}}
\CustomizeMathJax{\let\ointup\oint}
\CustomizeMathJax{\newcommand{\oiintup}{\mathop{\unicode{x222F}}\limits}}
\CustomizeMathJax{\newcommand{\oiiintup}{\mathop{\unicode{x2230}}\limits}}
\CustomizeMathJax{\newcommand{\varointclockwiseup}{\mathop{\unicode{x2232}}\limits}}
\CustomizeMathJax{\newcommand{\ointctrclockwiseup}{\mathop{\unicode{x2233}}\limits}}
\CustomizeMathJax{\newcommand{\sumintup}{\mathop{\unicode{x2A0B}}\limits}}
\CustomizeMathJax{\newcommand{\fintup}{\mathop{\unicode{x2A0F}}\limits}}
\CustomizeMathJax{\newcommand{\sqintup}{\mathop{\unicode{x2A16}}\limits}}
%
\CustomizeMathJax{\newcommand{\bigcupdot}{\mathop{\unicode{x2A03}}}}
\CustomizeMathJax{\newcommand{\bigcupplus}{\mathop{\unicode{x2A04}}}}
\CustomizeMathJax{\newcommand{\bigsqcap}{\mathop{\unicode{x2A05}}}}
%
```

```
%
\CustomizeMathJax{\newcommand{\bigtimes}{\mathop{\unicode{x2A09}}}}
\CustomizeMathJax{\let\varprod\bigtimes}
%

\CustomizeMathJax{\newcommand{\mappedfrom}{\mathrel{\unicode{x021A4}}}}
\CustomizeMathJax{\let\mappedfromchar\mappedfrom}
\CustomizeMathJax{\newcommand{\mapsfrom}{\mathrel{\unicode{x021A4}}}}
\CustomizeMathJax{\newcommand{\longmappedfrom}{\mathrel{\unicode{x027FB}}}}
%
\CustomizeMathJax{\newcommand{\Mapsto}{\mathrel{\unicode{x02907}}}}
\CustomizeMathJax{\let\Mapstochar\Mapsto}
\CustomizeMathJax{\newcommand{\Longmapsto}{\mathrel{\unicode{x027FE}}}}
\CustomizeMathJax{\newcommand{\Mappedfrom}{\mathrel{\unicode{x02906}}}}
\CustomizeMathJax{\let\Mappedfromchar\Mappedfrom}
\CustomizeMathJax{\newcommand{\Mapsfrom}{\mathrel{\unicode{x02906}}}}
\CustomizeMathJax{\newcommand{\Longmappedfrom}{\mathrel{\unicode{x27FD}}}}
%

\CustomizeMathJax{\newcommand{\medcirc}{\mathbin{\unicode{x025CB}}}}
\CustomizeMathJax{\newcommand{\medbullet}{\mathbin{\unicode{x025CF}}}}
\CustomizeMathJax{\newcommand{\varparallel}{\mathrel{\unicode{x02AFD}}}}
\CustomizeMathJax{\newcommand{\varparallelinv}{\mathrel{\unicode{x244A}}}}
\CustomizeMathJax{\newcommand{\nvarparallel}{\mathrel{\LWRoverlaysymbols{-}{\unicode{x02AFD}}}}}
\CustomizeMathJax{\newcommand{\nvarparallelinv}{\mathrel{\LWRoverlaysymbols{-}{\unicode{x244A}}}}}
%

\CustomizeMathJax{\newcommand{\coloneq}{\mathrel{\unicode{x02254}}}}
\CustomizeMathJax{\newcommand{\eqcolon}{\mathrel{\unicode{x02255}}}}
%
\CustomizeMathJax{\newcommand{\VDash}{\mathrel{\unicode{x22AB}}}}

%
\CustomizeMathJax{\newcommand{\preceqq}{\mathrel{\unicode{x02AB3}}}}
\CustomizeMathJax{\newcommand{\succeqq}{\mathrel{\unicode{x02AB4}}}}
%

\CustomizeMathJax{\newcommand{\nprecsim}{\mathrel{\LWRoverlaysymbols{/}{\unicode{x0227E}}}}}
\CustomizeMathJax{\newcommand{\nsuccsim}{\mathrel{\LWRoverlaysymbols{/}{\unicode{x0227F}}}}}
\CustomizeMathJax{\newcommand{\nlesssim}{\mathrel{\unicode{x02274}}}}
\CustomizeMathJax{\newcommand{\ngtrsim}{\mathrel{\unicode{x02275}}}}
%

\CustomizeMathJax{\newcommand{\nsubset}{\mathrel{\unicode{x02284}}}}
\CustomizeMathJax{\newcommand{\nsupset}{\mathrel{\unicode{x02285}}}}
\CustomizeMathJax{\newcommand{\notni}{\mathrel{\unicode{x220C}}}}
\CustomizeMathJax{\let\notowns\notni}
%
\CustomizeMathJax{\newcommand{\nlessapprox}{\mathrel{\LWRoverlaysymbols{/}{\unicode{x02A85}}}}}
\CustomizeMathJax{\newcommand{\ngtrapprox}{\mathrel{\LWRoverlaysymbols{/}{\unicode{x02A86}}}}}
%
\CustomizeMathJax{\newcommand{\npreccurlyeq}{\mathrel{\LWRoverlaysymbols{/}{\unicode{x0227C}}}}}
```

```
\CustomizeMathJax{\newcommand{\nsucccurlyeq}{\mathrel{\LWRoverlaysymbols{/}{\unicode{x0227D}}}}}
\CustomizeMathJax{\newcommand{\ngtrless}{\mathrel{\unicode{x02279}}}}
\CustomizeMathJax{\newcommand{\nlessgtr}{\mathrel{\unicode{x2278}}}}
\CustomizeMathJax{\newcommand{\nbumpeq}{\mathrel{\LWRoverlaysymbols{/}{\unicode{x0224F}}}}}
\CustomizeMathJax{\newcommand{\nBumpeq}{\mathrel{\LWRoverlaysymbols{/}{\unicode{x0224E}}}}}
%
\CustomizeMathJax{\newcommand{\nbacksim}{\mathrel{\LWRoverlaysymbols{/}{\unicode{x0223D}}}}}
\CustomizeMathJax{\newcommand{\nbacksimeq}{\mathrel{\LWRoverlaysymbols{/}{\unicode{x022CD}}}}}
\CustomizeMathJax{\newcommand{\nasymp}{\mathrel{\unicode{x226D}}}}
\CustomizeMathJax{\newcommand{\nequiv}{\mathrel{\unicode{x2262}}}}
\CustomizeMathJax{\newcommand{\napprox}{\mathrel{\unicode{x2249}}}}
%
\CustomizeMathJax{\newcommand{\nll}{\mathrel{\LWRoverlaysymbols{/}{\unicode{x0226A}}}}}
\CustomizeMathJax{\newcommand{\ngg}{\mathrel{\LWRoverlaysymbols{/}{\unicode{x0226B}}}}}
\CustomizeMathJax{\newcommand{\nthickapprox}{%
    \mathrel{\LWRoverlaysymbols{/}{{\mathbf{\unicode{x02248}}}}}%
}}
\CustomizeMathJax{\newcommand{\napproxeq}{\mathrel{\LWRoverlaysymbols{/}{\unicode{x0224A}}}}}
\CustomizeMathJax{\newcommand{\nprecapprox}{\mathrel{\LWRoverlaysymbols{/}{\unicode{x02AB7}}}}}
\CustomizeMathJax{\newcommand{\nsuccapprox}{\mathrel{\LWRoverlaysymbols{/}{\unicode{x02AB8}}}}}
\CustomizeMathJax{\newcommand{\npreceqq}{\mathrel{\LWRoverlaysymbols{/}{\unicode{x02AB3}}}}}
\CustomizeMathJax{\newcommand{\nsucceqq}{\mathrel{\LWRoverlaysymbols{/}{\unicode{x02AB4}}}}}
\CustomizeMathJax{\newcommand{\nsimeq}{\mathrel{\unicode{x02244}}}}
%
\CustomizeMathJax{\newcommand{\nSubset}{\mathrel{\LWRoverlaysymbols{/}{\unicode{x022D0}}}}}
\CustomizeMathJax{\newcommand{\nSupset}{\mathrel{\LWRoverlaysymbols{/}{\unicode{x022D1}}}}}
\CustomizeMathJax{\newcommand{\nsqsubseteq}{\mathrel{\unicode{x022E2}}}}
\CustomizeMathJax{\newcommand{\nsqsupseteq}{\mathrel{\unicode{x022E3}}}}
%
\CustomizeMathJax{\newcommand{\coloneqq}{\mathrel{\unicode{x02254}}}}
\CustomizeMathJax{\newcommand{\eqqcolon}{\mathrel{\unicode{x02255}}}}
\CustomizeMathJax{\newcommand{\Coloneqq}{\mathrel{\unicode{x02A74}}}}
\CustomizeMathJax{\newcommand{\Coloneq}{\mathrel{\unicode{x2237}-}}}
\CustomizeMathJax{\newcommand{\Eqcolon}{\mathrel{-\unicode{x2237}}}}
%
\CustomizeMathJax{\newcommand{\lvec}[1]{\mathord{\overset{\unicode{x02190}}{#1}}}}
\CustomizeMathJax{\newcommand{\lrvec}[1]{\mathord{\overset{\unicode{x2194}}{#1}}}}
\CustomizeMathJax{\newcommand{\harpoonacc}[1]{\mathord{\overset{\unicode{x021C0}}{#1}}}}
\CustomizeMathJax{\newcommand{\lharpoonacc}[1]{\mathord{\overset{\unicode{x021BC}}{#1}}}}
\CustomizeMathJax{\newcommand{\lrharpoonacc}[1]{\mathord{\overset{\unicode{x0294E}}{#1}}}}
\CustomizeMathJax{\newcommand{\barbar}[1]{\mathord{\overset{=}{#1}}}}
\CustomizeMathJax{\newcommand{\bartilde}[1]{\mathord{\overset{\simeq}{#1}}}}
\CustomizeMathJax{\newcommand{\barhat}[1]{\mathord{\hat{\bar{#1}}}}}
\CustomizeMathJax{\newcommand{\tildebar}[1]{\mathord{\overset{\eqsim}{#1}}}}
\CustomizeMathJax{\newcommand{\tildetilde}[1]{\mathord{\overset{\approx}{#1}}}}
\CustomizeMathJax{\newcommand{\tildehat}[1]{\mathord{\hat{\tilde{#1}}}}}
\CustomizeMathJax{\newcommand{\hatbar}[1]{\mathord{\bar{\hat{#1}}}}}
\CustomizeMathJax{\newcommand{\hattilde}[1]{\mathord{\tilde{\hat{#1}}}}}
\CustomizeMathJax{\newcommand{\hathat}[1]{\mathord{\hat{\hat{#1}}}}}

\CustomizeMathJax{\newcommand{\cdotB}{\mathord{\boldsymbol{\cdot}}}}
\CustomizeMathJax{\newcommand{\cdotBB}{\mathord{\unicode{x2022}}}}
\CustomizeMathJax{\newcommand{\circS}{\boldsymbol{\circ}}}
\CustomizeMathJax{\newcommand{\bulletSSS}{\bullet}}
\CustomizeMathJax{\newcommand{\bulletSS}{\mathord{\unicode{x025CF}}}}
```

```
\CustomizeMathJax{\newcommand{\bulletS}{\mathord{\unicode{x02B24}}}}
\CustomizeMathJax{\newcommand{\primeS}{\prime}}

\CustomizeMathJax{\newcommand{\invamp}{\mathbin{\unicode{x0214B}}}}
```

`lwarp_mathjax.txt` adds `\left`/`\right` support for delimiters.

```
\CustomizeMathJax{\newcommand{\Lbag}{\mathopen{\large\unicode{x027C5}}}}
\CustomizeMathJax{\newcommand{\Rbag}{\mathclose{\large\unicode{x027C6}}}}
\CustomizeMathJax{\newcommand{\circledless}{\mathrel{\unicode{x029C0}}}}
\CustomizeMathJax{\newcommand{\circledgtr}{\mathrel{\unicode{x029C1}}}}
\CustomizeMathJax{\newcommand{\circledbslash}{\mathbin{\unicode{x029B8}}}}


\CustomizeMathJax{\newcommand{\lJoin}{\mathrel{\unicode{x22C9}}}}
\CustomizeMathJax{\newcommand{\rJoin}{\mathrel{\unicode{x22CA}}}}
\CustomizeMathJax{\newcommand{\lrJoin}{\mathrel{\unicode{x2A1D}}}}

\CustomizeMathJax{\newcommand{\lrtimes}{\mathrel{\unicode{x2A1D}}}}
\CustomizeMathJax{\newcommand{\Diamondblack}{\mathord{\unicode{x025C6}}}}
\CustomizeMathJax{\newcommand{\nplus}{\mathrel{\LWRoverlaysymbols{+}{\unicode{x02229}}}}}
\CustomizeMathJax{\newcommand{\nsqsubset}{\mathrel{\LWRoverlaysymbols{/}{\unicode{x0228F}}}}}
\CustomizeMathJax{\newcommand{\nsqsupset}{\mathrel{\LWRoverlaysymbols{/}{\unicode{x02290}}}}}
\CustomizeMathJax{\newcommand{\dasharrow}{\mathrel{\unicode{x021E2}}}}
\CustomizeMathJax{\newcommand{\leftsquigarrow}{\mathrel{\unicode{x021DC}}}}
\CustomizeMathJax{\newcommand{\ntwoheadrightarrow}{\mathrel{\unicode{x02900}}}}
\CustomizeMathJax{\newcommand{\ntwoheadleftarrow}{\mathrel{\unicode{x02B34}}}}
\CustomizeMathJax{\newcommand{\boxast}{\mathbin{\unicode{x029C6}}}}
\CustomizeMathJax{\newcommand{\boxbslash}{\mathbin{\unicode{x29C5}}}}
\CustomizeMathJax{\newcommand{\boxbar}{\mathbin{\unicode{x025EB}}}}
\CustomizeMathJax{\newcommand{\boxslash}{\mathbin{\unicode{x029C4}}}}

\CustomizeMathJax{\newcommand{\varclubsuit}{\mathord{\unicode{x02667}}}}
\CustomizeMathJax{\newcommand{\vardiamondsuit}{\mathord{\unicode{x02666}}}}
\CustomizeMathJax{\newcommand{\varheartsuit}{\mathord{\unicode{x02665}}}}
\CustomizeMathJax{\newcommand{\varspadesuit}{\mathord{\unicode{x02664}}}}

\CustomizeMathJax{\newcommand{\Nearrow}{\mathrel{\unicode{x021D7}}}}
\CustomizeMathJax{\newcommand{\Searrow}{\mathrel{\unicode{x021D8}}}}
\CustomizeMathJax{\newcommand{\Nwarrow}{\mathrel{\unicode{x021D6}}}}
\CustomizeMathJax{\newcommand{\Swarrow}{\mathrel{\unicode{x021D9}}}}
\CustomizeMathJax{\newcommand{\Top}{\mathord{\unicode{x02AEA}}}}
\CustomizeMathJax{\newcommand{\Bot}{\mathord{\unicode{x02AEB}}}}

\CustomizeMathJax{\newcommand{\leadstoext}{\mathrel{\unicode{xFF5E}}}}

\CustomizeMathJax{\newcommand{\sqcupplus}{\mathbin{\LWRoverlaysymbols{+}{\unicode{x02294}}}}}
\CustomizeMathJax{\newcommand{\sqcapplus}{\mathbin{\LWRoverlaysymbols{+}{\unicode{x02293}}}}}

\CustomizeMathJax{\newcommand{\dlb}{\mathopen{\unicode{x027E6}}}}
\CustomizeMathJax{\newcommand{\drb}{\mathopen{\unicode{x027E7}}}}

\CustomizeMathJax{\newcommand{\varg}{g}}
\CustomizeMathJax{\newcommand{\vary}{y}}
\CustomizeMathJax{\newcommand{\varv}{v}}
\CustomizeMathJax{\newcommand{\varw}{w}}
```

```
\CustomizeMathJax{\let\longmmapsfrom\longmmappedfrom}% from kpfonts-otf

\CustomizeMathJax{\newcommand{\Mmapsto}{\mathrel{\unicode{x02907}}}}
\CustomizeMathJax{\let\Mmapstochar\Mmapsto}
\CustomizeMathJax{\newcommand{\Longmmapsto}{\mathrel{\unicode{x027FE}}}}
\CustomizeMathJax{\newcommand{\Mmappedfrom}{\mathrel{\unicode{x02906}}}}
\CustomizeMathJax{\let\Mmappedfromchar\Mmappedfrom}
\CustomizeMathJax{\newcommand{\Longmmappedfrom}{\mathrel{\unicode{x027FD}}}}
\CustomizeMathJax{\let\Mmapsfrom\Mmappedfrom}% from kpfonts-otf
\CustomizeMathJax{\let\Longmmapsfrom\Longmmappedfrom}% from kpfonts-otf
%
\CustomizeMathJax{\newcommand{\boxright}{\mathrel{\unicode{x025A1}\!\unicode{x02192}}}}
\CustomizeMathJax{\newcommand{\boxleft}{\mathrel{\unicode{x02190}\!\unicode{x025A1}}}}
\CustomizeMathJax{\newcommand{\boxdotright}{\mathrel{\unicode{x022A1}\!\unicode{x02192}}}}
\CustomizeMathJax{\newcommand{\boxdotleft}{\mathrel{\unicode{x02190}\!\unicode{x022A1}}}}

\CustomizeMathJax{\newcommand{\Diamondright}{\mathrel{\unicode{x025C7}\!\unicode{x02192}}}}
\CustomizeMathJax{\newcommand{\Diamondleft}{\mathrel{\unicode{x02190}\!\unicode{x025C7}}}}
\CustomizeMathJax{\newcommand{\Diamonddotright}{\mathrel{\unicode{x027D0}\!\unicode{x02192}}}}
\CustomizeMathJax{\newcommand{\Diamonddotleft}{\mathrel{\unicode{x02190}\!\unicode{x027D0}}}}

\CustomizeMathJax{\newcommand{\boxRight}{\mathrel{\unicode{x025A1}\!\unicode{x021D2}}}}
\CustomizeMathJax{\newcommand{\boxLeft}{\mathrel{\unicode{x021D0}\!\unicode{x025A1}}}}
\CustomizeMathJax{\newcommand{\boxdotRight}{\mathrel{\unicode{x022A1}\!\unicode{x021D2}}}}
\CustomizeMathJax{\newcommand{\boxdotLeft}{\mathrel{\unicode{x021D0}\!\unicode{x022A1}}}}

\CustomizeMathJax{\newcommand{\DiamondRight}{\mathrel{\unicode{x025C7}\!\unicode{x021D2}}}}
\CustomizeMathJax{\newcommand{\DiamondLeft}{\mathrel{\unicode{x021D0}\!\unicode{x025C7}}}}
\CustomizeMathJax{\newcommand{\DiamonddotRight}{\mathrel{\unicode{x027D0}\!\unicode{x021D2}}}}
\CustomizeMathJax{\newcommand{\DiamonddotLeft}{\mathrel{\unicode{x021D0}\!\unicode{x027D0}}}}
\CustomizeMathJax{\newcommand{\Diamonddot}{\mathrel{\unicode{x027D0}}}}

\CustomizeMathJax{\newcommand{\circleright}{\mathrel{\unicode{x025CB}\!\unicode{x02192}}}}
\CustomizeMathJax{\newcommand{\circleleft}{\mathrel{\unicode{x02190}\!\unicode{x025CB}}}}
\CustomizeMathJax{\newcommand{\circledotright}{\mathrel{\unicode{x02299}\!\unicode{x02192}}}}
\CustomizeMathJax{\newcommand{\circledotleft}{\mathrel{\unicode{x02190}\!\unicode{x02299}}}}
\CustomizeMathJax{\let\circleddotright\circledotright}
\CustomizeMathJax{\let\circleddotleft\circledotleft}

\CustomizeMathJax{\newcommand{\multimapinv}{\mathrel{\unicode{x027DC}}}}
\CustomizeMathJax{\newcommand{\multimapboth}{\mathrel{\unicode{x029DF}}}}
\CustomizeMathJax{\newcommand{\multimapdot}{{\mathrel{-\!\bullet}}}}
\CustomizeMathJax{\newcommand{\multimapdotinv}{\mathrel{\bullet\!-}}}
\CustomizeMathJax{\newcommand{\multimapdotboth}{\mathrel{{\bullet\!\!-\!\!\bullet}}}}
\CustomizeMathJax{\newcommand{\multimapdotbothA}{\mathrel{\unicode{x022B6}}}}
\CustomizeMathJax{\newcommand{\multimapdotbothB}{\mathrel{\unicode{x22B7}}}}

\CustomizeMathJax{\newcommand{\multimapbothvert}{%
    \mathrel{\overset{\unicode{x025CB}}{\underset{\unicode{x025CB}}{|}}}%
}}
\CustomizeMathJax{\newcommand{\multimapdotbothvert}{%
    \mathrel{\overset{\unicode{x025CF}}{\underset{\unicode{x025CF}}{|}}}%
}}
\CustomizeMathJax{\newcommand{\multimapdotbothBvert}{% bug in kpfonts-otf
    \mathrel{\overset{\unicode{x025CF}}{\underset{\unicode{x025CB}}{|}}}%
```

```
}}
\CustomizeMathJax{\newcommand{\multimapdotbothAvert}{% bug in kpfonts-otf
    \mathrel{\overset{\unicode{x025CB}}{\underset{\unicode{x025CF}}{|}}}%
}}

\CustomizeMathJax{\newcommand{\bignplus}{%
    \mathop{\LWRoverlaysymbols{\unicode{xFF0B}}{\unicode{x22C2}}}%
}}
\CustomizeMathJax{\let\bigcapplus\bignplus}
\CustomizeMathJax{\let\capplus\bignplus}% from kpfonts-otf

\CustomizeMathJax{\newcommand{\bigsqcapplus}{%
    \mathop{\LWRoverlaysymbols{\unicode{xFF0B}}{\unicode{x2A05}}}
}}
\CustomizeMathJax{\let\sqcapplus\bigsqcapplus}% from kpfonts-otf

\CustomizeMathJax{\newcommand{\bigsqcupplus}{%
    \mathop{\LWRoverlaysymbols{\unicode{xFF0B}}{\unicode{x2A06}}}
}}
\CustomizeMathJax{\let\sqcupplus\bigsqcupplus}% from kpfonts-otf

\CustomizeMathJax{\newcommand{\parallelslant}{\mathrel{\unicode{x02AFD}}}}
\CustomizeMathJax{\newcommand{\parallelbackslant}{%
    \mathrel{\unicode{x0005C}\!\!\unicode{x0005C}}%
}}

\CustomizeMathJax{\newcommand{\Eqqcolon}{\mathrel{=\!\unicode{x2237}}}}
\CustomizeMathJax{\let\eqqColon\Eqqcolon}% for kpfonts-otf
\CustomizeMathJax{\newcommand{\dashColon}{\mathrel{-\unicode{x2237}}}}
\CustomizeMathJax{\newcommand{\Colondash}{\mathrel{\unicode{x2237}-}}}

\CustomizeMathJax{\newcommand{\colonapprox}{\mathrel{:\approx}}}
\CustomizeMathJax{\newcommand{\colonsim}{\mathrel{:\sim}}}
\CustomizeMathJax{\newcommand{\Colonapprox}{\mathrel{\unicode{x2237}\!\approx}}}
\CustomizeMathJax{\newcommand{\Colonsim}{\mathrel{\unicode{x2237}\!\sim}}}

\CustomizeMathJax{\newcommand{\strictif}{\mathrel{\unicode{x0297D}}}}% right fish tail
\CustomizeMathJax{\newcommand{\strictfi}{\mathrel{\unicode{x0297C}}}}% left fish tail
\CustomizeMathJax{\newcommand{\strictiff}{%
    \mathrel{\unicode{x0297C}\!\!\unicode{x0297D}}%
}}% left/right fish tails

\CustomizeMathJax{\newcommand{\circledwedge}{%
    \mathbin{\LWRoverlaysymbols{\unicode{x025EF}}{\unicode{x02227}}}%
}}
\CustomizeMathJax{\newcommand{\circledvee}{%
    \mathbin{\LWRoverlaysymbols{\unicode{x025EF}}{\unicode{0x02228}}}%
}}
\CustomizeMathJax{\newcommand{\circledbar}{\mathbin{\unicode{x029B6}}}}

\CustomizeMathJax{\newcommand{\openJoin}{\mathrel{\unicode{x2AA4}}}}% overlapping ><
\CustomizeMathJax{\newcommand{\opentimes}{\mathrel{\unicode{x2AA4}}}}% overlapping ><

\CustomizeMathJax{\newcommand{\VvDash}{\mathrel{\unicode{x22AA}}}}

```

```
\CustomizeMathJax{\newcommand{\lambdabar}{%
    \mathord{\LWRoverlaysymbols{\raise{.5ex}{-}}{\lambda}}%
}}

\CustomizeMathJax{\newcommand{\lambdaslash}{\mathord{\unicode{x019B}}}}

\CustomizeMathJax{\newcommand{\Wr}{\mathbin{\unicode{x02240}\!\unicode{x02240}}}}

\CustomizeMathJax{\newcommand{\dashleftrightarrow}{%
    \mathrel{\unicode{x021E0}\!\unicode{x021E2}}%
}}
\CustomizeMathJax{\let\leftrightdasharrow\dashleftrightarrow}% for kpfonts-otf

\end{warpMathJax}
```

File 569 **lwarp-common-mathjax-overlaysymbols.sty**

§ 676 Package

# common-mathjax-overlaysymbols

Pkg Common code used by a number of packages to overlay two symbols for MathJax.

`lwarp-common-mathjax-overlaysymbols`

**for HTML output:**

```
\ProvidesPackage{lwarp-common-mathjax-overlaysymbols}[2020/08/17]
```

`\LWRoverlaysymbols` {⟨*symbol*⟩} {⟨*symbol*⟩}

Overlays one symbol over another.

```
\begin{warpMathJax}

\CustomizeMathJax{\newcommand{\LWRoverlaysymbols}[2]{%
    \mathord{%
        \smash{%
            \mathop{#2\strut}%
            \limits^{\smash{\lower3ex{#1}}}%
        }%
        \strut%
    }%
}}

\end{warpMathJax}
```

# Change History

§ 677

## Chg Hist

For the most recent changes, see page 1323.

v0.0.895
General: maybemath: Added. . . . . 933
v0.10
General: 2016/03/08 Initial version . . . . 1
v0.11
General: 2016/03/11 . . . . . 1
Added section: Operating-System portability. . . . . 224
Added section: Selecting the operating system. . . . . 117
Test Suite: MS-Windows in README.txt . . . . . 1
Test Suite: limages and index in README.txt . . . . . 1
v0.12
\LWR@newhtmlfile: Bugfix: toc with numbered files. . . . . 388
General: 2016/03/14 . . . . . 1
Global: Uses \p@(type) in float captions. . . . . 1
Test Suite: Sub-figures . . . . . 1
v0.13
\CaptionSeparator: Fix for newer babel package. . . . . 513
\LWR@LwarpStart: \up and \fup . . . 407
General: 2016/03/24 . . . . . 1
Fix dollar-redefined bug for newer package. . . . . 1158
Removed package: subfig . . . . . 1
Test Suite: Ordinals, Subcaption . . . . 1
v0.14
\LWR@htmlsectionfilename: Fix: Links to home page. . . . . 342
General: 2016/03/31 . . . . . 1
floatrow: Added. . . . . 798
Docs: Commands for a successful html conversion. . . . . 121
Docs: Commands into a warpprint environment. . . . . 118
Docs: Newclude limitations. . . . . 172
Docs: Table: Cross-referencing data structures. . . . . 496
Docs: Table: Float data structures. 509
Docs: Trademarks section. . . . . 198
Docs: Troubleshooting cross-references. . . . . 193
Test Suite: Assigned cleveref name for Test Float. . . . . 1
Test Suite: Floatrow . . . . . 1
v0.15
General: 2016/04/06 . . . . . 1
Added. . . . . 802
Ampersand (&): Fixed handling when passed as an argument. . . . . 443
Docs: Added warning icons for items needing special attention. . . . . 201
Docs: Clarify print/html output. . 117
Docs: Moved the supported features table to the introduction. . . . . 66
Files: lwarp_formal.css added. . . . . 1
Fix: steps counter . . . . . 802
Fixed & handling. . . . . 800
Test Suite: test_suite_formal.css file added. . . . . 1
v0.16
General: 2016/04/11 . . . . . 1
\titlingpage: Improved print-output spacing. . . . . 416
xfrac: Adjusted for the use of any font: . . . . . 1223
Added XeLaTeX, LuaLaTeX support. 202
Docs: Font and UTF-8 support. . . 101
Docs: Moved location of \usepackage{lwarp}. . . . . 104
Docs: Text not converting. . . . . 193
Lwarp no longer selects fonts. 101, 235
Removed package: suffix . . . . . 1
Test Suite: Improved titlingpage. . 416
Test Suite: Lwarp no longer selects fonts. . . . . 1
Test Suite: Supports XeLaTeX, LuaLaTeX. . . . . 1
v0.17
\LWR@htmlsectionfilename: Fix: Links when entire doc is one html page. . . . . 342
General: 2016/04/14 . . . . . 1
mdframed: Added. . . . . 933
Test Suite: Fix: Print-version front-matter page numbers. . . . . 1
Test Suite: Mdframed . . . . . 1

v0.18
\LWR@myshorttoc: Reorganize \HomeHTMLFilename logic. . . . . 518
\LWR@newhtmlfile: sideTOC after title, improving responsive design. . . . 387
\LWR@requesttoc: Reorganize \HomeHTMLFilename logic. . . . . 409
\LWR@subhyperref: Improved HTML output linebreaks. . . . . 505
\LWR@subhyperrefclass: Improved HTML output linebreaks. . . . . 506
\LWR@subinlineimage: Suppress extra space. . . . . 507
\hspace: \hspace supported. . . . . 611
General: 2016/05/19 . . . . . 1
graphics: Add: SVG file extension. . 834
graphics: Fix: \linewidth, \textwidth, \textheight inside a minipage. . . . . 834
graphics: Improved HTML output linebreaks. . . . . 834
graphics: em, ex, %, px dimensions preserved. . . . . 834
File: lwarp.css: Improved TOC outline display. . . . . 1
Files: lwarp.css and lwarp_formal.css: Improved responsive design. . . . . 1
Microtype disabled during HTML generation . . . . . 235
PDF Unicode input characters. . . . 218
Test Suite: Verse package . . . . . 1
lateximage: pdfcrop: --hires added. . 570
Reorganize \HomeHTMLFilename logic. . . . . 570
Suppress extra space. . . . . 570
verse: Supports verse, memoir packages. . . . . 1200
minipage: Fix: \linewidth, \textwidth, \textheight inside a minipage. . . . . 589
v0.19
\HTMLFilename: Docs: Escape filename underscores. . . . . 341
\HomeHTMLFilename: Docs: Escape filename underscores. . . . . 341
\LWR@LwarpStart: Enabled \\ equal to \newline. . . . . 406
\LWR@doequation: MathJax support. 557
\LWR@doubledollar: MathJax support. . . . . 551
\LWR@filestart: lwarp_mathjax.txt loaded. . . . . 403
\LWR@minipagestartpars: Suppresses paragraph tags between minipages. 610
\LWR@subsingledollar: MathJax support. . . . . 549
\LateximageFontSizeName: Add: User-adjustable math/lateximage font size. . . . . 567
\hspace: Fix: \hspace length computations. . . . . 611
\minipagefullwidth: Added: No width tag for the next minipage in HTML. . . . . 588
\warpHTMLonly: Added. . . . . 233
\warpprintonly: Replaces \rowprintedonly. . . . . 233
\xfracHTMLfontsize: Added. . . . . 1222
General: 2016/06/08 . . . . . 1
css for table note item. . . . . 1155
MathJax support added. 554, 562, 563
multirow: Added optional args. . . 965
xcolor: Supports colored \rule. . . 1213
Adapts to tikz version. . . . . 1158
Avoids MathJax. . . . . 542
cleveref: Loaded \AtEndPreamble. 586
Docs: Math options. . . . . 104
Docs: Table: Cross-referencing data structures, updated. . . . . 496
File: lwarp.css: tnoteitemheader added. . . . . 1
File: lwarp_mathjax.txt added. . . . 1
Introduction: MathJax support mentioned. . . . . 63
Options: mathsvg and mathjax . . 227
titleps: null \pagestyle and \thispagestyle for HTML. . . . 1159
v0.20
\BlockClassSingle: Renamed from "LWR@htmldivclassline". . . . . 357
\HTMLDescription: Added \NewHTMLdescription. (Renamed in v0.30.) . . . . . 368
\HTMLFilename: No longer escape underscores. . . . . 341
\HomeHTMLFilename: No longer escape underscores. . . . . 341
\InlineClass: Renamed from "inlineclass". . . . . 357
\LWR@closeparagraph: \unskip extra spaces. . . . . 361
No break tags in the start/end of a tabular. . . . . 361
\LWR@endofline: Fix: \\ . . . . . 610
\LWR@filestart: Adds meta description. . . . . 403
\LWR@htmldivclass: Added optional style. . . . . 355

\LWR@htmlelementclass: Added optional style. . . . . 355
\LWR@htmlsectionfilename: HTMLFilename: removed additional trailing '-', and may be empty. . . . . 342
Sections called "Index" or "index" have an underscore prepended to their filenames if no prefix. . . . . 342
\LWR@hyperindexrefsubtwo: Print mode provided in case hyperref not used. . . . . 533
\LWR@longtabledatacaptiontag: Fix: Pars in captions. . . . . 480
\LWR@section: Combined higher-level sections together into files. . . . . 394
\LWR@setOSWindows: Auto-detects operating system. . . . . 226
\LWR@subhtmlelementclass: Factored code. . . . . 354
\SetHTMLFileNumber: Add: Control file numbers. . . . . 341
\cpagerefFor: User-redefinable word for page references. . . . . 733
\dotfill: Inserts an ellipsis. . . . . 609
\hfill: Inserts a \qquad. . . . . 609
\hrulefill: Inserts a short rule. . . . 609
\hspace: Add: Supports HTML thin breakable space. . . . . 611
\pageref: Added. . . . . 504
\tracinglwarp: Added. . . . . 249
General: 2017/02/09 . . . . . 1
afterpage: Added. . . . . 639
alltt: Added. . . . . 644
bookmark: Added. . . . . 682
caption and subcaption supported. . . 1
cleveref and referencing patches: Applied \AfterEndPreamble. . . . 732
draftwatermark: Added. . . . . 749
eso-pic: Added. . . . . 769
everypage: Added. . . . . 773
extramarks: Added. . . . . 774
fancyhdr: Added. . . . . 779
float: Improved float caption type handling. . . . . 795
graphics: Fix: Expands filename. . 834
graphics: Fix: \linewidth in a floatrow. . . . . 834
hyperref: Additional user macros. 846
keyfloat: Added. . . . . 871
letterspace: User-interface emulated. . . . . 884
listings: Added. . . . . 894
ltcaption: Added. . . . . 904
lwarp-newproject: Added. . . . . 262
microtype: User-interface emulated. 950
needspace: Added. . . . . 976
nowidow: Added. . . . . 993
placeins: Added. . . . . 1028
ragged2e: Added. . . . . 1037
setspace: Improved support. . . . 1062
textpos: Added. . . . . 1147
titleps: Added. . . . . 1159
titlesec: Added. . . . . 1162
titletoc: Added. . . . . 1164
titling: Improved compatibility. . . 1166
tocloft: Added. . . . . 1174
wallpaper: Added. . . . . 1205
wrapfig: Added. . . . . 1208
xetexko-vertical: Added. . . . . 1221
Added @, <, > columns. . . . . 437
Added single-expansion data arrays. 337
Code factored into independent lwarp_html files. . . . . 627
Docs: Examples for generating HTML file names. . . . . 115
Docs: Improved index. . . . . 1
Enhanced titling support. . . . . 414
File: lwarp.css: Minor fixes for validation. . . . . 1
File: lwarpmk used to compile print, HTML, indexes, and lateximages. . . 1
Fix: \linewidth in a floatrow. . . . 800
Moved sidebar and example code to test suite. . . . . 1
Page geometry set to 6in wide with large margins. . . . . 236
Parallel versions of aux files for print/HTML. . . . . 1
Removed reliance on make, grep, gawk. . . . . 1
Tabular: \unskip extra spaces. . . 437
Test Suite: HTML meta descriptions. . 1
verbatim: Added. . . . . 426
BlockClass: Added optional style. . . 356
Renamed from "blockclass". . . . . 356
LWR@nestspan: Fix: Minipages inside a span. . . . . 352
v0.21
\LWR@LwarpStart: Changed lateximages to a .txt file. . . . . 406
\LWR@filestart: Skip title if not given. 403
\LWR@newhtmlfile: Skip title if not given. . . . . 387
\marginpar: Fixed source listing. . . . 374
\marginparBlock: Fixed source listing. 375
General: 2017/02/23 . . . . . 1
fontenc: Added. . . . . 807
*lwarpmk*: Fix: **lwarpmk again** for WINDOWS. . . . . 316

General: 2017/04/04 . . . . . 1
lettrine: Added. . . . . 884
microtype: Fix with XeLaTeX, LuaLaTeX. . . . . 950
soul: Added. . . . . 1099
ulem: Added. . . . . 1189
Docs: Installing utilities for MacOS. 81
Docs: Limitations of saveboxes. . . 124
Page geometry modified to reduce line overflow. . . . . 236
v0.28
\@wrindex: Improved indexing. . . . . 528
\HTMLAuthor: Added \HTMLauthor. (Renamed in v0.30.) . . . . . 367
\LWR@LwarpEnd: If FormatEPUB or FormatWP, no bottom nav. . . . . 409
\LWR@LwarpStart: FormatWordProcessor forces single-file output. . . . . 406
\LWR@filestart: Adds HTML meta author. . . . . 403
\LWR@forcenewpage: Forces new PDF page before major environments. . 347
\LWR@htmlcomment: Breaks ligatures in HTML comments. . . . . 354
\LWR@hyperindexrefsubtwo: Improved indexing. . . . . 533
\LWR@newhtmlfile: If FormatEPUB or FormatWP: skips headers, footers, nav. . . . . 387
\LWR@parsetablecols: Added L, C, R, J column types. . . . . 456
\LWR@startref: Removed space. . . . 502
\chapter: If EPUB, prints footnotes before each section. . . . . 401
\textup: Fixed span class. . . . . 600
General: 2017/04/14 . . . . . 1
glossaries: Added. . . . . 825
graphics: Adapts to graphics syntax. 834
graphics: Added. . . . . 826
tabularx: Fix for optional pos. . . . 1130
tabulary: Added. . . . . 1131
*lwarpmk*: Add: **printglossary** and **htmlglossary** commands. . . . . 316
Added boolean FormatEPUB. . . . . 255
Added boolean FormatWP. . . . . 255
Added boolean HTMLDebugComments. 249
Added boolean HTMLMarkFloats, changed to WPMarkFloats as of v0.42. . . . . 256
Docs: Modfying lwarpmk and index processing. . . . . 189
File: lwarp_mathjax.txt: Updated CDN repository. . . . . 312
Forced oneside to maintain large right margin. . . . . 236
v0.29
General: 2017/04/15 . . . . . 1
*.lwarpmkconf: Add: language option for config files. . . . . 269
lwarpmk.conf: Add: language option for config files. . . . . 269
graphics: Fix: Error when no optional arguments. . . . . 834
*lwarpmk*: Add: language option for config files. . . . . 316
Add: lwarpmklang option for lwarp. 228
Docs: Using a glossary . . . . . 94
v0.30
\CSSFilename: Renamed from \NewCSS. . . . . 366
\HTMLAuthor: Renamed from \HTMLauthor. . . . . 367
\HTMLDescription: Renamed from \NewHTMLdescription. . . . . 368
\HTMLFirstPageTop: Renamed from \SetFirstPageTop. . . . . 365
\HTMLLanguage: Renamed from \MetaLanguage. . . . . 402
\HTMLPageBottom: Renamed from \SetPageBottom. . . . . 366
\HTMLPageTop: Renamed from \SetPageTop. . . . . 366
General: 2017/04/29 . . . . . 1
lwarp-newproject removed, and combined with lwarp. . . . . 262
*lwarpmk*: Add: xdyfile configuration option. . . . . 316
*lwarpmk*: Fix: *xindy* and *texindy* adjusted for *pdflatex*, *xelatex* and *lualatex*. . . . . 316
*lwarpmk*: Fix: *xindy* now used for print index generation with *latexmk*. . . . . 316
*lwarpmk*: language now used for both index and glossary generation. 316
File: lwarp_html.xdy renamed to lwarp.xdy. . . . . 311
Fix: *.css files only written in print mode. . . . . 269
Fix: lwarp.xdy only written in print mode. . . . . 311
Fix: lwarp_mathjax.txt: Only written in print mode. . . . . 312
Option lwarpmklang changed to IndexLanguage. . . . . 228
Option OSWindows replaces macro \warpOSwindows. . . . . 229
Option xdyFilename added. . . . . 228

Option *latexmk* replaces macro \UseLatexmk. . . . . 230
Options HomeHTMLFilename and HTMLFilename replace macros \HomeHTMLFilename and \HTMLFilename. . . . . 229
v0.31
General: 2017/05/15 . . . . . 1
keyfloat: Improved compatibility. . 871
v0.32
\RequirePackage: Fix: Ignores blanks in package list. . . . . 244
General: 2016/06/09 . . . . . 1
glossaries: Prevent error with \glo@name not defined. . . . . 534
*lwarpmk*: Fix: **io.lines()** changed to **file:lines()** due to *luatex* changes. . . . . 316
v0.33
\HTMLAuthor: Fix: Provides empty default author if none given. . . . 367
\LWR@loadbefore: Fix: No \PackageError if already loaded. 204
\LWR@parseatcolumn: Fix: Column alignment with leftmost @. . . . . 447
\LWR@tabledatasinglecolumntag: Fix: Macros in tabular could cause extra data cell. . . . . 462
\LWR@vspace: Add: \vspace nullified. 613
\StartDefiningTabulars: Add: Avoids error: Misplaced alignment tab character &. . . 338
General: 2017/07/10 . . . . . 1
amsmath: Removed fleqn option. 645
fancyhdr: Fix: Optional args for \lhead, etc. . . . . 779
Add: Tabular at and bang columns now have their own HTML columns. 437
cleveref: Fix: Loaded \AtEndPreamble. . . . . 586
Fix: Incorrectly-inline math environments. . . . . 563
New handling of & to localize catcode changes. . . . . 437
v0.34
\@fnsymbol: Text symbols instead of math. . . . . 417
\InlineClass: Moved optional argument in front of mandatory. . 357
\LWR@htmldivclass: Moved optional argument in front of mandatory. . 355
\LWR@htmlelementclass: Moved optional argument in front of mandatory. . . . . 355
\LWR@htmlelementclassline: Moved optional argument in front of mandatory. . . . . 356
\LWR@htmlspanclass: Moved optional argument in front of mandatory. . 353
\LWR@nullfonts: Improved font control. . . . . 537
\LWR@restoreorigformatting: booktabs: Works inside lateximage. . . . . 535
Improved font control. . . . . 535
\LWR@subhtmlelementclass: Moved optional argument in front of mandatory. . . . . 354
\LWR@tabledatacolumntag: booktabs: Works inside lateximage. . . . . 486
\fboxBlock: Added. . . . . 595
\makebox: Fix: Handles paren arg. . . 593
General: 2017/08/08 . . . . . 1
babel-french: Adds fixed-width HTML spaces to punctuation. . . . . 349
balance: Added. . . . . 669
booktabs: Works inside lateximage. . . . . 490, 683
boxedminipage2e: Added. . . . . 685
crop: Added. . . . . 740
enumerate: Added. . . . . 762
enumitem: Added, no longer required. . . . . 763
everyshi: Added. . . . . 773
fancybox: Added. . . . . 776
fancyvrb: Added, no longer required. 781
figcaps: Added. . . . . 790
filecontents: Required. Patched for morewrites. . . . . 239
floatpag: Added. . . . . 797
flushend: Added. . . . . 803
fullpage: Added. . . . . 816
hyperxmp: Added. . . . . 856
idxlayout: Added. . . . . 857
marginfit: Added. . . . . 916
mdframed: Improved mdtheorem patch. . . . . 940
moreverb: Added. . . . . 957
paralist: Added. . . . . 1008
pdflscape: Added. . . . . 1017
pdfsync: Added. . . . . 1020
prelim2e: Added. . . . . 1030
rotfloat: Added. . . . . 1047
savetrees: Added. . . . . 1048
shadow: Added. . . . . 1063
syntonly: Added. . . . . 1129
titleps: No longer required. . . . . 1159
titleref: Prevented. . . . . 1162

fix2col: Added. . . . . 792
fncychap: Added. . . . . 804
grffile: Added. . . . . 839
metalogo: Added. . . . . 946
nonumonpart: Added. . . . . 991
nopageno: Added. . . . . 991
pagenote: Option page disabled. . 1007
realscripts: Added. . . . . 1037
relsize: Added. . . . . 1042
romanbarpagenumber: Added. . . 1046
romanbar: Added. . . . . 1046
scalefnt: Added. . . . . 1048
siunitx: Removed from lwarp core. 1079
textcomp: Removed from lwarp core. . . . . 1144
tocbibind: Added. . . . . 1171
xltxtra: Added. . . . . 1225
*lwarpmk*: Added **print1** and **html1** actions. . . . . 316
Added \markboth, \sloppy, etc. . 347
Docs: Enhanced *Supported Features* table. . . . . 66
Docs: Index, tocbibind. . . . . 137
Docs: Starred sections. . . . . 133

v0.39

\@maketitle: titling version. . . . . 1168
Native LaTeX version. . . . . 418
Removed minipages. . . . . 418, 1168
Supports authblk with s of class oneauthor instead of tabular. . . . . 418, 1168
\AddSubtitlePublished: Added. . . 419
\LWR@domulticolumn: Add: Optional vpos and # rows. . . . . 477
\LWR@restoreorigformatting: Appended with \appto instead of calling various macros. . . . . 535
\LWR@tabledatacolumntag: Don't start a data cell if see \TabularMacro. . . . . 486
\ResumeTabular: Added. . . . . 486
\TabularMacro: Added. . . . . 486
\multicolumnrow: Added. . . . . 484, 967
\printauthor: Removed minipages. 415
Supports authblk with s of class oneauthor instead of tabular. 415
\thanksmarkseries: Removed minipage footnotes. . . . . 1169
General: 2017/09/05 . . . . . 1
a4wide: Added. . . . . 629
a4: Added. . . . . 628
a5comb: Added. . . . . 629
addlines: Added. . . . . 638
anysize: Added. . . . . 653
authblk: Added. . . . . 663
bigdelim: Added. . . . . 679
bigstrut: Added. . . . . 680
ebook: Added. . . . . 751
fullwidth: Added. . . . . 817
midpage: Added. . . . . 951
multirow: Add: New optional vpos argument. . . . . 965
multirow: Add: Supports left/right border for bigdelim. . . . . 965
multirow: Fix: Long text argument. 965
supertabular: Added. . . . . 1127
textarea: Added. . . . . 1143
titling: Improved compatibility. . . 1166
titling: Removed extraneous center environments. . . . . 1167
typearea: Added. . . . . 1187
xtabular: Added. . . . . 1228
zwpagelayout: Added. . . . . 1233
Docs: Reorganized tabular discussion. . . . . 162
Titlepage \published and \subtitle removed. \AddSubtitlePublished restores. 419
titlepage: Clear pending footnotes. 414
Removed minipages. . . . . 414
titlingpage: Clear pending footnotes. . . . . 1166

v0.40

\@chapcntformat: Added for tocbibind, anonchap. . . . . 394
\LWR@HTMLhline: Added. . . . . 490
\LWR@nullfonts: Fix: Long arguments for expandable command. . . . . 537
\LWR@restoreorigformatting: Improved LaTeX logos inside a lateximage. . . . . 535
Improved symbols inside a lateximage. . . . . 535
Nullified \InlineClass, etc. inside a lateximage. . . . . 535
\LWR@tabledatacolumntag: Fix for bigdelim: \ldelim, \rdelim. . . . 486
\chapter: Added support for quotchap. . . . . 401
\multicolumnrow: Fix: Adapts to older multirow and xparse. . . . . 484
\simplechapterdelim: Added for tocbibind, anonchap. . . . . 393
\underline: Added. . . . . 606
General: 2017/09/25 . . . . . 1
adjmulticol: Added. . . . . 637
anonchap: Added. . . . . 653
bigdelim: Improved documentation. 679
cuted: Added. . . . . 743
dblfnote: Added. . . . . 744

fnpos: Added. . . . . 805
graphics: Add: Full \graphicspath support. . . . . 834
graphics: Moved out of the lwarp core. . . . . 826
graphics: Restores \includegraphics and \DeclareGraphicsExtensions in a lateximage. . . . . 826
graphicx: Moved out of the lwarp core. . . . . 839
grffile: Directly supported. . . . . 839
midfloat: Added. . . . . 950
multirow: Improved bigdelim borders. . . . . 965
pfnote: Added. . . . . 1023
quotchap: Added. . . . . 1035
sectsty: Added. . . . . 1059
stabular: Added. . . . . 1104
tabls: Added. . . . . 1130
textcomp: Additional symbols, improved XeLaTeX and LuaLaTeX support. . . . . 1144
tocbibind: Improved for \simplechapter. . . . . 1171
xfrac: No longer preloaded. . . . . 240
xltxtra: Fix for \showhyphens with XeLaTeX. . . . . 1225

v0.41

\LWR@addcmidruletrim: Add: \cmidrule trims. . . . . 467
\LWR@clearmidrules: Add: \cmidrule trims. . . . . 465
\LWR@closetabledatacell: Add: Mute > for \bottomrule. . . . . 442
Fix: At/bang column with \multirow. . . . . 442
Fix: Cancel < for \multicolumn. . 442
\LWR@domulticolumn: Add: \cmidrule trims. . . . . 477
Added vertical rules. . . . . 478
\LWR@nullifyNoAutoSpacing: babel-french: Fix: \NoAutoSpacing in a tabular. . . 491
\LWR@parsebarcolumn: Added vertical rules. . . . . 450
\LWR@printatbang: Add: \cmidrule trims. . . . . 461
Add: Mute at and bang columns for \bottomrule. . . . . 461
\LWR@printbartag: Added vertical rules. . . . . 461
\LWR@subaddcmidruletrim: Added. . 467
\LWR@subcmidrule: Add: \cmidrule trims. . . . . 465
\LWR@tabledatasinglecolumntag: Add: \cmidrule trims. . . . . 462
Add: Mute < for \bottomrule. . . . 462
\LWR@tabularfinishrow: Unfinished tabular rows automatically filled. . 444
\mcolrowcell: Added for \multicolumrow cells. . . . . 489
General: 2017/10/07 . . . . . 1
booktabs: Improved rules. . . . . 683
multirow: Add: \cmidrule trims. . 965
Added vertical rules. . . . . 965
Fix: < spec. . . . . 966
tabular: Fix: \NoAutoSpacing in a tabular with babel-french. . . . . 492

v0.42

\@ensuredmath: Improved \ensuremath. . . . . 552
\@textsubscript: Added. . . . . 606
\@textsuperscript: Added. . . . . 606
\LWR@HTMLhline: If FormatWP force explicit border. . . . . 490
\LWR@addformatwpalignment: If FormatWP add explicit style for cell alignment. . . . . 469
\LWR@addrulewidth: If FormatWP force explicit border. . . . . 468
\LWR@amsmathbody: Fix: Numbering and naming AMS math environments. . . . . 568
\LWR@amsmathbodynumbered: Fix: Numbering and naming AMS math environments. . . . . 568
\LWR@doequation: If FormatWP print LaTeX expression. . . . . 558
\LWR@domulticolumn: If FormatWP add cell alignment. . . . . 479
\LWR@doubledollar: If FormatWP print LaTeX expression. . . . . 551
Improved \ensuremath. . . . . 551
Improved line spacing with mathjax. 551
\LWR@floatbegin: If FormatWP add a text frame. . . . . 510
\LWR@floatend: If FormatWP add a text frame. . . . . 511
\LWR@remembertag: Fix: Numbering and naming AMS math environments. . . . . 568
\LWR@restoreorigformatting: Improved \ensuremath. . . . . 536
\LWR@subaddcmidruletrim: 0pt if no rule given. . . . . 467
\LWR@subsingledollar: If FormatWP print LaTeX expression. . . . . 549
\LWR@tabledatasinglecolumntag: If FormatWP add cell alignment. . . . 463

\LaTeX: If FormatWP use explicit style. 617
\TeX: If FormatWP use explicit style. . 617
\hspace: If FormatWP add \quads. . . 612
\listoffigures: Added boolean WPMarkLOFT. . . . . 520
\listoftables: Added boolean WPMarkLOFT. . . . . 520
\marginpar: If FormatWP emulate a wrapfig. . . . . 374
\marginparBlock: If FormatWP emulate a wrapfig. . . . . 375
\rule: If FormatWP add \quads. . . . . 615
\tableofcontents: Added boolean WPMarkTOC. . . . . 520
\underline: If FormatWP, use explicit styles for \underline, etc. . . . . 606
General: 2017/10/30 . . . . . 1
\textbf and related: If FormatWP, use explicit styles for \textsc, etc. 598
algorithmicx: If FormatWP add \quads. . . . . 643
booktabs: If FormatWP force explicit border. . . . . 683
epigraph: If FormatWP add HTML styles. . . . . 763
fancybox: If FormatWP add HTML styles. . . . . 776
floatflt: Added width. . . . . 796
graphics: Fix: Class key. . . . . 830
graphics: Fix: Filename expansion. 834
graphics: If FormatWP, use explicit size. . . . . 831
keyfloat: If FormatWP add explicit HTML style. . . . . 875
moreverb: Simplified formatting of listings. . . . . 957
multirow: If FormatWP add cell alignment. . . . . 965
overpic: Added. . . . . 1006
realscripts: Fix for subscripts in a lateximage. . . . . 1037
sidenotes: If FormatWP add explicit HTML style. . . . . 1067
siunitx: Improved \ensuremath. . . 1079
soul: If FormatWP, add explicit styles. . . . . 1099
textcomp: Improved \interrobangdown. . . . . 1144
wrapfig: If FormatWP add explicit HTML style. . . . . 1208
Added boolean WPMarkLOFT. . . . . 256
Added boolean WPMarkMath. . . . . 256
Added boolean WPMarkMinipages. 256
Added boolean WPMarkTOC. . . . . 256
Added boolean WPTitleHeading. . 256
Docs: Added support page. . . . . 2
Docs: Improper \prevdepth. . . . . 193
Docs: Reorganized math limitations 150
File: lwarp_mathjax.txt: Updated siunitx script. . . . . 312
Fix: Numbering and naming AMS math environments. . . . . 567
If FormatWP, shift section headings. 257
tabbing: Added. . . . . 426
lateximage: Fix: Numbering and naming AMS math environments. 570
center: If FormatWP use explicit text-align. . . . . 575
minipage: Added boolean WPMarkMinipages. . . . . 591
If FormatWP add a text frame. . . . . 590
eqnarray: Fix: Numbering and naming AMS math environments. . . . . 564
If FormatWP print LaTeX expression. 563
LWR@BlockClassWP: Added to factor code. . . . . 358
LWR@figcaption: If FormatWP forces italic captions. . . . . 515
v0.43
\LWR@domulticolumn: Fix for vertical rules. . . . . 478
Fix: Multicolumn trim. . . . . 478
\LWR@href: Made robust. . . . . 506
\LWR@maybeprintpendingfootnotes: Added FootnoteDepth. . . . . 374
\LWR@nolinkurl: Made robust. . . . 506
\LWR@nullfonts: Fix: Nullify dollar inside filesnames. . . . . 537
\LWR@parsetablecols: Ignore spaces in col spec. . . . . 456
\LWR@printmccoltype: Added vertical rules. . . . . 473
\LWR@section: Fix: Expansion in comparison. . . . . 395
Fix: Math in section name. . . 396, 399
Fix: Nullify fonts inside HTML comment. . . . . 396
\LWR@url: Made robust. . . . . 507
\TabularMacro: \newcommand instead of \relax to fix supertabular and xtab. . . . . 486
\nameref: Made robust. . . . . 504
General: 2017/11/08 . . . . . 1
LWR@currentautosec: Added. . . . 394
breakurl: Added. . . . . 686
hyperref: Made robust. . . 851, 853, 854
hyperref: \Gauge added. . . . . 855
luatodonotes: Added. . . . . 908
todonotes: Added. . . . . 1181
Added FootnoteDepth. . . . . 370

Docs: HTML settings table. . . . . 109
Docs: Reorganized HTML customization. . . . . 109
v0.44
\@currentlabelname: Adjustment for koma-script. . . . . 498
\HTMLTitle: Added. . . . . 367
\LWR@addformatwpalignment: Fix for multicolumn alignment if FormatWP. . . . . 469
\LWR@backgroundcolor: xcolor: Added \LWR@backgroundcolor. . . . . 1213
\LWR@filestart: Add \HTMLTitle. . 405
Fix \HTMLAuthor. . . . . 404
\LWR@listitem: Added list and trivlist. . . . . 430
\LWR@patchlists: Added list and trivlist. . . . . 433
\LWR@strresult: Fix: \providecommand. . . . . 440
\LWR@textcurrentcolor: xcolor: Added \LWR@textcurrentcolor. 1213
\addcontentsline: Automatic \LWR@newfloatanchor. . . . . 517
\chapter: Add preamble for koma-script. . . . . 401
\marginparBlock: Added. . . . . 375
\nopagecolor: xcolor: Fix for \nopagecolor. . . . . 1215
\part: Add preamble for koma-script. 400
\title: Added \thetitle. . . . . 367
General: 2017/11/22 . . . . . 1
algorithmicx: Improved comment symbol. . . . . 643
atbegshi: Added. . . . . 659
cancel: Added. . . . . 690
changepage: Additional options. . 698
easy-todo: Added. . . . . 750
fancyref: Added. . . . . 780
fixmetodonotes: Added. . . . . 794
fixme: Added. . . . . 793
fontenc: Allowed after lwarp. . . . 807
hang: Added. . . . . 840
ifoddpage: Added. . . . . 857
ltxtable: Added. . . . . 905
luatodonotes: Improved. . . . . 908
lwarp-patch-komascript: Added. . 1234
overpic: Fix: Groups for lateximages. . . . . 1006
pdfsync: Fixes. . . . . 1020
preview: Added. . . . . 1031
scrextend: Added. . . . . 1050
scrhack: Added. . . . . 1054
scrlayer-notecolumn: Added. . . . 1056
scrlayer-scrpage: Added. . . . . 1056
scrlayer: Added. . . . . 1054
section: Added. . . . . 1058
soulpos: Added. . . . . 1100
soulutf8: Added. . . . . 1101
supertabular: Fix for caption. . . . 1127
tikz: Fix: Groups for lateximages. . 1158
tocbasic: Added. . . . . 1170
tocloft: Added \newlistentry. . . 1178
tocloft: Improved \newlistof. . . 1179
tocstyle: Added. . . . . 1180
todonotes: Improved. . . . . 1181
todo: Added. . . . . 1180
typearea: Added expert commands. 1187
watermark: Added. . . . . 1205
xcolor: Added \LWR@currenttextcolorstyle. 1212
xcolor: Added \LWR@findcurrenttextcolor. . 1212
xtab: Fix for caption. . . . . 1229
Adjustment for koma-script. . . . . 216
AMS environments: Fix: Groups for lateximages. . . . . 646
If pdfLaTeX, require T1 and UTF-8 encoding. . . . . 217
picture: overpic: Fix: Groups for lateximages. . . . . 586
list: Added list and trivlist. . . . 431
LWR@nestspan: Added list and trivlist. . . . . 352
v0.45
\@currentHref: Added. . . . . 505
\@donoparitem: Modified for HTML. . 428
\@item: Modified for HTML. . . . . 429
\@mklab: Modified for HTML. . . . . 428
\CSSFilename: Improved filenames with underscores. . . . . 366
\LWR@LwarpStart: Fix: Lateximages on incorrect pages with MATHJAX. . . 407
\LWR@label@createtag: Fix: Labels with underscores. . . . . 500
\LWR@newautoidanchor: Fix: No anchor if frozen autoid. . . . . 512
\LWR@nolinkurl: Fix: Underscore in URL. . . . . 506
\LWR@notmemoirloadafter: Added. . 203
\LWR@printpendingmpfootnotes: Added. . . . . 374
\LWR@startref: Fix: Labels with underscores. . . . . 503
\LWR@subhyperref: Improved URLs with underscores. . . . . 505
\LWR@subhyperrefclass: Improved URLs with underscores. . . . . 506
\LWR@tabledatacolumntag: Fix: Empty line between rows. . . . . 489

\LWR@url: Improved URLs with underscores. . . . . 507
\chapter: Add optional heading title for memoir. . . . . 401
\newpage: Added. . . . . 609
\normalmarginpar: Added. . . . . 375
\reversemarginpar: Added. . . . . 375
\section: Add optional heading title for memoir. . . . . 401
\tableofcontents: Fix: Empty sidetoc. . . . . 519
Fix: Patch \AtBeginDocument. . . . 519
General: 2018/01/14 . . . . . 1
array: Added. . . . . 656
babel-french: Robust commands. . 349
backref: Added. . . . . 669
breakurl: Fix: Underscore in URL. . 686
changebar: Added. . . . . 696
cite: Added. . . . . 730
continue: Added. . . . . 739
endfloat: Added. . . . . 756
fancyvrb: Improvements. . . . 781, 783
flafter: Added. . . . . 794
fltrace: Added. . . . . 803
footnpag: Added. . . . . 810
fwlw: Added. . . . . 820
graphics: Improved URLs with underscores. . . . . 834
hanging: Added. . . . . 842
hyperref: Fix: Underscore in URL. . . . . 851, 852
lwarp-patch-memoir: Added. . . . 1237
memhfixc: Added. . . . . 945
memoir: Added. . . . . 621
natbib: Added. . . . . 973
pagesel: Added. . . . . 1007
prettyref: Added. . . . . 1031
subfigure: Added. . . . . 1125
subfig: Fix for subcaption end tag. 1123
subfig: Fix: Math in subcaptions. . 1121
textfit: Added. . . . . 1147
titleref: Added. . . . . 1162
turnthepage: Added. . . . . 1186
Allows memoir's preloaded packages. . . . . 206
Docs: Fix for double hyphens. . . . 81
Docs: Improved install instructions. 82
Docs: Improved MiKTEX install instructions. . . . . 78
Docs: Moved table so doesn't interfere with install docs. . . . . 77
File: lwarp_mathjax.txt: Allow MathJax inside tabbing. . . . . 312
File: lwarp_mathjax.txt: Allow MathJax inside verse. . . . . 312
Fix: Empty sidetoc. . . . . 519
Improved: Robust \,, \ , and \textellipsis commands. . . . 608
Separate LWR@thisautoidWP for word processor s. . . . . 512
thebibliography: Patched to emphasize titles. . . . . 534
minipage: Fix: Improper \prevdepth. 591
v0.46
\LWR@closeparagraph: Fix: Tabular empty lines. . . . . 362
\LWR@closeprevious: Fix: Stack unnesting. . . . . 347
\LWR@forcenewpage: Fix: Improper \prevdepth. . . . . 347
\LWR@lookforpackagename: Fix: Spaces in \usepackage. . . . . 244
\LWR@popclose: Fix: Stack unnesting. 336
\LWR@providelength: Added. . . . . 220
\LWR@pushclose: Fix: Stack unnesting. 336
\LWRPrintStack: Name changed from \PrintStack. . . . . 346
General: 2018/01/23 . . . . . 1
LWR@tabularpardepth added. . . . 439
amsthm: Adapted to trivlist changes. . . . . 651
mdframed: Fixes for SVG math or lateximage in title. . . . . 937
mdframed: Fixes for footnotes. . . 938
ntheorem: Adapted to trivlist changes. . . . . 993
theorem: Adapt to trivlist changes. . . . . 1150, 1151
tabular: Fix: Tabular empty lines. 494, 495
list: Fix: Stack unnesting. . . . . 431
v0.47
\LWR@HTML@caption@begin: Fix: Argument passed to \LWR@origcaption@begin. . . . 515
\LWR@LwarpStart: Fix for SVG math in \nameref. . . . . 408
\LWR@WPcell: Fix: Line wrap at HTML hyphen. . . . . 469
\LWR@createautosec: Fix: Line wrap at HTML hyphen. . . . . 392
\LWR@domulticolumn: Fix: Line wrap at HTML hyphen. . . . . 479
\LWR@floatbegin: Fix: Line wrap at HTML hyphen. . . . . 510
\LWR@htmlclosecomment: Add \mbox to prevent line breaks. . . . . 353
\LWR@label@createtag: Fix: Line wrap at HTML hyphen. . . . . 500
\LWR@newautoidanchor: Fix: Line wrap at HTML hyphen. . . . . 512

\LWR@printopenlist: Fix: Line wrap at HTML hyphen. . . . . 428
\LWR@startref: Fix: Line wrap at HTML hyphen. . . . . 502
\LWR@subsingledollar: Added SVG math image baseline adjust and em sizing. . . . . 549
\LWR@subsingledollarsvg: Fix: Line wrap at HTML hyphen. . . . . 547
\captionlistentry: Fix: Line wrap at HTML hyphen. . . . . 516
\hypertoc: Fix: Line wrap at HTML hyphen. . . . . 523
\hypertocfloat: Fix: Line wrap at HTML hyphen. . . . . 524
General: 2018/01/30 . . . . . 1
adjmulticol: Fix: Line wrap at HTML hyphen. . . . . 638
blowup: Added. . . . . 681
caption: Added. . . . . 691
changepage: Fix for pagecheck macros. . . . . 698
endheads: Added. . . . . 756
epigraph: Fix: Line wrap at HTML hyphen. . . . . 764
hanging: Fix: Line wrap at HTML hyphen. . . . . 842
hang: Fix: Line wrap at HTML hyphen. . . . . 840
keyfloat: Fix for SVG math in captions. . . . . 872
midpage: Fix: Line wrap at HTML hyphen. . . . . 951
multirow: Fix: Line wrap at HTML hyphen. . . . . 965
multitoc: Added. . . . . 968
ntheorem: Fix: Line wrap at HTML hyphen. . . . . 998
realscripts: Fix: Line wrap at HTML hyphen. . . . . 1037
scrextend: Fix: Line wrap at HTML hyphen. . . . . 1050
sectionbreak: Added. . . . . 1059
sidenotes: Fix for SVG math in captions. . . . . 1067
subfig: Fix for SVG math in captions. 1121
subfig: Fix: Support \nameref. . . . 1121
xurl: Added. . . . . 1231
*lwarpmk*: *pdfcrop*: Removed hires option for improved crop accuracy. 316
lateximage: Added CSS style option. 570
Fix: Line wrap at HTML hyphen. . . 574
center: Fix: Line wrap at HTML hyphen. . . . . 575
minipage: Fix: Line wrap at HTML hyphen. . . . . 590
flushleft: Fix: Line wrap at HTML hyphen. . . . . 576
flushright: Fix: Line wrap at HTML hyphen. . . . . 575
enumerate: Fix: Line wrap at HTML hyphen. . . . . 432
itemize: Fix: Line wrap at HTML hyphen. . . . . 432
LWR@BlockClassWP: Fix: Line wrap at HTML hyphen. . . . . 358
v0.48
\@@@setcpageref: Fix for new v0.21 of cleveref. . . . . 733
\@@@setcref: Fix for new v0.21 of cleveref. . . . . 732
\@@@setcrefrange: Fix for new v0.21 of cleveref. . . . . 733
\@biblabel: Improved bibliography label. . . . . 534
\@item: Honors \makelabel. . . . . 429
\@maketitle: Fix: Errors with IEEEtran class. . . . . 418
\LWR@LwarpStart: Adjusted space around captions. . . . . 407
\LWR@ProvidesPackageDropB: Fix: Options with braces. . . . . 246
\LWR@addtabularhrulecolor: colortbl: Added. . . . . 470
\LWR@addtabularrulecolors: colortbl: Added. . . . . 471
\LWR@closetabledatacell: colortbl: Added. . . . . 443
\LWR@lookforpackagename: Fix: Parsing similar package names. . . 243
\LWR@newautopagelabel: Fix: TOC, LOF, LOT links. . . . . 381
\LWR@newhtmlfile: Fix: TOC, LOF, LOT links. . . . . 389
\LWR@nullfonts: Fix: \newline in title. . . . . 537
\LWR@parsedrequirepackagenames: Fix: Parsing similar package names. 241
\LWR@parsetablecols: Fix: Ignore optional tabular column arguments. 457
\LWR@restoreorigformatting: Fix: Spacing in SVG math, lateximage, Ti*k*z. . . . . 535
\LWR@section: Fix: TOC, LOF, LOT links. 399
\LWR@tabledatasinglecolumntag: colortbl: Added. . . . . 463
\LWR@textcurrentfont: Added. Improves font control. . . . . 602
\centerline: Added. . . . . 577

`\l@part`: Adapts to classes without

ntheorem: Fix: Not standard nor amsthm selected. . . . . 1000
pbox: Added. . . . . 1013
phfqit: Added. . . . . 1023
schemata: Added. . . . . 1049
siunitx: Fix: Loads xcolor. . . . . 1079
siunitx: Improved SVG math alt tags. . . . . 1080
siunitx: Improved units. 579, 1079, 1082
xy: Added. . . . . 1231
*lwarpmk*: Error if lateximages.txt does not exist. . . . . 316
*lwarpmk*: Error if lwarpmk.conf points to lwarp. . . . . 316
*lwarpmk*: Improved error messages. 316
*lwarpmk*: MD5 hash avoids duplicate SVG math. . . . . 316
*lwarpmk*: Multiprocess support making lateximages. . . . . 316
AMS environments: Improved SVG math display. . . . . 646
Fix: Load fontspec if necessary. . . 235
Robustify macros. . . . . 602
lateximage: Fix: SVG math in a section name. . . . . 573
MD5 hash avoids duplicate SVG math. . . . . 571, 574
eqnarray: Improved SVG math display. 564
v0.51
\@ensuredmath: Hashes \ensuremath. 552
\@item: Restored list label space. . . . 430
\LWR@HTMLsanitizeexpand: Fix: Escapes double quotes. . . . . 383
\LWR@LwarpStart: MathJax: Nullifies \ensuremath. . . . . 408
\LWR@addbaselinemarker: Improved SVG math baseline. . . . . 543
\LWR@atbeginverbatim: Adds vertical offset. . . . . 424
\LWR@doequation: Fix: \addcontentsline inside SVG math. Provides an autoid anchor. . 558
\LWR@doubledollar: Fix: \addcontentsline inside SVG math. Provides an autoid anchor. . 551
\LWR@findcurrenttextcolor: Added \LWR@findcurrenttextcolor when no xcolor. . . . . 607
\LWR@newautoidanchor: Fix: No autoid is inside a lateximage. . . . . 512
\LWR@singledollarmeasure: Fix: lateximage inside $\mathcal{AMS}$ \text. . 545
Fix: Honors text font around SVG math. . . . . 544
Improved SVG math baseline. . . . . 545
Typeset SVG math only once during measurement. . . . . 545
\LWR@subHTMLsanitize: Fix: Escapes double quotes. . . . . 382
\LWR@subsingledollar: Fix: \ensuredmath inside SVG image. . 549
\LWR@subsingledollarsvg: Fix: SVG math with enclosed lateximage. . 546
SVG math baseline improved with invisible rule at corner. . . . . 548
\LWR@textcurrentcolor: xcolor: \LWR@textcurrentcolor if xcolor not loaded. . . . . 607
\addcontentsline: Add missing support for float mechanism if necessary. . . . . 517
No anchor ID if inside SVG image. . 517
\displaymathnormal: Processing for complicated display math. . . . . 561
\displaymathother: Processing for complicated display math. . . . . 561
General: 2018/03/24 . . . . . 1
MathJax: Nullifies \ensuremath. 385
lwarp_one_limage.txt: *pdftocairo* -noshrink added. . . . . 311
afterpackage: No longer required. 238
chemfig: Added. . . . . 704
chemformula: Added. . . . . 706
chemgreek: Added. . . . . 711
chemmacros: Added. . . . . 711
chemnum: Added. . . . . 729
epstopdf-base: Added. . . . . 765
fancybox: Fix: Optional tag for \item in a span. . . . . 778
grid: Added. . . . . 839
listings: Forces cleared options. . . 895
ltxgrid: Added. . . . . 904
mhchem: Added. . . . . 948
tikz: Fix for \tikz macro. . . . . 1158
tikz: Fix for tikz with optional argument. . . . . 1158
titling: Fix for \thanks mark. . . . 1168
*lwarpmk*: *pdfcrop*: Restored hires option. . . . . 316
*lwarpmk*: *pdftocairo* -noshrink added. . . . . 316
AMS environments: Fix: \addcontentsline inside SVG math. Provides an autoid anchor. . 646
Docs: tikz limitations. . . . . 159
Docs: Multiple authors and affiliations. . . . . 133
Docs: Things to avoid. . . . . 121
Docs: Updated Converting an existing document. . . . . 98

Fix: Remember original \# in case is redefined. . . . . 258
Named HTML entity used for text dollar. . . . . 542
lateximage: Added additional hashing option. . . . . 570
Fix: lateximage inside $\mathcal{AMS}$ \text. 570
Processing for complicated display math. . . . . 573
alignat: amsmath: Fix: Added. . . . 648
eqnarray: Fix: \addcontentsline inside SVG math. Provides an autoid anchor. . . . . 564
LWR@displaymathother: Processing for complicated display math. . . . . 554
LWR@equationother: Processing for complicated display math. . . . . 554
v0.52
\@ensuredmath: Improved hashing expansion. . . . . 552
\@mpfootnotetext: Fix: Paragraph handling. . . . . 373
\CustomizeMathJax: Added. . . . . 384
\LWR@@footnotetext: Fix: Paragraph handling. . . . . 372
\LWR@addbaselinemarker: Warnings if lwarp_baseline_marker.png is not present or if graphicx/s not loaded. . . . . 543
\LWR@customizedMathJax: Added. . 383
\LWR@doequation: Fix: equation* now based on equation instead of displaymath. . . . . 558
Fix: equation* with split. . . . . 557
\LWR@filenamenoblanks: Fix: \FileDepth with non-utf8 encoding. . . . . 380
\LWR@href: Fix: #, %, &, ~, _ in URL. . . 506
\LWR@nolinkurl: Fix: #, %, &, ~, _ in URL. . . . . 506
\LWR@nullfonts: Fix: \texorpdfstring in section names. . . . . 540
\LWR@section: Fix: Footnote numbering: Limited HTML comment if starred. . . . . 396
Fix: Footnote numbering: Use short TOC entry for HTMLDebug comments. . . . . 396
\LWR@singledollarmeasure: Added user-adjustable SVG math font scaling. . . . . 545
\LWR@url: Fix: #, %, &, ~, _ in URL. . . 507
\LatexImageFontScale: Added user-adjustable SVG math font scaling. . . . . 567
\theHTMLTitleSeparator: Fix: \FileDepth with non-utf8 encoding. . . . . 402
General: 2018/04/01 . . . . . 1
breakurl: Fix: #, %, &, ~, _ in URL. . . 686
endfloat: Updated for v2.6. . . . . 756
fancyvrb: Initial support for \VerbatimFootnotes. . . . . 776, 781
graphics: Added defaults. . . . . 829
graphics: Updated for v1.1a. . . . . 830
graphics: Updated for v1.1b. . . . . 830
hyperref: Fix: #, %, &, ~, _ in URL. 851–853
nicefrac: Added. . . . . 986
url: Added. . . . . 1198
*lwarpmk*: Fix: Memory overflow when spawning tasks. . . . . 316
*lwarpmk*: Fix: Skip image generation if from page 0. . . . . 316
Changed FootnoteDepth default to \subsbusection. . . . . 370
Docs: Improved install instructions. 79
Fix: MathJax script line wraps. Reduced right margin. . . . . 236
If pdfLaTeX, allow other input encoding. . . . . 217
Restore \kill in a lateximage. . . 903
tabbing: Fix to allow inside lateximage. . . . . 426
lateximage: Fix for hash expansion. 571
v0.53
General: 2018/04/01 . . . . . 1
*lwarpmk*: Added **lwarpmk cleanlimages**. . . . . 316
*lwarpmk*: Added warning for corrupted images. . . . . 316
Docs: **lwarpmk cleanlimages**. . . . 95
Docs: **lwarpmk pdftohtml**. . . . . 95
v0.54
\@xdlbfloat: Honor \centering, etc. in floats. . . . . 511
\LWR@afterendverbatim: Added vspace argument. . . . . 425
\LWR@atbeginverbatim: Improved column alignment. . . . . 425
\LWR@earlyloadnever: Added. . . . . 205
\LWR@endfloatalignment: Honor \centering, etc. in floats. . . . . 513
\LWR@floatalignment: Honor \centering, etc. in floats. . . . . 513
\LWR@floatend: Honor \centering, etc. in floats. . . . . 511

\LWR@floatbegin: Adds a <class> per float package style. . . . . 510
\LWR@multicolpartext: Fix: \multicolumn parameters. . . . . 474
\LWR@openparagraph: Added support for parnotes. . . . . 360
\LWR@parsebarcolumn: Adds support for double vertical rules. . . . . 450
\LWR@parsecoloncolumn: arydshln: Added. . . . . 450
\LWR@parsesemicoloncolumn: arydshln: Added. . . . . 451
\LWR@parsetablecols: Added array W column. . . . . 458
\LWR@printmccoldata: Added array W column. . . . . 475
Fix: \multicolumn parameters. . . 475
\LWR@printmccoltype: Added array W column. . . . . 473
Adds support for dashed vertical rules. . . . . 473
Adds support for double vertical rules. . . . . 473
\LWR@tabledatacolumntag: Fix: \morecmidrules . . . . . 488
\LWR@textcurrentfont: Added span.textbf, etc. . . . . 602
General: 2018/05/12 . . . . . 1
*.lwarpmkconf: Records --shell-escape. . . . . 269
lwarp.css: Added div.textbf, etc. 269
lwarp.css: Added span.textbf, etc. . . . . 269
lwarpmk.conf: Records --shell-escape. . . . . 269
arydshln: Added. . . . . 437, 657
lua-check-hyphen: Added. . . . . 905
paralist: Fixes for compactenum, compactitem, compactdesc. . . . 1008
parnotes: Added. . . . . 1012
quoting: Added. . . . . 1036
tocenter: Added. . . . . 1174
underscore: Added. . . . . 1191
*lwarpmk*: Added lwarpmk pdftosvg. . . . . 316
*lwarpmk*: Supports --shell-escape. . . . . 316
Added \thinspace. . . . . 608
Docs: **lwarpmk pdftosvg**. . . . . 95
LWR@blocktextcurrentfont: Added div.textbf, etc. . . . . 602
v0.57
\BlockClassSingle: Improved print/HTML output selection. . . . 357
\InlineClass: Improved print/HTML output selection. . . . . 357
\LWR@href: Fix: Text catcodes. . . . 506
\LWR@singledollarmeasure: Fix: Dynamic inline math expressions. 545
\LWR@subhyperref: Fix: Text catcodes. 505
\LWR@subhyperreftext: Fix: Text catcodes. . . . . 506
\LWR@subsingledollar: Fix: Dynamic inline math expressions. . . . . 549
\LWR@subsingledollarsvg: Fix: Dynamic inline math expressions. 547
\LWR@vspace: Improved print/HTML output selection. . . . . 613
\MathImageAltText: Added. . . . . 541
\PackageDiagramAltText: Added. . 541
\StartDefiningMath: Added. . . . . 338
\boxframe: xcolor: Fix: Colored \boxframe. . . . . 1218
\colorbox: xcolor: New system for switching print and HTML outputs. 1215
\colorboxBlock: xcolor: New system for switching print and HTML outputs. . . . . 1215
\fboxBlock: Improved print/HTML output selection. . . . . 595
\fcolorbox: xcolor: New system for switching print and HTML outputs. 1216
\framebox: Improved print/HTML output selection. . . . . 594
\inlinemathother: Added. . . . . 339
\listof: Fix: Provide \l@name if not defined. . . . . 521
\makebox: Improved print/HTML output selection. . . . . 593
\mbox: Improved print/HTML output selection. . . . . 592
\multicolumnrow: multirow: Improved print/HTML output selection. . . . 967
Improved print/HTML output selection. . . . . 484
\newfloat: rotfloat: Added float styles. . . . . 1047
rotfloat: Fix for listof sideways floats. . . . . 1048
\parbox: Improved print/HTML output selection. . . . . 592
\raisebox: Improved print/HTML output selection. . . . . 597
\reflectbox: Improved print/HTML output selection. . . . . 838
\resizebox: Improved print/HTML output selection. . . . . 838
\rotatebox: Improved print/HTML output selection. . . . . 836

\rule: Fix: Colored rules. . . . . 614
\scalebox: Improved print/HTML output selection. . . . . 837
\textcolor: xcolor: New system for switching print and HTML outputs. 1214
General: 2018/06/06 . . . . . 1
MathJax: Supports \footnote, \footnotemark. . . . . 385
lwarp.css: Added ruled, boxed, boxruled floats. . . . . 269
lwarp.css: Increased float vertical margins. . . . . 269
algorithm2e: Added. . . . . 639
bigdelim: Improved print/HTML output selection. . . . . 679
breakurl: Fix: Text catcodes. . . . . 686
colortbl: New system for switching print and HTML outputs. . . . . 737, 738
ellipsis: Added \midwordellipsis. 754
errata: Added. . . . . 768
float: Added float styles. . . . . 795
float: Fix: Do not pre-define \l@name. . . . . 795
ltablex: Added. . . . . 903
marginnote: Fix: Long optional argument. . . . . 916
multirow: Improved print/HTML output selection. . . . . 965
register: Added. . . . . 1041
subcaption: Fix: \subref. . . . . 852
trimclip: Added. . . . . 1184
vowel: Added. . . . . 1202
xellipsis: Added. . . . . 1220
xfrac: Improved print/HTML \scalebox control. . . . . 1223
xltabular: Added. . . . . 1224
xpiano: Added. . . . . 1226
*lwarpmk*: Improved code factoring. 316
*lwarpmk*: Improved error handling. 316
Docs: Recompiling *lwarpmk* or CSS files. . . . . 189
Docs: Recreating the index for lwarp source. . . . . 187
New system for switching print and HTML outputs. . . . . 252
minipage: Improved print/HTML output selection. . . . . 589
BlockClass: Improved print/HTML output selection. . . . . 356
fminipage: Improved print/HTML output selection. . . . . 595
LWR@BlockClassWP: Improved print/HTML output selection. . . . 358
v0.58
\LWR@HTML@caption@begin: Improved print/HTML output selection. . . . 515
\LWR@HTML@caption@end: Improved print/HTML output selection. . . . 515
\LWR@HTML@ref: Improved print/HTML output selection. . . . . 503
\LWR@doindexentrysubsub: Adds support for \see, \seealso, \emph, \textbf, etc. . . . . 531
\LWR@hyperindexrefnullified: Adds support for \see, \seealso, \emph, \textbf, etc. . . . . 531
\LWR@hyperindexrefsubtwo: Adds support for \see, \seealso, \emph, \textbf, etc. . . . . 533
\LWR@indexitem: Accepts optional arg for repeatindex. . . . . 527
\dotfill: Improved print/HTML output selection. . . . . 609
\hfill: Improved print/HTML output selection. . . . . 609
\hrulefill: Improved print/HTML output selection. . . . . 609
\printindex: Fix: Extra \newpage to flush pending \index writes. . . . 913
General: 2018/07/07 . . . . . 1
*.lwarpmkconf: Added option makeindexstyle. . . . . 269
*.lwarpmkconf: Added options makeindex and xindy. . . . . 269
*.lwarpmkconf: Generated \AtBeginDocument. . . . . 269
lwarp.xdy: Requires makeindex.xdy. . . . . 311
lwarp.xdy: Supports bold, italic. . 311
lwarp_html.ist: Added. . . . . 310
lwarpmk.conf: Added option makeindexstyle. . . . . 269
lwarpmk.conf: Added options makeindex and xindy. . . . . 269
lwarpmk.conf: Generated \AtBeginDocument. . . . . 269
array: Improved print/HTML output selection. . . . . 656
attachfile2: Added. . . . . 661
attachfile: Added. . . . . 660
cases: Added. . . . . 695
imakeidx: Added. . . . . 858
index: Added. . . . . 862
intopdf: Added. . . . . 864
lwarp-patch-komascript: Modified indexing. . . . . 1235
lwarp-patch-memoir: Fix for \specialindex. . . . . 1259

lwarp-patch-memoir: Fix for multiple indexes. . . . . 1260
makeidx: Added. Moved from lwarp core. . . . . 913
memoir: Fix for \firsthlline, \lasthline. . . . . 485
memoir: Fix for booktabs. . . . . 490
pdfpages: Added. . . . . 1017
pdfx: Added. . . . . 1021
repeatindex: Added. . . . . 1044
splitidx: Added. . . . . 1102
textcomp: Improved print/HTML output selection. . . . . 1144
*lwarpmk*: Added makeindex and xindy options. . . . . 316
*lwarpmk*: Added -p option for project name. . . . . 316
*lwarpmk*: Added optional list of names for **lwarpmk printindex** and /cmdslwarpmk htmlindex. . . 316
*lwarpmk*: Glossary generation now uses *makeglossaries*. . . . . 316
*lwarpmk*: **lwarpmk clean** removes all *.ind and *.idx files. . . . . 316
Added makeindex option. . . . . 230
Added xindy option. . . . . 230
Added option makeindexStyle. . 228
Docs: Index, *makeindex*, imakeidx. 137
Docs: Misplaced \omit. . . . . 193
Fix: memoir and ccaption. . . . . 206
Improved print/HTML output selection. . . . . 608
Replaced each \csuse with \@nameuse to force error if undefined. . . . . 1
tabbing: Improved print/HTML output selection. . . . . 426
v0.59
\LWR@addbaselinemarker: Uses .eps if DVI *latex*. . . . . 543
\LWR@latexmkcmd: Fix: --shell-escape with *latexmk*. . . 264
\LWR@writeconf: Compilation commands now preassigned by lwarp instead of being computed by *lwarpmk*. . . . . 268
\[: Fix with \displaymathnormal. . 552
General: 2018/09/07 . . . . . 1
Slunits: Added. . . . . 1070
accsupp: Added. . . . . 633
amsmath: Moved from the lwarp core. . . . . 645
asymptote: Added. . . . . 659
axessibility: Added. . . . . 667
breqn: Added. . . . . 687
bxpapersize: Added. . . . . 689
canoniclayout: Added. . . . . 691
chemformula: Fix for \NMR. . . . . 726
draftcopy: Added. . . . . 748
epstopdf-base: Improved. . . . . 765
epstopdf: Improved. . . . . 765
fnbreak: Added. . . . . 803
graphics: Fix: Expand filename. . . 834
graphics: Now works with .pdf and .eps filename extensions. . . . . 834
nccfancyhdr: Added. . . . . 974
pdftricks: Added. . . . . 1021
pst-eps: Added. . . . . 1032
pstricks: Added. . . . . 1033
units: Added support for MathJax. 1196
xunicode: Added. . . . . 1230
*lwarpmk*: Added **lwarpmk epstopdf**. . . . . 316
*lwarpmk*: Consolidated compiling options into printlatexcmd and HTMLlatexcmd. . . . . 316
*lwarpmk*: Double insead of single-dashed --shell-escape option. . . . . 316
*lwarpmk*: Error if lwarpmk.conf format changed. . . . . 316
*lwarpmk*: Warning if operating system changed. . . . . 316
Added option dvipdfmx. . . . . 230
Added option dvipdfm. . . . . 230
Added option dvips. . . . . 230
Docs: **lwarpmk epstopdf**. . . . . 95
File: lwarp_mathjax.txt: Fix: Removed chapter number from tagged non-numeric MathJax equations. . . . . 312
File: lwarp_mathjax.txt: Updated to MathJax v2.7.4. . . . . 312
picture: Added an alt tag. . . . . 586
v0.60
\LWR@clearmidrules: tabular: Fix for midrules. . . . . 465
\LWR@parsenormalcolumn: tabular: Improved memory management: Not using xstring. . . . . 451
\LWR@tabledatasinglecolumntag: tabular: Improved memory management: Not using xstring. . 463
\LWR@tabularendofline: Fix: Slowdown for long tables. . . . . 447
General: 2018/09/19 . . . . . 1
tabular: Improved memory management: Global boolean. . . 438

tabular: Improved memory management: Not using xstring. . . . . 440, 965
2up: Added. . . . . 628
booklet: Added. . . . . 682
bophook: Added. . . . . 685
diagbox: Fix for par tags. . . . . 746
draftfigure: Added. . . . . 749
fancytabs: Added. . . . . 781
fullminipage: Added. . . . . 816
grid-system: Added. . . . . 839
layaureo: Added. . . . . 880
leading: Added. . . . . 883
listings: Fix for HTML entities. . . . 895
listings: Fix if inside a list. . . . 896, 898
thumbs: Added. . . . . 1157
thumb: Added. . . . . 1156
widows-and-orphans: Added. . . . 1206
v0.61
\DeclareGraphicsExtensions: Fix: EPS for DVI LaTeX. . . . . 827
\LWR@HTMLLatexCmd: Added HTMLLatexCmd option. . . . . 268
Added PrintLatexCmd option. . . . 268
\LWR@addcompilecmd: Removed spaces. . . . . 263
\LWR@closetabledatacell: Fix: Par tags in tabular. . . . . 442
\LWR@hyperindexrefnullified: Made robust, . . . . . 531
\LWRopseq: Added spaces. . . . . 225
\RequirePackage: Support up to 20 packages. . . . . 244
\inlinemathnormal: Changed name from \StopDynamicMath to \inlinemathnormal. . . . . 339
\inlinemathother: Changed name from \StartDynamicMath to \inlinemathother. . . . . 339
\listof: Fix: newfloat lists. . . . . 521
\lwarpsetup: Added. . . . . 226
General: 2018/10/13 . . . . . 1
lwarp.css: Footnotes text align left. 269
lwarp.css: Minipage table and footnotes: tighter margin. . . . . 269
chkfloat: Added. . . . . 730
cmdtrack: Added. . . . . 736
copyrightbox: Added. . . . . 739
dprogress: Added. . . . . 748
epsfig: Added. . . . . 764
graphics: Fix: EPS for DVI LaTeX. . . 831
graphics: Set keys before using filename, for epsfig. . . . . 834
lua-visual-debug: Added. . . . . 905
pdfprivacy: Added. . . . . 1020
psfragx: Added. . . . . 1032
psfrag: Added. . . . . 1031
pstool: Added. . . . . 1033
refcheck: Added. . . . . 1040
srcltx: Added. . . . . 1103
srctex: Added. . . . . 1104
supertabular: Fix for caption w/o opt arg. . . . . 1127
thinsp: Added. . . . . 1152
threadcol: Added. . . . . 1154
uspace: Added. . . . . 1198
vpe: Added. . . . . 1203
xbmks: Added. . . . . 1209
xtab: Fix for caption w/o opt arg. . 1229
Added HTMLLatexCmd option. . . . 229
Added PrintLatexCmd option. . . . 229
Docs: \tracinglwarp . . . . . 249
Docs: HTML entities. . . . . 122
Docs: Compiling using custom shell commands. . . . . 175
Docs: Fonts. . . . . 101
Docs: HTMLDebugComments 109, 249
Docs: Multiple indexes. . . . . 198
Don't write configuration files if processing pstool image. . . . . 262
Spaces redefined \AtBeginDocument. . . . . 608
v0.62
\@partcntformat: Added for ctex. . 394
\@partnameformat: Added for ctex. . 394
\InlineClass: Added optional word-processing style. Replaces \LWR@HTMLtextstyle. . . . . 357
\LWR@PreloadedPackage: Added. . . 577
\LWR@ProvidesPackagePass: Fix: Unknown option error. . . . . 246
\LWR@endofline: Extra space if optional arg. . . . . 610
\LWR@filestart: Refactored. . . . . 405
\LWR@isolate: Added. . . . . 221
\LWR@textcurrentfont: Added print version. . . . . 607
Tracks depth to avoid nesting repeated font changes. . . . . 602
\colorboxBlock: xcolor: Fix: Horiz white space. . . . . 1215
\fcolorbox: Fix: No longer requires xifthen. . . . . 583
\fcolorboxBlock: xcolor: Fix: Horiz white space. . . . . 1216, 1217
\l@chapter: Don't define if no \chapter. Fix for algorithm2e. . . 525
\slshape: Added. . . . . 605
\textup: Fixed WP span class. . . . . 600
\theHTMLSection: Added. . . . . 403

\theHTMLTitleSection: Added. . . . 402
\theHTMLTitleSeparator: Refactored. 402
General: 2018/11/19 . . . . . 1
\textbf and related: Improved font detection. . . . . 598
lwarp.css: Added css for xfrac, nicefrac. . . . . 269
lwarp.css: Fixed css for \textup. 269
lwarp.css: Reduced margins in titlepage. . . . . 269
lwarp_formal.css: Fix: Font for verse. . . . . 306
2in1: Added. . . . . 628
CJKutf8: Prevented unless xeCJK. . 732
CJK: Prevented unless xeCJK. . . . 731
asymptote: Improved alt tags. . . 659
bitpattern: Added. . . . . 681
calc: Fix: Required for print version. 238
chngpage: Fix: Loads lwarp-chngpage. . . . . 730
ctexpatch: Added patch. . . . . 622
flippdf: Added. . . . . 794
graphics: Fix: Filename expansion. 833
graphics: Fix: FormatWP. . . . . 831
musicography: Added. . . . . 968
nicefrac: Improved font control and css, honors nice, ugly. . . . . 986
notespages: Added. . . . . 992
octave: Added. . . . . 1005
pdfcomment: Added. . . . . 1016
pdfmarginpar: Added. . . . . 1017
register: Updated to v1.8. . . . . 1041
rviewport: Added. . . . . 1048
semantic-markup: Added. . . . . 1060
textcomp: Fix conflict with xunicode. . . . . 1145
tram: Added. . . . . 1183
twoup: Added. . . . . 1186
ulem: Improved compatibility with CJKulem. . . . . 1189
ulem: Now works in a lateximage. 1189
unitsdef: Added. . . . . 1196
units: Improved font control and css, honors loose, tight. . . . . 1196
xcolor: Fix: Horiz white space. . . . 1217
xechangebar: Added. . . . . 1220
xfrac: Improved css. . . . . 1223
xunicode: Fix conflict with textcomp. . . . . 1230
Added early checks for CJK, CJKutf8. 205
Docs: asymptote. . . . . 161
Docs: miktex-poppler-bin-* . . . . . 82
Docs: *MiKTeX Console* . . . . . 78
Docs: Improved MiKTEX install instructions. . . . . 78
Docs: UTF-8 locale. . . . . 178
File: lwarp_mathjax.txt: Removed inoperable siunitx extension. . . . . 312
Logos: CSS instead of <sup>, <sub>. 616
Logos: Fix for XeTEX logo if graphics is not loaded. . . . . 616
Logos: Improved CSS. . . . . 616
Logos: Made robust. . . . . 616
fcolorminipage: xcolor: Fix: Horiz white space. . . . . 1218
Fix: No longer requires xifthen. . . 584
fminipage: Fix: Horiz white space. . 597
LWR@blocktextcurrentfont: Added print version. . . . . 607
v0.63
\LWR@HTMLLatexCmd: ujarticle and related: Compile options. . . . . 267
\LWR@LwarpStart: Fixes for xeCJK. . 406
\LWR@atbeginverbatim: Fix for xeCJK. 424
\LWR@checkloadbefore: Added. . . . 204
\LWR@checkloadfilename: Added to reduce number of lwarp-* files. . 242
\LWR@checkloadnever: Added. . . . . 204
\LWR@compileuplatex: Added. . . . . 264
\LWR@createautosec: Fix for xeCJK. 392
\LWR@earlyclassloadnever: Added. 205
\LWR@filestart: Fix: Break ligature for luatexko. . . . . 404
\LWR@firstoffour: Added. . . . . 222
\LWR@htmlclosecomment: Fix: Break ligature for luatexko. . . . . 353
\LWR@isolate: Fix for xeCJK. . . . . 221
\LWR@notltjloadafter: Added more classes. . . . . 203
Added. . . . . 203
\LWR@subhtmlelementclass: Fix for xeCJK. . . . . 354
\LinkHome: Fix: Print version. . . . . 344
\linkhomename: Added. . . . . 343
General: 2018/12/03 . . . . . 1
lwarp.css: Added css for vertical writing. . . . . 269
lwarp.css: Improved css for mdframed. . . . . 269
amsthm, mdframed: Fix for enforced load order. . . . . 649
emumitem: v3.6: Nullifiy \DrawEnumitemLabel. . . . . 763
everyhook: Fix for bxjs* classes. . . 239
geometry: Fix for bxjs* classes. . . 237
mdframed: Avoid thin rules. . . . . 935
mdframed: Improved font control. . . . . 938–940
stfloats: Adapted to ltj* classes. . . 1119
xpinyin: Added. . . . . 1226

zhlineskip: Added. . . . . 1232
Added pTEXsupport. . . . . 202
Docs: \linkhomename. . . . . 109
Docs: \sidetocname. . . . . 111
Fix: Default \LWR@mdfive. . . . . 217
Improved titles. . . . . 938, 939
pTEX: Encoding. . . . . 217
pTEX: Load upquote. . . . . 219
pTEX: No newunicodechar. . . . . 218
LWR@BlockClassWP: Fix for xeCJK. . . 358
v0.64
\LWR@HTMLLatexCmd: utarticle and related: Added. . . . . 267
\LWR@checkloadfilename: Prevented bitfield, doublespace, newthm, rplain, si. . . . . 242
\LWR@section: Support for ujarticle and related. . . . . 397
\enskip: Made robust. . . . . 611
\qquad: Made robust. . . . . 611
\quad: Made robust. . . . . 610
\theHTMLTitleSeparator: Added utarticle and related. . . . . 402
General: 2018/12/08 . . . . . 1
addlines: Updated to v0.3. . . . . 638
biblatex: Added patch for CTEX. . . 674
bsheaders: Added. . . . . 688
gmeometric: Added. . . . . 826
marginal: Added. . . . . 915
rmpage: Added. . . . . 1045
scrlayer-scrpage: Fixes. . . . . 1057
scrlayer: Fixes. . . . . 1055
scrpage2: Added. . . . . 1057
ujarticle and related: Improved \today. . . . . 621
Added utarticle and related. . . . . 621
v0.65
\LWR@LwarpEnd: Improved css for page layout. . . . . 409
\LWR@LwarpStart: Improved css for page layout. . . . . 408
\LWR@PreloadedPackage: \AtBeginDocument to avoid option clashes. . . . . 577
\LWR@hyperindexrefnullified: Added \textsi. . . . . 531
\LWR@newhtmlfile: Error if duplicate file name. . . . . 388
Improved css for page layout. 387, 390
\LWR@nullfonts: Added \textsi. . . 537
\LWR@restoreorigformatting: Fix: tabular*. . . . . 536
\enskip: Changed to Unicode EN SPACE. . . . . 611
\quad: Changed to Unicode EM SPACE. 610
\sishape: Added \sishape. . . . . 604
\textsi: Added. . . . . 601
General: 2018/12/22 . . . . . 1
lwarp.css: Added \sishape, \textsi. . . . . 269
lwarp.css: Improved css for page layout. . . . . 269
lwarp.css: Improved css for quotations. . . . . 269
lwarp.css: SideTOCto left for improved \marginpars. . . . . 269
lwarp_formal.css: SideTOCto left for improved \marginpars. . . . 306
lwarp_sagebrush.css: SideTOCto left for improved \marginpars. . . 301
bounddvi: Added. . . . . 685
embrac: Added. . . . . 755
footnoterange: Added. . . . . 810
gentombow: Added. . . . . 821
geometry: Fix for bxjs* classes. . . 237
graphics: Added \includegraphics alt key. . 581, 827, 829, 830, 833, 834
lltjext: Added. . . . . 899
multicolrule: Added. . . . . 962
multicol: Added \docolaction. . . 962
plarydshln: Added. . . . . 1028
plextarydshln: Added. . . . . 1029
plextcolortbl: Added. . . . . 1030
plext: Added. . . . . 1028
pxatbegshi: Added. . . . . 1034
pxeveryshi: Added. . . . . 1034
pxftnright: Added. . . . . 1035
pxjahyper: Added. . . . . 1035
tascmac: Added. . . . . 1134
versonotes: Added. . . . . 1201
Added early checks for jarticle, tarticle, and related. . . . . 205
Fix for \rensuji. . . . . 621
Fix space between class and id. . . 358
tabular: Added support for plext. . . 491
Fix: tabular*. . . . . 491
Fix: Rule color. . . . . 493
minipage: Refactored to later allow Japanese <t/y> argument. . . . . 589
LWR@figcaption: Uses <figurecaption> instead of <figcaption>. . . . . 515
v0.66
\@mpfootnotetext: Improved HTML formatting. . . . . 372
\IgnoreMinipageWidths: Added, . . 589
\LWR@@footnotetext: Improved HTML formatting. . . . . 371
\LWR@LwarpStart: Fix: TOC, LOF, LOT links. . . . . 408

Improved HTML formatting. . . . . 571
minipage: Honor \LWR@forceminipagefullwidth. 590
v0.67
\FilenameNullify: Added. . . . 540, 607
\FilenameSimplify: Added. . . . 377, 386
\LWR@doequation: xfakebold: Added support. . . . . 558
\LWR@doubledollar: xfakebold: Added support. . . . . 551
\LWR@filenamenoblanks: Improved file name generation. . . . . 377
\LWR@lookforpackagename: easyReview: Supported. . . . . 243
\LWR@nullfonts: Add'l symbols. . . . 537
\LWR@simplifycustom: Added. . . . . 377
\LWR@subsingledollar: xfakebold: Added support. . . . . 549
\LWR@subsingledollarsvg: xfakebold: Added support. . . 547, 548
General: 2019/02/23 . . . . . 1
academicons: Added. . . . . 631
bbding: Added. . . . . 669
changes: Added. . . . . 698
color: Fix for version number. . . . 737
dingbat: Added. . . . . 746
eurosym: Added. . . . . 772
fitbox: Added. . . . . 791
fontawesome5: Added. . . . . 806
fontawesome: Added. . . . . 805
foreign: Added. . . . . 811
gloss: Added. . . . . 824
karnaugh-map: Added. . . . . 868
marvosym: Added. . . . . 917
multicap: Added. . . . . 960
nomencl: Added. . . . . 990
notes: Added. . . . . 991
pifont: Added. . . . . 1027
struktex: Added. . . . . 1119
textcomp: Nullify in filenames. . . 1146
typicons: Added. . . . . 1188
umoline: Added. . . . . 1190
xfakebold: Added support. . . . . 541
xfakebold: Added. . . . . 1221
xunicode: Nullify in filenames. . . 1230
AMS environments: Added xfakebold support. . . . . 646
eqnarray: xfakebold: Added support. 564
v0.68
\LWR@@footnotetext: Factored for multiple foot boxes. . . . . 371
\LWR@checkloadfilename: Prevented alg, algorithmic, fncylab, pdfcprot. 242
\LWR@printpendingfootnotes: Factored for multiple footnote boxes. . . . . 373
\LWR@tabular@warpprintonly: Added. . . . . 491
General: 2019/03/05 . . . . . 1
bigfoot: Added. . . . . 680
fnpara: Added. . . . . 804
footnotebackref: Added. . . . . 810
layouts: Added. . . . . 881
listings: Fix for listings v1.7. . . . . 898
longtable: Improved error handling. 902
manyfoot: Added. . . . . 914
niceframe: Added. . . . . 987
perpage: Added. . . . . 1022
showtags: Added. . . . . 1065
tablefootnote: Added. . . . . 1130
threeparttablex: Added. . . . . 1156
threeparttable: Fix for caption type. . . . . 1155
*lwarpmk*: Improved error handling if incomplete compile. . . . . 316
Prevented alg, algorithmic, fncylab, pdfcprot. . . . . 205
tabular: Fix: \warpprintonly inside tabular. . . . . 493
v0.69
\LWR@maybetocdata: Added support for tocdata. . . . . 523
\framebox: Fix: Handle paren arg. . . 594
\hypertoc: Added support for tocdata. 523
\hypertocfloat: Added support for tocdata. . . . . 525
\makebox: Fix: Handle paren arg. . . . 593
\multicolumnrow: multirow: Error if \multirow without \mrowcell. . . 967
General: 2019/03/21 . . . . . 1
array: Fix for \tabularnewline. 656, 902
ctable: Added. . . . . 740
eqlist: Added. . . . . 766
eqparbox: Added. . . . . 767
ftcap: Added. . . . . 816
graphics: Warning if using scale option. . . . . 829
keyfloat: Updated for v2.00. . . . . 871
listliketab: Added. . . . . 899
minitoc: Added. . . . . 952
multirow: Error if \multirow without \mrowcell. . . . . 965
rotating: Requires graphicx. . . . . 1046
supertabular: Fix: Clear caption after use. . . . . 1128
tabularx: Require array. . . . . 1130
tabulary: Require array. . . . . 1131
tocdata: Added. . . . . 1172

topcapt: Added. . . . . 1183
xtab: Fix: Clear caption after use. . 1230
tabular: Error if \multirow without \mrowcell. . . . . 492, 494, 495
lateximage: Fix for *pdftotext* errors from font size change. . . . . 574
fminipage: Honors \minipagefullwidth. . . . . 596
v0.70
\LWR@closeparagraph: Reduced underfull \hbox warnings. . . . . 362
\LWR@lookforpackagename: changes: Updated to v3.1.2. . . . . 243
\LWR@mathjaxfilename: Added. . . . 366
\LWR@restoreorigformatting: Fix: \& in a lateximage. . . . . 536
\MathJaxFilename: Added. . . . . 367
\enddocument: If labels changed, require recompile before making limages. . . . . 410
\framebox: Fix: Accept long arg. . . . 594
\makebox: Fix: Accept long arg. . . . 593
Fix: Ignore width of 0pt. . . . . 593
Fix: No width given. . . . . 593
General: 2019/04/03 . . . . . 1
autonum: Added. . . . . 665
changelayout: Added. . . . . 697
changes: Updated to v3.1.2. . . . . 698
inputtrc: Added. . . . . 864
mathtools: Added. . . . . 925
metalogox: Added. . . . . 946
metalogo: Used in print mode. . . 946
textcomp: Fix for \textinterrobang. . . . . 1144
textpos: Added optional arg to textblock. . . . . 1147
xunicode: Fix for \textinterrobang. . . . . 1230
AMS environments: Refactored. . . 646
Ensure vector font. . . . . 218
File: lwarp_mathjax.txt: Loads autoload-all.js extension. . . . 312
File: lwarp_mathjax.txt: Updated to MathJax v2.7.5. . . . . 312
Logos: Improved for metalogox, lateximages. . . . . 616
LWR@nestspan: Improved minipage, \parbox inside a span. . . . . 352
v0.71
\@mpfootnotetext: Improved HTML formatting. . . . . 373
Reduced underfull \hbox warnings. 373
\LWR@closeparagraph: Flush left captions. . . . . 362
\LWR@closetabledatacell: Fix: Tabular par tags. . . . . 442
\LWR@stoppars: Reduced underfull \hbox warnings. . . . . 364
\expandcolspec: Added support for tabular '*' column. . . . . 453
General: 2019/04/29 . . . . . 1
caption: Reduced underfull \hbox warnings. . . . . 692
chemfig: Updated to v1.4. . . . . 704
endfloat: Updated for v2.7. . . . . 756
lwarp-common-multimedia: Added. . . . . 1265
media9: Added. . . . . 943
movie15: Added. . . . . 959
multimedia: Added. . . . . 963
textpos: Updated for v1.9.1. . . . . 1147
*lwarpmk*: If wrong lwarpmk.conf version, or wrong OS, displays the print command to recompile. . . 316
Docs: Error testing. . . . . 191
quotation: Fix: blockquotation tag. 422
v0.72
\LWR@newautopagelabel: Fix: References for xr, xr-hyper. . . . 381
\LWR@printmccoldata: Fix: \multicolumn parameters. . . . . 475
\LWR@restoreorigformatting: Use \LWR@formatted for \bfseries, etc. . . . . 536
\chapter: Added support for hypbmsec. . . . . 401
\ebweight: nfssext-cfr: Added. . . . 603
\hypertoc: Fix: References for xr, xr-hyper. . . . . 523
\hypertocfloat: Fix: References for xr, xr-hyper. . . . . 524
\lgweight: nfssext-cfr: Added. . . . 603
\paragraph: Added support for hypbmsec. . . . . 401
\part: Added support for hypbmsec. 400
\section: Added support for hypbmsec. . . . . 401
\subparagraph: Added support for hypbmsec. . . . . 401
\subsection: Added support for hypbmsec. . . . . 401
\subsubsection: Added support for hypbmsec. . . . . 401
\texteb: nfssext-cfr: Added. . . . . 599
\textlg: nfssext-cfr: Added. . . . . 599
\textulc: fontaxes: Added. . . . . 600
\ulcshape: fontaxes: Added. . . . . 604
General: 2019/06/08 . . . . . 1
lwarp.css: Added backnaur. . . . 269

lwarp.css: Removed unneeded support for \sishape, \textsi. . 269
backnaur: Added. . . . . 668
boxedminipage2e: Added support for lateximages. . . . . 685
changes: Fix references for xr, xr-hyper. . . . . 698
fontaxes: Added. . . . . 602, 807
gloss: Fix references for xr, xr-hyper. 824
hypbmsec: Added. . . . . 845
minibox: Added. . . . . 951
nfssext-cfr: Added. . . . . 980
nomencl: Fix references for xr, xr-hyper. . . . . 990
pdfcrypt: Added. . . . . 1017
shapepar: Added. . . . . 1064
slantsc: Added. . . . . 1098
soulutf8: Fix: Loads soul. . . . . 1101
tabfigures: Added. . . . . 1130
xr-hyper: Added. . . . . 1228
xr: Added. . . . . 1228
zhlineskip: Updated to v1.0e. . . . . 1232
Use \LWR@formatted for \bfseries, etc. . . . . 258, 602
v0.73
\@include: Fix: \newpage instead of \clearpage. . . . . 247
\HTMLTitle: Added default title if none specified. . . . . 367
\LWR@LwarpStart: Fix: Empty header/footer. . . . . 407
\LWR@addbaselinemarker: Improved warning messages. . . . . 543
\LWR@createfooter: Fix: Empty header/footer. . . . . 387
\LWR@descitem: Fix: HTML tags. . . . 432
\LWR@forceemptyline: Added. . . . . 221
\LWR@gsavebox: Added global save boxes. . . . . 222
\LWR@htmlelementclass: Vertical space. . . . . 355
\LWR@htmlelementclassline: Vertical space. . . . . 356
\LWR@indentHTMLtwo: Added. . . . . 351
\LWR@indexitem: Fix: Avoid empty . . . . . 527
\LWR@indexsubitem: Fix: Avoid empty . . . . . 527
\LWR@indexsubsubitem: Fix: Avoid empty . . . . . 527
\LWR@newhtmlfile: Fix: Empty header/footer. . . . . 390
\LWR@nullfonts: Fix: \hspace in sectioning file name. . . . . 539
\LWR@titlingmaketitle: titling: Fix: Paragraph tags. . . . . 419, 1169
Fix: Paragraph tags. . . . . 419
\attribution: Fix: Paragraph tags. . 421
\color: xcolor: Added HTML support. 1214
\fboxBlock: Fix: Paragraph tags. . . . 595
\hspace: Fix: Avoid empty . . 612
\l@book: Added \book for memoir. . 525
\maketitle: titling: Fix: Paragraph tags. . . . . 1168
Fix: Paragraph tags. . . . . 418
\marginparBlock: Fix: Paragraph tags. 375
\postbookname: Added \book for memoir. . . . . 400
\printthanks: Fix: Paragraph tags. . 414
\rule: Fix: Avoid empty . . . . 615
General: 2019/07/11 . . . . . 1
lwarp.css: Added \book for memoir. . . . . 269
lwarp.css: Improved pkgtocdata formatting. . . . . 269
lwarp_formal.css: Added \book for memoir. . . . . 301, 306
boxedminipage2e: Fix: Paragraph tags. . . . . 685
epigraph: Fix: Paragraph tags. . . . 763
fancyvrb: Fix: Nested /<pre>. . . . . 783, 786
fancyvrb: Btrivlist: Fixed paragraph tags. . . . . 777
intopdf: Updated to v0.2.1. . . . . 864
listings: Fix: Paragraph tags. . . . . 897
lwarp-common-multimedia: Fix: No size for audio file. . . . . 1266, 1267
lwarp-common-multimedia: Fix: Paragraph tags. . . . . 1268
lwarp-patch-komascript: Fix for captions. . . . . 1235
lwarp-patch-memoir: Added \book. . . . . 1243
lwarp-patch-memoir: Fix for \frontmatter* and \mainmatter*. . . . . 1243
lyluatex: Added. . . . . 911
musicography: Updated to 2019/05/28. Now supports lateximages. . . . . 968
quotchap: Fix: Paragraph tags. . . 1036
quotchap: Updated to v1.2. . . . . 1035
quoting: Fix: Paragraph tags. . . . . 1036
scrextend: Fix: Paragraph tags. . . . . 1052, 1053
stackengine: Added. . . . . 1105
threeparttable: Added measuredfigure. . . . . 1155

tocdata: Honors \tocdataformat. 1172
tocdata: Improved formatting. . . . 1173
tocdata: Updated to v2.03. . . . . 1172
versonotes: Updated to v0.4. . . . . 1201
vwcol: Fix: Paragraph tags. . . . . 1203
xy: Fix for \xybox. . . . . 1231
xy: Improved xy, reverted \xymatrix, for qcicuit. . . . . 1231
Added \book for memoir. . . . 334, 349
AMS environments: Fix: alt tags. 646
AMS environments: Fix: Paragraph tags. . . . . 646
Numbered HTML entity used for text dollar. . . . . 542
tabular: Fix and warning for tabular inside a . . . . . 491
LWR@blocktextcurrentfont: Fix: Paragraph tags. . . . . 602
LWR@nestspan: Fix: quote, quotation inside a span. . . . . 352
v0.74
\@ensuredmath: Add \ThisAltText. 553
\AltTextClose: Added. . . . . 540
\AltTextOpen: Added. . . . . 540
\ImageAltText: Added. . . . . 540
\LWR@ThisAltText: Add \ThisAltText. . . . . 541
\LWR@addlinktitle: Added. . . . . 502
\LWR@doequation: Add \ThisAltText. . . . . 559
\LWR@doubledollar: Add \ThisAltText. . . . . 552
\LWR@lateximage@oneimage: Factored from lateximage. . . . . 569
\LWR@lateximage@oneimageb: Factored from lateximage. . . . 569
\LWR@setcurrentfont: Factored. . . 542
\LWR@singledollar: Add \ThisAltText. . . . . 552
\LWR@singledollarmeasure: Fix: Font control. . . . . 544
\LWR@subinlineimage: Add \ThisAltText. . . . . 507
\LWR@subsingledollar: Add \ThisAltText. . . . . 550
\LWR@subsingledollarsvg: Adds star argument for lateximage. . . . . 547
\LateximageFontScale: Adjusted SVG math font scaling default to 1. . . . 567
\MathImageAltText: Renamed from \mathimage. . . . . 541
\PackageDiagramAltText: Renamed from \packagediagramname. . . . 541
\ThisAltText: Add \ThisAltText. . 541
\hspace: Ignore negative space. . . . . 611
General: 2019/09/02 . . . . . 1
lwarp.css: Added lyluatex. . . . . 269
amsmath: Add \ThisAltText. . . 647
forest: alt text. . . . . 811
geometry: Remembers user's geometry. . . . . 821
graphics: Add \ThisAltText. . . . . 829, 834, 835
lyluatex: Adapts to user's geometry. 911
lyluatex: Preserves left margin. . . 911
lyluatex: Renamef \lyluateximagename. . . . . 911
lyluatex: Split system images, assign class. . . . . 911
mhchem: Modified for new lateximage. . . . . 948
pdfpages: Adjust to user's paper size. . . . . 1019
stackengine: alt tags. . . . . 1105
struktex: alt text. . . . . 1119
tikz: Added alt text. . . . . 1158
*lwarpmk*: **lwarpmk clean** removes add'l files. . . . . 316
*lwarpmk*: **lwarpmk epstopdf** and **pdftosvg** honor directories. . . . . 316
Remembers user's geometry. . . . . 236
lateximage: Add \ThisAltText. . . . 575
Added second starred argument. 570, 575
Improved alt text. . . . . 571
New syntax for \LWR@subinlineimage. . . . . 574
eqnarray: Add \ThisAltText. . . . . 565
LWR@displaymathother: Uses \MathImageAltText. . . . . 554
LWR@equationother: Uses \MathImageAltText. . . . . 554
v0.75
\normalcolor: xcolor: Added for HTML. . . . . 1212
General: 2019/09/23 . . . . . 1
lwarp.css: Improved marginblock. 269
keyfloat: Fix: \normalcolor. . . . . 871
wrapfig: Fix for \linewidth. . . . 1208
wrapfig: Fix for width. . . . . 1208
minipage: Fix: \linewidth. . . . . 591
v0.76
General: 2019/10/08 . . . . . 1
lwarp.css: Fix for small caps. . . . 269
acro: Updated for v2.10. . . . . 634
xr-hyper: Updated for v6.1. . . . . 1228
xr: Updated for v5.05 and xr-hyper v6.1. . . . . 1228
Docs expanded: Multiple projects. . 95
File: lwarp_mathjax.txt: Updated to MathJax v2.7.6. . . . . 312

mathtools: Added MathJax emulation. . . . . 926
multirow: Add: MathJax emulation. 967
multirow: Fix: Centered vertical alignment. . . . . 966
niceframe: Fix: Adjust for virtual page size. . . . . 987
parallel: Added. . . . . 1008
parcolumns: Added. . . . . 1010
pdfcolfoot: Added. . . . . 1014
pdfcolmk: Added. . . . . 1015
pdfcolparallel: Added. . . . . 1015
pdfcolparcolumns: Added. . . . . 1015
pdfcol: Added. . . . . 1014
physics: Added. . . . . 1023
siunitx: Fix: \square, \cubed. . . . 1083
siunitx: Improved MathJax. 1080, 1081
slashed: Added. . . . . 1098
steinmetz: Added. . . . . 1118
svg: Added. . . . . 1128
transparent: Supports lateximages. . . . . 1184
unicode-math: Added. . . . . 1192
widetable: Added. . . . . 1206
witharrows: Added. . . . . 1206
xcolor: Fix: Nested tabulars. 1218, 1219
xltabular: Fix: Require ltablex. . . . 1224
xurl: Updated to v0.08. . . . . 1231
AMS environments: Fix: Nested. . 646
Factored to \LWR@setvirtualpage. . 800, 834, 876
Fix: Use newfloat instead of float. 801
Fix: Use full \linewidth. . . . . 800
Remember HTML font size. . . . . 608
tabular: colortbl: Fix: Nested tabulars. . . . . 493
Fix: Nested tabulars. . . . . 495
warpMathJax: Added. . . . . 235
lateximage: Improved \linewidth. . 572
minipage: Fix: \linewidth frame padding. . . . . 591
Fix: Adjust for virtual page size. . . 589
fminipage: Fix: Adjust for virtual page size. . . . . 596
LWR@setvirtualpage: Factored. . . . 588
v0.80
\CustomizeMathJax: Fix: Made \@onlypreamble. . . . . 384
Warn of slow compile. . . . . 384
\LWR@checkloadfilename: Prevented formula, shadethm, slashbox. . . 242
\LWR@infoprocessingmathjax: Add: Info message. . . . . 384
\LWR@restoreorigformatting: Improved math, displaymath. . . 536
\fcolorbox: Made robust. . . . . 583
\fcolorboxBlock: Made robust. . . . 583
\includegraphics: Made robust. . . 835
General: 2020/02/19 . . . . . 1
\textbf and related: Use HTML series, etc. . . . . 598
accessibility: Added MathJax emulation. . . . . 633
accsupp: Added MathJax emulation. . . . . 634
autobreak: Added. . . . . 664
biblatex: Creates hyperlinks. . . . . 675
centernot: Added. . . . . 696
chemmacros: Updated to v5.10. 718, 725
extarrows: Added. . . . . 773
fewerfloatpages: Added. . . . . 790
fouridx: Added. . . . . 811
gensymb: Added. . . . . 821
ghsystem: Added. . . . . 822
gmeometric: Requires geometry. 826
hhline: Added. . . . . 844
leftidx: Added. . . . . 884
mathcomp: Added. . . . . 919
mathdots: Added. . . . . 921
mathfixs: Added. . . . . 921
mismath: Added. . . . . 953
nccmath: Added. . . . . 975
noitcrul: Added. . . . . 990
pdfcomment: Added MathJax emulation. . . . . 1016
relsize: Added MathJax emulation. 1043
rmathbr: Added. . . . . 1045
subsupscripts: Added. . . . . 1126
tagpdf: Added. . . . . 1131
unicode-math: Improved MathJax. . . . . 1192, 1193
url: Creates hyperlinks. . . . . 1198
xfrac: Added MathJax emulation. 1224
AMS environments: Fix: Centering starred envs. . . . . 646, 647
Improved math, displaymath. . . . 553
Prevented formula, shadethm, slashbox. . . . . 205
lateximage: Fix: Rule color in lateximage. . . . . 573
fcolorminipage: Made robust. . . . . 584
eqnarray: Fix: eqnarray*. . . . . 564
v0.81
\LWR@addbaselinemarker: Improved warning messages. . . . . 543
\LWR@checkloadfilename: Prevented statex. . . . . 242
\LWR@replacestrings: Added. . . . . 381
\LWR@subHTMLsanitize: Faster. . . . 382

\textcolor: xcolor: \textcolor: Spurrious space. . . . . 1214
General: 2020/03/04 . . . . . 1
lwarp.css: Added nolbreaks. . . . 269
DotArrow: Added. . . . . 747
SIunits: Improved \unit. Fixed in math mode. Added MathJax emulation. . . . . 1070
axessibility: Added MathJax emulation. . . . . 667
axessibility: Updated to 2020/01/08 version. . . . . 667
colonequals: Added. . . . . 736
decimal: Added. . . . . 745
dotlessi: Added. . . . . 748
econometrics: Added. . . . . 751
engtlc: Added. . . . . 758
gridset: Updated to v0.3. . . . . 840
hyperref: Added \pdfstringdefDisableCommands. 854
luamplib: Added. . . . . 906
multiobjective: Added. . . . . 963
nolbreaks: Added. . . . . 990
physunits: Added. . . . . 1024
returntogrid: Added. . . . . 1044
stackrel: Added. . . . . 1106
statex2: Added. . . . . 1107
statmath: Added. . . . . 1116
*lwarpmk*: Improved error if in lwarp source directory. . . . . 316
Prevented statex. . . . . 205
v0.82
\LWR@disablepinyin: Added. . . . . 221
\LWR@doequation: MathJax: Improved footnotes. . . . . 559
\LWR@syncmathjax: Removed <par> tags. . . . . 556
General: 2020/03/25 . . . . . 1
MathJax: Improved footnotes. 385, 559
amsmath: Fixed: \intertext for MathJax. . . . . 648
chemfig: Updated to v1.5. . . . . 704
draftwatermark: Updated to v2.0. . 749
endnotes: Added MathJax emulation. . . . . 758
endnotes: Fix: Mark in print mode. 758
etoc: Added. . . . . 770
luatexko: Added. . . . . 906
lwarp-patch-memoir: Supports tocvsec2. . . . . 1243, 1247
marginnote: Added MathJax emulation. . . . . 917
marginnote: Fix: Neutralize in print mode. . . . . 917
nccfoots: Added MathJax emulation. . . . . 974
pagenote: Added MathJax emulation. . . . . 1007
parnotes: Added MathJax emulation. . . . . 1013
sidenotes: Added MathJax emulation. . . . . 1068
soul: Fixed: \<. . . . . 1099
syntonly: Added \nopages@. . . . 1129
syntonly: Added to \LWR@loadafter. . . . . 206
ulem: Fixed: \dashuline. . . . . 1189
xpinyin: Added full pinyin support. 1226
v0.83
General: 2020/03/27 . . . . . 1
lwarp-patch-memoir: Fixed framed. . . . . 1238
lwarp-patch-memoir: Fixed: \specialindex. . . . . 1260
lwarp-patch-memoir: No longer requires subfigure. . . . . 1238
lwarp-patch-memoir: Updated for new sizes. . . . . 1239
lwarp-patch-memoir: Updated. . . 1242
physunits: Updated to v1.0.4. . . . 1024
v0.84
\@currentHref: backref: Fixed from lwarp v0.72 changes. . . . . 505
\@currentlabelname: Default name for previous/next links. . . . . 498
\@fnsymbol: \LWR@formatted, fixed double bar. . . . . 417
\@makecaption: caption now optional. 513
Warn inside a . . . . . 514
\@textsubscript: Use \LWR@formatted. No longer \AtBeginDocument. . . . . 606
\@textsuperscript: Use \LWR@formatted. . . . . 606
\@xdlbfloat: caption now optional. 511
\AddSubtitlePublished: Added \subtitle, \published for koma*. . . . . 420
Fixed \subtitle, \printsubtitle if no titling. . . . . 420
\HTMLFirstPageBottom: Added \FirstPageBottom. . . . . 365
\LWR@LwarpEnd: Added prev/next links. 409
Fix: No footer for epub . . . . . 409
\LWR@LwarpStart: Added prev/next links. . . . . 408
\LWR@createfooter: Added \FirstPageBottom. . . . . 387

\LWR@domulticolumn: Fix: Multicolumn style. . . . . 478
\LWR@excludecomment: Independent cut files. . . . . 233
\LWR@filenamenoblanks: Fix: Dashes in filename. . . . . 380
\LWR@filestart: Improved HTML title. 403
\LWR@floatbegin: Warn inside a . . . . . 509
\LWR@forcenewautoidanchor: <par> handling. . . . . 512
\LWR@htmlsectionfilename: Fix: Sections called "Index" or "index" have -0 appended to their filenames if no prefix. . . . . 342
\LWR@new@label: Removed optional args. . . . . 501
\LWR@newhtmlfile: Added prev/next links. . . . . 388, 390
\LWR@nullfonts: Add'l symbols. . . . 537
Factored out redefinitions. . . . . 537
Fix: Accents. . . . . 537
Revised \texorpdfstring. . . . . 540
\LWR@section: Added prev/next links. 399
Warn inside a . . . . . 394
\LWR@startpars: Ignore if in lateximage. . . . . 363
\LWR@stoppars: Ignore if in lateximage. . . . . 364
\LinkNext: Added prev/next links. . . 345
\LinkPrevious: Added prev/next links. 345
\attribution: Added print mode. . . 421
\caption@end: caption now optional. 516
\captionlistentry: caption now optional. . . . . 516
\captionof: caption now optional. . 517
\end@dlbfloat: caption now optional. 511
\linknextname: Added prev/next links. 344
\linkpreviousname: Added prev/next links. . . . . 344
\printthanks: Fix: \printthanks in print mode. . . . . 414
\sscshape: Moved to core. . . . . 605
\textssc: Moved to core. . . . . 601
\textsubscript: Use \LWR@formatted. No longer \AtBeginDocument. . . . . 606
\textsuperscript: Use \LWR@formatted. . . . . 606
\theHTMLTitleSeparator: Improved spacing for xeCJK. . . . . 402
\verbatiminput: Added print mode. 425
General: 2020/04/24 . . . . . 1
LaTeX accents: Add'l symbols. . . . . 260
lwarp.css: Added koma-* subject. 269
lwarp.css: Fix: Minipage tex align. 269
lwarp.css: Fix: Top nav if narrow window. . . . . 269
lwarp.css: Improved nfssext-cfr. 269
lwarp.css: Improved realscripts. . 269
abstract: Updated for memoir. . . . 630
alltt: Added print mode. . . . . 644
amsthm: Fix for \nameref. . . . . 651
backref: Fixed from lwarp v0.72 changes. . . . . 669
biblatex: Fixed: Requires hyperref. 675
boxedminipage: Renamed from boxedminipage2e per author. 685, 686
caption: Improved integration. . . 692
caption: Non-width \parboxes. . . 691
caption: Simplified. . . . . 691
epigraph: Added print mode. . . . . 763
fixme: Added section name. . . . . 793
float: Fix: Recursive name. . . . . 795
fontaxes: Moved sscshape to core. \FilenameNullify. . . . . 807
lwarp-patch-memoir: Creates mark macros. . . . . 1246
lwarp-patch-memoir: Fix: \label. 1238
lwarp-patch-memoir: Fixed pagenotes. . . . . 1256
lwarp-patch-memoir: Improved cleveref support. . . . . 1257
lwarp-patch-memoir: No longer requires subcaption. . . . . 1238
lwarp-patch-memoir: No longer uses subcaption. . . . . 1253
lwarp-patch-memoir: Use LaTeX captions. . . . . 1252
lwarp-patch-memoir: Uses memoir's \newcomment, \commentsoff, \commentson. . . 1258
lwarp-patch-memoir: \contsubtop, etc. now as-is. . . . . 1264
lwarp-patch-memoir: caption now optional, removed dup caption. . 1254
mdframed: Warn inside a . 936
memoir: Preloads xcolor. . . . . 621
nfssext-cfr: Improved. . . . . 980
nfssext-cfr: \FilenameNullify. . . . . 982, 985
ntheorem: Warning if thref. . . . 994
parcolumns: Fixed: Missing \colplacechunks. . . . . 1011
realscripts: Added print mode. . . . 1037
realscripts: Fixed starred \textsuperscript, \textsubscript. . . . . 1037
realscripts: Improved supersub scripts. . . . . 1037

rotfloat: Fix: Requires rotating. . . 1047
scrextend: Added \titlehead, \subject, \subtitle, \published. . . . . 1050
scrextend: Updated to v3.29. . . . . 1050
sidenotes: \sidecaption not long arg. . . . . 1067
slantsc: \FilenameNullfiy. . . . . 1098
titling: \AtBeginDocument. . . . . 1167
xpinyin: Disables pinyin when null fonts. . . . . 1227
*lwarpmk*: clean also removes comment_*.cut . . . . . 316
Added \FirstPageBottom. . . . . 365
Added prev/next links. . . . . 341
Docs: JetBrain Mono font. . . . . 102
Docs: \linkpreviousname. . . . . 109
Fix: Multirow style. . . . . 966
Fixed: textcomp now in kernel. . . 620
Logos: Only warn about graphics if actually use \Xe. . . . . 616
tabbing: Restore spacing. . . . . 426
center: Added print mode. . . . . 575
verbatim: Added print mode. . . . . 426
verse: Added print mode. . . . . 423
flushleft: Added print mode. . . . 576
flushright: Added print mode. . . 575
longtable: caption now optional. . . 901
quotation: Added print mode. . . . 422
quote: Added print mode. . . . . 421
LWR@nestspan: Issue warnings inside a span. . . . . 352
Nullified minipage, \parbox inside a span. . . . . 352
v0.85
\LWR@atbeginverbatim: Fix: Added print macros for fontspec. . . . . 425
\LWR@htmlclosecomment: Fix: Added print macros for fontspec. . . . . 353
\LWR@htmlcomment: Fix: Added print macros for fontspec. . . . . 354
\LWR@htmltagc: Fix: Added print macros for fontspec. . . . . 351
General: 2020/05/01 . . . . . 1
idxlayout: Fixed: \AtBeginDocument for load order. . . . . 857
mathtools: Fixed: \shortintertext. . . . . 928
titlesec: pagestyles option. . . . . 1162
url: Fixed print mode. . . . . 1198
Fix: Added print macros for fontspec. . . . . 602
v0.86
\LWR@filenamenoblanks: Fix: *, (, ), . in filename. . . . . 378
\LWR@filestart: Error if missing file. 405
\LWR@href: hyperref: Adjusted emulation. . . . . 506
\LWR@label@createtag: Fix: Labels in eqnarray. . . . . 500
\LWR@label@inmathcomment: Fix: Labels in eqnarray. . . . . 500
\LWR@nolinkurl: hyperref: Adjusted emulation. . . . . 506
\LWR@phantomsection: hyperref: Adjusted emulation. . . . . 616
\LWR@startref: Fixed: \label inside lateximage. . . . . 503
\LWR@syncmathjax: Improved MathJax equation numbers. . . 556
\LWR@url: hyperref: Adjusted emulation. . . . . 507
\textcolor: xcolor: \textcolor: Fixed for babel-french. . . . . 1214
General: 2020/05/12 . . . . . 1
LWR@insidemathcomment: Added. 541
amsmath: Added support for MathJax. . . . . 648
hyperref: Adjusted emulation. . . 851
mathtools: Added \ArrowBetweenLines*. . . . . 928
mathtools: Added \shortvdotswithin*. . . . . 928
mathtools: Added starred delimited macros. . . . . 928
nccmath: Added \displaybreak. 976
nccmath: Fixed \nr, added starred. 976
File: lwarp_mathjax.txt: Added support for starred macros. . . . . 312
File: lwarp_mathjax.txt: Improved equation numbering. . . . . 312
File: lwarp_mathjax.txt: Updated to MathJax v3 current. . . . . 312
v0.87
\LWR@checkloadfilename: Prevented csvtools. . . . . 242
\bibliography: Reverted to original. 534
\scshape: Added FixSmallCaps to remove \LWR@print@scshape for erewhon, et. al. . . . . 604
\sishape: Added FixSmallCaps to remove \LWR@print@scshape for erewhon, et. al. . . . . 604
General: 2020/06/03 . . . . . 1
cancel: Now uses MathJax v3 extension. . . . . 690
citeref: Added. . . . . 731
drftcite: Added. . . . . 750
embrac: Neutralized kerning. . . 755

ifpdf, ifptex: Restored to work on TL2019 and earlier. . . . . 202
jurabib: Added. . . . . 866
mathtools: Improved \underbraket, \overbracket. . . . . 926
mathtools: Updated starred macros. 926
mhchem: Now uses MathJax v3 extension. . . . . 948
multibib: Added. . . . . 960
nccmath: Updated starred, improved \underref. . . . . 976
physics: Now uses MathJax v3 extension. . . . . 1023
splitbib: Added. . . . . 1101
statex2: \pBin exponent. . . . . 1107
Added FixSmallCaps to remove \LWR@print@scshape for erewhon, et. al. . . . . 598
Docs: Updated docs to compile lwarp documentation. . . . . 187
File: lwarp_mathjax.txt: Now provides \ifstar, \ifnextchar. . 312
Prevented csvtools. . . . . 205
v0.88
\@wrindex: Added support for *xindex*. 528
\IndexRangeSeparator: Added. . . . 526
\LWR@HTML@ref: Added MathJax. . . 504
Fixed: Starred. . . . . 503
\LWR@LetLtxMacrocs: Added. . . . . 224
\LWR@absorbstar: Added. . . . . 224
\LWR@checkloadfilename: Prevented shadethm. . . . . 242
\LWR@doindexentry: Adapts to gindex. . . . . 531
\LWR@doindexentrysub: Adapts to gindex. . . . . 531
\LWR@doindexentrysubsub: Handles a range, for *xindex*. . . . . 531
\LWR@forcenewautoidanchor: Inline handling. . . . . 512
\LWR@hyperindexrefsubtwo: Adds support for a range, for *xindex*. . . 533
\LWR@indexnameref: Added IndexRef option, refactored. . . . . 530
\LWR@maybe@orignewpage: Added. . 222
\LWR@printchaptername: Conditionally print \chaptername. 394
\LWR@restoreMathJaxformatting: Added. . . . . 535
\LWR@restoreorigformatting: Added \vdots. . . . . 536
Support for MathJax. . . . . 536
\LWR@section: Conditionally print \chaptername. . . . . 398
\LWR@xindex@modifyentry: Added support for *xindex*. . . . . 527
\hrulefill: Full line  if not started paragraph. . . . . 609
\hyperindexformat: Added. . . . . 533
\hyperindexref: Rewritten to parse commas and ranges. . . . . 532
\hyperpage: Added. . . . . 533
\nohyperpage: Added. . . . . 533
General: 2020/07/19 . . . . . 1
lwarp.css: Added indexheading for gindex. . . . . 269
lwarp.css: Added tcolorbox, thmbox. . . . . 269
amsmath: Added \dotso text mode. 645
amsthm: Requires amsmath. . . . 649
caption, scrextend: Fixed \caption*. . . . . 692
cleveref, varioref: Fix for starred macros. . . . . 734
fancyref: Now uses varioref which ignores page-related output. . . . 780
fbox: Added. . . . . 788
gindex: Added. . . . . 823
hhtensor: Added. . . . . 844
mleftright: Added. . . . . 957
pdfrender: Restored for xfakebold. 1020
shadethm: Added. . . . . 1063
tcolorbox: Added. . . . . 1135
termcal: Added. . . . . 1142
thm-listof: Added. . . . . 1152
thm-restate: Added. . . . . 1153
thmbox: Added. . . . . 1153
ushort: Added. . . . . 1198
varioref: Removed page-related text. . . . . 1199
xfakebold: Now works with pdfrender. . . . . 1221
Added \vdots. . . . . 259, 608
Added LWR@texboxdepth. . . . . 222
Added IndexRef option. . . . . 230
Added xindex option. . . . . 230
Option xindexConfig added. . . . 228
Prevented shadethm. . . . . 205
v0.883
General: nfssext-cfr: Fixed \textsw. 983
v0.89
\@opargbegintheorem: Allow preload of amsmath, amsthm, centernot. 427
\LWR@HTMLsanitizeexpand: Fix: Nested MathJax environments. . 383
\LWR@LwarpStart: MathJax: Improved info message. . . . . 408
\LWR@addmathjax: TT font for MathJax. . . . . 557

\LWR@amsmathbodynumbered: \textendash for number range. . 568
\LWR@customizeMathJax: Print MathJax customizations with typewriter font. . . . . 386
\LWR@doubledollar: TT font for MathJax. . . . . 551
\LWR@patcherror: Improved message. 221
\LWR@singledollar: TT font for MathJax. . . . . 552
\LWR@subsingledollar: TT font for MathJax. . . . . 550
\enddocument: Adapt to LaTeX core changes. . . . . 410
General: 2020/09/03 . . . . . 1
accents: Added. . . . . 632
atbegshi: Adapt to LaTeXkernel changes. . . . . 660
caption3: Split from lwarp-caption. 693
caption: Adapt to v3.5. . . . . 691
centernot: Improved. . . . . 696
econometrics: Uses lwarp-common-mathjax-letters. 751
everyshi: Adapt to LaTeXkernel changes. . . . . 773
everyshi: Included in LaTeX core. . . 620
hepunits: Added. . . . . 843
lwarp-common-mathjax-letters: Added. . . . . 1269
lwarp-common-mathjax-newpxtxmath: Added. . . . . 1276
lwarp-common-mathjax-overlaysymbols: Added. . . . . 1285
mathalpha: Added. . . . . 917
mathdesign: Added. . . . . 919
mathpazo: Added. . . . . 922
mathptmx: Added. . . . . 922
mathtools: Added \adjustlimits. 926
mathtools: Minor improvements. . . . . 926, 930
mismath: Improved math operators. 953
newpxmath: Added. . . . . 976
newtxmath: Added. . . . . 977
newtxsf: Added. . . . . 978
pxfonts: Added. . . . . 1034
shuffle: Added. . . . . 1065
siunitx: Fix: MathJax for \tothe, \raiseto. . . . . 1084
siunitx: Unicode for endash. . . . . 1088
statmath: Fixed abcbm, uses lwarp-common-mathjax-letters. 1116
thm-listof: Updated to v0.72. . . . . 1152
thm-restate: Updated to v0.72, no changes needed. . . . . 1153
thmtools: Added. . . . . 1154
txfonts: Added. . . . . 1186
upgreek: Added. . . . . 1197
*lwarpmk*: clean also removes *.bbl 316
Allow preload of amsmath, amsthm, centernot. . . . . 206, 620
AMS environments: Fix: <ALT> text env name. . . . . 646
Foreground/background hooks: Adapt to LaTeX core changes. . . . . 411
MathJax: Added \protect, and \mathcode and related. . . . . 386
Removed \let of \[, \]. . . . . 554
eqnarray: \textendash for number range. . . . . 564
v0.891
\LWR@atbeginverbatim: Fix for verbatim, alltt with lists . . . . . 424
\LWR@checkloadfilename: Prevented libgreek. . . . . 242
\LWR@excludecomment: Error if nested comment. . . . . 233
\LWR@subHTMLsanitize: Neutralized single quotes. . . . . 382
\verb: \verb as \texttt. . . . . 424
General: 2020/09/22 . . . . . 1
biblatex: Fixed: Back page references. . . . . 676
bussproofs: Added. . . . . 689
caption: Improved integration. . . 692
cmbright: Added. . . . . 735
colonequals: Uses Unicode and \mathrel. . . . . 736
fancyvrb: Fix: BVerbatim with labels. . . . . 783
fourier: Added. . . . . 812
hyperref: Added backref, pagebackref. . . . . 846
hyperref: Fixed \texorpdfstring with babel-french. . . . . 854
kpfonts-otf: Added. . . . . 879
kpfonts: Added. . . . . 877
libertinust1math: Added. . . . . 885
listings: Fix for MathJax: Moved \LWR@forcenewpage to start. 895, 896
listings: Improved HTML sanitizing. 895
listings: Improved spacing around ampersand. . . . . 895
lwarp-common-mathjax-newpxtxmath: Expanded for kpfonts. 1277, 1279, 1282
lwarp-common-mathjax-newpxtxmath: Factored non-Unicode. 1278, 1279, 1281
lwarp-common-mathjax-newpxtxmath: Reverse factored out Greek, non-Unicode. . . . . 1276

lwarp-common-mathjax-nonunicode: Added. . . . . 1282
mathdesign: Added \mathinner, \mathbin. . . . . 921
mathdesign: Added \mathop. . . . 920
mathdesign: Added \mathrel, \mathord. . . . . 920
mathdesign: Honors greekuppercase, greeklowercase. . . . . 920
mathdots: Added more macros, \mathinner. . . . . 921
mathfixs: Added \mathinner. . . . 921
mathpazo: Honors slantedGreek. 922
mathptmx: Honors slantedGreek. 922
mathtools: Improved \underbraket, \overbracket. . . . . 926
mathtools: Uses Unicode and \mathrel. . . . . 930
multiobjective: Improved. . . . . 963
newpxmath: Honors uprightGreek, slantedGreek. . . . . 976, 978
newtxmath: Honors uprightGreek, slantedGreek. . . . . 977
nicefrac: Added \mathinner, improved fraction. . . . . 986
scalerel: Added. . . . . 1049
shuffle: Added \mathbin, improved bar. . . . . 1066
txgreeks: Added. . . . . 1187
unicode-math: Added sans-style. . . . . 1193
units: Added \mathinner, improved fraction. . . . . 1196
File: lwarp_mathjax.txt: Renamed tagformat extension. . . . . 312
Prevented libgreek. . . . . 205
BVerbatim: fancyvrb: Fix: BVerbatim with labels. . . . . 787
v0.892
\LWR@subhtmlelementclass: Ignore empty class. . . . . 354
\fcolorbox: xcolor: Fixed second optional arg. . . . . 1216
\fcolorboxBlock: xcolor: Fixed second optional arg. . . . . 1216
General: 2020/10/07 . . . . . 1
fancyvrb: Adapted to fvextra. . . . 787
fancyvrb: Provided \FV@FrameFillLine. . . . . 786
fourier: Added \left/\right support in lwarp_mathjax.txt. . 813
fvextra: Added. . . . . 817
graphics: Fix path from kernel change. . . . . 835
libertinust1math: Added \left/\right support in lwarp_mathjax.txt. . . . . 886
lineno: Fix for internallinenumbers*. . . . . 892
lwarp-common-mathjax-newpxtxmath: Added \left/\right support in lwarp_mathjax.txt. . . . . 1277, 1281
minted: Added. . . . . 952
unicode-math: Adeed MathJax support for \left/\right. . . . 1194
File: lwarp_mathjax.txt: Added \left/\right delimiters. . . . . 312
fcolorminipage: xcolor: Fixed second optional arg. . . . . 1217
v0.893
\LWR@checkloadfilename: Allowed picinpar. . . . . 242
\LWR@expandableformatted: Improved error handling. . . . . 254
\LWR@expandableformattedenv: Improved error handling. . . . . 254
\LWR@formatted: Improved error handling. . . . . 253
\LWR@formatted@checkendname: Added. . . . . 253
\LWR@formatted@checkname: Added. 253
\LWR@formattedenv: Improved error handling. . . . . 254
\LWR@htmlcomment: Disabled in math mode. . . . . 354
\LWR@subHTMLsanitize: Optionally neutralized single quotes. . . . . 382
General: 2020/11/26 . . . . . 1
MathJax: Added \mathnormal. . . 385
lwarp.css: Added keystroke. . . . 269
braket: Now uses MathJax extension. . . . . 686
caption3: Updated date to v2.2e. . 693
caption: Updated date to v3.5g. . . 691
epstopdf-base: Updated date to v2.11. . . . . 765
epstopdf: Updated date to v2.11. . 765
esvect: Added. . . . . 770
fixmath: Added. . . . . 792
graphics: Updated date to v1.4c. . . 826
graphicx: Updated date to v1.2b. . . 839
keystroke: Added. . . . . 876
lwarp-common-mathjax-letters: Added \varbeta. . . . . 1269
mathastext: Added. . . . . 918
mathspec: Added. . . . . 923
menukeys: Added. . . . . 945
menukeys: Updated to v1.6.1. . . . 945
picinpar: Added. . . . . 1025

plimsoll: Added. . . . . 1030
pstricks: Fixed pspicture*. . . . . 1033
repltext: Added. . . . . 1044
schemata: Added <alt> text. . . . 1049
selectp: Added. . . . . 1060
seqsplit: Added. . . . . 1061
simplebnf: Added. . . . . 1068
statistics: Added. . . . . 1111
struktex: Removed package date. . 1119
svg: Updated date to v2.02j. . . . . 1128
swfigure: Added. . . . . 1129
tikz: Fixed font macros. . . . . 1158
Allowed picinpar. . . . . 205
v0.894
\LWR@forceSVGmessage: Improved MathJax warnings. . . . . 626
\LWR@mathjaxwarn: Improved MathJax warnings. . . . . 626
General: 2020/12/24 . . . . . 1
MathJax: Accept starred \hspace. 385
MathJax: Added \arabic, \number, \noalign. . . . . 385
lwarp.css: TEX logos no longer below baseline. . . . . 269
booktabs: MathJax: Absorb \cmidrule trim arg. . . . . 684
colortbl: Added MathJax emulation. 738
nicematrix: Added. . . . . 987
rmathbr: Updated to v1.1. . . . . 1045
v0.895
\LWR@addlinktitle: Improved HTML quotes. . . . . 502
\LWR@checkloadfilename: kpfonts load before lwarp. . . . . 242
Allowed epsf. . . . . 242
\LWR@domulticolumn: Improved HTML quotes. . . . . 478, 479
\LWR@floatbegin: Improved HTML quotes. . . . . 510
\LWR@forceSVGmessage: Improved MathJax warning. . . . . 626
\LWR@forcenewautoidanchor: Improved HTML quotes. . . . . 512
\LWR@hook@processingtags: Added. 349
\LWR@label@subcreatetag: Improved HTML quotes. . . . . 499
\LWR@mathjaxwarn: Added MathJax warnings for aligned-overset, autoaligne, boldtensors, liberitinust1math, tensind. . . . . 626
Improved MathJax warning for unicode-math. . . . . 626
\LWR@maybenewtablerow: Improved HTML quotes. . . . . 460
\LWR@printatbang: Improved HTML quotes. . . . . 461
\LWR@printopenlist: Improved HTML quotes. . . . . 428
\LWR@startref: Improved HTML quotes. . . . . 502, 503
\LWR@subaddtabularcellcolor: Improved HTML quotes. . . . . 472
\LWR@subhyperref: Improved HTML quotes. . . . . 505
\LWR@subhyperrefclass: Improved HTML quotes. . . . . 506
\LWR@subinlineimage: Improved HTML quotes. . . . . 507
\LWR@tabledatasinglecolumntag: Improved HTML quotes. . . . . 463
\LWR@tdaddstyle: Improved HTML quotes. . . . . 467
\LWR@tdendstyles: Improved HTML quotes. . . . . 467
\hspace: Improved HTML quotes. . . . 611
\rotatebox: Improved HTML quotes. 837
\rule: Improved HTML quotes. . 614, 615
\scalebox: Improved HTML quotes. . 837
\verb: Improved HTML quotes. . . . . 424
General: 2021/02/18 . . . . . 1
acro: Updated to v3.5. . . . . 634
amscdx: Added. . . . . 644
amsmath: Added \Hat, etc.. . . . . 648
changes: Updated to v4.0.1. . . . . 698
epsfig: Supports lateximage. . . . 764
epsf: Added. . . . . 764
fancyhdr: Updated to v4.0. . . . . 779
impnattypo: Added. . . . . 862
isomath: Added. . . . . 864
isotope: Added. . . . . 865
libertinust1math: MathJax: Fixed for Greek, ignoring sans. . . . . 886
lpic: Added. . . . . 903
luavlna: Added. . . . . 910
mattens: Added. . . . . 931
mdwmath: Added. . . . . 942
pinlabel: Added. . . . . 1028
rlepsf: Added. . . . . 1045
rotating: Supports lateximage. . . 1046
siunitx, MathJax: Scientific notation. . . . . 1085
siunitx, MathJax: \num sci notation, multiples, +-, decimals, comma. . 1085
siunitx: Fix: MathJax for \ang. . . 1085
siunitx: MathJax: \SI prefix parsing. . . . . 1087
skmath: Added. . . . . 1092
tensor: Added MathJax. . . . . 1141
tikz-imagelabels: Added. . . . . 1159

xevlna: Added. . . . . 1221
Allow \par. . . . . 966
Allowed epsf. . . . . 205
File: lwarp_mathjax.txt: Added \ifblank, \ifstrequal macros. . 312
Fixed libertinus-otf \textquotedbl kern. . . . . 259
Improved HTML quotes. 257, 349, 643, 783,
832, 833, 840, 851, 852, 896, 936, 965, 998
Use kpfonts-otf if LuaLaTeX, XeLaTeX. 219
lateximage: Improved HTML quotes. 571
minipage: Improved HTML quotes. . . 590
enumerate: Improved HTML quotes. . 432
itemize: Improved HTML quotes. . . . 432

# Index of Objects

This is an index of macros, environments, booleans, counters, lengths, packages, classes, options, keys, files, and various other programming objects. Each is listed by itself, and also by category. In some cases, they are further subdivided by [class].

Numbers written in italic refer to the page where the corresponding entry is described; numbers underlined refer to the code line of the definition.


**Symbols**

\$ . . . . . *542*
\& . . . . . *340*, 8456
\( . . . . . 11460
*-images.txt (file) . . . . . *570*
*_html.aux (file) . . . . . *381*, *496*, *498*, *570*
*_html.lof (file) . . . . . *514*
*_html.lot (file) . . . . . *514*
*_html.tex (file) . . . . . *262*
\, . . . . . *122*
--shell-escape (option) . . . . . *101*
\@@@setcpageref . . . . . 39
\@@@setcref . . . . . 2
\@@@setcrefrange . . . . . 17
\@author . . . . . *412*
\@begintheorem . . . . . 8081
\@biblabel . . . . . 10919
\@caption . . . . . 10342
\@captype . . . . . 10319
\@chapcntformat . . . . . 7179
\@currentHref . . . . . 10123
\@currentlabelname . . . . . 9937
\@date . . . . . *412*
\@donoparitem . . . . . 8111
\@endtheorem . . . . . 8095
\@ensuredmath . . . . . 11470
\@fnsymbol . . . . . 7819
\@footnotetext . . . . . 6548
\@include . . . . . 1530
\@item . . . . . 8124
\@makecaption . . . . . 10342
\@makefnmark . . . . . 6514
\@makefntext . . . . . 6513
\@maketitle . . . . . 57, 7851
\@mklab . . . . . 8105
\@mpfootnotetext . . . . . 6550
\@nbitem . . . . . 8191
\@opargbegintheorem . . . . . 8087
\@partcntformat . . . . . 7180
\@partnameformat . . . . . 7181
\@rowc@lors . . . . . 8827
\@rowcolors . . . . . 8826
\@seccntformat . . . . . 7177
\@starttoc . . . . . 10485
\@textsubscript . . . . . 12899
\@textsuperscript . . . . . 12895
\@title . . . . . *412*
\@wrglossary . . . . . 10738
\@wrindex . . . . . 10710
\@xdlbfloat . . . . . 10263
\@xfloat . . . . . 10263
\[ . . . . . 11460
\\ . . . . . *609*
$ . . . . . *551*
$$ . . . . . *551*
2in1 (package) . . . . . *628*
2up (package) . . . . . *628*

**A**

a4 (package) . . . . . *628*
a4wide (package) . . . . . *629*
a5comb (package) . . . . . *629*
abstract (environment) . . . . . 7918
abstract (package) . . . . . *133*, *629*
\abstractname . . . . . *112*, 7917
academicons (package) . . . . . *631*
accents (package) . . . . . *632*
accessibility (package) . . . . . *633*
accsupp (package) . . . . . *633*
acro (package) . . . . . *634*
acronym (package) . . . . . *636*
\addcontentsline . . . . . 10433
addlines (package) . . . . . *638*
\AddSubtitlePublished . . . . . 7881
adjmulticol (package) . . . . . *637*
Adobe (program) . . . . . *74*
\affiliation . . . . . 7719
afterpage (package) . . . . . *639*
algorithm2e (package) . . . . . *639*
algorithmicx (package) . . . . . *167*, *643*
align (environment) . . . . . 85
align* (environment) . . . . . 88
alignat (environment) . . . . . 97
alignat* (environment) . . . . . 100
alltt (package) . . . . . *644*
\AltTextClose . . . . . *114*, 11135

\AltTextOpen . . . . . 114, 11134
\AmS . . . . . 13257
amscdx (package) . . . . . 644
amsmath (package) . . . . . 645
amsthm (package) . . . . . 649
\and . . . . . 412
anonchap (package) . . . . . 653
anysize (package) . . . . . 653
appendix (package) . . . . . 134, 654
ar (package) . . . . . 654
arabicfront (package) . . . . . 656
array (package) . . . . . 656
\arrayrulecolor . . . . . 8834
\arrayrulecolornexttoken . . . . . 8834
arydshln (package) . . . . . 657
AsciiDoc (program) . . . . . 74
AsciiDoctor (program) . . . . . 74
Asciidoctor-LaTeX (program) . . . . . 74
asymptote (package) . . . . . 161, 659
atbegshi (package) . . . . . 659
attachfile (package) . . . . . 660
attachfile2 (package) . . . . . 661
\attrib . . . . . 171, 422, 1199
\attribution . . . . . 7928
authblk (package) . . . . . 134, 663
\author . . . . . 119, 412
autobreak (package) . . . . . 664
autonum (package) . . . . . 664
autosec . . . . . 392
awesomebox (package) . . . . . 666
axessibility (package) . . . . . 667
axodraw2 (package) . . . . . 667

**B**

babel (package) . . . . . 172
\backmatter . . . . . 7155
backnaur (package) . . . . . 668
backref (package) . . . . . 669
balance (package) . . . . . 669
\BaseJobname . . . . . 5731
BaseJobname (option) . . . . . 108, 228
bbding (package) . . . . . 669
\bfseries . . . . . 12799
biblatex (package) . . . . . 674
\bibliography . . . . . 10919
\BibTeX . . . . . 13250
bibunits (package) . . . . . 678
bigdelim (package) . . . . . 167, 678
bigfoot (package) . . . . . 680
bigstrut (package) . . . . . 680
bitpattern (package) . . . . . 681
BlockClass (environment) . . . . . 117, 6202
\BlockClassSingle . . . . . 6215
blowup (package) . . . . . 681
bm (package) . . . . . 681
booklet (package) . . . . . 682
bookmark (package) . . . . . 682
booktabs (package) . . . . . 683
boolean:
CombineHigherDepths . . . . . 111, 376
FileSectionNames . . . . . 111, 341
FixSmallCaps . . . . . 111, 122, 598
FormatEPUB . . . . . 179, 255
FormatWP . . . . . 181, 255
HTMLDebugComments . . . . . 112, 249
LWR@allowanothergeometry . . . . . 237
LWR@amsmultline . . . . . 562
LWR@copiedsidetoc . . . . . 519
LWR@doingapar . . . . . 359
LWR@doingcmidrule . . . . . 438
LWR@doingstartpars . . . . . 359
LWR@doingtbrule . . . . . 438
LWR@dynamicmath . . . . . 339
LWR@emptyatbang . . . . . 439
LWR@exitingtabular . . . . . 439
LWR@forceminipagefullwidth . . . . 588
LWR@foundmrowcell . . . . . 439
LWR@freezethisautoid . . . . . 512
LWR@indisplaymathimage . . . . . 541
LWR@insidemathcomment . . . . . 541
LWR@intabularmetadata . . . . . 439
LWR@isstartingequation . . . . . 567
LWR@MathJax@silentquotes . . . . . 381
LWR@mathmacro . . . . . 338
LWR@minipagefullwidth . . . . . 588
LWR@minipagethispar . . . . . 589
LWR@opttablecol . . . . . 439
LWR@origmathjax . . . . . 227
LWR@setseqfilelabel . . . . . 341
LWR@skipatbang . . . . . 439
LWR@skippingmcolrowcell . . . . . 438
LWR@skippingmrowcell . . . . . 438
LWR@starredlongtable . . . . . 441
LWR@startedrow . . . . . 438
LWR@tableparcell . . . . . 438
LWR@tabularcelladded . . . . . 438
LWR@tabularmutemods . . . . . 439
LWR@tracinglwarp . . . . . 249
LWR@unknownmathsize . . . . . 544
LWR@usedmultirow . . . . . 438
LWR@validtablecol . . . . . 439
LWR@verbtags . . . . . 424
LWR@warnbaselinemarker . . . . . 544
LWR@warnedcustomizemathjax . . . . 383
LWR@xfakebold . . . . . 541
mathjax . . . . . 227
usingOSWindows . . . . . 226
warpingHTML . . . . . 227
warpingprint . . . . . 227
WPMarkFloats . . . . . 182, 255
WPMarkLOFT . . . . . 183, 256

WPMarkMath . . . . . 183, 256
WPMarkMinipages . . . . . 183, 256
WPMarkTOC . . . . . 183, 256
WPTitleHeading . . . . . 184, 256
bophook (package) . . . . . 685
bounddvi (package) . . . . . 685
boxedminipage (package) . . . . . 685
boxedminipage2e (package) . . . . . 686
\boxframe . . . . . 194
braket (package) . . . . . 686
breakurl (package) . . . . . 686
breqn (package) . . . . . 687
bsheaders (package) . . . . . 688
bussproofs (package) . . . . . 689
BVerbatim (environment) . . . . . 255
bxpapersize (package) . . . . . 689
bytefield (package) . . . . . 689

## C

calc (package) . . . . . 238
cancel (package) . . . . . 690
canoniclayout (package) . . . . . 691
capt-of (package) . . . . . 517
caption (package) . . . . . 168, 517, 691
caption3 (package) . . . . . 693
\caption@begin . . . . . 10401
\caption@end . . . . . 10401
\captionlistentry . . . . . 10408
\captionof . . . . . 10449
\CaptionSeparator . . . . . 10341
cases (package) . . . . . 695
center (environment) . . . . . 12048
\centering . . . . . 12078
\centerline . . . . . 12097
centernot (package) . . . . . 696
changebar (package) . . . . . 696
changelayout (package) . . . . . 697
changepage (package) . . . . . 697
changes (package) . . . . . 698
chappg (package) . . . . . 703
\chapter . . . . . 7393
chapterbib (package) . . . . . 703
chemfig (package) . . . . . 704
chemformula (package) . . . . . 706
chemgreek (package) . . . . . 711
chemmacros (package) . . . . . 711
chemnum (package) . . . . . 729
chkfloat (package) . . . . . 730
chngpage (package) . . . . . 730
cite (package) . . . . . 730
citeref (package) . . . . . 731
CJK (package) . . . . . 731
CJKutf8 (package) . . . . . 732
class (key) [Gin] . . . . . 830
class:
internet . . . . . 73
komascript . . . . . 169
memoir . . . . . 169, 171, 1200
\cleardoublepage . . . . . 13079
\clearpage . . . . . 13079
cleveref (package) . . . . . 130, 732
clrdblpg (package) . . . . . 735
cm-super (package) . . . . . 101
cmap (package) . . . . . 102
cmbright (package) . . . . . 735
cmdtrack (package) . . . . . 736
colonequals (package) . . . . . 736
\color . . . . . 50
color (package) . . . . . 159, 737
\colorbox . . . . . 77
\colorboxBlock . . . . . 90, 12177
colortbl (package) . . . . . 166, 737
CombineHigherDepths (boolean) . . 111, 376
comment (package) . . . . . 233
\ConTeXt . . . . . 13245
continue (package) . . . . . 739
copyrightbox (package) . . . . . 739
counter:
FileDepth . . . . . 111, 376
FootnoteDepth . . . . . 111, 369
footnoteReset . . . . . 370
lofdepth . . . . . 524
lotdepth . . . . . 524
LWR@cellcolordepth . . . . . 441
LWR@currentautosec . . . . . 394
LWR@externalfilecnt . . . . . 541
LWR@hdashedlines . . . . . 438
LWR@hlines . . . . . 438
LWR@htmlfilenumber . . . . . 342
LWR@htmlseqfilenumber . . . . . 341
LWR@latestautopage . . . . . 514
LWR@lateximagedepth . . . . . 566
LWR@lateximagenumber . . . . . 566
LWR@LIpage . . . . . 567
LWR@midrulecounter . . . . . 441
LWR@nextautoid . . . . . 514
LWR@nextautopage . . . . . 514
LWR@nextequation . . . . . 554
LWR@prevFileDepth . . . . . 393
LWR@previousautopagelabel . . . . 380
LWR@spandepth . . . . . 359
LWR@splitstarcopies . . . . . 453
LWR@splitstarindex . . . . . 453
LWR@starcount . . . . . 453
LWR@startingequation . . . . . 567
LWR@tablecolspecindex . . . . . 440
LWR@tablecolspecwidth . . . . . 440
LWR@tableLaTeXcolindex . . . . . 440
LWR@tabletotalLaTeXcols . . . . . 440
LWR@tabletotalLaTeXcolsnext . . . 440
LWR@tabularDepth . . . . . 439

LWR@tabularpardepth . . . . . 439
LWR@thisautoid . . . . . 512
LWR@thisautoidWP . . . . . 512
LWR@virtualpagedepth . . . . . 588
SideTOCDepth . . . . . 109, 521
tocdepth . . . . . 109
\cpagerefFor . . . . . 38
crop (package) . . . . . 740
\CSSFilename . . . . . 112, 115, 6456
ctable (package) . . . . . 740
\CustomizeMathJax . . . . . 6916, 7009
cuted (package) . . . . . 743
cutwin (package) . . . . . 743

## D

\date . . . . . 119
dblfloatfix (package) . . . . . 744
dblfnote (package) . . . . . 744
dcolumn (package) . . . . . 744
decimal (package) . . . . . 745
\DeclareGraphicsExtensions . . . . . 2
\defaddtocounter . . . . . 828
dejavu (package) . . . . . 101
description (environment) . . . . . 8276
diagbox (package) . . . . . 745
dingbat (package) . . . . . 746
\displaymathnormal . . . . . 155, 561, 11714
\displaymathother . . . . . 155, 561, 11725
ditaa (package) . . . . . 178
DotArrow (package) . . . . . 747
\dotfill . . . . . 12997
dotlessi (package) . . . . . 748
\doublerulesepcolor . . . . . 8836
\doublerulesepcolornexttoken . . . . . 8836
dprogress (package) . . . . . 748
draftcopy (package) . . . . . 748
draftfigure (package) . . . . . 749
draftwatermark (package) . . . . . 749
drftcite (package) . . . . . 750
dvipdfm (option) . . . . . 104, 230
dvipdfmx (option) . . . . . 104, 230
dvips (option) . . . . . 104, 230

## E

easy-todo (package) . . . . . 750
ebook (package) . . . . . 751
\ebweight . . . . . 12804
econometrics (package) . . . . . 751
ed (package) . . . . . 754
ellipsis (package) . . . . . 755
embrac (package) . . . . . 755
\emph . . . . . 12615
emptypage (package) . . . . . 756
\end@dlbfloat . . . . . 10288
\end@float . . . . . 10288
\enddocument . . . . . 7655
endfloat (package) . . . . . 756
endheads (package) . . . . . 756
endnotes (package) . . . . . 134, 757
engtlc (package) . . . . . 758
\enlargethispage . . . . . 13078
\enskip . . . . . 610, 13023
enumerate (environment) . . . . . 8249
enumerate (package) . . . . . 762
enumitem (package) . . . . . 763
environ (package) . . . . . 240
environment:
BlockClass . . . . . 117
fminipage . . . . . 125
leteximage . . . . . 565
picture . . . . . 586
titlepage . . . . . 119
titlingpage . . . . . 119
warpall . . . . . 118
warpHTML . . . . . 114, 117
warpMathJax . . . . . 118
warpprint . . . . . 114, 118
environments:
abstract . . . . . 7918
align . . . . . 85
align* . . . . . 88
alignat . . . . . 97
alignat* . . . . . 100
BlockClass . . . . . 6202
BVerbatim . . . . . 255
center . . . . . 12048
description . . . . . 8276
enumerate . . . . . 8249
eqnarray . . . . . 11761
equation . . . . . 11692
equation* . . . . . 11700
fcolorminipage . . . . . 170, 12217
flalign . . . . . 91
flalign* . . . . . 94
flushleft . . . . . 12068
flushright . . . . . 12058
fminipage . . . . . 12541
gather . . . . . 79
gather* . . . . . 82
itemize . . . . . 8241
leteximage . . . . . 11904, 12043
list . . . . . 8211
longtable . . . . . 4
LWR@BlockClassWP . . . . . 6241
LWR@blocktextcurrentfont 12785, 12926
LWR@displaymathnormal . . . . . 11508
LWR@displaymathother . . . . . 11511
LWR@equationother . . . . . 11525
LWR@figcaption . . . . . 10371
LWR@glrbox . . . . . 881
LWR@nestspan . . . . . 6039

LWR@setvirtualpage . . . . . 12298
LWRcreatelwarpmk . . . . . 1183
math . . . . . 11507
minipage . . . . . 12324
multline . . . . . 72
multline* . . . . . 75
picture . . . . . 12289
quotation . . . . . 7955
quote . . . . . 7947
tabbing . . . . . 8059
tabular . . . . . 9781
thebibliography . . . . . 10920
theindex . . . . . 10661
titlepage . . . . . 7736
titlingpage . . . . . 14
verbatim . . . . . 8041
verse . . . . . 2, 7965
warpall . . . . . 1167
warpHTML . . . . . 1168
warpMathJax . . . . . 1174
warpprint . . . . . 1171
epigraph (package) . . . . . *763*
epsf (package) . . . . . *764*
epsfig (package) . . . . . *764*
epstopdf (package) . . . . . *159*, *765*
epstopdf (program) . . . . . *158*, *580*
epstopdf-base (package) . . . . . *765*
eqlist (package) . . . . . *766*
eqnarray (environment) . . . . . 11761
eqparbox (package) . . . . . *767*
equation (environment) . . . . . 11692
equation* (environment) . . . . . 11700
errata (package) . . . . . *768*
eso-pic (package) . . . . . *769*
esvect (package) . . . . . *770*
\etalchar . . . . . *134*
etoc (package) . . . . . *770*
etoolbox (package) . . . . . *202*
eurosym (package) . . . . . *772*
everyhook (package) . . . . . *239*
everypage (package) . . . . . *773*
everyshi (package) . . . . . *773*
\expandcolspec . . . . . 8712
expl3 (package) . . . . . *238*
extarrows (package) . . . . . *773*
extramarks (package) . . . . . *774*


## F


fancybox (package) . . . . . *127*, *774*
fancyhdr (package) . . . . . *779*
fancyref (package) . . . . . *780*
fancytabs (package) . . . . . *781*
fancyvrb (package) . . . . . *781*
\fbox . . . . . *125*, 12512
fbox (package) . . . . . *788*
\fboxBlock . . . . . *125*, 12521
\fcolorbox . . . . . 107, 12179
\fcolorboxBlock . . . . . 130, 12215
fcolorminipage (environment) . . 170, 12217
fewerfloatpages (package) . . . . . *790*
figcaps (package) . . . . . *790*
figsize (package) . . . . . *791*
file:
*-images.txt . . . . . *570*
*_html.aux . . . . . *381*, *496*, *498*, *570*
*_html.lof . . . . . *514*
*_html.lot . . . . . *514*
*_html.tex . . . . . *262*
glyphtounicode.tex . . . . . *102*
lwarp.css . . . . . *116*, *269*
lwarp.ist . . . . . *147*, *310*
lwarp.xdy . . . . . *147*, *310*
lwarp_baseline_marker.eps . . . . *542*
lwarp_baseline_marker.png . . . . *542*
lwarp_formal.css . . . . . *305*
lwarp_mathjax.txt . . . . . *312*
lwarp_one_limage.cmd . . . . . *311*
lwarp_sagebrush.css . . . . . *301*
lwarp_tutorial.txt . . . . . *83*
lwarpmk.conf . . . . . *268*
lwarpmk.lua . . . . . *189*
project.css . . . . . *116*
project.lwarpmkconf . . . . . *269*
sample_project.css . . . . . *116*, *309*
tutorial.tex . . . . . *83*
filecontents (package) . . . . . *239*
FileDepth (counter) . . . . . *111*, *376*
\FilenameLimit . . . . . *111*, 6660
\FilenameNullify . . . . . *129*, 11129, 12927
\FilenameSimplify . . . . . *129*, 6681, 7010
FileSectionNames (boolean) . . . . . *111*, *341*
fitbox (package) . . . . . *791*
fix2col (package) . . . . . *792*
fixmath (package) . . . . . *792*
fixme (package) . . . . . *173*, *792*
fixmetodonotes (package) . . . . . *794*
FixSmallCaps (boolean) . . . . . *111*, *122*, *598*
flafter (package) . . . . . *794*
\flagverse . . . . . *1200*
flalign (environment) . . . . . 91
flalign* (environment) . . . . . 94
Flare (program) . . . . . *74*
flippdf (package) . . . . . *794*
float (package) . . . . . *167*, *795*
floatflt (package) . . . . . *796*
floatpag (package) . . . . . *797*
floatrow (package) . . . . . *168*, *798*
fltrace (package) . . . . . *803*
\flushbottom . . . . . 5927
flushend (package) . . . . . *803*
flushleft (environment) . . . . . 12068

flushright (environment) . . . . . 12058
fminipage (environment) . . . . . 125, 12541
fnbreak (package) . . . . . 803
fncychap (package) . . . . . 804
fnlineno (package) . . . . . 804
fnpara (package) . . . . . 804
fnpos (package) . . . . . 805
fontawesome (package) . . . . . 805
fontawesome5 (package) . . . . . 806
fontaxes (package) . . . . . 807
fontenc (package) . . . . . 102, 807
fontspec (package) . . . . . 101, 235
footmisc (package) . . . . . 808
footnote (package) . . . . . 809
footnotebackref (package) . . . . . 810
FootnoteDepth (counter) . . . . . 111, 369
footnotehyper (package) . . . . . 810
footnoterange (package) . . . . . 810
footnoteReset (counter) . . . . . 370
footnpag (package) . . . . . 810
\ForceHTMLPage . . . . . 133, 7130
\ForceHTMLTOC . . . . . 133, 7136
foreign (package) . . . . . 811
forest (package) . . . . . 811
FormatEPUB (boolean) . . . . . 179, 255
FormatWP (boolean) . . . . . 181, 255
fouridx (package) . . . . . 811
fourier (package) . . . . . 812
\framebox . . . . . 12490
framed (package) . . . . . 813
FrameMaker (program) . . . . . 74
\frontmatter . . . . . 7152
ftcap (package) . . . . . 816
ftnright (package) . . . . . 816
fullminipage (package) . . . . . 816
fullpage (package) . . . . . 816
fullwidth (package) . . . . . 817
\fup . . . . . 12902
\fussy . . . . . 5929
fvextra (package) . . . . . 817
fwlw (package) . . . . . 820

## G

gather (environment) . . . . . 79
gather* (environment) . . . . . 82
GELLMU (program) . . . . . 73
gensymb (package) . . . . . 821
gentombow (package) . . . . . 821
geometry (package) . . . . . 236, 821
gettitlestring (package) . . . . . 238
ghsystem (package) . . . . . 822
[Gin]:
    class (key) . . . . . 830
gindex (package) . . . . . 138, 823
GladTeX (program) . . . . . 73
gloss (package) . . . . . 135, 823
glossaries (package) . . . . . 135, 824
GlossaryCmd (option) . . . . 108, 135, 230, 824
glyphtounicode.tex (file) . . . . . 102
gmeometric (package) . . . . . 826
graphics (package) . . . . . 157, 826
graphicx (package) . . . . . 157, 839
grffile (package) . . . . . 159, 839
grid (package) . . . . . 839
grid-system (package) . . . . . 839
gridset (package) . . . . . 840

## H

hang (package) . . . . . 840
hanging (package) . . . . . 842
hepunits (package) . . . . . 843
Hevea (program) . . . . . 73
\hfill . . . . . 12976
hhline (package) . . . . . 844
hhtensor (package) . . . . . 844
\HomeHTMLFilename . . . . . 5733
HomeHTMLFilename (option) . . . . . 104, 229
\hrule . . . . . 123
\hrulefill . . . . . 123, 12978
\hskip . . . . . 122
\hspace . . . . . 122, 610, 13031, 13062, 13068
htlatex (program) . . . . . 73
\HTMLAuthor . . . . . 113, 120, 6493
HTMLDebugComments (boolean) . . . . 112, 249
\HTMLDescription . . . . . 113, 120, 6498
\HTMLentity . . . . . 5715
\HTMLFilename . . . . . 5732
HTMLFilename (option) . . . . . 104, 229
\HTMLFirstPageBottom . . . . . 109, 6444
\HTMLFirstPageTop . . . . . 109, 6441
htmlglossary (option) [lwarpmk] . . 135, 824
HTMLIndexCmd (option) . . . . . 107, 229
\HTMLLanguage . . . . . 112, 7426
HTMLLatexCmd (option) . . . . . 106, 175, 229
\HTMLleftmargini (length) 171, 422, 423, 1199
\HTMLPageBottom . . . . . 113, 412, 6450
\HTMLPageTop . . . . . 113, 6447
\HTMLTitle . . . . . 112, 120, 6488
\HTMLTitleAfterSection . . . . . 112, 7449
\HTMLTitleBeforeSection . . . . . 112, 7444
\HTMLunicode . . . . . 5723
\HTMLvleftskip (length) . . 171, 422, 423, 1199
hypbmsec (package) . . . . . 845
hypcap (package) . . . . . 845
hypdestopt (package) . . . . . 846
\hyperindexformat . . . . . 10908
\hyperindexref . . . . . 10866
hypernat (package) . . . . . 846
\hyperpage . . . . . 10906
hyperref (package) . . . . . 130, 504, 846
\hypertoc . . . . . 10594
\hypertocfloat . . . . . 10617

hyperxmp (package) . . . . . 856
hyphenat (package) . . . . . 856

I

idxlayout (package) . . . . . 857
\if@titlepage . . . . . 7714
\ifnextchar . . . . . 153
ifoddpage (package) . . . . . 857
ifplatform (package) . . . . . 202
\ifstar . . . . . 153
\IgnoreMinipageWidths . . . . 125, 587, 12314
\ImageAltText . . . . . 113, 11136
ImagesDirectory (option) . . . . . 104, 228
ImagesName (option) . . . . . 104, 228
imakeidx (package) . . . . . 858
imakeidx (program) . . . . . 141
impnattypo (package) . . . . . 862
\includegraphics . . . . . 315
indentfirst (package) . . . . . 365
InDesign (program) . . . . . 74
index (package) . . . . . 862
index (program) . . . . . 138
\IndexPageSeparator . . . . . 112, 10659
\IndexRangeSeparator . . . . . 112, 10659
IndexRef (option) . . . . . 107, 230
\InlineClass . . . . . 117, 6225
\inlinemathnormal . . . . . 154, 5708
\inlinemathother . . . . . 154, 5704
inputenc (package) . . . . . 102
inputenx (package) . . . . . 102
inputtrc (package) . . . . . 864
internet (class) . . . . . 73
intopdf (package) . . . . . 864
isomath (package) . . . . . 864
isotope (package) . . . . . 865
itemize (environment) . . . . . 8241
\itshape . . . . . 12834

J

jurabib (package) . . . . . 866

K

karnaugh-map (package) . . . . . 868
\kern . . . . . 122
key:
  [Gin]:
    class . . . . . 830
keyfloat (package) . . . . . 169, 871
keystroke (package) . . . . . 876
komascript (class) . . . . . 169
kotex (package) . . . . . 174
kpfonts (package) . . . . . 877
kpfonts-otf (package) . . . . . 879
kvoptions (package) . . . . . 226

L

\l@book . . . . . 10637
\l@chapter . . . . . 10639
\l@figure . . . . . 10650
\l@paragraph . . . . . 10648
\l@part . . . . . 10638
\l@section . . . . . 10645
\l@subparagraph . . . . . 10649
\l@subsection . . . . . 10646
\l@subsubsection . . . . . 10647
\l@table . . . . . 10651
\LaTeX . . . . . 13199
LaTeX2HTML (program) . . . . . 73
\LaTeXe . . . . . 13199
lateximage (environment) . 565, 11904, 12043
\LateximageFontScale . . . . . 11834
\LateximageFontSizeName . . . . . 11833
latexmk (option) . . . . . 104, 230
latexmk (program) . . . . . 176
LatexmkIndexCmd (option) . . . . . 107, 229
LaTeXML (program) . . . . . 73
layaureo (package) . . . . . 880
layout (package) . . . . . 880
layouts (package) . . . . . 881
leading (package) . . . . . 883
leftidx (package) . . . . . 884
\leftline . . . . . 12096
length:
  \HTMLleftmargini . . . 171, 422, 423, 1199
  \HTMLvleftskip . . . . . 171, 422, 423, 1199
  \LWR@cmidrulewidth . . . . . 465
  \LWR@heavyrulewidth . . . . . 464
  \LWR@lightrulewidth . . . . . 464
  \LWR@minipageheight . . . . . 587
  \LWR@minipagewidth . . . . . 587
  \LWR@tempheight . . . . . 611
  \LWR@tempraise . . . . . 611
  \LWR@tempwidth . . . . . 611
  \LWR@thiscmidrulewidth . . . . . 465
  \VerbatimHTMLWidth . . . . . 423
  \vleftmargini . . . . . 171, 422, 1199
  \vleftskip . . . . . 171, 422, 1199, 1200
letltxmacro (package) . . . . . 202
letterspace (package) . . . . . 884
lettrine (package) . . . . . 884
\lgweight . . . . . 12809
libertinust1math (package) . . . . . 885
LibreOffice (program) . . . . . 74
\linebreak . . . . . 13072
lineno (package) . . . . . 892
\LinkHome . . . . . 113, 5802, 5807
\linkhomename . . . . . 109, 5799
\LinkNext . . . . . 113, 5835, 5848
\linknextname . . . . . 109, 5831
\LinkPrevious . . . . . 113, 5834, 5838

\linkpreviousname . . . . . 109, 5830
Linux (program) . . . . . 117, 224
lips (package) . . . . . 894
list (environment) . . . . . 8211
listings (package) . . . . . 894
listliketab (package) . . . . . 899
\listof . . . . . 10541
\listoffigures . . . . . 10515
\listoftables . . . . . 10528
lltjext (package) . . . . . 899
lmodern (package) . . . . . 101, 102
lofdepth (counter) . . . . . 524
longtable (environment) . . . . . 4
longtable (package) . . . . . 165, 900
lotdepth (counter) . . . . . 524
lpic (package) . . . . . 903
lscape (package) . . . . . 903
ltablex (package) . . . . . 903
ltcaption (package) . . . . . 904
ltxgrid (package) . . . . . 904
ltxtable (package) . . . . . 905
lua-check-hyphen (package) . . . . . 905
lua-visual-debug (package) . . . . . 905
luacolor (package) . . . . . 905
\LuaLaTeX . . . . . 13228
LuaLaTeX (program) [requirement] . . . . . 77
luamplib (package) . . . . . 906
\LuaTeX . . . . . 13228
luatexko (package) . . . . . 906
luatodonotes (package) . . . . . 173, 908
luavlna (package) . . . . . 910
lwarp (package) . . . . . 104
lwarp-common-mathjax-letters (package) . . . . . 1269
lwarp-common-mathjax-newpxtxmath (package) . . . . . 1276
lwarp-common-mathjax-nonunicode (package) . . . . . 1282
lwarp-common-mathjax-overlaysymbols (package) . . . . . 1285
lwarp-common-multimedia (package) . . 1264
lwarp-patch-komascript (package) . . . 1234
lwarp-patch-memoir (package) . . . . . 1236
lwarp.css (file) . . . . . 116, 269
lwarp.ist (file) . . . . . 147, 310
lwarp.xdy (file) . . . . . 147, 310
lwarp_baseline_marker.eps (file) . . . . 542
lwarp_baseline_marker.png (file) . . . . 542
lwarp_formal.css (file) . . . . . 305
lwarp_mathjax.txt (file) . . . . . 312
lwarp_one_limage.cmd (file) . . . . . 311
lwarp_sagebrush.css (file) . . . . . 301
lwarp_tutorial.txt (file) . . . . . 83
[lwarpmk]:
htmlglossary (option) . . . . . 135, 824
printglossary (option) . . . . . 135, 824
lwarpmk (option) . . . . . 108, 229, 316
lwarpmk (program) . . . . . 189, 316
lwarpmk epstopdf (program) . . . . 158, 580
lwarpmk pdftosvg (program) . . . . 157, 580
lwarpmk.conf (file) . . . . . 268
lwarpmk.lua (file) . . . . . 189
\lwarpsetup . . . . . 955
\LWR@@footnotetext . . . . . 6517
\LWR@@makebox@align . . . . . 12446
\LWR@@makebox@paren . . . . . 12431
\LWR@@printpendingfootnotes . . . . . 6584
\LWR@absorbstar . . . . . 908
\LWR@addbaselinemarker . . . . . 11171
\LWR@addcdashline . . . . . 9102
\LWR@addcmidruletrim . . . . . 9068
\LWR@addcmidrulewidth . . . . . 9099
\LWR@addcompilecmd . . . . . 1948
\LWR@addformatwpalignment . . . . . 9118
\LWR@addleftmostbartag . . . . . 8906
\LWR@addlinktitle . . . . . 10051
\LWR@addmathjax . . . . . 11604
\LWR@addmulticolvertrulecolor . . . . 9372
\LWR@addrulewidth . . . . . 9073
\LWR@addtabularcellcolor . . . . . 9247
\LWR@addtabularhrulecolor . . . . . 9146
\LWR@addtabularrowcolor . . . . . 9131
\LWR@addtabularrulecolors . . . . . 9192
\LWR@afterendverbatim . . . . . 8025
LWR@allowanothergeometry (boolean) . 237
\LWR@amsmathbody . . . . . 11867
\LWR@amsmathbodynumbered . . . . . 11873
LWR@amsmultline (boolean) . . . . . 562
\LWR@applyxfakebold . . . . . 11153
\LWR@atbeginverbatim . . . . . 8005
\LWR@avoiddupfilenames . . . . . 6692
\LWR@backgroundcolor . . . . . 38
\LWR@beginhideamsmath . . . . . 11744
LWR@BlockClassWP (environment) . . . . . 6241
LWR@blocktextcurrentfont (environment) . . . . . 12785, 12926
\LWR@botnavigation . . . . . 5825
LWR@cdashlines . . . . . 464
LWR@cellcolordepth (counter) . . . . . 441
\LWR@cellHTMLcolor . . . . . 8831
\LWR@checkloadbefore . . . . . 67
\LWR@checkloadfilename . . . . . 1348
\LWR@checkloadnever . . . . . 88
\LWR@clearmidrules . . . . . 8987
\LWR@closeparagraph . . . . . 6341
\LWR@closeparagraph@br . . . . . 6331
\LWR@closeprevious . . . . . 5890
\LWR@closetabledatacell . . . . . 8409
\LWR@cmidrulewidth (length) . . . . . 465
LWR@colafterspec . . . . . 441

LWR@colatspec . . . . . 441
LWR@colbangspec . . . . . 441
LWR@colbarspec . . . . . 441
LWR@colbeforespec . . . . . 441
\LWR@columnHTMLcolor . . . . . 8829
\LWR@columnspeclookahead . . . . . 8540
\LWR@compilecmd . . . . . 1945
\LWR@compileuplatex . . . . . 1980
\LWR@convertto . . . . . 823
LWR@copiedsidetoc (boolean) . . . . . 519
\LWR@copyfile . . . . . 1565
\LWR@createautosec . . . . . 7161
\LWR@createfooter . . . . . 7013
LWR@currentautosec (counter) . . . . . 394
\LWR@currentcss . . . . . 6455
\LWR@currenttextcolor . . . . . 12913
\LWR@customizedMathJax . . . . . 6901
\LWR@customizeMathJax . . . . . 6990
\LWR@descitem . . . . . 8257
\LWR@disablepinyin . . . . . 849
LWR@displaymathnormal (environment) 11508
LWR@displaymathother (environment) 11511
\LWR@docdashline . . . . . 9036
\LWR@docmidrule . . . . . 9020
\LWR@doequation . . . . . 11622
\LWR@doindexentry . . . . . 10847
\LWR@doindexentrysub . . . . . 10845
\LWR@doindexentrysubsub . . . . . 10834
LWR@doingapar (boolean) . . . . . 359
LWR@doingcmidrule (boolean) . . . . . 438
LWR@doingstartpars (boolean) . . . . . 359
LWR@doingtbrule (boolean) . . . . . 438
\LWR@domulticolumn . . . . . 9410
\LWR@doubledollar . . . . . 11411
LWR@dynamicmath (boolean) . . . . . 339
\LWR@earlyclassloadnever . . . . . 99
\LWR@earlyloadnever . . . . . 94
LWR@emptyatbang (boolean) . . . . . 439
\LWR@endfloatalignment . . . . . 10335
\LWR@endhideamsmath . . . . . 11753
\LWR@endofline . . . . . 13004
\LWR@ensuredoingapar . . . . . 6307
LWR@equationother (environment) . . . 11525
\LWR@equationtag . . . . . 11853
\LWR@excludecomment . . . . . 1127
LWR@exitingtabular (boolean) . . . . . 439
\LWR@expandableformatted . . . . . 1646
\LWR@expandableformattedenv . . . . . 1678
\LWR@expcolspec . . . . . 8708
LWR@externalfilecnt (counter) . . . . . 541
\LWR@fboxstyle . . . . . 12506
LWR@figcaption (environment) . . . . . 10371
\LWR@filenamenoblanks . . . . . 6705
\LWR@filestart . . . . . 7458
\LWR@findcurrenttextcolor . . . . . 12916
\LWR@findword . . . . . 1345
\LWR@firstoffour . . . . . 854
\LWR@floatalignment . . . . . 10321
\LWR@floatalignmentname . . . . . 10320
\LWR@floatbegin . . . . . 10226
\LWR@floatend . . . . . 10273
\LWR@floatstyle . . . . . 2
\LWR@footnotebox . . . . . 6512
\LWR@footnotetext . . . . . 6547
\LWR@forceemptyline . . . . . 850
LWR@forceminipagefullwidth (boolean) 588
\LWR@forceminwidth . . . . . 12495
\LWR@forcenewautoidanchor . . . . . 10296
\LWR@forcenewpage . . . . . 5910
\LWR@forceSVGmessage . . . . . 13484
\LWR@formatted . . . . . 1630
\LWR@formatted@checkendname . . . . . 1621
\LWR@formatted@checkname . . . . . 1612
\LWR@formattedenv . . . . . 1662
\LWR@formatting . . . . . 1611
LWR@foundmrowcell (boolean) . . . . . 439
\LWR@fourthoffour . . . . . 854
LWR@freezethisautoid (boolean) . . . . . 512
\LWR@futurenonspacelet . . . . . 8335
\LWR@FVstyle . . . . . 54
\LWR@getexparray . . . . . 5677
\LWR@getmynexttoken . . . . . 8345
LWR@glrbox (environment) . . . . . 881
\LWR@gsavebox . . . . . 867
LWR@hdashedlines (counter) . . . . . 438
\LWR@heavyrulewidth (length) . . . . . 464
\LWR@hidelatexequation . . . . . 11588
LWR@hlines (counter) . . . . . 438
\LWR@hook@processingtags . . . . . 5953
\LWR@href . . . . . 10167
\LWR@HTML@caption@begin . . . . . 10381
\LWR@HTML@caption@end . . . . . 10392
\LWR@HTML@ref . . . . . 10094
\LWR@htmlblockcomment . . . . . 6139
\LWR@htmlblocktag . . . . . 6141
\LWR@HTMLcline . . . . . 9762
\LWR@htmlclosecomment . . . . . 6106
\LWR@htmlcomment . . . . . 6127
\LWR@htmldivclass . . . . . 6178
\LWR@htmldivclassend . . . . . 6181
\LWR@htmlelement . . . . . 6192
\LWR@htmlelementclass . . . . . 6164
\LWR@htmlelementclassend . . . . . 6170
\LWR@htmlelementclassline . . . . . 6184
\LWR@htmlelementend . . . . . 6195
LWR@htmlfilenumber (counter) . . . . . 342
\LWR@htmlfileref . . . . . 9956
\LWR@HTMLhline . . . . . 9743
\LWR@HTMLLatexCmd . . . . . 1990
\LWR@htmlmulticolumn . . . . . 9476

\LWR@htmlopencomment . . . . . 6106
\LWR@htmlrefsectionfilename . . . . . 5789
\LWR@HTMLsanitize . . . . . 6871
\LWR@HTMLsanitizeexpand . . . . . 6879
\LWR@htmlsectionfilename . . . . . 5749
LWR@htmlseqfilenumber (counter) . . . . *341*
\LWR@htmlspan . . . . . 6083
\LWR@htmlspanclass . . . . . 6091
\LWR@htmltag . . . . . 6101
\LWR@htmltagc . . . . . 6013
\LWR@hyperindexref@@comma . . . . . 10877
\LWR@hyperindexref@comma . . . . . 10870
\LWR@hyperindexref@range . . . . . 10882
\LWR@hyperindexrefnullified . . . . . 10851
\LWR@hyperindexrefsub . . . . . 10885
\LWR@hyperindexrefsubtwo . . . . . 10892
\LWR@includecomment . . . . . 1127
\LWR@indentHTML . . . . . 6007
\LWR@indentHTMLtwo . . . . . 6010
\LWR@indexitem . . . . . 10676
\LWR@indexnameref . . . . . 10805
\LWR@indexnameref@anonref . . . . . 10746
\LWR@indexnameref@cref . . . . . 10772
\LWR@indexnameref@crefnameref . . . 10789
\LWR@indexnameref@ref . . . . . 10751
\LWR@indexnameref@refnameref . . . . 10760
\LWR@indexsubitem . . . . . 10680
\LWR@indexsubsubitem . . . . . 10684
LWR@indisplaymathimage (boolean) . . . *541*
\LWR@infoprocessingmathjax . . . . . 6936
LWR@insidemathcomment (boolean) . . . . *541*
\LWR@instertatbangcols . . . . . 8401
LWR@intabularmetadata (boolean) . . . . *439*
\LWR@isolate . . . . . 840
LWR@isstartingequation (boolean) . . . *567*
\LWR@itemizeitem . . . . . 8234
\LWR@label@createtag . . . . . 10002
\LWR@label@inmathcomment . . . . . 9988
\LWR@label@subcreatetag . . . . . 9984
LWR@latestautopage (counter) . . . . . *514*
\LWR@lateximage@oneimage . . . . . 11889
\LWR@lateximage@oneimageb . . . . . 11880
LWR@lateximagedepth (counter) . . . . . *566*
\LWR@lateximagedepthref . . . . . 9959
LWR@lateximagenumber (counter) . . . . . *566*
\LWR@lateximagenumberref . . . . . 9962
\LWR@lateximagesfile . . . . . 1527
\LWR@latexmkcmd . . . . . 1966
\LWR@latexmkdvipdfm . . . . . 1971
\LWR@latexmkvar . . . . . 1960
\LWR@LetLtxMacrocs . . . . . 904
\LWR@lightrulewidth (length) . . . . . *464*
\LWR@linkcatcodes . . . . . 10126
\LWR@linkmediacatcodes . . . . . 10134
LWR@LIpage (counter) . . . . . *567*
\LWR@listitem . . . . . 8196
\LWR@loadafter . . . . . 20
\LWR@loadbefore . . . . . 55
\LWR@loadnever . . . . . 73
\LWR@longtabledatacaptiontag . . . . . 9485
\LWR@lookforpackagename . . . . . 1398
\LWR@lwarpconfversion . . . . . 1939
\LWR@LwarpEnd . . . . . 7635, 13276
\LWR@LwarpStart . . . . . 7556, 13276
\LWR@maketitlesetup . . . . . 34, 7811
LWR@MathJax@silentquotes (boolean) . *381*
\LWR@mathjaxfilename . . . . . 6466
\LWR@mathjaxwarn . . . . . 13441
LWR@mathmacro (boolean) . . . . . *338*
\LWR@maybe@orignewpage . . . . . 860
\LWR@maybenewtablerow . . . . . 8838
\LWR@maybeprintpendingfootnotes . . 6603
\LWR@maybetocdata . . . . . 10593
LWR@midrulecounter (counter) . . . . . *441*
LWR@midrules . . . . . *464*
LWR@minipagefullwidth (boolean) . . . . *588*
\LWR@minipageheight (length) . . . . . *587*
\LWR@minipagestartpars . . . . . 13011
\LWR@minipagestoppars . . . . . 13014
LWR@minipagethispar (boolean) . . . . . *589*
\LWR@minipagewidth (length) . . . . . *587*
\LWR@multicolother . . . . . 9312
\LWR@multicolpartext . . . . . 9306
\LWR@multicolskip . . . . . 9318
\LWR@multirowborder . . . . . 3
\LWR@mynexttoken . . . . . 8334
\LWR@myshorttoc . . . . . 10461
\LWR@nameref . . . . . 9953
LWR@nestspan (environment) . . . . . 6039
\LWR@new@label . . . . . 10031
\LWR@newautoidanchor . . . . . 10314
\LWR@newautopagelabel . . . . . 6822
\LWR@newhtmlfile . . . . . 7032
LWR@nextautoid (counter) . . . . . *514*
LWR@nextautopage (counter) . . . . . *514*
LWR@nextequation (counter) . . . . . *554*
\LWR@nolinkurl . . . . . 10179
\LWR@notltjloadafter . . . . . 42
\LWR@notmemoirloadafter . . . . . 39
\LWR@nullfonts . . . . . 10996
\LWR@nullifycomment . . . . . 1339
\LWR@nullifyNoAutoSpacing . . . . . 9768
\LWR@nulllistfills . . . . . 8203
\LWR@openparagraph . . . . . 6313
LWR@opttablecol (boolean) . . . . . *439*
\LWR@orig@setBold . . . . . 11151
\LWR@orig@unsetBold . . . . . 11152
\LWR@origcolspec . . . . . 8384
LWR@origmathjax (boolean) . . . . . *227*
\LWR@overline . . . . . 12908

\LWR@parseaftercolumn . . . . . 8617
\LWR@parseatcolumn . . . . . 8550
\LWR@parsebangcolumn . . . . . 8579
\LWR@parsebarcolumn . . . . . 8629
\LWR@parsebeforecolumn . . . . . 8605
\LWR@parsecoloncolumn . . . . . 8654
\LWR@parseDcolumn . . . . . 8703
\LWR@parsedrequirepackagenames . . . 1338
\LWR@parsenormalcolumn . . . . . 8679
\LWR@parsepcolumn . . . . . 8691
\LWR@parsesemicoloncolumn . . . . . 8675
\LWR@parsestarcolumn . . . . . 8700
\LWR@parsetablecols . . . . . 8740
\LWR@parsewcolumn . . . . . 8695
\LWR@patcherror . . . . . 831
\LWR@patchlists . . . . . 8282
\LWR@pdfencoding . . . . . 734
\LWR@phantomsection . . . . . 13138
\LWR@popclose . . . . . 5641
\LWR@PreloadedPackage . . . . . 12101
LWR@prevFileDepth (counter) . . . . . *393*
LWR@previousautopagelabel (counter) . *380*
\LWR@printatbang . . . . . 8881
\LWR@printbartag . . . . . 8871
\LWR@printchaptername . . . . . 7182
\LWR@printcloselist . . . . . 8101
\LWR@PrintLatexCmd . . . . . 1990
\LWR@printlength . . . . . 1319
\LWR@printmccoldata . . . . . 9321
\LWR@printmccoltype . . . . . 9264
\LWR@printopenlist . . . . . 8102
\LWR@printpendingfootnotes . . . . . 6600
\LWR@printpendingmpfootnotes . . . . . 6612
\LWR@printpercentlength . . . . . 824
\LWR@printthetitle . . . . . 7763
\LWR@providelength . . . . . 820
\LWR@ProvidesPackageDrop . . . . . 1517
\LWR@ProvidesPackageDropA . . . . . 1502
\LWR@ProvidesPackageDropB . . . . . 1511
\LWR@ProvidesPackagePass . . . . . 1471
\LWR@pushclose . . . . . 5614
\LWR@pushoneclose . . . . . 7167
\LWR@quickfile . . . . . 1524
\LWR@remembertag . . . . . 11857
\LWR@replacestrings . . . . . 6830
\LWR@requesttoc . . . . . 7628
\LWR@requirepackagenames . . . . . 1337
\LWR@restoreMathJaxformatting . . . 10944
\LWR@restoreorigaccents . . . . . 1888
\LWR@restoreorigformatting . . . . . 10945
\LWR@restoreoriglists . . . . . 8310
\LWR@rowHTMLcolor . . . . . 8830
\LWR@ruleHTMLcolor . . . . . 8832
\LWR@sanitize . . . . . 1029
\LWR@sanitized . . . . . 1028
\LWR@secondoffour . . . . . 854
\LWR@section . . . . . 7187
\LWR@sectionnumber . . . . . 7158
\LWR@select@html@hspace . . . . . 13031
\LWR@select@html@nohspace . . . . . 13062
\LWR@select@print@hspace . . . . . 13065
\LWR@setcurrentfont . . . . . 11154
\LWR@setexparray . . . . . 5668
\LWR@setlatestname . . . . . 9939
\LWR@setOSWindows . . . . . 943
\LWR@setref . . . . . 9947
LWR@setseqfilelabel (boolean) . . . . . *341*
LWR@setvirtualpage (environment) . . 12298
\LWR@shellescapecmd . . . . . 1940
\LWR@sidetoc . . . . . 10567
\LWR@simplifycustom . . . . . 6680
\LWR@simplifyname . . . . . 6669
\LWR@singledollar . . . . . 11438
\LWR@singledollarmeasure . . . . . 11226
LWR@skipatbang (boolean) . . . . . *439*
LWR@skippingmcolrowcell (boolean) . . *438*
LWR@skippingmrowcell (boolean) . . . . . *438*
LWR@spandepth (counter) . . . . . *359*
\LWR@spanwarnformat . . . . . 6023
\LWR@spanwarninvalid . . . . . 6031
\LWR@splitstarcontents . . . . . 8711
LWR@splitstarcopies (counter) . . . . . *453*
LWR@splitstarindex (counter) . . . . . *453*
LWR@starcount (counter) . . . . . *453*
LWR@starredlongtable (boolean) . . . . . *441*
LWR@startedrow (boolean) . . . . . *438*
LWR@startingequation (counter) . . . . . *567*
\LWR@startingequationtag . . . . . 11852
\LWR@startnewdepth . . . . . 7171
\LWR@startpars . . . . . 6383
\LWR@startref . . . . . 10057
\LWR@stoppars . . . . . 6404
\LWR@stripperiod . . . . . 9938
\LWR@strresult . . . . . 8382
\LWR@subaddcmidruletrim . . . . . 9055
\LWR@subaddtabularcellcolor . . . . . 9239
\LWR@subcdashline . . . . . 9023
\LWR@subcmidrule . . . . . 9005
\LWR@subcustomizedmathjax . . . . . 6904
\LWR@subhtmlelementclass . . . . . 6146
\LWR@subHTMLsanitize . . . . . 6851
\LWR@subhyperref . . . . . 10142
\LWR@subhyperrefclass . . . . . 10156
\LWR@subhyperreftext . . . . . 10151
\LWR@subinlineimage . . . . . 10205
\LWR@subnewref . . . . . 10088
\LWR@subsingledollar . . . . . 11351
\LWR@subsingledollarsvg . . . . . 11272
\LWR@subtableofcontents . . . . . 10475
\LWR@subtabularhtmlcolumns . . . . . 9556

\LWR@syncmathjax . . . . . 11576
\LWR@syncnotenames . . . . . 11685
\LWR@syncnotenumbers . . . . . 11679
\LWR@synconenotename . . . . . 11680
\LWR@synconenotenumber . . . . . 11674
LWR@tablecolspec . . . . . 440
LWR@tablecolspecindex (counter) . . . . 440
LWR@tablecolspecwidth (counter) . . . . 440
\LWR@tabledatacolumntag . . . . . 9645
\LWR@tabledatasinglecolumntag . . . . 8920
LWR@tableLaTeXcolindex (counter) . . . 440
LWR@tableparcell (boolean) . . . . . 438
LWR@tabletotalLaTeXcols (counter) . . 440
LWR@tabletotalLaTeXcolsnext (counter) 440
\LWR@tabular@warpprintonly . . . . . 9764
LWR@tabularcelladded (boolean) . . . . . 438
LWR@tabularDepth (counter) . . . . . 439
\LWR@tabularendofline . . . . . 8519
\LWR@tabularfinishrow . . . . . 8470
\LWR@tabularhtmlcolumns . . . . . 9566
\LWR@tabularleftedge . . . . . 8911
LWR@tabularmutemods (boolean) . . . . . 439
LWR@tabularpardepth (counter) . . . . . 439
\LWR@tdaddstyle . . . . . 9042
\LWR@tdendstyles . . . . . 9048
\LWR@tdstartstyles . . . . . 9041
\LWR@tempcolor . . . . . 12914
\LWR@tempcolortwo . . . . . 12914
\LWR@tempheight (length) . . . . . 611
\LWR@tempraise (length) . . . . . 611
\LWR@tempwidth (length) . . . . . 611
\LWR@textcurrentcolor . . . . . 21, 12919
\LWR@textcurrentfont . . . . . 12763, 12925
\LWR@thirdoffour . . . . . 854
\LWR@ThisAltText . . . . . 11138
LWR@thisautoid (counter) . . . . . 512
LWR@thisautoidWP (counter) . . . . . 512
\LWR@thiscmidrulewidth (length) . . . . 465
\LWR@thiscolspec . . . . . 8919
\LWR@thisfilename . . . . . 6663
\LWR@thisnewfilename . . . . . 6668
\LWR@titlingmaketitle . . . . . 84, 7873
\LWR@topnavigation . . . . . 5822
\LWR@traceinfo . . . . . 1593
LWR@tracinglwarp (boolean) . . . . . 249
LWR@trimlrules . . . . . 464
LWR@trimrrules . . . . . 464
\LWR@unknownengine . . . . . 1952
LWR@unknownmathsize (boolean) . . . . . 544
\LWR@url . . . . . 10192
LWR@usedmultirow (boolean) . . . . . 438
LWR@validtablecol (boolean) . . . . . 439
LWR@verbtags (boolean) . . . . . 424
LWR@virtualpagedepth (counter) . . . . . 588
\LWR@vspace . . . . . 13069
LWR@warnbaselinemarker (boolean) . . . 544
LWR@warnedcustomizemathjax (boolean) 383
\LWR@WPcell . . . . . 9114
\LWR@write@lwarplabel . . . . . 9965
\LWR@writeconf . . . . . 2092
\LWR@xcolorrowHTMLcolor . . . . . 8828
LWR@xfakebold (boolean) . . . . . 541
\LWR@xindex@modifyentry . . . . . 10688
LWRcreatelwarpmk (environment) . . . . . 1183
\LWRopquote . . . . . 938
\LWRopseq . . . . . 939
\LWRPrintStack . . . . . 5868
\LWRsetnextfloat . . . . . 10365
\LWRtexttitlecase . . . . . 899
lyluatex (package) . . . . . 910
\LyX . . . . . 13272

## M

Mac OS (program) . . . . . 117, 224
\macrotocsname . . . . . 893
Madcap (program) . . . . . 74
magaz (package) . . . . . 912
\mainmatter . . . . . 7148
make (program) . . . . . 178
\makebox . . . . . 12455
makeidx (package) . . . . . 149, 150, 913, 1171
\MakeIndex . . . . . 13250
makeindex (option) . . . . . 106, 230
makeindex (program) . . . . . 137, 147
makeindexStyle (option) . . . . . 106, 147, 228
\makelabel . . . . . 428
\maketitle . . . . . 48, 119, 7832
manyfoot (package) . . . . . 913
marginal (package) . . . . . 915
marginfit (package) . . . . . 916
marginfix (package) . . . . . 916
marginnote (package) . . . . . 916
\marginpar . . . . . 124, 374, 6624
\marginparBlock . . . . . 124, 374, 6635, 6653
\markboth . . . . . 5924
\markright . . . . . 5925
marvosym (package) . . . . . 917
math (environment) . . . . . 11507
mathalpha (package) . . . . . 917
mathastext (package) . . . . . 918
mathcomp (package) . . . . . 919
mathdesign (package) . . . . . 919
mathdots (package) . . . . . 921
mathfixs (package) . . . . . 921
\MathImageAltText . . . . . 114, 11137
MathJax (program) . . . . . 152, 153
MathJax (program) [requirement] . . . . . 77
mathjax (boolean) . . . . . 227
mathjax (option) . . . . . 104, 227
\MathJaxFilename . . . . . 112, 6467
mathpazo (package) . . . . . 922

mathptmx (package) . . . . . 922
mathspec (package) . . . . . 923
mathsvg (option) . . . . . 104, 227
mathtools (package) . . . . . 156, 925
mattens (package) . . . . . 931
maybemath (package) . . . . . 933
\mbox . . . . . 12428
mcaption (package) . . . . . 933
\mcolrowcell . . . . . 9722
mdframed (package) . . . . . 128, 933
\mdseries . . . . . 12794
mdwmath (package) . . . . . 942
media9 (package) . . . . . 161, 943
memhfixc (package) . . . . . 945
memoir (class) . . . . . 169, 171, 1200
menukeys (package) . . . . . 945
metalogo (package) . . . . . 946
metalogox (package) . . . . . 946
mhchem (package) . . . . . 947
microtype (package) . . . . . 235, 950
midfloat (package) . . . . . 950
midpage (package) . . . . . 951
\MiKTeX . . . . . 13270
minibox (package) . . . . . 951
minipage (environment) . . . . . 12324
\minipagefullwidth . . . . . 12312
minitoc (package) . . . . . 952
minted (package) . . . . . 952
mismath (package) . . . . . 953
mleftright (package) . . . . . 957
mmap (package) . . . . . 102
morefloats (package) . . . . . 957
moreverb (package) . . . . . 957
movie15 (package) . . . . . 161, 958
mparhack (package) . . . . . 960
\mrowcell . . . . . 9719
MS-Windows (program) . . . . . 117, 224
multibib (package) . . . . . 960
multicap (package) . . . . . 960
multicol (package) . . . . . 961
multicolrule (package) . . . . . 962
\multicolumnrow . . . . . 45, 9589
multimedia (package) . . . . . 161, 962
multiobjective (package) . . . . . 963
\multirow . . . . . 965
multirow (package) . . . . . 964
multitoc (package) . . . . . 968
multline (environment) . . . . . 72
multline* (environment) . . . . . 75
musicography (package) . . . . . 968

## N

nameauth (package) . . . . . 971
\Nameref . . . . . 10120
\nameref . . . . . 10111
nameref (package) . . . . . 972
natbib (package) . . . . . 973
nccfancyhdr (package) . . . . . 974
nccfoots (package) . . . . . 974
nccmath (package) . . . . . 975
needspace (package) . . . . . 976
newclude (package) . . . . . 172
\newfloat . . . . . 5
newfloat (package) . . . . . 240
\newline . . . . . 13002
\newpage . . . . . 12999
newpxmath (package) . . . . . 976
\newtheorem . . . . . 426
newtxmath (package) . . . . . 977
newtxsf (package) . . . . . 978
newunicodechar (package) . . . . . 102
nextpage (package) . . . . . 979
nfssext-cfr (package) . . . . . 979
nicefrac (package) . . . . . 157, 986
niceframe (package) . . . . . 987
nicematrix (package) . . . . . 987
\noalign . . . . . 9732
\nohyperpage . . . . . 10907
noitcrul (package) . . . . . 990
nolbreaks (package) . . . . . 990
\nolinebreak . . . . . 13073
nomencl (package) . . . . . 136, 990
nonfloat (package) . . . . . 991
nonumonpart (package) . . . . . 991
\nopagebreak . . . . . 13077
\nopagecolor . . . . . 76
nopageno (package) . . . . . 991
\normalcolor . . . . . 8
\normalfont . . . . . 12872
\normalmarginpar . . . . . 6650
notes (package) . . . . . 991
notespages (package) . . . . . 992
nowidow (package) . . . . . 993
ntheorem (package) . . . . . 155, 993
\numberline . . . . . 10588
numindex (option) [tocbibind] . . . . . 150, 1171

## O

octave (package) . . . . . 1005
OpenOffice (program) . . . . . 74
option:
  --shell-escape . . . . . 101
  [lwarpmk]:
    htmlglossary . . . . . 135, 824
    printglossary . . . . . 135, 824
  [tocbibind]:
    numindex . . . . . 150, 1171
  [tocloft]:
    titles . . . . . 134
  BaseJobname . . . . . 108, 228
  dvipdfm . . . . . 104, 230
  dvipdfmx . . . . . 104, 230

dvips . . . . . 104, 230
GlossaryCmd . . . . . 108, 135, 230, 824
HomeHTMLFilename . . . . . 104, 229
HTMLFilename . . . . . 104, 229
HTMLIndexCmd . . . . . 107, 229
HTMLLatexCmd . . . . . 106, 175, 229
ImagesDirectory . . . . . 104, 228
ImagesName . . . . . 104, 228
IndexRef . . . . . 107, 230
latexmk . . . . . 104, 230
LatexmkIndexCmd . . . . . 107, 229
lwarpmk . . . . . 108, 229, 316
makeindex . . . . . 106, 230
makeindexStyle . . . . . 106, 147, 228
mathjax . . . . . 104, 227
mathsvg . . . . . 104, 227
OSWindows . . . . . 108, 117, 224, 229
pdftotextEnc . . . . . 108, 228
PrintIndexCmd . . . . . 106, 229
PrintLatexCmd . . . . . 106, 175, 229
warpHTML . . . . . 108, 227
warpprint . . . . . 108, 227
xindex . . . . . 106, 230
xindexConfig . . . . . 106, 148, 228
xindy . . . . . 106, 230
xindyCodepage . . . . . 106, 228
xindyLanguage . . . . . 106, 228
xindyStyle . . . . . 106, 148, 228
\OSPathSymbol . . . . . 942
OSWindows (option) . . . . . 108, 117, 224, 229
overpic (package) . . . . . 161, 1006

## P

package:
2in1 . . . . . 628
2up . . . . . 628
a4 . . . . . 628
a4wide . . . . . 629
a5comb . . . . . 629
abstract . . . . . 133, 629
academicons . . . . . 631
accents . . . . . 632
accessibility . . . . . 633
accsupp . . . . . 633
acro . . . . . 634
acronym . . . . . 636
addlines . . . . . 638
adjmulticol . . . . . 637
afterpage . . . . . 639
algorithm2e . . . . . 639
algorithmicx . . . . . 167, 643
alltt . . . . . 644
amscdx . . . . . 644
amsmath . . . . . 645
amsthm . . . . . 649
anonchap . . . . . 653
anysize . . . . . 653
appendix . . . . . 134, 654
ar . . . . . 654
arabicfront . . . . . 656
array . . . . . 656
arydshln . . . . . 657
asymptote . . . . . 161, 659
atbegshi . . . . . 659
attachfile . . . . . 660
attachfile2 . . . . . 661
authblk . . . . . 134, 663
autobreak . . . . . 664
autonum . . . . . 664
awesomebox . . . . . 666
axessibility . . . . . 667
axodraw2 . . . . . 667
babel . . . . . 172
backnaur . . . . . 668
backref . . . . . 669
balance . . . . . 669
bbding . . . . . 669
biblatex . . . . . 674
bibunits . . . . . 678
bigdelim . . . . . 167, 678
bigfoot . . . . . 680
bigstrut . . . . . 680
bitpattern . . . . . 681
blowup . . . . . 681
bm . . . . . 681
booklet . . . . . 682
bookmark . . . . . 682
booktabs . . . . . 683
bophook . . . . . 685
bounddvi . . . . . 685
boxedminipage . . . . . 685
boxedminipage2e . . . . . 686
braket . . . . . 686
breakurl . . . . . 686
breqn . . . . . 687
bsheaders . . . . . 688
bussproofs . . . . . 689
bxpapersize . . . . . 689
bytefield . . . . . 689
calc . . . . . 238
cancel . . . . . 690
canoniclayout . . . . . 691
capt-of . . . . . 517
caption . . . . . 168, 517, 691
caption3 . . . . . 693
cases . . . . . 695
centernot . . . . . 696
changebar . . . . . 696
changelayout . . . . . 697
changepage . . . . . 697
changes . . . . . 698

chappg . . . . . 703
chapterbib . . . . . 703
chemfig . . . . . 704
chemformula . . . . . 706
chemgreek . . . . . 711
chemmacros . . . . . 711
chemnum . . . . . 729
chkfloat . . . . . 730
chngpage . . . . . 730
cite . . . . . 730
citeref . . . . . 731
CJK . . . . . 731
CJKutf8 . . . . . 732
cleveref . . . . . 130, 732
clrdblpg . . . . . 735
cm-super . . . . . 101
cmap . . . . . 102
cmbright . . . . . 735
cmdtrack . . . . . 736
colonequals . . . . . 736
color . . . . . 159, 737
colortbl . . . . . 166, 737
comment . . . . . 233
continue . . . . . 739
copyrightbox . . . . . 739
crop . . . . . 740
ctable . . . . . 740
cuted . . . . . 743
cutwin . . . . . 743
dblfloatfix . . . . . 744
dblfnote . . . . . 744
dcolumn . . . . . 744
decimal . . . . . 745
dejavu . . . . . 101
diagbox . . . . . 745
dingbat . . . . . 746
ditaa . . . . . 178
DotArrow . . . . . 747
dotlessi . . . . . 748
dprogress . . . . . 748
draftcopy . . . . . 748
draftfigure . . . . . 749
draftwatermark . . . . . 749
drftcite . . . . . 750
easy-todo . . . . . 750
ebook . . . . . 751
econometrics . . . . . 751
ed . . . . . 754
ellipsis . . . . . 755
embrac . . . . . 755
emptypage . . . . . 756
endfloat . . . . . 756
endheads . . . . . 756
endnotes . . . . . 134, 757
engtlc . . . . . 758
enumerate . . . . . 762
enumitem . . . . . 763
environ . . . . . 240
epigraph . . . . . 763
epsf . . . . . 764
epsfig . . . . . 764
epstopdf . . . . . 159, 765
epstopdf-base . . . . . 765
eqlist . . . . . 766
eqparbox . . . . . 767
errata . . . . . 768
eso-pic . . . . . 769
esvect . . . . . 770
etoc . . . . . 770
etoolbox . . . . . 202
eurosym . . . . . 772
everyhook . . . . . 239
everypage . . . . . 773
everyshi . . . . . 773
expl3 . . . . . 238
extarrows . . . . . 773
extramarks . . . . . 774
fancybox . . . . . 127, 774
fancyhdr . . . . . 779
fancyref . . . . . 780
fancytabs . . . . . 781
fancyvrb . . . . . 781
fbox . . . . . 788
fewerfloatpages . . . . . 790
figcaps . . . . . 790
figsize . . . . . 791
filecontents . . . . . 239
fitbox . . . . . 791
fix2col . . . . . 792
fixmath . . . . . 792
fixme . . . . . 173, 792
fixmetodonotes . . . . . 794
flafter . . . . . 794
flippdf . . . . . 794
float . . . . . 167, 795
floatflt . . . . . 796
floatpag . . . . . 797
floatrow . . . . . 168, 798
fltrace . . . . . 803
flushend . . . . . 803
fnbreak . . . . . 803
fncychap . . . . . 804
fnlineno . . . . . 804
fnpara . . . . . 804
fnpos . . . . . 805
fontawesome . . . . . 805
fontawesome5 . . . . . 806
fontaxes . . . . . 807
fontenc . . . . . 102, 807
fontspec . . . . . 101, 235

footmisc . . . . . 808
footnote . . . . . 809
footnotebackref . . . . . 810
footnotehyper . . . . . 810
footnoterange . . . . . 810
footnpag . . . . . 810
foreign . . . . . 811
forest . . . . . 811
fouridx . . . . . 811
fourier . . . . . 812
framed . . . . . 813
ftcap . . . . . 816
ftnright . . . . . 816
fullminipage . . . . . 816
fullpage . . . . . 816
fullwidth . . . . . 817
fvextra . . . . . 817
fwlw . . . . . 820
gensymb . . . . . 821
gentombow . . . . . 821
geometry . . . . . 236, 821
gettitlestring . . . . . 238
ghsystem . . . . . 822
gindex . . . . . 138, 823
gloss . . . . . 135, 823
glossaries . . . . . 135, 824
gmeometric . . . . . 826
graphics . . . . . 157, 826
graphicx . . . . . 157, 839
grffile . . . . . 159, 839
grid . . . . . 839
grid-system . . . . . 839
gridset . . . . . 840
hang . . . . . 840
hanging . . . . . 842
hepunits . . . . . 843
hhline . . . . . 844
hhtensor . . . . . 844
hypbmsec . . . . . 845
hypcap . . . . . 845
hypdestopt . . . . . 846
hypernat . . . . . 846
hyperref . . . . . 130, 504, 846
hyperxmp . . . . . 856
hyphenat . . . . . 856
idxlayout . . . . . 857
ifoddpage . . . . . 857
ifplatform . . . . . 202
imakeidx . . . . . 858
impnattypo . . . . . 862
indentfirst . . . . . 365
index . . . . . 862
inputenc . . . . . 102
inputenx . . . . . 102
inputtrc . . . . . 864
intopdf . . . . . 864
isomath . . . . . 864
isotope . . . . . 865
jurabib . . . . . 866
karnaugh-map . . . . . 868
keyfloat . . . . . 169, 871
keystroke . . . . . 876
kotex . . . . . 174
kpfonts . . . . . 877
kpfonts-otf . . . . . 879
kvoptions . . . . . 226
layaureo . . . . . 880
layout . . . . . 880
layouts . . . . . 881
leading . . . . . 883
leftidx . . . . . 884
letltxmacro . . . . . 202
letterspace . . . . . 884
lettrine . . . . . 884
libertinust1math . . . . . 885
lineno . . . . . 892
lips . . . . . 894
listings . . . . . 894
listliketab . . . . . 899
lltjext . . . . . 899
lmodern . . . . . 101, 102
longtable . . . . . 165, 900
lpic . . . . . 903
lscape . . . . . 903
ltablex . . . . . 903
ltcaption . . . . . 904
ltxgrid . . . . . 904
ltxtable . . . . . 905
lua-check-hyphen . . . . . 905
lua-visual-debug . . . . . 905
luacolor . . . . . 905
luamplib . . . . . 906
luatexko . . . . . 906
luatodonotes . . . . . 173, 908
luavlna . . . . . 910
lwarp . . . . . 104
lwarp-common-mathjax-letters . . 1269
lwarp-common-mathjax-newpxtxmath . . . . . 1276
lwarp-common-mathjax-nonunicode 1282
lwarp-common-mathjax-overlaysymbols . . . . . 1285
lwarp-common-multimedia . . . . . 1264
lwarp-patch-komascript . . . . . 1234
lwarp-patch-memoir . . . . . 1236
lyluatex . . . . . 910
magaz . . . . . 912
makeidx . . . . . 149, 150, 913, 1171
manyfoot . . . . . 913
marginal . . . . . 915

marginfit . . . . . 916
marginfix . . . . . 916
marginnote . . . . . 916
marvosym . . . . . 917
mathalpha . . . . . 917
mathastext . . . . . 918
mathcomp . . . . . 919
mathdesign . . . . . 919
mathdots . . . . . 921
mathfixs . . . . . 921
mathpazo . . . . . 922
mathptmx . . . . . 922
mathspec . . . . . 923
mathtools . . . . . 156, 925
mattens . . . . . 931
maybemath . . . . . 933
mcaption . . . . . 933
mdframed . . . . . 128, 933
mdwmath . . . . . 942
media9 . . . . . 161, 943
memhfixc . . . . . 945
menukeys . . . . . 945
metalogo . . . . . 946
metalogox . . . . . 946
mhchem . . . . . 947
microtype . . . . . 235, 950
midfloat . . . . . 950
midpage . . . . . 951
minibox . . . . . 951
minitoc . . . . . 952
minted . . . . . 952
mismath . . . . . 953
mleftright . . . . . 957
mmap . . . . . 102
morefloats . . . . . 957
moreverb . . . . . 957
movie15 . . . . . 161, 958
mparhack . . . . . 960
multibib . . . . . 960
multicap . . . . . 960
multicol . . . . . 961
multicolrule . . . . . 962
multimedia . . . . . 161, 962
multiobjective . . . . . 963
multirow . . . . . 964
multitoc . . . . . 968
musicography . . . . . 968
nameauth . . . . . 971
nameref . . . . . 972
natbib . . . . . 973
nccfancyhdr . . . . . 974
nccfoots . . . . . 974
nccmath . . . . . 975
needspace . . . . . 976
newclude . . . . . 172
newfloat . . . . . 240
newpxmath . . . . . 976
newtxmath . . . . . 977
newtxsf . . . . . 978
newunicodechar . . . . . 102
nextpage . . . . . 979
nfssext-cfr . . . . . 979
nicefrac . . . . . 157, 986
niceframe . . . . . 987
nicematrix . . . . . 987
noitcrul . . . . . 990
nolbreaks . . . . . 990
nomencl . . . . . 136, 990
nonfloat . . . . . 991
nonumonpart . . . . . 991
nopageno . . . . . 991
notes . . . . . 991
notespages . . . . . 992
nowidow . . . . . 993
ntheorem . . . . . 155, 993
octave . . . . . 1005
overpic . . . . . 161, 1006
pagegrid . . . . . 1007
pagenote . . . . . 134, 1007
pagesel . . . . . 1007
paralist . . . . . 1008
parallel . . . . . 1008
parcolumns . . . . . 1010
parnotes . . . . . 1012
parskip . . . . . 1013
pbox . . . . . 1013
pdfcol . . . . . 1014
pdfcolfoot . . . . . 1014
pdfcolmk . . . . . 1015
pdfcolparallel . . . . . 1015
pdfcolparcolumns . . . . . 1015
pdfcomment . . . . . 1016
pdfcrypt . . . . . 1017
pdflscape . . . . . 1017
pdfmarginpar . . . . . 1017
pdfpages . . . . . 1017
pdfprivacy . . . . . 1020
pdfrender . . . . . 1020
pdfsync . . . . . 1020
pdftricks . . . . . 160, 1021
pdfx . . . . . 1021
perltex . . . . . 177
perpage . . . . . 1021
pfnote . . . . . 1023
phfqit . . . . . 1023
physics . . . . . 157, 1023
physunits . . . . . 1024
picinpar . . . . . 1025
pifont . . . . . 1027
pinlabel . . . . . 1028

termcal . . . . . 1142
textarea . . . . . 1143
textcomp . . . . . 102, 123, 1143
textfit . . . . . 1147
textpos . . . . . 1147
theorem . . . . . 1148
thinsp . . . . . 1152
thm-listof . . . . . 1152
thm-restate . . . . . 1153
thmbox . . . . . 1153
thmtools . . . . . 1154
threadcol . . . . . 1154
threeparttable . . . . . 1155
threeparttablex . . . . . 166, 1155
thumb . . . . . 1156
thumbs . . . . . 1157
tikz . . . . . 158, 1157
tikz-imagelabels . . . . . 1159
titleps . . . . . 1159
titleref . . . . . 1162
titlesec . . . . . 1162
titletoc . . . . . 1164
titling . . . . . 134, 1166
tocbasic . . . . . 1170
tocbibind . . . . . 150, 1171
tocdata . . . . . 1172
tocenter . . . . . 1174
tocloft . . . . . 134, 150, 653, 1174
tocstyle . . . . . 1180
todo . . . . . 1180
todonotes . . . . . 173, 1181
topcapt . . . . . 1183
tram . . . . . 1183
transparent . . . . . 1184
trimclip . . . . . 1184
trivfloat . . . . . 167, 1185
truncate . . . . . 1186
turnthepage . . . . . 1186
twoup . . . . . 1186
txfonts . . . . . 1186
txgreeks . . . . . 1187
typearea . . . . . 1187
typicons . . . . . 1188
ulem . . . . . 1189
umoline . . . . . 1190
underscore . . . . . 1191
unicode-math . . . . . 1191
units . . . . . 157, 1195
unitsdef . . . . . 1196
upgreek . . . . . 1197
upref . . . . . 1197
url . . . . . 130, 1198
ushort . . . . . 1198
uspace . . . . . 1198
varioref . . . . . 130, 1199
varwidth . . . . . 241
verbatim . . . . . 240
verse . . . . . 171, 1199, 1200
versonotes . . . . . 1201
vertbars . . . . . 1201
vmargin . . . . . 1202
vowel . . . . . 1202
vpe . . . . . 1203
vwcol . . . . . 1203
wallpaper . . . . . 1205
watermark . . . . . 1205
widetable . . . . . 1206
widows-and-orphans . . . . . 1206
witharrows . . . . . 1206
wrapfig . . . . . 1208
xbmks . . . . . 1209
xcolor . . . . . 159, 582, 1209
xechangebar . . . . . 1220
xellipsis . . . . . 1220
xetexko-vertical . . . . . 1221
xevlna . . . . . 1221
xfakebold . . . . . 1221
xfrac . . . . . 1222
xifthen . . . . . 240
xltabular . . . . . 1224
xltxtra . . . . . 1225
xmpincl . . . . . 1225
xparse . . . . . 238
xpatch . . . . . 202
xpiano . . . . . 1226
xpinyin . . . . . 1226
xr . . . . . 1228
xr-hyper . . . . . 1228
xstring . . . . . 240
xtab . . . . . 166, 1228
xunicode . . . . . 1230
xurl . . . . . 1231
xy . . . . . 1231
zhlineskip . . . . . 1232
zwpagelayout . . . . . 1233
\PackageDiagramAltText . . . . . 114, 11142
\pagebreak . . . . . 13074
\pagecolor . . . . . 75
pagegrid (package) . . . . . 1007
pagenote (package) . . . . . 134, 1007
\pagenumbering . . . . . 5930
\pageref . . . . . 10106
\pagerefPageFor . . . . . 10105
pagesel (package) . . . . . 1007
\pagestyle . . . . . 5922
Pandoc (program) . . . . . 74
\paragraph . . . . . 7418
paralist (package) . . . . . 1008
parallel (package) . . . . . 1008
\parbox . . . . . 12419

parcolumns (package) . . . . . 1010
parnotes (package) . . . . . 1012
\parsemulticolumnalignment . . . . . 9357
parskip (package) . . . . . 1013
\part . . . . . 7385
pbox (package) . . . . . 1013
pdfcol (package) . . . . . 1014
pdfcolfoot (package) . . . . . 1014
pdfcolmk (package) . . . . . 1015
pdfcolparallel (package) . . . . . 1015
pdfcolparcolumns (package) . . . . . 1015
pdfcomment (package) . . . . . 1016
pdfcrop (program) [requirement] . . . . . 77
pdfcrypt (package) . . . . . 1017
pdfLaTeX (program) [requirement] . . . . . 77
pdflscape (package) . . . . . 1017
pdfmarginpar (package) . . . . . 1017
pdfpages (package) . . . . . 1017
pdfprivacy (package) . . . . . 1020
pdfrender (package) . . . . . 1020
pdfseparate (program) [requirement] . 77, 82
pdfsync (package) . . . . . 1020
pdftocairo (program) . . . . . 157, 580
pdftocairo (program) [requirement] . . 77, 82
pdftotext (program) [requirement] . . 77, 82
pdftotextEnc (option) . . . . . 108, 228
pdftricks (package) . . . . . 160, 1021
pdfx (package) . . . . . 1021
perl (program) [requirement] . . . . . 82
perltex (package) . . . . . 177
perpage (package) . . . . . 1021
pfnote (package) . . . . . 1023
phfqit (package) . . . . . 1023
physics (package) . . . . . 157, 1023
physunits (package) . . . . . 1024
picinpar (package) . . . . . 1025
picture (environment) . . . . . 586, 12289
pifont (package) . . . . . 1027
pinlabel (package) . . . . . 1028
placeins (package) . . . . . 1028
plarydshln (package) . . . . . 1028
Plastex (program) . . . . . 73
plext (package) . . . . . 1028
plextarydshln (package) . . . . . 1029
plextcolortbl (package) . . . . . 1030
plimsoll (package) . . . . . 1030
\PN@parnotes@auto . . . . . 6312
polyglossia (package) . . . . . 172
\postbookname . . . . . 7365
\postchaptername . . . . . 7369
\postpartname . . . . . 7367
\postsectionname . . . . . 7371
\prebookname . . . . . 7365
\prechaptername . . . . . 7369
prelim2e (package) . . . . . 1030
\prepartname . . . . . 7367
\presectionname . . . . . 7371
prettyref (package) . . . . . 1031
preview (package) . . . . . 1031
\printauthor . . . . . 412, 7771, 7790
\printdate . . . . . 412, 7782, 7792
printglossary (option) [lwarpmk] . 135, 824
\printindex . . . . . 2
PrintIndexCmd (option) . . . . . 106, 229
PrintLatexCmd (option) . . . . . 106, 175, 229
printlen (package) . . . . . 240
\printthanks . . . . . 412, 7748
\printtitle . . . . . 412, 7755, 7789
program:
  [requirement]:
    LuaLaTeX . . . . . 77
    MathJax . . . . . 77
    pdfcrop . . . . . 77
    pdfLaTeX . . . . . 77
    pdfseparate . . . . . 77, 82
    pdftocairo . . . . . 77, 82
    pdftotext . . . . . 77, 82
    perl . . . . . 82
    XeLaTeX . . . . . 77
  Adobe . . . . . 74
  AsciiDoc . . . . . 74
  AsciiDoctor . . . . . 74
  Asciidoctor-LaTeX . . . . . 74
  epstopdf . . . . . 158, 580
  Flare . . . . . 74
  FrameMaker . . . . . 74
  GELLMU . . . . . 73
  GladTeX . . . . . 73
  Hevea . . . . . 73
  htlatex . . . . . 73
  imakeidx . . . . . 141
  InDesign . . . . . 74
  index . . . . . 138
  LaTeX2HTML . . . . . 73
  latexmk . . . . . 176
  LaTeXML . . . . . 73
  LibreOffice . . . . . 74
  Linux . . . . . 117, 224
  lwarpmk . . . . . 189, 316
  lwarpmk epstopdf . . . . . 158, 580
  lwarpmk pdftosvg . . . . . 157, 580
  Mac OS . . . . . 117, 224
  Madcap . . . . . 74
  make . . . . . 178
  makeindex . . . . . 137, 147
  MathJax . . . . . 152, 153
  MS-Windows . . . . . 117, 224
  OpenOffice . . . . . 74
  Pandoc . . . . . 74
  pdftocairo . . . . . 157, 580

Plastex . . . . . 73
splitidx . . . . . 139
TeX2page . . . . . 73
TeX4ht . . . . . 73
TeXMaths . . . . . 183
TtH . . . . . 73
Unix . . . . . 117, 224
Windows . . . . . 117, 224
Word . . . . . 74
xindex . . . . . 138, 148
xindy . . . . . 137, 147
project.css (file) . . . . . 116
project.lwarpmkconf (file) . . . . . 269
psfrag (package) . . . . . 160, 1031
psfragx (package) . . . . . 1032
pst-eps (package) . . . . . 1032
pstool (package) . . . . . 160, 1033
pstricks (package) . . . . . 160, 1033
pxatbegshi (package) . . . . . 1034
pxeveryshi (package) . . . . . 1034
pxfonts (package) . . . . . 1034
pxftnright (package) . . . . . 1035
pxjahyper (package) . . . . . 1035
pythontex (package) . . . . . 177

**Q**

\qquad . . . . . 610, 13022
\quad . . . . . 610, 13017
quotation (environment) . . . . . 7955
quotchap (package) . . . . . 1035
quote (environment) . . . . . 7947
quoting (package) . . . . . 1036

**R**

ragged2e (package) . . . . . 1037
\raggedbottom . . . . . 5926
\raggedleft . . . . . 12084
\raggedright . . . . . 12090
\raisebox . . . . . 12604
realscripts (package) . . . . . 1037
\ref . . . . . 10094
refcheck (package) . . . . . 1040
refcount (package) . . . . . 240
\reflectbox . . . . . 389
register (package) . . . . . 1041
relsize (package) . . . . . 124, 1042
repeatindex (package) . . . . . 1043
repltext (package) . . . . . 1044
[requirement]:
LuaLaTeX (program) . . . . . 77
MathJax (program) . . . . . 77
pdfcrop (program) . . . . . 77
pdfLaTeX (program) . . . . . 77
pdfseparate (program) . . . . . 77, 82
pdftocairo (program) . . . . . 77, 82
pdftotext (program) . . . . . 77, 82
perl (program) . . . . . 82
XeLaTeX (program) . . . . . 77
\RequirePackage . . . . . 1431
\resizebox . . . . . 398
resizegather (package) . . . . . 1044
\ResumeTabular . . . . . 9634
returntogrid (package) . . . . . 1044
\reversemarginpar . . . . . 6649
\rightline . . . . . 12098
rlepsf (package) . . . . . 1045
rmathbr (package) . . . . . 1045
\rmfamily . . . . . 12814
rmpage (package) . . . . . 1045
romanbar (package) . . . . . 1046
romanbarpagenumber (package) . . . . . 1046
\rotatebox . . . . . 347
rotating (package) . . . . . 1046
rotfloat (package) . . . . . 1047
\rowcolor . . . . . 8833
\rownum . . . . . 8825
rterface (package) . . . . . 177
\rule . . . . . 122, 13081
rviewport (package) . . . . . 1048

**S**

sagetex (package) . . . . . 177
sample_project.css (file) . . . . . 116, 309
savetrees (package) . . . . . 1048
\sb . . . . . 12892
\scalebox . . . . . 370
scalefnt (package) . . . . . 1048
scalerel (package) . . . . . 1049
schemata (package) . . . . . 1049
scrextend (package) . . . . . 1050
scrhack (package) . . . . . 1054
scrlayer (package) . . . . . 1054
scrlayer-notecolumn (package) . . . . . 1056
scrlayer-scrpage (package) . . . . . 1056
scrpage2 (package) . . . . . 1057
\scshape . . . . . 12839
\section . . . . . 7409
section (package) . . . . . 1058
sectionbreak (package) . . . . . 1059
sectsty (package) . . . . . 1059
selectp (package) . . . . . 1060
semantic-markup (package) . . . . . 1060
seqsplit (package) . . . . . 1061
\SetHTMLFileNumber . . . . . 5734
setspace (package) . . . . . 1062
\sffamily . . . . . 12819
\sfrac . . . . . 1222
shadethm (package) . . . . . 1063
shadow (package) . . . . . 1063
shapepar (package) . . . . . 1064
showidx (package) . . . . . 1064
showkeys (package) . . . . . 1064

showtags (package) . . . . . *1065*
shuffle (package) . . . . . *1065*
sidecap (package) . . . . . *1066*
sidenotes (package) . . . . . *1067*
SideTOCDepth (counter) . . . . . *109*, *521*
\sidetocname . . . . . *111*, 10564
simplebnf (package) . . . . . *1068*
\simplechapterdelim . . . . . 7178
\sishape . . . . . 12854
SIunits (package) . . . . . *1070*
siunitx (package) . . . . . *156*, *579*, *1078*
skmath (package) . . . . . *1092*
slantsc (package) . . . . . *1098*
slashed (package) . . . . . *1098*
\sloppy . . . . . 5928
\slshape . . . . . 12865
soul (package) . . . . . *1099*
soulpos (package) . . . . . *1100*
soulutf8 (package) . . . . . *1101*
\sp . . . . . 12891
splitbib (package) . . . . . *1101*
splitidx (package) . . . . . *1102*
splitidx (program) . . . . . *139*
srcltx (package) . . . . . *1103*
srctex (package) . . . . . *1104*
\sscshape . . . . . 12870
stabular (package) . . . . . *1104*
stackengine (package) . . . . . *1105*
stackrel (package) . . . . . *1106*
\StartDefiningMath . . . . . 5692
\StartDefiningTabulars . . . . . 5682
statex2 (package) . . . . . *1107*
statistics (package) . . . . . *1111*
statmath (package) . . . . . *1116*
steinmetz (package) . . . . . *1118*
stfloats (package) . . . . . *1119*
\StopDefiningMath . . . . . 5696
\StopDefiningTabulars . . . . . 5686
struktex (package) . . . . . *1119*
subcaption (package) . . . . . *168*, *1120*
subfig (package) . . . . . *168*, *1120*
subfigure (package) . . . . . *1125*
\subparagraph . . . . . 7421
\subsection . . . . . 7412
\subsubsection . . . . . 7415
subsupscripts (package) . . . . . *1126*
supertabular (package) . . . . . *166*, *1127*
svg (package) . . . . . *1128*
swfigure (package) . . . . . *1129*
sympytex (package) . . . . . *177*
syntonly (package) . . . . . *1129*

## T

tabbing (environment) . . . . . 8059
tabfigures (package) . . . . . *1130*
tablefootnote (package) . . . . . *1130*
\tableofcontents . . . . . *113*, 10494
tabls (package) . . . . . *1130*
tabular (environment) . . . . . 9781
\TabularMacro . . . . . 9632
tabularx (package) . . . . . *1130*
tabulary (package) . . . . . *1131*
tagpdf (package) . . . . . *1131*
tascmac (package) . . . . . *1134*
tcolorbox (package) . . . . . *128*, *1135*
tensor (package) . . . . . *1141*
termcal (package) . . . . . *1142*
\TeX . . . . . 13186
TeX2page (program) . . . . . *73*
TeX4ht (program) . . . . . *73*
TeXMaths (program) . . . . . *183*
textarea (package) . . . . . *1143*
\textbf . . . . . 12631
\textcolor . . . . . 62
textcomp (package) . . . . . *102*, *123*, *1143*
\texteb . . . . . 12639
textfit (package) . . . . . *1147*
\textgreater . . . . . 5727
\textit . . . . . 12687
\textless . . . . . 5725
\textlg . . . . . 12647
\textmd . . . . . 12623
\textnormal . . . . . 12738
textpos (package) . . . . . *1147*
\textrm . . . . . 12655
\textsc . . . . . 12695
\textsf . . . . . 12663
\textsi . . . . . 12711
\textsl . . . . . 12728
\textssc . . . . . 12736
\textsubscript . . . . . 12897
\textsuperscript . . . . . 12893
\texttt . . . . . 12671
\textulc . . . . . 12703
\textup . . . . . 12679
\tfl@chapter@fix . . . . . *1185*
\thanks . . . . . *120*
\thanksmarkseries . . . . . 92
\theauthor . . . . . *412*
thebibliography (environment) . . . . 10920
\thedate . . . . . *412*
\theHTMLSection . . . . . 7455
\theHTMLTitleSection . . . . . 7454
\theHTMLTitleSeparator . . . . . 7431
theindex (environment) . . . . . 10661
\thempfootnote . . . . . 6581
theorem (package) . . . . . *1148*
\thetitle . . . . . *412*
thinsp (package) . . . . . *1152*
\ThisAltText . . . . . *113*, 11139
\thispagestyle . . . . . 5923

thm-listof (package) . . . . . 1152
thm-restate (package) . . . . . 1153
thmbox (package) . . . . . 1153
thmtools (package) . . . . . 1154
threadcol (package) . . . . . 1154
threeparttable (package) . . . . . 1155
threeparttablex (package) . . . . . 166, 1155
thumb (package) . . . . . 1156
thumbs (package) . . . . . 1157
tikz (package) . . . . . 158, 1157
tikz-imagelabels (package) . . . . . 1159
\title . . . . . 119, 6477
titlepage (environment) . . . . . 119, 7736
titleps (package) . . . . . 1159
titleref (package) . . . . . 1162
titles (option) [tocloft] . . . . . 134
titlesec (package) . . . . . 1162
titletoc (package) . . . . . 1164
titling (package) . . . . . 134, 1166
titlingpage (environment) . . . . . 14, 119
tocbasic (package) . . . . . 1170
[tocbibind]:
  numindex (option) . . . . . 150, 1171
tocbibind (package) . . . . . 150, 1171
tocdata (package) . . . . . 1172
tocdepth (counter) . . . . . 109
tocenter (package) . . . . . 1174
[tocloft]:
  titles (option) . . . . . 134
tocloft (package) . . . . . 134, 150, 653, 1174
tocstyle (package) . . . . . 1180
todo (package) . . . . . 1180
todonotes (package) . . . . . 173, 1181
topcapt (package) . . . . . 1183
\tracinglwarp . . . . . 197, 1592
tram (package) . . . . . 1183
transparent (package) . . . . . 1184
trimclip (package) . . . . . 1184
trivfloat (package) . . . . . 167, 1185
truncate (package) . . . . . 1186
\ttfamily . . . . . 12824
TtH (program) . . . . . 73
turnthepage (package) . . . . . 1186
tutorial.tex (file) . . . . . 83
twoup (package) . . . . . 1186
txfonts (package) . . . . . 1186
txgreeks (package) . . . . . 1187
typearea (package) . . . . . 1187
typicons (package) . . . . . 1188

## U

\ulcshape . . . . . 12846
ulem (package) . . . . . 1189
umoline (package) . . . . . 1190
\underline . . . . . 12903
underscore (package) . . . . . 1191
unicode-math (package) . . . . . 1191
units (package) . . . . . 157, 1195
unitsdef (package) . . . . . 1196
Unix (program) . . . . . 117, 224
\up . . . . . 12901
upgreek (package) . . . . . 1197
upref (package) . . . . . 1197
\upshape . . . . . 12829
url (package) . . . . . 130, 1198
\UseMinipageWidths . . . . . 125, 587, 12313
ushort (package) . . . . . 1198
usingOSWindows (boolean) . . . . . 226
uspace (package) . . . . . 1198

## V

varioref (package) . . . . . 130, 1199
varwidth (package) . . . . . 241
\verb . . . . . 7990
verbatim (environment) . . . . . 8041
verbatim (package) . . . . . 240
\VerbatimHTMLWidth (length) . . . . . 423
\verbatiminput . . . . . 8033
verse (environment) . . . . . 2, 7965
verse (package) . . . . . 171, 1199, 1200
versonotes (package) . . . . . 1201
vertbars (package) . . . . . 1201
\vleftmargini (length) . . . . . 171, 422, 1199
\vleftskip (length) . . . . 171, 422, 1199, 1200
vmargin (package) . . . . . 1202
vowel (package) . . . . . 1202
vpe (package) . . . . . 1203
\vrule . . . . . 123
\vspace . . . . . 122
vwcol (package) . . . . . 1203

## W

wallpaper (package) . . . . . 1205
warpall (environment) . . . . . 118, 1167
warpHTML (environment) . . . . . 114, 117, 1168
warpHTML (option) . . . . . 108, 227
\warpHTMLonly . . . . . 115, 118, 1125
warpingHTML (boolean) . . . . . 227
warpingprint (boolean) . . . . . 227
warpMathJax (environment) . . . . . 118, 1174
warpprint (environment) . . . . 114, 118, 1171
warpprint (option) . . . . . 108, 227
\warpprintonly . . . . . 114, 118, 1124
watermark (package) . . . . . 1205
widetable (package) . . . . . 1206
widows-and-orphans (package) . . . . . 1206
Windows (program) . . . . . 117, 224
witharrows (package) . . . . . 1206
Word (program) . . . . . 74
WPMarkFloats (boolean) . . . . . 182, 255
WPMarkLOFT (boolean) . . . . . 183, 256
WPMarkMath (boolean) . . . . . 183, 256

WPMarkMinipages (boolean) . . . . . *183*, *256*
WPMarkTOC (boolean) . . . . . *183*, *256*
WPTitleHeading (boolean) . . . . . *184*, *256*
wrapfig (package) . . . . . *1208*

## X

xbmks (package) . . . . . *1209*
xcolor (package) . . . . . *159*, *582*, *1209*
xechangebar (package) . . . . . *1220*
\XeLaTeX . . . . . 13233
XeLaTeX (program) [requirement] . . . . . *77*
xellipsis (package) . . . . . *1220*
\XeTeX . . . . . 13233
xetexko-vertical (package) . . . . . *1221*
xevlna (package) . . . . . *1221*
xfakebold (package) . . . . . *1221*
xfrac (package) . . . . . *1222*
\xfracHTMLfontsize . . . . . 2
xifthen (package) . . . . . *240*
xindex (option) . . . . . *106*, *230*
xindex (program) . . . . . *138*, *148*
xindexConfig (option) . . . . . *106*, *148*, *228*
xindy (option) . . . . . *106*, *230*
xindy (program) . . . . . *137*, *147*
xindyCodepage (option) . . . . . *106*, *228*
xindyLanguage (option) . . . . . *106*, *228*
xindyStyle (option) . . . . . *106*, *148*, *228*
xltabular (package) . . . . . *1224*
xltxtra (package) . . . . . *1225*
xmpincl (package) . . . . . *1225*
xparse (package) . . . . . *238*
xpatch (package) . . . . . *202*
xpiano (package) . . . . . *1226*
xpinyin (package) . . . . . *1226*
xr (package) . . . . . *1228*
xr-hyper (package) . . . . . *1228*
xstring (package) . . . . . *240*
xtab (package) . . . . . *166*, *1228*
xunicode (package) . . . . . *1230*
xurl (package) . . . . . *1231*
xy (package) . . . . . *1231*

## Z

zhlineskip (package) . . . . . *1232*
zwpagelayout (package) . . . . . *1233*

# General Index

This is an index of instructions and concepts. Look here when wondering how to do something, and check the Troubleshooting Index when something goes wrong.


**Symbols**

\@ifnextchar with MathJax . . . . . 153
\@ifstar with MathJax . . . . . 153
\, . . . . . 122
~ . . . . . 122

**A**

accents
  in section & file names . . . . . 391
accessibility . . . . . 99
adapting
  class . . . . . 189
  document . . . . . 98
  package . . . . . 188
affiliation
  multiple authors . . . . . 133
algorithmicx
  with newfloat, trivfloat . . . . . 1185
alt text . . . . . 99
array
  mhchem . . . . . 947
audio . . . . . 161
author
  HTML meta tag . . . . . 120, 367
  multiple . . . . . 133

**B**

baseline
  tabular . . . . . 455
bibliography
  HTML page and TOC . . . . . 133
bitmapped fonts . . . . . 101
bugs . . . . . 191

**C**

*Calibre* . . . . . 179
chemistry
  Greek symbols . . . . . 711
class
  modifying for lwarp . . . . . 189
code listings . . . . . 122
compiling
  custom . . . . . 175
Computer Modern . . . . . 101
converting
  class . . . . . 189
  document . . . . . 98
  package . . . . . 188
CSS
  class . . . . . 117
  file selection . . . . . 116
  lwarp.css . . . . . 116
  per HTML page . . . . . 116
  project-specific changes . . . . . 116
  span . . . . . 117
ctable . . . . . 167

**D**

danger icon . . . . . 201
debugging . . . . . 191
  HTML debug comments . . . . . 249
  tracing log . . . . . 249
Deja Vu . . . . . 101
description
  HTML meta tag . . . . . 120, 368
display math
  complicated objects . . . . . 155
document
  convert existing . . . . . 98
documentation
  compile . . . . . 187
DVI LaTeX . . . . . 93, 101
dynamic math . . . . . 154, 155
dynamic math expressions . . . . . 339

**E**

endnotes
  HTML page and TOC . . . . . 133
EPS image
  converting . . . . . 95
  using . . . . . 157, 580
EPUB
  conversion software . . . . . 179
  HTML conversion settings . . . . 179, 255
equation numbering
  MathJax . . . . . 152
error messages . . . . . 191
export
  to word processor . . . . . 181

**F**

FAQ . . . . . 191
filename
  accent in . . . . . 391

hashed . . . 549, 569
international languages . . . 171
length . . . 111
simplify . . . 129
underscore in . . . 104, 124
unique . . . 111
font
Computer Modern . . . 101
Deja Vu . . . 101
ligatures . . . 102
packages . . . 102
selection . . . 101
size
lateximage . . . 151, 566
math, SVG . . . 151, 566
xfrac . . . 1222
type 1 vector . . . 101
type 3 bitmapped . . . 101
footnotes . . . 368
MathJax . . . 131
numbering . . . 131
foreign
section names . . . 171
framed objects . . . 125
Frequently Asked Questions . . . 191

G

generator
HTML meta tag . . . 404
GIF images . . . 158, 581
gindex . . . 138
gloss . . . 135
glossaries
HTML page and TOC . . . 133
language . . . 135
options . . . 135
processing . . . 94
graphics
file formats . . . 157, 580
Greek
chemistry symbols . . . 711

H

hash
SVG image filename . . . 549, 569
heading, word processor . . . 184
horizontal and vertical space . . . 122
horizontal rule . . . 123
horizontal space
between minipages . . . 610
\hrule . . . 123
HTML
alt text . . . 99
class . . . 117
conversion settings . . . 109
debug comments . . . 249
EPUB . . . 179, 255
word processor . . . 181, 255, 256
conversion suggestions . . . 121
 . . . 117
entities, conversion . . . 122
filename generation . . . 115
headings . . . 200
meta tag
author . . . 120, 367
description . . . 120, 368
generator . . . 404
title . . . 112, 120, 367
viewport . . . 404
selecting print/HTML definitions . . . 250
 . . . 117
style . . . 117
tabular column conversion . . . 455
verbatim, in . . . 122
hyperref
and *xindy* . . . 137
title text . . . 99

I

icon
warning . . . 201
\@ifnextchar with MathJax . . . 153
\@ifnextstar with MathJax . . . 153
image
alt text . . . 99
file formats . . . 157, 580
GIF . . . 158, 581
graphicx package . . . 580
hashed filename . . . 549, 569
PDF or EPS
converting . . . 95, 158, 580
using . . . 157, 580
PNG and JPG . . . 158, 581
processing . . . 316
\includegraphics
using . . . 157, 580
index
custom display styles . . . 149
formatting . . . 531
gindex
setup . . . 138
HTML page and TOC . . . 133
*imakeidx*
setup . . . 141
*index*
setup . . . 138
letter headings . . . 858
*makeindex*
custom style file . . . 147
setup . . . 137
memoir
setup . . . 144

placement . . . 149
placement and TOC options . . . 149, 1171
processing . . . 87, 88, 137
see, seealso, ranges . . . 137
source code . . . 136
*splitidx*
setup . . . 139
table of contents . . . 149, 1171
tocbibind . . . 149
UTF-8 . . . 103
*xindex*
custom configuration file . . . 148
setup . . . 138
*xindy*
custom style file . . . 147
and hyperref . . . 137
setup . . . 137
inline math
complicated objects . . . 154
international
section names . . . 171
item
empty . . . 428

**J**

JavaScript
MathJax . . . 150
JPG images . . . 158, 581

**L**

language
glossaries . . . 135
localization . . . 99
language HTML metadata . . . 402
lateximage
font size . . . 151, 566
processing . . . 316
Latin Modern font . . . 101
LibreOffice
conversion recommendations . . . 184
import into . . . 181
section headings . . . 184
ligatures . . . 102, 235
line numbers . . . 201
link
home/previous/next page . . . 113
`title` text . . . 99
list
empty item . . . 428
filename . . . 124
listings, program code . . . 122
locale . . . 178
localization . . . 99
LuaLaTeX
detection . . . 202
file & section names . . . 391
lwarp
compiling documentation . . . 187
loading . . . 104
options . . . 104
`lwarp.ist`
customizing . . . 147
`lwarp.xdy`
customizing . . . 147
*lwarpmk*
customizing . . . 189

**M**

make utility . . . 178
*makeindex* . . . 137
customizing . . . 147
margin
numbers . . . 201
tags . . . 201
markup languages . . . 74
math
`alt` text . . . 99
display with complicated objects . . . 155
dynamic . . . 154, 155, 339
MathJax . . . 152
font size — SVG . . . 151, 566
inline with complicated objects . . . 154
MathJax custom functions . . . 152
MathJax summary . . . 152
`mathjax` option . . . 227
`mathsvg` option . . . 227
mhchem . . . 947
SVG summary . . . 151
word processor conversion . . . 183
MathJax
`\@ifnextchar` macros . . . 153
`\@ifstar` macros . . . 153
accessibility . . . 99
custom functions . . . 152
custom script . . . 312
equation numbering . . . 152
`mathjax` option . . . 227
starred macros . . . 153
summary . . . 152
`\mcolrowcell` . . . 164
MD5 hash
SVG image filename . . . 549, 569
memoir
`framewithtitle`, `titledframe` . . . 170
meta tag, HTML
author . . . 120, 367
description . . . 120, 368
generator . . . 404
title . . . 120, 367
viewport . . . 404
minipage
framed . . . 125

horizontal space between . . . . . 610
modifying
class . . . . . 189
document . . . . . 98
package . . . . . 188
\mrowcell . . . . . 164
\multicolumn
with \multirow . . . . . 164
multimedia . . . . . 161
multiple projects in a directory . . . . . 95
\multirow
with \multicolumn . . . . . 164
multirow
\mrowcell and \mcolrowcell . . . . 164

**N**

navigation
link to home/previous/next page . . . 113
newfloat
with trivfloat, algorithmicx . . . . . 1185
nomencl . . . . . 136
numbers
left margin . . . . . 201

**P**

package
modifying for lwarp . . . . . 188
required . . . . . 235
\par
hooks . . . . . 363
PDF image
converting . . . . . 95
using . . . . . 157, 580
Perl . . . . . 82
PNG images . . . . . 158, 581
Poppler . . . . . 77, 82
print
selecting print/HTML definitions . . . 250
problems . . . . . 191
program listings . . . . . 122
programs
utility . . . . . 76
projects . . . . . 95
\published . . . . . 419

**R**

rule
horizontal . . . . . 123

**S**

section
depths . . . . . 200
file names . . . . . 129
heading, word processor . . . . . 184
international languages . . . . . 171
settings
accessibility . . . . . 99
CSS project-specific . . . . . 116
CSS selection . . . . . 116
filenames . . . . . 109
HTML conversion . . . . . 109
language . . . . . 99
lwarp package options . . . . . 104
selecting print/HTML output . . . . . 117
title page . . . . . 119
shell escape . . . . . 101
sidetoc
name . . . . . 99
sidetoc
depth . . . . . 109
siunitx
with *TeXMaths* . . . . . 183
space
horizontal
between minipages . . . . . 610
horizontal and vertical . . . . . 122
stack depths . . . . . 200
starred macros . . . . . 153
\StartDefiningTabulars . . . . . 163, 435
\subtitle . . . . . 419
SVG
converting from PDF or EPS . . . . . 95
dynamic math . . . . . 339
image processing . . . . . 316
math summary . . . . . 151
mathsvg option . . . . . 227

**T**

tabular
baseline . . . . . 455
HTML columnn conversion . . . . . 455
in environments, catcode of & . . 163, 435
macros inside . . . . . 163, 435
\multicolumn with \multirow . . . . 164
multirow \mrowcell and \mcolrowcell . . . . . 164
\StartDefiningTabulars . . . . 163, 435
tikz
catcodes . . . . . 1157
dollar redefined . . . . . 1157
title
HTML meta tag . . . . . 120, 367
titlepage
\subtitle and \published . . . . . 419
tracing log . . . . . 249
trivfloat
with newfloat, algorithmicx . . . . . 1185
troubleshooting . . . . . 191
HTML debug comments . . . . . 249
tracing log . . . . . 249
type 1 vector fonts . . . . . 101

type 3 bitmapped fonts . . . . . 101

**U**

underscore
  filename . . . . . 104, 124
Unicode
  enhanced coverage . . . . . 101
  file & section names . . . . . 391
  input characters . . . . . 218
  selection . . . . . 101
UTF-8
  enhanced coverage . . . . . 101
  file & section names . . . . . 391
  index . . . . . 103
  locale . . . . . 178
  selection . . . . . 101
utility
  programs . . . . . 76

**V**

vector fonts . . . . . 101
verbatim
  code and HTML tags . . . . . 122
vertical space . . . . . 122
video . . . . . 161
viewport
  HTML meta tag . . . . . 404

**W**

warning icon . . . . . 201
word processor
  conversion recommendations . . . . . 184
  HTML conversion settings . 181, 255, 256
  section headings . . . . . 184

**X**

xcite . . . . . 95
XeLaTeX
  detection . . . . . 202
  file & section names . . . . . 391
*xindex* . . . . . 138
  customizing . . . . . 148
*xindy* . . . . . 137
  and hyperref . . . . . 137
  customizing . . . . . 147
xr . . . . . 95
xr-hyper . . . . . 95

# Troubleshooting Index

This index is a sorted reference of problems and solutions. In order to make it easier to locate a solution, the same issue may be addressed by more than one entry.

Entries with higher page numbers are often duplicates of entries with lower page numbers, as the same warning may occur within the user manual and again within the source code for a given package.


**A**

abstract
- missing TOC . . . 133, 629

accents
- file names . . . 391

acro . . . 173

acronym
- multiply-defined labels . . . 636

\AddSubtitlePublished . . . 419

affiliation . . . 413

alt tags . . . 155, 195

amscdx . . . 644

AMSmath
- ntheorem
  - numbering . . . 155, 994

appendix
- incorrect TOC link . . . 134, 654

array
- chemformula . . . 173
- MathJax . . . 153

arydshln . . . 657

audio . . . 161

authblk
- \theauthor . . . 412, 413
- titling . . . 134, 411, 663, 1166

author
- affiliation . . . 413
- formatting . . . 119

autonum . . . 665

**B**

babel
- French . . . 172

backref . . . 669

backref . . . 131

bibliography
- HTML page and TOC . . . 133

bibtex
- \etalchar . . . 134
- Improper \prevdepth . . . 134

bigdelim . . . 167, 678

bigfoot . . . 132, 913

booktabs . . . 683

boxes . . . 124

breqn
- darray . . . 687

bussproofs . . . 689

**C**

*Calibre*
- EPUB conversion . . . 179

caption
- numbering . . . 168
- options . . . 121

changes . . . 698

chemfig . . . 173

chemformula
- MathJax . . . 173, 706

chemgreek
- fontspec mapping . . . 711
- text-mode symbols . . . 711

chemmacros
- \makepolymerdelims . . . 712
- redox reactions . . . 712

Chinese
- font . . . 122

CJK
- font . . . 122

cleveref
- cref reference format . . . 155, 993

cmbright . . . 735

colortbl . . . 166, 737

Command \textquoteright invalid in math mode . . . 195

comment . . . 170, 1237

compiling
- slow MathJax . . . 152

cref reference format . . . 155, 993

cross reference
- incorrect link . . . 196
- MathJax . . . 154
- missing . . . 195

CSS . . . 197

ctable . . . 167

**D**

ditaa . . . 178

documentation
index cross-references . . . 187
dotless j . . . 102
dotlessj . . . 193
duplcate filename . . . 129

**E**

\endhead, etc. . . . 165
endnotes
HTML page and TOC . . . 133
numbering . . . 134
\ensuremath . . . 194
epstopdf . . . 159, 765
EPUB
encoding . . . 179
page order . . . 179
search order . . . 179
section breaks . . . 180
equation numbering
MathJax . . . 152
error messages . . . 191
\etalchar . . . 134

**F**

fancybox
\VerbatimFootnotes . . . 132, 775, 781
fancyvrb
\VerbatimFootnotes . . . 132, 775, 781
figure
macro in name . . . 194
file
inaccessible . . . 111
multiple projects in directory . . . 95
File ended while scanning use of \next . 193
filename
accents . . . 391
corrupted . . . 129, 171
duplicate . . . 129
international, UTF-8 . . . 171
Korean . . . 174
macro in name . . . 129
math in . . . 98, 129, 150
Missing $ inserted . . . 194
fixme . . . 173, 792
float
alignment . . . 123, 167
numbering . . . 168
out of sequence . . . 196
floatrow
\FBwidth and \FBheight . . . 169, 798
with subfig . . . 168, 798
floatrow
\ttabbox . . . 162, 435
font
CJK . . . 122
JetBrain Mono . . . 102
ligatures . . . 102
missing symbols . . . 123, 1143
monospace . . . 102
package conflicts . . . 101
selection . . . 101
small caps . . . 122
UTF-8 . . . 101
fontspec
with monospaced fonts . . . 102
with XeLaTeX, LuaLaTeX. . . . 101
footmisc . . . 131, 369
footnote
displaymath . . . 132, 775, 781
in math . . . 132
in sectioning command . . . 131
MathJax . . . 131
memoir . . . 132, 369
numbering . . . 131
paragraph tags . . . 132, 775, 781
sectioning, footmisc . . . 131, 369
sectioning, verbatim . . . 132, 775, 781
title . . . 412
verbatim . . . 132
\VerbatimFootnotes . . . 132, 775, 781
forest . . . 811
formatting
\bfseries etc. . . . 122, 597
fourier . . . 812
frames . . . 125
framewithtitle . . . 170

**G**

gloss . . . 135
glossaries
HTML page and TOC . . . 133
*makeglossaries* not found . . . 135, 824
page numbers . . . 136, 825
style . . . 136, 825
graphics
\rotatebox, \scalebox, \reflectbox . . . 158, 581
image format priorities . . . 158, 581
images out of order . . . 89, 196
multimedia . . . 161
optional arguments . . . 158, 581
scale option . . . 98, 157, 580
scaled . . . 827
viewport . . . 158, 581
Greek packages . . . 711
grffile . . . 159, 839

**H**

\hrule . . . 123
HTML
&, <, > . . . 122, 598
alt tags . . . 155

author . . . 368
corrupted . . . 102, 119, 124, 193, 197
entities . . . 122, 593
image appear as html code . . . 89, 196
inaccessible pages . . . 111, 197
starred section . . . 133
invalid . . . 122
missing pages
filename not unique . . . 111
recompile . . . 197
SideTOCDepth and FileDepth . . . 111
SideTOCDepth and tocdepth . . . 111
page did not update . . . 111, 197
settings
changed . . . 109
undefined . . . 193
validation . . . 122
\HTMLAuthor . . . 368
HTMLIndexCmd
filenames . . . 107
hyperref
backref . . . 131
comments between arguments . . . 130
incorrect link . . . 196
Token not allowed in a PDF string . . . 195

I

image
appears as html code . . . 89, 196
format priorities . . . 158, 581
incorrect . . . 89, 196
svg math size and baseline . . . 151
viewport . . . 158, 581
Improper\prevdepth
bibtex . . . 134
boxes . . . 194
\includegraphics
optional arguments . . . 158, 581
scale . . . 98, 157, 580
index
?? and non-functional link . . . 108
documentation references . . . 187
empty . . . 149
empty link . . . 130, 195
formatting . . . 108, 531
html page and toc . . . 133
missing entries . . . 137
numbers, not links . . . 240
reference ranges . . . 149
see and seealso . . . 149
styling references . . . 149
xindy
and hyperref . . . 149
xstring bug . . . 240
isomath . . . 864

J

jpeg . . . 102
Japanese
font . . . 122
JetBrain Mono . . . 102

K

keyfloat . . . 169, 871
Korean
font . . . 122
kpfonts . . . 877
kpfonts-otf . . . 879

L

label
\nameref empty . . . 130, 195
characters . . . 130, 195
Label(s) may have changed . . . 194
LaTeX was unable to guess the total... . . . 194
\LateximageFontSizeName . . . 567
Leaders not followed by proper glue . . . 194
LibreOffice
import . . . 181
ligatures . . . 102
Linux . . . 117, 224
list
empty item . . . 123, 428
listings . . . 196
lists
label formatting . . . 428
locale . . . 178
longtable
\endhead, etc. . . . 165
lrbox . . . 124
ltxtable
numbering . . . 905
luaLaTeX . . . 101
\LWRbackslash . . . 175
\LWRdollar . . . 175
\LWRhash . . . 175
\LWRopquote . . . 175
\LWRopseq . . . 175
\LWRpercent . . . 175

M

Mac OS . . . 117, 224
makeglossaries
not found . . . 135, 824
\makelabel . . . 428
manyfoot . . . 132, 913
marginpar . . . 124, 374
math
\@ifnextchar macros and MathJax . . . 153
\@ifstar macros and MathJax . . . 153
alt tags . . . 195
appears as html code . . . 89, 196

nicefrac . . . 157
nicematrix . . . 987
No room for a new \write . . . 194
nomencl . . . 136
ntheorem . . . 994
  cref reference format . . . 155, 993
  font . . . 155, 993
  numbering . . . 155, 994

O

operating system . . . 117, 224
options
  clash with memoir . . . 169, 1236
  with braces . . . 121
overpic . . . 161, 1006

P

package
  MathJax support . . . 154
  options with braces . . . 121
  version numbers with memoir 170, 1236
page
  inacessible . . . 111
page counter
  references . . . 130
  SVG images . . . 89, 196
page numbers . . . 130, 195, 732
pagenote . . . 134, 1007
pdftricks . . . 160, 1021
perltex . . . 177
pfnote
  numbering . . . 132, 1023
physics
  MathJax . . . 157
polyglossia
  Undefined control sequence …begindocument . . . 172, 624
*poppler*
  Syntax Warning (ligature) . . . 805
PrintIndexCmd . . . 106
projects
  multiple . . . 95
psfrag . . . 160
pstool . . . 160, 1033
pstricks . . . 160, 1033
pythontex . . . 177

R

reference
  % character between arguments . . . 196
  empty link . . . 130, 195
  incorrect link . . . 196
  label characters . . . 130, 195
  MathJax . . . 154
  missing or incorrect . . . 195
  page number . . . 130, 195, 732
  undefined
    tcolorbox . . . 129
repeatindex . . . 1043
rlepsf . . . 1045
rterface . . . 177
Runaway argument? File ended … . . . 193

S

sample_projects.css
  overwritten . . . 116
\savebox . . . 124
\sbox . . . 124
scale (\includegraphics option) 98, 157, 580
sectioning
  accents . . . 391
  duplicate name . . . 129
  international language . . . 171
  macro in name . . . 129, 194
  math in name . . . 98, 129, 150
  missing . . . 111
  starred section . . . 133
  word processor import . . . 184
seqsplit . . . 1061
sidenotes
  numbering . . . 131
siunitx . . . 156, 579, 1078
  MathJax . . . 156, 579, 1078
  S column . . . 164, 436
  tabular S and s columns . . . 156, 579, 1078
  with *TeXMaths* . . . 183
small caps . . . 122
splitidx
  \thepage and \AtWriteToIndex 139, 1102
statistics . . . 1111
subcaption
  numbering . . . 168
subfig
  inline . . . 168, 1120
  numbering . . . 168, 1120
  options . . . 168, 1120
  with floatrow . . . 168, 798
subtable
  numbering
    subfig . . . 168, 1120
SVG image
  appears as HTML code . . . 89, 196
  incorrect . . . 89, 196
  math incorrect . . . 339
  math size and baseline . . . 151
  out of order . . . 89, 196
sympytex . . . 177
Syntax Warning (ligature) . . . 805

T

tabbing
  math . . . 162, 426

table
macro in name . . . 194
numbering
ltxtable . . . 905
subfig . . . 168, 1120
Table of Contents
missing . . . 113
tabular
baselines . . . 454
corrupt rows . . . 162, 435, 486
\endhead, \endfoot, \endlastfoot . . . 165, 900
inside an environment . . . 162, 435, 486
\kill . . . 165, 900
macro inside . . . 163, 435
Misplaced \noalign . . . 164, 436
Misplaced alignment tab character & . . . 162, 434
rules . . . 338
\multicolumn with \multirow . . . 164
multirow \mrowcell and \mcolrowcell . . . 164
\newcolumntype . . . 163, 436
numbering . . . 1224
row corruption . . . 163, 435
rules . . . 164, 436
S column . . . 164, 436
tcolorbox . . . 128
Temporary page . . . unable to guess . . . . . 194
tensor . . . 1141
TeX capacity exceeded
Text input levels equals 15 . . . 194
TeXMaths . . . 183
text
&, <, > . . . 122, 598
\bfseries etc. . . . 122, 597
corrupted . . . 101
Text input levels equals 15 . . . 194
textcomp
missing symbols . . . 123, 1143
\textquoteright invalid in math mode . 195
\theauthor and authblk . . . 412, 413
threeparttablex . . . 166
tikz
in math . . . 155
matrices, & . . . 158, 1157
title
affiliation . . . 413
newlines . . . 119
\thanks . . . 412
titledframe . . . 170
titling
authblk . . . 134, 411, 663, 1166
hooks . . . 419
tocloft
chapter titles . . . 134, 150, 653, 1174
todonotes . . . 173, 908, 1181
Token not allowed in a PDF string . . . 195
tracing lwarp . . . 197
tram . . . 1183
transparent . . . 1184

## U

Undefined control sequence . . . begindocument
polyglossia . . . 172, 624
Unicode
fonts . . . 101
UTF-8 locale . . . 178
unicode-math . . . 1191
units . . . 157
Unix . . . 117, 224
URL
Missing $ inserted . . . 194
\usebox . . . 124
UTF-8
locale . . . 178

## V

varioref . . . 130
verbatim
footnote . . . 132
framed . . . 127, 775
VerbatimFootnotes . . . 132, 775, 781
verse
spacing . . . 171, 422, 1200
verse
margin . . . 172, 422, 1200
version numbers
with memoir . . . 170, 1236
video . . . 161
viewport . . . 158, 581

## W

warning messages . . . 191
warpall . . . 118, 193
warpHTML . . . 118, 193
warpMathJax . . . 118, 193
warpprint . . . 118, 193
Windows . . . 117, 224
word processor
import . . . 181
sectioning headings . . . 184

## X

xcite . . . 95
xeLaTeX . . . 101
xfakebold . . . 1221
xfrac . . . 1222

*xindy*
and hyperref . . . . . 149
options
HTMLIndexCmd . . . . . 107
LatexmkIndexCmd . . . . . 107
PrintIndexCmd . . . . . 106
xltabular
numbering . . . . . 1224
xr . . . . . 95
xr-hyper . . . . . 95
xstring . . . . . 240

# Index of Indexes


**C**

Change History . . . . . 1286

**G**

General Index . . . . . 1348

**I**

Index of Objects . . . . . 1324

**T**

Troubleshooting Index . . . . . 1353